



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

### Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

### About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

*GENERAL LIBRARY of the  
UNIVERSITY OF MICHIGAN*

—PRESENTED BY—

*J. A. Cogburn, Statistician*

*3/30/05*



HA  
3001  
AS

Government Statistician's Office,  
Sydney,

Sir,

I have pleasure in forwarding herewith for your acceptance a copy of a publication which has just been issued by this Department.

I should be glad if you would sign and return the annexed form of receipt. Non-compliance with this request will be taken as an indication that future issues are not desired.

I am,

Sir,

Your obedient Servant,

T. A. COGHLAN,

Statistician.

3/30/05

GEN

UNIV

7a

HA  
3001  
.AS



**AUSTRALIA AND NEW ZEALAND.**



ELEVENTH ISSUE.

---

A STATISTICAL ACCOUNT

OF

AUSTRALIA

AND

NEW ZEALAND

1903-4

BY

T. A. COGHLAN.

PUBLISHED BY AUTHORITY OF THE GOVERNMENT OF THE STATE OF NEW SOUTH WALES  
AND OF THE COMMONWEALTH OF AUSTRALIA.

1904

SYDNEY: W. A. GULLICK, GOVERNMENT PRINTER.



## PREFACE.

THE general plan adopted in previous issues has been followed on the present occasion, but the scope of several chapters has been greatly enlarged. Owing to the necessity for printing off the chapters as they were compiled, no attempt has been made to arrange them in their natural order of sequence, but the voluminous index provided will save the reader inconvenience on this score.

In all cases the figures have been revised to accord with the latest information, and as a rule they refer either to the year 1903 or to the year 1904; in some instances, however, owing to the undue delay in publishing the official statistics, I have been compelled to use figures relating to 1902, but the instances where this was necessary were neither many nor important.

Care has been taken to correct errors which have escaped notice in previous editions, and to keep this edition free from them. Should any such have remained undetected, as in the multitude of references is quite possible, it would be deemed a favour if their nature and position were pointed out.

I desire to return thanks to the Statisticians of the States and New Zealand, and to the various officers of the Commonwealth and of the States who have on all occasions so readily supplied me with information asked for.


In the editions published in the year 1900-1 and 1901-2 there appeared short historical sketches of each state and of New Zealand; these have not been reprinted, as space was required for new matter.

T. A. COGHLAN.

*Statistician's Office,*

*Sydney, 1st December, 1904.*

134454



# CONTENTS.

	Page.
Area and Physical Configuration ... ..	1
Australia ... ..	2
New South Wales ... ..	6
Victoria ... ..	19
Queensland ... ..	24
South Australia ... ..	30
Western Australia ... ..	36
Tasmania ... ..	40
New Guinea ... ..	44
New Zealand... ..	46
Climate ... ..	54
The Discovery of Australia and New Zealand ... ..	60
The Commonwealth... ..	69
Constitution of the Commonwealth ... ..	93
Constitutions of the States and New Zealand ... ..	117
Population ... ..	148
Vital Statistics ... ..	177
Shipping ... ..	210
Commerce ... ..	228
Land and Settlement ... ..	287
Agriculture ... ..	345
Pastoral Resources and Dairy Industry ... ..	406
Industrial Progress ... ..	443
Private Property and Incomes ... ..	512
Defence ... ..	535

								<b>Page</b>
<b>Law and Crime</b>	...	...	...	...	...	...	...	<b>544</b>
<b>Railways</b>	...	...	...	...	...	...	...	<b>558</b>
<b>Commonwealth Finance</b>	..	...	...	..	...	...	...	<b>635</b>
<b>State Finance</b>	...	...	...	...	...	...	...	<b>660</b>
<b>Posts and Telegraphs</b>	...	...	...	...	...	...	...	<b>737</b>
<b>Local Government</b>	...	...	...	...	...	...	...	<b>757</b>
<b>Accumulation...</b>	...	...	...	...	...	...	...	<b>781</b>
<b>Social Condition</b>	...	...	...	...	...	...	...	<b>830</b>
<b>Education</b>	...	...	...	...	...	...	...	<b>855</b>
<b>Religion</b>	...	...	...	...	...	...	...	<b>880</b>
<b>Food Supply</b>	...	...	...	...	...	...	...	<b>889</b>
<b>Mineral Resources</b>	...	...	...	...	...	...	...	<b>913</b>
<b>The Manufacturing Industry</b>			...	...	...	...	...	<b>961</b>
<b>Employment and Production</b>			...	...	...	...	...	<b>1004</b>
<b>General Index</b>	...	...	...	...	...	...	...	<b>1024</b>

## AREA AND PHYSICAL CONFIGURATION.

THE Australasian colonies comprise the continent of Australia, the adjacent island of Tasmania, and the islands of New Zealand. The group was formerly subdivided politically into seven colonies; but on the 1st January, 1901, the five mainland states and Tasmania became the Commonwealth of Australia, New Zealand retaining its position as a separate colony. The respective areas of the six states and New Zealand are as follow :—

State.	Area in acres.	Area in square miles.
New South Wales .....	198,848,000	310,700
Victoria .....	56,245,760	87,884
Queensland .....	427,838,080	668,497
South Australia .....	578,381,600	903,690
Western Australia .....	624,538,800	975,920
Tasmania .....	16,778,000	26,215
<hr/>		
Commonwealth of Australia .....	1,902,660,240	2,972,906
New Zealand .....	66,861,440	104,471
<hr/>		
Australasia .....	1,969,521,680	3,077,377

To the area of the Commonwealth shown in the table might be added that of New Guinea, comprising 90,000 square miles. This would bring the area of territory controlled by the Commonwealth to 3,062,906 square miles, and the total area of British Australasia to 3,167,377 square miles.

The British Empire, exclusive of territories under protectorates and spheres of influence, extends over an area of 8,856,000 square miles; so that about 35 per cent. of its area lies within the limits of Australia and New Zealand. Australasia is more than twenty-six times as large as the United Kingdom; more than fifteen times as large as France; more than half as large again as Russia in Europe; and almost equal in extent to the continent of Europe or to the United States of America.

## AUSTRALIA.

THE sea-girt continent of Australia is situated in the Southern Hemisphere, between the Indian and Pacific Oceans, and lies in that portion of the globe extending from lat.  $10^{\circ} 39' S.$  to lat.  $39^{\circ} 11' S.$ , and from long.  $113^{\circ} 5' E.$  to long.  $153^{\circ} 16' E.$  On the north it is bounded by the Timor Sea, the Arafura Sea, and Torres Strait; on the east by the Pacific Ocean; on the south by Bass Strait and the Southern Ocean; and on the west by the Indian Ocean. From north to south the greatest length measures 1,971 miles, while the greatest breadth east and west is about 2,400 miles. Its superficial area is approximately 2,946,691 square miles, with a coast-line measuring about 8,850 miles. The coastal perimeter is equal to 1 mile for every 333 square miles of area—the smallest proportion shown by any of the continents. The Tropic of Capricorn divides Australia into two unequal parts, and in its vast area the continent contains every variety of climate from temperate to tropical.

As regards the general appearance of its land surface, Australia may be described as a plateau, fringed by a low-lying well-watered coast, with a depressed and, for the most part, arid interior. In its mean height, the land mass of the continent rises to a less elevation than that of any other of the continental surfaces of the globe. Fully 500,000 square miles of the area of Australia consist of a great central plain, the vast bulk of which is situated to the south of the 22nd degree; but portions of it stretch upward to the low-lying country in the region south of the Gulf of Carpentaria.

The vast cordillera of the Great Dividing Range originates in the south-eastern corner of the continent, and runs parallel with and close to the eastern shore, through the states of Victoria and New South Wales, right up to the far-distant York Peninsula of Queensland. In Victoria the greatest elevation is reached in the peaks of Mount Hotham and Mount Smyth, each over 6,000 feet in height, with various other summits exceeding 5,000 feet. The loftiest portion of the range is in the region near the confines of Victoria and New South Wales, where Mount Kosciuszko reaches an altitude of over 7,000 feet. The Dividing Range, with its lateral spurs, receives various sectional names in the states through which it passes. More detailed reference to these will be found in the chapters dealing with the physical characteristics of particular states. The seaward slope of the range is

generally sharp and precipitous, and in places marked by chasms and precipices unequalled in grandeur in any other part of the world. On the western side, the descent is more gradual, the table-land merging by easy degrees into the great plain region towards the centre of the continent. In Victoria, the mountain range known as the Grampians commences near the south coast at Portland Bay, and runs in a north and south direction connecting with the Dividing Range by the Pyrenees and Australian Alps. In South Australia, a chain of mountains of no great elevation runs northward from Cape Jervis to the region occupied by Lake Torrens and other salt-water lakes. The plateau in Western Australia is traversed by ranges in various localities, and these, while of no great altitude, possess a certain grandeur in some instances, from the fact that their rugged masses rise abruptly from a level plain. Little accurate knowledge is at present possessed of the mountainous region in the "Nor'-west" district of Western Australia, and in the Northern Territory of South Australia.

The continent possesses no mountains clothed with perpetual snow, nor are there any active volcanoes on its surface. More or less conclusive signs of past glacial action have been reported from the Southern States, and there is also evidence of convulsive volcanic movements in some regions. In Victoria certain peaks in the western district have been in eruption posterior to the arrival of the aboriginal. Perfectly shaped cones may be seen, together with beds of ash and scoriæ little affected by denuding agencies. In the Mount Gambier district of South Australia there are some beautiful little crater lakes occupying the crater hollows of extinct volcanoes. Considerable outpourings of lava took place in late Tertiary times from many points in the Great Dividing Range of Eastern Australia. In the Illawarra district of New South Wales the irruption of an igneous dyke turned portion of the coal seams into a natural coke, the article being largely used on the old metropolitan steam trams. The sandstone in the vicinity of Sydney has in places been hardened by similar means. It is noticeable, however, that all recent volcanic action was confined to the coastal area, no evidence of late lava flows being met with in the plain district of the interior. For a long time Mount Wingen in New South Wales was looked upon as a volcano, but the fires of this burning mountain result from the slow combustion of coal seams in its interior, probably ignited in the first instance by the agency of lightning.

It has been customary to regard the central portion of the continent as being a vast desert, but later knowledge has caused a considerable modification of this idea. There is undoubtedly a large area occupied by barren sandhills, or covered for miles with deposits of peculiar rounded boulders. Then there is the spinifex country, which looks fair enough from a distance, but is actually more hopeless for settlement purposes than what is sometimes called the "Stony Desert," which in good seasons is covered with fine pasturage, and has been occupied for pastoral purposes.

Although there are numerous spacious harbours on the coast of Australia, the shore line, generally speaking, is broken by few remarkable indentations, the most extensive being the Gulf of Carpentaria on the north, which extends inland for a distance of 650 miles, with a breadth of 400 miles, and Spencer's Gulf on the south, penetrating inland for 180 miles, with a breadth varying from 10 to 80 miles. On the north-west coast there are some fine inlets, but none reaches the dimensions of the smaller of the gulfs just mentioned.

Geological research seems to show that Australia is one of the oldest existing land surfaces, and the remarkable character of its fauna and flora as compared with those of other lands is due to this great antiquity.

A peculiar feature in the physical aspect of Australia is the absence of rivers connecting the coast line with the interior, and in keeping with this is the solid outline of the shore generally. From the appearance on the map of the concourse of streams comprised in the Murray and Darling systems, the idea of a well-watered country might be inferred. Many of the tributary streams, however, have running water only after periods of heavy rainfall, and generally fail to reach the main drainage line. The Darling is reckoned amongst the longest rivers in the world, for in certain seasons it is navigable from Walgett to its confluence with the Murray, a distance of 1,768 miles, and thence downward to the sea, a further 587 miles, making a total navigable extent of 2,345 miles. This by no means conveys a true idea of the river, for in dry seasons it can hardly be said to drain its own watershed, and gives water to, rather than receives it from, the surrounding country. In flood-time these rivers spread out over an immense extent of territory, but with the cessation of the rainfall the waters speedily drain off, and the flow is confined to the river beds. Another system of inland drainage comprises the streams which terminate in Lake Eyre, in South Australia. These include all the channels which lead south from the northern watershed, and from the MacDonnell Range, an isolated mass of eruptive granite in the centre of the continent. Such are the Barcoo, Thomson, Diamantina, Cooper's Creek, and several others. They are all absorbed in the saline swamp of Lake Eyre, and some of them, in dry periods, do not reach so far, but sink their scanty contents into the sands.

A large portion of the southern district of West Australia, and part of the western district of South Australia, is destitute of running streams. Indeed over a considerable extent of the coast line in the Great Australian Bight there is no break in the continuity of the bare and precipitous cliffs. Inland from the Bight the aspect is sterile and forbidding, but here and there patches of good country may be found, needing only the presence of permanent water to make them fit for occupation.

In the western half of Australia there are no river systems except upon the coast, and the desert indications begin on the crest of the



table-land. In the Kimberley district there are some fine streams which penetrate some distance inland, but this portion of the continent has yet to be thoroughly explored.

The absence of lakes of any considerable size or permanence is another characteristic of the physical features of Australia. As marked on some maps, the inland lakes of South Australia appear to possess a considerable size, but they are mostly shallow salt marshes, their area depending entirely on the rainfall. Lake Eyre is 39 feet below sea-level, and although in the wet seasons it receives a vast volume of water, it shrinks in periods of drought into a mere salt bog. Lake Torrens is 100 feet above sea-level, and lies between Lake Eyre and the sea. Lake Amadeus is a salt marsh in the interior of the continent, which receives the western drainage of the MacDonnell Range. Much of the drainage received by these lakes passes off by evaporation, but a large volume sinks into the earth, finding its way to the sea by subterranean channels, or else helping to swell the store of artesian water in the reservoirs hidden deep below the surface of the soil.

It will not be necessary here to refer further to the physical features of the country, as these are described with some detail in the following pages dealing with the characteristics of the various states.

## NEW SOUTH WALES.

### AREA AND BOUNDARIES.

THE State of New South Wales lies almost entirely between the 29th and 36th parallels of south latitude, and between the 141st and 153rd meridians east of Greenwich. It is bounded on the east by the Pacific Ocean, to which it presents a coast-line extending over 700 miles, from Point Danger at its north-eastern extremity to Cape Howe at the south-east. From the point last mentioned, which is also the north-east limit of the state of Victoria, it is bounded by an imaginary line, running in a north-westerly direction to the source of the Indi, a stream rising at the foot of Forest Hill, a few miles south of the Pilot Mountain, one of the most conspicuous peaks of the Australian Alps. The southern boundary of the state follows the course of the Indi, and afterwards of the Murray, into which the first-named stream ultimately merges, as far as the 141st meridian of east longitude. The intersection of the Murray with this meridian forms a common point of the three states of New South Wales, Victoria, and South Australia.

On the west, the state is separated from South Australia by the line of the 141st meridian, as far as its intersection with the 29th parallel of south latitude, at which point New South Wales, South Australia, and Queensland touch. Commencing at this point, the northern boundary of the state follows the 29th degree of latitude, till it is crossed by the Macintyre River, one of the upper branches of the Darling, not far from the 149th meridian. Thence it follows the course of the Macintyre upward, to the junction of its tributary, the Dumaresq; leaving the Macintyre, it follows the tributary stream till it meets a spur extending from the Main Dividing Range to the junction of Tenterfield Creek and the Dumaresq. The boundary runs along this spur until it joins the main range, thence, almost parallel to the coast, it follows the Dividing Range to Wilson's Peak, where the Macpherson Range branches eastward. Following the last-named range, the northern boundary reaches the coast at Point Danger.

The area comprised within these limits is estimated at 310,700 square miles. The length of the state, from Point Danger on the north to Cape Howe on the south, is 680 miles. From east to west, along the 29th parallel, the breadth is 760 miles, while diagonally from the south-west corner, where the Murray passes into South Australia, to Point Danger, the length reaches 850 miles.

## NEW SOUTH WALES.

### COASTAL FEATURES.

The coast-line of New South Wales, while not deeply indented, is by no means monotonous in outline. Rugged and precipitous cliffs alternate with long stretches of silver or golden sands, varied by curving bays and wide river estuaries. In places the coast-range approaches so close to the shore that the mountains appear to rise sheer out of the ocean. In no instance do the capes project very far out from the mainland, and the coast is singularly free from dangerous reefs or shoals, while lighthouses have been erected at various prominent points. The general trend of the shore-line is from north-east to south-west through about four degrees of longitude, from Point Danger on the north in longitude 154 degrees E. (about) to Cape Howe on the south in longitude 150 degrees E.

Commencing on the north, the principal indentations are as follow :—

Byron Bay, inside the cape of the same name offers shelter, in all but north-east weather, to vessels trading to Queensland. A large pier has been constructed, by means of which the produce of the neighbouring districts of the Brunswick and Tweed may be shipped when an entrance to these rivers is impracticable.

At Shoal Bay, the entrance to the Clarence, the anchorage is safe and commodious, and when the works designed for improving the river entrance are completed, it promises to be one of the best ports on the coast.

Trial Bay, at the mouth of the Macleay, Port Macquarie, at the mouth of the Hastings, and the harbour at Forster, near Cape Hawke, afford good anchorage. Port Stephens, a little farther south, is a safe and commodious port, and the scenery of its shores is remarkably beautiful. At present this harbour is little used, owing to its proximity to Newcastle and the sparseness of the population in its immediate neighbourhood.

Twenty miles farther south is Port Hunter, at the mouth of the river of that name. When first used, the harbour was inconvenient and dangerous; but this has been altered entirely by the breakwaters and training-walls which have been constructed. Newcastle harbour is now safe and roomy, with shipping facilities equal to those found in any other Australian port.

A few miles farther south is Lake Macquarie, in the centre of the coal-field of the Newcastle district, and covering an area of 44 square miles. The great drawback to the lake as a shipping port has been the shallowness of its entrance; but extensive dykes and training-walls have been commenced, which have already increased the draught of water in the channel.

Broken Bay, 15 miles north of Port Jackson, forms the mouth of the River Hawkesbury. It has a bold entrance, and on Barranjoey, the southern headland, a fine lighthouse has been erected. The bay has three branches, Brisbane Water being the northern, the Hawkesbury mouth the centre, and Pittwater the southern arm. The first-named opens

out into a series of lakes, and the town of Gosford, standing at the head of one of them—the Broadwater—is the centre of an important district. The scenery at and around Broken Bay is characteristically Australian, and in natural beauty rivals even Sydney Harbour. South of Broken Bay the coast-line is a succession of high cliffs and sandy beaches.

The entrance to Port Jackson lies between perpendicular cliffs of sandstone several hundred feet high, and only 74 chains, or nearly one mile, apart. Sydney Harbour has been too often described to require a lengthy reference here. It holds the first place amongst the harbours of the world for convenience of entrance, depth of water, and natural shipping facilities. Its natural beauties charm all who visit its shores, and in the quiet waters of its numerous bays and coves the navies of the world might securely rest. The area of water surface of the harbour proper is 15 square miles, and the shore-line is 165 miles in circuit. At the South Head is erected a splendid lighthouse, fitted with an electric arc light, visible at a distance of 25 miles. On the shores of Port Jackson stands Sydney, the capital of New South Wales and the mother city of the Australasia.

Botany Bay, the first port entered by Captain Cook, lies a few miles south of Sydney. It covers an area of 24 square miles, and receives the waters of several small rivers. The bay has very little trade; but it is frequented by craft in search of shelter during stress of weather.

Wollongong, Kiama, and Ulladulla are small harbours which have been snatched, as it were, from the sea, and are important shipping places.

About 80 miles to the south of Sydney the coast is broken by an important inlet called Jervis Bay. Its entrance is 2 miles wide, and on its bosom safe anchorage may be found in any part. It is surrounded by rich agricultural and mineral country.

Bateman's Bay, at the entrance to the Clyde, is an inlet of some importance, and coastal steamers also load produce at the mouths of the Moruya, Tuross, and Bega Rivers.

Twofold Bay is a magnificent sheet of water, near the southern limit of the state. Formerly it was the seat of a large whaling trade, which is now, however, all but extinct. It is well sheltered, and a fine jetty affords ample shipping facilities. Its trade is chiefly with the neighbouring states, in produce and live stock, the bay being the nearest outlet on the sea coast for the rich district of Monaro. A railway is planned to connect the port with the table-land and the metropolis, and Twofold Bay promises to become a considerable shipping place in the near future. On its shores is situated the town of Eden.

No islands of any note belong geographically to New South Wales. The Broughton Islands, lying a few miles northward of the Heads of Port Stephens, are the largest in extent. Solitary Island, situated near the northern part of the coast, between the Bellinger and Clarence Rivers, and Montagu Island, 18 miles south-east of the Moruya River estuary, have been selected as sites for lighthouses, but are not

otherwise important. Norfolk Island, having an area of 8,607 acres, has recently been placed under the administration of the New South Wales Government; and Lord Howe Island, 3,220 acres in extent, and lying some 360 miles off the coast, in the latitude of Port Macquarie, belongs politically to the state.

#### GENERAL PHYSICAL CHARACTERISTICS.

The surface of New South Wales is divided naturally into three distinct zones, each widely differing in general character and physical aspect, and clearly defined by the Main Dividing Range, which traverses the country from north to south. The tableland, which forms the summit of this range, comprises one of these zones, and marks the division between the coastal region, forming the eastern watershed, and the great plain district of the interior.

The tableland district is divided into two sections, a northern and a southern, and these are traversed by the vast cordillera known as the Great Dividing Range. The width and altitude of the tableland are the greatest in the south-eastern portion of the State, which has the appearance of having been convulsed in past ages by some tremendous plutonic force. In the Muring Range, the southernmost section of the cordillera, are found the loftiest peaks in Australia—Mount Kosciusko and Mount Townsend rising to a height of 7,328 and 7,260 feet respectively. The former is interesting, from the fact that it is probably one of the oldest land surfaces in the world. It has now the appearance of being the denuded remnant of a much higher peak—probably of volcanic origin—and must have stood out as a prominent landmark at the time when the sea extended through Central Australia, and washed the foothills of the Eastern ranges, when Tasmania was but a peninsula of the mainland, and when the Alps and the Himalayas were lying fathoms deep beneath the waters of the ocean. For six months of the year snow may be seen on the high peaks of the Muring Range, and although Kosciusko is 700 feet below the snow line, heavy snowfalls have been known to occur even in the middle of summer. The Monaro Range, as the next northern section of the Dividing Chain is called, averages about 2,000 feet in height, although the head of the Kybeyan River reaches an altitude of over 4,000 feet. This range encloses on the south the rich and beautiful pastoral and agricultural district known as the Monaro Plains. As the tableland runs northward, it decreases in height and width, until it narrows to a few miles only, with an elevation of scarcely 1,500 feet. Further north the plateau widens again, and also increases in altitude, although the average height of the Main Range is inconsiderable, compared with that of its principal lateral spurs. The Blue Mountains district is the best known portion of this division. It extends eastward from the Main Range, and is bounded on the north by the Colo River; on the

south and south-west by Cox's River, and on the east by the Nepean-Hawkesbury Valley. Its chief peaks are Mount Clarence (4,000 feet); Mount Victoria (3,525 feet), and Mount Hay (3,270 feet). These ranges for long offered an inaccessible barrier to the first settlers in New South Wales, and it was not until 1813 that they were successfully crossed by Messrs. Wentworth, Lawson, and Blaxland, and the way opened to the rich plains of the west. The Blue Mountain scenery possesses a charm, which is peculiarly and distinctively Australian. Seen from the plains, the mountains appear tame and insignificant; but the first view from some point on the edge of the tableland into the depths below, leaves a never-to-be-forgotten impression on the memory of the beholder. The mind here recoils with awe at the sight of the majestically stupendous scale on which Nature has worked. In many places, cliffs of bare sandstone, stained with various shades of brown and grey, rise almost perpendicularly to a height of 2,000 feet from the valley below. The hoary antiquity of these silent ranges appeals strongly to the mind of the scientific inquirer, for examination shows that these awe-inspiring precipices and stupendous gorges have not been caused by violent volcanic upheaval, but have been carved out by the slow but irresistible erosive agency of running water. On clear days the distances are softened by a curtain of delicate blue haze, a fact that has earned for the ranges their appellation of Blue Mountains. The prevailing Australian gum tree gives a somewhat monotonous aspect to the tableland, but in the valleys and on the mountain sides the wealth of beautiful ferns and characteristic Australian flowers lends a charming diversity to the scene.

The Dividing Range gradually decreases north of the Blue Mountains until as a narrow ridge it divides the waters of the Goulburn and Hunter on the east from those of the Namoi and Castlereagh on the west. The mass widens out once more in the Liverpool Ranges, where Mount Oxley rises to a height of 4,500 feet, and farther north in the New England Range, the highest peak of which, Ben Lomond, reaches an elevation of 5,000 feet. The average height of the northern tableland is between 2,500 and 3,000 feet. Mount Wingen, situated in a spur of the Liverpool Range, and close to the town of Scone, is one of the natural curiosities of Australia. It is a burning mountain. Its fires, however, are not volcanic, but result from the combustion of seams of coal some distance underground, and geologists have estimated that the burning has been going on for at least 800 years.

The main range throws off many spurs towards the sea on the eastern slope. These divide the waters of the numerous rivers which flow into the Pacific Ocean, but the ranges in the coastal district, as a rule, run parallel with the tableland, of which in some places they form the eastern edge.

The North Coast Range runs from north to south from Mount Marsh in the Richmond Range to the Hastings River district, at an average distance of 35 miles from the coast. It is not of great altitude,

the average elevation being about 2,000 feet. The Illawarra Range forms the western boundary of the Illawarra district. It commences at Clifton, on the sea coast, and gradually recedes inland, although its average distance from the ocean is only about five miles. As it approaches the north bank of the Shoalhaven it becomes locally known as the Cambewarra Range. Valuable coal seams occur on the seaward face of the Illawarra Range, and these are profitably worked at Clifton, Bulli, Corrimal, Mount Keira, and Mount Kembla. The Currockbilly Range commences near Marulan, on the south bank of the Shoalhaven, and terminates on the north bank of the Moruya, about eight miles from the ocean. Its chief elevations are Budawang (3,630 feet), Currockbilly (3,619 feet), and Pigeon House (2,398 feet). Throughout a large portion of its course, the range forms the eastern fringe of the southern tableland. The South Coast Range is a spur from the Monaro Range running in a southerly direction towards the Victorian border, on nearing which it deflects to the westward, and terminates on the left bank of the Snowy River. Its highest peak in New South Wales is Coolangubra (3,712 feet).

In addition to the above, there are various isolated peaks standing out as prominent landmarks in the coastal district. Mount Warning, so named by Captain Cook, is situated near the head of the Tweed River, and in clear weather is visible 60 miles away. Mount Wohiman, or Clarence Peak, lies to the south of Shoal Bay, and is about 1,200 feet in height. Mount Seaview, 3,100 feet in height, is about eight miles south of the Hastings Range and 40 miles from the coast. The Brothers are three conspicuous peaks, 1,700, 1,650, and 1,910 feet high respectively, situated near Camden Haven. They were so named by Captain Cook. Jellore, seven miles north-east of Mittagong, and 2,372 feet in height, may occasionally be seen from Sydney, 70 miles distant. Coolangatta, near the mouth of the Shoalhaven, is 1,000 feet in height. Dromedary, so named by Captain Cook, is a prominent landmark, south of the Turoos River, about 2,700 feet in height.

The western slope of the cordillera is entirely different from the eastern just described. Numerous ramifications of the general mountain system are thrown off, but all slope gently towards the great central plain of the interior. So gentle, indeed, is the declivity that the dividing lines of the various watersheds as they extend westward are scarcely visible, being only indicated by a succession of low ridges and isolated elevations.

In the extreme west of the state, verging on South Australia, another mountain system exists, forming the western edge of an immense depression, through which the largest rivers of the Australian Continent hold their devious course. The Barrier and the Grey Ranges are part of this system. They consist of low hills, hardly rising to the dignity of mountains, and culminating in a few solitary peaks, such as Mount Arrowsmith and Mount Lyell, which attain an elevation of only 2,000 feet above sea-level.

Traces have been found of the existence at some earlier period of a range of primary rocks, extending from Orange to Cobar and Wilcannia, and forming the watershed between the Lachlan and part of the basin of the Darling. The range no longer exists as a landmark, for owing to denudation it has almost entirely disappeared.

The main range already described, traversing the country from north to south, gives rise to numerous rivers flowing into the South Pacific.

In the extreme north of the state, the Tweed and Brunswick Rivers flow through a rich country of semi-tropical aspect. Their courses are short, and bar-entrances render them navigable only for small craft.

A few miles south of the Brunswick, the Richmond descends from the heights of the Macpherson Range, on the slope of Mount Lindsay, one of the highest peaks of the northern table-land. The river has three branches, and is navigable on the main arm as far as Casino, 62 miles, and on Wilson's Creek to Lismore, 60 miles from the sea. The Richmond drains an area of about 2,400 square miles of country, rugged in its upper basin and heavily timbered, and in its lower course flowing through rich alluvial land, where the produce of semi-tropical climes grows luxuriantly.

Immediately south of the last-named stream is the Clarence—the largest river on the eastern watershed. It takes its rise in a spur of the Main Dividing Range, and runs in a south-easterly direction for 240 miles, carrying a considerable body of water through one of the richest districts of the state, and emptying itself into the Pacific at Shoal Bay. The upper part of its basin is very rugged, so much so that its principal tributaries, the Mitchell, Nymboi, Timbarra, and Orara Rivers, rising in the New England table-land, between Armidale and Tenterfield, all flow in an opposite direction to the course of the main stream, generally trending to the north-east, and even, in the case of the Orara and the Nymboi, to the north-west. The Lower Clarence is a magnificent stream, averaging half-a-mile in width, from its mouth upwards, for nearly 50 miles, and it is navigable for 67 miles, as far as Copmanhurst. Ocean-going steamers of large tonnage ascend the river as far as Grafton, 42 miles from the sea. The area of country drained by the Clarence is over 8,000 square miles, or nearly half as large again as the basin of the Thames, whose course, although about as long as that of the Clarence, is navigable for only 60 miles.

Two short rivers, the Bellinger and the Nambucca, both navigable for some distance by small craft, enter the Pacific between the Clarence and Trial Bay.

Into Trial Bay, the Macleay, one of the principal rivers of the coast, discharges, after a course of 200 miles from its source near Ben Lomond. With its principal feeders, the Guyra, the Apaley, and the Chandler, the Macleay drains an area of 4,800 square miles of country, the upper part of which, especially that portion through which the Apaley flows, is extremely rugged and precipitous. Series of waterfalls, some of which have a perpendicular descent of over 200 feet, mark the course of this



stream, as it runs through narrow gorges whose sides rise in places to a height of about 2,000 feet; in its lower course the valley widens very considerably into magnificent alluvial plains. The Macleay is navigable for more than 30 miles, as far as the town of Greenhills, a few miles above Kempsey. The country through which it flows is for the most part thickly timbered.

The Hastings is the next stream met with, and empties itself into the sea at Port Macquarie. The country which it drains is rich, undulating, and densely wooded, and the area within its watershed is 1,400 square miles. Its chief arm is formed by the Wilson and Maria Rivers, on the left bank, the latter joining the main stream a few miles above Port Macquarie.

The Manning rises in the Main Dividing Range, and flows almost due east. The valley through which it flows is densely wooded, and the agricultural land on both sides of the river is unsurpassed for fertility. The Manning has a length of 100 miles, and, like most of the rivers of the seaboard, its course lies through undulating country, broken in the upper portion, but widening out as it nears the sea. Its chief tributary is the Barrington, on the right bank; on the left, it receives the Barnard River, the Dawson, the Lansdowne, the Nowendoc, Rowley's River, and other small streams. The Manning is navigable for ocean-going vessels as far as Wingham, about 20 miles from its mouth.

Before reaching the Hunter, several small streams are met with, amongst which may be mentioned the Wollomba and Maclean, falling into Wallis Lake; the Myall, which empties into Myall Lake; and the Karuah, which reaches the ocean at Port Stephens.

The Hunter is one of the chief rivers of the state, and has its source in the Liverpool Range. It flows first in a southerly direction until its confluence with the Goulburn; thence it takes an easterly course, and reaches the sea at Port Hunter, on the shores of which is situated the city of Newcastle. The Hunter receives numerous tributaries. The chief of these, in addition to the Goulburn, already mentioned, are the Wollombi, the Paterson, and the Williams. With its tributaries, the Hunter drains a country extending over 11,000 square miles—an area more than twice as large as the basin of the Thames. The river is navigable for ocean-going vessels as far as Morpeth, 34 miles from the sea; whilst the Paterson and the Williams are both navigable, the one for a distance of 18 miles, and the other for 20 miles. The upper courses of the main river and its branches are through hilly, if not mountainous districts; but its lower course is mainly through rich, sandy, alluvial flats. Through its lower course, the river drains the largest and most important coal-field in Australia. The length of the Hunter is over 200 miles.

Though less important than the Hunter, from a commercial point of view, the Hawkesbury, which reaches the sea at Broken Bay, is none the less one of the finest rivers of the eastern seaboard. It is formed

by the united waters of many streams, each of considerable local importance. Its chief tributaries come from the table-land or gorges of the Blue Mountains, but the principal branch of the river itself rises in the main range, farther south. The range forming the watershed between the Hawkesbury and the streams flowing eastward, leaves the main range near Lake Bathurst, runs north-easterly, and terminates at the sea near Coalcliff.

Under the name of the Wollondilly, the Hawkesbury has its source not many miles from Goulburn. Flowing past that town, it proceeds in a northerly direction until it receives the waters of the Cox River, which come from the Blue Mountains, after passing through wild gorges, wherein may be found some of the most magnificent scenery in Australia. From the junction of the Cox River the stream is known as the Warragamba, which name it retains until its junction with the Nepean. Though smaller than the Warragamba, the Nepean gives its name to the united waters of the two streams. After receiving the Nepean, the river flows along the foot of the Blue Mountains, through a rich valley highly cultivated. From the Blue Mountains it is augmented by the waters of two streams, the Grose and the Colo, and from the junction of the latter the river is called the Hawkesbury. Still running northward, it is joined by the Macdonald, an important stream, navigable for some distance above its confluence with the Hawkesbury. The Macdonald comes from the north, and joins the river on the left bank. After turning to the east, the Hawkesbury holds its course through broken country, the scenery of which has been pronounced equal to any other river scenery in the world, and finally reaches the sea at Broken Bay. Its course extends over 330 miles, and the drainage area may be set down as 8,000 square miles. Navigation is possible as far as Windsor, 70 miles from the mouth, and a little dredging would enable sea-going vessels to reach that town.

In the neighbourhood of Sydney, some small streams fall into Botany Bay. Two of these, the Woronora and George's River, have their sources on the eastern slope of the ranges in which the Nepean, Cordeaux, and Cataract rise, and after rapid courses unite their waters before falling into the bay.

Generally speaking, the rivers south of Sydney are of less importance than those to the north, as the width of the coastal strip narrows considerably. The Shoalhaven, nevertheless, merits more than passing notice. Rising in the coastal range and following the direction of the coast, it flows northerly through deep gullies, marked by magnificent scenery peculiarly Australian; then turning sharply to the east, it enters the alluvial plains, which are counted amongst the richest and most productive in the country. The Shoalhaven is 260 miles in length, but is navigable only for a few miles, and drains a district 3,300 miles in area. Farther south, in the narrow belt between the ranges and the sea, flow the Clyde, Moruya, Turoos, and Bega Rivers. They all pass through rich, undulating, agricultural country, and each has an average length

of 60 to 70 miles. The Towamba River, at the extreme south of the state, empties itself into the Pacific at Twofold Bay.

The physical aspect of the eastern rivers is much the same, their upper courses being amidst broken and mountainous districts, and their lower waters flowing through undulating country with rich alluvial flats along their banks, for the most part highly cultivated. Where uncultivated, the country is densely covered with timber, some of which attains a magnificent growth, yielding the finest hardwood, and, in the north, cedar and pine.

Though belonging to another river system, the upper basin of the Snowy River is situated in New South Wales. This river receives the snow-fed streams rising on the southern slopes of the Monaro Range, its principal tributaries being the Bombala and the Eucumbene. The Snowy River and its tributaries water a considerable portion of the highest table-land of the state, between the mountain ranges of which are found large tracts of arable land. After leaving New South Wales, the Snowy has a rapid and tortuous course, and finally enters the sea between Cape Howe and Bass Straits, in the state of Victoria. The area of its watershed in New South Wales is about 2,800 square miles.

The western watershed of the state is, in its physical features and geographical character, the antithesis of the eastern. Instead of a narrow strip of country shut in by the sea and mountains, and intersected by numerous short rivers with a rapid flow, the western watershed forms a vast basin through which the quiet waters of a few great rivers have their long though uncertain courses. The rivers of the western region all belong to the fluvial system of the Murray, which carries to the Southern Ocean, through the state of South Australia, the drainage of a watershed immense in extent, embracing the northern portion of Victoria and the western and larger part of New South Wales, and reaching almost to the centre of Queensland.

The Murray, or Hume, the southern branch of this vast river system, rises in the Snowy Mountains, from which its three principal sources, the Hume, the Tooma, and the Indi descend. The first two of these streams rise on the northern and western slopes of Mount Kosciusko; the Indi, which is really the main river, has a longer course, rising in a gully near the Pilot Mountain, at an elevation of 5,000 feet above the sea. From the confluence of these rivers the Murray rapidly descends towards the plains below Albury, where it is only 490 feet above sea level, with a course of 1,439 miles still to run. From Albury downwards the river receives many tributaries on both banks, those from New South Wales being the most important. Above Albury the tributaries are for the most part mountain torrents, carrying to the main stream the melted snows of the Australian Alps. In its lower course, however, the Murray is augmented, through the Murrumbidgee and the Darling, by the waters of secondary systems as important as its own.

Before being joined by the Murrumbidgee, the Murray receives, from a series of ana-branches, the drainage of a large portion of the country lying between the two main streams. The Billabong Creek runs almost through the centre of the plain spreading between the Murray and Murrumbidgee; in the middle of its course it communicates with the latter river, through Colombo and Yanko Creeks, whilst on the south it feeds the Murray by the channel of the Edward River. The Edward itself is an important stream. With the Wakool, Tupal, and Bullatale Creeks, and many other smaller and less important water-courses, it forms a fluvial system, interlacing the whole country from Tocumwal to the Murrumbidgee junction, which has been aptly named Riverina. From its farthest source at the foot of the Pilot Mountain to the town of Albury, the Murray has a length of 280 miles; thence to the Darling River junction its course is 852 miles; and from that point to the sea, below Lake Alexandrina, it is 587 miles in length. The river has thus a total course of 1,719 miles, of which 1,250 are between the states of Victoria and New South Wales. It has been navigated as far as the Ournie gold-field, about 150 miles above Albury, and 1,590 miles from its mouth.

The Murrumbidgee has its source at the foot of a hill overlooking the Coolamon Plains, at a height of nearly 5,000 feet above the sea. Its course first shapes itself southward, but near the town of Cooma it takes a sharp curve and runs in a northerly direction until it approaches Yass. Here it curves again, trending to the west in a line parallel to the Murray; but turning south-west on receiving the Lachlan, it finally joins the main river after a course of 1,350 miles. The area drained by the Murrumbidgee is estimated at 15,400 square miles. In the upper part of its course it receives from both sides numerous rivers and creeks, the most important of which are the Umaralla, Molonglo, and Yass Rivers on its right, and the Goodradigbee and Tumut Rivers on its left bank. All these flow through mountainous country over a series of plateaux, which from the Coolamon and Coorangorambula Plains to the plains round Gundagai and Wagga successively diminish in height from 5,000 feet to 720 feet and 607 feet above the sea.

The chief tributary of the Murrumbidgee is the Lachlan, rising in the Main Dividing Range, where its principal feeders also have their source. These are the Boorowa, Crookwell, Abercrombie, and Belubula—all rapid streams, occasionally swollen by melted snows from the tableland. After receiving the Boorowa, the Lachlan flows to the Murrumbidgee, through 500 miles of plain country, without receiving any tributary of a permanent character. The water-courses which carry off the surplus water from the plains on each side of the river, only reach it in time of flood. The total length of the stream is 700 miles, and its basin has an area of 13,500 square miles. The lines of demarcation between the Lachlan basin and that of the Murrumbidgee on the south and of the Darling on the north-west, are hardly perceptible on the ground, so flat is the country through which these great rivers flow.

Of all the tributaries of the Murray, the Darling drains the largest area, extending as it does over the greater portion of the western district of New South Wales, and embracing nearly all Southern Queensland. From its confluence with the Murray at Wentworth up to its junction with the Culgoa a few miles above Bourke, the Darling receives only two tributaries, the Paroo and the Warrego, both intermittent, though of vast size in times of flood. For over 1,000 miles this great river holds its solitary course, Nile-like, feeding the thirsty plains of the south with water falling many hundred miles distant on the downs of Queensland. The course of the river is tortuous in the extreme: in many places a narrow neck of land, a mile or two across, separates parts of the river 20 miles distant if the stream were followed. The Darling presents the phenomenon, not uncommon in Australian rivers, of banks much higher than the plain behind; indeed, the river bed itself, though from 30 to 40 feet beneath the bank, is in some places but little below the general level of the country. Successive floods have added to the height of the banks, and have raised the bed of the stream correspondingly.

The Darling has no source under that name, which applies only to that part of the river as far as the Bogan junction. Above this point it takes the name of the Barwon, until its confluence with the Gwydir; then it is known as the Macintyre, and afterwards the main branch receives the name of the Dumaresq. The last-named stream has its source in the Dividing Range, on the summit of the table-land at the extreme north-east of the state, not far from the head of the Richmond. The Dumaresq, Macintyre, and Barwon form, however, what might really be called the Upper Darling, and this appellation would be geographically accurate. The variety of names by which, not only the Darling, but many other Australian rivers are known, is due to the fact that they were discovered in sections, the identity of which was not established until years afterwards, and the sectional names have survived.

The Darling receives, in its upper course, many tributaries, which drain the southern portion of Queensland, but these rivers only flow for a short part of their courses in New South Wales. Chief among them are the Mooni, Narran, Bokhara, Culgoa, Warrego, and Paroo. The principal affluents of the Darling within the boundaries of New South Wales are on the left bank. The Gwydir, Namoi, Castlereagh, Macquarie, and Bogan are the most important. These streams are all of considerable length and similar in character; their upper valleys are on the tablelands, and their lower courses lie through alluvial plains and good pastoral country. The Darling is navigable, in times of freshets, as far as the township of Walgett, 1,758 miles from its confluence with the Murray; thence to the sea the distance is 587 miles, making a total length of navigable water from Walgett to the sea of 2,345 miles, and it therefore ranks high amongst the rivers of the world, as estimated by navigable length. Unfortunately, however, its upper course is open only during part of the year.

Here and there along the course of the western rivers are found lakes, sometimes of considerable dimensions. These lakes are in reality shallow depressions, receiving water from the overflow of the rivers in times of flood, and in return feeding them when the floods have subsided. Lake Urana is the most important in the Murray and Murrumbidgee basin, and Lakes Cowal, Cudgellico, and Waljeers, in that of the Lachlan. Along the Darling are Lakes Poopelloe and Gonyulka on the left bank, and Laidley's Ponds and Lakes Pammaroo, Tandou, and Cawndilla on the right, near Menindie. On the South Australian frontier are Lake Victoria, formed by the overflow of the Murray, and others of less importance. The area of these lakes is undefined, as they vary in size according to the rainfall, sometimes covering a vast extent of country, and at other times being reduced to the proportions of mere waterholes, whilst in seasons of great drought they are absolutely dry.

On the summit of the Main Dividing Range, and within a few miles of the inland towns of Goulburn, Queanbeyan, and Braidwood, two of the principal lakes of the state are situated. Lake George is 16 miles in length and 6 miles in width, draining a basin whose area is about 490 square miles. It is situated at an elevation of 2,200 feet above the sea, and the scenery around it is very beautiful. This lake exhibits the phenomenon of a large drainage area without a visible outlet, for though it receives many small water-courses, no stream leaves it. Lake Bathurst, a few miles east of Lake George, is another depression on the summit of the Dividing Range, and covers in ordinary seasons an area of about 15 square miles. It is similar in character to Lake George, having no outlet to the sea. Both lakes, in periods of great drought, shrink considerably in area; but Lake George in most seasons is a fine sheet of water.

## VICTORIA.

### AREA AND BOUNDARIES.

**VICTORIA** is situated in the south-eastern portion of the continent of Australia, and lies between the parallels of  $34^{\circ}$  and  $39^{\circ}$  south latitude, and the meridians of  $141^{\circ}$  and  $150^{\circ}$  east longitude. The greatest length east and west is about 480 miles, and the greatest width, in the west, about 250 miles. The surface area of the state is 87,884 square miles. Roughly speaking, the country has the shape of a scalene triangle, of which the vertex is at Cape Howe. On the north and north-east Victoria is bounded by the River Murray and a surveyed line running from Forest Hill, near the head waters of the stream, to Cape Howe. The southern boundary is formed by the Southern Ocean and Bass Strait, the Pacific forming the south-eastern boundary. On the west, the state is bounded by South Australia, the dividing line being about 242 geographical miles in length, and approximating to the position of the 141st meridian of east longitude.

### COASTAL FEATURES.

The total length of the coast line is about 750 miles. A reference to the map shows that there are three prominent projections on the south; terminating respectively in Cape Nelson, Cape Otway, and Wilson's Promontory. The last-mentioned projection is the southmost point on the continent of Australia, and is situated in latitude  $39^{\circ} 8'$  south, longitude  $146^{\circ} 26'$  east. The most western point on the coast, at the termination of the frontier line, is in latitude  $38^{\circ} 4'$  south. Proceeding thence eastward from the head of Discovery Bay, the coast begins with a succession of sandstone cliffs backed by grassy undulating country extending for some distance inland. Between Discovery Bay and Portland Bay there is a well-wooded peninsula broken by expanses of grassy meadow, Capes Bridgewater and Nelson lying at the extremities of small projections. Portland Bay is a crescent-shaped inlet with stretches of sandy beach backed by granite cliffs. Farther round are Port Fairy and Warrnambool Bay. From this point downwards to Cape Otway there is a series of precipitous cliffs; Cape Otway itself is a bluff headland at the extremity of a range of coastal mountains. It is provided with a lighthouse at an elevation of 300 feet above sea-level, and the beams from its powerful lantern are visible many miles out at sea. From this point the coast takes a decided sweep to the north-east to the head of Port Phillip through about a degree of latitude. Between Cape Otway and the Barwon Heads, close to the entrance of Port

Phillip, the coast is rugged, and along the whole extent of this shore line there are only two places where a landing can be effected—at Apollo Bay and Loutit Bay—and these are difficult of approach in south-easterly weather. Point Lonsdale and Point Nepean are the headlands marking the entrance to Port Phillip Bay, the largest inlet on the coast of Victoria. The bay is a land-locked inland sea, having an extreme length of 30 geographical miles from north to south, and a breadth from east to west of about 35 miles. The entrance is about 2 miles across, and a short distance within there were originally numerous sandbanks and shoals impeding navigation; these have been so dealt with that they do not now offer any serious hindrances to navigation, as the channels are well-defined and lighted. The western arm of Port Phillip, known as Corio Bay, forms the harbour at Geelong, and Hobson's Bay at the northern extremity is the port of Melbourne. At Queenscliff, just within the heads, there is a lighthouse at a height of 109 feet above sea-level. Cape Sohank is an imposing headland on the peninsula between Port Phillip and Western Port, and is provided with a lighthouse 278 feet above sea-level. The greater part of Western Port is shallow and unfit for navigation, but good anchorage may be found with shelter in all winds. The shores of the inlet are generally flat, and in some places swampy, but there is some excellent land in the surrounding district. Cape Liptrap is a narrow point on the western shore of Waratah Bay, and culminates a short distance inland in an eminence rising to a height of over 500 feet and constituting a prominent landmark. Wilson's Promontory, the southmost point of Australia, is a towering granitic mass connected with the mainland by a narrow sandy isthmus, and is a prominent turning-point for vessels from the westward bound for the east coast of Australia. The headland is provided with a lighthouse at an elevation of 383 feet above sea-level. Lying off its extremity are several rocky islets, whose granitic sides rise steeply out of the long rolling waves of the Southern Ocean. Rounding the promontory, the next important indentation is Corner Inlet, protected at its entrance by numerous islands, of which the largest is Snake Island. The inlet is not of much account for navigation purposes, as it is very shallow, portions of it being quite dry at low tide. From this point onward the coast trends north by east, and the greater part of it right up to Cape Howe is low and sandy. Here is situated the Ninety-mile Beach, consisting of an unbroken line of sandy shore, whose monotony is hardly relieved by a background of low sandy dunes. The length of this stretch of coast-line is, moreover, considerably in excess of 90 miles. Towards the eastern portion the sand dunes are backed by a succession of lakes, in places communicating with the sea by narrow channels. Farther on, where the shore line sweeps round to the east, the elevation increases, occasionally rising into bluff eminences. The principal headlands in this portion of the coast are Cape Conran, Cape Everard, and Ram Head. Cape Everard is supposed to have been the first



portion of the coast seen by Captain Cook, and the projection was named by him Point Hicks. Cape Howe, the eastern extremity of the state, lies in latitude  $37^{\circ} 31'$  south and longitude  $149^{\circ} 59'$  east.

The largest island possessed by Victoria is French Island, situated in Western Port, but a considerable portion of its area consists of mud-flats and swamps, so that it is but scantily peopled. Phillip Island, also situated in Western Port, has a population of about 400. Snake Island and Sunday Island, lying off Port Albert, are both low and swampy. Gabo Island, about 5 miles south-west, of Cape Howe is provided with a lighthouse and signalling station.

#### GENERAL PHYSICAL CHARACTERISTICS.

The southward projection of the Great Dividing Range of Australia traverses the state from east to west at a distance varying from 60 to 70 miles from the coast. There are thus, roughly speaking, three great surface divisions—the plain sloping from the mountains southwards to the sea, the elevated table-land country traversed by the Dividing Range, and the plain region sloping from the mountains northward to the Murray River.

The eastern portion of the Great Dividing Range is known as the Australian Alps, and the range terminates to the west in the Pyrenees and Grampians. There are at least six peaks in the cordillera exceeding 6,000 feet in height, and a considerable number between 5,000 and 6,000 feet, the principal being Mount Bogong, 6,508 feet; Mount Feathertop, 6,303 feet; Mount Hotham, 6,100 feet; Mount Cobberas, 6,025 feet; Mount Gibbs, 5,764 feet; and Benambra, 4,840 feet. The average elevation of the Victorian mountains is, however, only about 3,000 feet. Snow lies on the higher portions of the Dividing Range during several months of the year. Below the winter snow-line the mountains are generally well wooded, some of the trees reaching gigantic proportions; but the peaks above this line are bare, or partially covered with stunted trees and shrubs. The scenery in some of the mountain ranges, and particularly in the Bogong Mountains, makes a deep impression on all beholders, and, as in New South Wales, the characteristics are such as are not found in any other part of the world. The first impression left on the mind at sight of these examples of Nature's handiwork is one of stupendous power, coupled with a feeling of weirdness and utter loneliness. The absolute stillness is rarely broken by the song of birds, the whirring of wings, or the cry of wild animals. Parts of these primeval ranges have never been trodden by the foot of white man, and, it is believed, were inaccessible even to the aboriginal native. Geologists affirm that the mountain ranges here belong to the very dawn of time, and, indeed, the tremendous proportions of the giant trees found in the valleys are silent witnesses to a great antiquity. Under different atmospheric conditions, the mountains present many beautiful gradations of colouring, ranging, at times from deep purple to delicate blue. On

clear days the distant summits stand sharply outlined against the sky, while at other times looming through a wreath of mist and cloud, the mighty mass of the nearer elevations is strangely intensified.

The surface of Victoria is drained by two fluvial systems, the one consisting of streams which have their sources on the northward slope of the Dividing Range and flow towards the Murray, the other comprising the watercourses which have their origin on the seaward slope of the mountains and which drain into the Southern Ocean. Of the rivers comprised in the first category, the most important are as follows. The Goulburn, which has a total length of 345 miles, rises in the vicinity of Mount Matlock, and its course lies through some most picturesque country; in its upper portion it winds in and out through labyrinthine ranges whose sides are in places heavily timbered, while in others steep and bare precipices rise abruptly from the channel of the stream. Lower down it passes through stretches of rich agricultural land. Its tributaries, the Jamieson, Howqua, Seven Creeks, and Broken River all drain country possessing somewhat similar characteristics. The Loddon (225 miles) enters the Murray near Swan Hill. The Campaspe (150 miles) rises near Mount Macedon, and, after receiving the waters of the Coliban, drains some excellent agricultural land, and enters the Murray at Echuca. The Ovens has a course of 140 miles from its source in the vicinity of St. Bernard Mount till it gives up its waters to the Murray near Bundalong; its lower course runs through splendid pastoral country. Between the King River, which joins the Ovens at Wangaratta and the main stream, are situated the fertile Oxley Plains. The Mitta Mitta rises in the Bogong district at an altitude of over 2,000 feet, and after a course of 175 miles joins the Murray a few miles to the east of Albury. During its course the stream receives several tributaries, of which the most noteworthy are the Dark River on the right, and the Victoria, Bundarra, and Big Rivers on the left bank. Much of the country drained by this river is mountainous, and contains some very wild and picturesque scenery. The Avoca (163 miles) and the Wimmera (228 miles) both fail to reach the Murray, the lower courses of the rivers terminating in salt lakes or marshes.

The Snowy is the longest of the coastal rivers, and after a course of 300 miles, only 120 of which, however, are in Victoria, enters the sea near Point Ricardo. The country passed through in Victoria is wild and almost wholly unoccupied. West of the Snowy River the Tambo, Mitchell, and Latrobe drain into the lakes in the Gippsland district. The Yarra rises near Mount Baw Baw, and after a course of 150 miles enters the sea at Port Phillip. The name of the river is an aboriginal term, signifying everflowing. Its upper course lies through rough mountain country, clothed in places with magnificent forests of beech. After receiving the waters of Badger Creek, the stream emerges into a more open region, where it is joined by the river Watts. In the country drained by these tributaries there are some densely-covered forest areas,

containing magnificent specimens of *eucalyptus amygdalina*. Some of these giants of the bush reach a height of over 400 feet; in one specimen that was measured the distance from the ground to the first branch, where the tree had a diameter of 4 feet, was no less than 295 feet. Other trees measured close to the ground had a circumference of 130 feet. The leaves of the *E. amygdalina*, as well as of the *E. globulus*, which abounds in the district, yield on distillation a valuable medicinal oil. Near the sea, where the city of Melbourne stands, the stream widens considerably, and the channel has been deepened to afford increased facilities for navigation. The Hopkins (155 miles) rises in the southern slopes of the Pyrenees, and after draining some excellent pastoral country, and in addition the fertile Warrnambool district, enters the ocean near the town of Warrnambool. The Glenelg, which has a length of 280 miles, is one of the most tortuous rivers in the state; its basin contains fine pastoral country.

The lakes in the north-western district are indeterminate as to area, their size depending on the rainfall. Lake Hindmarsh in some seasons has an area of 30,000 acres, and Lake Albacuyta of 13,000 acres. These depend for their supplies on the expansion of the Wimmera River; Lake Tyrrell, 60 miles north-west of Lake Albacuyta, also owes its existence to a stream flowing into it from the south; but it has no ascertained outlet. In seasons of drought its waters dwindle considerably, and this applies also to Lake Buloke, 50 miles south of Lake Tyrrell, which has an area of 11,000 acres. On the southern side of the Dividing Range, and due north from Cape Otway, are situated Lakes Corangamite and Colac. The waters of Lake Corangamite, which is situated at an elevation of 380 feet above sea-level, are salt, and cover an area of 90 square miles. The lake is 16 miles long, and has a breadth of 8 miles in its widest part. Lake Colac, with an area of 10 square miles, is fresh. The soil in the districts surrounding these lakes is extremely fertile, and shares with the Gippsland district the claim to be considered as the garden of Victoria.

The Gippsland Lakes lie immediately to the rear of the Ninety-mile Beach, and are separated from the ocean by a narrow belt of sand interspersed with chains of salt-water lagoons. In places the lakes communicate with the sea by narrow shifting channels, and, to obviate this disability to navigation, the Victorian Government went to considerable expense in the construction of a permanent entrance. The most important of the lakes are Lake Wellington, Lake Victoria, and Lake King. Farther east is Lake Tyers, a beautiful expanse, the scenery surrounding which has been compared to that of Port Jackson and Port Stephens in New South Wales. The principal lakes, which receive the drainage of several rivers and creeks, are fresh water; they are visited by large numbers of tourists, to whom they offer many attractions. The Gippsland district is famed for its fertility, and is the home of a prosperous agricultural and pastoral population.

## QUEENSLAND.

### AREA AND BOUNDARIES.

THE State of Queensland occupies the north-eastern portion of the continent of Australia, and embraces within its limits an area of 668,497 square miles. It is bounded on the north by the Gulf of Carpentaria and Torres Strait, on the east by the Pacific Ocean, on the south by the State of New South Wales, and on the west by South Australia and the Northern Territory of that State.

### COASTAL FEATURES.

Queensland has a coast line measuring 3,000 miles, well marked and lighted throughout, and portions of it, particularly in the north after leaving Keppel Bay, are remarkable for the beauty of their scenery. From Mackay northwards towards Bowen, the Whitsunday Passage offers magnificent views of mountains rising abruptly from the margin of the ocean, together with many picturesque islands, whose densely-wooded sides dip down to waters of the deepest blue. The Hinchinbrook Passage is especially noted for the grandeur of its scenery, particularly in autumn, when the wild mountain sides next the sea are brightened by the presence of numerous flashing cascades. In addition to the hosts of islands off the east coast, the presence of the Great Barrier Reef tends to break the force of the waves, and affords a comparatively smooth passage up or down the coast. This vast natural breakwater, built up by the tireless energy of the coral polyp, lies at a distance of from 10 to 150 miles from the shore, and the long voyage from Torres Strait on the north, as far down as Cape Capricorn, may be performed entirely within the sheltered channel thus formed. There are numerous openings by means of which vessels sailing in the open ocean may pass through to the calmer waters between the reef and the shore, but these passages require very skilful negotiation. Captain Cook's vessel, the "Endeavour," had the misfortune to strike on the reef in 1770, and but for the fact that a portion of the coral came away when the ship floated off, and helped to block up the rent in her timbers, the historic voyage would have had a disastrous ending. Cook appropriately named the headland near by Cape Tribulation, and the stream at the mouth of which he careened and repaired his vessel the Endeavour River. The point in the reef where his mishap took place has been located, and a gun and various other relics are stated to have been recovered therefrom.

Proceeding northwards from Point Danger, the northernmost point of New South Wales, there is a stretch of rather uninteresting coastline, the first important headland being Lookout Point, on the extreme

end of Stradbroke Island. The projection on the north-western corner of the island is known as Amity Point. Cape Moreton, on Moreton Island, is a rocky promontory, on which a lighthouse has been erected. The next important projection is Double Island Point, on the southern crescent of Wide Bay. Here a lighthouse has been erected at a height of 315 feet above the level of the sea. From this point northward the coastline takes a decided sweep to the west, through about 11 degrees of longitude. Bustard Head stands at the entrance to Port Curtis. The bluff promontory on the north-eastern end of Curtis Island was named Cape Capricorn by Captain Cook, because it lies almost precisely under the tropic line. A lighthouse stands on the headland at a height of 316 feet above the sea. Continuing northward past Cape Manifold and Cape Townsend, shoals of small islands are passed through. Cape Conway lies at the northern end of Repulse Bay, and the passage northwards from this point is thickly studded with islands, the scenery in the neighbourhood being strikingly picturesque. Cape Bowling Green, on the southern part of the bay of the same name, is provided with a lighthouse. Near Cape Cleveland the coastal scenery for miles is dominated by Mount Elliott, which rises to the height of 4,000 feet. From Cape Grafton northwards the coastline offers much grand and striking scenery. At times the mountain sides rise directly out of the ocean, at others retreating inland, many charming vistas of wooded plain and rugged height are disclosed. Cape Tribulation, named by Captain Cook, is about 30 miles south of Cooktown, while 30 miles northward is the projection known as Cape Flattery. The Great Barrier Reef is here fairly close to the shore, and there are numerous subsidiary reefs and islets. Farther north Cape Melville stands at the entrance to Bathurst Bay. Higher up on Cape York Peninsula are the headlands named Cape Direction and Cape Grenville. Cape York, the most northern point of Queensland and of the Australian continent, is situated in latitude  $10^{\circ} 40'$ . Rounding Cape York and turning southward into the Gulf of Carpentaria, the scenery undergoes a complete change. Instead of the lofty precipices and richly-wooded heights and islands of the eastern coast, the Gulf shore for many miles consists of monotonously low swampy ground and dismal clumps of mangrove. The only noteworthy projections on the eastern side are Duyfken Point (erroneously spelled on the map as "Duyfhen") and Cape Keerweer, both reminiscent of the early Dutch visitors to these localities. On the southern shore are Points Tarrant and Bayly.

The eastern coast of Queensland, from Point Danger right up to Cape York, is diversified by numerous indentations, but the contour of the shore line in the Gulf of Carpentaria is more or less regular and unbroken. Commencing from the south, the first noteworthy indentation is Moreton Bay, the entrance to which is protected by Moreton and Stradbroke Islands. The bay, which receives the drainage of the Brisbane River, is shallow, and navigation is rendered difficult by the presence of numerous flats and banks. The channel, however, is well lighted, and

the more troublesome obstacles are being removed by constant dredging. Wide Bay is situated at the mouth of the Mary River, between Fraser or Great Sandy Island and the mainland. A dangerous shifting bar obstructs the entrance. Hervey Bay is protected by the northern end of Great Sandy Island. Higher up is Port Curtis, with Facing Island opposite it. Keppel Bay is a large inlet, on which the town of Rockhampton is situated, Curtis Island lying at the south. Broadsound is a considerable inlet situated in latitude 22°, the sea near its entrance being dotted with numerous small islands. Port Denison is the harbour of Bowen, and possesses excellent anchorage of from three to five fathoms. Cleveland Bay, on which Townsville is situated, is protected on the south by Cape Cleveland, and on the north by Magnetic Island. The approach is well marked and lighted. Rockingham Bay is a large inlet in latitude 18°, Hinchinbrook Island lying at its southern extremity. Mourilyan Harbour, north of Double Point, has a narrow entrance, but affords excellent anchorage of from four to twelve fathoms. Cooktown is situated on the Endeavour River, and while the entrance to the bay is narrow the port is easily negotiated. Princess Charlotte Bay is a large inlet situated in latitude 14°. Near the head of Cape York Peninsula is situated the harbour of Port Albany. The fortified harbour of Thursday Island, an important place of call for steamers trading to China and Japan, is situated in Torres Strait. In the Gulf of Carpentaria there is a fine harbour at the mouth of the Batavia River, named Port Musgrave. The best anchorage at the head of the Gulf is the Investigator Road.

#### GENERAL PHYSICAL CHARACTERISTICS.

As is the case in New South Wales, the main features in the relief of Queensland are a coastal belt, a table-land region, and a great interior plain district.

The Great Dividing Range extending northwards from New South Wales enters Queensland territory at Wallangarra. Proceeding northwards to Maryland the range divides, the Herries Range branching off to the north-west, and the Main Range continuing to the north-east for about 40 miles. Here another bifurcation takes place, the Macpherson Range stretching to the sea coast, where it terminates at Point Danger, and the Main Range extending in a general north-westerly and westerly direction for about 35 miles. Another spur here branches off in a seaward direction, while the Main Range extends westerly and then northerly, and with many twists and turns traverses the entire length of the State. Grey Range enters the State at the 142° meridian, and extends northward to Gowan's Range, the Cheviot Range branching off to the westward. In the central districts are the Drummond, Peak and Denham Ranges. Clarke's Range and Leichhardt Range extend northwards in the northern districts nearly parallel to each other. The Boomer Mountains, Broadsound Ranges, and Connor's Range form the coast range nearly to Mackay. From Townsville,

northwards, the coast range is in close proximity to the sea, and is rugged and picturesque in character, while some of the peaks reach a considerable elevation. In the southern coastal district much of the land between the mountains and the sea is very suitable for farming purposes, most of the rivers and creeks running through alluvial soil of great richness. The highest peak in Queensland is Mount Bartle Frere, 5,438 feet. Mount Roberts in the Central district is 4,350 feet in height, and Mount Barney in the Macpherson Range reaches 4,300 feet. In the Coast Ranges the highest points are Wooroonooran, 5,400 feet, in the Bellenden Ker Range, and Mount Dalrymple, 4,200 feet, in the Mackay Range.

The rivers of Queensland may be classified into four distinct systems:—1. Those flowing eastward into the Pacific. 2. Those which form the head waters of the Darling and its tributaries. 3. Those flowing westward from the Great Dividing Range. 4. Those flowing into the Gulf of Carpentaria. As in the case of New South Wales, the coastal rivers of Queensland flowing into the Pacific Ocean have short rapid courses, and in periods of excessive rainfall are liable to floods. The entrances also are sometimes difficult to negotiate, on account of the presence of sandbars and shoals. Much has been accomplished in the way of getting rid of these disabilities by persistent dredging, and the channels have been artificially deepened; nevertheless, it is only in the tidal waters of these rivers that navigation is possible for ocean-going steamers. In Southern Queensland the principal coastal rivers are the Logan, Brisbane, and Pine, which drain into Moreton Bay; the Caboolture, flowing into Deception Bay; the Mary and Burrum, entering Wide Bay; and the Burnett, Kolan, and Elliott Rivers, which debouch into Hervey Bay. In Central Queensland the Calliope and Boyne Rivers drain into Port Curtis. The Fitzroy River is the second in point of size on the eastern coast, and is navigable by deep-sea vessels as far as Rockhampton. The river enters the sea at Keppel Bay, and during its course receives several tributary streams, the principal of which are the Dee, Dawson, Mackenzie, and Isaac Rivers, the total area of its basin being about 55,600 square miles. In Northern Queensland the chief coastal rivers are the Pioneer, entering the sea at Mackay; the Don at Bowen. The Burdekin, which debouches into Upstart Bay, is the finest of Queensland's coastal rivers. Its drainage area covers 53,500 square miles. Numerous tributaries discharge into the main stream, the most important being the Boyne, Bogie, Belyando, Suttor, Cope, Campaspie, Basalt, Clarke, and Star Rivers. Even in the driest seasons the stream, within a few miles of its outlet, carries a large body of fresh water, and this probably prevents the formation of a defined bar close to its mouth. Farther north, the Ross River falls into Cleveland Bay; the Herbert enters the sea at Lucinda Point; the Tully flows into Kennedy Bay; the Moresby into Mourilyan Harbour; the Russell and Mulgrave at Bramston Point; the Barron near Cairns; the Endeavour at Cooktown; the Mosman

and Daintree near Port Douglas; the Bloomfield into Weary Bay; the Normanby into Princess Charlotte Bay; and various small streams higher up in Cape York Peninsula. The celebrated Barron Falls are situated on the Barron River, at the point where the stream descends from the table-land and leaps down a distance of 830 feet to the valley below. The main fall is 370 feet in height.

The rivers rising in the western slopes of the Dividing Range include the Macintyre or Barwon, which receives the Macintyre Brook, and the Dumaresq or Severn, and after crossing the New South Wales border, unites with the Moonie River. The Condamine, or Balonne, rises near Warwick, and after being joined by the Maranoa River, separates into branches, which all become united with the western fluvial system of New South Wales. The Warrego rises in the Warrego Range, and, flowing southerly, joins the Darling. The Paroo and the Bulloo, or Corni Paroo, lie between the Grey Range and the Warrego. These are in reality depressions, along which in seasons of exceptional rainfall a large body of water finds its way into New South Wales southwards towards the Darling. Further west the Victoria, or Barcoo, flows under the name of Cooper's Creek into Lake Eyre, while the Diamantina loses itself in the stony desert to the north-east of that lake.

Several fine navigable streams fall into the Gulf of Carpentaria; but as the northern country round the Gulf is only in the initial stages of development, their capabilities, with the exception of the Norman and Albert Rivers, remain unutilised. Amongst the principal streams debouching into the Gulf are the following:—Batavia, Archer, Colman, Mitchell, Staaten, and Gilbert on the eastern shore; and the Norman, Flinders, Leichhardt, Albert, and Gregory on the southern shore. Much of the country through which these rivers flow is excellently adapted for pastoral purposes, while the mountains in which they have their sources contain mineral treasures, as yet only partially developed.

The only lakes worthy of mention in Queensland are Lake Galilee, or Jochimo, and Lake Buchanan. These are situated in Central Queensland, and are both salt. Some of the western rivers flow into salt lakes, but their area is indeterminate, as their volume depends on the rainfall.

For general purposes the state has been divided into twelve districts. A brief description of the characteristics of each division may not be without interest.

The Moreton District occupies the south-eastern portion of the state immediately to the north of New South Wales, and extends inland to the Dividing Range. It is a fertile, well-watered district, drained by the Brisbane, Bremer, and Logan Rivers. Sugar cane and maize are grown and thrive luxuriantly, coal occurs in several localities on the Bremer, and gold is found in the Enoggera Ranges, west of Brisbane.

The Darling Downs District lies immediately to the west of the Moreton District, in the table-land region, and forms one of the richest



pastoral and agricultural areas of the State. The southern portion is the great wheat-growing district of the State, and at Stanthorpe, near the New South Wales border, large deposits of tin have been found. North of the Moreton District is the Burnett or Wide Bay District. The rich alluvial soil in this division is especially suitable for the growth of sugar, cotton, arrowroot, ginger, and other tropical productions. In the Gympie district rich deposits of gold have been found, while coal is worked on the Burrum River.

Port Curtis District lies to the north of the Burnett division, and is watered by the Dawson, Fitzroy, Calliope, and Boyne Rivers. This area is rich in mineral wealth, gold being found at the Calliope River, the Boyne, Fitzroy, and at Mount Morgan.

The Leichhardt District is a fine pastoral area west of the Port Curtis Division, and is watered by various tributaries of the Fitzroy. Copper, gold, coal, and other minerals are also found.

The Maranoa District consists of table-land and downs, and lies west of the Darling Downs and south of the Leichhardt District. It is watered by the Maranoa, Culgoa, Balonne, and Moonie Rivers. Much excellent pastoral country is found throughout, while in the Roma district the soil is well adapted for wheat.

The Warrego District lies westward of the Maranoa, and is almost exclusively pastoral in character. The rainfall is intermittent, and the water supply in many places is obtained from bores, which have generally yielded very successful results.

The Kennedy District occupies the middle coastal portion of the state, and is well watered by the Burdekin and other streams. The country round Mackay produces a large quantity of sugar. In this division also is situated the Charters Towers Goldfield, one of the richest in the State.

The Burke District lies west of the Kennedy division, and extends to the southern portion of the Gulf of Carpentaria. Much of this area is under occupation for pastoral purposes, but a large extent of country is yet undeveloped. At Croydon are situated the well-known goldfields of that name, while at Cloncurry, in addition to gold, there are rich deposits of copper.

The Mitchell District lies to the westward of the South Kennedy division. It is watered by the Barcoo and Thompson Rivers, and is entirely pastoral.

The Gregory District lies between the Mitchell, Burke, and Warrego Districts and the South Australian boundary. It is watered by the Diamantina, Herbert, Wilson, and Mulligan Rivers, and traversed by Cooper's Creek and other watercourses. The district is almost entirely given over to pastoral pursuits. Opals have been found in various places throughout the area. Its south-eastern boundary is formed by the Grey and Cheviot Ranges; other ranges in the south are the Coleman, Cameron, and Macgregor Mountains.

## SOUTH AUSTRALIA.

### AREA AND BOUNDARIES.

THE State of South Australia occupies a position midway between the other four provinces on the Australian mainland, and embraces within its limits a total area of 903,690 square miles. As originally constituted by the Imperial Statute 4 and 5 William IV, cap. 95, the 132nd meridian of east longitude formed the western boundary, and the 141st meridian the eastern limit. From north to south the province extended from the 26th parallel of south latitude to the Southern Ocean. The area of territory comprised within these boundaries was about 300,000 square miles. By fixing the western boundary at the 132nd meridian, a strip of country about 90 miles in width was left intervening between that meridian and the eastern frontier of Western Australia, and this region, containing an area of over 80,000 square miles, was added to South Australia in 1861. Two years later, a further accession was made by including within the confines of the State all the country stretching northward from the 26th parallel of south latitude to the Indian Ocean, in addition to the territory lying between the meridians of 129° and 138° east longitude. The area of the state was thus brought up to its present large proportions, next to Western Australia the province being the most extensive of the group. The portion of the state to the north of the 26th parallel, known as the Northern Territory, is so dissimilar, as regards climate and resources, to the southern division, that it may almost be looked upon as a separate possession.

### COASTAL FEATURES.

The coast line on the south, with the exception of the large inlets of Spencer Gulf and St. Vincent's Gulf, is not diversified by any very remarkable indentations. From west to east the shore line has a general downward trend through about six degrees. Commencing from the western extremity, there is a vast crescent-shaped curve terminating at Cape Catastrophe, and forming the eastern portion of the Great Australian Bight. For the first 120 miles from the western boundary the shore is backed by precipitous limestone ridges, varying in height from 400 to 600 feet. Passing the head of the Bight, the first noteworthy headland is Cape Nuyts, a lofty promontory a little to the eastward of longitude 132°. Rounding this point, Fowler's Bay opens

out, and thence, after passing through the cluster of islets known as Nuyts Archipelago, Streaky Bay is entered, one of the finest harbors in this portion of the coast. The northern headland is named Point Brown, while Cape Bauer lies at the south. Farther down is Cape Radstock, a well-known landmark for mariners sailing to the east. Then comes Anxious Bay, which affords good anchorage but is unsafe during the prevalence of certain winds. Off Cape Finniss lies Flinders Island and the Investigator Group, the names being reminiscent of the explorer of earlier days. Coffin's Bay, to the eastward of Point Sir Isaac, offers excellent shelter from westerly or southerly gales. Sleaford Bay, between Cape Wiles and Cape Catastrophe, is a fine inlet with deep water in various parts. Spencer's Gulf is the largest inlet on the south coast of Australia; its entrance lies between Cape Catastrophe at the western extremity, and Cape Spencer at the foot of Yorke's Peninsula on the eastern side, and is 47 miles wide. Port Augusta at the head of the Gulf is distant 180 miles from the entrance. The inlet has a shore line of about 400 miles and offers everywhere excellent facilities for navigation to vessels of the greatest burden. Spencer's Gulf is separated from the next large inlet, called St. Vincent's Gulf, by Yorke's Peninsula. St. Vincent's Gulf has a width at the entrance of thirty-four miles, and a length of about eighty miles. Port Adelaide is situated on its eastern shore, and is the principal harbor of the State. The entrance to St. Vincent's Gulf is protected on the south by Kangaroo Island, one of the largest islands on the Australian Coast. It measures eighty miles east and west, and has an average width of about twenty miles. Cape Borda, a well-defined headland, is situated on its western side, and Cape de Couedie and Cape Gantheaume on the south. The passage between the island and Yorke's Peninsula is called Investigator's Strait, and that between the eastern portion and the mainland, Backstairs Passage. From Encounter Bay to the eastern boundary of the state the coast is generally low and flat. Between Cape Jaffa, at the southern extremity of Lacedupe Bay, and Rivoli Bay, the presence of numerous reefs and shoals, in some cases extending out for many miles from the shore, necessitates extreme caution on the part of navigators. After leaving Rivoli Bay the next important headland is Cape Banks, conspicuous by a white sand hummock near its extremity. Cape Northumberland is the last projection on the eastward portion of the coast, and is a prominent elevation capped by the McDonnell Lighthouse. Generally speaking, the south coast, which has a total length of upwards of 1,600 miles, is well-marked and lighted.

The northern coast, which embraces the shore line of Arnhem Land with the western portion of the Gulf of Carpentaria, is more broken and irregular than the south coast. Here, too, are the estuaries of several fine rivers, while, with the exception of the Murray, there is hardly a river worthy of mention that reaches the Southern Ocean. Commencing on the western boundary, the chief inlets are Queen's

Channel and Keys Inlet. Passing the headlands of Cape Hay and Cape Scott, Anson Bay is entered, the Péron Islands lying at the northern entrance. After threading through several small islets, the entrance to Port Darwin opens out. This fine harbour was named after Dr. Darwin, who accompanied King on his surveys of the north coast (1818-1822), and is remarkable for its magnitude and security, as well as for the beauty of its scenery. Situated in latitude  $12^{\circ} 28' 22''$  south and longitude  $130^{\circ} 50' 26''$  east, the harbour has an entrance two miles in width, with a depth of water of about 15 fathoms. Within there is unlimited accommodation for all classes of vessels, the depth ranging from 4 to 15 fathoms, with good anchorage close up to the shore. The chief drawback to the many natural advantages of the port is the extraordinary rise and fall of the tide, the spring tides rising to from 16 to 24 feet, and the neaps from 2 to 12 feet. This disadvantage has, however, been combated by the erection of a splendid jetty, provided with every convenience for mooring. A peculiar feature of the harbour is the presence of a natural dock, formed by a sloping sand bank at the foot of Fort Hill, where vessels may be safely stranded at spring tides, repaired at low-water, and re-floated on the next recurring high tide. The town of Palmerston is situated on a plateau-like expanse 60 feet above the level of the sea, and occupies a commanding position near the entrance. Opposite Port Darwin, and to the westward of the large inlet of Van Diemen's Gulf, are the two large islands called Melville and Bathurst Islands. The former is 75 miles long and 38 broad, and is fertile and well watered. A military station at one time existed at Port Dundas, but since its abandonment in 1840 the island has been given over to the almost exclusive possession of the blacks. Between the Coburg Peninsula, enclosing the western portion of Van Diemen's Gulf and Melville Islands, the passage is known as Dundas Strait. Rounding the peninsula numerous groups of islands are passed through, the chief of those which have received names being the Goulburn, Crocodile, Elcho, and Wessel Islands, but none of them has any commercial importance, and indeed they are rarely visited, except perhaps by the proas of the Malay traders. In the Gulf of Carpentaria, the principal inlet is Blue Mud Bay, off which there are numerous islands, the largest bearing the Dutch name of Groote Eylandt.

#### GENERAL PHYSICAL CHARACTERISTICS.

As previously stated, the only river of importance discharging into the Southern Ocean is the Murray, which flows through South Australian territory from the 141st meridian of east longitude, and debouches into Lake Alexandrina, and thence into the sea at Encounter Bay. The entrance is dangerous during the prevalence of certain winds, but much has been done in the way of deepening and improving the channel. Proceeding westward from the Murray, two small rivers,

the Hindmarsh and the Inman, empty into the bay, but their mouths are obstructed by sand bars and reefs. The Torrens rises in the Mount Lofty Ranges, and, after many twists and turns in a westerly direction, reaches the Torrens Gorge, whence it emerges from the hills and drains the fertile Adelaide Plains. After separating North Adelaide from the southern portion of the city, it spreads its waters over a vast tract of swampy land at a short distance from the coast. Ten miles north of Port Adelaide, the Gawler flows into St. Vincent's Gulf at Port Gawler. Farther west there are no streams of importance, the country surrounding the Bight in particular being destitute of streams of any magnitude.

In the Northern Territory, however, there are several fine navigable rivers, and with the further development of this portion of South Australia they are certain to assume considerable importance. The McArthur flows into the Gulf of Carpentaria opposite the Sir Edward Pellew Islands, and is navigable for small vessels for a distance of 50 miles. Much of the basin drained by this stream consists of good pastoral lands. The Roper, which debouches into the Gulf at Limmen's Bight, is navigable for about 90 miles. This is the best known river on the northern coast, and much of the country surrounding it has been taken up for pastoral purposes. The Goyder flows into Castlereagh Bay, and is navigable for 13 miles, but the lower course of the stream is lined by dense and impenetrable mangrove jungles. The Blyth enters Boucaut Bay, and is navigable for a distance of 18 miles. Into Van Diemen's Gulf flow the three Alligator Rivers, discovered by King in 1820, and named respectively the East, West, and South Alligator. They are all navigable for some distance from their mouths. The Adelaide discharges into Adam Bay, after draining a large extent of good pastoral country. It is accessible to vessels drawing from 10 to 12 feet, and has been navigated for a distance of 80 miles. The Daly River debouches into Anson Bay, and is navigable for vessels of light draught for 60 miles. In spite of the fact that there is only about 3 feet of water on the bar at low tide, the rise of tide, being from 18 to 24 feet, permits the largest vessels to negotiate the entrance with safety. Good agricultural land is found on its banks, and deposits of copper also occur within its basin. The Victoria, discovered by Stokes in 1839, is the finest river on the northern coast. Between Turtle and Pierce Points the entrance is 20 miles wide, and the stream is navigable by vessels of the heaviest burthen for 50 miles from its mouth. The area of the basin of the Victoria has been computed as, approximately, 90,000 square miles. Little is known of the major portion of its watershed, but extensive tracts have been occupied for pastoral purposes.

Many watercourses are found in the interior, and some of them extend for hundreds of miles, but their volume varies with the season. Cooper's Creek, the Diamantina, and other streams from South-Western Queensland at times inundate the country for thousands of square

miles, at others dwindle to mere chains of pools. The Todd, the Finke, and the Macumba either sink into the plains or, in favourable seasons, reach the inland lakes.

A reference to the map will make it appear as if South Australia were well provided with lakes, some of them being of considerable extent. These expanses of water are, however, mostly salt and useless for purposes of navigation.

The largest group of salt lakes is found to the north of Spencer's Gulf, and includes Lake Eyre, the surface of which is 39 feet below sea-level, Lake Torrens, Lake Gairdner and Lake Frome. The largest of these occasionally exceed 100 miles in length, but in periods of drought they dwindle into comparative insignificance and at times become quite dry. Their sites are then marked by expanses of black mud with saline incrustations, and the earlier explorers who attempted to cross these hideous bogs had to turn back repeatedly in despair. Farther to the north, and towards the centre of the continent, is the salt morass called Lake Amadeus.

Several lakes are situated close to the south coast between Cape Banks and Guichen Bay. Lake Bonney is fresh and has a length of 25 miles by a breadth of 2 miles in its widest part. Its waters are, however, shallow, although it is surrounded by fairly high banks. Lake George is about 10 miles long by 5 in width at the broadest part. Lake St. Clair is a much smaller expanse, and is salt and shallow. The morass called Lake Hawdon lies north and east of Lake Eliza, and is 40 miles long by 8 wide. The Coorong, 40 miles west of Lake Hawdon, has an opening to the sea near the mouth of the Murray. It is about 70 miles long and 4 wide. Lakes Alexandrina and Albert are situated at the mouth of the Murray and are joined by a narrow channel. From their appearance, it seems a likely assumption that they were originally arms of the sea, and that their coastal banks have resulted from upheaval. Lake Alexandrina is 24 miles long and 14 miles wide, and is generally shallow. Lake Albert is 14 miles long by about 8 in breadth at its widest part.

In the Mount Gambier region several remarkable lakes are found occupying the craters of extinct volcanoes. The most celebrated of these is the Blue Lake, which is irregularly circular in shape and about a mile in diameter. The sides of the lakes which are several hundreds of feet in height, descend precipitously to the water and are agreeably diversified by charming verdure. Soundings have proved the depth of the principal lake to be about 240 feet, and on clear days its waters are of a most beautiful deep blue.

The general physical contour of the surface of South Australia in no way resembles that of the eastern states already described. In those States the general trend of the mountains is parallel to the shore, and there are the three more or less well-defined zones of coastal district, tableland, and interior plain. But in South Australia the mountains pierce the interior and end abruptly amongst the inland salt

lakes and swamps. North of Lake Torrens no well-defined system of mountains exists. The first group of mountains is that of the Adelaide Chain, which commences at Cape Jervis and penetrates in a northerly direction to Lake Frome, a distance of 350 miles. The range attains its greatest elevation in the Mount Lofty and Barossa districts, the highest points being Mount Lofty, 2,334 feet, and Razorback, 2,834 feet. Its course is interrupted here and there by a few narrow gorges, through which flow the small streams discharging into St. Vincent's Gulf. The Flinders Range commences in the conspicuous landmarks called the Hummocks, at the head of St. Vincent's Gulf, and pursues a northerly direction to the head of Lake Torrens. The highest points in this range are the Bluff, 2,404 feet, and Mount Remarkable and Mount Brown, each about 3,000 feet. On the west side of the Adelaide Chain are the fertile and extensive Adelaide Plains, one of the finest wheat-growing districts in the world. Plains of similar fertility, but of less extent, are found between the longitudinal ridges of the Flinders Range and the northern prolongation of the Adelaide Range. On the eastern side of the Adelaide chain stretches the plain of the south-east, towards the western boundary of which the Murray flows. From north to south this plain is 290 miles in width, and about 100 miles from east to west. A vast plain district also stretches north and west from Lake Torrens. The Gawler Range originates in Eyre Peninsula, on the western side of Spencer Gulf, and, reaching an elevation of 2000 feet, extends to the southern shores of Lakes Everard and Gairdner. The Warburton and Stewart Ranges lie west and north of these ranges, and where the province adjoins the boundary of the northern territory the country rises to the McDonnell Ranges, the highest elevation between the northern and southern watersheds. Respecting the mountains in the Northern Territory, little can be said, as they have not, up to the present, received any detailed examination.

In the south-eastern portion of the province are situated Mount Gambier, Mount Schanck, Mount Terrible, and several other isolated peaks, which were formerly volcanoes, the craters being now occupied by fresh-water lakes. The best known of these, the Blue Lake of Mount Gambier, has already been alluded to.

For a long time it was supposed that the interior of South Australia was a barren desert, the home of the hot blasts that periodically visit the south. Although a large portion of the territory is admittedly arid and inhospitable, in many places near perennial waters the soil is of surprising richness. With the further exploitation of the large stores of artesian water underlying the country, much of the seemingly hopeless wilderness will, in time to come, be made to "blossom as the rose."

## WESTERN AUSTRALIA.

### AREA AND BOUNDARIES.

THE state of Western Australia, as its name implies, occupies the western portion of the Australian continent, and is by far the largest of the states, containing within its confines an area of no less than 975,920 square miles. On its eastern boundary it is separated from South Australia by the 129th meridian; the Indian Ocean washes its northern and western shores; and the southern boundary is formed by the Great Southern Ocean. The greatest length of the territory, from Cape Londonderry on the north to Peak Head on the south, is 1,480 miles, and the greatest breadth, from Steep Point on the west to the meridian on the east, is about 1,000 miles.

### COASTAL FEATURES.

With the exception of that portion to the northward of the 18th parallel, the coast line of Western Australia is singularly regular and unbroken, so that the total estimated length, 5,200 miles, is small when compared with the area of the state. On the southern coast, a long unbroken rampart of limestone cliffs stretches from Eucla, on the eastern boundary, round the western horn of the Great Australian Bight to Cape Arid. No river or creek pierces these frowning precipices, nor is there refuge of any kind for the storm-beaten vessel. Westward from Cape Arid, Esperance Bay and Doubtful Island Bay afford safe anchorage, but they are difficult of access during the prevalence of certain winds. King George's Sound is one of the most important inlets on the south coast. The entrance is between two bluff headlands, named respectively Cape Vancouver and Bald Head, and the harbour, which extends inland for some 10 miles, is well sheltered from all but south-westerly gales. An inner sheet of water, called Oyster Bay, is connected by a narrow channel with the Sound. Three miles southward another break in the shore line of the Sound leads into Princess Royal Harbour, on the northern shore of which the town of Albany is located—once an important place of call for the mail steamers. Situated as it is, the Sound is an important strategic naval position, and this fact has been recognised by the authorities, who have taken steps to fortify it. The country round the shores of the Sound is celebrated for the variety and profusion of the



wild flowers flourishing there, amongst which the sweet-scented boronia is especially remarkable. From King George's Sound round to Cape Leeuwin the coast is fringed by rugged granitic masses, and is broken by several small streams flowing into the sea. Cape Leeuwin is situated in the south-western corner of the continent, where the Indian and Southern Oceans meet, and is a prominent landmark for vessels voyaging to Australia. On calm, bright days the view from the lighthouse on the point, 700 feet above the sea, discloses enchanting vistas of Hamelin Bay, the mouth of the Blackwood River, and numerous inlets and reefs flashing gaily in the sunlight; but when the wind blows strongly from the west, the Lioness quivers as the thunderous waves dash at her feet, while the swirling spray is borne by the blasts for a long distance inland. Passing the Leeuwin, and sailing northwards, the next important point is Cape Naturaliste, at the entrance to Geographe Bay, on the shores of which stands the town of Busselton, the outlet of a thriving timber and dairying district. Leaving Cape Bouvard, 40 miles to the south of Perth, the low, scrub-covered Garden Island, sheltering Cockburn Sound, comes into view. Near by is Rottnest Island, on which the Governor's marine residence is situated, and the site also of a native prison. Between the two islands, vessels from the south approach the port of Fremantle on the Swan River. Two hundred miles further up the coast is the port of Geraldton, off which lie the dangerous Houtman's Abrolhos, the scene of many a wreck when the Dutch vessels in times gone by were wont to visit this portion of the continent. The Abrolhos have for ages been the resort of countless numbers of sea fowl, and rich deposits of guano are obtained on several of the islands in the group. Shark's Bay is an extensive inlet in latitude 26°, Dirk Hartog Island lying to the westward. Valuable deposits of pearlshell have been obtained from the shallow banks in this bay. Steep Point, on the west, is the most westerly point of the continent. North of this bay is situated Exmouth Gulf, a capacious inlet, with North-west Cape at its outer extremity. From the Leeuwin up to this point, the shore-line has had a north-westerly sweep, but from this onward the general trend is to the north-east. Cossack Harbour is the port of the magnificent pastoral district known as the "Nor' West," lying between the Ashburton and De Grey Rivers. Higher up is Roebuck Bay, on which the township of Broome is situated. King Sound is an extensive indentation, on the western extremity of which is situated the important headland of Cape Leveque. The inlet is the centre of the shipping trade of the great West Kimberley district, and the harbour offers excellent facilities for vessels. At the entrance to the Sound is the cluster of rocky islets known as the Buccaneer Archipelago. Between King Sound and Cambridge Gulf, the coast is deeply indented, the principal inlets being Collier Bay, Brunswick Sound, York Sound, Montague Sound, and Admiralty Gulf. Cambridge Gulf is a fine inlet, offering excellent anchorage for vessels of every class. The township of Wyndham, at

the head of the gulf, is the business centre of the whole of the East Kimberley district, and is the north-eastern terminus of the West Australian system of telegraphs. A large volume of trade is carried on with the southern ports, and also with Port Darwin, in the northern territory of South Australia. Numerous islands lie off the coast between King Sound and the Gulf, the most important being Augustus Island, near Camden Sound, and Bigge Island, north of York Sound. None of these islands has been very carefully examined, but they appear to be of the same rugged sandstone formation as the adjoining coast. Dampier's Archipelago, Barrow Island, and numerous others lie north-east of the North-west Cape. They are chiefly of granite formation, and some of them are well-grassed.

#### GENERAL PHYSICAL CHARACTERISTICS.

The whole of the interior of Western Australia, embracing the country between the 19th and 31st parallels of latitude, and 121st and 129th meridians of longitude, consists of a vast tableland between one and two thousand feet above the level of the sea. Of this immense stretch of territory, the greater portion consists of sand dunes and stony ridges, with here and there areas of clayey soil. Except in connection with the development of its mineral resources, it is believed that little of this portion of the state will ever be available for settlement. The lakes found in this district, except in periods of heavy rainfall, are merely salt marshes of greater or less extent, and sometimes become dry clay-pans. North of the 19th parallel the country consists of alternately high and low-lying expanses of tableland, intersected by several ranges of mountains. The Kimberley portion of this district contains several fine rivers. Much of the south-western and southern sea boards is of a flat, sandy character, and is covered in parts with vast forests, containing jarrah, karri, white and red gum, and many other timbers of great commercial value. In the limestone region north of the Great Australian Bight there are some fine stretches of grass country, needing only a permanent water supply to make them rank amongst the productive divisions of the state.

As previously stated, there are no streams of much importance flowing into the Southern Ocean; indeed, on the shores of the Bight there is a stretch of country, 300 miles in length, unpierced by any watercourse. The Blackwood, Warren, Kalgan, and Phillips enter the sea west of the Bight, towards Cape Leeuwin, some magnificent forest country being found in the basin of these streams. Flowing into the Indian Ocean, on the west coast, are the Preston, Collie, Swan, Greenough, Murchison, and Gascoyne. The Swan, upon which Perth, the capital of the State, is situated, receives the name of Avon above the tidal waters. On the north-west are the Ashburton, Oakover, Fortescue, and Fitzroy. The Kimberley district is watered by the Fitzroy, Ord, Pentecost, Durack, Drysdale, &c. Pastoral occupation is rapidly

spreading in the districts traversed by these streams, while the rich auriferous discoveries have also conferred an added importance on the territory.

In the southern portion of the state the Stirling Range, situated about 40 miles to the north-east of Albany, attains its highest elevation in Mount Toolbrunup, which reaches an altitude of about 3,000 feet. The range possesses a certain grandeur from the fact of its being perfectly isolated and rising abruptly from a level plain. In the south-western district the Darling Range runs north and south from Yatheroo to Point D'Entrecasteaux on the south coast. From its proximity to the western seaboard, this range exercises a great influence over the climate of the state in its most populous area. The highest point is Mount William, 1,700 feet in altitude, situated in the Murray district. Between the Fortescue and Ashburton Rivers is the Hamersley Range, in which Mount Bruce rises to a height of 3,800 feet, and is supposed to be the loftiest peak in the state. In the Kimberley district is situated the Princess May Range, running in an easterly direction from York Sound, the highest point in which, called Mount York, is probably 3,000 feet high. Mount Hann, in the same range, reaches an elevation of 2,000 feet. The King Leopold Range stretches south-easterly from Collier Bay, but no point in the chain exceeds an elevation of 2,400 feet. In the south-western district, between Cape Naturaliste and the Leeuwin, an interesting series of limestone caves is found in undulating country at a distance of from 1 to 3 miles from the coast. For beauty and picturesqueness these caves rival those in the Jenolan district of New South Wales, and in some respects are unsurpassed anywhere in the world.

## TASMANIA.

### AREA AND BOUNDARIES.

THE island State of Tasmania is the smallest in the Federation, and contains an area of 26,215 square miles. On the north it is separated from the mainland of Australia by Bass Strait, a broad channel of from 80 to 150 miles in width. The Tasman Sea forms its eastern boundary, and its southern and western shores are washed by the waters of the Great Southern Ocean. From north to south the island is about 200 miles long, and the breadth from east to west in its widest part is about the same distance.

### COASTAL FEATURES.

The southern portion of the eastern shore of the island is rich in picturesque inlets and bold headlands. Hobart, the capital of the state, is beautifully situated on the river Derwent, which debouches into Storm Bay. Behind the city, the cone of Mount Wellington rises to a height of over 4,000 feet. The bay is protected on its eastern side by Tasman's Peninsula, the extremities of which are guarded by the bluff headlands of Cape Pillar and Cape Raoul. These two headlands are composed of masses of columnar basalt rising to a height of several hundreds of feet. Some of the pillars stand as outliers to the main body, the intervening softer mass having been detached by the combined action of wind and sea. For ages the waves of the Southern Ocean have been relentlessly beating at these lofty promontories, and at times large portions of the mighty mass, undermined by the ceaseless erosive agency of the salt water, topple over and sink heavily into the ocean. Tasman's Peninsula is connected with Forestier's Peninsula, lying to the northward, by the narrow isthmus of Eagle Hawk Neck. The land-locked harbour, enclosed by these two peninsulas, is called Norfolk Bay. On the north-eastern portion of Forestier's Peninsula lies North Bay. Sailing northwards from this inlet for about 10 miles the beautiful and peculiarly-shaped Maria Island is reached, supposed to have been named by Tasman after the daughter of his patron, Antony Van Diemen. The island, on the northern side of which cliffs of basalt rise to a height of over 2,000 feet, is almost severed in twain by the deep indentations of Oyster Bay and Reidle Bay, situated respectively on the western and eastern sides, and joined by a narrow neck of land. Higher up on the mainland is another large inlet named

Oyster Bay, with Freycinet's Peninsula on its eastern flank. Schouten Island lies off the extremity of this peninsula, being separated from it by the narrow passage called Geographe Strait. Proceeding southward from Tasman's Peninsula, the two large islands called North and South Bruni are found lying to the east of the D'Entrecasteaux Channel. These two islands, which are joined by a narrow sand spit, contain an area of 90,000 acres. Opposite South Bruni is the estuary of the Haon River. The channel is here bordered by numbers of beautiful bays with well-wooded slopes. Between the South-East and South-West Capes there are several small islands and reefs requiring very skilful navigation. From the South-West Cape the coast trends northward again, and after passing Hilliard Head the fine harbour of Port Davey opens out. Thence the most conspicuous headlands are Rocky Point, Point Hibbs, and Cape Sorell; the latter standing at the entrance to the splendid expanse of water known as Macquarie Harbour. Northward of this inlet the most prominent headlands are—Sandy Cape, Bluff Point, and Cape Grim. Opposite the western apex of the State are situated Hunter's Island, the Three Hummocks Islands, and Robbin's Island. Circular Head is one of the most remarkable projections on the northern coast. It consists of a narrow peninsula running out from the mainland for a distance of about six miles, and terminating in a rocky bluff about 400 feet high. This point is a prominent landmark for vessels sailing from Victoria to Tasmania. Amongst the chief indentations on the north coast are Port Frederick, Port Sorell, and Port Dalrymple, the latter receiving the drainage of the Tamar River on which is situated the town of Launceston. There are several islands off the eastern apex of the state, the most important being Clarke Island, Cape Barren Island, and Flinders Island. The last mentioned is the largest island dependency of the State, and contains an area of 513,000 acres.

#### GENERAL PHYSICAL CHARACTERISTICS.

It is believed that Tasmania originally constituted a southward prolongation of the mainland of Australia, and the continuation of the Great Dividing Range, lying near the eastern seaboard of the continent may be traced through the Furneaux and Kent's group across to the island state. From the central range, traversing the country from north-west to south, various lateral spurs diverge, further ramifications from which branch away in all directions. The centre of the island is occupied by an extensive plateau, with an elevation on the northern side, of between three and four thousand feet above the level of the sea. This table-land district extends from Dry's Bluff in the north-west to the Denison Range in the south-west, and although it recedes here and there at the sources of the chief rivers, presents a precipitous slope to the north, west, and east. Several fine fresh water lakes are situated on the comparatively level

stretches on the summit, and these in some instances act as feeders to the streams which reach the coast. The plateau determines the northern, western, and southern drainage slopes of the island and maintains its general elevation from Dry's Bluff at an altitude of 4,257 feet on the north to Cradle Mountain, 5,069 feet in the north-west, a distance of nearly 50 miles ; from the Bluff south-west to the Denison Range, for over 60 miles ; and from the same point in a southerly direction to Table Mountain, 3,596 feet, a distance of about 43 miles. Below this central plateau there is a second table-land region at a lower elevation, maintaining an altitude of between 1,200 and 2,000 feet. This division stretches westward, including the Middlesex Plains, the Hampshire Hills, and the Emu Plains, and its limits follow the coast line more or less closely, the space between it and the ocean in some localities widening out into low lying expanses raised very little above sea level. At intervals, rising abruptly from this region, various isolated peaks are to be seen, the chief being Mount Bischoff, 2,598 feet, Valentine's Peak, 3,637 feet, Mount Tor, and Mount Pearse, 3,800 feet. In addition there are, round the coast, ridges and plateaus more or less elevated such as Ben Lomond on the north-east, 5,010 feet, Mount Wellington, near Hobart, 4,166 feet, and the Frenchman's Cap, near Macquarie Harbour, 4,756 feet. It has been principally among the plains and lower levels of the North-western, Midland, and Southern portions of the island that settlement has taken place, chiefly in the geological areas of Tertiary and Mesozoic age. Here, in the recent Tertiary period, the soil of the plains and valleys has been enriched by extensive outbursts of basalt with accompanying tuffs. There is evidence to show that these basaltic sheets, which cover large areas in the Midland, North-western, and North-eastern districts, are invariably associated with the ancient Tertiary lake systems. It is from these volcanic rocks that the rich chocolate soils have been produced, and but for their agency a large portion of what is now the most fertile area of the State would have been comparatively poor or perhaps hopelessly barren.

Tasmania is well supplied with rivers, some of them of considerable volume, flowing through fine scenery and magnificent forests, and in some instances adorned with picturesque waterfalls. The largest is the Derwent, which rises in the central plateau, and enters the sea at Storm Bay. In the lower portion of its course, the river widens out into a magnificent estuary on which the capital city, Hobart, is situated. The Derwent receives numerous tributaries, of which the chief are the Nive, Dee, Ouse, Clyde, and Jordan from the north, and the Florentine, Russell, Styx, and Plenty from the south. The Huon issues from Lake Edgar, and after flowing through a heavily-timbered, rich, fruit-growing district, debouches into the D'Entrecasteaux Channel. The Coal River takes its rise in the eastern mountains and falls into the sea at Pittwater, near Hobart. On the north, the Tamar flows into Bass Strait, and after passing Launceston forms a fine estuary with excellent

facilities for navigation. The river is formed by the confluence of the North and South Esk at the city, and is fed by numerous tributaries higher up. The Mersey, on which the town of Latrobe is situated, enters the sea at Port Frederick. On the west and south-west the following streams flow into Macquarie Harbour:—The Gordon, which emerges from Lake Richmond, and receives in its course the Wedge, Denison, Serpentine, and Franklin, and the King River, with its affluents the Queen and the Eldon. In the north-west are the Pieman and Arthur rivers. On the east, the watershed approaches very close to the shore and there are no streams of any great importance. Two short rivers, the Swan and the Swanport, discharge into Oyster Bay.

Several large freshwater lakes are situated on the central table-land. Of these the most extensive are the Great Lake, 13 miles long by a maximum width of 8 miles, and with an area of 28,000 acres; Lakes Sorell and Crescent, 17,000 acres; Lake St. Clair, 10,000 acres; and Lakes Arthur and Echo, each about 8,000 acres. These lakes serve as natural reservoirs for the supply of numerous rivers flowing chiefly to the southward. Most of them are very deep and owe their origin to the same causes which have produced the beautiful lakes of Scotland and Wales. In addition to those mentioned there are numerous lagoons and mountain tarns.

## NEW GUINEA.

THE island of New Guinea lies close to the northern extremity of Queensland, being separated from the mainland by Torres Strait. Excluding Australia itself, New Guinea is the largest island in the world, and lies between the equator and 12° south, and between 130° 50' and 134° 30' east longitude. Its greatest length is 1,490 miles, and its maximum breadth 430 miles, its area being about 234,770 square miles. It is occupied by British, Dutch, and German colonists; the British portion includes the south-east of the island, with an area of 90,540 square miles, of which 87,786 are on the mainland, and 2,754 square miles comprise various groups of islands. The eastern end of the possession is very mountainous; moving westward, the various chains unite to form a great central cordillera, which attains its highest point in the Owen Stanley Range, where Mount Victoria rises to a height of 13,200 feet above sea-level. Conspicuous also in the eastern portion of the island are Mount Suckling (12,228 feet), Mount Obree (10,246 feet), Mount Yule (10,046 feet), and Mount Brown (7,940 feet). The mountains follow the coast, and are distant from it about 20 to 50 miles; at the head of the Gulf of Papua the ranges become broken and considerably reduced in height, as well as further removed from the seaboard. The western portion of the possession may be generally described as low and swampy, densely clothed with forest; dense forest growth is also characteristic of the mountains. New Guinea is a well-watered country; its two largest rivers are the Fly River, with its tributary (the Strickland), and the Purari. The Fly River has a total length of 600 miles, but some portion of its upper course lies within Dutch territory. The river has been navigated for a great distance, and it is said that small steamers of fair draught can ascend over 500 miles. The Purari rises in German territory, and is navigable for a considerable distance from its mouth. There are many other rivers, but, as they have not been explored, no detailed description of them can be given. The southern and south-east coast-line is well indented, and several fair harbours exist.

Lying as it does just under the equator, the climate of New Guinea is very warm, but as no extensive range of observations has been made, the maximum and minimum temperature cannot be definitely stated. At Port Moresby the average shade temperature at 9 a.m. is 81·6° Fahrenheit, with a maximum of 94°; this would argue very high



maximum daily temperature, but not greater than along some portions of the northern coast of Australia. The rainfall varies greatly in different parts of the island ; at Port Moresby the quantity recorded in 1902-3 was 41 inches, and at Sogeri 67 inches ; at Dogura on the north-east coast, on the opposite side of the island, the average is 59 inches ; but at Samarai, at the south-east end of the island, the rainfall registers between 120 and 130 inches per annum. At Daru, in the west of the possession, the average is about 85 inches, but a fall of nearly 150 inches has been registered, and it is probable that equally great rainfall is experienced in the central mountains.

## NEW ZEALAND.

### AREA AND BOUNDARIES.

THE Colony of New Zealand consists of the three main islands named respectively North Island, Middle Island, and Stewart Island, together with the numerous subsidiary islands which from time to time have been added to the territory by proclamation. The group is situated in the South Pacific Ocean about 1,200 miles to the south-east of Australia. That portion of the Southern Ocean which lies between the Australian Coast and New Zealand is now distinguished as the Tasman Sea, in honor of the first discoverer of New Zealand and Tasmania. Including outlying islands, the total area embraced within the limits of the Colony is 104,751 square miles, of which the North Island with adjacent islets constitutes 44,468 square miles, the Middle Island with adjacent islets 58,525 square miles, and Stewart Island with adjacent islets 665 square miles.

### THE NORTH ISLAND.

#### *Coastal Features.*

This island is, as its name implies, the northernmost of the group, and is separated from the Middle Island by Cook Strait. In shape it is peculiar, consisting of a roughly square main body, with projections stretching from each corner, the longest being to the north-west. This remarkable northward peninsula is about 280 miles long, and from 53 to 8 miles in breadth, and is almost cut in two by the Hauraki Gulf on the eastern side, and the Manukau Harbour on the west. On the narrow isthmus intervening, the town of Auckland has been built. At the extremity of the peninsula lies the headland of Cape Reinga, from which, according to Maori legend the souls of the dead were plunged into the abode of departed spirits. A little to the eastward is North Cape, and to the west Cape Maria Van Diemen. Off the point lie the rocky islets known as the Three Kings, the scene of several disastrous shipwrecks. Proceeding down the western coast from Cape Maria Van Diemen, the first inlet of importance is Ahipara Bay, with Reef Point at its southern entrance. Next come Kaipara Harbour and Manukau Harbour. Lower down is Kawhia Harbour, with Albatross Point on the southward entrance. Here the coast takes a westerly sweep and forms the North Taranaki Bight. On the extremity of the western projection of the island is situated Cape Egmont, with the prominent landmark of Mount Egmont standing a

little distance inland. Sweeping round to the south the coast line forms the capacious South Taranaki Bight. Port Nicholson and Palliser Bay are situated in the southern prolongation of the island. Rounding Cape Palliser a long stretch of unindented coast line leads up to Kidnapper's Point at the southern entrance to Hawke Bay. Passing Poverty Bay and East Cape and turning westward the Bay of Plenty is entered. Next comes the Hauraki Gulf, off which are situated the Barrier Islands, with Aiguilles Point on the extremity of the Great Barrier. The eastward coast line of the northern peninsula possesses numerous indentations, the most remarkable of which is the Bay of Islands with Cape Brett at its southern entrance. This inlet is one of the finest harbours in New Zealand, being superior to that of Auckland as regards facility of entrance, and possessing deep water and good anchorage in almost every part. As the name implies, the surface of the bay is diversified by numerous small islands, and these, with their verdurous slopes and lustrous beaches, together with the many beautiful bays and headlands on the mainland, constitute a scene which, for charm, stands almost unrivalled.

#### *General Physical Characteristics.*

The main body of the North Island is mountainous, although there are some extensive stretches of plain country, portions of which are of surprising richness and fertility. In the northern peninsula the ranges do not rise to any great altitude, Tutanoë, the highest point, having an elevation of 2,570 feet. Southward from East Cape the highest summit is Hikurangi, which reaches 5,530 feet. On the west coast, south of Whaingaroa Harbour, are Mount Karehōe and Mount Pironghia, reaching an altitude, respectively, of 2,370 and 2,800 feet. The volcanic summits to the south reach a much greater elevation. One of the most remarkable is Mount Egmont, in the New Plymouth District. This is an extinct volcanic cone, 8,260 feet in height, and the summit is clothed with perpetual snow. Rising abruptly from the plain, it presents a sublime spectacle, the cone being one of the most perfect in the world. Tarawera is the well-known volcanic summit in the celebrated Lake District, and rises to a height of 3,600 feet. Farther down are the Te Whaiti Range leading to Kaimanawha, near Hawke's Bay, and the prolongations to Kaweka and the Ruahine Range, ending in the Tararua and Haurangi at Cape Palliser, these successive ranges forming the backbone of the island to Cook's Strait. The Tongariro Mountain in the Lake Taupo District consists of the united outflow of lava from several distinct cones. Ngauruhoe, the highest of these, reaches 7,515 feet. From Ngauruhoe, the Red Crater, and Te Mari discharges of lava took place as recently as 1868, and steam and vapours are still given off from various vents, accompanied by considerable noise. Ruapehu lies south of the Tongariro group, and reaches an elevation of 9,008 feet, being in part above the line of perpetual snow. This mountain is in the solfatara stage, and possesses a crater-lake

which occasionally is troubled by alight eruptions giving rise to large volumes of steam. In March, 1895, an eruption took place, when several hot springs were formed, while the heat of the lake increased. The sides of the depression occupied by the lake are covered with ice and snow, and the water, which is 300 feet below the surrounding crater rims, is inaccessible except with the use of ropes and ladders. This area and the three craters on Tongariro are situated in a straight line which if produced would pass through the boiling springs of Tokaanu on the southern edge of Lake Taupo, the volcanic country north-east of the lake, and White Island, an active volcano in the Bay of Plenty, about 27 miles from the mainland.

The district occupied by the hot springs constitutes one of the most remarkable and interesting features of the North Island. They are found over a large extent of country from Tongariro, south of Lake Taupo, to Ohaeawai in the extreme north, a distance of about 300 miles, but it is in the neighbourhood of Lake Rotorua, about 40 miles north-east of Lake Taupo, that the principal seat of hydrothermal action is encountered. Many of the hot springs have been proved to possess remarkable curative powers in certain complaints, and the Government has taken considerable pains to render them accessible to the visitor in search of health. The beautiful Pink and White Terraces in this district were almost completely destroyed by the eruption of Mount Tarawera in 1886, but it is stated that natural agencies are at work which will in time renew them. Some of the hot springs assume the form of geysers, and eject boiling water, fragments of rock, mud, &c., to a considerable height.

Of the plains, the principal are those in the Hawke's Bay District; the Wairarapa Plain in the Wellington District; the West-Coast Plain, stretching from near Wellington to some distance north of New Plymouth; and the Kaingaroa Plain, which stretches in a north-easterly direction from Lake Taupo to the Bay of Plenty. A great portion of the last-mentioned is, however, covered with pumice sand and is unfit for agricultural or pastoral occupation.

The principal river in the North Island is the Waikato. Rising in the Central Range, near Ruapehu, it flows into Lake Taupo, thence flowing north-westward it enters the ocean a short distance to the south of Manukau Harbour. The river is navigable for 100 miles from its mouth by small vessels. The Thames rises in the high land near the Lake District, and after a course of 100 miles enters the sea at the Firth of Thames. Several small streams, including the Tarawera, drain into the Bay of Plenty. The Wairoa, Waikari, and Mohaka fall into Hawke Bay. The Wanganui flows into the South Taranaki Bight, and the Hutt into Port Nicholson.

A large number of streams drain the Auckland peninsula, their courses necessarily being very short. There is, indeed, little of the North Island that can be passed over without meeting a stream of ever-running water.

## THE MIDDLE ISLAND.

*Coastal Features.*

The Middle or South Island, as it is sometimes called, is much more compact in shape than the North Island, from which it is separated by Cook Strait, the passage being about 90 miles across in its widest part, and 16 at the narrowest. From Jackson's Head, in Cook Strait, to Pyssegur Point, at the extreme south-west, the length of the island is about 525 miles, the greatest breadth, in the Otago District, being about 180 miles. Sailing across from Wellington, in the North Island, the first port of call in the Middle Island would, probably, be Pictou on the opposite shore of the strait, at its narrowest part. Here is the beautiful inlet called Queen Charlotte Sound, which Captain Cook described as a collection of the finest harbours in the world. The immense bays in this fine stretch of water were much frequented by whalers in the early days. Westward lies another capacious inlet called Pelorus Sound. The approach to Tasman or Blind Bay, the next important indentation on the north, lies through a narrow but deep channel, between D'Urville Island and the mainland, called French Pass. Shut in by high precipitous hills, the scenery in this passage, with its swift-running current, is remarkably imposing. At the head of the bay is the township of Nelson, encircled by a background of lofty hills, and a few miles eastward is the village of Whakapuaka, where the cable from Australia reaches the land. Golden or Massacre Bay, at the extreme left of the northern shore, was the scene of the murder by the natives of an entire boat's crew belonging to the company of the explorer Tasman. Rounding Cape Farewell, the upper portion of the western coast will be found somewhat deficient in noteworthy indentations. Westport, on the southern shore of the Karamea Bight, possesses a good harbour. At Greymouth, lower down, large sums of money have been spent on the improvement of facilities for shipping, the port being the outlet for a rich mineral and agricultural district. Thence southward the coast line presents no important indentations until the wonderful inlets of the western Otago district are reached. Here, between the parallels of 44° and 46°, the rock-bound coast rises in places sheer from the ocean depths to a height of 5,000 or 6,000 feet, and is pierced by numerous sounds or fiords, which penetrate inland for distances ranging from 6 to 20 miles. These inlets are narrow and very deep. Milford Sound, the finest example, has a depth in its upper part of no less than 1,270 feet. It is surrounded by mountains, which, with the exception of Mount Cook, are the highest on the south coast, and its narrow entrance appears still more restricted from the height of the gigantic precipices on either side. Within the sound, a sublime spectacle opens out, towering mountains rising on both sides of the narrow channel, clothed with verdure at their base, and with magnificent waterfalls tumbling down their flanks. Here and there the cold blue mass of the glacier protrudes itself, while,

far above, the mist-wreathed snow-clad cones rear their heads in silent majesty to the skies. The great Sutherland Waterfall, in the vicinity of the Sound, is stated to be 1,904 feet in height. Of the other inlets of this class to the south of Milford Sound, the chief are George Sound, Doubtful Inlet, Daggs Sound, Breaksea Sound, Chalky Inlet, and Preservation Inlet.

The southern and eastern shores of the Middle Island do not offer any noteworthy indentations. Close to Invercargill is the Bluff Harbour, a well known port of call for vessels trading to the south. On the east coast the principal harbours are Otago Harbour, at the head of which Dunedin is situated; Oamaru, the outlet for the district of the same name; Timaru, at the elbow of Canterbury Bight; and Akaroa and Lyttelton Harbours, on Banks Peninsula.

#### *General Physical Characteristics.*

The inland physical features of the Middle Island are particularly striking. Almost throughout its entire length the island is traversed by a range of mountains called the Southern Alps, which throws off numerous lateral spurs towards the east and west. In the south, a network of ranges spreads out over the Otago district. In the east, towards the centre of the island, are the Malvern Hills and Hunter's Hills, and the ranges occupying the greater portion of Banks Peninsula. The Kaikoura Range runs between Cook's Strait and Banks Peninsula. South of Nelson, the Spenser and St. Arnaud Mountains break off towards the east. The highest peak in the Southern Alps is Mount Cook, situated about the centre of the range, and rising to a height of 12,349 feet. This mountain was called by the natives Ao Rangī, or the Cloud-Piercer. Other notable peaks are Mount Stokes, 12,200 feet, and Mount Aspiring, 9,940 feet. In the southern system are Earnslaw, 9,165 feet; Double Cone, 7,688 feet; and Mount St. Bathans, 6,600 feet.

In point of beauty and sublimity of scenery, the Southern Alps compare favourably with the Alps of Switzerland, while as regards variety they are superior to the European range. The snow line in New Zealand is below that of Switzerland, so that the mountains, while not quite so high as the Swiss Alps, nevertheless present all the varied features of the Alpine uplands. On both sides of the range there are extensive glaciers, those on the western side descending in places to within 700 feet of the sea level into the midst of evergreen forests, and most of them are easily accessible. The Tasman Glacier, on the eastern slope, has an area of 13,664 acres, with a length of 18 miles and an average width of over a mile, and as regards length and width is superior to the famous Alletsch Glacier of Switzerland. The Murchison Glacier contains 5,800 acres, and is 10 miles long and over three-quarters of a mile in average width; and the Godley Glacier, 8 miles long and over a mile wide, has an area of 5,312 acres. In addition to these, there are numerous others of smaller extent, all of

them possessing features of great beauty and interest. The waters produced by the melting of the snowfields and glaciers give rise to numerous rivers, nearly all of which flow through the fertile plains of the east.

The Middle Island possesses numerous lakes, many of which are of great beauty, and some of them are situated at a considerable elevation above the level of the sea. Lake Tekapo, in the Canterbury district, is 2,468 feet above the sea-level, and is 15 miles long by about 3 broad. Thirty miles distant, towards the south, is Lake Pukaki, one of the most picturesque Alpine lakes in the island. It lies at an elevation of 1,746 feet above sea-level, and, like similar lakes in this and other Alpine regions, has probably been formed by the retreat of an immense glacier. Close to the lake, the majestic cone of Mount Cook, crowned with snow and ice, is a conspicuous feature in the landscape. Lake Ohau, near Pukaki, is 12 miles long and  $2\frac{1}{2}$  miles in width, and its waters are less turbid than those of its larger neighbours. Several fine lakes are found in the Otago district. Lake Manapouri covers an area of 50 square miles, and is nearly surrounded by beautifully-wooded snow-capped mountains. Te Anau is the largest lake in New Zealand. It is 38 miles long, and from 1 to 6 miles in width, and has an area of 132 square miles. Wakatipu is 52 miles long, and from 1 to 3 miles broad, with an area of 114 square miles. The lake is situated at an elevation of 1,070 feet above the level of the sea, and, as its depth has been proved by soundings in various places to be from 1,170 to 1,240 feet, a large portion of its bed is considerably below sea-level. Wanaka and Hawea are two beautiful little lakes in the northern Otago district. From what has already been said, it will have been concluded that a great portion of the surface of the Middle island is mountainous; nevertheless there are several fairly extensive plain districts, particularly on the eastern side of the main range. Of these, the most noteworthy are the Canterbury Plains, with a length of about 130 miles, and a width varying from 30 miles north of the Rangitata to very narrow limits further south. In the north are the Karamea Plains, the Waimea Plains, the Fairfield Downs, the Wairau Plains, the Hanmer Plains, and the Amuri Plains, lying between Cook Strait and the Hurunui River. In the Southern district are the Oamaru Downs, Moraki Downs, and the Maitara Plains.

The Middle Island is well provided with rivers, but, for the most part, they are merely mountain torrents, fed by the snows and ice-fields of the ranges. At times, when there is a more excessive melting of the snows than usual, they are liable to rise in flood, and, where not confined by precipitous rocky walls, form beds of varying width, frequently strewn with enormous deposits of shingle. The Clutha is the largest river in New Zealand as regards volume of water. It drains an extensive area of the southern mountain region, and after a course of 154 miles enters the sea about 60 miles south of Dunedin. It is navigable for small vessels for about 30 miles from its mouth. From

the proximity of the mountains to the shore, the streams on the western coast have short rapid courses. The Buller, Grey, and Hokitika are navigable for a few miles, but great expense had to be incurred in connection with the removal of the obstructing sand-bars at their mouths. The Grey and Buller possess special importance from the fact that they are the chief ports of shipment in connection with the coal export trade of the west. On the eastern slope there are hundreds of small streams along the whole extent of the island.

#### STEWART ISLAND.

This small island, which embraces an area of about 425,000 acres, is the southernmost of the group. It is separated from Middle Island by the passage called Foveaux Strait, and is distant 25 miles from the Bluff on the south of the Middle Island. The greater portion of Stewart Island is rugged and forest clad; but, although lying so far to the south, the climate is mild, and the soil when cleared of the thick undergrowth is very fertile. Mount Anglem and Mount Rakeahua are the highest peaks, the former reaching an elevation of 3,900 feet, and the latter 2,110 feet. The coast line possesses numerous attractive bays and fiords. Half-Moon Bay is the principal port, and near by is situated a beautiful sheet of water, about 10 miles by 4 miles in extent, called Paterson Inlet. Port Pegasus is a fine land-locked harbour, 8 miles long and about  $1\frac{1}{2}$  mile wide. Fish and game are abundant, while the oysters are of fine size and flavour, and have achieved an Australasian reputation.

#### THE OUTLYING ISLANDS.

Of the outlying islands, the principal are the Chatham Islands, the Kermadecs, the Auckland Islands, and the Cook Group. The Chathams lie 460 miles east-south-east from Wellington. The largest island of the group has an area of about 222,500 acres, of which an irregularly-shaped lagoon in the interior contains 45,960 acres. A fourth of the entire area is clothed with forest, but there is good pastoral country in the remainder. Pitt Island has an area of 15,530 acres. In addition to these, there are several smaller unimportant islands. Sheep-raising is the principal industry in the group.

The four Kermadecs are named, respectively, Raoul or Sunday Island, Macaulay Island, Curtis Island, and L'Espérance or French Rock. Sunday Island contains 7,200 acres, Macaulay Island 764 acres, Curtis Island 128 acres, and L'Espérance 12 acres. Sunday Island is 20 miles in circumference, and its highest point reaches an elevation above sea-level of 1,723 feet. The surface is rugged, and almost the whole area is covered by a dense forest. Throughout the island the soil is exceedingly fertile, resulting from the decomposition of volcanic lavas and tuff. There are three fresh-water lakes in the interior, but they are so difficult of approach as to be practically useless.



The Auckland Islands are situated 290 miles to the southward of the Bluff Harbour. The largest of the group is 27 miles long, with a breadth of about 15 miles, and in its highest part is 2,000 feet above sea-level. There are some fine harbours in this island, Port Ross being considered one of the best harbours of refuge in the world. A dépôt for the use of shipwrecked mariners is maintained on the island by the Government of New Zealand.

The Cook Group contains several beautiful and fertile islands. Rarotonga rises to a height of 3,000 feet above the level of the sea, and its fertile soil is covered with rich vegetation right to the summits of the mountains. The island is well-watered, but is deficient in good harbourage. Aitutaki has a circumference of 18 miles, and contains some splendid groves of cocoanut trees on the level lands near the coast, with fine pasturage inland.

Palmerston Island is about 220 miles from the nearest island in the Cook Group, and contains areas of good soil with some fine hardwood timber. The island is remarkable as being the "San Pablo" of Magellan.

Penrhyn Island is about 1,200 miles east of Samoa, and is one of the most famous pearling islands of the Pacific. It possesses a splendid harbour, capable of accommodating the largest vessels.

Suwarrow lies about 500 miles to the eastward of Apia in the Samoan Islands. It is a coral atoll, 50 miles in circumference, with a reef enclosing a land-locked lagoon about 12 miles long and 8 miles wide. The entrance is half a mile in width, and there is unlimited anchorage with depths of from 3 to 30 fathoms. Situated out of the path of the hurricanes, the island, which is uninhabited, is sufficiently fertile to support a small population, and would form a valuable trading dépôt for the various islands in the neighbouring Pacific.

## CLIMATE.

THE Tropic of Capricorn divides Australia into two parts. Of these, the northern or inter-tropical portion contains 1,145,000 square miles, comprising half of Queensland, the Northern Territory of South Australia, and the north-western divisions of Western Australia. The whole of New South Wales, Victoria, New Zealand, Tasmania, and South Australia proper, half of Queensland, and more than half of Western Australia, comprising 1,932,000 square miles, are without the tropics. In a region so extensive, very great varieties of climate are naturally to be expected, but it may be stated as a general law that the climate of Australasia is milder than that of corresponding lands in the Northern Hemisphere. During July, which is the coldest month in southern latitudes, one half of Australasia has a mean temperature ranging from 40° to 64°, and the other half from 64° to 80°. The following are the areas subject to the various average temperatures during the month referred to:—

Temperature, Fahr.	Area in sq. miles.
35° — 40°.....	300
40° — 45°.....	39,700
45° — 50°.....	88,000
50° — 55°.....	617,800
55° — 60°.....	681,800
60° — 65°.....	834,400
65° — 70°.....	515,000
70° — 75°.....	275,900
75° — 80°.....	24,500

The temperature during December ranges from 50° to above 95° Fahr., half of Australasia having a mean temperature below 83°. Dividing the land into zones of average summer temperature, the following are the areas which would fall to each:—

Temperature, Fahr.	Area in sq. miles.
50° — 55°.....	300
55° — 60°.....	66,300
60° — 65°.....	111,300
65° — 70°.....	74,300
70° — 75°.....	362,300
75° — 80°.....	439,200
80° — 85°.....	733,600
85° — 90°.....	570,600
90° — 95°.....	584,100
95° and over.....	135,400

Judging from the figures just given, it must be conceded that a considerable area of the continent is not adapted for colonisation by European races. The region with a mean summer temperature in excess of 95° Fahr. is the interior of the Northern Territory of South Australia north of

the 20th parallel; and the whole of the country, excepting the seaboard, lying between the meridians of 120° and 140° and north of the 25th parallel, has a mean temperature in excess of 90° Fahr.

Climatically, as well as geographically, New South Wales is divided into three marked divisions. The coastal region, which lies between the parallels of 28° and 37° south latitude, has an average summer temperature ranging from 78° in the north to 67° in the south, with a winter temperature of from 59° to 52°. Taking the district generally, the difference between the mean summer and mean winter temperature may be set down as averaging not more than 20°, a range smaller than is found in most other parts of the world. The famed resorts on the Mediterranean seaboard bear no comparison with the Pacific slopes of New South Wales, either for natural salubrity or for the comparative mildness of the summer and winter.

Sydney, situated as it is midway between the extreme points of the state, in latitude 33° 51' S., has a mean temperature of 63°, corresponding with that of Barcelona, the great maritime city of Spain, and of Toulon, in France; the former being in latitude 41° 22' N., and the latter in 43° 7' N. At Sydney the mean summer temperature is 70·8°, and that of winter 53·9°. The range is thus 16·9° Fahr. At Naples, where the mean temperature for the year is about the same as at Sydney, the summer temperature reaches a mean of 74·4°, and the mean of winter is 47·6°, with a range of 26·8°. Thus the summer is warmer, and the winter much colder, than at Sydney. The highest temperature in the shade experienced in Sydney was 109°, and the lowest winter temperature 36°, giving a range of 73°. At Naples the range has been as great as 81°, the winter minimum falling sometimes below the freezing-point. The mean temperature of Sydney for a long series of years was—spring 62°, summer 71°, autumn 64°, and winter 54°.

Passing from the coast to the table-land, a distinct climatic region is entered. Cooma, with a mean summer temperature of 65·4° and a mean winter temperature of 41·4°, may be taken as illustrative of the climate of the southern table-land, and Armidale of the northern. The first-named town stands in the centre of the Monaro plains, at an elevation of 2,637 feet above sea-level, and enjoys a summer as mild as either London or Paris, while its winters are far less severe. On the New England table-land, the climate of Armidale and other towns may be considered as nearly perfect as can be found. The yearly average temperature is scarcely 56·5°, while the summer only reaches 67·7°, and the winter falls to 44·4°, a range of temperature approximating closely to that of the famous health-resorts in the south of France.

The climatic conditions of the western districts of the state are entirely different from those of the other two regions, and have often been cited as disagreeable. Compared with the equable temperature of the coastal district or of the table-land, there may appear some justification for such a reputation, but only by comparison. The climate of the great plains, in spite of the heat of part of the summer, is very

healthy. The town of Bourke may be taken as an example. Seated in the midst of the great plain of the interior, it illustrates peculiarly well the defects as well as the excellences of the climate of the whole region. Bourke has exactly the same latitude as Cairo, yet its mean summer temperature is  $1.3^{\circ}$  less, and its mean annual temperature  $4^{\circ}$  less than that of the Egyptian city. New Orleans also lies on the same parallel, but the American city is  $4^{\circ}$  hotter in summer. As regards winter temperature, Bourke leaves little to be desired. The mean winter reading of the thermometer is  $54.7^{\circ}$ , and accompanied as this is by clear skies and an absence of snow, the season is both refreshing and enjoyable.

The rainfall of New South Wales ranges from an annual average of 64 inches at Port Macquarie, on the northern coast, and Kiandra, in the Monaro district, to 9 inches at Milparinka, in the Trans-Darling country. The coastal districts average about 42 inches of rain per annum; on the table-land the mean rainfall is 32 inches, but in the western interior it is as low as 20 inches, while at the ten stations in the far west the average was only 14 inches. The average rainfall of Sydney during forty-two years was 50 inches, while during 1903 a fall of 38.57 inches was recorded.

The climate of Victoria does not differ greatly from that of New South Wales; the heat, however, is generally less intense in summer and the cold greater in winter. Melbourne, which stands in latitude  $37^{\circ} 50' S.$ , has a mean temperature of  $57.3^{\circ}$ , and therefore corresponds with Bathurst in New South Wales, Washington in the United States, Madrid, Lisbon, and Messina. The difference between summer and winter is, however, less at Melbourne than at any of the places mentioned. The mean temperature is  $6^{\circ}$  less than that of Sydney and  $7^{\circ}$  less than that of Adelaide—the result of a long series of observations being:—Spring,  $57^{\circ}$ ; summer,  $65.3^{\circ}$ ; autumn,  $58.7^{\circ}$ ; winter,  $49.2^{\circ}$ . The highest recorded temperature in the shade at Melbourne was  $110.7^{\circ}$ , and the lowest,  $27^{\circ}$ ; but it is rare for the summer heat to exceed  $85^{\circ}$ , or the winter temperature in the day time to fall below  $40^{\circ}$ .

Ballarat, the second city of Victoria, about 100 miles west from Melbourne, and situated at a height of about 1,400 feet above sea-level, has a minimum temperature of  $29^{\circ}$ , and a maximum of  $104.5^{\circ}$ , the average yearly mean being  $54.1^{\circ}$ . Bendigo, which is about 100 miles north of Melbourne, and 700 feet above the level of the sea, has a rather higher average temperature, ranging from a minimum of  $31.2^{\circ}$  to a maximum of  $106.4^{\circ}$ , the average yearly mean being  $59.4^{\circ}$ . At Wilson's Promontory, the most southerly point of Australia, the minimum heat is  $38.6^{\circ}$ , and the maximum  $96.4^{\circ}$ , the average yearly mean being  $56.7^{\circ}$ .

During the year 1903 the rainfall at Melbourne amounted to 28.43 inches; while for a long series of years it averaged 25.58 inches, with an average of 131 days during the year on which rain fell. At Echuca, during 1903, 20.71 inches fell, and 30.78 at Portland. At Wilson's Promontory the rainfall was 43.69 inches.

As about one-half of the state of Queensland lies within the tropics, it is but natural to expect that the climate should be very warm. The temperature, however, has a daily range less than that of other countries under the same isothermal lines. This circumstance is due to the sea-breezes, which blow with great regularity, and temper what would otherwise be an excessive heat. The hot winds which prevail during the summer in some of the other colonies are unknown in Queensland. Of course, in a territory of such large extent there are many varieties of climate, and the heat is greater along the coast than on the elevated lands of the interior. In the northern parts of the state the high temperature is very trying to persons of European descent.

The mean temperature at Brisbane, during December, January, and February, is about 76°, while during the months of June, July, and August it averages about 60°. Brisbane, however, is situated near the extreme southern end of the colony, and its average temperature is considerably less than that of many of the towns farther north. Thus the winter in Rockhampton averages nearly 65°, while the summer heat rises almost to 85°; and at Townsville and Normanton the average temperature is still higher.

The average rainfall of Queensland is high, especially along the northern coast, where it ranges from 60 to 70 inches per annum. At Brisbane 50·01 inches is the average of thirty-five years, and even on the plains of the interior from 20 to 30 inches usually fall every year. During 1903, 49·27 inches of rain fell in Brisbane, the number of wet days being 136.

South Australia, extending as it does over about 26 degrees of latitude, naturally presents considerable variations of climate. The southern portions have a climate greatly resembling that of the coast of Italy. The coldest months are June, July, and August, during which the temperature is very agreeable, averaging for a series of years 53·6°, 51·7°, and 54° for those months respectively. On the plains slight frosts occasionally occur, and ice is sometimes seen on the highlands. The summer is the only really disagreeable portion of the year. The sun at that season has great power, and the temperature frequently reaches 100° in the shade, with hot winds blowing from the interior. The weather on the whole is remarkably dry. At Adelaide there are on an average 120 rainy days per annum; during the last sixty years the mean rainfall has been 20·88 inches per annum, while farther north the quantity recorded was considerably less. The country is naturally very healthful, and in evidence of this it may be mentioned that no great epidemic has ever visited the state.

The climate of the Northern Territory of South Australia is extremely hot, except on the elevated table-lands. Altogether, the temperature of this part of the state is very similar to that of Northern Queensland, and the climate is equally unfavourable to Europeans. It is a fact worthy of notice that the malarial fevers which are so troublesome to the pioneers of the northern parts of Australia almost, and in some cases

entirely, disappear after the land has been settled and consolidated by stock. The rainfall in the extreme north, especially in January and February, is exceedingly heavy. The average yearly rainfall in the coast districts is about 63 inches.

Western Australia has practically only two seasons—the winter, or wet season, which commences in April and ends in October; and the summer, or dry season, which comprises the remainder of the year. During the wet season frequent and heavy rains fall, and thunderstorms with sharp showers occur in the summer. The extremes of drought and flood experienced in the other states are almost unknown in Western Australia, but during the summer months the north-west coast is sometimes visited by hurricanes of great violence. In the southern and early-settled parts of the state the mean temperature is about  $64^{\circ}$ ; but in the more northern portions the heat is excessive, though the dryness of the atmosphere makes it preferable to most tropical climates. At Perth, in 1903, the mean temperature was  $63.7^{\circ}$ , the maximum being  $106^{\circ}$  and the minimum  $40.1^{\circ}$ ; and the rainfall for the same year was 35.69 inches, rain having fallen on 140 days. Observations extending over a period of twenty-two years show the average rainfall at Perth as 33 inches. Although the heat is very great during three months of the year, the nights and mornings are almost always cool, and camping out is not attended with danger owing to there being so little moisture in the air.

Tasmania, protected as it is by its geographical position and by the tempering influence of the surrounding ocean from extremes of heat or cold, enjoys an exceedingly genial climate. The greater part of the island in the settled regions is characterised by a mild and equable temperature, ranging between the extremes of  $20^{\circ}$  to  $44^{\circ}$  in winter and  $78^{\circ}$  to  $96^{\circ}$  in summer. Spring and autumn are the most pleasant seasons of the year, especially the latter, when the mean reading of the thermometer is about  $57^{\circ}$ . The mean temperature of Hobart for the last fifty years has been  $55^{\circ}$ . The richness of its flora is an evidence of the genial nature of the climate of the state, while the purity of its atmosphere is proved by the small proportion of zymotic diseases recorded in the bills of mortality. The hot winds of the continent of Australia are felt in the northern parts of the island only, and even there they are greatly reduced in temperature by their passage across Bass Straits. Generally speaking, all through the summer months there are alternate land and sea breezes which tend to cool the atmosphere even on the hottest days. The climate is fresh and invigorating, and is much recommended as a restorative for those whose constitutions have been enfeebled by residence in hotter climes. Large numbers of tourists in search of health visit the island every summer. The rainfall, except in the mountain districts, is moderate and regular. The average downfall at Hobart for a long series of years was 25.10 inches, with 167 wet days per annum. In 1903 rain fell on 151 days, the total recorded for the year being 21.85 inches.

The climate of New Zealand is in some respects similar to that of Tasmania, but the changes of weather and temperature are often very

sudden. As the colony extends over more than 10 degrees of latitude, its climate is very varied. That of the North Island is somewhat similar to the climate of Rome, Montpellier, and Milan; while the Middle or Southern Island more resembles Jersey, in the Channel Islands. The mean annual temperature of the North Island is 57°, and of the Middle Island 52°, while the yearly average of the whole colony for each season is as follows:—Spring, 55°; summer, 63°; autumn, 57°; and winter, 48°. The mean temperature of New Zealand is lower than that of similar latitudes in Europe, though higher than is experienced in America on corresponding parallels. The mean temperature of the South or Middle Island is less by about 5° than that of the North Island. Snow very seldom lies on the ground at the sea-level in the North Island, and only occasionally in the South Island. The summits of Ruapehu, the highest mountain in the North Island, and of the great mountain chain in the South Island, are covered with perpetual snow from an altitude of 7,500 feet above the level of the sea. Ice is occasionally seen in winter-time in all parts of New Zealand. The whole colony is subject to strong breezes, which frequently culminate in gales. The rainfall during 1903 varied very much at the several observing stations. At Auckland it amounted to 45·13 inches, while at Wellington there was a fall of 53·8 inches. At Rotorua, in the North Island, 55·19 inches fell during the year, and at New Plymouth, on the west coast, 69·17 inches were recorded. At Dunedin, on the east coast of the Middle Island, the rainfall amounted to 42·77 inches, while at Hokitika, on the west coast, no less than 102·85 inches fell during the year. Periods of lasting drought are almost unknown in the colony; indeed, it is very seldom that the records of any station show the lapse of a whole month without rain. The number of days in the year on which rain fell varied from 127 at Lincoln to 241 at New Plymouth.

The following table shows the distribution of rainfall area in Australasia:—

Rainfall.	Rainfall area in square miles.			
	Australia.	Tasmania.	New Zealand.	Australasia.
Under 10 inches ...	1,219,600	.....	.....	1,219,600
10 to 20 " ...	843,100	1,527	.....	844,627
20 to 30 " ...	399,900	5,324	69,650	474,874
30 to 40 " ...	225,700	7,977	17,410	251,087
40 to 50 " ...	140,300	8,991	17,410	166,701
50 to 60 " ...	47,900	202	.....	48,102
60 to 70 " ...	56,100	185	.....	56,285
Above 70 " ...	14,100	1,994	.....	16,094
Total.....	2,946,700	26,200	104,470	3,077,370

## THE DISCOVERY OF AUSTRALIA AND NEW ZEALAND.

**I**T is impossible to say who were the first discoverers of Australia, although there is evidence that the Chinese had some knowledge of the continent so far back as the Thirteenth Century. The Malays, also, would seem to have been acquainted with the northern coast; while Marco Polo, who visited the East at the close of the Thirteenth Century, makes reference to the reputed existence of a great southern continent. There is in existence a map, dedicated to Henry the Eighth of England, on which a large southern land is shown, and the tradition of a Terra Australis appears to have been current for a long period before it enters into authentic history.

In 1503, a French navigator named Binot Paulmyer, Sieur de Gonneville, was blown out of his course, and landed on a large island, which was claimed to be the great southern land of tradition, although Flinders and other authorities are inclined to think that it must have been Madagascar. Some French authorities confidently put forward a claim that Guillaume le Testu, of Provence, sighted the continent in 1531. The Portuguese also advance claims to be the first discoverers of Australia, but so far the evidence cannot be said to establish their pretensions. As early as 1597, the Dutch historian, Wytfliet describes the Australis Terra as the most southern of all lands, and proceeds to give some circumstantial particulars respecting its geographical relation to New Guinea, venturing the opinion that, were it thoroughly explored, it would be regarded as a fifth part of the world.

Early in the Seventeenth Century, Philip the Third of Spain sent out an expedition from Callao, in Peru, for the purpose of searching for a southern continent. The little fleet comprised three vessels, with the Portuguese pilot, De Quiros, as navigator, and De Torres as admiral, or military commander. They left Callao on the 21st December, 1605, and in the following year discovered the island now known as Espiritu Santo, one of the New Hebrides Group, which De Quiros, under the impression that it was indeed the land of which he was in search, named "*La Austrialia del Espiritu Santo*." Sickness and discontent led to a mutiny on De Quiros' vessel, and the crew, overpowering their officers during the night, forced the captain to navigate his ship to Mexico. Thus abandoned by his consort, De Torres, compelled to bear up for the Philippines to refit, discovered and sailed through the strait that bears his name, and may even have caught a glimpse of the northern coast



of the Australian Continent. His discovery was not, however, made known until 1793, when Dalrymple rescued his name from oblivion, bestowing it upon the passage which separates New Guinea from Australia. De Quiros returned to Spain to re-engage in the work of petitioning the king to despatch an expedition for the purpose of prosecuting the discovery of the Terra Australis. He was finally successful in his petitions, but died before accomplishing his work, and was buried in an unknown grave in Panama, never being privileged to set his foot upon the continent the discovery of which was the inspiration of his life.

During the same year in which De Torres sailed through the strait destined to make him famous, a little Dutch vessel called the "Duyfken," or "Dove," set sail from Bantam, in Java, on a voyage of discovery. This ship entered the Gulf of Carpentaria, and sailed south as far as Cape Keerweer, or Turn-again. Here some of the crew landed, but being attacked by natives, made no attempt to explore the country. In 1616, Dirk Hartog discovered the island bearing his name. In 1622 the "Leeuwin," or "Lioness," made some discoveries on the south-west coast; and during the following year the yachts Pera and Arnhem explored the shores of the Gulf of Carpentaria. Arnhem Land, a portion of the Northern Territory, still appears on many maps as a memento of this voyage. Among other early Dutch discoverers were Van Edels; Pool, in 1629, in the Gulf of Carpentaria; Nuijts, in the "Gulden Zeepaard," along the southern coast, which he called, after himself, Nuijts Land; De Witt; and Pelsaert, in the "Batavia." Pelsaert was wrecked on Houtman's Abrolhos; his crew mutinied, and he and his party suffered greatly from want of water. The record of his voyage is interesting from the fact that he was the first to carry back to Europe an authentic account of the western coast of Australia, which he described in any but favourable terms. It is to Dutch navigators in the early portion of the Seventeenth Century that we owe the first really authentic accounts of the western coast and adjacent islands, and in many instances the names given by these mariners to prominent physical features are still retained. By 1665 the Dutch possessed rough charts of almost the whole of the western littoral, while to the mainland itself they had given the name of New Holland. Of the Dutch discoverers, Pelsaert was the only one who made any detailed observations of the character of the country inland, and it may here be remarked that his journal contains the first notice and description of the kangaroo that has come down to us.

In 1642, Abel Janszoon Tasman sailed on a voyage of discovery from Batavia, the head-quarters of the Governor and Council of the Dutch East Indies, under whose auspices the expedition was undertaken. He was furnished with a yacht, the "Heemskirk," and a fly-boat, the "Zeehaen" (or "Sea Hen"), under the command of Captain Jerrit Jansen. He left Batavia on what has been designated by Dutch historians the "Happy Voyage," on the 14th August, 1642. After

a visit to the Mauritius, then a Dutch possession, Tasman bore away to the south-east, and, on the 24th November, sighted the western coast of the land which he named Van Diemen's Land, in honor of the Governor under whose directions he was acting. The honor was later transferred to the discoverer himself, and the island is now known as Tasmania. Tasman doubled the southern extremity of Van Diemen's Land and explored the east coast for some distance. The ceremony of hoisting a flag and taking possession of the country in the name of the Government of the Netherlands was actually performed, but the description of the wildness of the country, and of the fabulous giants by which Tasman's sailors believed it to be inhabited, deterred the Dutch from occupying the island, and by the international principle of "non-user" it passed from their hands. Resuming his voyage in an easterly direction, Tasman sighted the west coast of the South Island of New Zealand on the 13th December of the same year, and describes the coast line as consisting of "high mountainous country."

Tasman was under the belief that the land he saw was part of a great polar continent discovered some years before by Schouten and Le Maire, to which the name of Staaten Land had been given. He, therefore, duplicated the designation; but within three months afterwards Schouten's "Staaten Land" was found to be merely an inconsiderable island. Tasman's discovery thereupon received the name of New Zealand, on account of a fancied likeness to a province of Holland to which it bears not the least resemblance, and by this name it has been known ever since. Tasman sailed along the coast to a bay, and there he anchored. This inlet is known as Golden or Massacre Bay, called by Tasman, Murderer's Bay. Here an unprovoked attack by the Maoris on a boat's crew resulted in the death of four of Tasman's sailors. Leaving Murderer's Bay, Tasman steered along the west coast of North Island. Vainly seeking a passage to the east, he passed and named Cape Maria Van Diemen, finally taking leave of New Zealand at North Cape. At the Three Kings Islands he made an attempt to land, but the ferocious aspect of the natives terrified his boat's crew, and the voyage was resumed. Tasman left New Zealand with a most unfavourable impression of its inhabitants. He had been off the coast for some three weeks without landing or planting the flag of his country thereon, and more than a century and a quarter elapsed before another European is known to have visited New Zealand.

The first English navigator to sight the Australian continent was William Dampier, who made a visit to these shores in 1688, as supercargo of the "Cygnet," a trader, whose crew had turned buccaneers. On his return to England he published an account of his voyage, which resulted in his being sent out in the "Roebuck" in 1699 to further prosecute his discoveries. To him we owe the exploration of the coast for about 900 miles—from Shark Bay to Dampier's Archipelago, and thence to Roebuck Bay. He appears to have landed in several places in search

of water. His account of the country was quite as unfavourable as Pelsaert's. He described it as barren and sterile, and almost devoid of animals, the only one of any importance somewhat resembling a racoon—a strange creature, which advanced by great bounds or leaps instead of walking, using only its hind legs, and covering 12 or 15 feet at a time. The reference is, of course, to the kangaroo, which Pelsaert had also remarked and quaintly described some 60 years previously.

During the interval elapsing between Dampier's two voyages, an accident led to the closer examination of the coasts of Western Australia by the Dutch. In 1684 a vessel had sailed from Holland for the Dutch possessions in the East Indies, and after rounding the Cape of Good Hope, she was never again heard of. Some twelve years afterwards the East India Company fitted out an expedition under the leadership of Commander William de Vlamingh, with the object of searching for any traces of the lost vessel on the western shores of New Holland. Towards the close of the year 1696 this expedition reached the island of Rottneest which was thoroughly explored, and early the following year a landing party discovered and named the Swan River. The vessels then proceeded northward without finding any traces of the object of their search, but, at the same time, making fairly accurate charts of the coast line.

The great voyage of Captain James Cook, in 1769-70, was primarily undertaken for the purpose of observing the transit of Venus, but he was also expressly commissioned to ascertain "whether the unexplored part of the Southern Hemisphere be only an immense mass of water, or contain another continent." H.M.S. "Endeavour," the vessel fitted out for the voyage, was a small craft of 370 tons, carrying twenty-two guns, and built originally for a collier, with a view rather to strength than to speed. Chosen by Cook himself, she was renamed the "Endeavour," in allusion to the great work which her commander was setting out to achieve. Mr. Charles Green was commissioned to conduct the astronomical observations, and Sir Joseph Banks and Dr. Solander were appointed botanists to the expedition. After successfully observing the transit from the island of Tahiti, or Otaheite, as Cook wrote it, the Endeavour's head was turned south, and then north-west, beating about the Pacific in search of the eastern coast of the great continent whose western shores had been so long known to the Dutch. On the 6th October, 1769, the coast of New Zealand was sighted, and two days later Cook cast anchor in Poverty Bay, so named from the inhospitality and hostility of the natives.

The expedition had thus far been sailing southward. Dissatisfied with the results, and finding it difficult to procure water in sufficient quantities, Cook put about, determining to follow the coast to the northward. He named a promontory in the neighbourhood Cape Turnagain. Another promontory more to the north, where a huge canoe made a hasty retreat, he called Cape Runaway. In the month

of November he touched at a point on the coast, where he landed and erected an observatory for the purpose of observing the transit of Mercury—one of the chief objects of his expedition on that occasion. A signal station was erected on the headland from which Cook took his observation, and which is now known as Shakespeare's Head. On the 9th of November the transit of Mercury was successfully observed, and the name Mercury Bay was given to the inlet where the observation was made. Two localities, for reasons which will be obvious, were called Oyster Bay and Mangrove River. Before leaving Mercury Bay, Cook caused to be cut upon one of the trees near the watering-place the ship's name and his own, with the date of arrival there, and, after displaying the English colours, took formal possession of it in the name of His Britannic Majesty King George the Third. It is noteworthy that Cook always managed to obtain wood and water wherever wood and water were to be had, no matter whether his intercourse with the natives were friendly or otherwise. He also contrived to carry on his surveys in spite of all opposition with such accuracy and deliberation that they remained the standard authority on the outlines of the islands for some seventy years or more. He was, moreover, a benefactor in no mean degree to the natives, who seldom knew the meaning of meat, save at a cannibal feast after a tribal victory. He not only improved their vegetables by giving them seed potatoes, but he turned loose fowls and pigs to supply their flesh larder. To the time of writing, the wild pigs which haunt the forests and the mountain gorges are called after Captain Cook, and they furnish many a solitary shepherd, miner, farmer, and gum-digger with excellent meat. Cook was, perhaps, either more prudent, or more successful than Captain Tobias Furneaux, of the consort "Adventure," who, in a subsequent voyage to New Zealand, lost an entire boat's crew of nine men, who were captured or killed, and duly cooked and eaten by the Maoris.

On the 17th December, the "Endeavour" doubled North Cape, which is the northern extremity of North Island, and began the descent of its western side. The weather now became stormy, and with a repetition of Tasman's experience from an opposite course on the same coast, very dangerous. Often was the vessel compelled to stand off in great distress, and intercourse with the natives was considerably interrupted. At one point, however, the English mariners satisfied themselves that the inhabitants ate human flesh—the flesh, at least, of enemies who had been killed in battle. On January 30th, 1770, Cook erected a flagpost on the summit of a hill in Queen Charlotte's Sound, where he again hoisted the Union Jack, and, after naming the bay where the ship was at anchor after the Queen, took formal possession of the South Island in the name of His Majesty King George the Third.

Cook crossed the waters of Doubtless Bay on the same day that the French Captain, De Surville, in the "St. Jean Baptiste," was

approaching the land at Mangonui. A few hours afterwards, and totally ignorant of Cook's presence in New Zealand waters, the Frenchman anchored in this very inlet and named it Lauriston Bay. This navigator was sent out by his Government, who believed that the English had found "an island of gold" in the South Seas, and sailed post haste from India to see if he could not participate in the exploitation of the precious metal. He was received by the natives with great hospitality; but, finding nothing more valuable than spars for his ship, he proceeded to South America, carrying away in irons the Rarawa chief, Ngakinui, who had entertained him and his sick seamen with great hospitality while on shore. Ngakinui pined on ship-board for his native food, and died some eighty days after his seizure. De Surville, only eleven days after the death of this unfortunate Maori chief, was drowned in the surf at Callao.

After voyaging westward for nearly three weeks Cook, on the 19th April, 1770, sighted the eastern coast of Australia at a point which he named after his lieutenant, who discovered it, Point Hicks, and which modern geographers identify with Cape Everard.

The "Endeavour" then coasted northward, and after passing and naming Mount Dromedary, the Pigeon House, Point Upright, Cape St. George, and Red Point, Botany Bay was discovered on the 28th April, 1770, and as it appeared to offer a suitable anchorage, the "Endeavour" entered the bay and dropped anchor. The ship brought to opposite a group of natives, who were cooking over a fire. The great navigator and his crew, unacquainted with the character of the Australian aborigines, were not a little astonished that these natives took no notice of them or their proceedings. Even the splash of the anchor in the water, and the noise of the cable running out through the hawse hole, in no way disturbed them at their occupation, or caused them to evince the slightest curiosity. But as the captain of the "Endeavour" ordered out the pinnace and prepared to land, the natives threw off their nonchalance; for on the boat approaching the shore, two men, each armed with a bundle of spears, presented themselves on a projecting rock and made threatening signs to the strangers. It is interesting to note that the ingenious "wommera," or throwing-stick, which is peculiar to Australia, was first observed on this occasion. As the men were evidently determined to oppose any attempt at landing, a musket was discharged between them, in the hope that they would be frightened by the noise, but it produced no effect beyond causing one of them to drop his bundle of spears, of which, however, he immediately repossessed himself, and with his comrade resumed the same menacing attitude. At last one cast a stone towards the boat, which earned him a charge of small shot in the leg. Nothing daunted, the two ran back into the bush, and presently returned furnished with shields made of bark, with which to protect themselves from the firearms of the crew. Such intrepidity is certainly worthy of passing notice. Unlike the American Indians, who supposed Columbus and his crew to be

supernatural beings, and their ships in some way endowed with life, and who were thrown into convulsions of terror by the first discharge of firearms which they witnessed, these Australians were neither excited to wonder by the ship, nor overawed by the superior number and unknown weapons of the strangers. Cook examined the bay in the pinnace, and landed several times ; but by no endeavour could he induce the natives to hold any friendly communication with him. The well-known circumstance of the great variety of new plants here obtained, from which Botany Bay derives its name, should not be passed over. Before quitting the bay the ceremony was performed of hoisting the Union Jack, first on the south shore, and then near the north head, formal possession of the territory being thus taken for the British Crown. During the sojourn in Botany Bay the crew had to perform the painful duty of burying a comrade—a seaman named Forby Sutherland, who was in all probability the first British subject whose body was committed to Australian soil.

After leaving Botany Bay, Cook sailed northward. He saw and named Port Jackson, but forebore to enter the finest natural harbour in Australia. Broken Bay and other inlets, and several headlands, were also seen and named, but the vessel did not come to an anchor till Moreton Bay was reached, although the wind prevented Cook from entering this harbour. Still sailing northward, taking notes as he proceeded for a rough chart of the coast, and landing at Bustard and Keppel Bays and the Bay of Inlets, Cook passed over 1,300 miles without the occurrence of any event worthy of being chronicled, till suddenly one night at 10 o'clock the water was found to shoal, without any sign of breakers or land. While Cook was speculating on the cause of this phenomenon, and was in the act of ordering out the boats to take soundings, the "Endeavour" struck heavily, and fell over so much that the guns, spare cables, and other heavy gear had at once to be thrown overboard to lighten the ship. As day broke, attempts were made to float the vessel off with the morning tide ; but these were unsuccessful. The water was rising so rapidly in the hold that with four pumps constantly going the crew could hardly keep it in check. At length one of the midshipmen suggested the device of "fothering," which he had seen practised in the West Indies. This consists in passing a sail, attached to cords, and charged with oakum, wool, and other materials, under the vessel's keel, in such a manner that the suction of the leak may draw the canvas into the aperture, and thus partially stop the vent. This was performed with great success, and the vessel was floated off with the evening tide. The land was soon after made near the mouth of a small stream, which Cook called, after the ship, the Endeavour River. A headland close by he named Cape Tribulation. The ship was steered into the river, and there careened and thoroughly repaired. Cook having completed the survey of the east coast, to which he gave the name of New South Wales, sighted and named Cape York, the northernmost point of Australia, and took final possession of his discoveries

northward from latitude 38° south to latitude 10½° south, on a spot which he named Possession Island, thence returning to England by way of Torres Straits and the Indian Ocean.

The great navigator's second voyage, undertaken in 1772, with the "Resolution" and the "Adventure" is of less importance. The vessels became separated, and both at different times visited New Zealand. Captain Tobias Furneaux, in the "Adventure," also found his way to Storm Bay in Tasmania. In 1777, while on his way to search for a north-east passage between the Atlantic and Pacific Oceans, Cook again touched at the coast of Tasmania and New Zealand.

On his return to England, Cook gave a most graphic description of New Zealand and its people. Men engaged in commerce became impressed with the value of the various articles which New Zealand produced, and hence of its importance as a market for manufactured goods; while the savant and the scientist regarded with great interest the information recently published respecting a race of people who, while having a real though hitherto undescribed form of civilisation, were yet greedy eaters of human flesh. Cook's report of the genial climate, the fertile soil, and the evergreen forests of the new archipelago, not only excited considerable interest in England, but so captivated the eminently practical mind of Benjamin Franklin that the American philosopher published a proposal for its immediate colonisation.

Meanwhile, in 1772, Captain Marion du Fresne anchored his two ships, the "Marquis de Castries" and the "Mascarin," in the Bay of Islands. These vessels formed a French expedition of discovery. Sailing from Nantes, on the Loire, Lieutenant Crozet, in command of the King's sloop "Mascarin," had lost his masts, and the two ships put into the Bay of Islands to refit. Du Fresne was frequently on shore during his stay, and habits of intimacy begat in the mind of the French Commander confidence in the friendship of the natives. Both races lived in harmony for several weeks. "They treated us," says Crozet, "with every show of friendship for thirty-three days, with the intention of eating us on the thirty-fourth." The Maori version, given by Dr. Thompson, is: "We treated Marion's party with every kindness for thirty days, and on the thirty-first they put two of our chiefs in irons, and burned our sacred places." It matters little whether the Maoris had any valid excuse for eating their guests or not, the fact remains that an attack was made on the French, when twenty-eight of their party and the commander were killed and eaten. Crozet, who had a party of men engaged in getting spars on the Kawakawa River, was also in danger of being trapped by the treacherous savages; but being forewarned, he was enabled to punish those who had killed his comrades and sought his own destruction. Before leaving the river he refitted the two vessels, and, after a stay of sixty-four days in the Bay of Islands, continued his voyage.

On his first voyage, in 1770, Cook had some grounds for the belief that Van Diemen's Land, as Tasmania was then called, was a separate island. The observations of Captain Furneaux, however, did not strengthen this belief, and when making his final voyage, the great navigator appears to have definitely concluded that it was part of the mainland of Australia. This continued to be the opinion of geographers until 1798, when Bass discovered the strait which bears his name. The next recorded expedition is a memorable one in the annals of Australian History—the despatch of a British colony to the shores of Botany Bay. The fleet sailed in May, 1787, and arrived off the Australian coast early in the following January. The history of the British settlements in the Southern Seas has been given with considerable detail in previous issues of this volume, and in the edition for 1902-3 will be found a table of the principal occurrences in Australia and New Zealand, arranged in chronological order from the earliest times up to the close of the year 1903.



## THE COMMONWEALTH.

THE question of the federation of the various provinces of Australia was not overlooked by the framers of the first free Australian Constitution, who proposed the establishment of a General Assembly "to make laws in relation to those intercolonial questions that have arisen, or may hereafter arise," and who, indeed, sketched out a tolerably comprehensive federation schema. Unfortunately, however, that proposition was included with another for the creation of a colonial hereditary nobility, and in the storm of popular opposition and ridicule with which the latter idea was greeted, the former sank out of sight. Again, in 1853, the Committees appointed in New South Wales and Victoria to draw up the Constitutions of their respective colonies, urged the necessity for the creation of a General Assembly; but the Home Government indefinitely postponed the question by declaring that "the present is not a proper opportunity for such enactment." From time to time, since Responsible Government was established, the evil of want of union among the Australian colonies has been forcibly shown, and the idea of federation has gradually become more and more popular. Some years ago (1883) the movement took such shape that, as the result of an Intercolonial Conference, the matter came before the Imperial Parliament, and a measure was passed permitting the formation of a Federal Council, to which any colony that felt inclined to join could send delegates. The first meeting of the Federal Council was held at Hobart in January, 1886. The colonies represented were Victoria, Queensland, Tasmania, Western Australia, and Fiji. New South Wales, South Australia, and New Zealand declined to join. South Australia sent representatives to a subsequent meeting, but withdrew shortly afterwards. The Council held eight meetings, at which many matters of intercolonial interest were discussed, the last having been held in Melbourne, early in 1899. One meeting every two years was necessary to keep the Council in existence. Being, from its inherent constitution, a purely deliberative body, having no executive functions whatever, the Federal Council possessed no control of funds or other means to put its legislation into force, and those zealous in the cause of federation had to look elsewhere for the full realisation of their wishes. The Council naturally ceased to exist at the inception of the Commonwealth.

An important step towards the federation of the Australasian colonies was taken early in 1890, when a Conference, consisting of representatives from each of the seven colonies of Australasia, was held in the Parliament House, Melbourne. The Conference met on the 6th February, thirteen members being present, comprising two representatives from each of the colonies, except Western Australia, which sent only one. Mr. Duncan Gillies, Premier of Victoria, was elected President. Seven meetings were held, the question of federation being discussed at considerable length; and in the end the Conference adopted an address to the Queen, expressing their loyalty and attachment, and submitting certain resolutions which affirmed the desirability of an early union under the Crown of the Australian colonies on principles just to all, suggested that the remoter Australasian colonies should be entitled to admission upon terms to be afterwards agreed upon, and recommended that steps should be taken for the appointment of delegates to a National Australasian Convention, to consider and report upon an adequate scheme for a Federal Constitution.

In accordance with the terms of that resolution, delegates were appointed by the Australasian Parliaments, and on the 2nd March, 1891, the National Australasian Convention commenced its sittings in the Legislative Assembly Chambers, Sydney, having been convened at the instance of Mr. James Munro, the Premier of Victoria. There were forty-five members of the Convention altogether, New South Wales, Victoria, Queensland, Tasmania, and Western Australia (which had only recently been placed in possession of the privilege of Responsible Government) each sending seven delegates, and New Zealand three. Sir Henry Parkes, then Premier of the mother colony, was unanimously elected President of the Convention; Mr. F. W. Webb, Clerk of the Legislative Assembly of New South Wales, was appointed Secretary; Sir Samuel Griffith, Premier of Queensland, was elected Vice-President; and Mr. (later Sir) J. P. Abbott, Speaker of the New South Wales Legislative Assembly, was elected Chairman of Committees.

A series of resolutions was moved by the President, Sir Henry Parkes, setting forth certain principles necessary to establish and secure an enduring foundation for the structure of a Federal Government, and approving of the framing of a Federal Constitution; and after discussion and amendment, the resolutions were finally adopted, affirming the following principles:—

1. The powers and rights of existing colonies to remain intact, except as regards such powers as it may be necessary to hand over to the Federal Government.
2. No alteration to be made in State boundaries without the consent of the Legislatures of such States, as well as of the Federal Parliament.
3. Trade between the federated colonies to be absolutely free.

4. Power to impose Customs and Excise Duties to rest with the Federal Government and Parliament.
5. Military and Naval Defence Forces to be under one command.
6. The Federal Constitution to make provision to enable each State to make amendments in its Constitution if necessary for the purposes of Federation.

Further resolutions approved of the framing of a Federal Constitution which should establish a Senate and a House of Representatives—the latter to possess the sole power of originating money Bills; also a Federal Supreme Court of Appeal, and an Executive consisting of a Governor-General, with such persons as might be appointed his advisers. On the 31st March, Sir Samuel Griffith, as Chairman of the Committee on Constitutional Machinery, brought up a draft Constitution Bill, which was fully and carefully considered by the Convention in Committee of the Whole, and adopted on the 9th April, when the Convention was formally dissolved.

The Bill of 1891 aroused no popular enthusiasm, and parliamentary sanction to its provisions was not sought in any of the colonies; thus federation fell into the background of politics.

At this juncture a section of the public began to exhibit an active interest in the cause, which seemed in danger of being temporarily lost through the neglect of politicians. Public Associations showed sympathy with the movement, and Federation Leagues were organised to discuss the Bill and to urge the importance of federal union upon the people. A conference of delegates from Federation Leagues and similar Associations in New South Wales and Victoria was called at Corowa in 1893. The most important suggestion made at this Conference was that the Constitution should be framed by a Convention to be directly elected by the people of each colony for that purpose. This new proposal attracted the favourable attention of Mr. G. H. Reid, then Premier of New South Wales, who perceived that a greater measure of success could be secured by enlisting the active sympathy and aid of the electors, and who brought the principle to the test in 1895. In January of that year he invited the Premiers of the other colonies to meet in conference for the purpose of devising a definite and concerted scheme of action. At this Conference, which was held at Hobart, all the Australasian colonies except New Zealand were represented. It was decided to ask the Parliament of each colony to pass a Bill enabling the electors qualified to vote for members of the Lower House to choose ten persons to represent the colony on a Federal Convention. The work of the Convention, it was determined, should be the framing of a Federal Constitution, to be submitted, in the first instance, to the local Parliaments for suggested amendments, and, after final adoption by the Convention, to the electors of the various colonies for their approval by means of the referendum.

In 1896 a People's Federal Convention, an unofficial gathering of delegates from various Australian organisations, met at Bathurst to

discuss the Commonwealth Bill in detail, and by its numbers and enthusiasm gave valuable evidence of the increasing popularity of the movement.

In accordance with the resolutions of the Convention of 1895, Enabling Acts were passed during the following year by New South Wales, Victoria, South Australia, Tasmania, and Western Australia; and were brought into operation by proclamation on the 4th January, 1897. Meanwhile Queensland held aloof from the movement, after several attempts to agree on the question of the representation of the Colony. The Convention met in Adelaide, Mr. C. C. Kingston, Premier of South Australia, being elected President; and Sir Richard Baker, President of the Legislative Council of South Australia, Chairman of Committees; while Mr. Edmund Barton, Q.C., one of the representatives of the mother colony, and a gentleman who had taken a deep interest in the movement, acted as leader of the Convention. The final meeting of the session was held on the 23rd April, when a draft Constitution was adopted for the consideration of the various Parliaments, and at a formal meeting on the 5th May, the Convention adjourned until the 2nd September. On that date the delegates re-assembled in Sydney, and debated the Bill in the light of suggestions made by the Legislatures of the federating colonies. In the course of the proceedings, it was announced that Queensland desired to come within the proposed union; and, in view of this development, and in order to give further opportunity for the consideration of the Bill, the Convention again adjourned. The third and final session was opened in Melbourne on the 20th January, 1898, the Colony of Queensland being still unrepresented; and, after further consideration, the Draft Bill was finally adopted by the Convention on the 16th March for submission to the people.

In its main provisions the Bill of 1898 followed generally that of 1891, yet with some very important alterations. It proposed to establish, under the Crown, a federal union of the Australasian colonies, to be designated the Commonwealth of Australia. A Federal Executive Council was created, to be presided over by a Governor-General appointed by the Queen. The Legislature was to consist of two Houses—a Senate, in which each colony joining the Federation at its inception was conceded the equal representation of six members; and a House of Representatives, to consist of, as nearly as possible, twice the number of Senators, to which the provinces were to send members in proportion to population, with a minimum number of five representatives for each of the original federating states. The principle of payment of members was adopted for the Senate as well as for the House of Representatives, the honorarium being fixed at £400 per annum. The nominative principle for the Upper House was rejected, both Houses being elective, on a suffrage similar to that existing in each colony for the popular Chamber at the foundation of the Commonwealth. At the same time, it was left to the Federal Parliament to establish a federal franchise, which, however,

could only operate in the direction of the extension, not the restriction, of any of the existing privileges of the individual colonies; so that in those States where the franchise has been granted to women their right to vote cannot be withdrawn by the central authority so long as adult suffrage prevails. While the House of Representatives was to be elected for a period of three years, Senators were to be appointed for twice that term, provision being made for the retirement of half their number every third year. The capital of the Commonwealth was to be established in federal territory.

Warmly received in Victoria, South Australia, and Tasmania, the Bill was viewed somewhat coldly by a section of the people of New South Wales, and this feeling rapidly developed into one of active hostility, the main points of objection being the financial provisions, equal representation in the Senate, and the difficulty which the larger colonies must experience in securing an amendment of the Constitution in the event of a conflict with the smaller States. So far as the other colonies were concerned, it was evident that the Bill was safe, and public attention throughout Australasia was riveted on New South Wales, where a fierce political contest was raging, which it was recognised would decide the fate of the measure for the time being. The fears expressed by its advocates were not so much in regard to securing a majority in favour of the Bill, as to whether the statutory number of 80,000 votes necessary for its acceptance would be reached. These fears proved to be well founded; for on the 3rd June, 1898, the result of the referendum in New South Wales showed 71,595 votes in favour of the Bill, and 66,228 against it, and it was accordingly lost. In Victoria, Tasmania, and South Australia, on the other hand, the Bill was accepted by triumphant majorities. Western Australia did not put it to the vote; indeed, it was useless to do so, as the Enabling Act of that colony only provided for joining a Federation of which New South Wales should form a part.

The existence of such a strong opposition to the Bill in the mother colony convinced even its most zealous advocates that some changes would have to be made in the Constitution before it would be accepted by the people; consequently, although the general election in New South Wales, held six or seven weeks later, was fought on the Federal issue, yet the opposing parties seemed to occupy somewhat the same ground, and the question narrowed itself down to one as to which should be entrusted with the negotiations to be conducted on behalf of the colony with the view to securing a modification of the objectionable features of the Bill. The new Parliament decided to adopt the procedure of sending the Premier, Mr. Reid, into conference, armed with a series of resolutions affirming its desire to bring about the completion of federal union, but asking the other colonies to agree to the reconsideration of the provisions which were most generally objected to in New South Wales. As they left the Assembly, these resolutions submitted—first, that, with equal representation in the Senate, the

three-fifths majority at the joint sitting of the two Houses should give way to a simple majority, or the joint sitting be replaced by a provision for a national referendum ; second, that the clause making it incumbent upon the Federal Government to raise, in order to provide for the needs of the States, £3 for every £1 derived from Customs and Excise Duties for its own purposes, and thus ensuring a very high tariff, should be eliminated from the Bill ; third, that the site of the Federal Capital should be fixed within the boundaries of New South Wales ; fourth, that better provision should be made against the alteration of the boundaries of a State without its own consent ; fifth, that the use of inland rivers for the purposes of water conservation and irrigation should be more clearly safeguarded ; sixth, that all money Bills should be dealt with in the same manner as Taxation and Appropriation Bills ; and seventh, that appeals from the Supreme Courts of the States should uniformly be taken, either to the Privy Council or to the Federal High Court, and not indiscriminately to either ; while the House also invited further inquiry into the financial provisions of the Bill, although avowing its willingness to accept these provisions if in other respects the Bill were amended. These were all the resolutions submitted by the Government to the House, but the Assembly appended others in respect to the alteration of the Constitution and the number of Senators, submitting, on the first of these points, that an alteration of the Constitution should take effect, if approved by both Houses and a national referendum ; that a proposed alteration should be submitted to the national referendum, if affirmed in two succeeding sessions by an absolute majority in one House, and rejected by the other ; and that no proposed alteration, transferring to the Commonwealth any powers retained by a State at the establishment of the federation, should take effect in that State, unless approved by a majority of electors voting therein ; and, on the second point, that the number of Senators should be increased from six to not less than eight for each State.

The Legislative Council adopted the resolutions with some important amendments, discarding the suggestion in the first resolution for a national referendum ; submitting that the seat of the Federal Government should be established at Sydney ; more clearly preserving the rights of the people of the colony to the use of the waters of its inland rivers for purposes of water conservation and irrigation ; carrying all appeals from the Supreme Courts of the States to the Privy Council ; and declining to affirm its preparedness to accept the financial scheme embodied in the Bill. Further, the House suggested that the plan of submitting proposed alterations of the Constitution to the people by means of the referendum should be altered, and that no rights or powers retained by a State should be afterwards transferred to the Commonwealth without the consent of both Houses of Parliament of that State. The New South Wales Premier decided to submit the resolutions of both Houses to the other Premiers in conference, attaching, however, greater importance to those of the Assembly, as embodying the views

of a House which had just returned from the country. This conference was held in Melbourne at the end of January, 1899, Queensland being represented; and an agreement was arrived at, whereby it was decided that, in the event of a disagreement between the two Houses of Parliament, the decision of an absolute majority of the members of the two Houses should be final; that the provision for the retention by the Commonwealth of only one-fourth of the Customs and Exchequer revenue might be altered or repealed at the end of ten years, another clause being added, permitting the Parliament to grant financial assistance to a State; that no alterations in the boundaries of a State should be made without the approval of the people as well as of the Parliament of that State; and that the seat of Government should be in New South Wales, at such place, at least 100 miles from Sydney, as might be determined by the Federal Parliament, and within an area of 100 square miles of territory, to be acquired by the Commonwealth, it being provided that the Parliament should sit at Melbourne until it met at the seat of Government. A special session of the New South Wales Parliament was convened to deal with this agreement, and the Legislative Assembly passed an Enabling Bill, referring the amended Constitution to the electors. The Council, however, amended the Bill demanding—first, the postponement of the referendum for a period of three months; second, making it necessary for the minimum vote cast in favour of the Bill to be one-fourth of the total number of electors on the roll; third, deferring the entrance of New South Wales into the Federation until Queensland should come in. These amendments were not accepted by the Assembly, and a conference between representatives of the two Houses was arranged; but this proved abortive, and twelve new members were appointed to the Upper House in order to secure the passage of the Bill. This course had the effect desired by the Government; for the Council passed the Bill on the 19th April, an amendment postponing the referendum for eight weeks being accepted by the Assembly. The Bill received its final assent on the 22nd April, and the 20th June following was appointed as the date of the referendum. The poll resulted in a majority of 24,679 in favour of the Bill; the votes recorded for and against being 107,420 and 82,741 respectively. South Australia on the 29th April had re-affirmed its acceptance of the Bill by a majority of 48,937 votes, in Victoria it was again passed with a majority of 142,848 on the 27th July, while on the same date the Bill passed in Tasmania with a margin in its favour of 12,646 votes. Queensland adopted the measure on the 2nd September by a majority of 6,216. Western Australia still hung back, but at a referendum taken on the 31st July, 1900, the Bill was accepted with the decisive majority of 25,109 votes.

Though the Bill was favourably received by the Imperial Government, certain amendments, the most important of which referred to the appeal to the Privy Council, were proposed by Mr. Chamberlain, the Secretary of State for the Colonies. At a Premier's Conference, held

in Sydney at the end of January, it was decided to send delegates to England from each of the federating colonies, who were to give their joint support to the Bill, but were not to consent to any amendment of its provisions. The six delegates arrived in England in March, 1900, and a series of conferences took place amongst themselves, and also with officers representing the Imperial Government. The most serious ground of contention was Clause 74, which prohibited appeals to Her Majesty in Council in matters involving the interpretation of the Constitution of the Commonwealth or of a State unless the public interests of other parts of Her Majesty's dominions were concerned. On all other questions the right of appeal from Supreme Courts of the States, as well as from the Federal High Court, was left untouched. Mr. Chamberlain proposed that, notwithstanding anything in the Constitution, the prerogative of Her Majesty of granting special leave to appeal might be exercised with respect to any judgment or order of the High Court of the Commonwealth or of the Supreme Court of any State. In other words, the Secretary of State insisted that Clause 74 should be amended so as to maintain the royal prerogative as to appeals on constitutional questions as well as other matters, while at the same time he promised a re-constituted Court of Appeal for the Empire in which the Australian Colonies would find representation. The delegates opposed most strongly the submission of constitutional disputes to the decision of the Privy Council under any pretext. A compromise, supported by four of the six delegates, was therefore agreed upon, by which the consent of the Executive Government or Governments was made a necessary condition precedent to an appeal from the High Court to the Privy Council on constitutional questions. The new arrangement, however, evoked such hostile criticism in the colonies that the Premier cabled a rejection of it. A fresh compromise was thereupon arrived at, by which it was determined that the right of appeal to the Privy Council, where a constitutional point purely Australian in character was involved, might be granted at the pleasure of the High Court. By this settlement the finality of the decisions of the High Court upon matters of constitutional interpretation is preserved. The arrangement proved satisfactory to both sides, and the amendment was accepted by the legislatures of the federating colonies. Thenceforward no further objection was made to the passing of the measure, and it received the royal assent on the 9th July.

Lord Hopetoun, who had formerly occupied the position of Governor of Victoria, was appointed first Governor-General of the Commonwealth of Australia, and arrived in Sydney on the 15th December. Meanwhile, by royal proclamation, the first day of January, 1901, was fixed on as the date of inauguration of the new Commonwealth. The first Federal Ministry was formed under the leadership of Mr. (now Sir) E. Barton, and was composed of the following members:—

Mr. (now Sir) E. Barton (N.S.W.), Prime Minister and Minister of State for External Affairs; Sir William Lyne (N.S.W.), Minister of State for



Home Affairs; Sir George Turner (Vic.), Treasurer; Mr. Alfred Deakin (Vic.), Attorney-General and Minister for Justice; Mr. C. C. Kingston (S.A.), Minister for Trade and Customs; Sir J. R. Dickson (Q.), Minister for Defence; Sir John Forrest (W.A.), Postmaster-General. Mr. R. E. O'Connor (N.S.W.), and Mr. (now Sir) N. E. Lewis (Tas.) were also appointed as Ministers without portfolio, the former occupying the position of Vice-President of the Executive Council. A few days later Sir James Dickson died after a short illness, and the portfolio of Minister of Defence was assigned to Sir John Forrest, while Mr. J. G. Drake, who held office as Postmaster-General of Queensland, was appointed to a similar position in the Federal Executive. Mr. Lewis only held office in the Commonwealth Cabinet until the Federal elections had taken place, when he resigned, and was succeeded by Sir Philip O. Fysh. The Ministry as above constituted was sworn in on the 1st January, 1901, the ceremony taking place in a specially-erected pavilion in the Centennial Park, Sydney. The festivities in connection with this epoch-making event in Australian history lasted for several days, additional interest being lent to the proceedings by the presence of detachments of troops from Great Britain, India, and the various provinces of Australasia. The death of Queen Victoria, which took place on the 22nd January, 1901, possesses a melancholy interest for these States from the fact that one of the last great public acts of the deceased sovereign was the signing of the proclamation establishing the Commonwealth. Under the Constitution, the control of Customs and Excise in the various States passed over to the Federal authority with the inauguration of the Commonwealth, and attention was at once devoted to placing matters in connection with these services in working order. The taking over of the postal administrations of the States was not finally dealt with till the 1st March, and the same date saw the transfer of the Defence Departments. These were the only divisions of State administration over which the Commonwealth Government thought necessary to assume control, though the Constitution rendered it permissible to take over lighthouses, lightships, beacons, buoys, and quarantine, by the simple act of proclaiming the dates, and without further legislation.

As it was necessary for the Federal elections to take place early in 1901, much detail work was cast upon the Ministry in the shape of arranging for the various preliminaries in connection with recording the votes in the six States. In the first Parliament each State returned six members to the Senate, while section 26 of the Constitution provided for the number of representatives in the Lower House as follows:—New South Wales, 26; Victoria, 23; Queensland, 9; South Australia, 7; Western Australia, 5; Tasmania, 5. Parliament may increase or diminish the number of members, provided that it does not alter the proportion of members to Senators, and does not bring the number of members returned from an original State below five. The chief interest in the elections settled round the question of the fiscal policy of the new

Commonwealth. When the Constitution Act was under consideration, the problem arose of ensuring a sufficient Customs Revenue to enable each State to receive back from the Federal Treasurer an amount equal to what its own receipts would have been, less the net expenditure of the Commonwealth. This necessity was met by the "Braddon Clause," as section 87 was called, providing that during a period of ten years after the establishment of the Commonwealth, and thereafter until further legislative action is taken by Parliament, not more than one-fourth of the net revenue of the Commonwealth from Customs and Excise shall be applied annually towards Commonwealth Expenditure. The balance of three-fourths is to be returned to the States, or applied towards the payment of interest on the debts of the several States taken over by the Commonwealth. Under these circumstances it was recognised that it would be necessary to raise a revenue, certainly over £6,000,000 and more probably approximating £8,500,000, so that the States should be recouped in the manner indicated. It was, therefore, apparent that the elections could not be contested on a clear-cut Freetrade-Protection issue, and the parties divided on the question as to whether the tariff should be revenue-producing alone, or of a more or less protective character. The Prime Minister, in his official declaration of ministerial policy, announced himself in favour of a tariff that would yield revenue without destroying industries, or a policy of "moderate protection." The fiscal issue was made most prominent in New South Wales and Victoria, although in the other States more or less powerful organisations ranged themselves on either side. Representatives of labour, for the most part, took up an independent position.

The elections were conducted as provided by the different State laws. Each State voted as one constituency for the Senate, and in Tasmania and South Australia the same procedure was adopted in voting for the House of Representatives. The elections took place on the 29th and 30th March, each of the opposing parties claiming the victory when the final results were published. From the declared policy of the candidates it appeared probable that the protectionists would have a majority in the Lower House, while the "revenue-tariffists" had a stronger hand in the Senate. The attitude of the Labour Party, which had secured 23 seats in the two Houses, was now of prime importance, but a semi-official statement from one of their number made it clear that the party intended to "retain the balance of power and use their strength only to defeat a government which refused to obey the will of the people." In addition to completing arrangements for the mechanical working of both Houses, preliminary action with regard to the framing of a tariff had to be initiated in the interval between the elections and the meeting of Parliament. The Prime Minister was also called upon to deal with questions affecting the condition of affairs in the New Hebrides, and the ownership of Kerguelen Island, and the policy pursued in these matters showed that the Commonwealth was prepared to take cognisance of subjects that lay outside the dominion of Australia. This

development met with some adverse criticism, but, generally speaking, the introduction into Australian politics of a more-extended range of interests and a broader aspect of national life was hailed with satisfaction.

The ceremony of opening the first session of the first Federal Parliament of the Commonwealth took place on the 9th May, 1901, in the Exhibition Building at Melbourne, which had been specially decorated for the occasion. Under commission from His Majesty King Edward VII., His Royal Highness the Duke of Cornwall and York formally opened the Parliament and in his speech from the throne, reference was made to His Majesty's deep interest in the consummation of Australian union, and eloquent testimony was given to the loyalty and devotion of the Colonies to the Empire. On the same day the Senate elected Sir Richard Chaffey Baker, of South Australia, as its first President, while the House of Representatives elected Mr. Frederick William Holder, also of South Australia, as Speaker. The Governor-General delivered his speech to members of both Houses on the following day, in which an outline was given of the policy of the Commonwealth. In addition to proposals necessary for adapting the recently-transferred Customs and Excise, Posts and Telegraphs, and Defence Departments to the new conditions, measures covering a wide range of subjects were promised. Bills establishing a High Court of Australia, a Commission for the execution and maintenance of the provisions of the Constitution relating to Trade and Commerce, and for regulating the Public Service of the Federation were included in the first part of the Government programme, and the selection of the site for a Federal capital was looked upon as a matter of comparative urgency. As regards the fiscal policy, it was stated that "The fiscal proposals of any Government must be largely dependent on the financial exigencies of the States. The adoption of the existing tariff of any one of these States is impracticable, and would be unfair. To secure a reasonably sufficient return of surplus revenue to each State, so as fully to observe the intention of the Constitution, while avoiding unnecessary destruction of sources of employment, is a work which prohibits a rigid adherence to fiscal theories. Revenue must, of course, be the first consideration, but existing tariffs have in all States given rise to industries, many of which are so substantial that my advisers consider that any policy tending to destroy them is inadmissible. A tariff which gives fair consideration to these factors must necessarily operate protectively as well as for production of revenue."

Bills were also promised dealing with the restriction of immigration of Asiatics, and the diminution and gradual abolition of the introduction of labour from the South Sea Islands, while measures were stated to be in preparation providing for conciliation and arbitration in cases of industrial disputes extending beyond the limits of any one State, for the uniform administration of the law relating to patents and inventions, and for a uniform franchise in all federal elections. Amongst

other legislation foreshadowed, but not designed for immediate consideration, were Bills dealing with Old Age Pensions, Banking Laws, Federal Elections, Navigation, Shipping, Quarantine, and the management of State Debts. Reference was also made, and attention promised to the question of the relations of the Commonwealth with the islands of the Pacific, the construction of railways, connecting the eastern states with Western Australia, and also the Northern Territory of South Australia, while with regard to the latter its transference to the Commonwealth was also projected. Mention was also made of such matters as the strengthening of Commonwealth defences, the assimilation of postal and telegraph rates, and the adoption of universal penny postage. After the formal opening of Parliament, both Houses adjourned until the 21st May, when the real work of the session began. Early in the debate on the Address in Reply the Labour Party raised the question of a "White Australia" by moving amendments to the effect that black labour on the sugar plantations of Queensland and northern New South Wales should cease at once, but on the assurance being given that the Ministry had the matter under consideration the amendments were negatived. The address was finally adopted in the Senate on the 31st May, and in the House of Representatives on June 5th, and the way was then clear for practical legislation.

The first measure introduced into the House of Representatives was the Acts of Parliament Interpretation Bill on the 10th May, while in the Senate leave to introduce the Service and Execution of Process Bill was moved for on the opening day. On June 5th notification was given of several bills dealing with such subjects as Pacific Island Labourers, Judiciary, High Court Procedure, Federal Elections, Federal Franchise, Conciliation and Arbitration, Immigration Restriction, Public Service, Interstate Commission, Acquisition of Property for Public Purposes, Defence, and Customs. On the same date the Postmaster-General introduced the Post and Telegraphs Bill in the Senate.

Early in the session the Senate gave token of its intention to maintain strictly the privileges granted to it by the Constitution. Exception was taken to the first Supply Bill sent from the House of Representatives because the accounts of proposed expenditure had not been incorporated in the measure, but submitted in the form of a schedule. The Bill was returned to the Lower House, which consented to amend it in accordance with the wishes of the Senate. In the House of Representatives deliberations were commenced on the Public Service Bill, and although the Lower House had passed the measure on to the Senate by the end of July it was not till near the close of the session that it finally became law. The second reading of the Customs Bill, a purely machinery measure, passed the Lower House early in July, but the Defence Bill, which proposed to introduce compulsory military service, was shelved. Another measure which met with little success was the Property Acquisition Bill, the various schemes devised for payment for property acquired from individuals or States evoking much

opposition from the State Governments, while the Government did not persevere with the bill to institute the Interstate Commission. During July and August, in addition to Supply Bills, the Acts Interpretation Act and an Audit Act received royal assent, while the State Laws and Records Recognition Bill had been practically finally dealt with, and the Postal Bill (assented to on the 20th November) was also in a fair way towards completion, a novel clause being inserted in the latter measure at the instigation of the Labour Party providing for the employment of white labour only in the carriage of mails. While awaiting the completion of these and of other measures preparatory to the introduction of the tariff, some important legislation was introduced in the shape of the Immigration Restriction Bill and the Pacific Islands Labourers Bill.

Under the Constitution, a period of two years was allowed before the imposition of uniform duties became compulsory, but the feeling, both in Parliament and amongst the people of the various States, was in favour of its early introduction in order to secure adequate adjustment of commercial relations. Before the tariff proposals proper could be tabled, however, various machinery measures, such as the Customs Bill, already mentioned, the Excise Bill, and the Beer Excise and Distillery Bills had to be dealt with. Attention was again devoted to the Immigration Restriction Bill, and the Pacific Islands Labourers Bill. After a long debate the first of these measures was passed, but not quite in the form desired by the labour organisation. The Pacific Island Labourers Bill provides for a gradual lessening of the number of Kanakas employed in the northern plantations up till 1904, and none were to enter Australia after the 31st March in that year, while no agreement was to be made, or remain in force, after the same date in 1906. As it stood, the measure met with strenuous opposition in Queensland, where it was maintained that the sugar industry would be extinguished if the Bill became law. Despite the efforts made, both in Parliament and outside, the Bill passed both Houses practically unamended, and received the royal assent at the end of the year.

While the above-mentioned Bills were before the House, in some form or another, the Treasurer delivered his budget speech, and the tariff was laid on the table by the Minister for Trade and Customs on the 8th October. Reference was made by the Treasurer to the financial considerations involved in constructing the proposals. The Cabinet had decided that £21,000,000 represented the value of goods available for taxation in a normal year, and on this amount duties had been framed to produce £2 7s. 6d. per head of revenue. In a normal year the yield from the Customs was estimated at £7,388,056, which with £1,554,345 from Excise, brought the total to £8,942,401. It was proposed to raise a loan of £1,000,000, and a sinking fund for redemption of loans was to be provided, such fund to be invested in Commonwealth Stock. The Minister of Trade and Customs, upon whom devolved the duty of tabling the tariff, did so with the

declaration that interstate freetrade had arrived. After stating that the tariff was neither freetrade nor protectionist in character, the Minister proceeded to detail the methods under which it had been drawn up. From the total annual value of imports into the Commonwealth, calculated at £63,000,000, various deductions were to be made. The establishment of interstate freetrade took away £29,000,000 from this sum, and it was estimated that the total taxable balance left amounted to £21,000,000. Of this amount the value of narcotics and stimulants was £1,910,000, and the duties proposed on these articles, together with £1,131,000 from excise would yield £4,100,000. From fixed and composite duties averaging 30·94 per cent. £2,020,471 would be raised on £6,530,000 worth of goods, and ad valorem duties ranging from 10 per cent. to 25 per cent. would yield £2,362,211 on £12,583,740 worth of goods, or an average of 18·7 per cent. The excise on sugar was to be charged from the 1st July, 1902, and would cease in 1907, when, according to the terms of the Kanaka Bill, sugar would be produced by white labour. In the course of his speech the Minister indicated that the Government intended to adopt a reasonable system of bonuses to encourage the establishment or extension of industries which were not yet established, or to which protection could not be immediately extended.

It was to be expected that a tariff constructed under such difficulties as beset the framers would not meet with unqualified approval, and immediate signs were not wanting that extensive amendments would be proposed. On the 15th October the Right Hon. G. H. Reid, the leader of the Opposition, moved a vote of censure to the effect that the financial and tariff proposals of the Government did not meet with the approval of the House. After a protracted debate the motion was put to the vote on the 1st November, and resulted in a victory for the Government by a majority of 14, every member of the House being represented.

When finally dealt with in Committee the tariff had undergone extensive alteration. Amongst the more important changes was the abolition of composite duties, a novel form of impost in most of the States, and in many instances the rates were lessened. The duties on tea and kerosene were abandoned, and the placing of these items on the free list deprived the Treasurer of some £500,000 of his anticipated revenue. The abolition of these duties was viewed with dismay by the Treasurers of the smaller States, and Queensland, South Australia, and Tasmania were united in their protest. Assurance was, however, given by the Government that if it were found necessary fresh duties would be imposed at a later date. The tariff finally emerged from the House of Representatives during the second week in April, and the necessary machinery measures were thereupon pushed through. Under the Constitution the Senate has no power to alter the tariff, but it may suggest alterations and refuse to pass the duties until such suggestions have been acceded to.

The transfer of British New Guinea to the Commonwealth, effected towards the close of 1901, is interesting, as the territory possesses great, though almost undeveloped, resources, while in connection with Commonwealth defences, the position may prove of strategic importance.

One of the disabilities under which the Commonwealth laboured during the first months of its existence was the absence of a Federal Judicature to deal with cases arising out of the administration of the Federal laws. In some instances, of course, the State Courts were appealed to, but there was some doubt as to whether the Commonwealth itself could be sued under the existing legislation. To obviate in some measure this inconvenience, the State Laws and Records Recognition Act and the Service and Execution of Process Act were introduced at the beginning of the session, and the Punishment of Offences Act was also passed to provide that offenders against the Commonwealth might be dealt with by State laws. It was recognised, however, that a Judiciary Bill and High Court Procedure Bill were still urgently needed. The second reading of the former was moved on the 18th March. This Bill provided for a High Court, with one Chief Justice and four other justices; the principal seat of the Court to be at the Federal capital. Power was given to appoint a judge of the Supreme Court of any State as a judge of the High Court sitting in Chambers, in order to enable the initiatory steps to actual hearing to be proceeded with prior to the visit of a High Court judge. The measure also allotted certain Federal jurisdiction to State Courts, and permitted the transfer in certain instances of cases from the State Courts to the High Court. Subsequently the Bill was shelved by the Government until a more favourable opportunity presented itself for its discussion.

During 1901 efforts were made, both in Parliament and by public men outside, to have a site fixed on for the Federal Capital. Several localities were suggested and discussed, and the Government of New South Wales obtained reports as to their suitability, but it was not till 1902 that any definite move was made by the Federal Parliament. In February certain members of the Senate made a tour of inspection to several of the suggested sites, while members of the House of Representatives were given a similar opportunity in May. Both excursions were of necessity somewhat hurried, but they at least served the useful purpose of giving members some knowledge as to the localities suggested. The sites visited included Albury, Tumut, Dalgety, Wagga, Yass, Goulburn, Orange, Cooma, Bombala, and Armidale.

Towards the close of 1901 a commencement was made with the laying of a Pacific Cable, the Australian terminal of which is at Southport, in Queensland. From this point the line runs to Norfolk Island, thence to New Zealand, to Fiji, to Fanning Island, and to Vancouver. The cable was completed and opened for business in November, 1902.

During the adjournment at the end of 1901 the Premier received a request from the Imperial Authorities for 1,000 troops for service in South Africa. This contingent was made up of 348 men each from

Victoria and New South Wales, 116 each from Queensland and South Australia, and 116 from Tasmania and Western Australia combined, the united forces being known, at a later date, as the Australian Commonwealth Horse. When the House met after vacation, the Premier took occasion to refer to the charges made against the people and army of the Empire, and moved resolutions expressive of the determination of the Commonwealth to give all the assistance in its power to His Majesty's Government with a view to a speedy termination of the war. On the 20th January the Government sent another contingent of 1,000 men, and in March a request was received for 2,000 additional troops, and these were also despatched.

At one time it seemed as though the new legislation of the Commonwealth would involve the Federal Government in international complications. By the operation of the Customs Act it was provided that deep-sea vessels should pay duty on all stores consumed by passengers and crew during the period between their first touching at an Australian port until they finally left the coast. When a mail steamer arrived at a Western Australian port, therefore, a Customs official boarded the vessel, superintended the removal of sufficient stores to last till the next port of call, and sealed up the storeroom. If on arrival at the next port these seals were found to have been broken, prosecution followed. The first case occurred in connection with an English mailboat, and the Full Court of Victoria decided in favour of the Commonwealth. The owners of the vessel pleaded that, as they were on the high seas between the ports, the Commonwealth had no jurisdiction. When the law was enforced with reference to the German vessels, the matter was taken up warmly by the authorities in Germany, and representations were made to the British Government on the matter. An amicable settlement was, however, arrived at, both English and foreign steamship companies agreeing to the payment of the duties until the matter had been decided by the Privy Council. Judgment was given by the Privy Council in favour of the Commonwealth towards the close of 1903.

Universal regret was expressed throughout the Commonwealth when it became known in May, 1902, that the Earl of Hopetoun had resigned his office as Governor-General. Lord Tennyson, Governor of South Australia, was appointed to the position in November; but, in accordance with his wishes, held office only until January, 1904, when he was succeeded by Lord Northcote.

In June, 1902, an Imperial Conference was held in London, the Hon. E. Barton being delegated to represent the Commonwealth of Australia. The subjects for discussion suggested by the Commonwealth included (1) Army and Navy supply contracts; (2) Ocean cables and purchase thereof; (3) Imperial Court of Appeal; (4) Mutual protection of patents; (5) Loss of most favoured nation treatment if preference given to British manufacturers; (6) Imperial stamp charges for colonial bonds. The decisions of the Conference were to be brought before Parliament on its re-assembling.



In August the Tariff Bill was again under consideration by the Senate. After some three or four months spent in revising the Bill as passed by the House of Representatives, the Senate sent down requests for 103 amendments to be made. Of these 51 were acceded to by the Lower Chamber and the remaining 52 were rejected. The Senate pressed for consideration of its requests, and the Lower House proving obdurate, it was feared that a deadlock would ensue. The conciliatory attitude of both Houses after maturer consideration happily averted this crisis, the Lower Chamber agreeing to a number of the Senate's proposals, while the two Houses compromised as to the main points at issue. The Bill finally became law on the 16th September, a little over eleven months after its introduction.

The important matter of re-arranging the electorates of the Commonwealth was dealt with at the close of the session, and a Commissioner for each state was appointed. A division of each state was accordingly made, and Parliament accepted the distribution of South Australia and Tasmania, but rejected those of the other states. The elections of 1903 were carried out in accordance with the new distribution in the first-mentioned states, and on the old basis in the others. The number of members of the House of Representatives to which a state is entitled is determined by section 24 of the Constitution Act, which provides that the population of the Commonwealth shall be determined according to the latest statistics, and a quota thereof ascertained by dividing that population by twice the number of the Senate (72). The number of representatives to which a state is entitled being determined by dividing the population by the ascertained quota, any remainder on such division greater than one-half of the quota is taken as entitling a state to one more member. In reckoning the number of people, aborigines are to be excluded as well as all persons of any race disqualified from voting at elections for the more numerous House of Parliament.

This last provision is an extremely important one. It will be found on reference to the Acts governing the exercise of the franchise that several states have an alien exclusion provision; thus Section 6 of the Queensland Act of 1885 provides that "No aboriginal native of Australia, India, China, or of the South Sea Islands shall be entitled to be entered on the roll except in respect of freehold qualification."

The question arises whether it can be said that all persons of any race are disqualified from voting in view of the exception in regard to a freehold qualification. The matter was submitted to the Attorney-General of the Commonwealth, who decided that the provision of the Queensland Act does disqualify all persons of the races named within the meaning of Section 25 of the Constitution, and persons of those races cannot therefore be reckoned for electoral purposes as people of the Commonwealth. This decision affects Queensland, South Australia, and Western Australia only, as the laws in force in New South Wales, Victoria, and Tasmania do not exclude "all persons of any specified race."

The persons disqualified under the various State Acts are the aboriginal natives of India, China, and the South Sea Islands by Queensland; the aboriginal natives of Asia and Africa, and persons of half-blood, by Western Australia; and the immigrants under the "Indian Immigration Act, 1882," in the Northern Territory of South Australia.

In establishing a quota it will be necessary, therefore, to exclude from consideration the aliens disqualified by state electoral laws, and, making this exclusion, the population of the Commonwealth on the 30th June, 1904, was 3,925,685 persons, distributed as follows :—

State.	Population, 30th June, 1904, exclusive of Aborigines.	Aliens, Disqualified by State Electoral Acts.	Population, excluding Aborigines and Aliens.	Number of Representa- tives.
New South Wales.....	1,441,441	.....	1,441,441	26·4
Victoria .....	1,206,098	.....	1,206,098	22·1
Queensland .....	519,948	18,038	501,910	9·2
South Australia.....	369,045	2,805	366,240	6·7
Western Australia .....	238,010	5,963	232,047	4·3
Tasmania .....	177,949	.....	177,949	3·3
Total .....	3,952,491	26,806	3,925,685	72·0

A quota was therefore 54,523, and the number of members to which the various states are entitled is—

New South Wales .....	26	Western Australia .....	5
Victoria .....	22	Tasmania .....	5
Queensland .....	9		
South Australia .....	7		74

The number of aliens set down as disqualified in Western Australia is in excess of the total coloured aliens in that state, as shown in the table on page 172. The figures for that state, given above, however, are furnished on the authority of the Statistician of Western Australia.

The present representation of the various states in the House of Representatives gives Victoria twenty-three members instead of twenty-two as shown in the foregoing statement—that is to say, an excess of one member. The figures quoted in the foregoing table are those published by each Statistician in regard to his own state. It is, however, questionable whether, before changing the representation of any state, the matter should not be delayed until a general check can be placed upon the returns relating to the migration of the population by sea. Such a check will be obtainable early in 1905, when the statements of immigration to and emigration from the Commonwealth in regard to places outside Australia will be published by the Customs Department, which has now undertaken the compilation of the necessary returns. At present the migration into each state is taken irrespective of the other states of the Commonwealth. The Customs returns will deal with the Commonwealth as a whole, and a more exact statement will, therefore, be available than can be arrived at from the returns of the different state offices. In any case, it would seem desirable that the representation

of the states should not depend upon mere estimates of population, however carefully such estimates may have been made. A more scientific basis of representation would doubtless be obtained from a census taken under the authority of the Commonwealth; and this, in itself, forms a strong argument in favour of a quinquennial enumeration of the population.

Towards the close of 1902, a difficulty arose in connection with granting permission to enter the Commonwealth to six operatives who had been brought out from England under contract to labour in a hat factory at Sydney. The Immigration Restriction Act expressly forbids the introduction of immigrants under contract to perform manual labour in the Commonwealth, unless it can be shown that such persons possess special qualifications required in the Commonwealth. As soon as a declaration was made to the effect that the men were specially skilled, they were permitted to land. The incident aroused a good deal of angry comment at the time, but it is clear that the Federal authorities simply complied with the law in detaining the operatives on board ship until the necessary declaration was forthcoming.

In view of the senatorial elections falling due at the close of 1903, and consequent on the extension of the Commonwealth franchise to all adults, the work of re-adjustment of the various Federal electorates was vigorously pushed forward. When the returns were published early in 1903, it was found that there were marked discrepancies in some districts between the number of electors shown and the persons of voting age as recorded at the census. Special efforts were therefore made to ensure the enrolment of all persons qualified to vote, and the rolls, as finally compiled, accounted for all but a very small proportion of those entitled to the suffrage.

The first session of the first Federal Parliament concluded its labours on the 10th October, 1902, after a period of activity lasting seventeen months. The second session opened on the 26th May, 1903. Attention was at once devoted to the passage of a Judiciary Bill and a Sugar Bonus Bill. The need for the former measure had already been made apparent, for early in April a decision given by the Chief Justice of Victoria impugned the validity of the Customs Act, while just previously the Supreme Court of New South Wales had denied the power of the Commonwealth to tax State Government imports. "The Constitution," as has been pointed out, "is in effect a deed of national partnership between the States, and until a Federal Court is established there exists no authority competent to settle its true meaning where differences take place as to its interpretation." The Government showed its earnestness in the matter by introducing the Judiciary Bill on the 26th May, while the first reading of the High Court Procedure Bill took place on the 9th June.

The question of the division of cost of the excise rebate of £2 per ton granted to Australian sugar planters who employ white labour occupied the attention of the Cabinet in the early months of 1903. It was anticipated when the Bill was passed that a fair division of the rebate would

fall to the share of each state, but the system broke down owing to the large importation of foreign sugar into Victoria and South Australia, which consequently consumed little white-grown Australian sugar, and it was found that Queensland and New South Wales, the sugar producing states, had to bear the brunt of the payment. Both of these states urged the necessity for treating the payment as a bonus, and charging it to all the States in proportion to population. This course eventually was adopted, and the Sugar Rebate Abolition Bill was presented and read the first time on the 10th June, and the Sugar Bonus Bill was also introduced on the same date.

On the 12th June the Report of the Select Committee on Commonwealth Coinage, which was ordered to be printed on the 4th April, 1902, was presented to Parliament, and a motion for its adoption was proposed. The Committee recommended that the Commonwealth should have its own silver coinage with the profits arising therefrom, and in addition proposed the introduction of a decimal system. Under this system the sovereign, half-sovereign, florin, shilling, and sixpence were to be retained, but provision was made for four new coins—a mixed coin equal to a tenth of a florin (2·4d.), and three bronze coins, equal respectively to 0·96d., 0·48d., and 0·24d. The question of reform in the coinage has not evoked widespread interest, but the useful labours of the Committee will sooner or later be recognised.

Royal assent to the Sugar Bounty Bill and the Sugar Rebate Abolition Bill was reported on the 31st July, and on the 26th August following the Judiciary Bill became law. In consequence of the retirement of Mr. Kingston from the portfolio of Trade and Customs on the 24th July some rearrangement of the Cabinet became necessary. Sir William Lyne took over the administration of the Customs Department on the 11th August, and Sir John Forrest assumed the direction of the Department of Home Affairs on the same date. On the 10th August the Hon. J. G. Drake accepted the portfolio of Minister of Defence, and the portfolio of Postmaster-General was filled by the appointment of the Hon. Sir P. O. Fysh. On the 18th August Mr. G. H. Reid, leader of the Opposition, resigned his seat in the House of Representatives as a protest against the action of the Government in connection with the re-arrangement of the Federal electorates. Early in the following month Mr Reid was re-elected, a remarkable feature of the election contest being that out of a total of 13,000 electors on the rolls in the East Sydney division, only about 2,000 took the trouble to record their votes.

On the 24th September, 1903, it was announced in the House of Representatives that the Premier, Sir Edmund Barton, had tendered his resignation, and that the Governor-General had called upon Mr. Deakin to undertake the task of re-arranging the Ministry. The new administration comprised the following members:—Minister for External Affairs, Hon. Alfred Deakin; Attorney-General, Hon. James George Drake; Minister for Home Affairs, Right Hon. Sir John

Forrest, P.C., G.C.M.G.; Treasurer, Right Hon. Sir George Turner, P.C., K.C.M.G.; Minister of Trade and Customs, Hon. Sir William John Lyne, K.C.M.G.; Minister of Defence, Hon. Austin Chapman; Postmaster-General, Hon. Sir Philip Oakley Fysh, K.C.M.G.; Vice-President of Executive Council, Hon. Thomas Playford. On the same day it was announced that Sir S. W. Griffith had accepted the position of Chief Justice of the Federal High Court, while Sir Edmund Barton and Mr. R. E. O'Connor had agreed to accept positions on the High Court Bench. The first sitting of the newly-constituted Court was held in Melbourne on the 7th October.

It was hoped that the question of selecting a site for the Federal capital would have been disposed of during the session of 1903. The House of Representatives favoured Tumut as the site, while the Senate selected Bombala, a bill introduced by the Government to deal with the matter being allowed to lapse. Further consideration was given to the question by the House of Representatives in August, 1904, when Dalgety was selected as the site, the choice being ratified by the Senate. The proposed capital area is situated near Bombala, in the south-eastern district of New South Wales.

Prior to the formal prorogation on the 22nd October, 1903, assent was given to several important legislative enactments. The Defence Act provides for a uniform system of defence for the Commonwealth, which it is hoped will increase the efficiency of the forces, while avoiding unnecessary expense; and the Patents Act enables inventors to secure protection for their inventions throughout the Commonwealth with the minimum of expense and trouble. Under the provisions of the "Naturalisation Act of 1903," which was assented to on the 13th October, the right of issuing certificates of naturalisation is exclusively vested in the government of the Commonwealth, and after the commencement of this Act no certificate of naturalisation or letters of naturalisation issued under any state Act shall have any effect.

Parliament was dissolved on the 24th November, and the elections of members of the House of Representatives and of Senators to replace those who retired in accordance with the terms of the Constitution Act, took place on the 16th December. The following table shows the number of electors on the roll, together with the number and proportion of those who recorded their votes at the elections in each state. The first table refers to the Senate.

State.	Electors enrolled.			Votes recorded.				Percentage of Votes to Electors.
	Males.	Females.	Total.	Males.	Females.	Total.	Informal.	
New South Wales ..	300,235	326,764	627,049	189,877	134,437	324,364	15,796	47.21
Victoria ..	302,089	310,448	612,472	171,829	141,648	313,487	7,093	51.18
Queensland ..	127,914	99,166	227,080	79,938	44,569	124,507	4,612	54.83
South Australia ..	55,947	81,828	137,775	35,786	19,049	54,786	1,209	32.65
Western Australia ..	74,754	42,188	116,942	26,878	6,370	33,148	2,001	23.36
Tasmania ..	43,515	33,753	82,268	23,729	12,292	37,021	1,441	45.00
Commonwealth ..	994,484	899,192	1,893,586	527,997	359,315	887,312	32,061	46.86

Similar information regarding the elections in contested districts for the House of Representatives will be found in the table below :—

State.	Electors enrolled.			Votes recorded.				Percentage.
	Males.	Females.	Total.	Males.	Females.	Total.	Informal.	
New South Wales ..	305,254	274,763	578,017	164,133	118,331	282,514	7,334	48·68
Victoria .....	241,134	247,180	488,223	142,460	130,329	262,790	4,818	53·83
Queensland .....	114,550	33,375	202,925	74,042	41,680	115,731	3,087	57·03
South Australia .....	23,866	25,789	49,655	12,304	7,723	20,122	542	40·53
Western Australia ..	41,500	23,324	64,824	16,824	4,409	21,233	1,251	30·41
Tasmania .....	43,515	33,753	82,268	23,729	13,294	37,015	1,164	44·99
Commonwealth..	767,809	703,093	1,470,902	433,582	305,830	739,402	18,666	50·20

The elections were contested in 22 divisions in New South Wales, 18 in Victoria, 8 in Queensland, 2 in South Australia, 3 in Western Australia, and 5 divisions in Tasmania.

It will be seen from the foregoing tables that the proportion of votes cast for the Senate was about 47 per cent. of the total enrolment, the percentage varying from 28 per cent. in Western Australia to 55 per cent. in Queensland, these two states also showing the lowest and highest proportions respectively at the election of representatives. If the informal votes, which are included in the totals in each state, be excluded, the proportions for all the states will be still lower. The figures point to a remarkable degree of apathy on the part of a large proportion of the population with respect to the exercise of the franchise, and it would appear as if the value placed on the privilege of voting varied in the different states. It is not possible, however, to draw any hard and fast inference from the above returns, as the proportions are liable to be affected by various causes, such as weather conditions, accessibility of polling places, and other local influences. The proportion of women voting in all the states was remarkably small, the lowest percentage being shown by Western Australia, where only 14·9 per cent. of the female electors voted for senators, and 18·5 per cent. for representatives. In South Australia, also, the proportions were low, 23·3 per cent. voting for senators and only 20 per cent. for representatives. In Tasmania, only 34 per cent. of the women electors voted. Victoria shows the highest percentages, viz. : 45·6 for senators and 48·7 per cent. for representatives. For Queensland the figures were, 44·9 per cent. and 47·1 per cent. ; and for New South Wales, 41·2 and 43·1 per cent., the average for the Commonwealth being 40 per cent. for senators and 42·1 for representatives. The above figures show that the women in the Commonwealth care less for the privilege of voting than do their sisters in New Zealand, where nearly 75 per cent. of the female electors voted at the election in 1902.

The formal swearing-in of Lord Northcote, the new Governor-General, took place on the 21st January, 1904, the appointment of this distinguished Imperial representative being hailed with universal satisfaction

in all the states of the union. In the following month the Commonwealth lost the services of one of its ablest advisers by the death of Sir Edward Braddon, author of the popularly-termed "Braddon Blot" in the financial provisions of the Constitution. Despite the adverse criticisms from time to time levelled against this clause, the fact remains that no attempt has yet been made to devise any other scheme which will ensure the solvency of the states, having regard to the fact that the principal sources of their revenue are under the federal control. Moreover, as is clearly indicated in another part of this work, the unfortunate financial condition of some of the states at the present time is in no way due to the operation of this portion of the Federal Constitution.

When the new Parliament assembled on the 2nd March, it was seen that the position of the Ministry was extremely critical, the House being divided into three parties of almost equal strength. The first measure brought in was the Arbitration and Conciliation Bill, and the Government found itself immediately involved in difficulties. Prior to leaving the Cabinet, Sir Edmund Barton had emphatically declared against any proposal to include state servants within the scope of an Arbitration Bill, and the measure introduced by Mr. Deakin differed little from that dropped in the preceding session. A Navigation Bill was also circulated, containing as many as 429 clauses, the most controversial of which aimed at imposing Australian rates of wages on all shipping trading to Australian waters, but exempted British mail steamers from the common rule between the ports of Fremantle and Adelaide until the completion of the proposed Transcontinental railway. It was on the Arbitration Bill, however, that the Government suffered defeat, Mr. Fisher proposing an amendment aiming at the inclusion of public servants within the scope of the Bill. This proposal was carried on the 21st April, and the Ministry thereupon resigned office. Mr. J. C. Watson was then sent for, and succeeded in forming an administration, drawn principally from the ranks of the Labour Party, and constituted as follows:—Treasurer, Hon. J. C. Watson; Minister of External Affairs, Hon. W. M. Hughes; Attorney-General, Hon. H. B. Higgins, K.O.; Minister of Home Affairs, Hon. E. L. Batchelor; Minister of Trade and Customs, Hon. A. Fisher; Minister of Defence, Hon. A. Dawson; Postmaster-General, Hon. H. Mahon; Vice-President of Executive Council, Hon. G. McGregor. This Ministry was sworn in on the 27th April, and Parliament adjourned for three weeks to give the new ministers time to formulate their policy, which was announced both to the Senate and the Representatives, on the 18th May. The chief points in the Ministerial statement were as follows: The Arbitration Bill was to be taken up at the stage where it was left by the preceding Government, but with certain important amendments. Of these the principal were, the appointment of a Judge of the Supreme Court as Chairman of the Board, the appointment by the parties in dispute of assessors, who were to sit with the Judge, and the inclusion within the scope of the Bill of all industrial servants of the Commonwealth or of

a state. A Bill to determine the site of the Capital was also to be introduced. Mention was made of measures dealing with the electoral system, trade-marks, and the proposed transcontinental railway scheme. Legislation in respect to quarantine was provided for; while, as regards the Navigation Bill, it was stated that the Government intended to appoint a Royal Commission to deal with the matter. Reference was also made to a proposal to initiate a scheme of Commonwealth old age pensions. In addition to the foregoing the Prime Minister outlined the Government's intentions respecting various other matters of federal concern. On the 12th August, the Ministry was defeated on the re-committal of certain clauses of the Arbitration Bill. Mr. McCay, one of the Victorian section of the Opposition, proposed to except from the re-committal clause 48, which required a majority of persons employed in an industry to approve of it before preference to unionists could be granted. The Government proposed, in place of a majority, to substitute a number substantially representative of the industry in numbers and commerce, and staked its existence on the issue, the voting for the Government being 34 as against 36. The Premier stated his intention of applying for a dissolution, but this was not granted; and the task of forming a new administration was entrusted to the Right Hon. G. H. Reid.

Mr. Reid's Government was constituted as follows:—Prime Minister and Minister for External Affairs, Right Hon. G. H. Reid; Minister of Customs, Hon. A. McLean; Attorney-General, Hon. Sir J. H. Symon; Treasurer, Right Hon. Sir G. Turner; Minister for Home Affairs, Hon. D. Thomson; Minister for Defence, Hon. J. W. McCay; Postmaster-General, Hon. S. Smith; Vice-President of Executive Council, Hon. J. G. Drake. The Right Hon. G. H. Reid's administration dates from the 18th August. In announcing the Government the Premier stated that he had invited Sir George Turner to join with him on terms of perfect equality, but owing to Sir George Turner's illness the position of joint leader was offered to and accepted by the Hon. A. McLean. The first session of the Reid-McLean administration lasted from the 18th August to the 15th December, 1904, Parliament being prorogued on the latter date until the 21st January, 1905. During this short session the Defence Act and the Conciliation and Arbitration Act were passed, in addition to the Bill determining on Dalgely as the site of the federal capital. One of the last acts of the Government prior to prorogation was the appointment of a Royal Commission to inquire into the working of the Customs Tariff and its effect on Australian industries.



## CONSTITUTION OF THE COMMONWEALTH.

**W**HEREAS the people of New South Wales, Victoria, South Australia, Queensland, and Tasmania humbly relying on the blessing of Almighty God, have agreed to unite in one indissoluble Federal Commonwealth under the Crown of the United Kingdom of Great Britain and Ireland, and under the Constitution hereby established :

And whereas it is expedient to provide for the admission into the Commonwealth of other Australasian Colonies and possessions of the Queen :

Be it therefore enacted by the Queen's Most Excellent Majesty, by and with the advice and consent of the Lords Spiritual and Temporal, and Commons, in this present Parliament assembled, and by the authority of the same, as follows :—

1. This Act may be cited as "The Commonwealth of Australia Constitution Act."

2. The provisions of this Act referring to the Queen shall extend to Her Majesty's heirs and successors in the sovereignty of the United Kingdom.

3. It shall be lawful for the Queen, with the advice of the Privy Council, to declare by Proclamation that, on and after a day therein appointed, not being later than one year after the passing of this Act, the people of New South Wales, Victoria, South Australia, Queensland, and Tasmania, and also, if Her Majesty is satisfied that the people of Western Australia have agreed thereto, of Western Australia, shall be united in a Federal Commonwealth under the name of "The Commonwealth of Australia." But the Queen may, at any time after the Proclamation, appoint a Governor-General for the Commonwealth.

4. The Commonwealth shall be established, and the Constitution of the Commonwealth shall take effect on and after the day so appointed. But the Parliaments of the several Colonies may at any time after the passing of this Act make any such laws, to come into operation on the day so appointed, as they might have made if the Constitution had taken effect at the passing of this Act.

5. This Act, and all laws made by the Parliament of the Commonwealth under the Constitution, shall be binding on the Courts, Judges, and people of every State, and of every part of the Commonwealth, notwithstanding anything in the laws of any State ; and the laws of the Commonwealth shall be in force on all British ships, the Queen's ships of war excepted, whose first port of clearance and whose port of destination are in the Commonwealth.

6. "The Commonwealth" shall mean the Commonwealth of Australia as established under this Act.

"The States" shall mean such of the Colonies of New South Wales, New Zealand, Queensland, Tasmania, Victoria, Western Australia, and South Australia, including the Northern Territory of South Australia, as for the time being are parts of the Commonwealth, and such Colonies or Territories as may be admitted into or established by the Commonwealth as States; and each of such parts of the Commonwealth shall be called a "State."

"Original States" shall mean such States as are parts of the Commonwealth at its establishment.

7. The Federal Council of Australasia Act, 1885, is hereby repealed, but so as not to affect any laws passed by the Federal Council of Australasia and in force at the establishment of the Commonwealth.

Any such law may be repealed as to any State by The Parliament of the Commonwealth, or as to any colony not being a State by The Parliament thereof.

8. After the passing of this Act the Colonial Boundaries Act, 1895, shall not apply to any colony which becomes a State of the Commonwealth; but the Commonwealth shall be taken to be a self-governing colony for the purposes of that Act.

9. The Constitution of the Commonwealth shall be as follows:—

## CHAPTER I.

### THE PARLIAMENT.

#### *Part I.—General.*

1. The legislative power of the Commonwealth shall be vested in a Federal Parliament, which shall consist of the Queen, a Senate, and a House of Representatives, and which is hereinafter called "The Parliament," or "The Parliament of the Commonwealth."

2. A Governor-General appointed by the Queen shall be Her Majesty's representative in the Commonwealth, and shall have and may exercise in the Commonwealth during the Queen's pleasure, but subject to this Constitution, such powers and functions of the Queen as Her Majesty may be pleased to assign to him.

3. There shall be payable to the Queen out of the Consolidated Revenue Fund of the Commonwealth, for the salary of the Governor-General, an annual sum which, until the Parliament otherwise provides, shall be ten thousand pounds.

The salary of a Governor-General shall not be altered during his continuance in office.

4. The provisions of this Constitution relating to the Governor-General extend and apply to the Governor-General for the time being, or such person as the Queen may appoint to administer the Government of the Commonwealth; but no such person shall be entitled to receive any salary from the Commonwealth in respect of any other office during his administration of the Government of the Commonwealth.

5. The Governor-General may appoint such times for holding the sessions of the Parliament as he thinks fit, and may also from time to

time, by Proclamation or otherwise, prorogue The Parliament, and may in like manner dissolve the House of Representatives.

After any general election The Parliament shall be summoned to meet not later than thirty days after the day appointed for the return of the writs.

The Parliament shall be summoned to meet not later than six months after the establishment of the Commonwealth.

6. There shall be a session of The Parliament once at least in every year, so that twelve months shall not intervene between the last sitting of The Parliament in one session and its first sitting in the next session.

*Part II.—The Senate.*

7. The Senate shall be composed of senators for each State, directly chosen by the people of the State, voting, until The Parliament otherwise provides, as one electorate.

But until The Parliament of the Commonwealth otherwise provides, the Parliament of the State of Queensland, if that State be an Original State, may make laws dividing the State into divisions and determining the number of senators to be chosen for each division, and in the absence of such provisions the State shall be one electorate.

Until The Parliament otherwise provides, there shall be six senators for each Original State. The Parliament may make laws increasing or diminishing the number of senators for each State, but so that equal representation of the several Original States shall be maintained and that no Original State shall have less than six senators.

The senators shall be chosen for a term of six years, and the names of the senators chosen for each State shall be certified by the Governor to the Governor-General.

8. The qualification of electors of senators shall be in each State that which is prescribed by this Constitution, or by the Parliament, as the qualification for electors of members of the House of Representatives, but in the choosing of senators each elector shall vote only once.

9. The Parliament of the Commonwealth may make laws prescribing the method of choosing senators, but so that the method shall be uniform for all the States. Subject to any such law, the Parliament of each State may make laws prescribing the method of choosing the senators for that State.

The Parliament of a State may make laws for determining the times and places of election of senators for the State.

10. Until The Parliament otherwise provides, but subject to this Constitution, the laws in force in each State, for the time being, relating to elections for the more numerous House of the Parliament of the State shall, as nearly as practicable, apply to elections of senators for the State.

11. The Senate may proceed to the despatch of business, notwithstanding the failure of any State to provide for its representation in the Senate.

12. The Governor of any State may cause writs to be issued for elections of senators for the State. In case of the dissolution of the Senate the writs shall be issued within ten days from the proclamation of such dissolution.

13. As soon as may be after the Senate first meets, and after each first meeting of the Senate following a dissolution thereof, the Senate shall divide the senators chosen for each State into two classes, as nearly equal in number as practicable; and the places of the senators of the first class shall become vacant at the expiration of the third year, and the places of those of the second class at the expiration of the sixth year from the beginning of their term of service; and afterwards the places of senators shall become vacant at the expiration of six years from the beginning of their term of service.

The election to fill vacant places shall be made in the year at the expiration of which the places are to become vacant.

For the purposes of this section the term of service of a senator shall be taken to begin on the first day of January following the day of his election, except in the cases of the first election and of the election next after any dissolution of the Senate, when it shall be taken to begin on the first day of January preceding the day of his election.

14. Whenever the number of senators for a State is increased or diminished, The Parliament of the Commonwealth may make such provision for the vacating of the places of senators for the State as it deems necessary to maintain regularity in the rotation.

15. If the place of a senator becomes vacant before the expiration of his term of service The Houses of Parliament of the State for which he was chosen shall, sitting and voting together, choose a person to hold the place until the expiration of the term, or until the election of a successor as hereinafter provided, whichever first happens. But if the Houses of Parliament of the State are not in session at the time when the vacancy is notified, the Governor of the State, with the advice of the Executive Council thereof, may appoint a person to hold the place until the expiration of fourteen days after the beginning of the next session of The Parliament of the State, or until the election of a successor, whichever first happens.

At the next general election of members of the House of Representatives, or at the next election of senators for the State, whichever first happens, a successor shall, if the term has not then expired, be chosen to hold the place from the date of his election until the expiration of the term.

The name of any senator so chosen or appointed shall be certified by the Governor of the State to the Governor-General.

16. The qualifications of a senator shall be the same as those of a member of the House of Representatives.

17. The Senate shall, before proceeding to the despatch of any other business choose a senator to be the President of the Senate; and as

often as the office of President becomes vacant the Senate shall again choose a senator to be the President.

The President shall cease to hold his office if he ceases to be a senator. He may be removed from office by a vote of the Senate, or he may resign his office or his seat by writing addressed to the Governor-General.

18. Before or during any absence of the President, the Senate may choose a senator to perform his duties in his absence.

19. A senator may, by writing, addressed to the President, or to the Governor-General if there is no President, or if the President is absent from the Commonwealth, resign his place, which thereupon shall become vacant.

20. The place of a senator shall become vacant if for two consecutive months of any session of The Parliament he, without the permission of the Senate, fails to attend the Senate.

21. Whenever a vacancy happens in the Senate, the President, or if there is no President, or if the President is absent from the Commonwealth, the Governor-General shall notify the same to the Governor of the State in the representation of which the vacancy has happened.

22. Until The Parliament otherwise provides, the presence of at least one-third of the whole number of the senators shall be necessary to constitute a meeting of the Senate for the exercise of its powers.

23. Questions arising in the Senate shall be determined by a majority of votes, and each senator shall have one vote. The President shall in all cases be entitled to a vote; and when the votes are equal the question shall pass in the negative.

### *Part III.—The House of Representatives.*

24. The House of Representatives shall be composed of members directly chosen by the people of the Commonwealth, and the number of such members shall be, as nearly as practicable, twice the number of the senators.

The number of members chosen in the several States shall be in proportion to the respective numbers of their people, and shall, until The Parliament otherwise provides, be determined, whenever necessary, in the following manner :—

- I. A quota shall be ascertained by dividing the number of the people of the Commonwealth as shown by the latest statistics of the Commonwealth, by twice the number of the senators.
- II. The number of members to be chosen in each State shall be determined by dividing the number of the people of the State, as shown by the latest statistics of the Commonwealth, by the quota; and if on such division there is a remainder greater than one-half of the quota, one more member shall be chosen in the State.

But notwithstanding anything in this section, five members at least shall be chosen in each Original State.

25. For the purposes of the last section, if by the law of any State all persons of any race are disqualified from voting at elections for the more numerous House of the Parliament of the State, then, in reckoning the number of the people of the State or of the Commonwealth, persons of that race resident in that State shall not be counted.

26. Notwithstanding anything in section 24, the number of members to be chosen in each State at the first election shall be as follows :—

New South Wales...	Twenty-three.	South Australia ...	Six.
Victoria ...	Twenty.	Tasmania ...	Five.
Queensland ...	Eight.		

Provided that if Western Australia is an Original State, the numbers shall be as follows :—

New South Wales...	Twenty-six.	South Australia ...	Seven.
Victoria ...	Twenty-three.	Western Australia...	Five.
Queensland ...	Nine.	Tasmania ...	Five.

27. Subject to this Constitution, The Parliament may make laws for increasing or diminishing the number of the members of the House of Representatives.

28. Every House of Representatives shall continue for three years from the first meeting of the House, and no longer, but may be sooner dissolved by the Governor-General.

29. Until the Parliament of The Commonwealth otherwise provides, the Parliament of any State may make laws for determining the divisions in each State for which members of the House of Representatives may be chosen, and the number of members to be chosen for each division. A division shall not be formed out of parts of different States.

In the absence of other provision, each State shall be one electorate.

30. Until The Parliament otherwise provides, the qualification of electors of members of the House of Representatives shall be in each State that which is prescribed by the law of the State as the qualification of electors of the more numerous House of the Parliament of the State ; but in the choosing of members each elector shall vote only once.

31. Until The Parliament otherwise provides, but subject to this Constitution, the laws in force in each State for the time being relating to elections for the more numerous House of The Parliament of the State shall, as nearly as practicable, apply to elections in the State of members of the House of Representatives.

32. The Governor-General in Council may cause writs to be issued for general elections of members of the House of Representatives.

After the first general election, the writs shall be issued within ten days from the expiry of a House of Representatives, or from the proclamation of a dissolution thereof.

33. Whenever a vacancy happens in the House of Representatives, the Speaker shall issue his writ for the election of a new member, or if there is no Speaker, or if he is absent from the Commonwealth, the Governor-General in Council may issue the writ.

34. Until The Parliament otherwise provides, the qualifications of a member of the House of Representatives shall be as follows :—

- i. He must be of the full age of twenty-one years, and must be an elector entitled to vote at the election of members of the House of Representatives, or a person qualified to become such elector, and must have been for three years at the least a resident within the limits of the Commonwealth as existing at the time when he is chosen :
- ii. He must be a subject of the Queen, either natural-born or for at least five years naturalised under a law of the United Kingdom, or of a Colony which has become or becomes a State, or of the Commonwealth, or of a State.

35. The House of Representatives shall, before proceeding to the despatch of any other business, choose a member to be the Speaker of the House, and as often as the office of Speaker becomes vacant the House shall again choose a member to be the Speaker.

The Speaker shall cease to hold his office if he ceases to be a member. He may be removed from office by a vote of the House, or he may resign his office or his seat by writing addressed to the Governor-General.

36. Before or during any absence of the Speaker, the House of Representatives may choose a member to perform his duties in his absence.

37. A member may by writing addressed to the Speaker, or to the Governor-General if there is no Speaker or if the Speaker is absent from the Commonwealth, resign his place, which thereupon shall become vacant.

38. The place of a member shall become vacant if for two consecutive months of any session of The Parliament he, without the permission of the House, fails to attend the House.

39. Until the Parliament otherwise provides, the presence of at least one-third of the whole number of the members of the House of Representatives shall be necessary to constitute a meeting of the House for the exercise of its powers.

40. Questions arising in the House of Representatives shall be determined by a majority of votes other than that of the Speaker. The Speaker shall not vote unless the numbers are equal, when he shall have a casting vote.

#### *Part IV.—Both Houses of the Parliament.*

41. No adult person who has or acquires a right to vote at elections for the more numerous House of the Parliament of a State, shall, while the right continues, be prevented by any law of the Commonwealth from voting at elections for either House of The Parliament of the Commonwealth.

42. Every senator and every member of the House of Representatives shall before taking his seat make and subscribe before the Governor-General, or some person authorised by him, an oath or affirmation of allegiance in the form set forth in the Schedule to this Constitution.





48. Until The Parliament otherwise provides, each senator and each member of the House of Representatives shall receive an allowance of Four Hundred Pounds a year, to be reckoned from the day on which he takes his seat.

49. The powers, privileges, and immunities of the Senate and of the House of Representatives, and of the members and the committees of each House shall be such as are declared by The Parliament, and until declared shall be those of the Commons House of Parliament of the United Kingdom, and of its members and committees, at the establishment of the Commonwealth.

50. Each House of The Parliament may make rules and orders with respect to—

- i. The mode in which its powers, privileges, and immunities may be exercised and upheld :
- ii. The order and conduct of its business and proceedings either separately or jointly with the other House.

*Part V.—Powers of The Parliament.*

51. The Parliament shall, subject to this Constitution, have power to make laws for the peace, order, and good government of the Commonwealth, with respect to :—

- i. Trade and commerce with other countries, and among the States:
- ii. Taxation ; but so as not to discriminate between States or parts of States :
- iii. Bounties on the production or export of goods, but so that such bounties shall be uniform throughout the Commonwealth :
- iv. Borrowing money on the public credit of the Commonwealth :
- v. Postal, telegraphic, telephonic, and other like services :
- vi. The naval and military defence of the Commonwealth and of the several States, and the control of the forces to execute and maintain the laws of the Commonwealth :
- vii. Light-houses, light-ships, beacons, and buoys :
- viii. Astronomical and meteorological observations :
- ix. Quarantine :
- x. Fisheries in Australian waters beyond territorial limits :
- xi. Census and statistics :
- xii. Currency, coinage, and legal tender :
- xiii. Banking other than State banking ; also State banking extending beyond the limits of the State concerned, the incorporation of banks, and the issue of paper money :
- xiv. Insurance, other than State Insurance ; also State Insurance extending beyond the limits of the State concerned :
- xv. Weights and measures :
- xvi. Bills of exchange and promissory notes :
- xvii. Bankruptcy and insolvency :
- xviii. Copyrights, patents of inventions and designs, and trade-marks :

- XIX. Naturalization and aliens :**
- XX. Foreign corporations, and trading or financial corporations formed within the limits of the Commonwealth :**
- XXI. Marriage :**
- XXII. Divorce and matrimonial causes ; and in relation thereto, parental rights, and the custody and guardianship of infants :**
- XXIII. Invalid and old-age pensions :**
- XXIV. The service and execution throughout the Commonwealth of the civil and criminal process and the judgments of the courts of the States :**
- XXV. The recognition throughout the Commonwealth of the laws, the public acts and records, and the judicial proceedings of the States :**
- XXVI. The people of any race, other than the aboriginal race in any State, for whom it is deemed necessary to make special laws :**
- XXVII. Immigration and emigration :**
- XXVIII. The influx of criminals :**
- XXIX. External affairs :**
- XXX. The relations of the Commonwealth with the islands of the Pacific :**
- XXXI. The acquisition of property on just terms from any State or person for any purpose in respect of which The Parliament has power to make laws :**
- XXXII. The control of railways with respect to transport for the naval and military purposes of the Commonwealth :**
- XXXIII. The acquisition, with the consent of a State, of any railways of the State on terms arranged between the Commonwealth and the State :**
- XXXIV. Railway construction and extension in any State with the consent of that State :**
- XXXV. Conciliation and arbitration for the prevention and settlement of industrial disputes extending beyond the limits of any one State :**
- XXXVI. Matters in respect of which this Constitution makes provision until The Parliament otherwise provides :**
- XXXVII. Matters referred to the Parliament of the Commonwealth by the Parliament or Parliaments of any State or States, but so that the law shall extend only to States by whose Parliament the matter is referred, or which afterwards adopt the law :**
- XXXVIII. The exercise within the Commonwealth, at the request or with the concurrence of the Parliaments of all the States directly concerned, of any power which can at the establishment of this Constitution be exercised only by the Parliament of the United Kingdom or by the Federal Council of Australasia :**

**XXIX.** Matters incidental to the execution of any power vested by this Constitution in the Parliament or in either House thereof, or in the Government of the Commonwealth, or in the Federal Judicature, or in any department or officer of the Commonwealth.

**52.** The Parliament shall, subject to this Constitution, have exclusive power to make laws for the peace, order, and good government of the Commonwealth with respect to—

- i. The seat of Government of the Commonwealth, and all places acquired by the Commonwealth for public purposes :
- ii. Matters relating to any department of the public service the control of which is by this Constitution transferred to the Executive Government of the Commonwealth :
- iii. Other matters declared by this Constitution to be within the exclusive power of The Parliament.

**53.** Proposed laws appropriating revenue or moneys, or imposing taxation, shall not originate in the Senate. But a proposed law shall not be taken to appropriate revenue or moneys, or to impose taxation, by reason only of its containing provisions for the imposition or appropriation of fines or other pecuniary penalties, or for the demand or payment or appropriation of fees for licenses, or fees for services under the proposed law.

The Senate may not amend proposed laws imposing taxation, or proposed laws appropriating revenue or moneys for the ordinary annual services of the Government.

The Senate may not amend any proposed law so as to increase any proposed charge or burden on the people.

The Senate may at any stage return to the House of Representatives any proposed law which the Senate may not amend, requesting, by message, the omission or amendment of any items or provisions therein. And the House of Representatives may if it thinks fit make any of such omissions or amendments, with or without modifications.

Except as provided in this section, the Senate shall have equal power with the House of Representatives in respect of all proposed laws.

**54.** The proposed law which appropriates revenue or moneys for the ordinary annual services of the Government shall deal only with such appropriations.

**55.** Laws imposing taxation shall deal only with the imposition of taxation, and any provision therein dealing with any other matter shall be of no effect.

Laws imposing taxation, except laws imposing duties of customs or of excise, shall deal with one subject of taxation only ; but laws imposing duties of customs shall deal with duties of customs only, and laws imposing duties of excise shall deal with duties of excise only.

**56.** A vote, resolution, or proposed law for the appropriation of revenue or moneys shall not be passed unless the purpose of the

appropriation has in the same session been recommended by message of the Governor-General to the House in which the proposal originated.

57. If the House of Representatives passes any proposed law and the Senate rejects or fails to pass it, or passes it with amendments to which the House of Representatives will not agree, and if after an interval of three months the House of Representatives, in the same or the next session, again passes the proposed law with or without any amendments which have been made, suggested, or agreed to by the Senate, and the Senate rejects or fails to pass it, or passes it with amendments to which the House of Representatives will not agree, the Governor-General may dissolve the Senate and the House of Representatives simultaneously. But such dissolution shall not take place within six months before the date of the expiry of the House of Representatives by effluxion of time.

If after such dissolution the House of Representatives again passes the proposed law with or without any amendments which have been made, suggested, or agreed to by the Senate, and the Senate rejects or fails to pass it, or passes it with amendments to which the House of Representatives will not agree, the Governor-General may convene a joint sitting of the members of the Senate and of the House of Representatives.

The members present at the joint sitting may deliberate and shall vote together upon the proposed law as last proposed by the House of Representatives, and upon amendments, if any, which have been made therein by one House and not agreed to by the other, and any such amendments which are affirmed by an absolute majority of the total number of the members of the Senate and House of Representatives shall be taken to have been carried, and if the proposed law, with the amendments, if any, so carried is affirmed by an absolute majority of the total number of the members of the Senate and the House of Representatives it shall be taken to have been duly passed by both Houses of The Parliament, and shall be presented to the Governor-General for the Queen's assent.

58. When a proposed law passed by both Houses of The Parliament is presented to the Governor-General for the Queen's assent, he shall declare, according to his discretion, but subject to this Constitution, that he assents in the Queen's name, or that he withholds assent, or that he reserves the law for the Queen's pleasure.

The Governor-General may return to the House in which it originated any proposed law so presented to him, may transmit therewith any amendments which he may recommend, and the Houses may deal with the recommendations.

59. The Queen may disallow any law within one year from the Governor-General's assent, and such disallowance on being made known by the Governor-General, by speech or message to each of the Houses of the Parliament, or by Proclamation, shall annul the law from the day when the disallowance is so made known.

60. A proposed law reserved for the Queen's pleasure shall not have any force unless and until within two years from the day on which it was presented to the Governor-General for the Queen's assent the Governor-General makes known, by speech or message to each of the Houses of The Parliament, or by Proclamation, that it has received the Queen's assent.

## CHAPTER II.

### THE EXECUTIVE GOVERNMENT.

61. The Executive power of the Commonwealth is vested in the Queen, and is exercisable by the Governor-General as the Queen's representative, and extends to the execution and maintenance of this Constitution, and of the laws of the Commonwealth.

62. There shall be a Federal Executive Council to advise the Governor-General in the government of the Commonwealth, and the members of the Council shall be chosen and summoned by the Governor-General and sworn as Executive Councillors, and shall hold office during his pleasure.

63. The provisions of this Constitution referring to the Governor-General in Council shall be construed as referring to the Governor-General acting with the advice of the Federal Executive Council.

64. The Governor-General may appoint officers to administer such Departments of State of the Commonwealth as the Governor-General in Council may establish.

Such officers shall hold office during the pleasure of the Governor-General. They shall be members of the Federal Executive Council, and shall be the Queen's Ministers of State for the Commonwealth.

After the first general election no Minister of State shall hold office for a longer period than three months unless he is or becomes a senator or a member of the House of Representatives.

65. Until The Parliament otherwise provides, the Ministers of State shall not exceed seven in number, and shall hold such offices as The Parliament prescribes, or, in the absence of provision, as the Governor-General directs.

66. There shall be payable to the Queen, out of the Consolidated Revenue Fund of the Commonwealth, for the salaries of Ministers of State, an annual sum which, until The Parliament otherwise provides, shall not exceed twelve thousand pounds a year.

67. Until The Parliament otherwise provides, the appointment and removal of all other officers of the Executive Government of the Commonwealth shall be vested in the Governor-General in Council, unless the appointment is delegated by the Governor-General in Council or by law of the Commonwealth to some other authority.

68. The command in chief of the naval and military forces of the Commonwealth is vested in the Governor-General as the Queen's representative.

69. On a date or dates to be proclaimed by the Governor-General after the establishment of the Commonwealth, the following Departments of the public service in each State shall become transferred to the Commonwealth :—

Posts, telegraphs, and telephones :

Naval and military defence :

Light-houses, light-ships, beacons, and buoys :

Quarantine.

But the Departments of customs and of excise in each State shall become transferred to the Commonwealth on its establishment.

70. In respect of matters which, under this Constitution, pass to the Executive Government of the Commonwealth, all powers and functions which at the establishment of the Commonwealth are vested in the Governor of a colony, or in the Governor of a colony with the advice of his Executive Council, or in any authority of a colony, shall vest in the Governor-General, or in the Governor-General in Council, or in the authority exercising similar powers under the Commonwealth, as the case requires.

### CHAPTER III.

#### THE JUDICATURE.

71. The judicial power of the Commonwealth shall be vested in a Federal Supreme Court, to be called the High Court of Australia, and in such other federal courts as The Parliament creates, and in such other courts as it invests with federal jurisdiction. The High Court shall consist of a Chief Justice, and so many other Justices, not less than two, as The Parliament prescribes.

72. The Justices of the High Court and of the other courts created by The Parliament

I. Shall be appointed by the Governor-General in Council :

II. Shall not be removed except by the Governor-General in Council, on an Address from both Houses of The Parliament in the same session praying for such removal on the ground of proved misbehaviour or incapacity :

III. Shall receive such remuneration as The Parliament may fix ; but the remuneration shall not be diminished during their continuance in office.

73. The High Court shall have jurisdiction, with such exceptions and subject to such regulations as The Parliament prescribes, to hear and determine appeals from all judgments, decrees, orders, and sentences :

I. Of any Justice or Justices exercising the original jurisdiction of the High Court :

II. Of any other federal court, or court exercising federal jurisdiction ; or of the Supreme Court of any State, or of any other court of any State from which at the establishment of the Commonwealth an appeal lies to the Queen in Council :

III. Of the Inter-State Commission, but as to questions of law only :

and the judgment of the High Court in all such cases shall be final and conclusive.

But no exception or regulation prescribed by The Parliament shall prevent the High Court from hearing and determining any appeal from the Supreme Court of a State in any matter in which at the establishment of the Commonwealth an appeal lies from such Supreme Court to the Queen in Council.

Until The Parliament otherwise provides, the conditions of and restrictions on appeals to the Queen in Council from the Supreme Courts of the several States shall be applicable to appeals from them to the High Court.

74. No appeal shall be permitted to the Queen in Council from a decision of the High Court upon any question, howsoever arising, as to the limits inter se of the Constitutional powers of the Commonwealth and those of any State or States, or as to the limits inter se of the Constitutional powers of any two or more States, unless the High Court shall certify that the question is one which ought to be determined by Her Majesty in Council.

The High Court may so certify if satisfied that for any special reason the certificate should be granted, and thereupon an appeal shall lie to Her Majesty in Council on the question without further leave.

Except as provided in this section, this Constitution shall not impair any right which the Queen may be pleased to exercise, by virtue of Her Royal Prerogative, to grant special leave of appeal from the High Court to Her Majesty in Council. The Parliament may make laws limiting the matters in which such leave may be asked, but proposed laws containing any such limitation shall be reserved by the Governor-General for Her Majesty's pleasure.

75. In all matters—

- I. Arising under any treaty :
- II. Affecting consuls, or other representatives of other countries :
- III. In which the Commonwealth, or a person suing or being sued on behalf of the Commonwealth, is a party :
- IV. Between States, or between residents of different States, or between a State and a resident of another State :
- V. In which a writ of mandamus or prohibition or an injunction is sought against an officer of the Commonwealth :

the High Court shall have original jurisdiction.

76. The Parliament may make laws conferring original jurisdiction on the High Court in any matter—

- I. Arising under this Constitution, or involving its interpretation :
- II. Arising under any laws made by The Parliament :
- III. Of admiralty and maritime jurisdiction :
- IV. Relating to the same subject-matter claimed under the laws of different States.

77. With respect to any of the matters mentioned in the last two sections, The Parliament may make laws—

- i. Defining the jurisdiction of any federal court other than the High Court :
- ii. Defining the extent to which the jurisdiction of any federal court shall be exclusive of that which belongs to or is vested in the courts of the States :
- iii. Investing any court of a State with federal jurisdiction.

78. The Parliament may make laws conferring rights to proceed against the Commonwealth or a State in respect of matters within the limits of the judicial power.

79. The federal jurisdiction of any court may be exercised by such number of judges as The Parliament prescribes.

80. The trial on indictment of any offence against any law of the Commonwealth shall be by jury, and every such trial shall be held in the State where the offence was committed, and if the offence was not committed within any State the trial shall be held at such place or places as The Parliament prescribes.

## CHAPTER IV.

### FINANCE AND TRADE.

81. All revenues or moneys raised or received by the Executive Government of the Commonwealth shall form one Consolidated Revenue Fund, to be appropriated for the purposes of the Commonwealth in the manner and subject to the charges and liabilities imposed by this Constitution.

82. The costs, charges, and expenses incident to the collection, management, and receipt of the Consolidated Revenue Fund shall form the first charge thereon ; and the revenue of the Commonwealth shall in the first instance be applied to the payment of the expenditure of the Commonwealth.

83. No money shall be drawn from the Treasury of the Commonwealth except under appropriation made by law.

But until the expiration of one month after the first meeting of The Parliament, the Governor-General in Council may draw from the Treasury and expend such moneys as may be necessary for the maintenance of any department transferred to the Commonwealth and for the holding of the first elections for The Parliament.

84. When any department of the public service of a State becomes transferred to the Commonwealth, all officers of the department shall become subject to the control of the Executive Government of the Commonwealth.

Any such officer who is not retained in the service of the Commonwealth shall, unless he is appointed to some other office of equal



emolument in the public service of the State, be entitled to receive from the State any pension, gratuity, or other compensation payable under the law of the State on the abolition of his office.

Any such officer who is retained in the service of the Commonwealth shall preserve all his existing and accruing rights, and shall be entitled to retire from office at the time, and on the pension or retiring allowance, which would be permitted by the law of the State if his services with the Commonwealth were a continuation of his service with the State. Such pension or retiring allowance shall be paid to him by the Commonwealth; but the State shall pay to the Commonwealth a part thereof, to be calculated on the proportion which his term of service with the State bears to his whole term of service, and for the purpose of the calculation his salary shall be taken to be that paid to him by the State at the time of the transfer.

Any officer who is, at the establishment of the Commonwealth, in the public service of a State, and who is, by consent of the Governor of the State with the advice of the Executive Council thereof, transferred to the public service of the Commonwealth, shall have the same rights as if he had been an officer of a department transferred to the Commonwealth and were retained in the service of the Commonwealth.

85. When any department of the public service of a State is transferred to the Commonwealth—

- i. All property of the State, of any kind, used exclusively in connection with the department, shall become vested in the Commonwealth; but, in the case of the departments controlling customs and excise and bounties, for such time only as the Governor-General in Council may declare to be necessary.
- ii. The Commonwealth may acquire any property of the State, of any kind, used, but not exclusively used, in connection with the department; the value thereof shall, if no agreement can be made, be ascertained in, as nearly as may be, the manner in which the value of land, or of an interest in land, taken by the State for public purposes, is ascertained under the law of the State in force at the establishment of the Commonwealth.
- iii. The Commonwealth shall compensate the State for the value of any property passing to the Commonwealth under this section; if no agreement can be made as to the mode of compensation, it shall be determined under laws to be made by The Parliament.
- iv. The Commonwealth shall, at the date of the transfer, assume the current obligations of the State in respect of the department transferred.

86. On the establishment of the Commonwealth, the collection and control of duties of customs and of excise, and the control of the payment of bounties, shall pass to the Executive Government of the Commonwealth.

87. During a period of ten years after the establishment of the Commonwealth, and thereafter until the Parliament otherwise provides, of the net revenue of the Commonwealth from duties of customs and of excise, not more than one-fourth shall be applied annually by the Commonwealth towards its expenditure.

The balance shall in accordance with this Constitution, be paid to the several States, or applied towards the payment of interest on debts of the several States taken over by the Commonwealth.

88. Uniform duties of customs shall be imposed within two years after the establishment of the Commonwealth.

89. Until the imposition of uniform duties of customs—

I. The Commonwealth shall credit to each State the revenues collected therein by the Commonwealth.

II. The Commonwealth shall debit to each State—

(a) the expenditure therein of the Commonwealth incurred solely for the maintenance or continuance, as at the time of transfer, of any department transferred from the State to the Commonwealth.

(b) The proportion of the State, according to the number of its people, in the other expenditure of the Commonwealth.

III. The Commonwealth shall pay to each State month by month the balance (if any) in favour of the State.

90. On the imposition of uniform duties of customs the power of the Parliament to impose duties of customs and of excise, and to grant bounties on the production or export of goods, shall become exclusive.

On the imposition of uniform duties of customs all laws of the several States imposing duties of customs or of excise, or offering bounties on the production or export of goods, shall cease to have effect; but any grant of or agreement for any such bounty lawfully made by or under the authority of the Government of any State shall be taken to be good if made before the thirtieth day of June, one thousand eight hundred and ninety-eight, and not otherwise.

91. Nothing in this Constitution prohibits a State from granting any aid to or bounty on mining for gold, silver, or other metals, nor from granting, with the consent of both Houses of the Parliament of the Commonwealth expressed by resolution, any aid to or bounty on the production or export of goods.

92. On the imposition of uniform duties of customs, trade, commerce, and intercourse among the States, whether by means of internal carriage or ocean navigation, shall be absolutely free.

But notwithstanding anything in this Constitution, goods imported before the imposition of uniform duties of customs into any State, or into any Colony which, whilst the goods remain therein, becomes a State, shall, on thence passing into another State within two years after

the imposition of such duties, be liable to any duty chargeable on the importation of such goods into the Commonwealth, less any duty paid in respect of the goods on their importation.

93. During the first five years after the imposition of uniform duties of customs, and thereafter until The Parliament otherwise provides :—

1. The duties of customs chargeable on goods imported into a State and afterwards passing into another State for consumption, and the duties of excise paid on goods produced or manufactured in a State and afterwards passing into another State for consumption, shall be taken to have been collected not in the former but in the latter State :
11. Subject to the last subsection, the Commonwealth shall credit revenue, debit expenditure, and pay balances to the several States as prescribed for the period preceding the imposition of uniform duties of customs.

94. After five years from the imposition of uniform duties of customs, The Parliament may provide, on such basis as it deems fair, for the monthly payment to the several States of all surplus revenue of the Commonwealth.

95. Notwithstanding anything in this Constitution, the Parliament of the State of Western Australia, if that State be an Original State, may, during the first five years after the imposition of uniform duties of customs, impose duties of customs on goods passing into that State, and not originally imported from beyond the limits of the Commonwealth ; and such duties shall be collected by the Commonwealth.

But any duty so imposed on any goods shall not exceed during the first of such years the duty chargeable on the goods under the law of Western Australia in force at the imposition of uniform duties, and shall not exceed during the second, third, fourth, and fifth of such years respectively, four-fifths, three-fifths, two-fifths, and one-fifth of such latter duty, and all duties imposed under this section shall cease at the expiration of the fifth year after the imposition of uniform duties.

If at any time during the five years the duty on any goods under this section is higher than the duty imposed by the Commonwealth on the importation of the like goods, then such higher duty shall be collected on the goods when imported into Western Australia from beyond the limits of the Commonwealth.

96. During a period of ten years after the establishment of the Commonwealth and thereafter until The Parliament otherwise provides, The Parliament may grant financial assistance to any State on such terms and conditions as The Parliament thinks fit.

97. Until the Parliament otherwise provides, the laws in force in any colony which has become or becomes a State with respect to the receipt of revenue and the expenditure of money on account of the Government of the colony, and the review and audit of such receipt and expenditure, shall apply to the receipt of revenue and the expenditure

of money on account of the Commonwealth in the State in the same manner as if the Commonwealth, or the Government, or an officer of the Commonwealth, were mentioned whenever the colony, or the Government, or an officer of the colony is mentioned.

98. The power of The Parliament to make laws with respect to trade and commerce extends to navigation and shipping, and to railways the property of any State.

99. The Commonwealth shall not, by any law or regulation of trade, commerce, or revenue, give preference to one State or any part thereof over another State or any part thereof.

100. The Commonwealth shall not, by any law or regulation of trade or commerce, abridge the right of a State or of the residents therein to the reasonable use of the waters of rivers for conservation or irrigation.

101. There shall be an Inter-State Commission, with such powers of adjudication and administration as The Parliament deems necessary for the execution and maintenance, within the Commonwealth, of the provisions of this Constitution relating to trade and commerce, and of all laws made thereunder.

102. The Parliament may by any law with respect to trade or commerce forbid, as to railways, any preference or discrimination by any State, or by any authority constituted under a State, if such preference or discrimination is undue and unreasonable, or unjust to any State: due regard being had to the financial responsibilities incurred by any State in connection with the construction and maintenance of its railways. But no preference or discrimination shall, within the meaning of this section, be taken to be undue and unreasonable, or unjust to any State, unless so adjudged by the Inter-State Commission.

103. The members of the Inter-State Commission—

- I. Shall be appointed by the Governor-General in Council :
- II. Shall hold office for seven years, but may be removed within that time by the Governor-General in Council, on an address from both Houses of the Parliament in the same Session praying for such removal on the ground of proved misbehaviour or incapacity :
- III. Shall receive such remuneration as The Parliament may fix ; but such remuneration shall not be diminished during their continuance in office.

104. Nothing in this Constitution shall render unlawful any rate for the carriage of goods upon a railway, the property of a State, if the rate is deemed by the Inter-State Commission to be necessary for the development of the territory of the State, and if the rate applies equally to goods within the State and to goods passing into the State from other States.

105. The Parliament may take over from the States their public debts as existing at the establishment of the Commonwealth, or a proportion thereof, according to the respective numbers of their people as

shown by the latest statistics of the Commonwealth, and may convert, renew, or consolidate such debts, or any part thereof; and the States shall indemnify the Commonwealth in respect of the debts taken over, and thereafter the interest payable in respect of the debts shall be deducted and retained from the portions of the surplus revenue of the Commonwealth payable to the several States, or if such surplus is insufficient, or if there is no surplus, then the deficiency or the whole amount shall be paid by the several States.

## CHAPTER V.

### THE STATES.

106. The Constitution of each State of the Commonwealth shall, subject to this Constitution, continue as at the establishment of the Commonwealth, or as at the admission or establishment of the State, as the case may be, until altered in accordance with the Constitution of the State.

107. Every power of the Parliament of a colony which has become or becomes a State, shall, unless it is by this Constitution exclusively vested in The Parliament of the Commonwealth or withdrawn from the Parliament of the State, continue as at the establishment of the Commonwealth, or as at the admission or establishment of the State, as the case may be.

108. Every law in force in a colony which has become or becomes a State, and relating to any matter within the powers of The Parliament of the Commonwealth, shall, subject to this Constitution, continue in force in the State; and until provision is made in that behalf by The Parliament of the Commonwealth, the Parliament of the State shall have such powers of alteration and of repeal in respect of any such law as the Parliament of the colony had until the colony became a State.

109. When a law of a State is inconsistent with a law of the Commonwealth, the latter shall prevail, and the former shall, to the extent of the inconsistency, be invalid.

110. The provisions of this Constitution relating to the Governor of a State extend and apply to the Governor for the time being of the State, or other chief executive officer or administrator of the government of the State.

111. The Parliament of a State may surrender any part of the State to the Commonwealth: and upon such surrender, and the acceptance thereof by the Commonwealth, such part of the State shall become subject to the exclusive jurisdiction of the Commonwealth.

112. After uniform duties of customs have been imposed, a State may levy on imports or exports, or on goods passing into or out of the State, such charges as may be necessary for executing the inspection laws of the State; but the net produce of all charges so levied shall be for the use of the Commonwealth; and any such inspection laws may be annulled by The Parliament of the Commonwealth.

113. All fermented, distilled, or other intoxicating liquids passing into any State or remaining therein for use, consumption, sale, or storage shall be subject to the laws of the State as if such liquids had been produced in the State.

114. A State shall not, without the consent of The Parliament of the Commonwealth, raise or maintain any naval or military force, or impose any tax on property of any kind belonging to the Commonwealth; nor shall the Commonwealth impose any tax on property of any kind belonging to a State.

115. A State shall not coin money, nor make anything but gold and silver coin a legal tender in payment of debts.

116. The Commonwealth shall not make any law for establishing any religion, or for imposing any religious observance, or for prohibiting the free exercise of any religion, and no religious test shall be required as a qualification for any office or public trust under the Commonwealth.

117. A subject of the Queen, resident in any State, shall not be subject in any other State to any disability or discrimination which would not be equally applicable to him if he were a subject of the Queen resident in such other State.

118. Full faith and credit shall be given, throughout the Commonwealth, to the laws, the public acts and records, and the judicial proceedings, of every State.

119. The Commonwealth shall protect every State against invasion and, on the application of the Executive Government of the State, against domestic violence.

120. Every State shall make provision for the detention in its prisons of persons accused or convicted of offences against the laws of the Commonwealth, and for the punishment of persons convicted of such offences, and the Parliament of the Commonwealth may make laws to give effect to this provision.

## CHAPTER VI.

### NEW STATES.

121. The Parliament may admit to the Commonwealth or establish new States, and may upon such admission or establishment make or impose such terms and conditions, including the extent of representation in either House of The Parliament, as it thinks fit.

122. The Parliament may make laws for the Government of any territory surrendered by any State to and accepted by the Commonwealth, or of any territory placed by the Queen under the authority of and accepted by the Commonwealth, or otherwise acquired by the Commonwealth, and may allow the representation of such territory in either House of the Parliament to the extent and on the terms which it thinks fit.

123. The Parliament of the Commonwealth may, with the consent of the Parliament of a State and the approval of the majority of the

electors of the State voting upon the question, increase, diminish, or otherwise alter the limits of the State, upon such terms and conditions as may be agreed on, and may, with the like consent, make provision respecting the effect and operation of any increase or diminution or alteration of territory in relation to any State affected.

124. A new State may be formed by separation of territory from a State, but only with the consent of the Parliament thereof, and a new State may be formed by the union of two or more States or parts of States, but only with the consent of the Parliaments of the States affected.

## CHAPTER VII.

### MISCELLANEOUS.

125. The seat of Government of the Commonwealth shall be determined by The Parliament and shall be within territory which shall have been granted to or acquired by the Commonwealth and shall be vested in and belong to the Commonwealth, and if New South Wales be an Original State shall be in that State, and be distant not less than one hundred miles from Sydney.

Such territory shall contain an area of not less than one hundred square miles, and such portion thereof as shall consist of Crown lands shall be granted to the Commonwealth without any payment therefor.

The Parliament shall sit at Melbourne until it meet at the seat of Government.

126. The Queen may authorise the Governor-General to appoint any person or any persons jointly or severally to be his deputy or deputies within any part of the Commonwealth, and in that capacity to exercise during the pleasure of the Governor-General such powers and functions of the Governor-General as he thinks fit to assign to such deputy or deputies, subject to any limitations expressed or directions given by the Queen, but the appointment of such deputy or deputies shall not affect the exercise by the Governor-General himself of any power or function.

127. In reckoning the numbers of the people of the Commonwealth or of a State or other part of the Commonwealth, aboriginal natives shall not be counted.

## CHAPTER VIII.

### ALTERATION OF THE CONSTITUTION.

128. This Constitution shall not be altered except in the following manner :

The proposed law for the alteration thereof must be passed by an absolute majority of each House of The Parliament, and not less than two nor more than six months after its passage through both Houses the proposed law shall be submitted in each State to the electors qualified to vote for the election of members of the House of Representatives.

But if either House passes any such proposed law by an absolute majority and the other House rejects or fails to pass it or passes it with any amendment to which the first-mentioned House will not agree, and if after an interval of three months the first-mentioned House in the same or the next session again passes the proposed law by an absolute majority with or without any amendment which has been made or agreed to by the other House, and such other House rejects or fails to pass it, or passes it with any amendment to which the first-mentioned House will not agree, the Governor-General may submit the proposed law as last proposed by the first-mentioned House, and either with or without any amendments subsequently agreed to by both Houses to the electors in each State qualified to vote for the election of the House of Representatives.

When a proposed law is submitted to the electors, the vote shall be taken in such manner as The Parliament prescribes. But until the qualification of electors of members of the House of Representatives becomes uniform throughout the Commonwealth only one-half the electors voting for and against the proposed law shall be counted in any State in which adult suffrage prevails.

And if in a majority of the States a majority of the electors voting approve the proposed law, and if a majority of all the electors voting also approve the proposed law, it shall be presented to the Governor-General for the Queen's assent.

No alteration diminishing the proportionate representation of any State in either House of The Parliament, or the minimum number of representatives of a State in the House of Representatives, or increasing diminishing, or otherwise altering the limits of the State, or in any manner affecting the provisions of the Constitution in relation thereto, shall become law unless the majority of the electors voting in that State approve the proposed law.

#### SCHEDULE.

##### OATH.

I, A.B., do swear that I will be faithful and bear true allegiance to Her Majesty Queen Victoria, Her heirs and successors, according to law. So HELP ME GOD!

##### AFFIRMATION.

I, A.B., do solemnly and sincerely affirm and declare that I will be faithful and bear true allegiance to Her Majesty Queen Victoria, Her heirs and successors, according to law.

(NOTE.—*The name of the King or Queen of the United Kingdom of Great Britain and Ireland for the time being is to be substituted from time to time.*)



## CONSTITUTIONS OF THE STATES OF THE COMMONWEALTH AND OF NEW ZEALAND.

### NEW SOUTH WALES.

THE present form of government in New South Wales was inaugurated fifty years ago, the "Act to confer a Constitution on New South Wales, and to grant a Civil List to Her Majesty," having received the Royal assent on the 16th July, 1855. This important statute was proclaimed in Sydney on the 24th November of the same year, and at once came into operation, sweeping away entirely the former system, and constituting an elective representative Chamber—thus, by the granting of equal privileges, making the colonists of New South Wales the equals of their countrymen in other parts of the Empire. The ties which bound the state to the mother country were in no way loosened, for the Constitution Act simply conceded to the people of New South Wales the rights which prevailed in the United Kingdom, namely, of taxing themselves, and of being governed by Ministers responsible to a Parliament elected by popular vote. The authority vested in the Sovereign remains the same as before, though the mode of its exercise is widely different. Prior to Responsible Government, the Sovereign exercised, through the Governor, almost despotic power, this official uniting in himself the executive and legislative functions. Personal liberty and independence were, therefore, to no small degree in his control; but with the establishment of Responsible Government this state of things ceased, and the greatest measure of individual liberty is now found compatible with the full protection of public rights. The readiness with which the people of the state adapted themselves to the forms and practice of their new government was not a little remarkable, and fully justified their assumption of its privileges.

All laws are enacted in the name of the King, "by and with the advice of the Legislative Council and Legislative Assembly," the Governor, as the Royal Deputy, immediately giving the assent of the Sovereign to Acts of Parliament, or, if he should think fit, reserving them for the consideration of His Majesty. In order that the Constitution may be clearly understood, it will be well to consider, under distinct heads, the several elements of which the Government and Legislature consist.

*The Governor.*

Prior to 1879 the Governor of the state was appointed by Letters Patent under the Great Seal; but in that year the practice was discontinued on the advice of Sir Alfred Stephen, given during the tenure of office of Sir Hercules Robinson. The change was first carried out in the appointment of Sir Augustus Loftus. The office of Governor is now constituted by permanent Letters Patent, and by a standing Commission, instead of as formerly by letters issued *pro hac vice* only. The Governor receives his appointment at present by Commission under the Royal sign manual and signet, which recites the Letters Patent of the 29th April, 1879, as well as the instructions issued (under sign manual and signet) in further declaration of the King's "will and pleasure." The original Letters Patent, thus recited and enforced, declare that the Governor is directed and empowered "to do and execute all things that belong to his office according to the tenor of the Letters Patent, and of such Commission as may be issued to him under our sign manual and signet, and according to such instructions as may from time to time be given to him under our sign manual and signet, or by our order in our Privy Council, or by us through one of our Principal Secretaries of State, and to such laws as are now or shall hereafter be in force in the colony." In accordance with a custom which has long prevailed, no Governor retains his office for a longer period than six years; and should he die or become incapable of performing his duties during his tenure of office, or be removed before the arrival of his successor, or should he have occasion to leave the state for any considerable period, the government is to be administered (1) by the Lieutenant-Governor; or, if there be no Lieutenant-Governor, (2) by an Administrator to be appointed according to the provisions of the Letters Patent and Instructions. The present Governor is Admiral Sir Harry Holdsworth Rawson, R.N., K.C.B. The present Lieutenant-Governor is Sir Frederick Matthew Darley, G.C.M.G., C.J., who was appointed by a Commission, dated the 23rd November, 1891; and in recent years the duties of Administrator have been fulfilled by Sir John Lackey, K.C.M.G., President of the Legislative Council, and since his decease by Mr. Justice M. H. Stephen.

The Lieutenant-Governor, or, in his absence, the Administrator, is empowered by his Commission to fill the office of Governor during any temporary absence of the Governor from the state; but the Governor may not be absent from the state, except in accordance with the terms of his instructions. Without the King's special leave he may not leave the state for a period exceeding one month at a time, or exceeding in the aggregate one month for every year of his service, unless on a visit to the Governor of a neighbouring state; but, on the other hand, he may leave the state for any period not exceeding one month without its being reckoned as a departure, if he shall have previously informed the Executive Council in writing of his intention,

and appointed a deputy to act for him till his return. This deputy must, in the first instance, be the Lieutenant-Governor ; but if, from any cause, the services of the Lieutenant-Governor should not be available, the Governor may appoint whomsoever he pleases as his deputy.

The Governor's functions, according to the Letters Patent, Commission, and Instructions, may be recapitulated as follow :—

The Governor is the custodian of the Great Seal, under which all Crown grants, etc., must pass.

The Governor has the appointment of his own Council—the Executive. He is also to summon that Council, and is ordinarily its President ; but in his absence some other member may be nominated to preside. It is usual, however, to appoint some member of the Ministry permanent Vice-President, who presides in the absence of the Governor.

The Governor is the fountain of honour within the state, since to him belongs the power to appoint, in the King's name, all Judges, Justices of the Peace, Commissioners, and other "necessary officers and Ministers"; and, by virtue of his powers as Viceroy, he may remove from the exercise of his office any official so appointed.

The Governor is also the depositary of the prerogative of mercy within the state, having it in his power to pardon, either absolutely or conditionally, any offender convicted in New South Wales. He can also remit fines, penalties, and forfeitures due to the Crown, but he cannot pardon or remit on the condition of the offender voluntarily leaving the state, unless the offence has been a political one only. In all capital cases until recently the final responsibility of deciding whether or not the death penalty should be carried out rested solely with the Governor, but, by a new arrangement which has been agreed to by all the Australasian colonies, such final power is now exercised by the Governor "with the advice of the Executive Council." This places the procedure of these colonies, in regard to capital cases, on similar lines to the system that has for some time past been in force in Canada. Its adoption was suggested and strongly urged by Lord Onslow, the former Governor of New Zealand ; and Lord Knutsford, the Secretary of State for the Colonies in the second Salisbury Administration, ascertained the views of the various Australasian colonies upon the subject. It being found that they all accepted the proposal as an improvement upon the practice then existing, a circular despatch was sent to each colony with instructions for its adoption. The new system was first brought into operation in New South Wales towards the end of October, 1892.

The Governor is also vested with the authority of the Crown, enabling him to nominate the members of the Upper House of the Legislature, and to summon, prorogue to a future day, or dissolve "any legislative body" existing in the state. His instructions, however, provide that in the exercise of the above powers he is to act by the advice of the Executive Council in all cases except those whose nature is such that in his opinion the public service "would sustain material prejudice

were he to follow such advice," or in matters too trivial to submit to the Council, or "too urgent to admit of their advice being given"; but in all such urgent cases he must communicate to the Council as soon as practicable the measures taken by him, and his reasons for acting. It is expressly provided, however, that the Governor may, if he think fit, disregard the advice of the Executive and act in direct opposition to the declared will of his advisers, but in such cases he is required to make a full report of the whole circumstances for the information of the Secretary of State for the Colonies.

The Governor acts as Viceroy as regards giving the Royal assent to or vetoing Bills passed by the Legislature, or reserving them for the special consideration of the Sovereign. The instructions deal at large with this matter, but it is usual in practice to be guided to a large extent by the advice of the law officers of the Crown. There are eight different classes of Bills, however, to which the Governor is bound to refuse the Royal assent. They are:—

- (1.) Divorce Bills (that is, private bills divorcing particular persons).
- (2.) Bills making any kind of grant, gratuity, or donation to the Governor.
- (3.) Bills affecting the currency.
- (4.) Bills imposing differential duties, which are not in accordance with the Australian Colonies Duties Act, 1873.
- (5.) Bills apparently contrary to Imperial treaty obligations.
- (6.) Bills interfering with the discipline or control of His Majesty's land or sea forces employed in the state.
- (7.) Bills of great importance, or extraordinary in their nature, whereby the Royal prerogative, or the rights and property of His Majesty's subjects residing beyond the state, or the trade and shipping of the United Kingdom and its dependencies, may be prejudiced.
- (8.) Bills containing provisions to which the Royal assent has already been refused, or which have been once disallowed, unless they contain a clause suspending their operation until the King's pleasure has been signified, or unless the Governor is satisfied that there is urgent necessity for bringing any such Bill into immediate operation, in which case he is empowered to assent to the Bill on behalf of the King, if it is not repugnant to the law of England, or inconsistent with Imperial treaty obligations; and in every such case he is required to transmit the Bill to His Majesty, together with his reasons for assenting to it.

The following Acts of Parliament regulate the action of the Governor in assenting to Bills on behalf of the King, or reserving them for the consideration of the Sovereign:—5 and 6 Vic., cap. 76, secs. 31–32; 7 and 8 Vic., cap. 74, sec. 7; and 13 and 14 Vic., cap. 59, secs. 13, 32, and 33. The effect of these enactments is to deprive any reserved Bill

of all force and legality until the King's assent thereto has been formally communicated to the Governor; and power is given to His Majesty to veto any Bill to which the Governor has assented on his behalf within two years after the receipt of such Bill by the Secretary of State for the Colonies, in which case the Bill is to be declared null and void by message of the Governor, and proclamation. Reserved Bills are to be laid before His Majesty in Council, and the King may allow them or not within a period of two years from the day on which they were reserved by the Governor. The King's assent to reserved Bills may be transmitted by telegram.

By Act 7 Vic., No. 16, all Acts of Parliament which become law are required to be registered by the Registrar-General within ten days of their so becoming law.

The Governor of New South Wales is also Governor of Norfolk Island, under an order dated October 18, 1900, and it is incumbent on him to visit the possession once at least during his term of office.

The above is a summary of the powers and duties of the Governor, as defined by his instructions and the Letters Patent; but additional duties have been imposed upon him by the Constitution and Electoral Acts. In accordance with these enactments he must summon the Legislative Assembly; appoint the President of the Legislative Council; prorogue or dissolve Parliament; appoint his ministers *proprio motu*; also appoint, with the advice of the Executive, all public officers whose appointment is not vested in heads of departments; issue all warrants for the payment of money; issue the writs for general elections, and, in the absence of the Speaker, issue writs to fill vacancies occurring in the Assembly.

In summoning, proroguing, or dissolving Parliament, the Governor usually acts according to the advice tendered him by the Cabinet; but he is in no way bound to do so, and, as a matter of fact, he has sometimes declined to be guided by his Ministers. This, however, has never happened except in respect to granting a dissolution. As to summoning or proroguing, a difference of opinion is hardly likely to arise. The relations established between the Ministry and the representatives of the people are in accordance with the time-honoured precedents prevailing in Great Britain, which may be thus defined. The Cabinet must be chosen from—“(1) Members of the Legislature; (2) holding the same political views, and chosen from the party possessing a majority in the House of Commons; (3) carrying out a concerted policy; (4) under a common responsibility, to be signified by a collective resignation in the event of Parliamentary censure; and (5) acknowledging a common subordination to one Chief Minister.”

The Imperial rule as to the circumstances under which a Government is bound to resign is as follows:—Censure, involving loss of office, rests entirely with the Lower House, or popular branch of the Legislature; hence, directly a Ministry fails to command a majority of the House of Commons, it must give place to another. Want of confidence in a Cabinet may be shown in three ways: first, by a direct vote of censure,

or a specific declaration of want of confidence; second, by a vote disapproving of some act of the Government; or, third, by the rejection of some important measure introduced by the Ministry. In any of these cases Ministers must either resign, or appeal to the country if they can get the Sovereign to sanction a new election.

These rules have been virtually adopted in New South Wales, and the undoubted right of the Governor, as the depositary of the Royal prerogative, to refuse to grant a dissolution, if he think fit, has been more than once exercised. In March, 1877, Sir Hercules Robinson refused to grant a dissolution to Sir John Robertson, and in September of the same year he also declined to enable Sir Henry Parkes to go to the country. The reason alleged in each case was that the Assembly refused to make provision for the expenditure of the year. It will thus be seen that a grave responsibility is thrown upon the Governor in the exercise of the unquestioned right of granting or refusing a dissolution of Parliament, and in the cases mentioned it can hardly be doubted that Sir Hercules Robinson acted within his powers. The Viceroy is the conservator of the rights and interests of the whole population, and it must be evident that grave evils would ensue were a dissolution to take place before supplies had been granted.

The exercise of the prerogative of mercy is such an important function of the Governor, and he is so liable on some occasions to have strong pressure brought to bear upon him in connection with it, that it will be well to quote at length the instructions received a few years ago upon this point. The mode of procedure in capital cases has already been referred to, and in other cases the Governor is instructed not to pardon or reprieve any offender without receiving the advice of one, at least, of his Ministers; and in any case in which such pardon or reprieve might directly affect the interests of the Empire, or of any country or place beyond the jurisdiction of the Government of the state, the Governor must, before deciding as to either pardon or reprieve, take those interests specially into his own personal consideration in conjunction with such advice as aforesaid. In another part of his instructions the Governor is permitted to act in opposition to the advice of the Executive Council "if he see sufficient cause," but he is to report any such matter to the Sovereign without delay.

#### *The Executive.*

The Executive Council is now composed of seven salaried Ministers, namely: the Premier, Colonial Treasurer and Minister for Railways, the Colonial Secretary, the Attorney-General and Minister of Justice, the Secretary for Lands, the Secretary for Public Works, the Minister of Public Instruction and Minister for Labour and Industry, the Secretary for Mines and Agriculture, with a Vice-President, and one member without portfolio. These form the Cabinet, and, of course, are responsible to Parliament. The Ministry, as the advisers of the Governor, must also retain his confidence; but, practically,

this is seldom likely to be withdrawn, so long as they command a working majority in the Assembly. The Governor may dissolve Parliament although the Ministry have not sustained a defeat, and in this case the continued existence of any Government would depend directly on the vote of the constituencies, but such a contingency can happen but seldom.

Apart from the Vice-President of the Executive Council, who holds no portfolio, it is rare for more than one Minister to be selected from the Upper House, and it will thus be seen that the principle of the responsibility of members of the Government to Parliament is fully carried out. For every act of the Governor as Viceroy some Minister is responsible to Parliament; and even in matters of Imperial interest, where the final onus rests upon the Governor, he himself is responsible to the Imperial Government, whose members are under the control of the House of Commons, so that no loophole is left for the exercise of any arbitrary act. The Crown, except in two instances (appeals to the Privy Council, and the bestowal of titles), acts towards the Executive through its representative, the Governor; and so long ago as the inception of Responsible Government, Earl Grey declared, in an official despatch, that he should make "a judicious use of the influence, rather than of the authority, of his office," which wise maxim has usually been followed. But in extreme cases, such as when his sanction is requested to any illegal proceeding, the Governor is bound, without question, to keep the law, though he may thereby be brought into hostile relations with the Cabinet. Sir Michael Hicks-Beach, in a communication to the Governor-General of Canada in 1879, clearly laid down the doctrine that the Governor of any British Colony "has an unquestionable constitutional right to dismiss his Ministers, if from any cause he feels it incumbent on him to do so." This does not militate against the doctrine of responsibility; for if the Ministry appointed by the Governor do not possess the confidence of Parliament, they cannot hold office, and the Governor will be forced to give way, or else persevere till he can select a Ministry whom the Assembly will accept. The final control will thus be, as in every other case, with the representatives of the people. In matters of routine the Governor will necessarily act on the advice of his Ministers, and in most cases relating to the internal economy of the departments, he will even adopt the individual recommendations of the Ministers by whom they are severally controlled.

As regards matters of purely Imperial interest, the Governor is responsible to the British authorities for their due conservation. If in consequence of his action in any such matter, he is involved in a dispute with his Ministers, he is bound to refer them to the Sovereign, should his action have been endorsed by the Colonial Office. If his conduct were not approved of in England he would most likely be recalled. It follows from this, that in no case can the Governor be held to be responsible directly to Parliament for his conduct. His Ministers are

responsible, but personally he has only to render an account to the Crown itself—that is, to the Imperial Parliament.

The Executive Council cannot discharge any function unless duly summoned by the Governor, and unless at least two members, in addition to the Governor or presiding member, be present to form a quorum. Formal minutes are, of course, kept of all proceedings.

Since the introduction of Responsible Government there have been thirty-two Ministries; but as five of these became merged into those next succeeding without the resignation of their members, the actual number of cabinets holding power may properly be said to have been twenty-seven, whose average tenure of office, excluding the Ministry at present in power, has been about one year and six and a half months. Ten Governments were displaced by votes of censure, expressed or implied; three resigned in consequence of defeat on important measures of policy; two retired on being saved from defeat only by the Speaker's casting-vote, and three others through a motion for the adjournment of the House being carried against them; five, as previously stated, were merged into the succeeding Ministries; six resigned without a direct vote being carried against them, but in consequence of not possessing a working majority; one Government fell to pieces through internal disagreements; and one resigned in consequence of the Governor declining to appoint to the Legislative Council a certain number of its nominees.

#### *The Parliament.*

It seems a singular omission in the Constitution Act that no definition is given of the relative powers of the Legislative Council and Legislative Assembly. Such is the fact, but little inconvenience has arisen thereby, since by common consent it has been agreed that the precedents regulating the proceedings and relations, *inter se*, of the two Houses of the Imperial Parliament shall be followed, so far as applicable, in New South Wales. The Constitution Act provides that all money Bills shall be introduced in the Lower House only. The important rule of the House of Commons, affirmed two hundred years ago and constantly enforced ever since, that "all aids and supplies, and aids to His Majesty in Parliament, are the sole gift of the Commons, and it is the undoubted right of the Commons to direct, limit, and appoint in such Bills the ends, purposes, considerations, conditions, limitations, and qualifications of such grants, which ought not to be changed or altered by the House of Lords," is also held to be in force as regards the Parliament of this state, and has generally been recognised and acted upon.

The two Houses, however, do not possess the most important of the privileges of the Imperial Parliament, namely, the right of punishing for contempt, although the Legislative Assembly has, on one occasion, punished one of its members, by expelling him for conduct, beyond its precincts, assumed to be dishonourable. As regards disorderly conduct within the walls of the Chamber, it has been held by the Supreme Court, and affirmed by the Privy Council, that the Assembly only possesses the



power of suspending a member for disorderly conduct for the period of the sitting at which he displays such conduct. A member may also be removed from the House by order of the Speaker if he persists in obstruction or contemns the Standing Orders; but fortunately this course has seldom been rendered necessary.

Witnesses may be summoned to give evidence before either House, or before committees of the Council or Assembly, the necessary powers for compelling their attendance having been conferred by an Act passed in 1881. Any person disobeying a summons may be arrested on a Judge's warrant; and the maximum penalty for refusing to give evidence is imprisonment for one calendar month.

The number of members of the Legislative Council is not limited by the Constitution Act, although the minimum number is fixed at twenty-one. It will be seen that this gives power to a Governor to quash any possible obstruction on the part of the Council to the will of the Government and the Lower House by "swamping" the Council. Such a proceeding, however, can hardly be held to be allowable, except under extreme circumstances. As a matter of fact, an attempt to "swamp" the Council was made during one of the premierships of Sir Charles Cowper, but public opinion condemned the course most strongly, although the somewhat peculiar circumstances of the case were thought at the time to justify the Governor's action. The authorities in England severely rebuked the Governor (Sir John Young) for the course he had taken, and since then "swamping" the Council has never been seriously entertained, nor is there much chance that it will ever again be attempted. The principle in fact has been affirmed, on the basis of an understanding entered into between Sir John Young and the leading statesmen of the day (on both sides of the House), that the members of the Legislative Council should be limited to a convenient number, and that no nominations should ever be made merely for the purpose of strengthening the party which happens to be in power. A deadlock between the two Houses is provided against by the universal feeling that the Assembly represents the will of the people, and in such case the Council would certainly have to give way to the deliberate will of the people's representatives. The Council is intended as a check to hasty legislation; and it doubtless acts as a useful "brake" to violent party feeling.

#### *The Legislative Council.*

As before stated, the members of the Upper House are nominated by the Governor, the minimum number composing the House being fixed at twenty-one. No limit to the number is fixed by the Constitution Act, but, in accordance with the arrangement already described, the number of members is practically kept down by the exclusion of all purely political appointments. There were sixty-one Councillors in September, 1904. Every member of the Council must be of full age, and either a natural-born or a duly naturalised subject. Four-fifths

of the members must be persons not holding any paid office under the Crown, but this is not held to include officers "in His Majesty's sea and land forces on full or half pay, or retired officers on pensions." Though the appointment is for life, a member may resign his seat, and he also forfeits it by absence from the House for two consecutive sessions without leave, by becoming naturalised in a foreign State, by becoming bankrupt, by becoming a public contractor or a defaulter, and by being attainted of treason or being convicted of felony or any infamous crime. The Governor appoints, and, if necessary, removes the President, who may speak in debate, but can only give a casting-vote. An attendance of one-third of the members on the roll was formerly necessary to constitute a quorum, but an Act has been carried reducing the proportion to one-fourth. The Council must hold a sitting at least once in every year, and no greater interval than twelve months must elapse between session and session. The proceedings are regulated by standing orders, which are, in the main, similar to those of the Assembly, the latter being framed on the model of the rules obtaining in the House of Commons. No member may sit or vote till he has taken the oath of allegiance, or the affirmation prescribed in lieu of that oath.

#### *The Legislative Assembly.*

In the Session of 1892-3, an Act was passed, entitled the Parliamentary Electorates and Elections Act of 1893, by which the course of procedure in regard to elections for the Legislative Assembly of New South Wales was almost entirely changed. The enactments under which such elections had been conducted up to that time—the Electoral Act of 1880, and the Wentworth Subdivision Act—were repealed upon the passing of the Act of 1893, with the exception of certain provisions which have since been abrogated by proclamation. During the year 1896 several important alterations were made in the 1893 Act in the direction of the extension of the franchise, and of the removal of restrictions placed upon electors changing their residence from one district to another. In 1902 the franchise was extended to women. The main principles of the new electoral system may be thus summarised :—

The number of members of the Legislative Assembly, which had grown by virtue of the Expansion Clauses of the Act of 1880 from 108 to 147, was reduced to 125, and the number of electorates, now denominated Electoral Districts, was increased from seventy-four to 125. Under the new system, therefore, there are exactly as many members as electorates, or, in other words, there are single electorates. This, of course, involved a complete re-distribution of the electorates, and special machinery had to be created in order that this might be done. In accordance with the Act three Commissioners were appointed, to whom was entrusted the duty of dividing the state into 125 districts, each containing as nearly as might be the same number of electors. In order to ascertain the quota of electors to be apportioned to each electorate, the number of

resident electors on the roll for 1892-3, which happened to be 282,851, was divided by 125, and the quotient, 2,263, was fixed as the standard number of electors entitled to one representative. In mapping out the new Electoral Districts, the Commissioners were required to form them so as to include the standard number of electors as nearly as possible; at the same time, in order to avoid inconvenient divisions, a margin of 200 voters either above or below the standard number was allowed, which margin it was permitted, in exceptional cases, to increase to 600 either way, on satisfactory reason for taking that action being furnished by the Commissioners. As a result of the referendum on the question of reduction of members, taken in December, 1903, the state was divided in 1904 into ninety districts, each of which is represented by one member in the Assembly.

The qualification for an elector is that he must be a natural-born subject who has resided in New South Wales for a continuous period of one year, or a naturalised subject who has resided in the state continuously for one year after naturalisation. It was provided in the principal Act that in either case he must have resided three months continuously in the electoral district for which he claimed to vote; but by the amending Act 60 Vic. No. 25 the period of residence was reduced to one month in the case of a person already on the rolls, and who had but removed from one district to another. Every such person, being of the full age of 21 years, and not otherwise disqualified, is entitled to have his name on the electoral roll, and to have an elector's right issued to him. The disqualifications, under the Constitution Act, apply to persons attainted or convicted of treason, felony, or other infamous offence in any part of His Majesty's dominions, unless they have received a free or conditional pardon, or have undergone the sentence passed on them for such offence; and, under subsequent enactments, to persons in the Naval and Military Service on full pay (except the militia and volunteers), and to persons of unsound mind, or in receipt of public charity. All other disqualifications have now been removed. The Woman's Franchise Act, passed in 1902, entitles all females of the age of 21 years and upwards to vote, and this right was exercised for the first time at a state election at the general election in 1904.

Power was given to the Governor under the Act of 1893 to subdivide each electoral district into divisions, and to appoint to each district an Electoral Registrar, with Deputy Registrars for the several divisions. It is one of the duties of these Registrars and Deputy Registrars to issue certificates known as electors' rights to those entitled to them. These electors' rights are printed in red ink upon paper specially prepared to prevent fraudulent imitations, with butts, like cheques, in accordance with the forms shown in Schedule A of the principal and amending Acts. They are bound in books, and numbered consecutively in black figures. Every person who has established his qualification to vote, and who has been placed on the electoral roll, is entitled to receive an elector's right upon signing his name in a

book kept for that purpose, as well as on the butt and the face of the right itself. Under the principal Act an elector who removed from one district to another within three months of an election was practically disfranchised; but, as stated above, this period has now been reduced to one month, and until the elector is qualified to vote in the district to which he has removed he may use his right in his old district. Provision is also made for the issue of a substituted right in the event of a right being lost or defaced. Every elector's right remains in force until cancelled in the prescribed manner. It is provided by the amending legislation of 1896 that an elector who has changed his abode from one district to another may obtain a right for his new district after he has resided one month therein, and may have his name inscribed on the Additional Roll on a declaration by the Registrar of his original district stating that he was enrolled there. When the Registrar of any district grants an application for an elector's right other than in lieu of one held for another district, he inscribes the name of the elector in a Provisional List, copies of which, during the first week of each month, are exhibited at every post-office and police-office within the district, so that objection to any name may be taken and heard at the Revision Court of the district, to be presided over by a Stipendiary or Police Magistrate, specially appointed as a Revising Magistrate. All names passed at the monthly Revision Court are then inscribed on the Additional Roll.

During the first week in August of each year, the Registrar must make out a general list of all persons on the electoral roll for his district, as well as of those to whom electors' rights have been issued since the last roll was printed; and copies of all such lists are exhibited for public inspection at every post-office in the electoral district. Any person objecting to any name upon the list must give to the Registrar, in writing, his reasons for such objection, and the Registrar must notify the same to the person to whom objection is taken. Every Registrar is supplied quarterly, by the District Registrar of Births, Deaths, and Marriages, with a list of all males above the age of 21 years whose deaths have been registered within the quarter in that particular district. As no provision is made for the exchange of these lists of deceased persons between different districts, it is possible for the names of electors who died outside their own districts to remain on the roll, and it is known that this often happens, unless sufficient proof of death is furnished by objectors. The Comptroller-General of Prisons and the Inspector-General of Police must forward quarterly to the Minister charged with the administration of the Act a list of all males above the age of 20 years in any gaol, lock-up, or other place of detention; and the Minister must send to the Registrar of each district such particulars as may be necessary for the purification of the electoral roll for such district. The Registrar must then write on a copy of the electoral roll, against the name of every person on the lists supplied to him as above, the words "dead" or "in custody, disqualified," or simply "in custody" where the

particulars supplied do not appear to be such as to disqualify the person. Under the principal Act a Revision Court was held in October each year; but under the amending Act a monthly Revision Court is now held, at which objections may be heard, and claims for insertion on the lists considered; and from the lists, when duly corrected and certified to by the magistrate presiding at the Court, the electoral roll is printed. In the year 1900 and every third year thereafter the General List is to be made up from the butts of the electors' rights issued to persons "then" entitled to vote. A new issue of electors' rights was made at the beginning of 1901, and these remain in force until duly cancelled.

Writs for the election of members of the Assembly are issued by the Governor in the case of a general election, and by the Speaker, or, in his absence or if there should be no Speaker, by the Governor, in the case of a bye-election. The writs for a general election are required to be issued within four clear days from the proclamation dissolving Parliament, and are made returnable not later than thirty-five days from the date of issue. Parliament must meet not later than seven days from the return of the writs. The polling day for a general election is fixed as the eighteenth day from the date of the issue of the writs.

A person, to be qualified as a candidate, must be the holder of an elector's right. Each candidate must be nominated by at least six electors for the district. The nomination must be made in writing, signed by the nominators, and endorsed by the candidate, consenting to the nomination. No elector can have more than one vote in the state, or, in other words, the "one man one vote" principle is enforced. No elector can nominate more than one candidate. No deposit from a candidate is required. Proper provision is made for the appointment of Returning Officers, substitutes, deputies, poll-clerks, and scrutineers, much as in the Act of 1880. Under the principal Act the poll was open from 8 a.m. to 6 p.m. in the months from October to March inclusive, and from 8 a.m. to 5 p.m. from April to September inclusive; but under the Parliamentary Elections (Polling) Act (No. 20 of 1898) the poll remains open from 8 a.m. to 6 p.m., irrespective of the season of the year when the election is held. Every person claiming to vote must exhibit his elector's right, satisfy the Returning Officer that he is the person on the roll who should possess that right, and demand a ballot-paper. He is then furnished with a ballot-paper, containing the names of the candidates; and his elector's right, as well as the butt, is punctured to denote that he has voted at that election. The elector has then to retire to some unoccupied compartment of the polling-booth, there to strike out the names of all the candidates on the paper except the one for whom he votes, and the ballot-paper, folded so that the names are not visible, but that the puncture can be seen by the Returning Officer or his deputy, is placed by him in the ballot-box. No provision is made whereby an elector can record his vote if away from his own electorate, except where outside polling places have been

appointed, under the provisions of the Act, before the issue of the writs. At the close of the poll the votes are counted, and the result declared by a notice signed by the Returning Officer, and posted in some conspicuous position in the principal polling place, and published in some newspaper circulating in the district.

Very stringent clauses against bribery, treating, or intimidation are included in the Act. It is even forbidden to make a wager on the result of an election under a penalty of from £5 to £50. There are also sections providing for the appointment of a Committee of Elections and Qualifications, with powers similar to those conferred by the Act of 1880.

The disqualifications for membership of the Legislative Assembly, provided by the Constitution Act, still remain in force. They are as follow:—

1. He must not be a member of the Legislative Council.
2. He must not hold any office of profit under the Crown, either for a term of years or during pleasure.
3. He must not be in any way interested in any contract for the public service.

By the Constitution Act Amendment Act of 1884, the disqualification of persons holding offices of profit was declared not to apply to the Colonial Secretary or any other member of the Ministry. The third disqualification also does not apply to any contract made by a company consisting of more than twenty persons. If any disqualified person be elected, the election is voided by the House, and should such person presume to sit or vote he is liable to a fine of £500.

By an Act assented to on the 21st September, 1889, members of the Assembly are allowed the sum of £300 per annum to reimburse them for expenses incurred in the discharge of their duties. Members of both Houses are allowed free passes on the railways and tramways of the state.

Before taking his seat each member must take the oath of allegiance in the prescribed form, or make an affirmation in lieu of it. A member may resign his seat at any time, and he is held to have vacated it under any of the following conditions:—Absence during a whole session without leave, naturalisation in a foreign country, bankruptcy, being a defaulter, or convicted of treason, felony, or other infamous crime; becoming pecuniarily interested in any contract for the public service excepting as member of a Company exceeding twenty in number, acceptance of an office of profit under the Crown, becoming a member of either House of Parliament of the Australian Commonwealth.

The Act 37 Vic. No. 7 provides that no Assembly can prolong its existence beyond the term of three years. One session, at least, must be held every year, and twelve months must not elapse between any two sessions. On meeting after a general election, the first business is to elect a Speaker, who has only a casting vote.

The first Parliament elected under the Constitution Act met on the 22nd May, 1856, just six months after the proclamation of the Constitution. The duration of Parliament, unless it should be previously

prorogued, was originally fixed at five years; but in 1874 an Act was passed establishing triennial Parliaments, which has ever since remained law. Since the inauguration of Responsible Government there have been nineteen appeals to the people, so that it will be seen the duration of each Assembly has not averaged even the shorter period of life to which its existence is now limited. The subjoined table gives the duration of each Parliament elected under Constitutional Government:—

Parliament.	Opened.	Dissolved.	Duration.			No. of Sessions.
			Yr.	mtl.	dy.	
First .....	22 May, 1856...	19 Dec., 1857...	1	6	27	2
Second .....	23 March, 1858...	11 April, 1859...	1	0	19	2
Third .....	30 Aug., 1859...	10 Nov., 1860...	1	2	11	2
Fourth .....	10 Jan., 1861...	10 Nov., 1864...	3	10	0	5
Fifth .....	24 Jan., 1865...	15 Nov., 1869...	4	9	22	6
Sixth .....	27 Jan., 1870...	3 Feb., 1872...	2	0	7	3
Seventh .....	30 April, 1872...	28 Nov., 1874...	2	6	29	4
Eighth .....	27 Jan., 1875...	12 Oct., 1877...	2	8	15	3
Ninth .....	27 Nov., 1877...	9 Nov., 1880...	2	11	13	3
Tenth .....	15 Dec., 1880...	23 Nov., 1882...	1	11	8	3
Eleventh .....	3 Jan., 1883...	7 Oct., 1885...	2	9	4	6
Twelfth .....	17 Nov., 1885...	28 Jan., 1887...	1	2	9	2
Thirteenth .....	8 March, 1887...	19 Jan., 1889...	1	10	11	3
Fourteenth .....	27 Feb., 1889...	6 June, 1891...	2	3	10	4
Fifteenth .....	14 July, 1891...	25 June, 1894...	2	11	12	4
Sixteenth .....	7 Aug., 1894...	5 July, 1895...	0	10	29	1
Seventeenth .....	13 Aug., 1895...	8 July, 1898...	2	10	26	4
Eighteenth .....	16 Aug., 1898...	11 June, 1901...	2	9	26	5
Nineteenth .....	23 July, 1901...	16 July, 1904...	2	11	23	4
Twentieth .....	23 Aug., 1904...	.....	.....	.....	.....	...
Average.....			2	4	19	3 to 4

The system of one man one vote came into operation on the dissolution of the fifteenth Parliament. At the first election under the new system in 1894, a total poll of 204,246 votes was recorded. The electors on the rolls numbered 298,817, and those qualified to vote in districts that were contested, 254,105. The poll, therefore, represented 80·38 per cent. of effective voters—by far the best percentage of votes recorded at a general election in New South Wales. The second election under the new Act gave a poll of 153,034 votes out of a total enrolment of 238,233 electors in contested constituencies, the proportion of votes cast being 64·24 per cent. At the election held in July, 1901, 195,359 votes were recorded, the electors enrolled numbering altogether 346,184, and those qualified in contested electorates only, 270,861, so that the percentage of votes recorded was 72·13. At the general election of 1904, when women recorded their votes for the first time at a state election, the voters enrolled numbered 689,459, of whom 326,411 were women. The votes cast totalled 400,595, or 59·3 per cent. of the voters on the roll in contested districts, the percentages for males and females being 63·8 and 54·4 respectively.

The subjoined table gives the result of the five general elections which have taken place since the principle of one man one vote became law :—

Parliament.	Votes on Roll.	Number of Electors to a Member.	Total Members returned.	Members unopposed.	Contested Electorates.				
					Electors on Roll.	Votes recorded.	Percentage of Votes recorded.	Informal Votes.	Percentage of Informal Votes.
Sixteenth .....	298,817	2,296	123	1	254,105	204,246	80.38	3,310	1.62
Seventeenth ...	267,458	2,139	125	8	238,233	153,034	64.24	1,354	0.88
Eighteenth ...	324,338	2,595	125	3	294,481	178,717	60.69	1,638	0.92
Nineteenth ...	346,184	2,769	125	13	270,861	195,369	72.13	1,534	0.79
Twentieth .....	639,439	7,661	90	2	675,417	400,595	59.31	...	...

As the table shows, the percentage of votes recorded at the general election of 1904 was the lowest during the period.

#### VICTORIA.

UP to the 1st July, 1851, Victoria formed a part of New South Wales, being included with the parent settlement under the name of Port Phillip District. The separation was effected in pursuance of an Act of the Imperial Parliament, dated 5th August, 1850, entitled "An Act for the better government of Her Majesty's Australian Colonies." This measure provided that "the territories now comprised within the said district of Port Phillip, including the town of Melbourne, and bounded on the north and north-east by a straight line drawn from Cape Howe to the nearest course of the River Murray, and thence by the course of that river to the eastern boundary of the colony of South Australia, shall be separated from the colony of New South Wales, and shall cease to return members to the Legislative Council of such colony, and shall be created into and thenceforth form a separate colony, to be known and designated as the Colony of Victoria."

It was also enacted that there should be a separate Legislative Council for Victoria, one third of the number of members to be appointed by Her Majesty and the remainder to be elected by the inhabitants of the colony. Authority was given to the Governor and Legislative Council of New South Wales to determine by Act of Parliament the number of members of which the Legislative Council of Victoria was to consist, and to make provision for dividing the new colony into electoral districts, for appointing the number of members for each district, and generally for carrying on the necessary elections.

The measure provided also that electors should be possessed of freehold estate of the clear value of £100, or be occupiers or three-years leaseholders of the clear annual value of £10 a year.

On the issuing of writs for the first election of members of the Legislative Council of Victoria, the colony was to be accounted as legally established, and the powers of the Governor and Council of New South Wales over the territories comprised in Victoria thereupon ceased.



In accordance with the provisions of the Imperial Act the Governor and Legislative Council of New South Wales passed the Victoria Electoral Act of 1851, which provided that the Legislative Council of Victoria should consist of thirty members, ten to be appointed and twenty elected. The new colony was also divided into sixteen electoral districts.

On the 1st July, 1851, Sir Charles Fitzroy, the Governor-General of Australia, issued the writs for the election of members, and declared the district of Port Phillip to be separated from New South Wales, and established as an independent colony to be known and designated as the colony of Victoria. The constitution thus established continued until the 23rd November, 1855.

At the close of 1852 the Secretary of State for the Colonies forwarded a despatch to Lieutenant-Governor La Trobe, in which the Legislative Council of the colony was invited to consider the question of forming a second Legislative Chamber. This suggestion was shortly afterwards acted upon, and on the 24th March, 1854, a Bill "to establish a constitution in and for the Colony of Victoria" was passed and submitted to the Lieutenant-Governor, who at once forwarded it to the Secretary of State. On the 16th July, 1855, the Imperial Parliament passed an Act "to enable Her Majesty to assent to a Bill as amended of the Legislature of Victoria to establish a constitution in and for the Colony of Victoria." The Bill itself appeared as the first schedule to the Imperial Act, and was assented to on the 21st July, 1855. This course of procedure was rendered necessary owing to the fact that the Legislative Council of Victoria had exceeded its powers in passing the Bill before submitting it to the Imperial Government. It was, however, explained by the Secretary of State that the Parliament did not consider it necessary to supersede the Bill by direct legislation, as it was thought that the colonial legislature should be trusted for all the details of local representation and internal administration.

The new "Constitution Act" was formally proclaimed on the 23rd November, 1855, and the first meeting of the new Parliament was held on the 21st November, 1856.

Under the terms of the Act the elective and nominee Council was abolished, and an elective Council and Assembly were established, "with power to make laws in and for Victoria in all cases whatsoever." Subject to certain limitations, the Parliament may alter, repeal, or vary the Constitution." This power, which was conferred by Section 60, has been extensively availed of. Thus, under the Act as originally passed, the Legislative Council consisted of thirty members, elected for ten years, representing six districts. Under the Constitution Act of 1903, the Council consists of thirty-five members, elected for six years. Of these, thirty-four are representatives of, and elected by, the electors of the seventeen provinces, and one member is representative of, and elected by, the public officers and railway officers. The Legislative Assembly, as first constituted, consisted of sixty members, representing thirty-seven districts; at present there

are sixty-eight members, of whom sixty-five are representative of, and elected by, the electors of the sixty-five electoral districts, one member representative of, and elected by, the public officers, and two members representative of, and elected by, the railway officers. The property qualification for members and electors of the Upper House has been considerably reduced, while at present no property qualification is required in the case of members and electors for the Legislative Assembly. An important provision of the Amended Constitution Act refers to the power of the Council to suggest alterations in Appropriation Bills. This may be exercised at the following stages:—(a) The consideration of the Bill in committee, (b) the consideration of the report of the Committee, and (c) the consideration of the question that the Bill be read a third time.

The powers and duties of the Governor are very similar in all the states, and the subject is referred to at some length in the previous sub-chapter, dealing with the constitution of New South Wales.

The present Governor is Sir R. Talbot. The Governor is, *ex officio*, President of the Executive Council, the other members, consisting of not more than eight Ministers, holding paid offices. There are two legislative chambers—a Legislative Council, consisting of thirty-five members, of whom thirty-four are returned for seventeen provinces, and one member representative of, and elected by public servants and railway officers; and a Legislative Assembly, composed of sixty-eight members, of whom sixty-five are returned from the sixty-five districts, one by the public servants, and two by the railway officers. The term "railway officers" includes every person who is employed on the permanent staff of the Victorian Railways Department, and is subject to the Railways Acts. Subject to the provisions of the Constitution as to dissolutions, every member of the Council (except a member elected to fill a casual vacancy) shall be entitled to hold his seat for a period of six years only, but one half of the members who are elected for provinces at any general election of the Council shall be entitled to hold their seats for three years only. It is provided that the member obtaining the least number of votes at his election shall be the first to retire, and in case of equality of voting or no poll at an election, it shall be decided by lot which member shall retire. A retiring member is capable of being re-elected, and may sit and vote up till the day prior to the polling at the election. A public servant or railway officer may be elected a member of the Council or of the Assembly (notwithstanding anything contained in the Constitution), and at the expiration of his tenure of office is entitled to resume his position in the public service or railways service with status and pay similar to that held at the time of his election. The qualification for members of the Upper House is the possession of freehold rateable property of an annual rateable value of £50, and a minimum age limit of 30 years. Electors for this Chamber must possess freehold property rated in some municipal district at not less than £10 per annum, or be leasees,

assignees, or occupying tenants of property of an annual rateable value of not less than £15. Resident graduates of Universities within the British dominions, legal and medical practitioners, clergymen, certificated schoolmasters, matriculated students of Melbourne University, and naval and military officers are also entitled to vote for the Legislative Council. All voters not being natural born subjects of His Majesty must have resided in Victoria for twelve months previous to 1st January, or 1st July, in any year, and must have taken out letters of naturalisation at least three years previously. Every elector must be a male of the full age of 21 years.

For the Legislative Assembly, the qualifications required of members are that they have reached the age of 21 years, and are natural-born subjects of the King, or, in case of aliens, have been naturalised for five years; but judges of Victorian courts, ministers of religion, and persons who have been attainted of treason, or convicted of any felony or infamous crime, are not eligible. Persons holding offices of profit, uncertificated bankrupts or insolvents, and members of either House of the Federal Legislature are also ineligible. There is no property qualification required, either for members or electors. Manhood suffrage is the basis on which electors vote, and they must be natural-born subjects, or naturalised for one year prior to the 1st January, or 1st July, in any year, possessing an elector's right, and untainted by crime, or be enrolled on the roll of ratepaying electors, or hold a voter's certificate under the provisions of section 23 of Act No. 1601. The Plural Voting Abolition Act of 1899 provides, however, that it shall not be lawful for any one person to vote more than once at the same election, nor to vote in more than one district.

Women are not eligible as members or electors of either House of Parliament.

Ratepayers in the municipal districts have their names placed on the roll without any action on their own part; but non-ratepayers and freeholders residing in another electorate and not enrolled as ratepayers, must take out "electors' rights." To qualify for an elector's right a person must have resided in Victoria for twelve months, and in a division of his district for at least one month prior to application. The non-residential qualification for a right consists in possessing property of the clear value of £50, or an annual value of £5, in an electoral district. As before stated, no person is permitted to exercise more than one vote at the same election.

Members of the Legislative Council receive no remuneration for their services, while in the Lower Chamber the members receive "reimbursement of expenses" at the rate of £300 per annum.

Under the Constitution Act of 1903, provision is made for compiling an electors' roll of public officers, and an electors' roll of railway officers. Both classes of officers are only allowed to vote at elections of their own particular representatives.

Since the inauguration of responsible government in Victoria, there have been eighteen complete Parliaments, the first of which was opened on the 21st November, 1856, and dissolved on the 9th August, 1859, and the eighteenth opened on the 13th November, 1900, and dissolved on the 16th September, 1902. The present Parliament began its sessions on the 14th October, 1902. The table below shows the date of opening and dissolution of each Parliament up till the present time :—

Parliament.	Opened.	Dissolved.	Duration.			Number of Sessions.
			yr.	mt.	dy.	
First.....	21 Nov., 1856...	9 Aug., 1859...	2	8	19	3
Second.....	13 Oct., 1859...	11 July, 1861...	1	9	0	2
Third.....	30 Aug., 1861...	25 Aug., 1864...	2	11	27	3
Fourth.....	28 Nov., 1864...	11 Dec., 1865...	1	0	14	1
Fifth.....	12 Feb., 1866...	30 Dec., 1867...	1	10	17	6
Sixth.....	13 Mar., 1868...	25 Jan., 1871...	2	10	14	4
Seventh.....	25 April, 1871...	9 Mar., 1874...	2	10	15	3
Eighth.....	19 May, 1874...	23 April, 1877...	2	11	8	3
Ninth.....	22 May, 1877...	9 Feb., 1880...	2	8	19	3
Tenth.....	11 May, 1880...	29 June, 1880...	0	1	20	1
Eleventh.....	22 July, 1880...	3 Feb., 1883...	2	6	13	3
Twelfth.....	27 Feb., 1883...	19 Feb., 1886...	2	11	24	4
Thirteenth.....	16 Mar., 1886...	11 Mar., 1889...	2	11	27	3
Fourteenth.....	9 April, 1889...	5 April, 1892...	2	11	27	3
Fifteenth.....	11 May, 1892...	4 Sept., 1894...	2	3	25	3
Sixteenth.....	4 Oct., 1894...	28 Sept., 1897...	2	11	28	4
Seventeenth.....	25 Oct., 1897...	18 Oct., 1900...	2	11	25	4
Eighteenth.....	13 Nov., 1900...	16 Sept., 1902...	1	10	4	3
Nineteenth.....	14 Oct., 1902...	24 Dec., 1903...	1	2	12	3
Twentieth.....	29 June, 1904...	.....	.....	.....	.....	.....
Average.....			2	4	8	3 to 4

The following table gives particulars of the voting at the last six general elections :—

Year.	Legislative Council.				Legislative Assembly.			
	Electors on Roll.	Electors in Contested Districts.	Voters in Contested Districts.	Per-centage.	Electors on Roll.	Electors in Contested Districts.	Voters in Contested Districts.	Per-centage.
1889	151,803	31,134	14,726	47.29	243,730	220,973	147,129	66.53
1892	163,236	25,300	10,536	41.64	278,812	243,585	158,611	68.12
1894	145,629	•	•	•	234,552	196,482	139,501	70.99
1897	133,575	•	•	•	254,155	224,987	158,225	70.33
1900	129,363	15,551	6,383	41.08	280,600	203,200	128,980	63.47
1902	134,087	•	•	•	290,241	216,063	141,471	65.47
1904	172,495	104,843	61,392	58.54	264,709	223,600	140,127	62.66

\* No contest.

#### QUEENSLAND.

QUEENSLAND was formerly included in New South Wales, but was separated from the mother colony by Her Majesty's Letters Patent,

dated the 6th June, 1859. The Letters Patent provided that a form of government should be established in Queensland, based on similar lines to that existing in New South Wales, and ordered the constitution of a Legislative Council and Legislative Assembly "to make laws for the peace, welfare, and good government of the colony in all cases whatsoever."

On the 10th December, 1859, Sir George Bowen, the first Governor, landed, assumed the government, and formally proclaimed the establishment of the colony.

The administration is carried on by the Governor with the advice of an Executive Council, consisting of eight salaried members and one member without portfolio. The Premier is usually, but not invariably, the Vice-President of the Executive.

The Orders in Council provided that the Legislative Council should be summoned and appointed by the Governor. As first constituted it consisted of such persons as the Governor nominated, who were to be not fewer than five, and to hold their seats for five years. All subsequent appointments were to be for life. Members of the Council were to be of the full age of 21 years, and natural-born or naturalised subjects of Her Majesty.

It was also provided that four-fifths of the members nominated should be persons not holding any office or emolument under the Crown, except officers of Her Majesty's sea and land forces, on full or half pay, or retired officers on pension. One-third of the members of the Legislative Council, exclusive of the President, are required to form a quorum. The Governor was also authorized by the Orders in Council to summon a Legislative Assembly, to fix the number of members of which it was to be composed, and to divide the colony into electoral districts. It was also provided that every Legislative Assembly so elected should continue for five years, subject to prorogation or dissolution by the Governor before the expiration of such period. The qualifications of persons who could be elected to the Assembly and of those eligible to vote at elections of members were ordered to be arranged in accordance with the qualifications then in force in New South Wales.

As thus constituted, the Parliament was to have power to make laws for the peace, welfare, and good government of the colony; also to make laws altering or repealing any of the provisions of the Orders in Council, except such as related to the giving and withholding of Royal assent to Bills, the reservation of Bills for Her Majesty's pleasure, the instructions to Governors for their guidance in such matters, and the disallowance of Bills by Her Majesty. The Orders in Council also provided that in the event of any Bill being passed making the Legislative Council elective wholly or in part, it should be reserved for Her Majesty's pleasure, and a copy of the Bill should be laid before both Houses of the Imperial Parliament for at least thirty days before Her Majesty's pleasure should be signified. It was further provided that no alteration in the constitution of the colony could be made unless the second and third readings of the Bill containing such alterations

should have been passed with the concurrence of two-thirds of the members for the time being of the Legislative Council and Legislative Assembly, and that such Bill be reserved for the signification of Her Majesty's pleasure thereon; also that all Bills for appropriating any part of the public revenue, or for imposing any new rate, tax, or impost, subject to certain limitations, should originate in the Legislative Assembly; the limitation referred to being that it should not be lawful for the Legislative Assembly to pass any such Bill that had not first been recommended to them by a message from the Governor, sent during the session in which such Bill should be passed. The power of the Legislative Council to alter Money Bills is doubtful, and although it has done so, objection to the course has always been taken by the Queensland Legislative Assembly.

In 1867 the Queensland Parliament passed an Act which consolidated the law relating to the Constitution and embodied the Orders in Council with the exception of two sections, namely, that relating to the giving or withholding of Her Majesty's assent to Bills, and the one referring to the power of altering the Constitution.

This Act is now the Constitution Act of Queensland, the amendments introduced later being of a comparatively unimportant character. The last Governor of Queensland was Sir Herbert Charles Chermiside, but his term of office ceased in October, 1904, and the duties of administration are at present carried on by the Lieutenant-Governor, Sir H. M. Nelson.

The Legislative Council consists of thirty-seven members nominated by the Governor in Council, and contingent on the observation of certain rules of the Chamber, such as attendance at each session, &c.; these members hold their seats for life. The Legislative Councillors receive no remuneration for their services, but are allowed a free railway pass from the date of being sworn in. The qualification has already been stated.

The number of members to be elected to the Legislative Assembly has been altered by various Acts of Parliament. At present there are seventy-two members, representing sixty-one electorates, eleven returning two members each, while the remainder are single electorates. Members of the Assembly receive a remuneration of £300 per annum each, with free railway pass and allowances for travelling expenses. To be qualified for membership of the Legislative Assembly a person must be absolutely free, and qualified and registered as a voter in and for any electoral district. The disqualifications preventing election to the Assembly are:—being a minister of religion; being at the time a member of the Legislative Council; holding any office of profit under the Crown except as member of the Ministry, and excepting also such officers, not more than two, whom the Governor may declare capable of being elected; being in receipt of a pension from the Crown (officers of Her Majesty's army and navy excepted). Every male of the full age of 21 years, who is a natural born or naturalised subject of His Majesty, or legally made a denizen of Queensland, is entitled to have his name entered on the electoral roll, subject to the following qualifications:—(a) Six months

residence in an electoral district; (b) Freehold estate of the clear value of £100; (c) Household occupation for six months of clear annual value of £10; (d) Leasehold estate. Natives of China, South Sea Islands and India, and Australian aborigines are entitled to vote under freehold qualifications. The persons disqualified comprise members of the military and police forces, police magistrates and clerks of petty sessions, insane, and persons tainted with crime.

Since the introduction of responsible government in Queensland there have been thirteen complete Parliaments. The first Parliament was opened on the 29th May, 1860, and dissolved on the 20th May, 1863. The third session of the fourteenth Parliament was opened on the 20th September, 1904. At the general election for the Legislative Assembly in 1904, the total number of electors on the roll was 103,943. The number of electors recording votes was returned at 60,710, and the percentage of voters to the total enrolment in contested districts was 67·9.

#### SOUTH AUSTRALIA.

THE Constitution of the state of South Australia is based upon the Imperial Statute 13 and 14 Vic. c. 59. Under section 32 of that Act the Governor and Legislative Council established thereby were empowered to alter, from time to time, the provisions and laws in force under the said Act for the time being, and to constitute separate Legislative Chambers, in place of the said Legislative Council. The present form of Constitution was embodied in "An Act to establish a Constitution for South Australia, and to grant a civil list to Her Majesty," passed by the old Legislative Council in 1855, and reserved for the signification of Her Majesty's pleasure in January, 1856. By proclamation dated October 24th, 1856, Her Majesty's assent to the Constitution Act, No. 2 of 1855-6, was made known in the colony. This statute provided for two Houses of Parliament—a Legislative Council and a Legislative Assembly. The Legislative Council, which consisted of eighteen members, was elected by the whole province, voting as a single electorate. Each member was elected for twelve years, but it was provided that at the expiration of each period of four years the first six members on the roll, their places in the first instance having been determined by ballot, should retire, and an election take place to supply the vacancies. The names of the members who were elected to fill their places were inscribed at the bottom of the list, and at the end of a further term of four years six others retired, and the same order was observed in placing the newly-elected members. In this way frequent changes were made in the personnel of the Council, in addition to those which occurred by death, resignation, or other causes, such as bankruptcy, etc. By an amendment in the Constitution it was provided that at the end of three years from the 3rd May, 1902, three members from the central and two members from each of the other electoral districts should retire, and new members be elected to fill their seats. A similar number will thereafter retire

every three years, but it is provided that no member is necessarily to retire until he has sat for six years, except those elected to fill vacancies, who retire at the time when their predecessors would have retired. The qualification of a member for the Council consists in being of the full age of 30 years, a natural-born or naturalised subject of His Majesty, or legally made a denizen of the province, and a resident therein of the full period of three years. For an elector the age was fixed at 21 years, with a property qualification of a freehold estate of the value of £50 ; or a leasehold of £20 annual value, with three years to run ; or occupation of a dwelling house of £25 annual value, and being registered on the electoral roll of the province for six months prior to the election. The same qualification with regard to citizenship was demanded of both members and electors. By Act No. 236 of 1881 the number of members of the Council was increased to twenty-four, and the province divided into four electoral districts, each returning six members, but from the end of March, 1902, the membership was reduced to eighteen.

As originally constituted, the House of Assembly consisted of thirty-six members elected for three years. By an amendment of the Constitution Act the number was increased to fifty-four, but in accordance with the scheme of Parliamentary economy the House was reduced to forty-two members after the end of March, 1902. The qualification of a member was that he should be entitled to be registered as a voter in and for an electoral district within the province, and that he should have resided in the province for the full period of five years. All that was required of an elector was that he should be 21 years of age, a natural-born or naturalised subject of Her Majesty, and registered on the electoral roll of any electoral district for six months previous to the election.

By the Constitution Amendment Act of 1894 the franchise was extended to women.

The disqualifications for both Houses comprise persons attainted of treason or convicted of felony who have not been pardoned, or who have not served their sentence, persons brought into the Northern Territory under the Northern Territory Indian Immigration Act of 1882, and persons residing in the Northern Territory who are not natural-born or naturalised subjects of His Majesty, of European nationality or citizens of the United States, naturalised as subjects of His Majesty, and insane persons.

The powers of both Houses of Parliament, with one important exception, are similar. The first clause of the Constitution Act requires that all Bills for appropriating any part of the revenue of the province, or for imposing, altering, or repealing any rate, tax, duty, or impost, shall originate in the House of Assembly. By an agreement between the two Houses, the Council may suggest amendments, and if acceptable the Assembly may embody them in a "money" Bill, but the Council has no power to force their acceptance on the Assembly.

The duration of Parliament is for three years, but the Governor, on the advice of his Ministers, or "*ex mero motu*," may dissolve it at any



time. Members of both Houses receive £200 per annum each, and a free pass over Government railways. As originally constituted, the Ministry was formed by five members of the Legislature—the Chief Secretary, the Attorney-General, the Treasurer, the Commissioner of Crown Lands, and the Commissioner of Public Works. Later on a sixth Minister was added to the number. Five of these were members of the House of Assembly and one of the Legislative Council. Under the terms of the Constitution Amendment Act of 1901 the number of responsible Ministers was reduced to four from the 31st March, 1902. The Ministers are removable by adverse vote of the Legislative Assembly, or if the contingency arose to require the exercise of the prerogative they may be dismissed by the Governor. The Ministry formulates the policy to be submitted to the Legislature, and advises the Governor as to his course of procedure. It also forms the Executive Council, over which the Governor "*ex officio*" is President, while the Lieutenant-Governor also occupies a seat. The present Governor of South Australia is Sir G. Le Hunte.

Since the inauguration of responsible Government there have been sixteen complete Parliaments. The first Parliament was opened on the 22nd April, 1857, and dissolved on the 1st March, 1860, while the seventeenth was opened on the 3rd July, 1902. The number of electors on the roll of the Legislative Council at the last general election in May, 1903, was 51,909, and of these, 37,918, or 73 per cent., recorded their votes. At the general election for the House of Assembly there were 77,147 males and 72,030 females on the rolls, or a total of 149,177, and of these, 53,471 males and 36,545 females recorded votes, the percentage of males voting being 69·3, and of females, 50·7.

#### WESTERN AUSTRALIA.

THE Bill enabling Her Majesty "to grant a Constitution to Western Australia," received the Royal assent on the 15th August, 1890. When the measure was first discussed in the Imperial Parliament strong opposition was aroused, chiefly owing to a misunderstanding of questions relating to the Crown lands. It was argued that to hand over the control of such a vast territory to the 45,000 inhabitants thinly scattered over it was a piece of political folly. But, through the exertions of the colonial delegates then in England, aided by the influence of Sir William Robinson, and supported by the assistance of the Agents-General of the other Australasian provinces, the final obstacles were swept away. In all essential points, the Constitution of Western Australia is similar to those of the other states of Australia.

The executive power is vested in the Governor, who is appointed by the Crown, and who acts under the advice of a Cabinet. The present Governor of Western Australia is Sir F. Bedford.

The legislative authority is vested in a Parliament, composed of two Houses—a Legislative Council and a Legislative Assembly.

After the establishment of responsible government, the members of the Upper House were, in the first instance, nominated by the Governor, but it was provided that, in the event of the population of the province reaching 60,000, the Chamber should be elective. This limit was reached in 1893, and the constitution was shortly afterwards amended so as to give effect to the proviso mentioned. There are at present thirty members of the Legislative Council, each of the ten electorates returning three members. The qualification for membership is as follows :—being (1) a man of 30 years of age and free from legal incapacity ; (2) a resident in Western Australia for at least two years ; (3) a natural-born subject of His Majesty, or naturalised for five years and resident in Western Australia during that period. The disqualifications are :—being (1) a member of the Legislative Assembly ; (2) a Judge of the Supreme Court ; (3) Sheriff of Western Australia ; (4) a clergyman or minister of religion ; (5) an undischarged bankrupt ; (6) attainted of treason or convicted of felony in any part of the King's dominions ; (7) directly or indirectly concerned in any contracts for the public service, except as member of an incorporated trading society ; (8) holding an office of profit under the Crown other than that of Minister, President of the Council, or officer of His Majesty's sea or land forces on full, half, or retired pay.

Members of the Legislative Council are paid at the rate of £200 per annum, and are provided with free railway passes. At the expiration of two years from the date of election, and every two years thereafter, the senior member for the time being for each province retires. Seniority is determined (1) by date of election ; (2) if two or more members are elected on the same day, then the senior is the one who polled the smaller number of votes ; (3) if the election be uncontested, or in case of an equality of votes, then the seniority is determined by the alphabetical precedence of surnames, and, if necessary, of Christian names.

The electoral qualification for the Upper House is as follows :—Being (1) at least 21 years of age, and not subject to legal incapacity ; (2) a natural-born or naturalised subject of His Majesty resident in the state for twelve months, or a denizen of Western Australia ; (3) either (a) have possessed for at least one year before being registered in his electoral province a freehold estate of the clear value of £100 above all charges or encumbrances ; or (b) have been a householder for the last preceding twelve months of a dwelling of the clear annual value of £25 ; or (c) be a holder of a leasehold of the clear annual value of £25, the lease having eighteen months to run ; or (d) have been a holder of a leasehold for the last preceding eighteen months of the annual value of £25 ; or (e) be a holder of a lease or license from the Crown at an annual rental of at least £10 ; or (f) have his name on the electoral list of a municipality or Roads Board in respect of property in the province of the annual ratable value of £25. Foreigners or persons who are not

naturalised subjects of His Majesty, insane persons, and those who are in receipt of charitable aid, or any person attainted or convicted of treason, felony, or any infamous offence in His Majesty's dominions who has not served the sentence for the same, or received a pardon for the offence, are disqualified as electors.

For the Legislative Assembly in Western Australia there are fifty electorates, each returning a single member. The tenure of seat is three years, and members are paid at the rate of £200 per annum, with a free railway pass over all Government lines, and by courtesy the same privilege is extended to them on private lines. The qualification for membership is as follows :—being (a) a man of 21 years of age and free from legal incapacity ; (b) a natural-born subject of the King, or naturalised for five years, and resident in Western Australia for two years ; (c) resident in Western Australia for at least twelve months. A person is disqualified if (a) a member of the Legislative Council ; (b) a Judge of the Supreme Court ; (c) Sheriff of Western Australia ; (d) clergyman or minister of religion ; (e) an undischarged bankrupt or debtor whose affairs are in course of liquidation or arrangement ; (f) under attainder of treason or conviction of felony in any part of the King's dominions ; (g) directly or indirectly concerned in contracts for the public service except as member of an incorporated trading society. Paid officers under the Crown, except officers of His Majesty's sea and land forces on full, half, or retired pay, or political officers, are also ineligible.

The electoral qualification for the Legislative Assembly is as follows :—electors must be 21 years of age, natural-born or naturalised subjects of the King, and must have resided in the state for six months and been six months on the roll. They must also be resident in the district or hold freehold estate there of the clear value of £50, or be householders occupying a dwelling of the annual value of £10, or holders of an annual lease of the value of £10, or holders of a lease or license or Crown lands of an annual rental of £5, or have their names on the electoral list of a municipality or Roads Board in respect of property within the district. Electors for both Houses may be of either sex. Aborigines, natives of Asia and Africa, and persons of half-blood, are not entitled to vote except in respect of freehold qualifications.

Since the establishment of responsible Government in Western Australia there have been four complete Parliaments. The first Parliament was opened on the 30th December, 1890, and dissolved on the 1st June, 1894. The present Parliament commenced its sittings on the 28th July, 1904. At the general election in June, 1904, there were 108,861 males and 54,965 females on the roll, and the votes recorded by each sex numbered 43,285 and 23,500 respectively. The male vote in contested districts amounted to 49 per cent. of the enrolment, and the female vote to 47 per cent.

## TASMANIA.

THE Constitution of Tasmania is embodied in Act 18 Vic. No. 17, known as the "Constitutional Act," and in the amending acts subsequently introduced, viz., 23 Vic. No. 23, 34 Vic. No. 42, 48 Vic. No. 54, 49 Vic. No. 8, 54 Vic. No. 58, 60 Vic. No. 1, 60 Vic. No. 54, 62 Vic. No. 67, 64 Vic. No. 5, and 1 Edward VII Nos. 57, 58. A form of government is provided for, consisting of a Governor, appointed by the Crown, and a Legislative Council and House of Assembly, elected by the people. These constitute the "Parliament of Tasmania." Amongst the most important of the powers of the Governor are the appointment, according to law, of the members of the Executive, Ministers of the state, judges, commissioners, and other necessary officers. The Governor also possesses the prerogative of mercy, in the exercise of which he is guided by the advice of the Executive. He may dissolve the House of Assembly at any time; but he cannot adopt this procedure with the Legislative Council, the members of which are appointed for six years. The Governor, in the exercise of his powers, is generally supposed to consult the Executive Council; but in some cases he may act on his own authority, should he consider that circumstances demand such procedure. In all such cases, however, he is required to report immediately to the Imperial authorities, setting out the reasons for his action. The Governor is not permitted to leave the state for more than one month at a time without first obtaining His Majesty's sanction. The present Governor of Tasmania is Sir Gerald Strickland.

The Legislative Council consists of eighteen members, appointed for a term of six years. Members must be natural-born or naturalised subjects of His Majesty, not holding offices of profit under the Crown, and not less than 30 years of age. There are fifteen electorates, each returning a single member, with the exception of Hobart, which returns three, and Launceston two.

Electors for the Legislative Council must be natural-born or naturalised male subjects of His Majesty, 21 years of age, resident in Tasmania for twelve months, and possessing freehold of the annual value of £10, or leasehold of the annual value of £30, within the electoral district, or be graduates of any university in the British dominions, or associates of arts of Tasmania, or legal practitioners in the Supreme Court of Tasmania, or legally-qualified medical practitioners, or officiating ministers of religion, or officers or retired officers of His Majesty's land and sea forces not on actual service, or retired officers of the Volunteer Force of Tasmania.

The Legislative Council may, within constitutional limits, originate legislation in respect of any matter, with the exception of bills for appropriating revenue or imposing taxation. The Constitution, however, really leaves to either branch of the Legislature the task of determining the form and extent of its rights and privileges.

Members of the Legislative Council, and also of the House of Assembly, receive an honorarium of £100 each per annum.

The House of Assembly consists of thirty-five members, elected for three years. Members must be 21 years of age and natural-born or naturalised subjects of His Majesty. The following list of disqualifications applies to both Houses as regards right of election or membership:—(a) accepting office of profit under the Crown; (b) being a contractor for the Government, except as member of a company of more than six persons; (c) declaring allegiance to any foreign power; (d) holding the office of Judge of the Supreme Court; (e) being insane, attainted or convicted of treason, felony, or any infamous offence. The electoral qualification for the House of Assembly is as follows:—Every man of the age of 21 years, who is a natural-born or naturalized subject of His Majesty, and has resided in Tasmania for a period of twelve months, is entitled to have his name placed on the electoral roll, and to vote at an election of a Member of the House of Assembly for the district in which he resides.

An Act to confer the franchise on women has been reserved for the Royal assent.

Since the inauguration of responsible Government, there have been thirteen complete Parliaments in Tasmania. The first Parliament was opened on the 2nd December, 1856, and dissolved on the 8th May, 1861. The first session of the fourteenth Parliament opened on the 31st May, 1903. On the 31st March, 1902, the number of electors on the roll for the Legislative Council was 10,502. In contested electorates the number was 7,613, and of these, 4,919, or 64·6 per cent., recorded votes. On the 2nd April, 1903, there were 43,999 electors on the roll of the Legislative Assembly. At the election in contested districts the number of ballot-papers was 24,111. The votes recorded numbered 23,766, or 59·1 per cent. of the enrolment, and there were 345 informal ballot-papers.

#### NEW ZEALAND.

THE Act of the Imperial Legislature granting representative institutions to New Zealand was assented to in 1852. Under this Act the constitution of a General Assembly for the whole colony was provided for, to consist of a Legislative Council, the members of which were to be nominated by the Governor and a House of Representatives on an elective basis. By the Act of 1852 the colony was divided into six provinces, each presided over by an elective Superintendent, and with a separate Provincial Council, empowered to legislate except on certain specified subjects. These Provincial Councils, the number of which was afterwards increased to nine, remained as integral parts of the Constitution until 1876, when they were abolished by the General Assembly, that body having the power of amending the Constitution Act. The powers previously exercised by Superintendents and provincial officers were delegated to local boards called County Councils, or vested in the Governor. The present Governor of New Zealand is Lord Plunket.

The Governor is appointed by the Crown, but his salary and allowances are paid by the colony, the present salary being £5,000 per annum with allowances amounting to £2,000. Executive administration is vested in the Governor, and is conducted according to the principles of responsible government. The Governor can appoint or dismiss his Ministers, but his Ministers must possess the confidence of the majority in the House of Representatives. He can assent to bills or withhold assent therefrom, or reserve them for the signification of His Majesty's pleasure. He can summon, prorogue, and dissolve the colonial Parliament. He can send drafts of bills to either House for consideration, and can return bills to either House for specific amendment after they have been passed by both Houses, and before they are assented to or reserved by him. The Commission from the King delegates to the Governor certain powers of the royal prerogative, and provides for the constitution of an Executive Council to advise him in matters of importance, such Executive Council consisting of responsible Ministers for the time being. The number of members constituting the Legislative Council cannot be less than ten, but otherwise is practically unlimited. At present the number is forty-four. Councillors are remunerated for their services at the rate of £200 per annum, payable monthly, and actual travelling expenses to and from Wellington are also allowed. A deduction of £1 5s. per sitting day is made in case of absence, except through illness or other unavoidable cause, exceeding five sitting days in any one session. To be qualified as a member of the Council a person must be of the full age of 21 years, and a British subject either by birth or by Act of the Imperial Parliament or the Parliament of New Zealand. All contractors to the public service to an amount of over £50, and civil servants of the colony are ineligible. Prior to 1891, Councillors held their appointments for life, but on the 17th September of that year an Act was passed making seven years the period of tenure of a seat, though members may be reappointed. Two members of the Council are aboriginal native chiefs.

The House of Representatives consists of eighty members, of whom four are representatives of native constituencies. All the electoral districts for European representation, which number sixty-eight, return one member each, with the exception of the cities of Auckland, Wellington, Christchurch, and Dunedin, each of which returns three members. Representatives are remunerated for their services at the rate of £300 per annum, payable monthly, but £2 per day for every sitting day exceeding five is deducted on account of absence during the session not due to illness or other unavoidable cause. Travelling expenses to and from Wellington are also allowed. To be qualified for membership of the House of Representatives a person must be of the male sex, duly registered on the electoral roll, and free from the disabilities mentioned in Section 8 of the Electoral Act of 1893. All contractors to the public service of New Zealand to whom any public money above the sum of £50 is payable, directly or indirectly, in any one financial

year, as well as civil servants of the colony, are incapable of being elected, or of sitting and voting as members.

Every man or woman of the full age of 21 years, who is either a natural-born or naturalised British subject, and resident in the colony one year, and three months in one electoral district, is qualified to be registered as an elector and vote at elections of members for the House of Representatives. In the Maori districts, adult Maoris are entitled to vote without registration. Under the provisions of the Electoral Act of 1893, the franchise is extended to women of both races in accordance with the qualifications specified above, but women may not be elected as members of the House of Representatives. No person may be represented on more than one electoral roll. The Act also provides that the name of every qualified elector who fails to record his vote shall be removed from the roll after the election.

Since the passing of the Constitution Act conferring representative institutions upon the colony of New Zealand there have been fourteen complete Parliaments. The first Parliament was opened on the 27th May, 1854, and dissolved on the 15th September, 1855, and the fourteenth opened on the 22nd June, 1900, and dissolved on the 4th October, 1902. The first session of the fifteenth Parliament opened on the 29th June, 1903.

At the general election for the first Parliament, which took place in 1853, the population of the colony numbered 30,000, and the electors on the roll 5,934. At the last general election for the House of Representatives, in November, 1902, the electors on the roll numbered 415,789 of whom 185,944 were females. The male and female electors numbered respectively 229,845 and 185,944, and the male voters numbered 175,320, or 76·3 per cent. of the enrolment, while 138,565, or 74·5 per cent. of the females recorded their votes.

## POPULATION.

ON the 26th January, 1788, Captain Phillip arrived in Sydney Harbour, bringing with him an establishment of about 1,030 people all told. Settlement soon spread from the parent colony, first to Tasmania in 1803, and afterwards to other parts of the continent and to New Zealand. At the census of 1901 the population of Australasia, exclusive of aborigines and Maoris, was 4,545,967, distributed as follows:—

State.	Males.	Females.	Total.
New South Wales .....	710,005	644,841	1,354,846
Victoria .....	603,720	597,350	1,201,070
Queensland .....	277,003	221,126	498,129
South Australia .....	184,422	178,182	362,604
Western Australia .....	112,875	71,249	184,124
Tasmania .....	89,624	82,851	172,475
Commonwealth .....	1,977,649	1,795,599	3,773,248
New Zealand .....	406,992	366,727	772,719
Australasia .....	2,383,641	2,162,326	4,545,967

The figures are inclusive of half-caste aborigines living in a civilised condition, and if there be added an estimated population of 148,000 Australian aborigines in an uncivilised state and of 43,000 Maoris in New Zealand, the total population of Australasia at the date of the census would be about 4,737,000.

The growth of the population of Australasia from the date of the first settlement is shown in the following table. An official enumeration of the people was made in most of the years quoted:—

Year.	Commonwealth.		New Zealand.		Australasia.	
	Population.	Annual Increase per cent.	Population.	Annual Increase per cent.	Population.	Annual Increase per cent.
1788 .....	1,030	.....	.. .....	.....	1,030	.....
1801 .....	6,508	15·25	.....	.....	6,508	15·25
1811 .....	11,525	5·88	.....	.....	11,525	5·88
1821 .....	35,610	11·94	.....	.....	35,610	11·94
1831 .....	79,306	8·34	.....	.....	79,306	8·34
1841 .....	206,095	10·02	5,000	.....	211,095	10·23
1851 .....	403,889	6·98	26,707	18·24	430,596	7·39
1861 .....	1,153,973	11·07	99,021	14·00	1,252,994	11·27
1871 .....	1,668,377	3·75	256,393	9·98	1,924,770	4·39
1881 .....	2,252,617	3·05	489,933	6·69	2,742,550	3·00
1891 .....	3,183,237	3·52	626,658	2·49	3,809,895	3·34
1901 .....	3,773,248	1·71	772,719	2·12	4,545,967	1·78



The high rate prior to 1831 arose from the small numbers on which the increase was calculated; while between 1831 and 1841, it was due to the policy of state-aided immigration which was then in vogue. The discovery of gold, which proved a strong incentive towards emigration to Australia, accounted for the high rate during the period from 1851 to 1861. The rate of increase since 1861 has shown a regular decline during each decennial period, and from 1891 to 1901 the annual increase was only 1·78 per cent., which is but slightly in excess of the natural increase due to the excess of births over deaths.

The chief factor determining the increase of population in Australia prior to 1860 was immigration, and until recent years the states of Queensland and Western Australia gained more largely from this source than from births; but taking the whole period of forty-two years from 1862 to 1903 embraced in the following table, the two elements of increase compare as follows:—

Arrivals from abroad in excess of departures.....	782,809
Births in excess of deaths .....	1,986,999

The population of each state (exclusive of aborigines of full blood and nomadic half-castes) at the last five census periods, and at the 31st December, 1903, is shown below:—

State.	1861.	1871.	1881.	1891.	1901.	31st Dec., 1903.
New South Wales...	350,860	503,981	751,468	1,132,234	1,354,846	1,427,342
Victoria .....	540,322	731,528	862,346	1,140,405	1,201,070	1,208,854
Queensland .....	30,059	120,104	213,525	393,718	498,129	515,530
South Australia ...	126,830	185,626	279,865	320,431	362,604	368,823
Western Australia..	15,691	25,353	29,708	49,782	184,124	226,964
Tasmania .....	90,211	101,785	115,705	146,667	172,475	179,487
Commonwealth	1,153,973	1,668,377	2,252,617	3,183,237	3,773,248	3,926,990
New Zealand.....	99,021	256,393	489,933	626,658	772,719	832,505
Australasia ...	1,252,994	1,924,770	2,742,550	3,809,895	4,545,967	4,759,495

In order to show the great differences in the growth of the population of the individual states during the last ten years, the appended table has been prepared, giving the population at the end of each year since 1894. In this table aborigines are included:—

Year.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	New Zealand.	Australasia.
1894	1,239,350	1,182,661	428,540	347,919	82,014	153,292	686,128	4,119,704
1895	1,262,370	1,186,321	441,110	351,468	101,143	165,560	698,706	4,196,478
1896	1,278,970	1,180,561	450,900	352,186	137,796	169,844	714,162	4,278,809
1897	1,301,780	1,182,061	460,430	352,987	161,694	164,873	729,066	4,353,251
1898	1,323,130	1,183,331	471,510	355,780	167,819	168,746	743,463	4,413,770
1899	1,344,080	1,189,741	482,400	359,890	170,651	172,572	756,505	4,475,829
1900	1,364,590	1,197,477	498,250	361,757	179,703	172,979	768,278	4,548,089
1901	1,379,581	1,211,163	511,086	365,783	194,109	174,880	787,667	4,622,643
1902	1,407,021	1,211,721	515,960	366,660	213,827	177,465	807,959	4,700,713
1903	1,431,629	1,209,125	520,667	368,628	226,964	179,487	832,505	4,769,190

The average annual rates of increase in the various states during each period of ten years from the beginning of 1862 to the end of 1901, and for the years 1902-3 were as follow :—

State.	Average Annual Rate of Increase.				
	1862-71.	1872-81.	1882-91.	1892-1901.	1902-3.
	per cent.	per cent.	per cent.	per cent.	per cent.
New South Wales .....	3·76	4·21	4·04	1·73	1·87
Victoria .....	3·27	1·65	2·78	0·45	*0·08
Queensland .....	13·80	6·13	5·83	2·48	0·93
South Australia .....	3·88	4·43	1·30	1·16	0·42
Western Australia .....	4·92	1·70	5·91	13·60	8·13
Tasmania .....	1·21	1·50	2·51	1·43	1·45
Commonwealth .....	3·85	3·15	3·42	1·67	1·30
New Zealand .....	10·43	6·49	2·39	2·19	2·81
Australasia .....	4·52	3·67	3·24	1·76	1·56

\* Rate of decrease.

The total populations, at the end of each of the last ten years, of the six states which form the Australian Commonwealth are given below :—

1894 .....	3,433,576	1899 .....	3,719,324
1895 .....	3,497,772	1900 .....	3,774,761
1896 .....	3,559,647	1901 .....	3,835,986
1897 .....	3,624,195	1902 .....	3,892,784
1898 .....	3,670,307	1903 .....	3,936,685

The following table gives the total increase in each state during the forty-two years, 1862-1903, distinguishing the natural increase arising from the excess of births over deaths from the increase due to the excess of arrivals over departures :—

State.	Excess of—		Total Increase.
	Births over Deaths.	Immigration over Emigration.	
New South Wales .....	733,967	339,684	1,073,651
Victoria .....	660,401	6,924	667,325
Queensland .....	231,042	255,258	486,300
South Australia .....	229,000	12,993	241,993
Western Australia .....	40,708	170,555	211,263
Tasmania .....	91,881	(- )2,605	89,276
Commonwealth .....	1,986,999	782,809	2,769,808
New Zealand .....	438,800	294,684	733,484
Australasia .....	2,425,799	1,077,493	3,503,292

(-) Excess of Emigration over Immigration.

The information conveyed by the above figures is important, as illustrating, not only the movement of population, but also the effect upon immigration of local influences, such as the attraction of liberal land

laws, the fertility of the soil, the permanence of employment, and the policy of assisted immigration. But a bare statement of the gross increase to each state from immigration is apt to be misleading, since the original density of population must be deemed a factor affecting the current of immigration. The following figures show the density of population per square mile in each state at the time of taking the census on the last five occasions and also at the close of 1903 :—

State.	1861.	1871.	1881.	1891.	1901.	31st Dec., 1903.
New South Wales.....	1·13	1·62	2·42	3·65	4·36	4·61
Victoria .....	6·15	8·32	9·81	12·98	13·66	13·76
Queensland .....	0·04	0·18	0·32	0·59	0·75	0·78
South Australia .....	0·14	0·20	0·31	0·35	0·40	0·41
Western Australia.....	0·02	0·03	0·03	0·05	0·19	0·23
Tasmania .....	3·44	3·88	4·41	5·59	6·57	6·85
Commonwealth .....	0·39	0·56	0·76	1·07	1·27	1·32
New Zealand .....	0·95	2·45	4·69	6·00	7·39	7·97
Australasia .....	0·41	0·63	0·89	1·24	1·48	1·55

At the close of the year 1903 the population of Australasia, including the native races, only reached a density of 1·61 persons per square mile—a rate which is far below that of any other civilised country; and excluding Australian aborigines and Maoris, the density was only 1·55 per square mile. But a comparison of the density of population in Australasia with that in older countries of the world is of little practical use, beyond affording some indication of the future of these states when their population shall have reached the proportions to be found in the old world. The latest authoritative statements give the density of the populations of the great divisions of the world as follows :—

Continent.	Area in square Miles.	Population.	Persons per square Mile.
Europe .....	3,742,000	372,925,000	99·66
Asia .....	17,101,000	830,558,000	48·57
Africa .....	11,510,000	170,050,000	14·77
America .....	14,805,000	132,718,000	8·96
Australasia and Pacific Islands.	3,457,000	5,907,000	1·71
Polar Regions.....	1,732,000	82,000	0·05
The World .....	52,347,000	1,512,240,000	28·89

From the earliest years of settlement there was a steady if not powerful stream of immigration into these states; but in 1851, memorable for the finding of gold, the current was swollen by thousands

of men in the prime of life who were attracted to the shores of Australia by the hope of speedily acquiring wealth. By far the greater number of these new arrivals settled in Victoria, which had just been separated from New South Wales, and for some years afterwards Victoria had an unprecedented addition to its population. The vast changes which took place will be evident when it is stated that in 1850, just prior to the gold rush, the population of the northern and southern portions of New South Wales was :—

Port Phillip (afterwards Victoria) .....	76,162
Remaining portion of the Colony .....	189,341

While five years afterwards the population of each was :—

Victoria .....	364,324
New South Wales .....	277,579

Victoria enjoyed the advantage in population and increased its lead yearly until 1871, when its inhabitants exceeded in number those of New South Wales by no less than 227,547. But from that time almost every year showed a nearer approach in the numbers of the inhabitants of the two states, until at the census of 1891 Victoria had a lead of only 8,171, while at the end of that year New South Wales had the greater population by about 4,241. At the 31st December, 1903, the parent state had increased its lead to 222,504. In considering the question of increase of population, attention should be paid to the density as well as to the actual number of the population; in regard to the case in point, the density of Victoria is 13·76 per square mile, and in New South Wales only 4·61.

New Zealand and Queensland, and Western Australia also, in recent years, owe much of their remarkable progress to the discovery of gold. In New Zealand the gold fever broke out in 1861, when the population numbered only 99,021, and the period of its activity extended over many years. At the end of 1903 the population had reached 832,505 souls, exclusive of Maoris, or more than eight times that of 1861. In Queensland the attractive force of the goldfields was exerted at a later date, and was a powerful factor in stimulating the growth of population in that state; while the development of Western Australia during the past thirteen years has been wholly due to the gold deposits discovered there, the population increasing from the small number of 46,290 at the end of 1890 to 226,954 at the close of 1903. The great rush of a few years ago has moderated considerably, but the net increase by excess of immigration over emigration during 1903 amounted, nevertheless, to 9,716; and in view of the vast mineral possibilities of the state it will not be surprising if fresh discoveries should at any time be made, and immigration on an extensive scale again set in.

Much of the increase of population, especially in New South Wales, Victoria, Queensland, and New Zealand, was due to the state policy of assisted immigration. The following table shows the number of all

immigrants introduced into Australasia either wholly or partly at the expense of the state, up to the end of 1903 :—

State.	Prior to 1881	1881 to 1903.	Total.
New South Wales .....	177,234	34,738	211,972
Victoria .....	140,102	.....	140,102
Queensland .....	52,899	117,139	169,538
South Australia .....	88,050	7,298	95,348
Western Australia.....	889	6,439	7,328
Tasmania.....	18,965	2,734	21,699
Commonwealth .....	477,639	168,348	645,987
New Zealand .....	*100,920	14,658	*115,578
Australasia .....	578,559	183,006	761,565

\* Exclusive of a number prior to 1870, of which no record can be found.

Queensland and Western Australia are the only states that at present assist immigrants ; New South Wales ceased to do so in 1888, Victoria practically ceased assisted immigration in 1873, South Australia in 1886, Tasmania and New Zealand in 1891.

The following table shows the increase of population by excess of immigration over emigration for the five decennial periods ended 1901, and for the years 1902-3 :—

State.	1862-61.	1862-71.	1872-81.	1882-91.	1892-1901.	1902-3.
New South Wales .....	98,141	50,807	120,651	164,690	7,904*	11,440
Victoria .....	370,324	51,270	11,045*	111,926	114,941*	30,286*
Queensland .....	12,349†	68,962	63,681	103,159	24,156	4,700*
South Australia .....	31,109	16,945	49,499	29,229*	17,122*	6,100*
Western Australia .....	5,656	5,778	131	15,842	123,279	25,525
Tasmania .....	8,134	4,604*	409	7,709	5,091*	1,028*
Commonwealth ..	520,713	188,158	223,326	374,097	2,377	5,149*
New Zealand .....	54,610‡	112,295	125,143	2,901	35,078	19,267
Australasia .....	575,323	300,453	348,469	376,998	37,455	14,118

\* Denotes excess of emigrants. † Increase during five years. ‡ Increase during seven years.

It will be seen that Australia has lost by excess of emigration over immigration during the past twelve years. For the period 1882-91 the gain from excess of immigration numbered 374,097 ; but in the ensuing period it fell to 2,377, and in four of the states there was an actual loss by emigration. From the experience of recent years, it would appear that Western Australia alone seems to attract intending emigrants from other countries, and but for the excess of arrivals over departures in that state the Commonwealth would have suffered a considerable net loss by emigration.

If the results for the last twelve years be compared, it will be seen that there was an exodus both from Victoria and South Australia, the

former losing 145,227 persons, and the latter 23,222, by excess of emigration, while Tasmania also lost 6,119 persons from the same source. The gain in the other states of the Commonwealth was very limited, with the exception of Western Australia, where there was a net increase of 148,804 persons; the remaining states showed an increase of only 22,992 persons. The following table shows the increase of population by excess of arrivals over departures in each state for the twenty-two years ending 1903:—

Year.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
1882	16,034	6,563	17,043	*3,679	94	587	36,642	3,489	40,131
1883	27,278	6,597	34,371	4,266	436	669	73,637	10,029	83,666
1884	23,944	8,525	18,620	275	871	816	53,051	9,321	62,372
1885	24,829	9,027	7,056	*9,280	1,628	*388	32,872	*2,690	30,182
1886	18,073	15,436	7,695	*8,819	3,738	*302	35,821	996	36,817
1887	7,202	15,445	11,527	*3,008	2,049	1,797	35,012	977	35,989
1888	6,633	25,757	5,651	*8,325	*1,196	*383	28,137	*9,175	18,962
1889	8,241	9,794	4,340	*2,348	580	1,175	21,782	*4,013	17,769
1890	15,298	9,973	*769	1,863	1,569	415	23,349	*2,828	25,521
1891	17,158	4,809	*2,375	*174	6,073	3,303	28,794	*3,205	25,589
1892	3,969	*11,058	*727	2,036	4,473	*3,846	*5,153	4,958	*195
1893	*1,560	*12,484	231	3,030	5,223	*2,995	*8,555	10,412	1,857
1894	919	*12,698	1,891	*2,347	15,912	*152	3,525	2,253	5,778
1895	*840	*14,410	2,848	*3,055	18,360	*711	2,192	895	3,067
1896	*3,967	*22,134	818	*5,247	35,891	1,582	6,943	3,276	10,219
1897	*173	*13,754	1,240	*4,767	22,520	1,792	6,858	2,752	9,610
1898	1,789	*11,127	3,390	*1,395	3,864	2,152	*1,327	2,696	1,369
1899	390	*8,020	3,135	*844	*9	1,356	*3,992	1,887	*2,105
1900	*1,518	*7,828	6,796	*3,463	5,843	*2,554	*2,724	*573	*3,297
1901	*6,913	*1,428	4,534	*1,070	11,202	*1,715	4,610	6,522	11,132
1902	6,901	*13,716	*3,102	*3,706	15,809	*86	2,100	7,992	10,092
1903	4,539	*16,570	*1,598	*2,394	9,716	*942	*7,249	11,275	4,026

\* Denotes excess of departures.

The great bulk of the movement of population within recent years, shown above, is only inter-state; and it is evident that immigrants are not attracted to these shores from abroad, the long sea voyage and cost of passage probably being the chief deterring reasons.

#### CENTRALISATION OF POPULATION.

One of the most notable problems in the progress of modern civilisation is the tendency of the population, everywhere exhibited in the chief countries of the world, to accumulate in great cities. Not only is this apparent in England, France, and other countries where the development of manufactures has brought about an entire change in the employments of the people, and has necessarily caused the aggregation of workers in towns, but it is seen also in the United States, the most favoured country for the agricultural labourer.

The progress of the chief cities of Australasia has been remarkable, and has no parallel among the cities of the old world. Even in America the rise of the great cities has been accompanied by a corresponding increase

in the rural population, but in Australia, perhaps for the first time in history, was presented the spectacle of magnificent cities growing with marvellous rapidity, and embracing within their limits one-third of the population of the states of which they are the seat of government. The abnormal aggregation of the population into their capital cities is a most unfortunate element in the progress of these states, and as regards some of them is becoming more marked each year.

One satisfactory feature in connection with the growth of population in the chief cities of Australia is that, until very recently, such increase did not take place through absorption of the rural population. In all new countries the tendency has been for immigrants to settle in or near the principal towns which mostly lie near the seaboard, and the fact that these states possess no good navigable waterways leading from the interior tends still further to the aggregation of population in the cities.

The population of the chief cities of Australasia and the estimated numbers of their inhabitants at the various census periods, and at the close of 1903, are shown in the following table, which illustrates the remarkable progress referred to:—

City.	1841.	1851.	1861.	1871.	1881.	1891.	1901.	1903.
Sydney .....	22,973	53,924	95,789	137,776	224,989	333,238	487,900	511,080
Melbourne .....	4,479	23,143	139,916	206,780	282,947	490,896	494,129	501,480
Brisbane .....	4829	2,543	6,051	15,029	31,109	93,667	119,428	124,463
Adelaide .....	78,480	114,577	18,303	42,744	103,864	133,252	162,261	168,066
Perth .....	.....	.....	.....	5,244	5,822	8,447	26,274	46,400
Hobart .....	.....	.....	19,449	19,062	21,118	33,460	34,026	34,917
Wellington .....	.....	.....	.....	7,906	20,563	33,224	49,344	53,082

\* In 1846. † In 1840. ‡ In 1850.

The aggregation of population is most marked in the cases of Adelaide and Melbourne, while Sydney is also conspicuous. The other cities are not so remarkable, the proportion of the people resident in Wellington especially being very small. The proportion of population in each capital compared with that of the whole state at the last four census periods, and on the 31st December 1903, is shown below.

City.	1871.	1881.	1891.	1901.	1903.
	per cent.	per cent.	per cent.	per cent.	per cent.
Sydney .....	27·34	29·93	33·86	35·90	35·70
Melbourne .....	28·27	32·81	43·05	41·13	41·47
Brisbane .....	12·51	14·57	23·79	23·73	23·90
Adelaide .....	23·03	37·11	41·59	44·75	45·57
Perth .....	20·68	19·60	16·97	19·70	20·44
Hobart .....	18·76	18·25	22·81	20·08	19·45
Wellington .....	3·08	4·20	5·30	6·39	6·38

Although Wellington is the capital of New Zealand, it is exceeded in population by Auckland and Christchurch, and probably by Dunedin.

Still, even in the largest of these cities—Auckland,—the population is not more than 8·70 per cent., and in the four together is only 29·25 per cent. of that of the whole colony.

The following is a list of the cities and most important towns of Australasia, with their populations at the latest available dates. In the case of the capital cities, the populations are as at the 31st December, 1903; the dates to which the other figures refer are as follow:—New South Wales, 2nd February, 1903; Victoria, Western Australia, and New Zealand, 31st March, 1901; Queensland and Tasmania, 31st December, 1903; while the figures for South Australia show the mean populations for 1902. In all but the most important towns, where the suburbs are included, the populations quoted are those of the boroughs or municipal districts:—

City or Town.	Population.	City or Town.	Population.
<b>New South Wales—</b>		<b>South Australia—</b>	
Sydney .....	511,030	Adelaide .....	168,006
Newcastle .....	58,620	Port Adelaide .....	20,459
Broken Hill .....	27,160	Port Pirie .....	8,481
Parramatta .....	12,600	Mount Gambier .....	3,225
Goulburn .....	10,560		
Maitland .....	10,340	<b>Western Australia—</b>	
Bathurst .....	9,380	Perth .....	46,400
Orange .....	6,650	Fremantle .....	20,448
Albury .....	6,390	Kalgoorlie .....	6,632
Lithgow .....	6,130	Boulder .....	4,601
Tamworth .....	5,820	Coolgardie .....	4,249
Grafton .....	5,700	Albany .....	3,594
Wagga Wagga .....	5,030		
<b>Victoria—</b>		<b>Tasmania—</b>	
Melbourne .....	501,460	Hobart .....	34,917
Ballarat .....	43,823	Launceston .....	21,606
Bendigo .....	30,774	Queenstown .....	5,293
Geelong .....	18,289	Zeehan .....	5,252
Eaglehawk .....	8,367	Beaconsfield .....	2,658
Warrnambool .....	6,404		
Stawell .....	5,318	<b>New Zealand—</b>	
Castlemaine .....	5,703	Auckland .....	67,226
Maryborough .....	5,622	Christchurch .....	57,041
<b>Queensland—</b>		Dunedin .....	62,390
Brisbane .....	124,463	Wellington .....	53,062
Rockhampton .....	18,476	Napier .....	8,774
Townsville .....	10,960	Wanganui .....	7,329
Gympie .....	13,200	Nelson .....	7,010
Maryborough .....	12,000	Palmerston North .....	6,534
Toowoomba .....	10,600	Timaru .....	6,424
Ipswich .....	8,637	Invercargill .....	6,215
Mount Morgan .....	7,000	Oamaru .....	4,336
Charters Towers .....	5,500	New Plymouth .....	4,405
Toowong .....	5,025	Thames .....	4,009
Bundaberg .....	5,000		



The above statement shows clearly where the people have settled, for, excluding the capitals, there are only five cities in the whole of Australasia with a population of over 40,000, viz., Newcastle, 58,620; Auckland, 67,226; Dunedin, 52,390; Ballarat, 43,823; Christchurch, 57,041; and of these five, three are in New Zealand.

## AGES OF THE PEOPLE.

The ages of the people, as ascertained at the census of 1901, were as shown by the following statement, in which the population has been arranged in five-year groups. There is the same tendency in Australia as in other countries for the people to state their ages at the nearest decennial or quinquennial period, hence it is necessary to adjust the census figures before they can be stated under individual ages. The grouping in five-year periods, as indicated below, although not entirely satisfactory, is sufficiently accurate for practical purposes. The following table shows the ages of males, exclusive of aborigines:—

*Males.*

Age Group.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.
Under 5 .....	80,806	66,792	31,307	20,280	10,441	10,702	219,810	44,224
5 and under 10 ..	84,199	72,045	31,908	22,756	8,891	11,180	290,949	48,814
10 " 15 ..	81,522	67,374	29,005	22,193	7,505	10,649	218,308	43,106
15 " 20 ..	70,423	58,982	23,684	20,007	7,068	9,888	189,472	42,456
20 " 25 ..	12,754	10,429	4,880	3,618	1,967	1,764	35,352	8,559
25 " 30 ..	49,604	40,150	19,760	13,023	9,884	6,497	139,008	32,637
30 " 35 ..	56,273	45,458	23,634	13,771	15,832	7,276	162,234	35,307
35 " 40 ..	52,596	46,628	22,689	12,945	14,845	6,422	156,075	29,694
40 " 45 ..	52,335	45,715	22,083	12,013	12,441	6,262	151,849	24,301
45 " 50 ..	44,980	37,111	18,419	11,371	8,722	6,273	125,828	21,589
50 " 55 ..	33,388	24,126	13,045	9,083	5,220	3,760	88,523	19,184
55 " 60 ..	25,615	18,337	10,137	6,767	3,453	2,797	67,156	15,413
60 " 65 ..	19,684	15,337	7,981	5,386	2,311	1,906	52,565	13,711
65 " 70 ..	16,733	14,972	6,783	3,992	1,767	1,729	45,976	12,808
70 " 75 ..	13,005	15,977	4,131	2,872	1,101	1,392	38,478	10,180
75 " 80 ..	7,772	11,777	2,230	2,232	692	1,123	25,376	5,848
80 " 85 ..	2,578	5,732	950	1,290	290	755	12,605	2,295
85 " 90 ..	1,858	2,452	453	645	140	459	6,083	1,050
90 and over .....	800	775	143	247	36	199	2,300	375
Unspecified (children) .....	277	502	5	....	8	....	792	24
Unspecified (adults) ..	2,286	2,049	3,043	....	261	120	1,759	408
Aboriginal half-castes (unspecified) .....	....	....	773	....	....	....	773	....
Total .....	710,005	608,729	277,008	184,422	112,875	89,624	1,977,649	405,992

In the next table similar information is given regarding females.

*Females.*

Age Group.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.
Under 5 .....	78,553	65,163	30,657	19,817	10,234	10,163	214,617	42,482
5 and under 10 .....	81,946	70,438	30,947	22,612	8,856	10,864	225,708	42,422
10 " 15 .....	80,097	66,628	28,557	21,599	7,320	10,437	214,698	42,125
15 " 20 .....	70,736	59,712	22,792	20,162	5,849	9,063	188,314	42,358
20 " 21 .....	13,457	11,629	4,368	3,727	1,278	1,836	36,296	5,558
21 " 25 .....	51,361	45,969	16,818	13,813	6,001	6,313	140,295	23,377
25 " 30 .....	56,043	52,822	18,234	14,253	8,677	6,561	156,640	23,233
30 " 35 .....	46,097	48,160	15,958	12,368	7,298	5,576	136,047	27,272
35 " 40 .....	41,593	43,988	13,706	11,313	5,322	5,217	120,438	21,217
40 " 45 .....	33,436	33,546	10,710	9,696	3,391	4,467	95,146	17,347
45 " 50 .....	24,001	21,804	7,402	7,277	2,151	3,064	65,729	13,967
50 " 55 .....	19,327	17,589	6,042	5,673	1,673	2,379	52,588	11,991
55 " 60 .....	15,376	15,156	4,918	4,545	1,177	1,835	43,057	9,968
60 " 65 .....	12,192	14,288	3,957	4,026	908	1,726	37,096	8,017
65 " 70 .....	9,237	13,342	2,400	3,051	570	1,321	30,421	6,022
70 " 75 .....	5,292	8,359	1,382	2,230	279	910	13,412	3,266
75 " 80 .....	2,344	4,231	706	1,262	133	514	9,689	1,679
80 " 85 .....	1,574	2,065	343	698	56	302	5,083	852
85 and over .....	678	750	127	310	25	147	2,087	340
Unspecified (children) .....	44	376	11	....	15	....	446	15
Unspecified (adults) .....	447	1,380	253	....	31	27	2,138	193
Aboriginal half-castes (unspecified) .....	....	....	760	....	....	....	760	....
Total ....	644,841	597,350	221,126	178,182	71,249	82,851	1,795,599	396,727

In the following table will be found the ages of the total population, exclusive of aborigines.

## TOTAL POPULATION.

Age Group.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.
Under 5 .....	158,961	131,955	61,994	40,077	20,675	20,865	434,427	86,806
5 and under 10 .....	196,136	142,528	62,855	45,368	17,747	22,024	456,657	85,736
10 " 15 .....	161,679	134,002	57,662	43,792	14,826	21,136	432,996	85,225
15 " 20 .....	141,159	118,594	46,476	40,189	12,987	13,451	377,788	84,814
20 " 21 .....	26,211	22,058	9,198	7,345	3,235	3,600	71,647	17,142
21 " 25 .....	101,055	96,139	36,578	26,836	15,835	12,310	279,303	66,014
25 " 30 .....	112,316	96,290	41,918	28,024	24,499	13,337	318,574	68,540
30 " 35 .....	99,293	94,778	33,597	25,313	22,143	11,998	292,122	56,066
35 " 40 .....	93,928	90,103	35,768	23,226	17,763	11,479	272,337	45,518
40 " 45 .....	78,366	70,657	29,129	20,967	12,113	9,740	220,972	38,936
45 " 50 .....	57,339	45,930	20,448	16,310	7,871	6,354	154,262	33,131
50 " 55 .....	44,942	35,926	16,229	12,340	5,131	5,178	119,744	27,404
55 " 60 .....	35,010	30,493	12,809	9,881	3,438	3,381	96,652	23,674
60 " 65 .....	28,925	29,260	10,740	8,013	2,675	3,454	83,072	20,320
65 " 70 .....	22,242	29,019	6,531	6,923	1,671	2,613	63,890	16,188
70 " 75 .....	12,974	20,136	3,612	4,562	1,071	2,033	44,288	8,584
75 " 80 .....	6,432	9,963	1,664	2,552	423	1,270	22,594	3,964
80 " 85 .....	3,457	4,517	796	1,344	196	761	11,071	1,802
85 and over .....	1,478	1,525	270	557	61	346	4,237	715
Unspecified (children) .....	321	878	16	....	23	....	1,238	39
Unspecified (adults) .....	2,733	3,429	3,296	....	292	147	9,397	601
Aboriginal half-castes (unspecified) .....	....	....	1,533	....	....	....	1,533	....
Total ....	1,354,846	1,301,070	498,129	362,804	184,134	172,475	3,773,248	772,719

Of the total population of Australasia, 53·03 per cent were over 21 years of age. The largest proportion of adults is to be found in

Western Australia, where they comprise 62·29 per cent. of the population; and the lowest proportion in Tasmania, where they represent 50·09 per cent. The following table shows the number of persons under 21 years of age, and those 21 and over, with the proportion of adults of each sex to the total population in the several states :—

State.	Under 21 years.			21 years and over.			Proportion per cent. of adults.	
	Males.	Females.	Total.	Males.	Females.	Total.	Males.	Female
New South Wales	329,533	324,833	654,366	380,472	320,006	700,480	53·59	49·62
Victoria	276,024	273,991	550,015	327,696	323,359	651,055	54·23	54·13
Queensland	120,730	117,862	238,591	155,491	103,004	258,495	56·29	46·74
South Australia	88,834	87,917	176,751	95,588	90,365	185,953	51·93	50·66
Western Australia	35,890	33,552	69,442	76,985	37,697	114,682	68·20	52·91
Tasmania	43,663	42,413	86,076	46,961	40,438	86,399	51·23	48·81
Commonwealth	894,683	880,068	1,774,751	1,082,193	914,771	1,996,964	54·74	50·97
New Zealand	181,777	177,985	359,762	244,215	188,742	432,957	55·22	51·47
Australasia	1,076,460	1,068,053	2,134,513	1,806,408	1,103,513	2,409,921	54·82	51·06

These figures show that the proportion of adults differs considerably in the various states. Western Australia has the largest percentage of males, a result due to the large accession of adult immigrants during recent years, and the same cause also slightly affected the proportion of females. The differences, however, will be more readily apprehended by considering the population in the conventional groups of dependent and supporting ages. The figures, therefore, have been arranged so as to show the number of males at the dependent ages from infancy to 15 years; at the supporting ages, from 15 to 65; in the old-age group, from 65 years upwards; and at the military ages, from 20 to 40 years :—

State.	Dependent Ages, up to 15 years.		Supporting Ages, 15 and under 65.		Old Ages, 65 and over.		Military Ages, 20 to 40 years.	
	Number.	Proportion of total male population.	Number.	Proportion of total male population.	Number.	Proportion of total male population.	Number.	Proportion of total male population.
New South Wales	246,079	34·79	434,325	61·39	27,093	3·82	223,652	31·61
Victoria	205,211	34·20	358,145	59·57	36,813	6·13	159,880	31·50
Queensland	92,220	33·76	173,046	63·34	7,916	2·90	92,946	34·02
South Australia	63,209	35·36	111,876	60·66	7,537	3·98	55,370	30·02
Western Australia	26,537	23·83	83,510	74·16	2,259	2·01	54,949	48·30
Tasmania	32,511	36·32	58,164	59·40	3,329	4·23	26,221	31·53
Commonwealth	609,067	33·99	1,214,066	61·68	85,192	4·33	644,518	32·74
New Zealand	130,738	32·24	255,604	63·02	19,318	4·74	130,496	32·18
Australasia	799,305	33·69	1,469,670	61·91	104,410	4·40	775,016	32·65

In Western Australia the males in the supporting ages represent 74·16 per cent. of the male population, while the average for the remaining states is only 60·92 per cent.; the male dependents in Western Australia constitute 23·83 per cent., and those who have reached old age only 2·01 per cent. of the total male population. In the other states the most marked difference is in the old age group, where Victoria shows by far the largest proportion. The proportion of population in the dependent groups ranges from 32·24 per cent. in New Zealand to 36·32 per cent. in Tasmania; the variation is a trifle greater in the supporting ages, the proportion for Tasmania being 59·40 per cent. as against 63·34 per cent. in Queensland. In the old age group there is a comparatively wider margin, the proportions ranging from 2·90 per cent. in Queensland to 6·13 per cent. in Victoria. Western Australia and Queensland show the greatest proportions of males at the military ages, the other states being remarkably even. On the 31st March, 1901, there were 644,500 men in the Commonwealth who could be called upon to perform military service, and 130,500 in New Zealand.

The female population of Australasia may be conveniently grouped in four divisions, namely, dependent ages from infancy to 15 years; reproductive ages, from 15 to 45; mature ages from 45 and under 65; and old ages from 65 years. The numbers of each class in the different states at the time of the census are shown below:—

State.	Dependent Ages, up to 15 years.		Reproductive Ages, 15 and under 45.		Ages of 45 and under 65.		Old Ages, 65 years and over.	
	Number.	Proportion of total female population.	Number.	Proportion of total female population.	Number.	Proportion of total female population.	Number.	Proportion of total female population.
		per cent.		per cent.		per cent.		per cent.
New South Wales .....	240,596	37·34	313,323	48·63	70,896	11·00	19,535	3·03
Victoria .....	202,274	33·96	296,236	49·57	68,837	11·56	29,947	4·91
Queensland .....	90,191	40·98	102,635	46·63	22,319	10·14	4,967	2·25
South Australia .....	64,028	36·93	85,132	47·78	21,421	12·02	7,601	4·27
Western Australia .....	26,410	37·09	37,816	53·11	5,914	8·31	1,063	1·49
Tasmania .....	31,514	38·06	39,033	47·13	9,063	10·97	3,194	3·85
Commonwealth .....	655,013	36·55	873,176	48·72	198,470	11·07	65,597	3·66
New Zealand .....	127,029	34·66	183,387	50·03	43,968	12·00	12,135	3·31
Australasia .....	732,042	36·23	1,056,563	48·94	242,438	11·23	77,732	3·60

The age constitution of the female population shows more general variation in the different states than that of the male population, but

Western Australia does not differ from the other states in any marked degree. In the dependent group there is a considerable margin, for while in Victoria this division comprises but 33·96 per cent. of the total female population, in Queensland it constitutes 40·98 per cent. In the reproductive ages Queensland has the smallest proportionate number, representing 46·63 per cent. of the population, as against 53·11 per cent. in Western Australia. The next age group embraces females aged 45 and under 65, and in Western Australia these comprise 8·31 per cent. only, as against 12·02 per cent. in South Australia. In the old age group Victoria has the largest proportion with 4·91 per cent., while Western Australia only shows 1·49 per cent.

From a consideration of the two preceding tables it will be evident that in Western Australia a fairly large element of the male population consists of married men whose wives and families are living elsewhere, for while the number of males above the dependent age is 85,769, the females of corresponding ages number only 44,793. This is borne out by the information referring to the conjugal condition of the people of Australasia, which appears later on in this chapter.

As regards some of the states great changes have taken place in the age constitution of the population during the ten years from 1891 to 1901, and a notable feature is the decline in the proportionate number of dependents under 15 years of age. This decline is general throughout Australasia, and when it is considered that 93 per cent. of the increase of population during the ten years was due to natural increase by excess of births over deaths, the decline in the birth rate is evidenced in a striking manner.

The proportion of the male population in the different groups at each census period was as shown below.

<i>Males.</i>						
State.	Under 15 years.		15 and under 65.		65 and over.	
	Per cent. of male population.		Per cent. of male population.		Per cent. of male population.	
	1891.	1901.	1891.	1901.	1891.	1901.
New South Wales .....	35·85	34·79	61·41	61·39	2·74	3·82
Victoria .....	33·37	34·30	62·68	59·57	3·95	6·13
Queensland .....	33·15	33·76	65·22	63·34	1·63	2·90
South Australia .....	38·37	35·36	58·33	60·66	3·30	3·98
Western Australia .....	28·73	23·83	67·59	74·16	3·68	2·01
Tasmania .....	37·39	36·32	57·06	59·40	5·55	4·28
Commonwealth .....	34·82	33·99	61·96	61·68	3·22	4·33
New Zealand .....	38·01	32·24	59·48	63·02	2·51	4·74
Australasia .....	35·34	33·69	61·56	61·91	3·10	4·40

There has been a decrease in the proportion of males at dependent ages in all the states with the exception of Victoria and Queensland.

The largest decrease is shown in Western Australia where the proportion has fallen from 28·73 per cent. in 1891 to 23·83 per cent. in 1901. The changes were more general in the supporting ages, for while South Australia, Western Australia, Tasmania, and New Zealand show increases, the proportions in the other states decreased. In 1891 Western Australia had the highest proportionate population at supporting ages with 67·59 per cent., but in 1901 this had been increased to 74·16 per cent., a proportion greatly in advance of that for any other state. In regard to the population which has reached old age, the proportions in most of the states have increased, and Victoria with 6·13 per cent. holds the position occupied in 1891 by Tasmania when 5·55 per cent. of the population of the latter state were aged 65 years and over.

The proportions of female populations in the various groups at the two periods under review were as follow :—

State.	Under 15 years.		15 and under 45.		45 and under 65.		65 and over.	
	Per cent. of female population.		Per cent. of female population.		Per cent. of female population.		Per cent. of Female population.	
	1891.	1901.	1891.	1901.	1891.	1901.	1891.	1901.
New South Wales .....	41·32	37·34	46·42	48·63	9·99	11·00	2·27	3·03
Victoria .....	36·05	33·96	48·46	49·57	12·58	11·56	2·91	4·91
Queensland ... ..	42·61	40·96	46·72	46·63	9·28	10·14	1·39	2·25
South Australia .....	40·47	35·93	44·78	47·78	11·41	12·02	3·34	4·27
Western Australia .....	41·89	37·09	46·45	53·11	9·76	8·31	1·90	1·49
Tasmania .....	40·99	38·05	44·27	47·13	11·22	10·97	3·52	3·85
Commonwealth .....	39·43	36·55	46·93	48·72	11·07	11·07	2·57	3·66
New Zealand .....	42·17	34·66	44·74	50·03	11·04	12·00	2·05	3·31
Australasia .....	39·89	36·23	46·57	48·94	11·06	11·23	2·48	3·00

The proportionate number of female dependents decreased in each of the states during the ten years, and the average for Australasia was only 36·23 per cent. in 1901 compared with 39·89 per cent. in 1891. In Queensland only does the proportion of women at reproductive ages show a decline during the period; the greatest increase is shown in Western Australia, where the proportion is now much higher than in any other state. There were many changes in the proportions of female population in the various states at ages from 45 to 65, but the general

average for Australasia is much the same, in fact the figures for the Commonwealth show exactly the same proportion as existed ten years ago. A general increase is noticeable in all the states regarding the number of females aged 65 and over, the only exception being Western Australia.

CONJUGAL CONDITION.

At a conference of statisticians held at Sydney, during February, 1900, it was decided to tabulate the conjugal condition of the people, as ascertained by the census of 1901, under the heads of "Never married," "Married," "Widowed," and "Divorced"; but this decision was not adhered to in South Australia, where the divorced were probably included under the heading of unmarried. For the sake of comparison a similar classification has therefore been made in the tabulation of the other states. The people who returned themselves as "divorced" were very few in number, and it is reasonable to assume that the numbers were wide of the truth, owing to the reluctance on the part of many people whose marriage bonds had been severed to return themselves as "divorced" in the census schedules.

The following table shows the number of males in each state under the headings of "Unmarried," "Married," and "Widowers"; and the proportion of each to the male population. The figures are exclusive of aborigines, and the proportions are calculated only on the number of those persons whose conjugal condition was set down :—

*Males.*

State.	Unmarried.		Married.		Widowers.		Total.
	Number.	Proportion of Male Population.	Number.	Proportion of Male Population.	Number.	Proportion of Male Population.	
		per cent.		per cent.		per cent.	
New South Wales ...	484,942	68·56	202,922	28·69	19,451	2·75	707,315
Victoria .....	405,977	67·25	177,629	29·42	20,114	3·33	603,720
Queensland .....	196,740	71·34	72,213	26·19	6,812	2·47	275,765
South Australia .....	124,566	67·54	54,754	29·69	5,102	2·77	184,422
Western Australia ...	77,567	68·91	32,063	28·48	2,932	2·61	112,562
Tasmania .....	60,952	68·24	25,807	28·89	2,560	2·87	89,319
Commonwealth ...	1,350,744	68·46	565,388	28·65	56,971	2·89	1,973,103
New Zealand .....	275,864	68·10	118,536	29·26	10,666	2·64	405,066
Australasia .....	1,626,608	68·40	683,924	28·76	67,637	2·84	2,378,169

The figures show that only 28·65 per cent. of the male population of the Commonwealth is married. The rates are fairly uniform throughout Australasia with the single exception of Queensland, where unmarried males form 71·34 per cent. of the male population. The following table shows similar information regarding the female population of Australasia :—

*Females.*

State.	Unmarried.		Married.		Widows.		Total.
	Number.	Proportion of Female Population.	Number.	Proportion of Female Population.	Number.	Proportion of Female Population.	
		per cent.		per cent.		per cent.	
New South Wales ...	403,034	62·54	206,186	32·00	35,207	5·46	644,427
Victoria .....	370,809	62·06	183,390	30·70	43,151	7·22	597,350
Queensland .....	138,568	62·91	71,469	32·45	10,218	4·64	220,255
South Australia .....	112,122	62·92	55,341	31·06	10,719	6·02	178,182
Western Australia ...	41,046	57·65	27,043	37·98	3,112	4·37	71,201
Tasmania .....	52,593	63·57	25,460	30·78	4,672	5·65	82,725
Commonwealth ...	1,118,172	62·2	568,889	31·71	107,079	5·97	1,794,140
New Zealand .....	230,524	62·94	117,839	32·17	17,902	4·89	366,265
Australasia .....	1,348,696	62·43	686,728	31·79	124,981	5·78	2,160,405

The smallest proportion of unmarried females is in Western Australia, where the number of adult males is relatively large. From the foregoing figures it will be seen that unmarried males are largely in excess of unmarried females in each state. Amongst the widowed, females largely outnumber males, as was to be expected from the higher death-rate and the proportionately larger number of males



remarried. The following table shows the excess of unmarried males 21 years of age and upwards, over unmarried females of like ages, and the number of unmarried females to 1,000 unmarried males of these ages. Age 21 is taken as the beginning of the marriageable period, and the figures include the widowed and divorced as well as those who have never been married :—

State.	Excess of Unmarried Males over Unmarried Females.	Number of Unmarried Females to 1,000 Unmarried Males.
New South Wales .....	58,893	668
Victoria .....	7,098	952
Queensland .....	49,898	398
South Australia .....	5,236	848
Western Australia .....	33,335	254
Tasmania .....	4,469	776
Commonwealth .....	158,929	691
New Zealand .....	32,705	688
Australasia .....	191,634	691

The proportion of unmarried females is lowest in Western Australia and Queensland, the two states which have gained most through immigration during the past ten years, and is highest in South Australia, Victoria, and Tasmania, where there has been a loss by excess of emigration. As the population of the two states first mentioned has been largely recruited from the other states, it is evident that the movement of population has been chiefly of unmarried males animated by a desire to better their position.

#### BIRTHPLACES.

One of the subjects of inquiry at the census of 1901, as at previous enumerations, was the birthplaces of the population. The result of the tabulation shows that while there are differences in the component parts of the population in the several states, these differences are slight, and the great majority of the people in Australasia—to the extent, indeed, of fully 95 per cent.—are of British origin. Probably the population of Australasia is more homogeneous than that of most European countries; for even in Queensland, where people of foreign descent are proportionately more numerous than in any of the other states, they only amount to 8·71 per cent. of the total population. The subjoined table shows in a condensed form the results of the tabulation of the

birthplaces of the population of each state, the figures being exclusive of aborigines :—

Birthplaces.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	New Zealand.
New South Wales .....	977,176	22,404	24,968	4,128	14,122	2,075	6,492
Victoria .....	66,019	875,775	10,272	10,334	39,491	7,949	12,563
Queensland .....	14,968	3,018	282,961	606	2,595	288	1,271
South Australia .....	22,069	21,924	2,384	271,671	16,250	887	1,575
Western Australia .....	887	1,467	199	956	52,363	96	190
Tasmania .....	7,577	15,363	1,308	819	1,750	136,029	2,729
Australia, State not specified ..	468	876	19	936	81	14	1,222
Total, Commonwealth ..	1,079,154	940,826	321,911	239,440	126,962	147,938	27,063
New Zealand .....	10,589	9,020	1,571	711	2,704	1,193	516,106
Total, Australasia .....	1,089,743	949,846	323,482	240,151	129,666	149,131	543,169
England .....	128,117	113,432	68,589	37,789	25,390	12,658	111,964
Wales .....	8,622	3,676					
Scotland .....	30,717	35,751					
Ireland .....	59,945	61,512					
Total, United Kingdom ..	220,401	214,871	126,159	66,892	41,551	19,815	205,111
India and Ceylon .....	2,957	1,939	1,476	710	842	332	1,396
Canada .....	1,063	995	404	190	267	87	1,439
Other British Possessions ..	1,983	1,617	857	439	871	108	1,697
Total, British Empire ..	1,316,097	1,168,768	452,378	348,352	173,187	169,583	752,492
German Empire .....	8,716	7,608	12,166	6,664	1,527	773	4,327
France and Possessions .....	2,129	955	370	225	290	56	610
Russia .....	1,202	954	454	251	400	37	484
Austria .....	667	404	240	162	418	23	1,674
Switzerland .....	454	908	441	104	118	19	333
Denmark and Possessions ..	1,366	1,022	2,161	202	339	155	2,739
Sweden and Norway .....	3,190	2,207	2,142	981	1,174	219	2,827
Italy .....	1,577	1,526	847	327	1,354	50	428
Other European Countries and Possessions ..	1,910	1,815	683	470	999	129	570
United States of America .....	3,130	2,135	1,315	523	1,035	224	1,671
Chinese Empire .....	9,903	6,230	8,472	3,253	1,475	484	2,902
Other Foreign Countries .....	948	323	11,964	335	1,238	44	246
Total, Foreign Countries ..	25,344	25,582	43,254	13,507	10,378	2,223	18,582
Born at Sea .....	1,967	1,564	634	539	317	152	1,393
Unspecified .....	1,438	5,156	330	206	242	487	442
Aboriginal half-castes .....	.....	.....	1,583	.....	.....	.....	.....
Total .....	1,364,346	1,201,070	496,129	362,904	184,124	172,475	772,719

It will be seen at a glance that natives of the Australasian states formed three-fourths of the population, and that the great majority of the Australasian-born population were natives of the particular state in which they were enumerated, the only exception being in the case of Western Australia. The proportion of the people born in the state in

which they were resident at the time of the census, of those born in the other states, and of the total Australasian-born population to the total population of each state, are shown below :—

State.	Percentage of Total Population of—		
	Natives of State of Enumeration.	Natives of other States.	Australasian-born Population.
New South Wales.....	72·20	8·32	80·52
Victoria .....	73·23	6·19	79·42
Queensland.....	57·01	8·19	65·20
South Australia.....	74·96	5·10	80·06
Western Australia.....	28·64	41·87	70·51
Tasmania.....	79·44	7·27	86·71
New Zealand .....	66·83	3·50	70·33

These figures show that proportionately the largest Australasian-born population is to be found in Tasmania, where nearly 80 out of every 100 of the inhabitants were born in the state, and over 86 per cent. were Australasians. In Queensland, on the contrary, more than one-third of the population were natives of countries outside Australasia, and only 57 per cent. were Queenslanders by birth. The low proportion of native-born in this state is due to the policy of state assisted immigration, which is still in force, the addition to the population from this source during the twenty-two years ended with 1903, amounting to 117,139 souls. The exodus of population from other parts of the Continent to Western Australia is evidenced in a striking manner, as persons born in the other Australasian provinces, comprised 42 per cent. of the total in that state. The following figures set forth still more clearly the extent to which each state is indebted for population to its neighbours :—

State.	Number of Natives of other six States enumerated.	Number of Natives enumerated in other six States.	Net gain from other States.	Net loss to other States.
New South Wales.....	112,099	74,089	38,010	.....
Victoria .....	73,196	136,638	.....	63,442
Queensland.....	40,602	22,746	17,856	.....
South Australia.....	17,544	65,079	.....	47,535
Western Australia .....	76,912	3,795	73,117	.....
Tasmania .....	12,488	30,537	.....	18,049
New Zealand .....	25,831	25,788	43	.....

Next to the Australasian-born population, natives of the United Kingdom were by far the most numerous class in each state. The following table shows the percentages of natives of England and Wales, Scotland, and Ireland to the total population of each state :—

State.	Natives of—			
	England and Wales.	Scotland.	Ireland.	United Kingdom.
New South Wales.....	9.58	2.27	4.43	16.28
Victoria .....	9.79	2.99	5.14	17.92
Queensland.....	13.82	4.02	7.58	25.42
South Australia.....	10.67	1.92	3.10	15.69
Western Australia ..	14.30	2.94	5.86	22.80
Tasmania .....	7.52	1.74	2.26	11.52
New Zealand .....	14.73	6.20	5.63	26.56
Australasia .....	11.18	3.30	5.02	19.50

The percentage of natives of the United Kingdom is highest in New Zealand, while of the Commonwealth States Queensland shows the highest proportion, a result only to be expected in view of the large number of assisted immigrants introduced during the last twenty years. Although natives of England and Wales are numerically stronger, if the composition of the population of the United Kingdom be taken into consideration, it will be seen that Scotch and Irish colonists are proportionately much more numerous than those of English birth. A curious feature is the apparent preference on the part of Irishmen for Queensland and Sootamen for New Zealand.

The number of natives of parts of the British Empire other than the United Kingdom and Australasia enumerated in these states was very small, amounting only to the following percentages of the total population :—In New South Wales, 0.44 per cent. ; in Victoria, 0.38 per cent. ; in Queensland, 0.55 per cent. ; in South Australia, 0.37 per cent. ; in Western Australia, 1.07 per cent. ; in Tasmania, 0.37 per cent. ; and in New Zealand, 0.54 per cent. ; average for Australasia, 0.47 per cent. Natives of Canada and of India and Ceylon make up the majority of this class, which numbered only 21,419 altogether. It is not considered necessary to give a complete tabulation of natives of all foreign countries, and only the more numerous are quoted. Immigrants from Germany formed by far the largest proportion. The Chinese are next in point of numbers, followed by Scandinavians, while natives of the United States, France and Italy are also fairly numerous. Polynesians constitute a considerable section of the community in Queensland, but are almost unknown in some of the other states. The percentages of the total population in each state of natives of Germany, of the Scandinavian Kingdoms (Sweden and Norway and

Denmark), and of the total foreign-born population, are shown in the subjoined table :—

State.	Percentage of—		
	Germans.	Scandinavians.	Total Foreign-born Population.
New South Wales .....	0·64	0·33	2·61
Victoria .....	0·64	0·27	2·15
Queensland .....	2·65	1·07	8·71
South Australia .....	1·84	0·28	3·73
Western Australia .....	0·83	0·81	5·65
Tasmania .....	0·45	0·22	1·29
New Zealand .....	0·55	0·64	2·41
Australasia .....	0·94	0·28	2·28

It will be seen that both Germans and Scandinavians are proportionately most numerous in Queensland, where together they amount to 3·72 per cent. of the population. Germans are also very numerous in South Australia, and Scandinavians in Western Australia and New Zealand.

The remainder of the population whose birthplaces were stated, is made up of those born at sea ; the persons whose birthplaces were unspecified numbered 8,301, and have been excluded from consideration in computing the proportions arrived at in these pages. The proportion of the population born at sea to the total population of each state is shown below :—

State.	Persons born at Sea. Per cent.
New South Wales .....	0·15
Victoria .....	0·13
Queensland .....	0·12
South Australia .....	0·15
Western Australia .....	0·17
Tasmania .....	0·11
New Zealand .....	0·16
Australasia .....	0·14

From the returns of those states where the people born at sea have been classified into those born of British and of foreign parentage, it appears that the great majority are of British parentage.

## NATIVE RACES.

At the census of 1901 only 48,248 aborigines were enumerated, of whom 40,880 were full-blooded and 7,368 half-castes. The following table shows the distribution of each class amongst the various states.

State.	Aborigines enumerated at Census of 1901.		
	Full-blooded.	Half-castes.	Total.
New South Wales .....	3,778	3,656	7,434
Victoria .....	271	381	652
Queensland .....	5,137	1,533	6,670
South Australia .....	26,433	690	27,123
Western Australia .....	5,261	951	6,212
Tasmania .....	.....	157	157
Total .....	40,880	7,368	48,248

These figures only represent aborigines enumerated at the census, and except in Victoria, Tasmania, and New South Wales, they must not be taken as indicating the strength of the aboriginal population. At the various mission stations and schools, numbers of the aboriginal population who have abandoned their wild habits are following settled occupations. This is more especially the case with half-castes, many of whom have received a rudimentary education and are in constant employment on farms and stations. In view of their civilised condition, a number of half-castes have been included with the general population of the states as follows:—New South Wales, 3,147; Victoria, 381; Queensland, 1,533; Western Australia, 951; and Tasmania, 157. The native aboriginal race is extinct in Tasmania, and practically so in Victoria where the number recorded was only 271. The aborigines in New South Wales totalled 7,434 at the census of 1901, and as their number was 8,280 ten years previously, they are apparently decreasing at a rate slightly in excess of 1 per cent. yearly. In Queensland, only 6,670 aborigines were enumerated, but their full strength is estimated at 25,000; while in South Australia, although 27,123 were enumerated, the total number cannot be far short of 50,000. The census of Western Australia included only those aboriginals within the bounds of settlement, and as large portions of this, the greatest in area of all the Australian states, are as yet unexplored, it is evident that the number shown, 6,212, gives no idea as to the total aboriginal population. It is estimated that the aborigines in Western Australia are fully 70,000 in number, which would make the total aboriginal population of the continent about 153,000. The difficulty of enumerating the aborigines, even in the civilised area of Australia, will be apparent when their migratory habits are considered; and as by far the greater portion of

their number lives outside the bounds of civilisation, in practically unexplored territory, this estimate of their numerical strength is advanced with the utmost diffidence. The Maoris, who are popularly supposed to be the original natives of New Zealand, are quite a different race from the aborigines of Australia. They are gifted with a considerable amount of intelligence, are quick at imitation, and brave even to rashness.

Their numbers, as ascertained at various census periods, were as follow:—

Year.	Males.	Females.	Total.
1881 .....	24,368	19,729	44,097
1886 .....	22,840	19,129	41,969
1891 .....	22,861	19,132	41,993
1896 .....	21,673	18,181	39,854
1901 .....	23,112	20,031	43,143

The figures for 1901 include 31 Morioris, who are supposed to be a branch of the same race as the Maoris. It is thought that both races came from the islands of the Pacific, but the Morioris preceded the Maoris by many years. They held possession until the arrival of the Maoris, whose superior numbers enabled them to overcome the original possessors and drive them from the mainland to the surrounding isles, and it is only in the Chatham Islands that a small remnant of their race is left.

In the totals given for 1896 and 1901 there are included 3,503 and 3,123 half-castes respectively, who were living as members of Maori tribes. It is said that when New Zealand was first colonised, the number of Maoris was fully 120,000; but this, like all other estimates of aboriginal population, is founded on very imperfect information. So far as the above table shows, their number has been almost stationary during the last twenty years; in the last quinquennial period there was an increase of 3,289 persons.

#### ALIEN RACES.

The number of coloured aliens enumerated in the Commonwealth at the census of 1901 was 54,441, distributed amongst the various states as follows. The figures in this table are not exact in the case of South Australia and Western Australia. The former state published part of the information only, and there are included among the "others" 266 persons who are probably coloured, but in regard to whom there is no certainty. Western Australia did not publish the information, and with the exception of the Chinese and Japanese, the persons shown in the table may or may not be coloured, since, although the persons enumerated were born in a country such as India, where the aboriginal natives are coloured, it does not necessarily

follow that they were also of coloured race, and some of them certainly were persons of European origin. It may be reasonably assumed, however, that the great majority of those shown were coloured.

State.	Chinese (full- blood.)	Japanese.	Hindoos and Cingalese.	Pacific Islanders.	Others.	Total Coloured Aliens.
New South Wales .....	10,222	161	1,681	467	1,261	13,792
Victoria .....	6,347	55	789	2	435	7,628
Queensland .....	8,587	2,269	939	9,327	1,787	22,909
South Australia .....	3,359	205	439	2	453	4,458
Western Australia .....	1,521	864	833	31	1,817	5,066
Tasmania .....	506	...	...	...	82	588
Commonwealth .....	30,542	3,554	4,681	9,829	5,835	54,441

These figures show that coloured aliens number 14·43 per 1,000 of the population (exclusive of aborigines) in the Commonwealth. The highest proportion is found in Queensland, where large numbers of Pacific Islanders have been imported to work on the sugar plantations. The coloured aliens in that state number 46·13 per 1,000 of the population; in Western Australia, 27·51; in South Australia, 12·29; in New South Wales, 10·18; in Victoria, 6·35; and in Tasmania, 3·41 per 1,000. Amongst the Chinese included in the table there are a certain number who were born outside the Chinese Empire. The figures for New South Wales include 282; Victoria, 187; Queensland, 142; South Australia, 129; Western Australia, 54; and Tasmania, 22.

The further immigration of Pacific Islanders to Australia is now restricted by the Pacific Islands Labourers Act. This Act is particularly directed against the continued employment of these aliens on the sugar plantations, and under its provisions only a certain limited number were allowed to enter Australia up to the 31st March, 1904. After that date their further immigration was prohibited, and all agreements for their employment must terminate on the 31st December, 1906, when any Pacific Islander found in Australia will be deported.

The influx of Hindoos and other Eastern races has long caused a feeling of uneasiness amongst the people of Australia, and restrictive legislation was already in force in some of the states prior to federation. One of the first measures passed by the Federal Parliament was the Immigration Restriction Act, which provides for the exclusion of any person who, when asked to do so, fails to write out and sign a passage of fifty words in a European language specified by an officer of the Customs. Other undesirable persons enumerated in the Act are debarred from entering the Commonwealth, and a further important clause prohibits the immigration of any person under a contract or agreement



to perform manual labour within the Commonwealth. Exemptions are allowed in the case of workmen whose special skill, in the opinion of the Minister, is required in Australia, and persons under contract to serve as crew of a vessel engaged in the Australian coasting trade if the rates of wages specified therein are not lower than the rates existing in the Commonwealth. During 1902 admission was refused to 653 persons, and in 1903 to 152 persons, of whom 618 and 136 respectively failed to pass the education test. The Act does not apply, however, to persons in possession of certificates of exemption, to His Majesty's land and sea forces, to the master and crew of any public vessel of any Government, to any person duly accredited by any Government, or to any person who satisfies an officer of the Customs that he has been formerly domiciled in the Commonwealth.

The number of Chinese in the various states had increased so rapidly prior to 1880 that it was deemed expedient by the Governments to enact prohibitive laws against the immigration of these aliens, and their migration from one state to another. In each of the states restrictive measures were passed, and in several of them a poll-tax was imposed, but as all these measures were superseded by the Immigration Restriction Bill the Chinese now in the Commonwealth are free to travel anywhere within its confines. The Chinese to whom admission was refused in 1902 numbered 459, and 99 in 1903. In New Zealand one Chinese passenger was allowed to every 100 tons, with a poll-tax of £10, until 1896, when the poll-tax was raised to £100, and the number of passengers restricted to one for every 200 tons burden. These stringent regulations have had the effect of greatly restricting the influx of this undesirable class of immigrants, and at the census of 1901 they numbered only 36,022, as against 42,521 ten years previously. The following table shows the number of Chinese in each state at the five last census periods: the figures for 1891 and 1901 including half castes:—

State.	1861.	1871.	1881.	1891.	1901.
New South Wales .....	12,988	7,220	10,205	14,156	11,263
Victoria .....	24,732	17,935	12,128	9,377	6,956
Queensland .....	538	3,305	11,229	8,574	9,313
South Australia .....	40	*	4,151	3,997	3,455
Western Australia .....	.....	*	145	917	1,569
Tasmania .....	.....	*	844	1,056	609
Commonwealth .....	38,298	28,460	38,702	38,077	33,165
New Zealand .....	.....	*	5,004	4,444	2,857
Australasia .....	.....	.....	43,706	42,521	36,022

\* Information not available.

The decrease in the Chinese population will be more apparent when it is stated that in 1901 they only numbered 7·92 per 1,000 of the population in Australasia as against 11·16 in 1891.

#### NATURALISATION.

Up to the 31st December, 1903, certificates of naturalisation were granted to aliens in the various states in accordance with enactments which did not differ materially, but with the passing of the Commonwealth Naturalisation Act this power was taken away from the states, and vested exclusively in the Commonwealth Government. The Act was assented to on the 13th October, 1903, but only came into operation from 1st January, 1904. No letters or certificates of naturalisation granted in the states after the coming into operation of the Federal law are to have any effect.

Under the Commonwealth Act, any person who had, before the passing of the Act, obtained a certificate of naturalisation in any state is deemed to be naturalised. Any person resident in the Commonwealth not being a British subject, and not being an aboriginal native of Asia, Africa, or the islands of the Pacific, excepting New Zealand, who intends to settle in the Commonwealth, and who has resided in Australia continuously for two years immediately preceding the application, or who has obtained in the United Kingdom a certificate of naturalisation, may apply to be naturalised.

An applicant under the first heading must produce, in support of his application, his own statutory declaration exhibiting his name, age, birth-place, occupation, residence, the length of his residence in Australia, and stating that he intends to settle in the Commonwealth, as well as a certificate signed by some competent person that the applicant is known to him and is of good repute. An applicant under the second heading must produce, in support of his application, his certificate of naturalisation and his own statutory declaration that he is the person named in the certificate, that he obtained it without fraud, that the signature thereto is genuine, and that he intends to settle in the Commonwealth.

The Governor-General, if satisfied with the evidence adduced, may in his discretion grant or withhold a certificate as he thinks most conducive to the public good, provided that he shall not issue the certificate until the applicant has taken the necessary oath of allegiance.

Any person to whom a certificate of naturalisation is granted shall be entitled to all political and other rights, powers and privileges, and be subject to all the obligations of a natural-born British subject, provided that where, by the provisions of any state Act, a distinction is made between the rights of natural-born British subjects and those naturalised in the state, the rights conferred by the Commonwealth Act shall be only those to which persons naturalised by the state Act are entitled. Under the previously existing Acts in New South

Wales, Victoria, and South Australia, aliens may hold and acquire both real and personal property, but may not qualify for any office, nor have any rights or privileges except such as are expressly conferred upon them, while in Queensland and Tasmania they may hold personal property, but lands for twenty-one years only. In Western Australia alone were they granted equal rights and privileges with natural born British subjects.

Any alien woman who marries a British subject shall be deemed to be thereby naturalised. Any infant, not being a natural-born British subject, whose father has become naturalised, or whose mother is married to a natural-born British subject or to a naturalised person, and who has at any time resided in Australia with such father or mother, shall be deemed to be naturalised.

On the whole, the conditions to be fulfilled under the Commonwealth Act do not differ greatly from those under the old state Acts, but the term of residence necessary is now two years, whereas in New South Wales it was five years, in South Australia six months, and in the other states no specified time. Under the Commonwealth Act Asiatics, Africans, and Pacific Islanders are refused the rights of naturalisation; previously only the Chinese were so treated in New South Wales, Queensland, and Western Australia. In Queensland it was necessary for an Asiatic or African alien to be married and have his wife living in the state, and to have resided in the state for three years. On naturalisation he became entitled to all privileges except that of becoming a member of the Legislature.

In New Zealand, every alien of good repute residing within the colony who desires to become naturalised may present a memorial signed by himself and verified upon oath, stating his name, age, birth-place, residence, occupation, and length of residence in the colony, and his desire to settle therein, together with all other grounds on which he seeks to obtain the rights of naturalisation, and apply for a certificate, which the Governor may grant if he thinks fit. After the letters of naturalisation have been received, and the oath of allegiance taken, the holder becomes entitled to all the privileges which are conferred upon subjects of His Majesty. Naturalised persons may hold and acquire both real and personal property, but may not qualify for any office.

Excluding Queensland, where the information was not ascertained, the number of naturalised foreigners in the Commonwealth at the census of 1901 was 10,910, distributed as follows:—New South Wales, 3,265 males, 354 females; Victoria, 3,304 males, 1,262 females; South Australia, 1,360 males, 545 females; Western Australia, 576 males, 101 females; Tasmania, 119 males, 24 females. In New Zealand the number of naturalised persons was 4,672. It is probable, however, that the above numbers are under-stated. Germans have availed themselves most largely of the privileges of naturalisation, having taken out about one-half of the certificates granted.

The number of persons naturalised in Australasia during 1903 distributed amongst the various states was as follows :—

State.	Germans and other German- speaking nations.	Scan- dinavians.	Chinese.	Others.	Total.
New South Wales ...	140	89	.....	171	400
Victoria .....	160	57	.....	180	397
Queensland .....	160	109	10	76	355
South Australia .....	16	14	.....	13	43
Western Australia ...	23	22	.....	30	75
Tasmania .....	54	13	69	13	149
Commonwealth...	553	304	79	483	1,419
New Zealand.....	161	56	3	56	276
Australasia .....	714	360	82	539	1,695

## VITAL STATISTICS.

### BIRTHS

THE total number of births in each state, and the rate per thousand of the population during the year 1903 are shown in the following table :—

State.	Births.			Birth-rate.
	Males.	Females.	Total.	
New South Wales.....	18,377	17,589	35,966	25·28
Victoria .....	15,115	14,454	29,569	24·45
Queensland .....	6,427	6,194	12,621	24·35
South Australia.....	4,484	4,024	8,508	23·41
Western Australia .....	3,433	3,266	6,699	30·27
Tasmania .....	2,570	2,510	5,080	28·61
Commonwealth .....	50,406	48,037	98,443	25·16
New Zealand .....	11,217	10,612	21,829	26·61
Australasia.....	61,623	58,649	120,272	25·41

Leaving out Western Australia, it will be observed that the birth-rates of the various states are fairly even amongst themselves. The comparatively high rate in the western state is due to the larger proportion of married women in its population. Taking the general average for the last three years (26·28), the birth-rate of Australasia will be found lower than that of most European countries, and very much below the former experience of these states, as shown by the following statement, which gives the number of births in each state and in the

whole of Australasia, in quinquennial periods from 1861 to 1900, and for the years 1901-3.

State.	1861-65.	1866-70.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
New South Wales	79,958	92,643	106,543	127,572	158,965	183,300	197,566	183,582	111,676
Victoria.....	123,353	131,052	136,363	132,347	140,258	172,307	180,852	155,437	91,023
Queensland .....	11,761	22,622	29,279	37,535	48,979	70,150	72,963	70,963	41,140
South Australia ..	30,472	35,067	36,398	46,310	56,618	58,200	53,093	47,179	26,566
Western Australia	3,362	3,724	4,033	4,611	5,446	7,096	10,242	22,399	13,649
Tasmania .....	15,454	14,679	15,313	17,165	21,425	23,710	24,794	23,404	15,095
Commonwealth	264,350	299,787	327,929	365,540	431,691	515,363	539,410	502,964	304,164
New Zealand ....	26,811	46,770	59,891	88,205	96,482	94,071	91,410	94,685	62,975
Australasia ..	290,961	346,557	387,820	453,745	528,173	609,434	630,820	597,649	367,139

The average birth-rates per thousand of population for each state during the same periods are given hereunder, and, together with the rates appearing elsewhere in this chapter, have been amended to agree with the latest estimates of population.

State.	1861-65.	1866-70.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
New South Wales	42·71	40·70	39·05	38·53	37·65	36·36	32·93	27·98	29·66
Victoria .....	43·30	39·27	35·99	31·43	30·76	32·72	30·94	26·06	25·11
Queensland .....	43·07	43·91	40·81	36·72	36·37	33·81	35·15	30·40	26·77
South Australia ..	44·14	40·60	37·24	38·23	38·52	34·43	31·46	26·54	24·51
Western Australia	37·69	33·52	31·30	32·97	34·57	36·33	30·73	23·73	30·43
Tasmania .....	33·30	29·65	29·72	31·54	35·02	34·59	32·30	26·20	23·64
Commonwealth	42·43	39·48	36·90	35·36	34·93	35·09	32·31	27·62	26·23
New Zealand ....	38·22	42·23	40·02	41·32	36·36	31·19	27·06	25·75	26·23
Australasia ..	42·01	39·83	37·35	36·38	35·19	34·42	31·54	27·31	26·23

It is a matter of common knowledge that for some years past the birth-rate in Australasia has been declining, and so important is the subject—not only as regards the growth of the population, but also as affecting general progress—that in 1899, and again in 1902, the author made a special investigation into the question of childbirth in Australia, but more particularly with reference to New South Wales. The conclusions arrived at with respect to that state, however, may be

held to obtain for all the others, seeing that the conditions of living do not differ materially in any of them. During the course of these investigations it was found that for all women the proportion of fecund marriages was decreasing; that amongst fecund women the birth-rate was much reduced as compared with what it was twenty years ago, and that the decline had been persistent and regular since 1885. Public interest was strongly aroused by the author's treatise on the subject, published in 1903, and a Royal Commission was appointed to investigate the causes which contributed to the decline in the birth-rate, and to inquire into the question of the mortality of infants. After numerous sittings and exhaustive inquiries, the Commission presented its report in March, 1904. The report is of too voluminous a character to admit of any other than the most general reference in this work, but its tenor was in thorough accord with the conclusions mentioned above. It was found that there had been a serious diminution of fecundity since 1889, due chiefly to the deliberate prevention of conception and the destruction of foetal life, and to pathological causes consequent upon the means used and the practices involved. In addition to enumerating the causes which have led to the decline in the birth-rate, the Commission tendered certain valuable suggestions as to the best means of counteracting the evil influences at work.

It would have been interesting to have compared the number of births to married women of specified ages at regular intervals from the date when the birth-rate first showed marked decline. Unfortunately, the information is not available for the different states, but the following figures, relating to New South Wales, possess strong interest. These show the number of legitimate births and the birth-rate per cent. among married women of various ages at each of the four decennial periods 1871, 1881, 1891, and 1901.

Age groups of married women.	Legitimate births.				Birth-rate per 100 married women.			
	1871.	1881.	1891.	1901.	1871.	1881.	1891.	1901.
15 and under 20 .....	741	1,099	1,377	1,443	50·10	51·90	47·91	56·23
20    "    25 .....	4,290	6,353	8,344	7,805	44·15	45·79	41·63	39·70
25    "    30 .....	5,918	7,553	11,333	9,742	40·75	40·52	35·27	29·87
30    "    35 .....	4,340	5,946	8,022	7,843	33·67	33·36	29·22	22·63
35    "    40 .....	3,019	4,410	5,336	5,711	27·04	27·36	23·63	17·25
40    "    45 .....	1,027	1,645	2,134	2,369	13·41	12·39	11·34	8·81
45 and over .....	123	200	225	244	·71	·78	·55	·43

The rates in 1871 and 1881 were practically the same, but at all ages there was a large decline between 1881 and 1891, and again between 1891 and 1901. The apparent increase from 1891 to 1901 among women aged 15 and under 20 is due to the increased number of ante-nuptial conceptions in 1901 compared with 1891.

Taking the women of child-bearing age (15 to 44) at each period, the birth-rate per 100 married women was 34·25 in 1871, 33·47 in 1881, 29·70 in 1891, and 23·36 in 1901, so that the rates for 1901 showed a decrease of nearly 32 per cent. on those for 1871.

Although like information cannot be given for the other states, the births compared with the total married women of child-bearing ages have been ascertained for some of the states for the periods 1881, 1891, and 1901, and were as follows:—

State.	1881.	1891.	1901.
New South Wales .....	33·63	28·87	23·53
Victoria .....	29·84	29·77	22·86
Queensland .....	31·62	32·77	25·40
New Zealand .....	31·22	27·57	24·61

Particulars relating to illegitimate births will be found in the chapter headed "Social Condition."

#### DEATHS.

The following table shows the total number of deaths and the rate per thousand of the population during the year 1903:—

State.	Deaths.			Death-rate.		
	Males.	Females.	Total.	Males.	Females.	Total.
New South Wales .....	9,428	7,069	16,497	12·58	10·50	11·59
Victoria .....	8,626	6,969	15,595	14·25	11·54	12·90
Queensland .....	3,951	2,395	6,346	13·75	10·37	12·24
South Australia .....	2,242	1,709	3,951	12·07	9·39	10·74
Western Australia .....	1,829	959	2,788	13·71	7·19	12·60
Tasmania .....	1,136	980	2,116	12·31	11·49	11·92
Commonwealth .....	27,212	20,081	47,293	13·25	10·78	12·07
New Zealand .....	4,947	3,581	8,528	11·43	9·24	10·40
Australasia .....	32,159	23,662	55,821	12·93	10·51	11·78

The death-rate of Australia is much below that of any of the European states, and is steadily declining. Every year sees an advance in the sanitary condition of the people in the large centres of population, and to this cause may be ascribed the greater part of the improvement in the death-rate shown in the following tables, but there are other causes.



The decline in the birth-rate elsewhere alluded to has an immediate effect on the death-rates. In ordinary years about 30 per cent. of the deaths are of children under one year, and the decline in the birth-rate from 35 to 25 per thousand, which has happened during the last thirteen years, means a reduction of over 1 per thousand in the death-rate.

The number of deaths in each state and in the whole of Australasia, in quinquennial periods from 1861 to 1900, and during the years 1901-3, is shown in the following table. Of the Commonwealth States, South Australia showed the lowest death-rate during 1903, followed by Tasmania, but the lowest rate for Australasia was exhibited by New Zealand.

State.	1861-65.	1866-70.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
New South Wales..	31,561	26,466	40,909	53,256	66,108	71,457	76,802	77,783	49,164
Victoria .....	49,462	55,186	59,759	62,811	66,811	84,648	82,056	81,328	47,676
Queensland .....	5,751	9,812	12,809	17,284	25,781	28,040	26,581	29,202	18,557
South Australia ..	10,840	12,963	15,475	18,026	21,616	19,361	20,535	21,174	12,330
Western Australia	1,399	1,711	2,068	2,003	2,709	3,532	5,430	11,943	8,180
Tasmania .....	6,963	6,962	8,000	8,904	9,790	10,389	10,128	10,813	5,844
Commonwealth	105,956	122,550	139,140	162,374	192,760	217,227	221,527	231,743	141,701
New Zealand .....	10,001	13,328	19,354	25,254	29,074	29,746	38,525	35,151	24,537
Australasia ..	115,957	135,878	158,494	187,628	221,834	246,973	255,052	266,894	166,238

The average death-rates per thousand of the population of each state for the periods shown in the above table are given below, but the statement does not afford a just comparison between them as no account is taken of the ages of the people :—

State.	1861-65.	1866-70.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
New South Wales	16.86	16.06	14.99	16.09	15.66	13.80	12.90	11.35	11.74
Victoria .....	17.36	16.62	15.64	14.92	14.65	16.07	14.04	13.64	13.15
Queensland .....	21.06	18.07	17.94	16.90	19.10	15.62	12.32	12.51	12.08
South Australia ..	15.70	15.01	15.33	14.90	14.71	12.55	12.17	11.91	11.37
Western Australia	15.73	15.40	16.03	14.32	17.19	15.97	16.32	15.34	13.29
Tasmania .....	15.20	14.06	15.64	16.52	16.00	15.16	13.39	12.43	11.09
Commonwealth	17.01	16.14	15.65	15.71	15.60	14.79	13.27	12.73	12.24
New Zealand .....	14.36	12.06	12.96	11.83	10.96	9.86	10.14	9.56	10.24
Australasia ..	16.74	15.62	15.26	15.04	14.73	13.95	12.75	12.20	11.90

If this table be compared with that showing the birth-rates, it will be observed that the experience of Australasia corresponds with that of other countries, viz., that a low birth-rate and a low death-rate accompany each other, so that although the birth-rate has been declining it has had an effect in reducing the death-rate, as indicated on the preceding page, and the balance in favour of births has not been reduced so much as it might have been. From the next table, which shows the mean natural increase in various foreign countries during the decennial period 1893-1902, and for Australasia and the United Kingdom during the period 1894-1903, it will be seen that the case of Australasia is much better than that of any of the countries of the United Kingdom or Europe, for notwithstanding that the birth-rate of these countries in some cases is higher, the death-rate is so much higher as to more than outweigh any advantage in that respect.

Country.	Birth-rate.	Death-rate.	Excess of Births per 1,000 Inhabitants.
New South Wales .. .. .	28.20	11.87	16.33
Victoria.....	26.39	13.43	12.96
Queensland.....	29.81	12.31	17.50
South Australia.....	26.55	11.62	14.93
Western Australia.....	29.30	14.64	14.66
Tasmania.....	28.94	11.97	16.97
Commonwealth .....	27.74	12.53	15.21
New Zealand.....	26.16	9.87	16.29
Australasia .....	27.47	12.08	15.39
England and Wales .....	29.15	17.21	11.94
Scotland .....	29.75	17.78	11.97
Ireland.....	23.14	18.03	5.11
United Kingdom.....	28.55	17.37	11.18
Denmark .....	30.21	16.65	13.56
Norway .....	29.79	15.42	14.37
Sweden .....	26.85	15.97	10.88
Austria .....	36.93	25.66	11.27
Hungary .....	39.83	28.21	11.62
Switzerland .....	28.17	18.43	9.74
German Empire.....	35.88	21.47	14.41
Prussia.....	36.82	22.06	14.74
The Netherlands .....	32.16	17.45	14.71
Belgium .....	28.55	18.09	10.46
France .....	22.00	20.90	1.10
Italy .....	34.24	23.37	10.87

In regard to the above table it must be stated that, had the figures of any of the last five years been taken as the basis of comparison,

the gain by natural increase in Australasia would have been below that of some European countries, where the decline in the birth-rate, although distinctly evident, has not been so great as in Australasia.

#### INDEX OF MORTALITY.

So far consideration has only been given to the actual death-rates as they are obtained by taking the proportion which the number of deaths bears to the number of inhabitants. It is well known, however, that the death-rate of a country is affected by more than the salubrity of its climate, the degree of perfection to which the sanitary condition of its cities and towns and villages has been brought, and the nature of the industrial pursuits of its people. It is known that the ages of the people considerably affect the death-rate of a country; that, for instance, one which has a large proportion of young people will, other things being equal, have a lower death-rate than another which has a comparatively large proportion of old persons; and it is this fact that statistical science now seeks to take into account in establishing the rates of mortality of the various countries of the world. In order to have a comparison of the mortality of the principal countries on a uniform basis, the International Statistical Institute, in its 1895 session, held at Berne, decided to recommend the population of Sweden, in five age-groups, as ascertained at the census of 1890, as the standard population, by which the index of mortality should be calculated. Applying the co-efficient of mortality in each age-group in the Commonwealth and New Zealand to the age constitution of the standard population, the "index of mortality," as distinguished from the actual "death-rate," is found as given below for the year 1903. How greatly the ages of the people of a country affect its mortality will be evident from the fact that whereas in 1903 the death-rate in Victoria was higher than in Queensland, the index of mortality was lower, and while the death-rates ranged from 10·40 in New Zealand to 12·90 in Victoria, a difference of only 2·50 per thousand, the indexes of mortality showed a range of 3·58, namely, from 12·64 in New Zealand to 16·22 in Queensland.

State.	1903.
New South Wales .....	15·06
Victoria .....	15·25
Queensland .....	16·22
South Australia .....	13·89
Western Australia .....	15·75
Tasmania .....	14·86
Commonwealth .....	15·24
New Zealand .....	12·64
Australasia .....	14·76

## AGES AT DEATH.

A detailed statement of the ages at death of the males who died during the year 1903 in the various states is given below. The figures for South Australia in this and subsequent detailed tables refer to the province proper exclusive of the Northern Territory.

Ages at Death.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australia.
Under 1 year.....	2,170	1,664	617	470	549	299	5,369	977	6,976
1 and under 2 years...	435	271	184	64	81	35	1,060	142	1,192
2 " 3 " ..	130	100	53	19	17	16	335	70	405
3 " 4 " ..	99	76	47	14	15	7	299	61	379
4 " 5 " ..	46	47	28	8	5	5	149	33	181
5 " 10 " ..	181	127	86	46	29	29	558	117	675
10 " 15 " ..	155	143	79	49	21	20	461	84	545
15 " 20 " ..	210	169	101	58	29	44	611	125	746
20 " 25 " ..	306	196	164	69	96	44	875	194	1,069
25 " 30 " ..	310	248	195	79	114	27	994	189	1,144
30 " 35 " ..	327	287	193	62	100	36	1,005	156	1,161
35 " 40 " ..	464	345	199	66	123	25	1,201	182	1,383
40 " 45 " ..	418	372	216	72	135	40	1,251	188	1,439
45 " 50 " ..	427	368	204	94	87	34	1,214	189	1,403
50 " 55 " ..	423	322	204	118	69	46	1,191	214	1,405
55 " 60 " ..	450	374	207	123	86	37	1,277	263	1,540
60 " 65 " ..	572	495	276	134	75	51	1,608	344	1,947
65 " 70 " ..	662	713	316	152	62	61	1,666	446	2,302
70 " 75 " ..	666	961	205	144	55	77	1,926	390	2,386
75 years and upwards	1,025	1,847	222	318	66	201	3,248	550	3,798
Unspecified.....	14	1	13	1	3	2	89	33	72
Total .....	9,428	8,686	3,961	2,171	1,829	1,136	27,141	4,947	32,088

Similar information respecting the deaths of females in 1903 is given in the following table :—

Ages at Death.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australia.
Under 1 year .....	1,799	1,452	698	350	398	264	4,967	793	5,760
1 and under 2 years...	906	267	152	55	58	30	961	183	1,094
2 " 3 " ..	133	103	60	22	16	7	345	56	402
3 " 4 " ..	92	67	84	14	13	12	232	60	298
4 " 5 " ..	71	51	30	6	11	5	177	33	209
5 " 10 " ..	197	155	90	37	27	36	542	102	644
10 " 15 " ..	152	153	55	43	19	29	452	67	519
15 " 20 " ..	248	205	69	66	21	30	681	106	737
20 " 25 " ..	352	237	71	71	41	39	701	177	878
25 " 30 " ..	290	258	109	78	45	45	835	170	1,005
30 " 35 " ..	223	206	116	74	53	33	864	168	1,022
35 " 40 " ..	316	321	107	73	49	46	912	152	1,064
40 " 45 " ..	290	226	92	62	37	36	728	137	919
45 " 50 " ..	253	229	72	75	37	34	715	111	825
50 " 55 " ..	229	215	80	49	30	30	683	162	796
55 " 60 " ..	254	276	105	59	23	31	758	157	896
60 " 65 " ..	325	342	109	82	13	43	919	207	1,126
65 " 70 " ..	395	473	102	123	36	51	1,180	223	1,413
70 " 75 " ..	355	576	87	103	20	57	1,193	210	1,408
75 and upwards .....	719	990	168	269	34	117	2,277	382	2,659
Unspecified .....	1	.....	.....	.....	.....	1	2	6	8
Total .....	7,099	6,999	2,395	1,702	969	980	20,074	3,581	23,655

The next table shows the ages of all the persons who died during 1903 :—

Ages at Death.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
Under 1 year .....	3,290	3,146	1,513	820	945	568	10,966	1,770	12,726
1 and under 2 years...	331	538	316	122	139	65	2,011	275	2,286
2 " 2 " ..	308	303	113	41	38	23	681	126	807
3 " 4 " ..	191	143	81	28	23	19	490	111	601
4 " 5 " ..	127	98	58	17	16	16	329	64	390
5 " 10 " ..	378	342	176	83	66	65	1,700	219	1,919
10 " 15 " ..	307	296	129	92	40	49	913	151	1,064
15 " 20 " ..	453	374	170	121	60	74	1,242	241	1,483
20 " 25 " ..	558	423	235	140	137	83	1,576	371	1,947
25 " 30 " ..	600	516	304	148	169	72	1,799	350	2,149
30 " 35 " ..	609	593	309	136	153	69	1,869	314	2,183
35 " 40 " ..	720	668	306	159	181	81	2,113	334	2,447
40 " 45 " ..	696	658	308	184	162	75	2,083	325	2,358
45 " 50 " ..	690	604	276	167	124	68	1,929	300	2,229
50 " 55 " ..	662	547	284	167	88	76	1,824	378	2,200
55 " 60 " ..	714	650	312	182	109	68	2,036	400	2,436
60 " 65 " ..	897	837	385	216	83	99	2,522	551	3,073
65 " 70 " ..	1,067	1,196	318	275	98	102	3,036	679	3,715
70 " 75 " ..	1,011	1,437	290	247	75	134	3,194	600	3,794
75 and upwards.....	1,744	2,387	460	577	99	318	5,625	982	6,457
Unspecified.....	15	1	18	1	8	3	41	39	80
Total.....	16,497	15,696	8,346	3,873	2,788	2,116	47,315	8,628	56,743

The ages of the people were ascertained at the census of March, 1901, and a comparison of the foregoing figures with the numbers living at each age can now be made. Using the same age groups as for the index of mortality given on page 183, the following rates are obtained. For age 0 (under 1 year) the number of births during the year has been used in place of figures deduced from the census results :—

Age Groups.	Deaths in each Age Group per 1,000 living.								
	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
Under 1 year .....	110.47	106.40	120.13	97.09	141.51	111.02	111.47	81.45	106.02
1 and under 20.....	4.10	3.96	4.90	3.11	4.28	3.90	4.05	3.47	3.95
20 " 40.....	5.45	5.56	6.76	5.38	6.29	5.53	5.72	5.09	5.61
40 " 60.....	12.13	12.30	14.37	11.30	14.31	10.66	12.78	10.76	12.39
60 and over.....	60.31	60.20	58.78	67.17	50.00	60.68	59.18	60.07	57.48

Tasmania usually shows a much more favourable rate than any of the other states of the Commonwealth, and especially as regards children under 1 year of age ; but in 1903 a severe epidemic of whooping cough visited the island, and as a consequence the death-rate of children under 1 year rose from 79.96 in 1902, to 111.02 in 1903. During last year

South Australia showed much the lowest rate in Australia, but was still unable to compare with New Zealand, where the rates in each age group were lower than in any of the Commonwealth states.

### INFANTILE MORTALITY.

The mortality of infants under 1 year of age may be measured accurately by comparing the deaths with the number of births; this is a most sensitive and reliable test of the healthiness and sanitary condition of a country, since at this early age children are most susceptible to the attacks of disease. The following table shows for each state the number of deaths of children under 1 year of age, and the rate per 1,000 births, since 1870, arranged in five-year periods:—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
--------	----------	----------	----------	----------	----------	------------	---------

### DEATHS under 1 Year.

New South Wales .....	11,036	14,626	19,709	21,586	21,930	20,819	12,049
Victoria .....	16,981	15,865	17,043	22,582	20,221	17,299	8,646
Queensland .....	3,596	5,068	6,732	8,339	7,496	7,337	4,395
South Australia .....	5,758	6,516	7,594	5,593	5,227	5,266	2,566
Western Australia .....				939	1,332	3,488	2,567
Tasmania .....	1,560	1,830	2,331	2,437	2,337	2,284	1,404
Commonwealth ...	38,931	43,905	53,409	61,476	58,543	56,493	31,627
New Zealand .....	6,390	8,432	8,733	7,924	8,005	7,578	4,945
Australasia .....	45,321	52,337	62,142	69,400	66,548	64,071	36,572

### RATE per 1,000 Births.

New South Wales .....	103·58	114·65	123·98	114·64	111·00	113·40	107·89
Victoria .....	124·53	119·87	121·51	131·06	111·81	111·29	94·97
Queensland .....	122·82	135·02	137·45	118·87	102·88	103·39	106·83
South Australia .....	158·20	140·70	134·13	105·13	98·67	111·97	96·59
Western Australia .....				109·15	130·05	155·72	137·65
Tasmania .....	101·87	106·61	108·75	102·78	94·26	97·59	93·01
Commonwealth ...	119·47	120·55	123·48	117·51	107·96	112·35	103·98
New Zealand .....	106·69	95·60	90·51	84·23	87·57	80·03	78·52
Australasia ...	118·09	116·53	118·88	113·71	105·51	107·23	99·61

The infantile mortality of New South Wales has not shown great fluctuations during the thirty-three years included in the foregoing tables. The highest death-rate was in the five years 1881-85. The mortality at the end of the period, namely 107·89 per 1,000 was slightly greater than in 1871-75, when it stood at 103·58.

The rate for Victoria has sensibly declined since 1890, and from being amongst the highest in Australia it has fallen below that of any of the continental states.

The Queensland rates have considerably improved since 1885, as also have those of South Australia. The infantile mortality of Western Australia is still very high, which is accounted for by the difficulty of obtaining fresh milk on some of the gold-fields, and the dearness of artificial foods in the same districts.

The infantile mortality of Tasmania has always been very favourable, and the range in the table just given is from 93·01 per 1,000 in 1901-3 to 108·75 in the period 1881-85.

New Zealand also stands out most favourably, and it is doubtful if any country in the world can show a more favourable infantile mortality than this Colony.

The returns exhibit an infantile mortality in South Australia in 1871-75 of 158·2 per thousand births, and in subsequent periods the rate was also very high. There was nothing in the condition of South Australia to warrant so high a death-rate, and there is reason to suppose that the high average rate was attributable to incorrectness in registration, the deaths of many children one year old being wrongly included by the registering officers with those under 1 year.

A striking feature in the records of infantile mortality is the wide margin between the death-rates of legitimate and illegitimate children. In New South Wales, for the nine years 1895-1903, the infantile mortality rate of legitimates was 98·56 per 1,000 legitimate births, while for illegitimates the corresponding figure was 276·62 per 1,000 illegitimate births. The records for each year since 1895 were as follows :—

Year.	Legitimate Children.			Illegitimate Children.		
	Births.	Deaths under 1 year.	Death-rate per 1,000 births.	Births.	Deaths under 1 year.	Death-rate per 1,000 births.
1895	36,250	3,488	96·22	2,524	618	244·85
1896	34,061	3,717	109·13	2,445	718	293·66
1897	34,795	3,163	90·90	2,452	638	260·20
1898	33,711	3,671	108·90	2,511	747	297·49
1899	33,852	3,584	105·87	2,609	745	285·55
1900	34,541	3,087	89·37	2,605	749	287·52
1901	35,163	3,213	91·37	2,712	716	264·01
1902	35,338	3,436	97·23	2,497	716	286·74
1903	33,553	3,318	98·89	2,413	651	269·79
Total ...	311,264	30,677	98·56	22,768	6,298	276·62

From these figures it would appear that a child born in wedlock has nearly three times as much chance of surviving twelve months as the illegitimate.

## CAUSES OF DEATH.

The system of classifying the causes of death adopted in Australasia is that arranged by Dr. William Ogle on the basis of the older system of Dr. William Farr, his predecessor as Superintendent of the Statistical Department of the Registrar-General's Office, England. Under this classification deaths are divided into eight classes, namely, deaths from specific febrile or zymotic diseases, from parasitic diseases, from dietetic diseases, from constitutional diseases, from developmental diseases, from local diseases, from violence, and from ill-defined or unspecified causes. The following were the assigned causes of death of the 55,743 persons who died in Australasia during 1903 :—

Classification	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	New Zealand.	Australasia.
<b>Specific febrile or zymotic diseases—</b>								
Miasmatic diseases.....	1,051	633	406	194	214	176	622	3,236
Diarrhoeal diseases.....	654	460	248	166	101	66	184	1,979
Malarial diseases.....	10	2	79	1	25	1	.....	118
Zoogenous diseases.....	2	.....	.....	.....	.....	.....	.....	2
Veneral diseases.....	74	60	87	3	9	9	17	218
Septic diseases.....	167	194	78	37	23	21	93	680
<b>Total.....</b>	<b>1,968</b>	<b>1,358</b>	<b>945</b>	<b>401</b>	<b>372</b>	<b>223</b>	<b>916</b>	<b>6,263</b>
<b>Parasitic diseases.....</b>	<b>49</b>	<b>38</b>	<b>22</b>	<b>17</b>	<b>6</b>	<b>7</b>	<b>10</b>	<b>149</b>
<b>Dietetic diseases.....</b>	<b>165</b>	<b>138</b>	<b>108</b>	<b>14</b>	<b>40</b>	<b>18</b>	<b>67</b>	<b>550</b>
<b>Constitutional diseases.....</b>	<b>2,775</b>	<b>2,905</b>	<b>923</b>	<b>742</b>	<b>314</b>	<b>304</b>	<b>1,534</b>	<b>9,497</b>
<b>Developmental diseases.....</b>	<b>1,765</b>	<b>1,701</b>	<b>262</b>	<b>471</b>	<b>224</b>	<b>112</b>	<b>683</b>	<b>5,408</b>
<b>Local diseases—</b>								
Diseases of nervous system....	1,366	1,442	535	304	201	165	832	4,985
Diseases of organs of special sense.....	18	23	9	2	3	.....	6	66
Diseases of circulatory system..	1,373	1,682	666	437	223	236	918	5,439
Diseases of respiratory system..	1,750	1,792	645	389	263	208	979	6,030
Diseases of digestive system.....	2,431	1,965	1,036	401	471	200	752	7,236
Diseases of lymphatic system and ductless glands.....	36	15	10	4	2	5	30	111
Diseases of urinary system.....	748	837	296	162	80	58	331	2,511
Diseases of organs of generation.....	77	40	24	10	7	7	26	198
Diseases of parturition.....	160	126	58	21	24	21	100	520
Diseases of organs of locomotion.....	23	51	11	15	5	7	23	134
Diseases of integumentary system.....	63	57	26	12	8	9	22	197
<b>Total.....</b>	<b>9,044</b>	<b>8,035</b>	<b>3,215</b>	<b>1,847</b>	<b>1,292</b>	<b>910</b>	<b>4,079</b>	<b>27,422</b>
<b>Violence—</b>								
Accident or negligence.....	839	622	430	167	209	111	614	3,153
Homicide.....	36	15	14	6	6	3	3	67
Suicide.....	133	133	89	43	50	10	105	613
Execution.....	3	.....	2	.....	3	.....	.....	8
Violent deaths not classified.....	74	.....	.....	.....	.....	.....	.....	74
<b>Total.....</b>	<b>1,169</b>	<b>776</b>	<b>566</b>	<b>216</b>	<b>228</b>	<b>124</b>	<b>723</b>	<b>3,930</b>
<b>Ill-defined and not specified causes.....</b>	<b>572</b>	<b>614</b>	<b>296</b>	<b>166</b>	<b>212</b>	<b>263</b>	<b>317</b>	<b>2,534</b>
<b>Grand Total.....</b>	<b>16,497</b>	<b>15,595</b>	<b>6,346</b>	<b>3,878</b>	<b>2,788</b>	<b>2,116</b>	<b>5,523</b>	<b>55,743</b>



Comparing the figures of the total deaths in each class and order with the population, the following results are obtained. The figures represent the number of deaths per 100,000 living based on the experience of the five years ended with 1903.

Classification.	Number of deaths per 100,000 living.		
	Males.	Females.	Total Population.
<b>Specific, febrile, or zymotic diseases—</b>			
Miasmatic diseases.....	83.59	78.78	81.31
Diarrhoeal diseases.....	45.42	39.26	42.49
Veneral diseases.....	5.46	3.13	4.35
Septic diseases.....	6.43	17.59	11.72
Other specific, febrile, or zymotic diseases.....	3.22	0.40	1.88
<b>Total.....</b>	<b>144.12</b>	<b>139.16</b>	<b>141.76</b>
<b>Parasitic diseases.....</b>	<b>3.81</b>	<b>3.39</b>	<b>3.61</b>
<b>Dietetic diseases.....</b>	<b>16.78</b>	<b>7.71</b>	<b>12.43</b>
<b>Constitutional diseases.....</b>	<b>211.59</b>	<b>183.20</b>	<b>198.11</b>
<b>Developmental diseases.....</b>	<b>129.12</b>	<b>105.04</b>	<b>117.69</b>
<b>Local diseases—</b>			
Diseases of nervous system.....	122.64	99.85	111.82
Diseases of circulatory system.....	129.94	100.79	116.11
Diseases of respiratory system.....	158.32	116.88	138.65
Diseases of digestive system.....	141.96	135.20	138.75
Diseases of urinary system.....	62.67	33.86	49.00
Diseases of organs of generation.....	0.33	7.91	3.93
Diseases of parturition.....	.....	22.79	10.82
Diseases of organs of locomotion.....	3.46	2.46	2.98
Diseases of integumentary system.....	4.18	3.14	3.68
Other local diseases.....	2.91	3.94	3.40
<b>Total.....</b>	<b>626.41</b>	<b>526.82</b>	<b>579.14</b>
<b>Violence—</b>			
Accident or negligence.....	104.88	33.82	71.15
Homicide.....	2.51	1.59	2.08
Suicide.....	18.75	4.05	11.77
Other deaths from violence.....	1.62	0.40	1.04
<b>Total.....</b>	<b>127.76</b>	<b>39.86</b>	<b>86.04</b>
<b>Ill-defined or not specified causes.....</b>	<b>53.86</b>	<b>45.92</b>	<b>50.09</b>
<b>Grand total.....</b>	<b>1,313.45</b>	<b>1,061.10</b>	<b>1,188.92</b>

## SPECIFIC FEBRILE OR ZYMOTIC DISEASES.

The deaths from specific febrile or zymotic diseases in the Commonwealth during 1903 numbered 5,347, and in New Zealand 916, representing 13·67 and 11·17 deaths respectively per 10,000 of the population, the rate for Australasia being 13·23. Under this class are included the highly infectious diseases—measles, scarlet fever, whooping-cough, and diphtheria—which are especially fatal to children; diarrhoeal diseases, chiefly fatal to persons at the extremes of life; and typhoid (enteric) fever, the death-rate from which at times is very high.

It would be interesting to compare the fatality of these diseases in the various states in proportion to the number of cases occurring, but unfortunately the necessary information is lacking. In some of the states legal enactments provide for the notification of infectious diseases, but they are not rigidly enforced, and doubtless many cases escape notice.

In New South Wales, since the beginning of 1898, under the provisions of the Public Health Act of 1896, notification of the three diseases scarlet fever, diphtheria, and typhoid has been compulsory, and careful record has been kept of the number of cases and deaths. The following table shows the number of cases notified in the metropolis during the six years 1898 to 1903, and the fatality per cent. :—

Disease.	Number of cases notified.	Number of Deaths.	Fatality per cent.
Scarlet Fever .....	8,492	139	1·6
Diphtheria .....	2,698	235	10·6
Typhoid .....	4,865	484	9·9

The average annual experience of London during the ten years 1891-1900 is also given.

Disease.	Number of cases notified.	Number of Deaths.	Fatality per cent.
Scarlet Fever .....	21,156	818	3·9
Diphtheria .....	11,658	2,192	18·8
Typhoid .....	3,518	616	17·0

## MEASLES.

Measles, which is mainly a children's disease, was the cause in 1903 of the deaths of 89 persons in the Commonwealth and 143 in New Zealand equal to rates of 0·23 and 1·74 per 10,000 living, the rate for Australasia being 0·49. The disease was epidemic in New Zealand, and to a lesser extent in Queensland. The following tables show the number of deaths in each state from this disease, and the death-rate per 10,000 living, in five-year periods since 1870, and for the years 1901-3:—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
--------	----------	----------	----------	----------	----------	------------	---------

## NUMBER of Deaths.

New South Wales	.....	311	200	293	885	734	160
Victoria .....	1,809	271	386	148	696	827	121
Queensland .....	179	36	102	4	302	261	49
South Australia ...	356	18	240	8	291	83	245
Western Australia	.....	1	129	nil	27	41	67
Tasmania .....	132	3	66	1	49	59	1
Commonwealth	.....	640	1,123	454	2,250	2,005	643
New Zealand .....	*359	10	246	85	526	204	283
Australasia ...	.....	650	1,369	539	2,776	2,209	926

## DEATH-RATE per 10,000 living.

New South Wales	.....	0·94	0·47	0·57	1·48	1·12	0·38
Victoria .....	4·73	0·66	0·81	0·28	1·19	1·39	0·33
Queensland .....	2·50	0·35	0·76	0·02	1·46	1·12	0·32
South Australia ...	3·64	0·15	1·63	0·05	1·75	0·47	2·26
Western Australia	.....	0·07	8·19	0·00	0·81	0·53	1·09
Tasmania .....	2·56	0·06	1·06	0·01	0·65	0·71	0·02
Commonwealth	.....	0·62	0·91	0·31	1·35	1·10	0·56
New Zealand .....	*2·90	0·05	0·93	0·28	1·59	0·55	1·18
Australasia ...	.....	0·52	0·91	0·30	1·39	1·01	0·66

\* Four years, 1872-75.

With regard to the diseases which are almost solely confined to children, the rates would of course be more accurately stated if the deaths were compared with the children living of like ages. However taking them as they appear, it will be seen that measles has been more prevalent since 1891 than during the preceding fifteen years, and it seems to have been most common in the first three states shown in the table. In 1902 there were 245 deaths from this disease in South Australia, which accounts for the high rate shown for the period 1901-3. Although the disease is in evidence every year, it usually occurs as an epidemic, and, according to the records, the outbreaks occur with more or less regularity and severity about every five years. Measles was epidemic in nearly all the states in 1875 (when the attack was very severe), in 1880, in 1884 (when Western Australia suffered heavily) in 1889, in 1893, in 1898, and in 1899.

#### SCARLET FEVER.

The deaths from scarlet fever during 1903 in the Commonwealth numbered 193, and in New Zealand 131, giving a death-rate of 0.49 and 1.60 respectively per 10,000 living, the rate for Australasia being 0.68. In the table below are shown the number of deaths and the death-rates in each state arranged quinquennially since 1870:—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
NUMBER of Deaths.							
New South Wales .....	.....	1,295	476	404	460	244	164
Victoria .....	1,455	2,646	282	148	172	230	63
Queensland .....	77	37	19	73	31	157	20
South Australia ...	626	520	141	27	56	47	20
Western Australia .....	.....	.....	.....	nil.	1	4	5
Tasmania .....	72	304	49	9	8	38	40
Commonwealth .....	.....	4,802	967	661	728	720	321
New Zealand .....	*58	383	312	96	40	18	137
Australasia .....	.....	5,185	1,279	757	768	738	508

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
DEATH-RATE per 10,000 living.							
New South Wales	.....	3.91	1.13	0.78	0.77	0.37	0.39
Victoria .....	3.81	6.44	0.59	0.28	0.29	0.39	0.17
Queensland .....	1.07	0.36	0.14	0.40	0.15	0.67	0.13
South Australia ...	6.40	4.30	0.96	0.17	0.34	0.27	0.18
Western Australia	.....	.....	.....	0.00	0.03	0.05	0.08
Tasmania .....	1.40	5.59	0.80	0.13	0.11	0.46	0.93
Commonwealth	.....	4.65	0.78	0.45	0.44	0.40	0.28
New Zealand .....	*0.47	1.79	1.18	0.32	0.12	0.05	0.78
Australasia.....	.....	4.16	0.85	0.43	0.38	0.34	0.36

\* Four years, 1872-75.

The rate of mortality from scarlet fever for the first ten years shown in the table was much higher than that recorded for measles, but, in spite of the highly infectious nature and difficulty of isolation of the former disease, the death-rate has since been consistently lower than that of the latter. From 1871 to 1880 the rate of mortality from scarlet fever was high, but during the next five years a great decrease was manifested, and later there was a further decline, while during the three quinquennial periods ending 1900 the rate was practically constant, but with a tendency to rise in Victoria, Queensland, and Tasmania. Since 1900, the rate has fallen in Victoria, Queensland, and South Australia, but has risen in the other states, the general rate for the Commonwealth being 0.28. In 1903 the disease was epidemic in New Zealand, and to a mild extent in New South Wales. In Victoria the extremely high rate for 1876-80 was caused by a very virulent outbreak of the disease in 1876, and in Tasmania an outbreak in 1877 largely increased the rate; in fact, during the three years 1875, 1876, and 1877 all the states were more or less affected by an epidemic of scarlet fever. In Queensland the disease has never been very prevalent, and in Western Australia it is virtually unknown.

#### WHOOPIING-COUGH.

There were 483 deaths in the Commonwealth from this disease during 1903, equal to a rate of 1.23 per 10,000 living. In New Zealand the deaths numbered 204, showing a rate of 2.49.

A curious fact in connection with whooping-cough, the third of the diseases of infancy and childhood, is that the mortality resulting from it is higher in the case of girls than of boys. During 1903 whooping-cough was responsible for 697 deaths in Australasia (332 males and 365 females), equal to 1.47 deaths per 10,000 of the population, the male

rate being 1·34 and the female 1·62. The table below shows the number of deaths and the death-rates in each state since 1870 :—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
NUMBER of Deaths.							
New South Wales .....		676	632	979	1,157	947	706
Victoria .....	1,053	921	701	691	851	498	483
Queensland.....	117	198	184	306	381	454	135
South Australia...	181	211	341	263	279	264	137
Western Australia .....		nil.	19	65	57	80	78
Tasmania .....	99	84	59	89	79	88	92
Commonwealth .....		2,090	1,936	2,393	2,804	2,331	1,631
New Zealand.....	*465	589	592	443	752	245	296
Australasia...	... ..	2,670	2,528	2,836	3,556	2,576	1,927
DEATH-RATE per 10,000 living.							
New South Wales .....		2·04	1·50	1·89	1·93	1·44	1·69
Victoria .....	2·76	2·24	1·47	1·31	1·46	0·84	1·33
Queensland.....	1·83	1·94	1·37	1·69	1·84	1·94	0·88
South Australia...	1·85	1·74	2·32	1·70	1·68	1·51	1·36
Western Australia .....		0·00	1·21	3·12	1·71	1·03	1·27
Tasmania .....	1·92	1·54	0·96	1·30	1·05	1·06	1·75
Commonwealth .....	... ..	2·02	1·57	1·63	1·68	1·28	1·42
New Zealand .....	*3·75	2·76	2·23	1·47	2·28	0·67	1·24
Australasia...	.....	2·15	1·68	1·60	1·78	1·18	1·39

\* Four years, 1872-75.

The death-rate from whooping-cough, which has never been remarkably high, declined after the second quinquennium (1876-80), and thenceforward remained fairly constant during the next fifteen years. The returns show an especially gratifying decrease since 1895, considering that the disease was mildly epidemic during 1896-1900. During the period 1901-3, whooping-cough was more or less epidemic, and the rates both for the Commonwealth and New Zealand showed an increase over the preceding quinquennium. In 1903 there were 204 deaths in New Zealand from this cause. Generally speaking, whooping-cough seems to have been most prevalent in New South Wales, South Australia, and New Zealand; but it is gradually decreasing in these states, and, in fact, throughout Australasia, with the single exception of Queensland, where, until 1900, the tendency was towards an increase. On the whole, the rates up to the year 1895 were very even amongst themselves in all the states. In Western Australia the rate rose regularly to a maximum during 1886-90—a very severe epidemic being experienced in 1886—and then declined.

## DIPHTHERIA.

Diphtheria, the last of the febrile diseases mentioned which mainly affect children, caused, in 1903, a total of 363 deaths, equal to a rate of 0·77 per 10,000 persons living. Of this number 340 deaths occurred in the Commonwealth, and 23 in New Zealand, the death-rates being 0·87 and 0·28 respectively. In the following table are shown the number of deaths and the death-rates in each state since 1870 :—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
NUMBER of Deaths.							
New South Wales .....	1,109	1,005	1,325	1,753	584	339	
Victoria .....	1,609	1,431	681	1,835	994	892	351
Queensland .....	246	170	224	530	551	273	127
South Australia ..	379	329	387	570	513	153	67
Western Australia .....	11	28	19	38	79	86	
Tasmania .....	124	329	96	182	208	65	28
Commonwealth .....	3,379	2,421	4,511	4,057	2,046	948	
New Zealand .....	*535	316	525	542	577	289	121
Australasia .....	3,695	2,946	5,053	4,634	2,335	1,069	
DEATH-RATE per 10,000 living.							
New South Wales .....	3·35	2·39	2·56	2·92	0·89	0·81	
Victoria .....	4·21	3·48	1·43	3·58	1·70	1·50	0·97
Queensland .....	3·43	1·66	1·66	2·93	2·66	1·17	0·83
South Australia .....	3·88	2·72	2·63	3·69	3·08	0·86	0·62
Western Australia .....	.....	0·79	1·78	0·91	1·14	1·01	0·59
Tasmania .....	2·41	6·05	1·57	2·66	2·75	0·79	0·53
Commonwealth .....	.....	3·27	1·96	3·07	2·43	1·13	0·82
New Zealand .....	*4·32	1·48	1·98	1·80	1·75	0·79	0·51
Australasia .....	.....	2·96	1·96	2·85	2·32	1·07	0·77

\* Four years, 1872-75.

The present rates for diphtheria, as compared with those of twenty or twenty-five years ago, show a decrease. The decline, however, has been by no means regular, owing to the fact that this disease, in common with the others affecting children, sometimes occurs as an epidemic. Thus the increase in the rates during 1886-90 over those prevailing in the previous five years was due to an epidemic in nearly all the provinces in 1890.

The decreased mortality in Australia during the last twenty-five years, from the four diseases just mentioned, together with croup, represents a gain of about 10 children to the population in every 10,000 persons living. This improvement is very gratifying, since it may be taken that cases of these diseases, which are particularly liable to be attended with dangerous after-effects in the shape of lung and other local troubles, are not so numerous, and that in consequence the general health of the people is better.

## CROUP.

Croup, although classed as a disease of the respiratory system, was formerly classified with the zymotic diseases, and is included here on account of its similarity to diphtheria, and the confusion which often arises between them, and of the deaths set down to a combination of both. It is a disease that may be said to affect children only, and in 1903 caused 63 deaths in the Commonwealth and 17 in New Zealand, equal to rates of 0·16 and 0·21 per 10,000 of the population, the rate for Australasia being 0·17. In the subsequent table are shown the number of deaths and the death-rate in each state since 1870 :—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
NUMBER of Deaths.							
New South Wales	.....	968	971	951	683	278	83
Victoria.....	647	1,250	795	1,209	458	199	64
Queensland .....	273	324	483	382	239	103	23
South Australia ...	258	330	443	192	145	45	15
Western Australia	.....	24	31	45	64	26	5
Tasmania .....	80	76	113	112	101	29	7
Commonwealth...	.....	2,972	2,836	2,891	1,690	680	197
New Zealand .....	*281	277	334	340	304	186	60
Australasia ...	.....	3,249	3,170	3,231	1,994	866	257
DEATH-RATE per 10,000 living.							
New South Wales	.....	2·92	2·31	1·84	1·14	0·42	0·20
Victoria.....	1·69	3·04	1·66	2·30	0·78	0·33	0·18
Queensland .....	3·81	3·17	3·59	2·11	1·15	0·44	0·15
South Australia ...	2·64	2·74	3·01	1·24	0·87	0·26	0·14
Western Australia	.....	1·72	1·97	2·16	1·92	0·33	0·08
Tasmania .....	1·55	1·40	1·85	1·63	1·34	0·35	0·13
Commonwealth...	.....	2·87	2·29	1·97	1·01	0·37	0·17
New Zealand .....	*2·27	1·30	1·26	1·13	0·92	0·51	0·25
Australasia ...	.....	2·61	2·11	1·83	1·00	0·40	0·18

\* Four years, 1872-75.

Generally speaking, deaths from this disease show a steady and consistent fall from the earliest period, although in some of the states, especially Victoria and South Australia, the rates fluctuate slightly. The greatest decline has taken place in New South Wales, Victoria, Queensland, and South Australia, until at the present time croup is about equally prevalent throughout the Commonwealth. In New Zealand the rate is somewhat higher than in Australia, but is considerably lower than in any preceding period. If croup and diphtheria be taken together, as they usually are, it will be found that the rates in the Commonwealth generally have declined to the extent of over 5 per 10,000 during the last twenty-seven years.



## DIARRHOEAL DISEASES.

Diarrhoeal diseases, comprising cholera, diarrhoea, and dysentery, carry off mostly young children and old persons. In 1903 these diseases were fatal to 1,795 persons in the Commonwealth and 184 in New Zealand, equal to death-rates of 4·59 and 2·24 respectively per 10,000 living, the rate for Australasia being 4·18. The number of deaths and the death-rates in each state in quinquennial periods since 1870, are shown below.

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
NUMBER of Deaths.							
New South Wales .....	3,913	4,775	4,323	3,794	3,622	1,777	
Victoria.....	6,030	5,006	4,886	5,489	3,290	2,679	1,325
Queensland .....	1,618	2,469	3,833	2,865	2,125	1,779	1,085
South Australia ...	1,628	1,620	2,105	1,388	1,079	1,205	518
Western Australia .....	140	106	251	323	794	353	
Tasmania .....	437	512	474	605	354	309	164
Commonwealth.....	13,660	16,179	14,921	10,965	10,388	5,172	
New Zealand .....	*1,528	2,375	1,879	1,789	1,280	1,363	598
Australasia ...	.....	16,035	18,058	16,710	12,245	11,751	5,770
DEATH-RATE per 10,000 living.							
New South Wales .....	11·82	11·34	8·34	6·32	5·52	4·24	
Victoria.....	15·78	12·18	10·23	10·42	5·63	4·49	3·66
Queensland .....	22·56	24·15	28·46	15·85	10·25	7·62	6·74
South Australia ...	16·65	13·39	14·32	8·99	6·49	6·87	4·78
Western Australia .....	10·01	6·73	12·03	9·71	10·20	5·77	
Tasmania .....	8·48	9·41	7·75	8·83	4·68	3·72	3·11
Commonwealth.....	13·21	13·00	10·16	6·58	5·71	4·47	
New Zealand .....	*12·33	11·13	7·08	5·93	3·87	3·71	2·50
Australasia ...	.....	12·86	12·02	9·44	6·13	5·38	4·13

\* Four years, 1872-75.

The high death-rates of earlier years are not surprising, and may be ascribed to the hard fare and exposure incidental to the development of the pastoral and mining industries. This will be evident from a comparison of the present rates in Queensland, South Australia, and New South Wales with those of former periods. In all the states there has been a marked improvement during the last twenty-three years. The most noticeable improvement has occurred in Queensland, where the rate has declined from 24·15 to 6·74. That temperature and climate have an effect on the death-rates from these diseases is proved by the fact that they are much more prevalent and more fatal in summer than in any other season of the year, and that in Tasmania and New Zealand,

where the climate is mild and genial, the rates are much lower than in Queensland and Western Australia, where the climate is very warm, and in some parts tropical, while the other states, whose climates are fairly temperate, show rates between the two extremes.

The decline in the number of deaths from diarrhoea may be in part due to the fact that of late years more skilful diagnosis in some cases makes possible the ascription of death to ailments of which diarrhoea may be only a symptom

#### TYPHOID (ENTERIC) FEVER.

Seeing that typhoid is entirely a filth disease, the poison of which is propagated by sewage, and that it yields readily to sanitary precautions, it is a matter of very great regret that the annual mortality, although steadily declining, should still be so heavy. In 1903 typhoid was responsible for 1,145 deaths in the Commonwealth and 61 in New Zealand, the death rates being 2·93 and 0·74 respectively per 10,000 living. The rate for Australasia was 2·55 per 10,000 of the population, as against the English rate of 1·55 for the year 1901. The table below shows the number of deaths from this disease, and the death rate in each state, arranged in five-year periods since 1870 :—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-5.
NUMBER of Deaths.							
New South Wales .....	.....	1,722	2,132	2,307	1,533	1,968	1,042
Victoria .....	1,799	2,174	2,364	3,209	1,571	1,722	637
Queensland .....	424	525	1,303	990	513	747	470
South Australia .....	372	446	632	566	369	512	218
Western Australia .....	.....	.....	.....	59	500	1,379	433
Tasmania .....	156	184	213	401	230	251	87
Commonwealth .....	.....	5,051	6,644	7,532	4,716	6,579	2,887
New Zealand .....	*632	739	626	674	561	511	209
Australasia .....	.....	5,790	7,270	8,206	5,277	7,090	3,096
DEATH-RATE per 10,000 living.							
New South Wales .....	.....	5·20	5·06	4·46	2·56	3·00	2·49
Victoria .....	4·71	5·29	5·18	6·09	2·69	2·89	1·76
Queensland .....	5·91	5·14	9·67	5·48	2·48	3·20	3·06
South Australia .....	3·80	3·69	4·30	3·67	2·22	2·92	2·01
Western Australia .....	.....	.....	.....	2·83	15·03	17·72	7·08
Tasmania .....	3·03	3·38	3·48	5·85	3·04	3·02	1·65
Commonwealth .....	.....	4·89	5·38	5·13	2·83	3·62	2·49
New Zealand .....	*5·10	3·46	2·36	2·23	1·70	1·39	0·87
Australasia .....	.....	4·64	4·84	4·64	2·64	3·24	2·22

\* Four years, 1872-75.

It will be observed that the rates over the whole period covered by the table show a decline. The disease is of an epidemic nature, but still the rates do not fluctuate greatly, and during the last three years in all the states, excluding Western Australia, were fairly uniform, ranging from .87 in New Zealand to 3.06 in Queensland. An epidemic occurred in the year 1889 in New South Wales, Victoria, Queensland, and Tasmania. Typhoid was almost unknown in Western Australia prior to the gold rush of 1894, when the disease may be said to have commenced. The maximum was soon reached, for in 1895 the death-rate was 35.46 per 10,000. With improved sanitation the rate is steadily declining, and although the table shows an apparent increase in the quinquennial period, 1896-1900, it must be remembered that, as previously stated, the disease was comparatively unknown prior to 1894, and this accounts for the lower rate of the period 1891-1895. The rapid decline of the death-rate may be seen when it is stated that in 1895 it was 35.46 per 10,000, for the period 1896-8 only 25.38, while in 1901-3 it had fallen to 7.08, considerably less than half the rate for the preceding five years.

In England and Wales since the measures which have been taken to improve the drainage and water supply the rate has steadily fallen from 3.74 in 1871-75 to 1.73 in 1897-1901.

#### PARASITIC DISEASES.

The deaths from parasitic diseases in the Commonwealth during 1903 numbered 139, and in New Zealand 10, the death-rates being 0.36 and 0.12 respectively per 10,000 living, and for Australasia 0.31. The chief disease of this group is hydatids, which was responsible for 158 deaths, or 0.33 per 10,000 of the population, and was most common in South Australia, where the rate was 0.39.

#### DIETETIC DISEASES.

Dietetic diseases in 1903 carried off 483 persons in the Commonwealth and 67 in New Zealand, the death-rates being 1.23 and 0.82 respectively per 10,000 living, and for Australasia, 1.16. The chief contributing causes were privation and intemperance.

#### CONSTITUTIONAL DISEASES.

The next class of diseases is the constitutional, which caused 7,963 deaths in the Commonwealth and 1,534 in New Zealand during 1903, the death-rates being 20.35 and 18.70 respectively per 10,000 living, the rate for Australasia being 20.07. Of these diseases, phthisis and cancer stand out most prominently, and deserve special consideration.

## PHTHISIS.

Phthisis claims more victims in Australasia than any other disease, but notwithstanding this fact the death-rates are lower than in the other countries of the world. This is all the more gratifying when it is considered that many persons afflicted with the disease, or predisposed to it, are attracted to this country in the hope of obtaining relief, as the Australian climate is undoubtedly favourable to people suffering from pulmonary complaints. During 1903 phthisis caused 3,571 deaths in the Commonwealth, and 570 in New Zealand, equal to rates of 9·13 and 6·95 respectively per 10,000 living, the rate for Australasia being 8·75. The following table shows the number of deaths and the death-rates in each state since 1870, arranged in five-year periods:—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
NUMBER of Deaths.							
New South Wales ..	2,532	3,363	4,805	5,127	5,198	5,225	3,600
Victoria .....	4,594	5,397	6,428	7,662	7,751	7,049	4,169
Queensland .....	784	1,330	2,332	2,412	2,266	2,117	1,287
South Australia .....	872	1,244	1,558	1,640	1,667	1,544	890
Western Australia .....	*89	120	135	194	250	534	441
Tasmania .....	522	536	658	671	658	578	318
Commonwealth .....	.....	11,990	15,916	17,706	17,790	17,047	10,705
New Zealand .....	*1,060	1,805	2,418	2,529	2,693	2,886	1,783
Australasia .....	.....	13,795	18,334	20,235	20,483	19,933	12,488
DEATH-RATE per 10,000 living.							
New South Wales .....	9·28	10·16	11·41	9·90	8·66	7·96	8·59
Victoria .....	12·02	13·13	14·10	14·55	13·26	11·82	11·50
Queensland .....	10·93	13·01	17·31	13·35	10·93	9·07	8·38
South Australia .....	8·92	10·28	10·60	10·63	10·02	8·81	8·21
Western Australia .....	*8·58	8·58	8·57	9·30	7·51	6·86	7·21
Tasmania .....	10·13	9·85	10·76	9·79	8·70	6·97	6·03
Commonwealth .....	.....	11·60	12·88	12·06	10·67	9·37	9·25
New Zealand .....	*8·72	8·46	9·11	8·38	8·15	7·85	7·44
Australasia .....	10·09	11·06	12·22	11·43	10·25	9·12	8·94

\* Four years, 1872-75.

For the first half of the period covered by the table, phthisis seems to have been on the increase; but since 1885 it has steadily decreased, and the mortality rate is now lower than that of England—where the rate is nearly 13 per 10,000 living—or of any European country. The decline is general, and is evidence of the more skilful treatment of the disease and the effectiveness of the preventive measures taken against

it. Phthisis has always been most prevalent in Victoria, and up to 1900 the rate was fairly uniform throughout the rest of Australasia, the lowest being in Western Australia. During 1901-3, however, the order was changed; the rate increased in New South Wales and Western Australia, and decreased in the other states, so that now Tasmania has the lowest rate. In Queensland the rate is adversely affected by the peculiar liability of the Pacific Island labourers to contract the disease, while the Maori population of New Zealand is also extremely susceptible to its ravages.

## CANCER.

Next to phthisis, cancer is the most deadly of the constitutional diseases, and during 1903 was the cause of the death of 2,556 persons in the Commonwealth and 582 in New Zealand, the death-rates being 6.53 and 7.10 respectively per 10,000 of the population, the rate for Australasia being 6.63. In the table below are shown the number of deaths and the death-rates in each state since 1870:—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
NUMBER of Deaths.							
New South Wales	772	934	1,146	1,876	2,587	3,548	2,646
Victoria .....	1,245	1,712	2,065	2,799	3,621	4,086	2,654
Queensland.....	125	225	336	508	731	1,071	815
South Australia...	199	352	475	592	803	968	744
Western Australia	*16	23	52	85	102	248	260
Tasmania .....	249	255	308	341	371	459	305
Commonwealth	.....	3,501	4,382	6,201	8,215	10,380	7,424
New Zealand .....	*262	526	806	1,270	1,725	2,153	1,633
Australasia...	.....	4,027	5,188	7,471	9,940	12,533	9,057

## DEATH-RATE per 10,000 living.

New South Wales	2.83	2.82	2.72	3.62	4.31	5.41	6.32
Victoria .....	3.26	4.16	4.53	5.32	6.19	6.85	7.32
Queensland.....	1.74	2.20	2.49	2.81	3.53	4.59	5.30
South Australia...	2.04	2.91	3.23	3.84	4.83	5.82	6.86
Western Australia	*1.54	1.64	3.30	4.07	3.06	3.19	4.25
Tasmania .....	4.83	4.69	5.04	4.98	4.91	5.53	5.79
Commonwealth	.....	3.39	3.55	4.22	4.93	5.71	6.41
New Zealand .....	*2.11	2.46	3.04	4.21	5.22	5.86	6.82
Australasia ...	2.76	3.23	3.46	4.22	4.97	5.73	6.48

\* Four years, 1873-76.

It will be observed that with some slight irregularity the death-rate from cancer has steadily risen in Australasia over the whole period covered by the table. For the first half of the period Tasmania had the highest rate, but so rapid has been the progress of the disease in the other states that in all, except Queensland and Western Australia, the rates are now higher than in Tasmania. With the exception of the ten years 1881 to 1890, Western Australia has always shown the lowest rates.

Although part of the increase may arise from the fact that more skilful diagnosis in recent years enables cancer to be ascribed as the cause of death in obscure malignant diseases more often than was formerly the case, yet after making due allowance on this score, the conclusion must inevitably be arrived at that the spread of the disease is a dread reality. Australia is not alone in this respect, for in England the rate is still higher, and has increased from 7·62 per 10,000 of the population in 1896 to 8·42 in 1901.

#### DEVELOPMENTAL DISEASES.

The deaths in the Commonwealth from developmental diseases during 1903 numbered 4,525, and in New Zealand 883, the death rates being 11·57 and 10·77 respectively per 10,000 of the population, and for Australasia 11·43. Of the 5,408 deaths in Australasia, 3,429, or 7·25 per 10,000 living, were ascribed to the vague cause, old age. Premature birth was set down as the cause of death of 1,873 infants, a mortality equal to 15·57 per thousand children born alive, or 1 in every 64.

#### LOCAL DISEASES.

During 1903 local diseases were the cause of 23,343 deaths in the Commonwealth and 4,079 in New Zealand, equal to rates of 59·56 and 49·73 respectively per 10,000 of the population, the Australasian rate being 57·94. This group comprises diseases of the various systems and special organs of the body, the principal being diseases of the nervous system and of the circulatory system, which are further considered below. Under this heading also are classified diseases of the respiratory system, which caused 6,030 deaths in Australasia, equal to 12·74 per 10,000; of the digestive system, responsible for 7,236 deaths, or 15·29 per 10,000; and of the urinary system, the deaths from which numbered 2,511, equal to a rate of 5·31 per 10,000.

#### DISEASES OF THE NERVOUS SYSTEM.

It has been asserted that coincident with the advance of civilisation there has been an increase in diseases of the nerves and brain, but from the figures in the following table showing for each state the number of deaths, and the death-rates, since 1870, it will be seen that such has not been the case. Moreover, it has been ascertained that deaths from

apoplexy and convulsions in proportion to population are now less frequent than formerly. During 1903 the total deaths in the Commonwealth from diseases of the nerves and brain numbered 4,103, and in New Zealand 882, equal to rates of 10·49 and 10·75 respectively per 10,000 living, the rate for Australasia being 10·53.

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
NUMBER of Deaths.							
New South Wales	5,881	6,844	8,522	8,432	8,256	7,938	4,254
Victoria .....	6,503	7,029	7,414	8,585	7,852	7,382	4,451
Queensland .....	1,656	2,190	2,684	3,005	2,778	2,790	1,708
South Australia ...	2,068	2,249	2,645	2,177	2,127	2,086	1,221
Western Australia ...	*230	309	296	379	510	802	586
Tasmania .....	1,133	1,238	1,577	1,388	1,210	1,142	555
Commonwealth .....		19,859	23,138	23,966	22,733	22,140	12,77
New Zealand .....	*1,850	2,614	3,244	3,320	3,528	3,842	2,560
Australasia ...		22,473	26,382	27,286	26,261	25,982	15,335

DEATH-RATE per 10,000 living.							
New South Wales	21·56	20·67	20·23	16·28	13·76	12·10	10·16
Victoria .....	17·02	17·10	16·26	16·30	13·43	12·38	12·28
Queensland .....	23·09	21·42	19·93	16·63	13·40	11·95	11·11
South Australia ...	21·15	18·59	17·99	14·11	12·79	11·90	11·26
Western Australia ...	*22·17	22·09	18·79	18·16	15·33	10·30	9·58
Tasmania .....	21·99	22·75	25·78	20·25	16·01	13·76	10·53
Commonwealth .....		19·21	18·72	16·32	13·64	12·18	11·04
New Zealand .....	*14·93	12·25	12·22	11·01	10·67	10·45	10·68
Australasia ...		18·02	17·57	15·41	13·15	11·69	10·98

\* Four years, 1872-75.

A study of the table shows that the death-rate for diseases of the nervous system in Australia has decreased by considerably more than one-third during the last twenty-three years ended with 1903, representing a gain of over 8 persons to the population in every 10,000 living. Among the various states the rates for 1901-3 were fairly even, ranging from 9·58 in Western Australia to 12·28 in Victoria. Up to the quinquennial period ending 1900 the rate was consistently lower in New Zealand than in any other state, while from 1875 to 1900 Tasmania always had the highest rate. During 1901-3 Victoria showed the highest rate.

#### DISEASES OF THE CIRCULATORY SYSTEM.

Diseases of the heart, which now command more attention than previously on account of their more frequent occurrence, and also on account of the better knowledge of the organ which at present exists, were responsible for 4,521 deaths in the Commonwealth, or 11·56 per

10,000 living. In New Zealand the deaths numbered 918, equal to a rate of 11·19, the rate for Australasia being 11·49. The following table shows the number of deaths and the death-rates in each state since 1870 :—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-2.
NUMBER of Deaths.							
New South Wales	2,197	2,755	3,282	4,289	4,826	5,724	4,319
Victoria .....	3,138	3,666	4,453	6,198	7,365	8,066	5,148
Queensland .....	444	586	991	1,406	1,575	2,353	1,658
South Australia ..	649	934	1,130	1,359	1,605	1,995	1,393
Western Australia	*102	147	201	239	408	749	646
Tasmania .....	499	578	700	799	875	1,089	635
Commonwealth	.....	8,666	10,787	14,290	16,654	19,965	13,799
New Zealand .....	*795	1,422	1,762	2,234	2,767	3,824	2,805
Australasia ...	.....	10,088	12,549	16,574	19,421	23,789	16,604

DEATH-RATE per 10,000 living.							
New South Wales	8·05	8·32	7·74	8·23	8·04	8·72	10·31
Victoria .....	8·21	8·92	9·77	11·77	12·60	13·51	14·20
Queensland .....	6·19	5·73	7·36	7·78	7·60	10·08	10·79
South Australia ...	6·64	7·72	8·03	8·81	9·65	11·38	12·85
Western Australia	*9·83	10·51	12·76	11·45	12·26	9·61	10·56
Tasmania .....	9·69	10·62	11·44	11·66	11·57	13·12	12·05
Commonwealth	.....	8·38	8·73	9·73	9·99	10·98	11·92
New Zealand .....	*6·42	6·66	6·64	7·57	8·37	10·40	11·71
Australasia ...	7·58	8·09	8·36	9·36	9·72	10·88	11·89

\* Four years, 1872-75.

It will be seen that deaths from the diseases of the organs of circulation have steadily and rapidly increased during the last twenty-five years. It is questionable whether the increase shown is not partly due to more skilful diagnosis, as many deaths formerly attributed to old age are now assigned to some more definite cause. The highest death-rates prevail in Victoria and South Australia, which contain the largest number of persons of middle and old age who are most prone to this order of diseases.

#### DEATHS IN CHILDBIRTH.

Included under the heading of local diseases are diseases of parturition, which, together with puerperal fever, a septic disease of the symiotic group, comprise the causes of death of women in childbed. In



1903, deaths from these diseases averaged 1 in every 168 births, which differs slightly from the ratio to confinements, as some births are multiple. The table below gives the number of deaths from these diseases in each state since 1872, and the deaths per 1,000 births, the usual method of stating the rate :—

State.	1873-77.	1878-82.	1883-87.	1888-92.	1893-97.	1898-1902.	1903.
NUMBER of Deaths.							
New South Wales	*448	555	833	824	1,336	1,311	236
Victoria .....	997	899	895	916	943	925	189
Queensland .....	189	244	311	368	317	319	69
South Australia...	208	255	241	217	263	223	39
Western Australia	32	27	31	25	58	167	32
Tasmania .....	123	74	88	88	106	116	22
Commonwealth	.....	2,054	2,399	2,438	3,023	3,061	587
New Zealand .....	367	435	582	464	459	479	128
Australasia...	.....	2,489	2,981	2,902	3,482	3,540	715

DEATH-RATE per 1,000 Births.							
New South Wales	*6.43	3.99	4.79	4.24	6.96	7.07	6.56
Victoria .....	7.42	6.74	5.96	4.96	5.61	6.03	6.39
Queensland .....	5.75	6.07	5.33	5.00	4.43	4.48	5.47
South Australia...	5.32	5.00	4.22	4.06	5.13	4.90	4.56
Western Australia	7.48	5.54	4.86	3.01	4.32	6.06	4.78
Tasmania .....	7.88	3.94	3.85	3.62	4.39	4.81	4.33
Commonwealth	.....	5.32	5.12	4.52	5.81	6.03	5.96
New Zealand .....	5.13	4.68	5.99	5.06	4.96	4.96	5.86
Australasia...	.....	5.18	5.27	4.60	5.68	5.84	5.94

\* 1876-77.

The rate showed a tendency to decline up to 1893, since when it has risen. The statistics presented above, however, are not absolutely to be relied upon, for the reason that medical attendants do not take sufficient care when furnishing the certificate required of them by law to state the real cause of death; for instance, it is believed that the word *puerperal* is omitted in many cases, especially of pyæmia and septicæmia where death occurred in childbirth. It is absurd to suppose, as the rates indicate, that there is a greater degree of risk attached to childbirth in New South Wales than in the other states. The only assurance that can be given is that since 1890 the figures for New South Wales are absolutely correct.

## DEATHS FROM VIOLENCE.

Deaths by violence in the Commonwealth during 1903 numbered 3,198 and in New Zealand 722, the rates being 8·17 and 8·80 respectively per 10,000 living, the rate for Australasia being 8·28. Of the deaths from this cause, more than 80 per cent. were the results of accidents or negligence, and more than 16 per cent. were due to suicide, the latter being more fully dealt with in the chapter "Social Condition."

## ACCIDENTS.

The total number of accidental deaths in Australia during 1903 was 2,539, or 6·49 per 10,000 living. In New Zealand the deaths numbered 614, the rate being 7·49 per 10,000 of the population, while for Australasia it was 6·66. The following table shows the number of deaths in each state from this cause, and the death-rates since 1870 :—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-3.
NUMBER of Deaths.							
New South Wales .....	2,982	3,569	4,174	4,542	4,520	4,852	2,882
Victoria .....	3,908	3,539	3,662	4,612	4,262	4,016	2,057
Queensland .....	1,134	1,389	1,874	2,639	2,349	2,681	1,406
South Australia .....	610	877	919	1,038	912	1,141	544
Western Australia .....	*106	184	184	277	400	1,000	730
Tasmania .....	492	497	441	551	500	583	273
Commonwealth.....	.....	10,055	11,254	13,659	12,943	14,273	7,892
New Zealand.....	*1,259	2,200	2,216	2,369	2,494	2,415	1,631
Australasia .....	.....	12,255	13,470	16,028	15,437	16,688	9,523
DEATH-RATE per 10,000 living.							
New South Wales .....	10·93	10·78	9·91	8·77	7·53	7·39	6·88
Victoria .....	10·23	8·61	8·03	8·76	7·29	6·73	5·67
Queensland .....	15·81	13·59	13·91	14·60	11·33	11·49	9·15
South Australia .....	6·24	7·25	8·25	6·73	5·48	6·51	5·02
Western Australia .....	*10·22	13·16	11·68	13·23	12·02	12·85	11·93
Tasmania .....	9·55	9·13	7·21	8·04	6·61	7·03	5·18
Commonwealth.....	.....	9·73	9·11	9·30	7·76	7·85	6·82
New Zealand .....	*10·16	10·31	8·38	7·86	7·55	6·57	6·81
Australasia .....	.....	10·10	9·83	9·06	7·73	7·63	6·82

\* Four years, 1872-75.

The death-rates from accidents have fallen considerably, as the table shows, but they are still by no means low, and only Tasmania and South Australia exhibit so small a rate as that of England and Wales, viz., 5·3

per 10,000 living. Western Australia and Queensland, which have the most scattered populations, show the largest rates, while South Australia, where accidents seem always to have been less frequent than in the other states, shows the lowest rate. The most common accidents appear to be fractures, contusions, and drowning, the last mentioned causing a large number of deaths in Queensland every year, the high rate during 1886-90 in that state being due to the great number of people (340) who were drowned in 1890.

## MARRIAGES.

The number of marriages and the marriage-rate per thousand of the population for each state during the year 1903 are shown below :—

State.	Marriages.	Marriage-rate.
New South Wales .....	9,759	6·86
Victoria .....	7,605	6·29
Queensland .....	2,933	5·66
South Australia .....	2,272	6·18
Western Australia .....	2,064	9·33
Tasmania .....	1,344	7·57
Commonwealth .....	25,977	6·63
New Zealand .....	6,748	8·23
Australasia .....	32,725	6·91

During 1903 the marriage-rate of the Commonwealth decreased from 7·24 to 6·63 per thousand, and of New Zealand from 7·37 to 6·91, but taking the last three years the rates were higher than the average for the preceding ten years, and this may be looked upon as a sure sign of returning prosperity.

The number of marriages in each state and in the whole of Australasia, in quinquennial periods from 1861 to 1900, and for the years 1901-3 was as follows :—

State.	1861-1865.	1866-1870.	1871-1875.	1876-1880.	1881-1885.	1886-1890.	1891-1895.	1896-1900.	1901-1903
New South Wales ....	16,920	18,271	21,210	25,904	35,787	38,071	39,924	45,909	30,733
Victoria .....	22,237	22,902	24,268	25,416	33,589	42,832	37,717	39,245	24,488
Queensland .....	3,699	4,648	6,276	7,466	11,632	15,271	13,526	15,479	9,517
South Australia .....	6,226	6,485	7,472	10,682	12,379	10,334	10,686	10,942	6,964
Western Australia .....	705	825	835	978	1,112	1,495	2,332	7,902	5,909
Tasmania .....	3,340	3,143	3,290	4,087	5,005	4,796	4,524	5,568	3,995
Commonwealth ..	53,177	56,227	63,451	74,533	99,454	113,399	108,709	125,075	81,656
New Zealand .....	7,240	9,965	12,060	16,220	18,102	18,097	20,210	26,418	19,237
Australasia .....	60,417	66,182	75,501	90,753	117,556	131,496	128,919	151,493	100,893

The average marriage-rates for each state during the same periods are given below. The table shows the ratio of marriages to population; to ascertain the ratio of persons married it is necessary to double the figures:—

State.	1861- 1865.	1866- 1870.	1871- 1875.	1876- 1880.	1881- 1885.	1886- 1890.	1891- 1895.	1896- 1900.	1901- 1905.
New South Wales ....	9.04	8.04	7.77	7.82	8.46	7.47	6.65	7.00	7.35
Victoria .....	7.81	6.86	6.28	6.08	7.37	8.13	6.45	6.58	6.76
Queensland .....	12.51	9.02	8.75	7.30	8.64	8.45	6.53	6.33	6.15
South Australia .....	9.08	7.45	7.64	8.33	8.42	6.79	6.23	6.18	6.24
Western Australia .....	8.90	7.45	6.48	6.99	7.06	7.16	7.01	10.15	9.08
Tasmania .....	7.30	6.35	6.39	7.51	8.18	7.01	5.98	6.75	7.58
Commonwealth ..	8.54	7.40	7.14	7.21	8.06	7.72	6.51	6.37	7.05
New Zealand .....	10.39	9.09	8.05	7.60	6.82	6.00	6.11	7.19	8.03
Australasia .....	8.72	7.61	7.27	7.28	7.83	7.43	6.46	6.92	7.22

During the five years ended 1895 the marriage-rate fell considerably in Australasia. With the exception of New Zealand it was lower in every state than during the preceding quinquennial period, and lower everywhere than during the five years 1881-85, but during the last five years the rate rose again in every state except South Australia. This is another proof of the truth of the oft-repeated statement that commercial depression always exerts an adverse influence on the marriage-rate. The abnormal rise in the case of Western Australia is what might be expected from the large number of men whom the industrial activity in that state has placed in a position to take upon their shoulders the responsibility of a household.

As marriage is the great institution by which the birth-rate is controlled, and through which the population is regulated, it will not be out of place to consider the fertility of marriages in Australasia. The two chief elements influencing this are the age at marriage of the parents, especially of the mother, and the duration of married life. The mean age at marriage of bridegrooms in Australasia is a little over 29 years, and of brides about 24.5 years, and it is known that these ages have been increasing for some years past. As regards the duration of married life, it is not possible to speak with certainty; all that is known is that the length of lifetime of married persons surpasses that of the unmarried—both male and female. The fertility of marriages is reckoned by the number of children to each marriage; and as the difference between the mean age of mothers and the mean age of brides in Australia is between 5 and 6 years, the average number of children to a marriage has been computed for the following

table by dividing the number of legitimate births during each quinquennium by the number of marriages during the preceding five years :—

NUMBER of Children to a Marriage.

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-2.
New South Wales.....	5.59	5.76	5.87	5.01	4.80	4.28	3.97
Victoria .....	5.77	5.20	5.26	4.88	3.99	3.89	3.77
Queensland.....	6.12	5.75	6.29	5.76	4.54	4.93	4.44
South Australia.....	5.53	6.06	6.19	4.19	4.97	4.25	4.00
Western Australia .....	4.72	5.33	5.35	6.02	.....	.....	4.05
Tasmania .....	4.68	5.01	5.01	4.56	4.93	4.88	4.68
Commonwealth .....	5.63	5.53	5.55	4.95	4.48	4.25	4.00
New Zealand .....	5.94	7.15	5.77	5.63	4.86	4.48	4.05
Australasia.....	5.68	5.79	5.59	4.98	4.53	4.29	4.01

Western Australia has been excluded from the table during the period from 1890 to 1900, as the sudden influx of population, consequent on the discovery of the gold-fields, unduly increased the number of births to be divided by the number of marriages of the preceding five years, and would have made the marriages of that state appear more fertile than they really are. Of course, the above means of determining the fecundity of marriages is only to be used in the absence of more direct methods; still the results cannot be very far from the truth, as is proved by the case of New South Wales, where accurate computations have shown the number of children to be expected from the present marriages to be only 3.64. The table shows that, on the whole, the fertility of marriages has been steadily declining since 1885, which bears out what has been before remarked in dealing with this question.

Particulars relative to divorce in Australasia will be found in the chapter headed "Social Condition."

## SHIPPING.

THE earliest date for which there is reliable information in regard to the shipping of the states now constituting the Commonwealth of Australia, and also of the colony of New Zealand is the year 1822. Since that time the expansion of the trade has been marvellous, and although population has increased at a high rate, yet the growth of shipping has been even more rapid. In the table given below the increase in the number and tonnage of vessels may be traced. The shipping of New Zealand is treated separately, and all tonnage of this colony, of course, is shown, but it is necessary to point out that the figures for the Commonwealth of Australia include the interstate traffic, and are, therefore, of little value in a comparison between the shipping trade of Australia and that of other countries, as the vessels plying between the various states represent merely coasting trade when the Commonwealth is considered as a whole. This distinction is to be kept in view throughout the chapter.

Commonwealth of Australia.			New Zealand.		
Year.	Entered and Cleared.		Year.	Entered and Cleared.	
	Vessels.	Tonnage.		Vessels.	Tonnage.
1822	268	147,869	1822	.....	.....
1841	2,576	552,347	1841	.....	.....
1851	4,780	975,959	1851	560	112,149
1861	9,174	2,425,148	1861	1,142	403,336
1871	11,836	3,689,643	1871	1,438	540,261
1881	14,408	8,109,924	1881	1,527	833,621
1891	16,987	16,235,213	1891	1,481	1,244,322
1901	18,638	26,197,436	1901	1,379	2,139,180
1903	18,158	27,152,668	1903	1,225	2,215,229

In the year 1822 all the settlements on the mainland were comprised in the designation of New South Wales, and as late as 1859 Queensland formed part of that state. Thus an exact distribution of shipping amongst the states comprising the Commonwealth of Australia can be made only for the period subsequent to the year last named. Such a division of the total tonnage entered and cleared is shown in the following

table for the five census years commencing with 1861, and for the year 1903.

State.	Total Tonnage Entered and Cleared.					
	1861.	1871.	1881.	1891.	1901.	1903.
Commonwealth of Australia—						
New South Wales.....	745,696	1,500,479	2,736,500	5,094,236	8,521,234	9,005,401
Victoria .....	1,090,002	1,355,025	2,412,534	4,715,109	6,715,491	6,857,854
Queensland.....	44,045	93,296	832,491	997,118	1,636,820	1,796,455
South Australia .....	199,331	337,026	1,359,591	2,738,589	4,127,903	4,280,890
Western Australia .....	115,256	137,717	285,046	1,045,555	3,714,263	3,335,895
Tasmania.....	230,218	216,160	383,762	1,044,606	1,432,725	1,874,173
Total.....	2,425,148	3,689,643	8,109,924	16,235,213	26,197,436	27,152,068
Colony of New Zealand .....	408,336	540,261	833,621	1,244,322	2,139,180	2,215,229

The tonnage of 1891 exceeded that of any preceding year. This result was not altogether due to the actual requirements of the trade of that year, as, in consequence of the maritime strike, a large quantity of goods remained unshipped at the close of 1890, and helped to swell the returns for the succeeding twelve months. It was not until 1895 that the tonnage of 1891 was again reached; but since 1895 there has been a great expansion of shipping, and 1903 showed not only the largest total tonnage recorded but, with the exception of Western Australia, the greatest for each individual state.

Below will be found the proportion of the tonnage of each state to the total shipping of the Commonwealth of Australia in each of the years quoted above :—

State.	Percentage of Total of Commonwealth.					
	1861.	1871.	1881.	1891.	1901.	1903.
Commonwealth of Australia—						
New South Wales .....	30·8	40·7	34·4	35·1	32·5	33·2
Victoria .....	44·9	36·7	29·7	29·0	25·6	25·2
Queensland .....	1·8	2·5	10·9	6·2	6·4	6·7
South Australia .....	8·2	10·5	16·8	16·9	15·8	15·7
Western Australia .....	4·8	3·7	3·5	6·4	14·2	12·3
Tasmania .....	9·5	5·9	4·7	6·4	5·5	6·9
Total .....	100·0	100·0	100·0	100·0	100·0	100·0

It cannot be claimed that these figures have much meaning, and they would not have been repeated in this work, except for the purpose of showing how easy it is to make fallacious comparisons from reasonably correct data. Queensland appears almost last amongst the states in point of tonnage, yet, unquestionably, that state ranks third as regards the importance of its trade. The explanation of the discrepancy between the real and apparent trade lies in the fact which will hereafter be reverted to, that the same vessels are again and again included as distinct tonnage in the returns of the southern states. For example, a mail-steamer which calls at Fremantle, in Western Australia, continues its voyage to Sydney by way of Adelaide and Melbourne, sometimes calling at Hobart, and figures as a separate vessel at each port. The Canadian mail-steamers and the vessels of the Nippon Yusen Kaisha, or Imperial Japanese Mail Line, are also counted twice in the New South Wales and Queensland returns, but on account of the less number of trips, and the small tonnage of the vessels, the figures for each of these states are not so much inflated as is the case with those of other Commonwealth states. It is apparent therefore that the returns are only of value as indicating the comparative progress of the trade of each separate state, and not the progress of one state as compared with another.

#### INTERSTATE SHIPPING.

The total shipping of the Commonwealth of Australia, dealt with in the preceding section, included the trade between the various states, which represents 57·31 per cent. of the total for Australia. In the following table will be found the number and tonnage of vessels entered at the ports of each state from the other states. As a rule, the expansion of the trade of a state with its neighbours has kept pace with the growth of its commerce with outside countries. It should be remembered that the trade between New Zealand and Australia has been eliminated from the tables showing interstate shipping.

State.	Entered from other States of the Commonwealth.					
	1891.		1901.		1908.	
	Vessels.	Tonnage.	Vessels.	Tonnage.	Vessels.	Tonnage.
Commonwealth of Australia—						
New South Wales .....	2,111	1,687,300	2,303	2,094,297	2,237	2,295,699
Victoria .....	1,954	1,481,974	1,745	1,992,118	1,661	2,080,716
Queensland .....	376	267,753	430	545,469	475	553,798
South Australia .....	761	683,095	719	1,135,714	779	1,275,784
Western Australia ...	149	237,708	448	973,474	338	806,876
Tasmania .....	680	371,205	713	485,023	802	627,500
Total .....	6,031	4,709,035	6,356	7,226,095	6,292	7,640,363



The peculiar feature of the foregoing table is the large increase in the tonnage of Western Australia and South Australia, due in both cases to the influx of population and expansion of trade resultant on the great gold discoveries in the former state.

State.	Cleared for other States of the Commonwealth.					
	1891.		1901.		1908.	
	Vessels.	Tonnage.	Vessels.	Tonnage.	Vessels.	Tonnage.
Commonwealth of Australia—						
New South Wales .....	1,861	1,385,357	1,995	1,907,228	2,019	1,961,383
Victoria .....	2,166	1,761,027	1,794	2,072,747	1,886	2,443,065
Queensland .....	389	302,723	395	440,659	478	546,690
South Australia .....	865	854,236	826	1,377,399	872	1,523,445
Western Australia .....	158	269,256	456	977,848	360	854,845
Tasmania .....	679	352,406	694	433,735	788	560,871
Total .....	6,118	4,925,005	6,160	7,209,612	6,403	7,920,299

A comparison of the figures given above with those in the preceding table shows that in the case of Victoria, South Australia and Western Australia the tonnage cleared is largely in excess of that entered. This partly arises from the necessity of many vessels clearing at the southern and Western Australian ports in ballast and proceeding for outward cargo to New South Wales ports, principally Newcastle, where on their outward voyage such vessels are, of course, reckoned amongst the external shipping.

The combined tonnage of inter-state shipping entered and cleared, with the percentage for each state to the total inter-state shipping of the Commonwealth, will be found below :—

State.	Entered from and Cleared for other States.					
	Total Tonnage.			Percentage of each State to Total.		
	1891.	1901.	1908.	1891.	1901.	1908.
Commonwealth of Australia—						
New South Wales .....	3,072,657	4,001,523	4,257,072	31·9	27·7	27·3
Victoria .....	3,223,001	4,064,865	4,523,781	33·5	28·2	29·1
Queensland .....	570,476	986,128	1,100,488	5·9	6·8	7·1
South Australia .....	1,537,581	2,513,113	2,799,229	15·9	17·4	18·0
Western Australia .....	506,964	1,951,320	1,691,721	5·3	13·5	10·9
Tasmania .....	723,611	918,758	1,188,371	7·5	6·4	7·6
Total .....	9,634,040	14,435,707	15,560,662	100·0	100·0	100·0

## EXTERNAL SHIPPING.

It has been explained that in any comparison between the shipping of the Commonwealth of Australia and that of other countries the interstate trade would have to be excluded; but even then the tonnage would be too high, because of the inclusion of mail-steamers and other vessels on the same voyage in the returns of several of the states. However, it is scarcely possible to amend the returns so as to secure the rejection of the tonnage which is reckoned more than once; and in considering the following statement, showing the shipping trade of the Commonwealth with countries beyond Australia, this point should be borne in mind:—

Division.	1891.		1901.		1908.	
	Vessels.	Tonnage.	Vessels.	Tonnage.	Vessels.	Tonnage.
United Kingdom—						
Entered .....	868	1,699,958	716	2,066,167	678	2,234,679
Cleared .....	588	1,217,582	784	2,144,587	561	1,975,546
Total .....	1,456	2,917,540	1,500	4,210,754	1,239	4,110,225
British Possessions—						
Entered .....	894	790,608	1,403	1,971,931	1,105	1,638,567
Cleared .....	942	903,972	1,349	2,081,623	1,082	1,798,701
Total .....	1,836	1,694,580	2,752	4,053,554	2,187	3,437,268
Foreign Countries—						
Entered .....	681	880,814	906	1,774,013	983	2,069,566
Cleared .....	865	1,108,239	964	1,723,408	1,054	1,974,947
Total .....	1,546	1,989,053	1,870	3,497,421	2,037	4,044,513
All External Trade—						
Entered .....	2,443	3,371,390	3,025	5,812,111	2,766	5,942,819
Cleared .....	2,395	3,229,793	3,097	5,949,618	2,697	5,649,194
Total .....	4,838	6,601,173	6,122	11,761,729	5,463	11,592,006

The external shipping of the Commonwealth of Australia during 1903 was over 75 per cent. more than the tonnage entered and cleared in 1891, when trade was inflated by the shipment of goods left over from the previous year on account of the maritime strike. A distribution of the traffic amongst the leading divisions of the British Empire and

the principal foreign countries with which the states of the Commonwealth have commercial relations will be found below :—

Country.	Entered from and cleared for Countries beyond the Commonwealth.					
	1891.		1901.		1903.	
	Vessels.	Tonnage.	Vessels.	Tonnage.	Vessels.	Tonnage.
<b>British Empire—</b>						
United Kingdom .....	1,456	2,917,540	1,500	4,210,754	1,239	4,110,225
New Zealand .....	1,007	749,886	999	1,345,471	940	1,463,030
India and Ceylon .....	134	276,030	142	330,714	165	431,204
Hong Kong .....	227	324,820	241	380,174	159	278,599
Canada .....	27	29,952	61	118,523	56	131,353
Cape Colony .....	63	55,611	430	681,869	260	434,884
Natal .....	35	12,950	423	794,583	144	294,805
Fiji .....	107	105,033	60	58,799	84	78,492
Straits Settlements .....	61	75,269	90	129,112	142	217,092
Other British Possessions	175	65,029	306	214,309	237	102,809
<b>Total, British .....</b>	<b>3,292</b>	<b>4,612,120</b>	<b>4,252</b>	<b>8,264,308</b>	<b>3,428</b>	<b>7,547,493</b>
<b>Foreign Countries—</b>						
France .....	101	255,351	117	304,026	123	325,489
Germany .....	208	393,001	274	900,798	270	1,001,305
Netherlands .....	13	15,731	7	14,748	6	9,831
Belgium .....	27	41,907	14	29,716	19	29,403
United States .....	418	519,252	385	758,281	485	979,389
China .....	34	33,135	11	23,797	6	8,908
Japan .....	7	13,677	80	192,674	133	310,539
New Caledonia .....	154	155,226	125	179,486	134	217,954
Java .....	37	58,379	88	183,349	44	104,872
Philippine Islands .....	29	36,305	52	87,809	63	135,280
Hawaiian Islands .....	1	430	107	106,205	101	122,049
Peru .....	16	21,520	39	48,554	26	34,994
Chili .....	131	146,448	218	324,892	212	327,333
Other Foreign Countries	370	298,691	353	334,086	415	437,167
<b>Total, Foreign .....</b>	<b>1,546</b>	<b>1,989,053</b>	<b>1,870</b>	<b>3,497,421</b>	<b>2,037</b>	<b>4,044,513</b>
<b>All External Tonnage</b>	<b>4,838</b>	<b>6,601,173</b>	<b>6,122</b>	<b>11,761,729</b>	<b>5,463</b>	<b>11,592,006</b>

It will be seen from the above figures that out of a total external tonnage amounting to 11,592,006 tons in 1903, vessels from the United Kingdom aggregated 4,110,225 tons, or 35·5 per cent. of the whole. New Zealand furnished the next largest tonnage, with 1,468,030 tons, or 12·7 per cent., followed by Germany, with 1,001,305 tons, equal to 8·6 per cent., and the United States, with 979,389 tons, or 8·4 per cent. of the total. During the twelve years, 1891-1903, the tonnage of the United Kingdom increased by 1,192,685 tons, or 41 per cent., while British tonnage as a whole increased by 2,935,373 tons, or 64 per cent., the German by 608,304 tons, or 155 per cent., and the United States tonnage by 460,137 tons, or 89 per cent.

The enormous increase in the German tonnage is due to the large volume of business captured by the heavily subsidised vessels of the various German lines.

As the following table shows, the largest share of the external tonnage of Australia falls to New South Wales, which takes considerably more than one-third of the total; Victoria comes next with a little over one-fifth, followed by Western Australia with about one-seventh. The figures in the chapter on "Commerce," however, give a better idea of the relative importance of the states in external trade, as the tonnage of the mail steamers entered and cleared at Fremantle and Port Adelaide is out of all proportion to the goods landed and shipped there:—

State.	External Tonnage Entered and Cleared.						Percentage of each State to Total of Commonwealth.		
	1901.		1901.		1903.				
	Vessels	Tonnage.	Vessels	Tonnage.	Vessels	Tonnage.	1901.	1901.	1903.
New South Wales .....	2,149	2,621,579	2,529	4,519,711	2,519	4,748,329	29.7	38.4	41.0
Victoria .....	971	1,492,108	1,236	2,850,626	920	2,334,073	22.6	22.6	20.1
Queensland .....	405	426,642	584	620,692	500	697,967	6.6	6.0	6.0
South Australia .....	803	1,201,258	721	1,614,790	546	1,481,661	18.2	13.7	12.3
Western Australia .....	291	538,591	883	1,762,948	713	1,644,174	8.1	15.0	14.2
Tasmania .....	219	320,966	229	513,967	265	635,902	4.9	4.4	5.9
Total .....	4,838	6,601,173	6,122	11,761,729	5,463	11,592,006	100.0	100.0	100.0

A comparison between the shipping of the principal countries of the world and the external tonnage of the Commonwealth of Australia is appended:—

Country.	Tonnage Entered and Cleared.		Country.	Tonnage Entered and Cleared.	
	Total.	Average per head.		Total.	Average per head.
United Kingdom.....	105,619,344	2.4	Spain .....	30,091,799	1.6
Russia in Europe.....	19,548,000	0.1	Italy .....	46,298,739	1.4
Norway .....	6,490,786	2.9	United States .....	48,603,539	0.6
Sweden .....	16,566,699	3.2	Argentine Republic .....	17,195,713	3.6
Denmark .....	12,021,815	4.8	Canada .....	14,731,488	2.8
Germany .....	30,882,531	0.5	Cape Colony .....	12,511,691	5.1
Netherlands .....	18,936,046	3.5	New Zealand .....	2,215,229	2.7
Belgium .....	20,246,022	2.9	Commonwealth of Australia .....	11,592,006	3.0
France .....	38,644,015	1.0			

On the basis of population, therefore, the shipping of the states of the Commonwealth exceeds that of the United Kingdom and the great countries of the United States of America, France, Germany, Italy, Russia, and Spain.

## TONNAGE IN BALLAST.

A peculiar feature of the shipping trade is the small though varying proportion of tonnage in ballast arriving from and departing for places beyond Australia. Thus in the year 1881 this description of tonnage amounted to 5·2 per cent., and in 1891 to 4·1 per cent., of the total external shipping; while in 1903 the proportion was 7·2 per cent. The increase during recent years is chiefly due to the larger number of vessels which come to New South Wales in quest of freights, the proportion of shipping in ballast for that state being over 10 per cent. of the total external tonnage. The figures for Tasmania were again high in 1903, the tonnage in ballast being 12·6 per cent. of the total external tonnage, the proportion for the previous year being 14·4. Of the 86,615 tons entered and cleared this state in 1903, 15,671 tons represented sailing vessels entered in ballast from North America, and 16,077 tons sailing vessels in ballast from South Africa. Amongst the clearances there were no less than 10,420 tons representing sailing vessels cleared in ballast for Japan. The total external tonnage entered and cleared the Commonwealth in ballast during the years 1891, 1901, and 1903 was as follows:—

State.	External Tonnage Entered and Cleared in Ballast.			Percentage of Tonnage in Ballast to Total External Tonnage.		
	1891.	1901.	1903.	1891.	1901.	1903.
Commonwealth of Australia—						
New South Wales .....	100,167	579,904	517,012	3·8	12·8	10·9
Victoria .....	47,721	194,442	23,246	3·2	7·3	1·0
Queensland .....	36,700	24,869	25,945	8·6	3·6	3·7
South Australia .....	52,515	102,899	34,339	4·4	6·4	2·3
Western Australia .....	14,104	210,581	151,044	2·6	11·9	9·2
Tasmania .....	16,357	2,355	86,615	1·6	0·5	12·6
Total .....	267,564	1,115,050	838,201	4·1	9·5	7·2

The reason why so small a proportion of Australian shipping clears in ballast is principally to be found in the great and varied resources of the country; for when the staple produce—wool—is not available, cargoes of wheat, coal, silver, copper, live-stock, frozen meat, butter, fruit, tallow, leather, skins and hides, and other commodities may generally be obtained. Besides, owing to the great distance of the ports of the Commonwealth from the commercial centres of the old world, vessels are not usually sent out without at least some prospect of securing a return cargo. As a rule, it does not pay to send vessels to Australasia seeking freights, as is commonly done with regard to European and American ports. It is strong testimony, therefore, of the value of the trade of New South Wales to shipowners to find entered at the ports of that state direct from outside countries the comparatively large quantity of 419,700 tons of shipping in ballast, the following being the chief countries represented:—Cape Colony, 157,619 tons; New Zealand, 83,628 tons; Natal, 58,104 tons; Portuguese East Africa, 26,438 tons; Philippine Islands, 10,924 tons.

The tonnage in ballast which entered and cleared at New Zealand ports and the percentage of such to the total tonnage of that colony may be seen in the following table.

Year.	Tonnage in ballast.	Percentage to total tonnage.
1881 .....	76,247	9.0
1891 .....	103,754	8.3
1901 .....	191,266	8.9
1903 .....	175,335	7.9

The proportion of tonnage in ballast to the total shipping of some of the principal countries of the world is subjoined:—

Country.	Percentage of Shipping in Ballast.	Country.	Percentage of Shipping in Ballast.
United Kingdom .....	17.3	France .....	16.9
Russia in Europe .....	33.3	Spain .....	28.2
Norway .....	27.9	United States .....	16.1
Sweden .....	45.1	New Zealand .....	8.9
Germany .....	20.1	Commonwealth of Australia .....	7.2
Netherlands .....	33.2		
Belgium .....	22.2		

#### NATIONALITY OF ALL VESSELS.

The shipping trade of the Commonwealth of Australia and of the colony of New Zealand is almost entirely in British hands, as will be seen from the subjoined tables, which deal with the total tonnage, both inter-state and external. Although direct communication with continental Europe has been established within recent years, and several lines of magnificent steamers, subsidised by foreign Governments, have entered into the trade between Australia and foreign ports, yet the proportion of shipping belonging to Great Britain and her dependencies has only fallen from 86.8 to 85 per cent. during the period extending from 1891 to 1903. The chief increases during the period have been amongst vessels trading from Germany and Japan, the proportion of the former rising from 5.2 per cent. to 7 per cent., and of the latter from 0.2 per cent. to 1.2 per cent.:—

Nationality.	Total Shipping Entered and Cleared the Commonwealth.						Percentage of each Nationality.		
	1891.		1901.		1903.		1891.	1901.	1903.
	Vessels.	Tonnage.	Vessels.	Tonnage.	Vessels.	Tonnage.			
British .....	15,473	14,087,469	16,544	22,368,652	16,235	22,065,914	86.8	85.3	85.0
French .....	247	591,524	305	654,475	427	893,693	3.6	2.5	3.3
German .....	526	843,652	662	1,771,945	609	1,900,546	5.2	6.8	7.0
Scandinavian .....	319	292,071	408	350,040	239	277,428	1.8	1.3	1.0
Italian .....	11	9,736	93	118,881	109	150,368	0.1	0.5	0.6
Japanese .....	17	34,907	120	235,870	123	338,906	0.2	1.1	1.2
American .....	307	296,096	401	520,705	350	381,716	1.8	2.0	1.4
Other nationalities.	88	79,758	110	137,368	102	124,098	0.5	0.5	0.5
Total .....	16,987	16,235,313	18,638	26,197,436	18,158	27,152,668	100.0	100.0	100.0

The returns published by the various states are not in such a form as to admit of the separation of the purely local tonnage from the other shipping of the Empire, and vessels owned in the Commonwealth are classed in the above table as "British." The number and tonnage of the steam and sailing vessels registered in each of the states of the Commonwealth and New Zealand may be found on a succeeding page. Few of the large vessels employed in the inter-state trade have been built in Australia.

The nationality of vessels trading with New Zealand may be seen in the following table :—

Nationality.	Entered and Cleared New Zealand.						Percentage of each Nationality.		
	1891.		1901.		1903.		1891.	1901.	1903.
	Vessels.	Tonnage.	Vessels.	Tonnage.	Vessels.	Tonnage.			
British .....	1,350	1,120,435	1,234	1,881,590	1,090	1,881,619	90.0	85.6	84.9
French .....	4	1,862	1	1,562	1	1,248	0.2	0.1	0.1
German .....	16	12,876	2	1,684	13	16,103	1.0	0.1	0.7
Scandinavian .....	17	12,906	39	26,541	32	19,660	1.0	1.2	0.9
American .....	81	91,387	80	263,134	79	288,619	7.4	12.3	18.1
Other nationalities .....	4	4,856	23	14,609	10	7,980	0.4	0.7	0.3
Total .....	1,481	1,244,322	1,379	2,139,180	1,225	2,215,229	100.0	100.0	100.0

The following table shows the relative increase during the last ten years in British, foreign, and colonial trade with New Zealand, and the figures possess a certain amount of interest in view of the laws recently passed in that colony granting preferential trade in certain commodities to Great Britain :—

Year.	Shipping Entered and Cleared New Zealand.								
	British.			Colonial.			Foreign.		
	Vessels.	Tonnage.	Crews.	Vessels.	Tonnage.	Crews.	Vessels.	Tonnage.	Crews.
1894	281	542,458	12,893	855	616,597	26,806	87	103,161	4,054
1903	236	917,863	15,689	804	963,756	33,000	135	333,610	12,571

These figures apply to external trade only ; but in addition thereto, as might be expected in a country with such an extensive seaboard as New Zealand, there is a very large coastal trade, amounting in 1903 to 9,216,221 tons entered, and 9,266,980 cleared.

#### STEAM AND SAILING VESSELS.

The tendency to substitute steamers for sailing vessels, which is general throughout the world, is very marked in the Australian trade. Unfortunately the subdivision of the total tonnage into steam and

sailing was not obtainable for the whole of the Commonwealth States until 1902. It is not possible, therefore, to show the total increase of steam tonnage, but appended will be found the figures of the external trade of the various states so far as they can be given :—

State.	Steam Tonnage entered and cleared.			Percentage of Steam to Total Tonnage.		
	1891.	1901.	1903.	1891.	1901.	1903.
Commonwealth of Australia.....						
New South Wales.....	1,582,308	3,258,228	3,376,642	60·3	72·1	71·1
Victoria .....	1,044,467	2,194,863	2,061,472	70·0	82·8	88·3
Queensland .....	.....	.....	379,158	.....	.....	54·3
South Australia .....	.....	.....	1,306,201	.....	.....	88·3
Western Australia.....	483,460	1,460,619	1,347,584	89·8	82·9	82·0
Tasmania .....	287,188	488,379	564,518	89·5	95·0	82·3
Colony of New Zealand .....	822,086	1,860,622	1,990,423	66·1	87·0	89·9

The substitution of steam for sailing vessels in the shipping trade of some of the principal countries of the world may be gathered from the following table. The figures refer in most cases to the year 1902, the latest for which information is obtainable for the places specified :—

Country.	Percentage of Steam to Total Tonnage.		
	1881.	1891.	1902.
United Kingdom.....	67·7	84·2	94·8 (1903)
Russia in Europe.....	74·3	91·0	95·9
Norway .....	31·1	55·7	72·0
Sweden .....	46·8	72·1	84·5
Denmark .....	61·9	81·7	86·9
Germany .....	70·8	87·2	91·5
Netherlands.....	74·4	92·5	97·1
Belgium .....	81·3	94·0	96·5
France .....	69·5	87·0	95·0
Portugal .....	52·1	93·6	98·0
Spain.....	.....	94·0	98·0
Italy .....	72·8	88·3	97·3
United States .....	55·5	72·3	87·9
Argentine Republic .....	70·4	86·7	93·7
Canada .....	.....	66·2	82·9
Cape Colony .....	62·5	79·8	90·1
Natal .....	.....	91·3	93·1
New Zealand .....	.....	66·1	89·9
Commonwealth of Australia.....	68·6	81·8	78·0 } 1903

A comprehensive view of the changes which have taken place since the year 1881 in the class of vessel engaged in the inter-state and the



external shipping trade of the Commonwealth is afforded by the following figures :—

Year.	Vessels.	Tonnage.	Average Tonnage per vessel.
INTER-STATE SHIPPING.			
1881	10,484	4,941,294	471
1891	12,149	9,634,040	793
1901	12,516	14,435,707	1,153
1903	12,695	15,560,662	1,225
EXTERNAL SHIPPING.			
1881	3,924	3,168,630	808
1891	4,838	6,601,173	1,364
1901	6,122	11,761,729	1,921
1903	5,463	11,592,006	2,122
ALL COMMONWEALTH SHIPPING.			
1881	14,408	8,109,924	563
1891	16,987	16,235,213	956
1901	18,638	26,197,436	1,406
1903	18,158	27,152,668	1,496

As the table shows, the total number of vessels engaged in the shipping trade of the Commonwealth of Australia during 1903 was 1,171 more than the figure for 1891, and the returns of tonnage show an increase of over 10½ millions. The average tonnage of shipping is 1,496, as compared with 956 in 1891, and 563 in 1881. The explanation of this increase of course lies in the fact that a superior type of vessel is now engaged in the shipping trade, and the enterprise of the great British and foreign trading companies will doubtless have the effect of raising still higher the average for succeeding years. Several of the vessels belonging to the fleet of the North German Lloyd are over 10,000 tons, the largest exceeding 13,000 tons. The Peninsular and Oriental Company possesses a magnificent fleet, the steamers ranging in size from 6,600 tons to 10,500 tons. The average tonnage of the steamers of the Orient Pacific Royal Mail Line is over 7,200 tons, of the Messageries Maritimes 6,500 tons, and of the White Star Line, the vessels of which were built principally as cargo carriers, 12,000 tons. Considerable impetus has been given to the foreign shipping trade with Australia through the subsidising of the lines by several of the foreign governments. The North German Lloyd, for example, receives an annual subsidy from the German Government of £115,000, equal to 6s. 8d. per mile. To protect the interests of the German agriculturists it is stipulated in the agreement that the vessels

shall not carry on their homeward journey frozen meat, dairy produce, or cereals in the nature of those grown in Germany. The Japanese Government subsidises its steamers trading to Australia to the extent of £50,000 per annum, and the Messageries Maritimes receives a subsidy of 8s. 4d. per mile. The British lines—the Peninsular and Oriental and the Orient Pacific—each receive £85,000 per annum for carrying the mails to and from Australia.

It is somewhat remarkable to find that the vessels engaged in the inter-state trade have more than kept pace in increase of tonnage with those trading between the Commonwealth and other countries. Of course, the increase in the average tonnage of inter-state vessels is represented as greater than it actually has been, because the mail-steamers on their way to Sydney are cleared at Fremantle, Adelaide, and Melbourne for the states further east; but when allowance has been made on this score, the improvement in the class of vessel trading in local waters will be found most noteworthy. It is well known, however, that the steamers running on the Australian coast favourably compare with those engaged in the coasting trade of any of the great maritime countries of the world. Several of the vessels are over 7,000 tons burthen, and are provided with twin screws and fitted with the most modern appliances and conveniences for the transport of passengers and cargo.

The trade of the Commonwealth with New Zealand appears as external shipping in all returns given in this chapter, and has, therefore, not been distinguished separately, but in the following table will be found figures showing the total shipping of that colony with all countries :—

Year.	Vessels.	Tonnage.	Crews.	Average Tonnage per Vessel.	Average Tonnage per hand.
1881	1,527	833,621	30,409	546	27
1891	1,481	1,244,322	43,969	840	28
1901	1,379	2,139,180	59,752	1,551	36
1903	1,225	2,215,229	61,260	1,808	36

The improvement in the class of vessel engaged in the trade will be apparent from the fact that although the number of vessels has decreased by 256 since 1891, the total tonnage has increased by about 971,000 tons, while the average per vessel is more than double that of 1891.

#### RELATIVE IMPORTANCE OF PORTS.

The relative importance of the various ports of the Commonwealth of Australia and New Zealand may be ascertained by an inspection of the table given hereunder. Melbourne takes first place in the amount of tonnage; but the figures are inflated by the counting of the great

ocean steamers as twice entering and twice clearing at Port Phillip. This remark applies equally to Port Adelaide and Albany, and in the last two years to Fremantle. If allowance be made on this score, it will be found that Sydney has a larger quantity of shipping than any other Australasian port, and that it is followed by Melbourne, Newcastle, and Port Adelaide. The figures for the years 1881 and 1891 given for Queensland ports, other than Brisbane, include coastal trade, and the quantity of tonnage shown for these years is, therefore, somewhat in excess of the truth. As this table is only intended to show the relative importance of ports, the inter-state shipping of the Commonwealth has not been excluded, but no account has been taken of the purely coastal trade within each state:—

Port.	Total Tonnage entered and cleared.			
	1881.	1891.	1901.	1908.
COMMONWEALTH OF AUSTRALIA.				
New South Wales—				
Sydney .....	1,610,692	3,469,862	5,413,677	5,934,411
Newcastle .....	1,127,238	1,844,842	2,609,861	2,673,605
Wollongong .....	14,642	101,888	300,699	204,730
Victoria—				
Melbourne .....	2,144,949	4,362,138	6,366,103	6,487,290
Geelong .....	93,347	190,932	259,573	278,458
Queensland—				
Brisbane .....	406,032	855,993	1,207,295	1,408,794
Townsville .....	205,886	544,470	95,101	98,311
Rockhampton .....	207,706	471,837	36,653	14,520
Cooktown .....	217,144	469,577	31,670	16,316
Cairns .....	56,447	326,898	4,084	524,662
Mackay .....	104,174	330,119	4,473	410,521
South Australia—				
Port Adelaide .....	1,078,920	1,990,938	3,296,108	3,568,997
Port Pirie .....	33,325	321,781	376,856	242,569
Port Darwin .....	90,100	170,642	163,705	194,736
Western Australia—				
Fremantle .....	42,618	63,068	1,864,195	2,117,454
Albany .....	219,902	931,502	1,667,707	877,224
Bunbury .....	7,905	1,189	8,942	235,958
Tasmania—				
Hobart .....	204,007	646,683	870,733	1,142,756
Launceston .....	138,657	293,537	199,444	238,401
Devonport .....	.....	8,121	124,964	219,559
NEW ZEALAND.				
Wellington .....	119,243	293,451	591,154	715,117
Auckland .....	238,886	345,183	736,005	805,340
Bluff Harbour .....	91,692	196,540	303,496	274,524
Lyttelton .....	167,151	161,387	208,476	116,402
Dunedin .....	114,637	97,409	112,718	112,541

A better idea of the relative importance of the principal ports of the states is obtainable from the trade figures, which are given below for the year 1903 :—

Port.	Total Trade.	Average per ton of Shipping.	Port.	Total Trade.	Average per ton of Shipping.
New South-Wales—	£	£ s. d.	Western Australia—	£	£ s. d.
Sydney.....	41,607,263	7 0 3	Fremantle .....	13,098,197	6 3 8
Newcastle .....	3,193,786	1 3 11	Albany.....	953,127	1 1 9
Victoria—			Tasmania—		
Melbourne .....	32,584,784	5 0 6	Hobart .....	1,860,895	1 12 7
Queensland—			Launceston .....	1,760,553	7 7 8
Brisbane .....	5,862,245	4 3 3	New Zealand—		
South Australia—			Wellington .....	6,704,653	9 4 9
Port Adelaide.....	9,603,611	2 13 11	Auckland.....	5,668,790	7 0 9

The comparative importance of the ports of the Commonwealth of Australia and New Zealand may be seen by viewing them in connection with the shipping and trade of the chief ports of the United Kingdom, the 1902 figures for which are appended. It will be seen that in aggregate tonnage Melbourne is exceeded only by London, Liverpool, Cardiff, and Newcastle. Sydney comes next on the list, exceeding all other British ports. In value of trade Sydney is exceeded only by London, Liverpool, and Hull. If the Commonwealth of Australia be regarded as one country, however, the comparison is somewhat misleading, as the inter-state trade has been included in the returns :—

Port.	Total Shipping.	Total Trade.	Port.	Total Shipping.	Total Trade.
England and Wales—	tons.	£	Scotland—	tons.	£
London.....	19,063,829	268,109,356	Glasgow .....	4,297,054	35,654,729
Liverpool.....	14,499,618	243,607,200	Leith .....	1,952,570	18,612,496
Cardiff .....	13,179,156	14,660,914	Kirkcaldy ...	2,297,199	1,700,823
Newcastle and N. & S. Shields	9,021,217	17,725,844	Grangemouth.	1,440,229	5,081,729
Hull .....	4,686,918	52,655,977	Ireland—		
Southampton ..	3,758,801	30,327,773	Belfast .....	716,569	8,895,730
Sunderland ....	1,941,790	2,327,037	Dublin .....	425,097	3,260,414
Grimsby .....	1,749,155	20,397,588	Cork .....	169,537	1,199,971
Dover .....	1,895,399	12,034,875	Australia—		
Newport .....	2,712,574	4,913,629	Sydney.....	5,934,411	41,607,263
Harwich .....	1,477,382	24,092,151	Melbourne ...	6,487,290	32,584,784
Bristol .....	1,366,487	14,905,945	Brisbane .....	1,408,794	5,862,245
Newhaven.....	661,006	14,316,213	Adelaide .....	3,563,987	9,603,611
Swansea .....	2,470,614	10,040,222	Fremantle ...	2,117,454	13,098,197
Manchester ....	1,962,579	29,576,320	Hobart .....	1,142,756	1,860,895
Middlesbrough	1,801,241	5,995,892	New Zealand—		
			Wellington ...	715,117	6,704,653
			Auckland.....	805,340	5,668,790

The yearly movement of tonnage at Melbourne and Sydney far exceeds that of the ports of any other British possession, Hong Kong and Singapore excepted. Two other exceptions might be mentioned—

Gibraltar and Malta; but as these are chiefly ports of call, and the trade is very limited compared with the tonnage, they can scarcely be placed in the same category.

#### REGISTRATION OF VESSELS.

The number and tonnage of steam and sailing vessels on the registers of each of the six states of the Commonwealth and the colony of New Zealand at the end of 1903 are given below :—

State.	Steam.		Sailing.		Total.	
	Vessels.	Net Tonnage.	Vessels.	Net Tonnage.	Vessels.	Net Tonnage.
Commonwealth of Australia—						
New South Wales .....	540	67,469	527	55,386	1,067	122,855
Victoria .....	159	77,071	223	36,055	382	113,126
Queensland .....	85	13,751	98	5,939	183	19,690
South Australia .....	113	38,029	216	19,560	329	57,589
Western Australia .....	36	13,548	288	8,064	324	21,612
Tasmania .....	57	9,038	150	8,744	207	17,782
Total—Australia ...	990	218,906	1,502	133,748	2,492	352,654
Colony of New Zealand ...	235	62,722	335	43,897	570	106,619

For comparative purposes a statement is subjoined, showing the merchant navies of some of the principal maritime countries of the world. In considering the figures, allowance must be made for the fact that the minimum tonnage of vessels included in the registrations is not the same in every instance. Thus for Norway it is 4 tons; Sweden, 20 tons; Denmark, 4 tons; France, 2 tons; Italy, 2 tons; Germany, 17½ tons; and the United States, 5 tons.

Country.	Steam.		Sailing.		Total.	
	Vessels.	Net Tonnage.	Vessels.	Net Tonnage.	Vessels.	Net Tonnage.
United Kingdom .....	10,122	8,399,668	10,330	1,868,936	20,452	10,268,604
New Zealand .....	235	62,722	335	43,897	570	106,619
Canada .....	2,419	338,251	4,601	344,896	7,020	683,147
Australia .....	990	218,906	1,502	133,748	2,492	352,654
Russia and Finland .....	1,394	441,598	4,984	568,568	6,378	1,010,166
Norway .....	1,290	567,161	5,569	883,955	6,859	1,451,116
Sweden .....	965	361,756	2,167	296,874	3,132	658,630
Denmark .....	533	272,883	3,372	158,845	3,905	431,728
German Empire .....	1,545	1,622,439	2,500	581,365	4,045	2,203,804
Austria .....	140	235,990	30	18,369	170	254,359
Hungary .....	64	83,745	13	6,543	77	90,288
Netherlands .....	257	334,398	436	72,911	693	407,309
Belgium .....	68	105,305	5	877	73	106,182
France .....	1,330	548,921	14,691	668,693	16,021	1,217,614
Spain .....	520	727,945	466	83,157	986	811,102
Italy .....	485	448,404	5,205	570,403	5,690	1,018,807
United States .....	8,064	3,466,088	16,371	2,679,257	24,425	6,086,345

## WAGES OF SEAMEN.

In calculating the average wages paid to seamen, regard must be had to the fact that shipping companies, in some instances, take into consideration personal qualifications and length of service of employees, when fixing rates. The following table shows the average wages, per calendar month, in 1903, paid to white crews of British ocean-going steamers trading with the Commonwealth, and also the rates for white crews of steamers engaged in the inter-state trade. The rates were obtained from the ships' articles deposited with the state shipping officers :—

Capacity	Average monthly wages. White crews.		Capacity.	Average monthly wages. White crews.	
	Ocean-going steamers.	Inter-State steamers.		Ocean-going steamers.	Inter-State steamers.
Navigation—	£ s.	£ s.	Cooking and Providoring—	£ s.	£ s.
1st Mate .....	15 0	15 0	Purser .....	£10 to £25	10 0
2nd „ .....	10 0	12 0	Chief Cook .....	11 0	12 0
3rd „ .....	8 0	10 0	2nd „ .....	6 0	7 0
Boatswain .....	6 10	7 10	Baker .....	6 0	8 0
Carpenter .....	7 10	8 10	Butcher .....	6 0	5 0
A.B. Seaman .....	4 0	6 10	Pantryman .....	4 0	5 10
Ordinary Seaman .....	2 5	3 0	Attendance—		
Winchman .....	7 0	9 10	Head Steward .....	10 0	12 0
Engineer's Department—			2nd „ .....	7 0	7 0
1st Engineer .....	25 0	£22 to £25	Stewardess .....	2 10	2 10
2nd „ .....	15 0	£17 to £18	General Servant .....	3 0	4 0
3rd „ .....	12 10	£14 to £15			
4th „ .....	10 0	12 0			
5th „ .....	8 0	10 0			
6th „ .....	8 0	10 0			
Fireman .....	4 0	8 10			
Greaser .....	4 10	8 10			
Trimmer .....	3 10	6 10			

The crews of some of the British steamers trading to the Commonwealth are composed partly of coloured seamen, chiefly Lascars and

Chinese. In the following table will be found the average rates of wages paid to the various employees in this class :—

Capacity.	Ocean-going steamers.		Capacity.	Ocean-going steamers.	
	Average monthly wages.			Average monthly wages.	
	Lascars.	Chinese.		Lascars.	Chinese.
Navigation—	£ s. d.	£ s. d.	Cooking and Providoring—	£ s. d.	£ s. d.
1st Serang (Boatswain) . . .	2 8 8	2 8 0	Bhandary (Cook) . . . . .	1 6 8	1 3 0
1st Tindal (Boatswain's Mate) . . . . .	1 17 4	....	Baker . . . . .	2 0 0	....
2nd " " . . . . .	1 14 8	....	Casub (Storekeeper) . . . . .	1 10 0	1 18 4
3rd " " . . . . .	1 12 0	....	Butcher . . . . .	2 6 8	....
Seacox ("Helmsman") . . . . .	1 17 4	....	Pantryman . . . . .	1 5 0	....
Carpenter . . . . .	2 17 6	....	Scullion . . . . .	0 17 4	....
Winchman . . . . .	1 9 4	1 18 4	Knifeman . . . . .	0 17 4	....
Oilman . . . . .	1 13 4	....	Ice-man . . . . .	0 18 8	....
Lascars (not otherwise described) . . . . .	1 4 0	....	Paniwalla (Water Turn-cock) . . . . .	1 10 0	....
Engineers Department—			Attendance—		
Fireman . . . . .	1 2 8	1 10 8	Waiter . . . . .	1 6 8	1 18 4
Trimmer . . . . .	0 16 0	1 6 8	Topass (Sweeper) . . . . .	0 16 0	....
			Cabin Boy . . . . .	0 16 0	1 8 9

## COMMERCE.

THE external trade of Australia is larger than that of any British possession, India alone excepted, and if the transit and re-export trade be excluded, compares very favourably as regards proportion to population with that of any other country. The growth of Australian trade is shown in the following table:—

Year.	Imports.	Exports.	Total Trade.	Value per Inhabitant.
	£	£	£	£ s. d.
1861.....	17,562,960	17,399,656	34,962,616	30 5 10
1871.....	16,715,442	21,225,797	37,941,239	22 14 10
1881.....	29,031,131	27,528,583	56,559,714	24 16 0
1891.....	37,711,053	36,052,145	73,763,198	22 19 1
1901.....	42,433,811	49,696,172	92,129,983	24 4 3
1902.....	40,675,950	43,915,087	84,591,037	21 17 10
1903.....	37,811,471	48,170,164	85,981,635	21 18 11

Large as these totals are, they would be still larger had a proper record been kept of the imports and exports. Until September, 1903, it was the practice of the various customs offices to ignore transshipments, so that goods which arrived from a country outside Australia at any Australian port, and were thence transhipped to another Australian state, were recorded in the state at which they ultimately arrived as an import from the state where they were transhipped, and not as they ought to have been, as an oversea import. On the other hand, as regards goods of Australian produce sent from one state to another and thence transhipped oversea, the only record of the movement was in the returns of the original state, where they were treated as exports to the transshipping state, no record being kept of the movement oversea. It is estimated that if these movements—inwards and outwards—had been recorded properly as they have been since 1st September, 1903, the imports for the year 1901 would be over two millions greater than is shown, and for 1902 more than one and a half millions; while for the first eight months of 1903 the difference would be a little over a million. For 1901 and 1902 the amount to be added to the exports is between three and four millions. During the last four months of 1903 the transshipments from New South Wales and Victoria, the only states affected by the outward movement, amounted to £1,108,546. The additions to be made to the imports and exports on



this account will, however, be more accurately known later when the matter has been more fully investigated.

The imports recorded during 1903 from countries outside Australia into the states comprised in the Commonwealth were as follows :—

State.	Value of Imports.	Value per Inhabitant.
	£	£ s. d.
New South Wales .....	13,977,917	9 16 5
Victoria .....	12,389,615	10 3 11
Queensland .....	3,249,627	6 5 5
South Australia .....	3,224,370	8 15 7
Western Australia.....	4,228,554	19 4 0
Tasmania .....	791,388	4 8 8
Commonwealth .....	37,811,471	9 13 0

The values of the external exports for 1903 were as shown below :—

State.	Value of Exports.	Value per Inhabitant.
	£	£ s. d.
New South Wales .....	18,861,213	13 4 9
Victoria :.. .....	11,188,939	9 4 10
Queensland .....	3,728,975	7 3 9
South Australia .....	3,638,242	9 18 2
Western Australia.....	9,458,125	42 18 11
Tasmania..... .....	1,296,670	7 5 4
Commonwealth .....	48,170,164	12 5 11

The total extra-Australian trade for the year 1903 was therefore as follows :—

State.	Total Extra Australian Trade.	Value per Inhabitant.
	£	£ s. d.
New South Wales .....	32,839,130	23 1 2
Victoria .....	23,528,554	19 8 9
Queensland .....	6,976,602	13 9 2
South Australia .....	6,862,612	18 13 9
Western Australia.....	13,686,679	62 2 11
Tasmania..... .....	2,088,058	11 14 0
Commonwealth .....	85,981,635	21 18 11

As the table shows, the total value of the external trade of the Commonwealth in 1903 was £85,981,635, equal to £21 18s. 11d. per head of population. These figures indicate an improvement on the returns for 1902, when the trade was valued at £84,593,461, or £21 17s. 10d. per head of population. Turning to individual states, it will be found that in proportion to population, the trade of Western Australia is far in excess of that of any of the other Commonwealth

states. This of course is only to be expected in a rich gold-producing state with a comparatively small population. New South Wales comes next with £23 1s. 2d., followed by Victoria with £19 8s. 9d., Tasmania occupying the lowest position with £11 14s. 0d. per inhabitant. Comparisons of this description are, however, apt to mislead, since states like Queensland and Tasmania, possessing but a small direct trade, appear at a disadvantage.

The foregoing represent the figures as returned by the statistical branches of the various Customs departments. As regards imports, the value represents the amount on which duty is payable or would be payable if the duty were *ad valorem*. The value of goods subject to duty is taken to be the fair market value in the country of origin, with an addition of 10 per cent. to such value. The value of goods exported is the value in the principal markets of the Commonwealth in the ordinary commercial acceptance of the term.

The trade of the last three years represents an average of £22 13s. 5d. per inhabitant, including a very small re-export trade. Similar information for some of the more important countries of the world is as follows:—

Country.	Total Trade.	Value per Inhabitant.
	£	£ s. d.
Argentine Republic .....	56,505,196	11 6 0
Austria-Hungary .....	151,516,000	3 8 9
Belgium .....	172,232,000	25 14 8
Denmark .....	56,293,070	22 16 8
France .....	352,390,440	9 0 10
Germany .....	530,931,000	9 7 5
Greece .....	8,601,170	3 10 8
Italy .....	131,716,830	3 19 9
Portugal .....	18,906,900	3 9 8
Roumania .....	28,326,600	4 8 10
Russian Empire .....	142,277,000	1 2 1
Spain .....	62,518,150	3 7 2
Sweden .....	45,545,500	8 15 0
Norway .....	25,560,800	11 8 2
Switzerland .....	84,966,410	25 12 5
Turkey (Europe and Asia) .....	36,079,150	1 11 14
United Kingdom .....	808,815,270	19 6 0
United States .....	503,739,690	6 12 0
Japan .....	55,865,600	1 5 6

The trade of Australia, per inhabitant, exceeds that of any of the countries included in the foregoing list with the exception of Belgium. It would appear that the trade of the Netherlands and Switzerland, compared with population, is greater than that of Australia; but it is impossible to arrive at comparative figures for either of these states, so great is their transit and re-export business.

The articles imported into Australia cover a long list; for tariff purposes they have been divided into sixteen divisions, and for convenience of reference to the tariff these divisions have been maintained.

Imports into Australia during 1903 from countries beyond the Commonwealth were as follows:—

Article.	Quantity.	Value.
DIVISION I.—STIMULANTS.		£
Ale, Porter, and other Beer, Cider and Perry—		
Bottled .....	gal 2,108,010	360,733
Other .....	" 470,338	42,862
Spirits—		
Brandy, Bottled .....	" 113,488	80,958
Bulk .....	" 139,594	43,306
Gin, British .....	" 52,398	12,739
Hollands, or Geneva .....	" 198,201	23,864
Schnapps .....	" 117,539	30,484
Rum, Bottled .....	" 10,903	3,688
Bulk .....	" 145,210	17,806
Whisky, Bottled .....	" 361,102	152,466
Bulk .....	" 1,056,415	291,657
Amylic Alcohol and Fusel Oil .....	" 118	22
Bitters .....	" 2,492	2,493
Cordials, or Liqueurs, and other Spirituous Compounds, n.e.i. ....	" 17,051	9,267
Collodion .....	" 909	400
Methylated .....	" 312	36
Perfumed and Rav Rum .....	" 9,172	32,750
Essences, Tinctures, Extracts .....	" 20,446	33,282
Sarsaparilla .....	" 6,039	7,753
All Other .....	" 25,553	13,431
Wine, Fermented—Sparkling .....	" 41,211	78,999
N.E.I., including Medicinal or Medicated, and Vermouth, in Bottle .....	" 20,085	10,653
N.E.I. Other .....	" 61,137	18,961
Total, Division I.....		£1,290,578
DIVISION II.—NARCOTICS.		
Opium .....	lb. 42,429	50,138
Tobacco—		
Manufactured .....	" 2,508,342	133,327
Unmanufactured .....	" 321,803	15,749
Unmanufactured, but entered to be locally made into Tobacco, Cigars, or Cigarettes .....	" 4,835,190	217,135
Cigars .....	" 305,705	106,622
Cigarettes .....	" 131,816	41,823
Snuff .....	" 6,901	1,114
Total Division II.....		£629,914
DIVISION III.—SUGAR.		
Saccharine .....	lb. 1,375	716
Sugar—The Produce of Sugar Cane .....	cwt. 1,830,595	1,054,338
Golden Syrup and Syrups, n.e.i. ....	" 2,670	2,373
Glucose .....	" 46,621	26,971
Molasses .....	" 13,169	1,715
Other .....	" 1,719	985
Total, Division III .....		£1,087,098

Article.	Quantit	Value.
DIVISION IV.—AGRICULTURAL PRODUCTS AND GROCERIES.		<b>£</b>
Aerated and Mineral Waters .....		12,615
Animals (Living)—		
Birds .....		3,723
Cattle .....	No. 161	9,569
Dogs .....	" 79	1,160
Horses .....	" 181	14,278
Pigs .....	" 21	121
Poultry .....	" 577	1,167
Sheep .....	" 4,727	9,840
Other .....		826
Arrowroot .....	lb. 80,043	1,912
Biscuits .....	" 263,973	10,398
Blue, Laundry .....	" 196,188	4,904
Broom Corn Millet .....	cental 680	660
Butter .....	lb. 1,887,148	88,754
Candles, Tapers, Night Lights, or Solid Spirit Heaters .....	" 3,352,049	66,506
Caramel, Caramel Paste, and Caramel Butter .....	" 137,931	1,633
Cheese .....	" 1,141,300	33,071
Cocoa and Chocolate, Ground, or in any way manufactured .....	" 2,103,790	128,103
Coffee and Chicory, Raw, and Kiln-dried .....	" 1,425,415	40,080
Roasted, or Ground, and in Liquid Form .....	" 307,177	16,372
Confectionery, n.e.i. ....	" 2,651,227	80,024
Copra .....	cwt. 269,047	157,510
Eggs .....	doz. 161,099	3,748
Fish—		
Fresh Oysters .....	cwt. 7,269	3,526
Fresh .....	lb. 8,750	136
Smoked or Preserved by Cold Process .....	" 931,087	14,622
Potted or Concentrated, including Extracts .....		12,998
Preserved in Tins, or other Air-tight Vessels .....	" 13,283,471	272,572
N.E.I. ....	cwt. 20,913	30,905
Fodder (Including Compressed Fodder) .....	" 18	5
Fruits and Vegetables—		
Fruits, Dried—		
Currants .....	lb. 8,640,693	61,313
Dates .....	" 2,587,328	13,544
Raisins .....	" 1,237,470	16,549
Other .....	" 1,013,765	15,033
N.E.I., Preserved in Liquid, or Partly Preserved or Pulped, Half-pints, or Smaller Sizes .....	doz. 1,775	364
Pints and over Half-pints .....	" 96,114	16,050
Quarts and over Pints .....	" 19,357	4,991
Exceeding a Quart .....	" 9,370	1,097
Fruits, Fresh—		
Apples .....	cental 4,222	3,796
Bananas .....	" 47,641	12,972
Oranges and Lemons .....	" 33,527	24,391
Pineapples .....	" 401	306
N.E.I. ....	" 6,175	5,834
Vegetables—		
Dried or Concentrated .....		5,109
N.E.I. ....	" 4,451	1,679
Ginger—		
Preserved in Liquid .....	lb. 199,052	2,664
Preserved, not in Liquid .....	" 455,845	6,935
Green .....	" 446,788	6,126
Grain and Pulse—		
Barley .....	bush. 731,494	136,997
Beans and Peas .....	" 51,808	13,215
Maize .....	" 1,346,702	204,484
Oats .....	" 2,086,335	222,306
Wheat .....	" 9,114,490	1,989,483
N.E.I. ....	cental 28,146	19,445
Prepared or Manufactured—		
Barley, Pearl and Scotch .....	lb. 119,400	594
Bran, Pollard, and Sharps .....	bush. 572,715	29,940
Flour .....	ton 69,869	647,485
Groats .....	lb. 306,948	7,149

Article.	Quantity.	Value.
DIVISION IV.—AGRICULTURAL PRODUCTS AND GROCERIES—contd.		\$
Grain and Pulse—		
Prepared or Manufactured—		
Malt (including Granulated Malt and Rice Malts) .....	bush. 175,512	54,832
Maizena and Cornflour .....	lb. 2,284,352	22,576
Oatmeal, Wheatmeal, and Rolled Oats .....	cwt. 16,220	17,206
Pean. Split .....	" 3,059	1,783
Rice, Uncleaned .....	" 156,706	31,222
Rice, for Manufacturing Starch .....	" 6,781	2,900
Rice, N.E.I. ....	" 260,115	140,226
N.E.I. ....	cental 42,850	22,025
Hay and Chaff .....	cwt. 17,244	3,143
Honey .....	lb. 205	5
Hops .....	" 975,658	57,019
Isinglass .....	" 42,307	6,466
Jams and Jellies .....	" 379,300	7,410
Lard, and Refined Animal Fats .....	" 608,798	17,708
Limejuice and Other Fruit Juices and Fruit Syrups—Non-Spirituos.	gal. 47,266	7,573
Linned .....	cental 10,066	5,022
Linned Meal .....	" 189	103
Linned Cake and Oil Cake .....	" 40,477	9,451
Liquorice—Crude .....	lb. 206,980	7,062
" Other .....	" 146,037	4,912
Macaroni and Vermicelli .....	" 316,179	3,964
Malt Extract, non-spirituos .....	" 88,212	2,684
Manures .....	cwt. 1,588,808	246,746
Matches and Vestas—Wax .....	gross 799,483	80,203
" " Wood or Other .....	" 445,167	22,739
Meats—		
Bacon and Ham, partly or wholly cured .....	lb. 626,791	24,152
Preserved by Cold Process—Beef .....	" 1,176,671	30,429
" " " Game .....	" 12,830	711
" " " Mutton and Lamb .....	" 917,964	13,038
" " " Pork .....	" 2,467,782	65,136
" " " Poultry .....	" 23,601	963
" " " Other .....	" 2,701	5,757
Fresh and Smoked .....	" 2,701	99
rotted and Concentrated, including Extracts of and Caviare .....		49,506
Preserved in tins or other air-tight vessels .....	lb. 617,156	25,795
N.E.I. ....	cwt. 3,760	6,807
Milk and Cream—Concentrated .....	lb. 4,637	98
" " Preserved .....	" 12,664,776	288,632
Mustard .....	" 645,109	24,032
Nuts, Edible—Almonds .....	" 319,002	12,428
" " Cocoanuts .....	cwt. 8,672	1,092
" N.E.I., Whole or Prepared, including Cocoanuts Prepared .....	lb. 1,024,703	22,803
Oldman's Stores, n.e.i. ....		59,694
" " Free, including Infants' and Invalids' Foods, Special Preparation of .....		57,923
Onions .....	cwt. 1,190	613
Peel, Drained or Preserved in Brine, Acid, or Water .....	lb. 1,515,089	5,161
" Preserved, not in Liquid .....	" 84,592	736
Pickles, Sauces, Chutneys, Olives, and Capers—		
Quarter pints and smaller sizes .....	doz. 42,123	7,558
Half pints, and over quarter pints .....	" 121,890	40,210
Pints, and over half pints .....	" 58,034	20,941
Quarts, and over pints .....	" 6,108	2,758
Exceeding a quart .....	gal. 30,116	1,766
Potatoes .....	cwt. 47,831	7,752
Rape .....	cental 12,727	5,012
Salt, Brown Rock .....	cwt. 139,685	7,400
" N.E.I. ....	" 172,996	12,144
Sausage Casings .....		24,065
Seeds—		
Canary, Hemp, and Rape .....	cental 49,198	22,081
Mustard .....	lb. 120,270	1,262
Other .....		57,310
Soap, Perfumed Toilet, etc. ....	lb. 755,375	87,098

Article.	Quantity.	Value.
DIVISION IV.—AGRICULTURAL PRODUCTS AND GROCERIES— <i>contd.</i>		\$
Soap, N.E.I. ....	lb. 189,829	2,530
Sparklets .....	.....	9,319
Spices—		
Pepper, Ground .....	lb. 9,305	438
"    Unground .....	" 680,892	21,329
Other, Ground, n.e.i. ....	" 194,216	9,460
"    Unground, n.e.i. ....	" 907,321	22,194
Starch, including Starch in powdered form .....	" 1,561,851	15,806
"    Flours, including Rice Meal and Rice, Tapioca, and Potato Flours .....	" 503,004	2,300
Stearine .....	" 817,508	12,894
Straw .....	cwt. 21,501	2,119
Tallow, n.e.i. ....	" 7,528	9,989
Tapioca .....	cental 44,653	17,832
Tea .....	lb. 24,716,420	696,881
Wax—		
Beeswax .....	" 12,851	652
Japanese or Vegetable .....	" 59,923	1,753
Paraffin .....	" 4,769,915	55,512
Wine, Unfermented .....	gal. 96	35
Total, Division IV .....	.....	7,004,685
DIVISION V.—APPAREL AND TEXTILES		
Apparel and Attire—		
Articles, n.e.i. ....		1,162,449
Diving Dresses .....		5,161
Socks and Stockings (Cotton) .....		99,511
(Woolen, or containing Wool) .....		187,683
Towels and Handkerchiefs (made of Cotton or Linen) .....		129,472
Military or Naval Clothing for the Army or Navy .....		7,584
Regalia, viz., Embroidery Woven Sashes .....		310
Minor Articles for .....		192,178
Bags and Sacks (durable) .....		7,028
Bags, Sacks, Packs, and Bales (free) .....	doz. 2,275,922	550,746
Blankets and Blanketing .....		70,946
Canvas (Tent and Sail), and Duck, Hessians, Bunting, and Brattice Cloth .....		140,765
Carpets and Carpeting .....		97,899
Coses, Cushions, Mantel and Furniture Drapery and Coverings, Bed-covers and Furnishings, n.e.i. ....		117,125
Cotton—Wick, Candle, and Lamp .....		5,890
Curtains .....		74,050
Feathers (dressed) .....		19,619
"    (undressed) .....		1,727
Floor Cloths and Coverings .....		202,632
Frillings, Ruffings, Tucked Lawns, Pleatings, and Ruchings .....		13,019
Furs, Dressed or Prepared .....		8,413
Hatters' .....		219
Gloves (including Mittens and Flesh Gloves) .....		179,067
Hats and Caps—		
Men's, Women's, Boys', and Children's Felt Hats .....		126,397
Dress Hats .....		1,091
Bewn .....		8,275
Firemen's Helmets and Miners' Caps .....		159
Hats, Caps, and Bonnets, n.e.i., and Hat and Bonnet Shapes .....		179,190
Hats and Caps—Felt Pullover Hoods .....		1,054
Minor Articles for .....		55,877
Mats, n.e.i., including Carriage Mats .....		15,533
Piece Goods .....		
Cotton and Linen .....		2,055,188
Horsehair Cloth and Hop Cloth .....		9,436
Silk, or containing Silk, or having Silk worked thereon .....		545,010
Silk, Milling .....		1,186
Velvets, Velvetines, Flushes, &c. ....		495,983
Woolens, or containing Wool, n.e.i. ....		1,377,799

Article.		Quantity.	Value.
<b>DIVISION V.—APPAREL AND TEXTILES—continued.</b>			<b>£</b>
Piece Goods—			
Flannels .....			53,071
Flannelettes .....			203,589
Woolens (Free) .....			18,179
Cloakings, Vestings, and Trouserings, n.e.i. ....			67,414
Piece Goods, to be used in the manufacture of cloth made Waterproof with Indiarubber .....			1,673
Rugs, Rugging, and Lap Dusters .....			29,098
Trous, Tarpanlins, Sails, and Flags .....			2,793
Trimnings—Mantle, Dress, Bonnet, and Hat, n.e.i. ....			215,984
Umbrellas, Parasols, and Sunshades .....			22,749
Handles, Sticks and Fitups .....			5,869
Umbrellas—Minor Articles for " .....			13,864
Hair and other Articles of Natural or Artificial Human Hair ..			6,616
Yarns—Angora .....			38
" Partly or wholly of Wool .....			60,235
Total, Division V.....			8,888,078
<b>DIVISION VI.—METALS AND MACHINERY.</b>			
Anchors—Over 10 cwt. ....	No.	3,845	930
" Not over 10 cwt. ....	cwt.	30,309	2,256
Chains, n.e.i. ....			30,890
Arms, Ammunition, etc.—			
Shot, Bullets, and Slugs .....	"	3,048	3,692
Revolvers and Pistols .....			6,209
Rifles, n.e.i., and Shot Guns .....			45,266
Rifles, Military and Match, including Cadet .....			18,787
Other Arms .....			2,825
Brass—Bars, Ingots, Scrap, Sheet, and Strips .....	cwt.	1,771	6,907
" Pipes and Tubes .....	"	3,431	13,613
Britannia Metal, Aluminium, Bronze, Yellow Metal, Nickel, and German Silver, viz.—Pigs, Ingots, Scrap, Blocks, Bars, Strips, Sheets, and Plates .....	"	9,578	27,085
Copper—Bars, Strips, Scrap, and Sheets .....	"	11,856	47,484
" Pipes and Tubes .....	"	4,471	20,290
Cutlery, n.e.i. (including Manicure Sets and Knife Sharpeners)			98,255
Diving Apparatus—Metal .....			18,374
Electrical Materials .....			249,015
Implements and Machinery, Agricultural, Horticultural, and Viticultural—			
N.E.I. ....			949,985
Reapers and Binders .....			132,583
Free .....			72,654
Instruments—Surveying, Drawing, and Mathematical			6,291
Iron and Steel—			
Angle, Bar, Rod, Tee .....	cwt.	699,112	386,250
Galvanised, Plate, and Sheet .....	"	896,570	766,413
Girders, Beams, Channels, Joists, Columns, Rolled, &c. ....	"	136,971	42,309
Hoop .....	"	55,344	36,776
Ingots, Blooms, Slabs, &c. ....	"	15,317	6,138
Pig .....	"	839,215	136,508
Plate and Sheet (except Galvanised) .....	"	274,693	111,975
Scrap .....	"	150,783	24,627
Lamps and Lampware, n.e.i., and Lanterns and Lamp Stoves, and all parts thereof .....			78,548
Lamps—Miners' Safety .....			2,378
Lead—Sheet and Piping .....	cwt.	8,395	6,505
Leaf and Foil—Gold and Silver .....			7,949
" Tin and Other .....			9,829
Machines and Machinery—			
Cash Registers, Computing Machines, and Attachments ..			18,775
Cream Separators, Testers, and Pasteurisers .....			79,398
Engines—			
Fire .....			2,331
Gas and Oil .....			52,641
High Speed and Turbine, Water, and Steam .....			1,253

Article.	Quantity.	Value.
DIVISION VI.—METALS AND MACHINERY—(continued).		£
Machines and Machinery—		
Engines—		
Portable and Traction .....		67,407
Other .....		372,521
Mangles, Clothes Wringers, and Washing Machines .....		5,089
N.E.I., and Parts thereof, including Boilers and Pumps .....		531,879
Machinery, 15 per cent. ....		17,427
Free, and Parts thereof .....		126,957
Electrical and Appliances, n.e.i. ....		167,786
Electrical (Duty, 20 per cent.) .....		1,580
Mining .....		129,005
Printing Machines and Presses, and Machinery used exclusively for and in the actual process of Electrotyping and Stereotyping; Aluminium Rotary Graining Machines, and Linotype, Monotype, Monoline, and other Type-Composing Machines .....		64,497
Sewing, Stitching, and Knitting Machines .....		126,144
Typewriters .....		41,920
Weighing Machines, Weighbridges, and Scales, n.e.i. ....		24,085
Machine Tools .....		75,308
Metals—Manufactures of—		
Axles and Springs .....		74,661
Bolts and Nuts .....		33,835
Mixed Metal Ware .....		13,585
Nails, Horseshoe .....	cwt. 5,773	9,961
Nails, Wire and other, Staples, Spikes, Brads, and Tacks. .	80,340	52,015
N.E.I. ....		582,225
Pipes and Tubes (Iron and Steel) .....		226,708
Plated Ware and Plated Cutlery .....		108,316
Tanks, containing goods, or empty .....	No. 7,120	15,867
Wire, Iron and Steel .....	cwt. 582,973	204,264
Wire, Barbed .....	92,549	55,114
Wire Netting .....		95,931
Wire, n.e.i. ....		61,119
Free .....		273,475
Platinum—Bars, Strips, Sheets, Plates, Retorts, Pans, Condensers, Tubing, or Pipes .....	oz. 392	1,902
Printers' Materials—Circles, Clumps, Curves, Knives (Faring), Rules, Leads, Slugs, and Type .....		16,089
Rails, Fish Plates, Fish Bolts, Tie Plates, Switches, Points, Crossings, and Intersections for Railways and Tramways .....		463,735
Rails, Fish Plates, &c. ....		30,863
Ships' Fittings .....		2,785
Spalter, Concentrates, Dross and Ashes .....	cwt. 14,197	15,017
Tin Plates, Plain .....	boxes 216,870	161,162
Tools of Trade, not being machines .....		254,212
Zinc—Bar, Scrap, and Sheet and Circles and Ingots, Bored and Unbored, for Cyanide Gold Process .....		31,788
Total, Division VI .....		7,394,661
DIVISION VII.—OILS, PAINTS, AND VARNISHES.		
Blacking, including Dressings, &c. ....		41,180
Dyes .....		47,342
Greases, Axle and Thickened or Solidified Oils; Solid or Viscous Compounds for Lubricating, in packages not exceeding 4lb. in weight. ....	cwt. 2,403	3,677
Greases, n.e.i. ....	15,698	12,698
Naphtha .....	gal. 127,446	8,157
Naphtha, Wood .....	20,518	2,895
Oils (in vessels not exceeding 1 gallon)—		
Quarter Pints and Smaller Sizes .....	dos. 72,078	7,571
Half Pints and over Quarter Pints .....	20,708	4,041
Pints and over Half Pints .....	3,963	1,367
Quarts and over Pints .....	3,274	2,961
Over a Quart .....	gal. 2,817	945



Article.	Quantity.	Value.
DIVISION VII.—OILS, PAINTS, AND VARNISHES—continued.		£
<b>Oils (in bulk)—</b>		
Castor .....	gal. 390,831	26,535
China .....	" 307,481	21,869
Cocconut .....	" 3,121	537
Colza .....	" 16,865	1,399
Cotton Seed, in bulk or otherwise .....	" 50,365	5,680
" when methylated .....	" 12,795	1,307
Essential, non-spirituous .....		19,429
Eucalyptus .....		36
Fish, including Cod unrefined, Seal and Whale .....	gal. 500,568	27,677
Kerosene .....	" 15,009,609	408,007
Lined .....	" 875,997	104,086
Lubricating Mineral, and Mineral, n.e.l. ....	" 1,267,088	116,037
Neatfoot .....	" 987	102
Olive .....	" 14,199	2,356
Solar and Residual .....	" 1,155,224	9,981
Stearine .....	" 446,263	19,682
Beardine and Gasoline, n.e.l. ....	" 191,304	20,301
<b>Oils—Free, including Coal Tar, Penguin, Degras, Sod, Mirbane</b>	" 20,296	2,468
<b>Paints and Colours—</b>		
Ground in Liquid .....	cwt. 96,909	112,991
Prepared for use .....	" 22,956	40,461
Colours Dry .....	" 58,339	47,216
Dry White Lead and Patent Dryers, Putty .....	" 8,092	3,431
N.E.I., Free .....		14,032
Sulphate of Copper .....	cwt. 333	308
Turpentine .....	gal. 188,513	20,611
Varnishes .....	" 130,246	47,714
Whiting .....	cwt. 67,938	4,693
<b>Total, Division VII</b> .....		<b>1,243,086</b>
DIVISION VIII.—EARTHENWARE, CEMENT, CHINA, GLASS AND STONE.		
<b>Bricks—</b>		
Bath .....		386
Fire and Glazed .....	No. 923,978	4,086
Fire, for Special use in Reverberatory Furnaces .....	" 84,500	448
Other .....	" 19,000	21
<b>Cement (Portland), Gypsum, &amp;c.</b> .....	cwt. 964,006	99,481
China, Parian, and Porcelain Ware, and Mosaic Flooring .....		68,169
Earthenware, Brownware, and Stoneware, n.e.l. ....		110,981
Earthenware, viz., Spurs, Stilts, and Thimbles .....		1,974
Films of all kinds .....		4,306
Fireing Manufactures, n.e.l., and Fire Lumps .....		2,702
Gelatine, Sheet .....	lb. 379,621	19,650
<b>Glass—</b>		
Bent, Bevelled, Heraldic, Sand-blasted, Enamelled, Embossed, Etched, Silvered and Cut; Corners Out, Bevelled, or Engraved; Panes, Prisms, and all other framed with metal .....		5,089
Polished Plate, n.e.l. ....	sup. ft. 489,583	23,741
Polished Plate, each Plate not exceeding 7 superficial feet .....	" 123,239	4,324
Polished Plate, each Plate exceeding 7 superficial feet and not exceeding 12 superficial feet .....	" 67,493	3,348
Sheet .....	" 6,969,721	45,482
N.E.I., also Seltzogenes and Accessories, Syphon Bottles .....		22,866
<b>Glassware—</b>		
N.E.I. ....		137,879
Empty Wine and Beer Bottles .....	doz. 166,866	4,531
Bottles, Empty, of not more than 5 fluid drams capacity .....	" 132,474	2,387
Bottles, over 5 fluid drams and not exceeding 9 fluid oz. in capacity, containing goods not subject to ad valorem duty .....	" 248,769	1,721
Signs, Process Engravers' .....		204
Scientific Instruments and Apparatus .....		3,548

Article.	Quantity.	Value.
DIVISION VIII.—EARTHENWARE, CEMENT, CHINA, GLASS, AND STONE—continued.		£
Glasses—		
Field, Marine, Opera .....		4,138
Lenses, n.e.i., Looket, Brooch, and Watch .....		4,440
Glue, Gelatine, n.e.i., and Cements .....		17,408
Gums Dry, Dextrine, Sandarach, and Mastic .....	cwt. 4,702	9,721
Lime .....	" 127	84
Plaster of Paris and other like preparations .....	" 49,010	7,009
Shellac .....	" 428	3,445
Stone (including Marble and Slate)—		
Monumental, Wrought .....		15,798
Wrought, n.e.i. ....		12,147
Unwrought Marble .....		6,894
Roofing Slates .....	No. 3,617,301	27,680
Slate Slabs, Unwrought .....		535
Grindstones .....		1,106
Lithographic .....		588
Oil and Whetstones, and Emery Stones .....		4,642
Sawn, or in the Rough, n.e.i. ....		1,225
Tiles—		
Asphalt and Roofing .....		8,770
N.E.I. ....		12,409
Total, Division VIII .....		705,312
DIVISION IX.—DRUGS AND CHEMICALS.		
Acids—		
Acetic .....	gal. 11,935	2,628
Boric and Salicylic .....	cwt. 3,889	5,372
Muriatic, Nitric, and Sulphuric .....	" 610	606
Tartaric .....	" 7,075	26,150
Other .....	" 2,764	9,673
Alkalies—		
Soda Acetate .....	" 4,392	3,098
" Ash .....	" 90,165	17,678
" Bicarbonate and Carbonate, in powder form only .....	" 54,173	17,727
" Caustic .....	" 59,884	35,323
" Crystals .....	" 686	146
" Nitrate .....	" 14,401	6,725
" Silicate .....	" 17,214	4,831
Alum .....	" 2,209	680
Ammonia, Carbonate of .....	" 1,087	2,067
Calcium, Carbide of .....	" 32,086	30,222
Drugs and Chemicals—		
Bisulphites, and Sulphites of Potassium, Sodium, Calcium, and Magnesium, and Foaming Powders and Liquids .....		7,006
Potassium, Cyanide of .....	lb. 5,987,306	229,308
Bacteriological Products and Serum .....		2,670
Cream of Tartar .....	cwt. 34,920	94,082
Food Preservatives .....		409
Free .....		134,402
Glycerine (unrefined) .....	lb. 4,999	174
Insecticides, Sheep-washes, and Disinfectants, n.e.i. ....		29,611
Medicines .....		196,577
Medical Preparations containing Opium .....	lb. 7,749	1,909
Perfumery .....		63,573
Vinegar, including Acetic Acid, containing not more than 6 per cent. of absolute acid .....	gal. 189,457	13,947
Total, Division IX .....		931,155
DIVISION X.—WOOD, WICKER, AND CANE.		
Furniture, n.e.i. (except Metal) .....		143,129
Billiard Balls in the rough .....		323
Minor Articles for .....		22,914
Hair, Curled .....	lb. 19,226	771

Article.	Quantity.	Value
<b>DIVISION X.—WOOD, WICKER, AND CANE—continued.</b>		
<b>Timber—</b>		<b>£</b>
Architraves, Mouldings, and Skirtings of any material	lin. ft. 46,257	341
Dressed, n.e.l.	sup. ft. 24,763,771	172,840
Undressed Oregon, in sizes of 12 x 6 in. (or its equivalent) and over	" 29,724,761	94,628
Undressed, n.e.l., in sizes of 12 x 6 in. (or its equivalent) and over	" 4,385,712	24,500
Undressed, n.e.l., in sizes of less than 12 x 6 in. (or its equivalent)	" 66,645,492	372,055
Laths	No. 18,524,843	16,701
Pickets, Undressed	" 760,375	3,492
Shingles	" 2,786,554	2,010
Doors of Wood, 1½ in. and over	" 152	89
" " over 1½ in. and under 1½ in.	" 4,191	2,527
" " 1½ in. and under	" 35,998	11,296
Hickory, Undressed	sup. ft. 59,602	968
Logs, not sawn, and Spars in the rough	" 218,128	930
Staves, Undressed or Roughly Dressed, but not shaped	No. 814,368	6,674
New Zealand Pine, Undressed	sup. ft. 51,068,578	239,456
Other	.....	18,479
<b>Wicker, Bamboo, Cane, or Wood—</b>		
Manufactures of	.....	74,881
Axe, and other Unattached Tool Handles	.....	17,277
Canes, Rattans, Unmanufactured Cane Compressed in Sheet and Unshaped, and Bamboo, Clouded	.....	8,412
Free	.....	8,838
<b>Total, Division X</b>		<b>1,234,516</b>
<b>DIVISION XI.—JEWELLERY AND FANCY GOODS.</b>		
Clocks, and Parts thereof, Time Registers, and Detectors	.....	36,256
Fancy Goods	.....	289,002
<b>Gold—</b>		
Bullion, Bar, Dust, Ingot, and Sheet	oz. 307,203	1,219,852
<b>Instruments—</b>		
Photographs, Cameras, Magic Lanterns, and the like	.....	44,476
Telescopes, Thermometers, Compasses, and the like	.....	7,986
Jewellery and Imitation Jewellery (25 per cent.)	.....	291,064
" (15 per cent.)	.....	11,028
" Cameos and Precious Stones, Unset	.....	103,763
<b>Silver—</b>		
Bullion, Bar, Ingot, and Sheet	oz. 456	51
Watches, and Parts thereof, Pedometers, Pocket Counters, and Chronometers, n.e.l.	.....	97,691
<b>Total, Division XI</b>		<b>2,061,169</b>
<b>DIVISION XII.—LEATHER AND RUBBER.</b>		
<b>Belt—</b>		
Composition	.....	24,653
Leather	.....	6,046
<b>Boots and Shoes—</b>		
Men's, Youths', Boys', Women's, and Girls', except partly or wholly of lasting or stuff, and Slippers (leather)	.....	162,580
N.E.L.	.....	56,485
Rubber Sand Shoes	.....	22,827
Infants' Boots, Shoes, and Slippers, sizes 0-6	.....	52,637
Gum Boots	.....	1,320
Minor Articles for	.....	46,618
Cloths made Waterproof with India-rubber	.....	22,466
India-rubber, Hose or other Manufactures, n.e.l.	.....	105,949
" Canvas or Tyre-fabric, made Waterproof and India-rubber Manufactures (free)	.....	9,664
" " and India-rubber Manufactures (free)	.....	91,348
Leather, n.e.l.	.....	193,624
" Free	.....	8,430

Article.	Quantity.	Value.
<b>DIVISION XII.—LEATHER AND RUBBER—continued.</b>		<b>£</b>
Leather Manufactures, n.e.l. ....	.....	42,450
Minor Articles for Harness, Saddles, Leatherware, and Whips (including Saddle Trees, Saddlers' Tacks and Nails, snaps (Harness and Halter), Spurs and Spur Boxes).....	.....	27,711
Saddlers' and Harness Makers' Materials.....	.....	15,236
Total, Division XII .....		850,103
<b>DIVISION XIII.—PAPER AND STATIONERY.</b>		
Books (printed), Music, Periodicals, Newspapers, and Pamphlets (not advertising) .....	gross 4,125	406,004
Boxes, Match and Vests, empty (paper) .....	doz. pkts. 18,842	95
Cards, Playing, in sheet or cut .....		4,060
Paper—		
Advertising Matter .....	lb. 858,525	20,323
Bags .....	cwt. 13,900	13,011
Browns and Sugar (grey, blue, and other tints), Fruit Bag Paper .....	" 67,751	50,715
Cartridge and Blotting .....		2,185
Millboard, Greyboard, Leatherboard, and Woodboard .....		6,990
Printing, Uncoated .....		400,141
Strawboard .....	cwt. 49,950	17,500
Writing .....		4,577
Toliet .....		2,183
N.E.L. ....		100,438
Free .....		174,422
Paperhangings .....		33,950
Pictures, not being advertising .....		21,850
Spectacles .....		7,702
Stationery—Manufactured, dutiable .....		176,646
Manufactured, free .....		40,486
Total, Division XIII .....		1,506,961
<b>DIVISION XIV.—VEHICLES.</b>		
Vehicles—		
Bicycles, Tricycles, and similar vehicles and parts .....		165,417
Cycle parts, n.e.l. ....		17,088
Cycle parts, free .....		14,645
N.E.L. and parts thereof, n.e.l., duty 20 per cent. ....		153,087
Barouches, Broughams, Waggonas, &c., duty 25 per cent. ....	No. 306	8,287
Vehicle parts, viz., Wheels (tyrod and bolted), Bodies, Under-gears, Under-carriages, and Tops .....		6,256
Motors .....	No. 275	22,692
Minor Articles for Vehicles .....		6,943
Total, Division XIV. ....		404,060
<b>DIVISION XV.—MUSICAL INSTRUMENTS.</b>		
Instruments, Musical—		
N.E.L. ....		24,413
For Bands, imported by and for the use of the Army or Navy .....		1,508
Military Band, and Orchestra and Bagpipes .....		14,373
Metal Pipes for Organs .....		205
Organs, Pipe .....		1,139
Organs, others, and Harmoniums .....	No. 1,150	12,077
Pianos .....	" 7,128	154,880
Pianos, parts, n.e.l. ....		423
Parts of, viz., Actions, Strings, Peltz, Hammers, and Iveries .....		7,380
Total, Division XV. ....		222,906

Article.	Quantity.	Value.
DIVISION XVI.—MISCELLANEOUS.		
		£
Arms, Ammunition, and Explosives—		
Caps, Percussion .....		3,492
Cartridges, Military .....		1,970
Cartridges, n.e.l. ....		74,842
Cartridges for the Army and Navy .....		45,570
Cartridge Cases (empty or capped) and Wads .....		22,783
Detonators .....		16,584
Dynamite Gelatine, Dynamite Gelignite, and Gelatine Blasting .....	lb. 6,398,006	336,486
Explosives, n.e.l. ....		19,566
Explosives for the Army and Navy .....		13,069
Fireworks .....		2,919
Fuse .....	cwt. 965,655	22,048
Powder, Blasting .....	lb. 2,064,147	38,068
Powder, Sporting .....	" 262,994	15,129
Arms for the Army and Navy .....		21,139
Articles for the Commonwealth .....		27,236
Articles for the official use of the Governor-General or State Governors .....		2,737
Articles for the Army or Navy—Military stores .....		74,503
Munitions of war .....		30,433
Articles for the Blind, Deaf, and Dumb .....		226
Art—Works of .....		10,568
Bags, Baskets, Boxes, Cases, or Trunks, including fittings .....		43,209
Minor articles for .....		5,960
Baskets—Carpenters' .....		363
Boats, Launches, and Yachts, including fittings .....	No. 57	3,477
Brushware and Combs—Toilet .....		51,923
" N.E.L., including Brooms, Mops, Crumb Trays, and Brushes .....		48,735
" Other .....		3,341
Coke .....	tons 4,226	6,069
Cordage and Twines—		
Twine and Yarn—Reaper and Binde .....	cwt. 17,999	39,148
Metal .....	" 38,060	60,168
Other articles manufactured from, including Halters and Nets, and Netting .....		1,315
N.E.L. ....	cwt. 28,597	76,793
Engine Packing in rope form .....		12,061
Sewing Silks, Twists, Threads, and Cottons, and Crochet Cottons .....		261,160
Unserviceable .....	cwt. 142	34
Corks, Bungs, and Net Floats .....		59,232
Cork Mats and other manufactures of cork .....		2,905
Instruments, Scientific and Apparatus for use in Universities, Colleges, Schools, or Public Hospitals .....		7,068
Surgical and Dental, and appliances .....		56,116
Models of Inventions, &c., and Models and Casts for teaching purposes for Universities, Colleges, or Schools .....		100
Nets, fishing, and Netting therefor .....		9,866
Photographic Dry Plates, and Sensitized Films and Paper .....		23,286
Pipes (smoking), Cigar and Cigarette Holders and Cases .....		66,737
Specimens of Natural History .....		2,232
Theatrical Costumes and Properties .....		2,822
Trophies won abroad .....		1,572
Yarns, other, including Coir .....		14,169
Total, Division XVI. ....		£1,063,662
FREE GOODS NOT SPECIALLY MENTIONED IN THE TARIFF.		
Bark, Tanning .....	cwt. 265	186
Bars .....	" 1,674	3,675
Black Lead .....		4,377
Bones, Hides, and Horns .....	cwt. 2,987	1,718
Charcoal .....	" 177	155
Coal .....	tons 883	360

Article.	Quantity.	Value.
FREE GOODS NOT SPECIALLY MENTIONED IN THE TARIFF— <i>contd.</i>		£
Cocoa Beans, and Cocoa unmanufactured .....	lb. 659,898	20,008
Copper Ore .....	cwt. 5	4
Cotton, Raw .....	lb. 464,984	9,304
Waste .....	.....	25,636
Fibre—Coiir .....	cwt. 16,954	8,239
Flax and Hemp, including Phormium Tenax .....	75,898	129,739
Jute .....	2,943	2,432
Flock .....	988	598
Glue pieces and Sinews .....	779	411
Gold Ore and Concentrates .....	21,677	13,750
Hair, Human, not made up .....	.....	1,108
Free .....	lb. 100,561	3,711
Kapok .....	1,792,954	32,472
Lead, Pig .....	cwt. 637	614
Strap and Old .....	293	136
Oakum and Tow .....	7,361	4,080
Ores—Cobalt .....	3,000	1,540
Manganese .....	212	61
N.E.L., including Earths (Alkaline and Infusorial), Fire-clay, Mica, Black and Moulding Sands .....	23,219	6,132
Pearlshell .....	378	1,494
Personal and Household Effects, Passengers' .....	.....	18,885
Pitch and Tar .....	cwt. 19,458	5,653
Plants, Trees, and Bulbs .....	.....	5,029
Platinum Ore .....	lb. 23	8
Plumbago .....	cwt. 5,557	3,363
Potash and Pearl Ash (crude) and Caustic Potash (in bulk) .....	2,934	3,119
Pumice Stone .....	10,506	2,002
Quicksilver .....	lb. 198,029	21,925
Rags .....	cwt. 7	10
Resin .....	80,337	24,294
Saltpetre .....	4,659	4,460
Shale, Kerosene .....	ton 5	20
Skins—Hides .....	No. 72,891	81,565
Rabbit and Hare .....	67,500	858
Sheep, with Wool .....	39,374	8,006
Sheep, without Wool .....	235,113	12,241
Other .....	.....	3,332
Specie—Gold .....	.....	1,942
Silver .....	.....	32,901
Bronze .....	.....	5,780
Sulphur, Brimstone .....	cwt. 180,719	48,378
Tin—Ingots .....	408	703
Ore .....	1	2
Tortoiseshell .....	lb. 2,920	2,125
Wool—Greasy .....	304,694	9,379
Scoured and Washed .....	7,066	420
All other articles .....	.....	59,198
Total, Free Goods, &c. ....	.....	£626,748
Total Imports .....	.....	£37,811,471
SUMMARY OF IMPORTS.		
Merchandise .....	.....	36,561,542
Specie .....	.....	40,024
Bullion .....	.....	1,219,905
.....	.....	£37,811,471

In the foregoing table the values represent the fair market price of the goods in the principal markets of the countries whence they were exported, with an addition of 10 per cent. to such market value, this addition representing, roughly, freight and charges between the port of shipment and Australia. In many places there are blanks where the

quantities should appear ; in these instances the quantities were declared as packages, and consequently did not indicate the number, capacity, or weight of the goods imported.

The exports from the Commonwealth for the year 1903 are shown in the following list, which distinguishes, as to value, Australian from other produce. The practice of the Customs Department in regard to export values, is to take the value of the goods for export as their value in the ordinary commercial acceptance of the term in the principal markets of the Commonwealth.

EXPORTS.

Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
DIVISION I.—STIMULANTS.				
Ale, Porter, and Other Beer, Cider and Perry—		£	£	£
In Bottle	gal. 46,897	1,980	6,585	8,515
Other	3,948	228	35	273
Spirits—				
Brandy, Bottled.....	12,747	3,568	2,793	6,361
Bulk .....	41,409	7,306	826	8,132
Gin, British .....	884	39	234	273
Hollands or Geneva .....	10,704	.....	1,826	1,826
Schnapps .....	2,486	.....	1,290	1,290
Rum, Bottled .....	696	16	277	293
Bulk .....	4,797	121	602	723
Whisky, Bottled .....	17,745	94	8,377	8,471
Bulk .....	17,232	.....	6,548	6,548
Bitters .....	79	.....	84	84
Cordials or Liqueurs, and other Spirituous Compounds, n.e.l. ....	476	13	453	466
Methylated .....	1,791	114	72	186
Perfumed and Bay Rum .....	243	40	554	594
Essences, Tinctures, Extracts .....	889	149	1,507	1,656
Sarsaparilla .....	90	10	108	118
All Other .....	38,455	3,622	125	3,753
Wine, Fermented, Sparkling .....	2,194	143	4,018	4,161
N.E.L., including Medicinal or Medicated, and Vermouth, in Bottle. ....	45,105	15,969	2,367	18,336
N.E.L., Other .....	678,179	81,850	830	82,680
Total, Division I. ....	£	115,278	33,401	153,739
DIVISION II.—NARCOTICS.				
Opium .....	lb. 2,575	.....	3,146	3,146
Tobacco—				
Manufactured .....	702,914	10,597	33,145	43,742
Unmanufactured .....	8,049	14	583	597
Cigars .....	40,095	72	10,098	10,090
Cigarettes .....	13,634	453	3,608	4,066
Total, Division II. ....	£	11,141	50,490	61,631
DIVISION III.—SUGAR.				
Saccharine .....	lb. 435	.....	381	381
Sugar, the Produce of Sugar Cane .....	cwt. 47,295	22,079	11,163	33,242
Golden Syrup and Syrups, n.e.l. ....	214	222	12	234
Glucose .....	149	.....	102	102
Molasses .....	145	65	.....	65
Other .....	431	.....	236	236
Total, Division III. ....	£	22,366	11,894	34,260

Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
<b>DIVISION IV.—AGRICULTURAL PRODUCTS AND GROCERIES.</b>		£	£	£
Aerated and Mineral Waters.....		974	297	1,271
Animals (living), Birds.....		3,769	7	3,776
Cattle.....	No. 939	9,302	.....	9,302
Dogs.....	" 65	232	.....	232
Horses.....	" 9,527	161,144	5,080	166,224
Pigs.....	" 77	106	.....	106
Poultry.....	" 1,388	371	.....	371
Sheep.....	" 18,111	24,192	276	24,468
Other.....	".....	91	112	204
Arrowroot.....	lb. 62,921	913	70	983
Biscuits.....	" 2,412,252	31,526	195	31,721
Blue, Laundry.....	" 29,977	267	529	796
Broom Corn Millet.....	cental. 1,209	1,288	91	1,380
Butter.....	lb. 32,124,709	1,213,177	54,234	1,267,411
Candles, Tapers, Night Lights, and Solid Spirit Heaters.....	" 62,441	83	1,301	1,384
Caramel, Caramel Paste, and Caramel Butter..	" 2,682	18	27	45
Cheese.....	" 243,176	5,218	1,859	7,077
Cocoa and Chocolate, Ground, or in any way manufactured.....	" 25,411	200	1,608	1,808
Coffee and Chicory, Raw and Kiln Dried.....	" 122,958	24	4,408	4,432
Roasted or Ground, and in Liquid Form.....	" 30,815	225	1,290	1,485
Confectionery, n.e.i.....	" 237,190	8,741	541	9,282
Copra.....	cwt. 4,128	.....	2,548	2,548
Eggs.....	doz. 46,973	437	1,355	2,292
<b>Fish—</b>				
Fresh (Oysters).....	cwt. 35	23	.....	23
Smoked or Preserved by Cold Process.....	lb. 10,279	117	59	176
Potted or Concentrated, including Extracts of.....	.....	.....	130	130
Preserved in Tins or Other Air-tight Vessels N.E.I.....	" 426,746	21	9,406	9,517
Fodder—including Compressed Fodder.....	cwt. 4,693	15,392	5,575	20,967
Fruits and Vegetables—	" 272,102	98,543	.....	98,543
Fruits Dried—				
Currants.....	lb. 92,650	.....	800	800
Dates.....	" 48,392	.....	378	378
Raisins.....	" 689,736	7,023	1,885	8,918
Other.....	" 82,240	576	1,108	1,684
N.E.I. (Preserved in Liquid, or Partly Preserved, and Pulped)—Half-pints or Smaller Sizes.....	doz. 662	239	57	296
Pints and over Half-pints.....	" 28,011	2,474	2,018	4,492
Quarts and over Pints.....	" 49,011	11,784	2,740	15,524
Exceeding a Quart.....	gal. 6,217	121	.....	121
Fruit, Pulped.....	lb. 3,816,191	37,240	.....	37,240
Fruits, fresh—				
Apples.....	cental. 223,258	160,090	684	161,374
Bananas.....	" 1,876	1,136	.....	1,136
Oranges and Lemons.....	" 41,113	20,091	1,554	22,245
Pineapples.....	" 2,069	982	.....	982
N.E.I.....	" 97,852	30,468	790	31,253
<b>Vegetables—</b>				
Dried or Concentrated.....	".....	81	887	968
N.E.I.....	cental. 19,316	3,948	31	2,979
<b>Ginger—</b>				
Preserved in Liquid.....	lb. 1,814	.....	38	38
Preserved, not in Liquid.....	" 1,783	.....	38	38
Green.....	" 2,844	.....	36	36
<b>Grain and Pulse—</b>				
Barley.....	bus. 14,286	4,789	772	5,561
Beans and Peas.....	" 35,078	7,842	844	8,686
Maize.....	" 17,396	437	2,312	2,749
Oats.....	" 184,822	21,419	1,286	23,205
Wheat.....	" 1,530,143	181,355	55,349	236,604
N.E.I.....	" 225	78	8	8



Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
<b>DIVISION IV.—AGRICULTURAL PRODUCTS AND GROCERIES—continued.</b>				
<b>Grain and Pulse—</b>				
Prepared or Manufactured—				
Barley, Pearl and Scotch .....	lb. 4,078	7	82	89
Brant, Pollard, and Sharpe .....	bus. 168,219	7,552	573	8,124
Flour (ton, 2,000 lb.) .....	ton 8,050	61,199	21,742	82,941
Groats .....	lb. 648	11	8	19
Malt, including Granulated Malt, and Rice Malt .....	bus. 198	9	67	76
Maisena and Cornflour .....	lb. 22,284	89	234	32
Oatmeal, Wheatmeal, and Rolled Oats .....	cwt. 1,090	1,287	91	1,377
Pean, Split .....	399	131	116	243
Rice, n.e.l. ....	30,068	10,663	16,668	27,331
N.E.I. ....	392	97	81	179
Hay and Chaff .....	cwt. 178,724	48,091	1,028	49,119
Beany .....	lb. 21,996	444	2	446
Hops .....	38,578	518	2,105	2,623
Isinglass .....	cwt. 60	9	1	10
Jam .....	2,334	521	596	1,117
Jams and Jellies .....	2,097,371	39,110	1,276	40,386
Lard and Refined Animal Fats .....	426,507	7,461	399	7,860
Limejuice and Other Fruit Juices and Fruit Syrups .....	gal. 10,456	1,509	190	1,699
Linned .....	cental. 25	6	18	24
Linned Meal .....	4	4	4	8
Linned Cake and Oilcake .....	11,399	2,470	2,470	4,940
Liquorice—				
Crude .....	lb. 600	12	12	24
Other .....	2,070	87	87	174
Macaroni and Vermicelli .....	9,448	82	117	149
Malt Extract, Non-spirituous .....	10,344	239	14	253
Marmos .....	cwt. 106,428	46,997	2,607	49,604
Matches and Vestas .....				
Wax (gross per 100 matches) .....	8,007	49	985	1,034
Wood or Other (gross per 100 matches) ..	31,567	2,386	2,386	4,772
<b>Meats—</b>				
Bacon and Hams, Partly or Wholly Cured Preserved by Cold Process—	lb. 281,570	9,419	337	9,756
Beef .....	61,176,230	827,456	45	827,501
Game .....	984	40	40	80
Mutton and Lamb .....	35,888,903	489,984	2,180	492,114
Pork .....	277,510	7,174	113	7,287
Poultry .....	55,122	10,364	10,364	20,728
Rabbits and Hares .....	4,619,245	219,522	219,522	439,044
Other .....	516,578	6,270	6,270	12,540
Fresh and Smoked .....	1,061	23	23	46
Potted and Concentrated (including Extracts of and Caviare) .....	11,135,608	198,902	3,208	202,110
Preserved in Tins or other Airtight Vessels ..	5,334	3,222	6,009	9,231
N.E.I. ....				
Milk and Cream—				
Concentrated .....	lb. 484,841	9,622	9,622	19,244
Preserved .....	224,708	381	4,180	4,561
Milk .....	6,704	6	406	412
Yam, Edible—				
Almonds .....	12,976	164	239	393
Oconuts .....	cwt. 19	10	10	20
N.E.I., whole or prepared, including Coconut Prepared .....	lb. 65,274	775	775	1,550
<b>Oils and Stores—</b>				
N.E.I. ....		3,498	6,778	10,276
Free, including Infants' and Invalids' Foods, Special Preparations of .....		69	2,918	3,087
Oils .....	cwt. 48,761	9,424	183	9,607
Fat .....				
Drained, or Preserved in Brine, Acid, or Water .....	lb. 27,227	198	198	396
Preserved, not in Liquid .....	667	5	11	16

Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
DIVISION IV.—AGRICULTURAL PRODUCTS AND GROCERIES—continued.				
Pickles, Sauces, Chutneys, Olives and Capers— Quarter Pints, and Smaller Sizes .....	dos. 114	1	31	32
Half Pints, and over Quarter Pints .....	1,540	125	483	608
Pints, and over Half Pints .....	4,157	614	492	1,106
Quarts, and over Pints .....	433	124	94	218
Exceeding a Quart .....	gal. 1,040	50	52	102
Potatoes .....	cwt. 68,134	9,736	2,600	12,336
Sago .....	cental 154	.....	87	87
Salt— Brown Rock .....	cwt. 1,046	3	122	125
N.E.I. ....	160,486	13,196	656	13,851
Sausage Casings .....	.....	26,586	1,820	28,406
Seeds— Canary, Hemp, and Rape .....	cental 407	.....	353	353
Cotton .....	2	.....	10	10
Other .....	.....	6,744	1,938	8,682
Soap— Perfumed, Toilet, &c. ....	lb. 69,615	697	2,581	3,278
N.E.I. ....	3,191,776	32,153	29	32,182
Sparklets .....	.....	.....	148	148
Spices— Pepper, Ground .....	lb. 4,003	103	84	187
Unground .....	19,381	.....	748	748
Other, Ground, n.e.i. ....	19,436	497	370	867
Other, Unground, n.e.i. ....	33,069	.....	751	751
Starch, including Starch in Powdered Form .....	40,574	17	514	531
Starch Flours, including Rice Meal and Rice, Tapioca, and Potato Flours. ....	41,364	1	209	210
Stearine .....	lb. 15,800	290	.....	290
Straw .....	cwt. 154	26	.....	26
Tallow, n.e.i. ....	248,814	307,467	998	308,465
Tapioca .....	cental 800	.....	484	484
Tea .....	lb. 1,879,168	.....	65,373	65,373
Wax— Beeswax .....	68,421	3,375	.....	3,375
Japanese or Vegetable .....	520	.....	24	24
Paraffin .....	215,670	.....	2,794	2,794
Wine—Unfermented .....	gal. 50	19	.....	19
Total, Division IV .....	.....	£ 4,488,216	327,894	4,816,109
DIVISION V.—APPAREL AND TEXTILES.				
Apparel and Attire—Articles n.e.i. ....	.....	11,372	35,775	47,047
Diving Dresses .....	.....	.....	108	108
Socks and Stockings (cotton) .....	.....	.....	395	395
(Woollen or containing wool) .....	.....	2	530	532
Towels and Handkerchiefs (made of cotton or linen). ....	.....	.....	1,834	1,834
Regalia, viz., Embroidery Woven Sashes .....	.....	.....	8	8
Minor Articles for .....	.....	167	2,068	2,173
Bags and Sacks (durable) .....	.....	1,122	522	1,644
Bags, Sacks, Packs, and Bales—Free .....	No. 1,523,179	42	20,743	20,785
Blankets and Blanketing .....	.....	50	1,282	1,332
Canvas (Tent and Sall) and Duck Hessians, Bunting, and Brattice Cloth. ....	.....	.....	3,310	3,310
Carpets and Carpeting .....	.....	.....	1,003	1,003
Coses, Cushions, Mantel and Furniture Drapery and Coverings, Bed-covers and Furnish- ings, n.e.i. ....	.....	350	4,909	5,459
Cotton—Wick, Candle, and Lamp .....	.....	.....	12	12
Curtains .....	.....	36	794	830
Feathers—Dressed .....	.....	55	710	765
Undressed .....	.....	874	.....	874
Floor Cloths and Coverings .....	.....	1	706	707

Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
DIVISION V.—APPAREL AND TEXTILES—contd.				
Fillings, Ruffings, Tucked Lawns, Pleatings, and Ruchings.	.....	.....	84	84
Furs—Dressed or Prepared	.....	646	40	686
Gloves—Including Mittens and Flesh Gloves..	.....	8	1,609	1,612
Hats and Caps—Men's, Women's, Boys', and Children's Felt Hats.	.....	121	1,967	2,088
Sewn	.....	2	186	18
Hats, Caps, and Bonnets, n.e.i., and Hat and Bonnet Shapes.	.....	787	1,805	2,542
Felt Pull-over Hoods	.....	.....	23	23
Minor Articles for	.....	84	717	751
Mats, n.e.i., including Carriage Mats	.....	88	223	321
Place Goods—Cotton and Linen	.....	.....	41,265	41,265
Horsehair Cloth and Hop Cloth	.....	22	194	216
Silk, or containing Silk, or having Silk worked thereon.	.....	.....	21,245	21,245
Silk—Milling	.....	.....	82	82
Velvets, Velvetseams, Plushes, &c.	.....	.....	9,682	9,682
Woollens, or containing Wool, n.e.i.	.....	177	35,746	35,923
Flannels	.....	69	205	274
Flannelettes	.....	.....	1,653	1,653
Woollens (Free)	.....	.....	470	470
Coatings, Vestings, and Trouserings, n.e.i.	.....	.....	142	142
Rugs, Ruggings, and Lap Dusters	.....	2,196	562	2,788
Tents, Tarapaulins, Sails, and Flags	.....	675	232	907
Trimmings—Mantle, Dress, Bonnet and Hat, n.e.i.	.....	2	2,064	2,066
Umbrellas, Parasols, and Sunshades	.....	904	800	1,704
Umbrella, Parasol, and Sunshade Handles, Sticks, and Fit-ups.	.....	.....	323	323
Umbrellas—Minor Articles for	.....	.....	84	84
Wigs and other Articles of Natural or Artificial Human Hair.	.....	872	127	999
Yarns—Partly or Wholly of Wool	.....	.....	678	678
Total, Division V.	.....	£ 21,019	196,585	217,554
DIVISION VI.—METALS AND MACHINERY.				
Anchors, over 10 cwt.	No. 1	.....	64	64
Not over 10 cwt.	270	.....	245	245
Chains, n.e.i.	cwt. 1,560	88	1,866	1,902
Arms, Ammunition, and Explosives—Shot, Bullets, and Slugs.	" 242	84	177	261
Revolvers and Pistols	.....	.....	98	98
Rifles, n.e.i., and Shot-guns	.....	.....	2,344	2,344
Other Arms	.....	.....	143	143
Bars—Bars, Ingots, Scrap, Sheet, and Strips.	cwt. 878	239	1,380	1,578
Pipes and Tubes	" 215	215	355	570
Britannia Metal, Aluminium, Bronze, Yellow Metal, Nickel, and German Silver, viz.—Pigs, Ingots, Scrap, Blocks, Bars, Strips, Sheets, and Plates.	" 2,615	89	5,273	5,312
Copper—				
Bars, Strips, Scrap, and Sheets	cwt. 1,927	1,120	2,580	3,709
Pipes and tubes	" 20	20	109	129
Cutlery, n.e.i. (Including Manicure sets and knife sharpeners)	.....	20	4,819	4,839
Diving Apparatus—Metal	.....	.....	643	643
Electrical Materials	.....	927	14,249	15,176
Implements and Machinery—				
Agricultural, Horticultural, and Viticultural, n.e.i.	.....	50,777	5,745	56,522
Reapers and Binders	.....	.....	983	983
Free	.....	476	997	1,473

Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
DIVISION VI.—METALS AND MACHINERY—contd.				
Instruments—Surveying, Drawing, and Mathematical.	.....	.....	257	257
Iron and Steel—				
Bar, Rod, Angle, Tee .....	cwt 8,079	1,229	2,206	4,085
Galvanised, Plate and Sheet .....	" 12,557	.....	11,176	11,176
Girders, Beams, Channels, Joists, Columns, rolled, etc.	" 5,022	.....	2,414	2,414
Hoop .....	" 650	.....	374	374
Pig .....	" 3,578	.....	847	847
Plate and Sheet (except galvanised) .....	" 4,025	7	2,728	2,735
Scrap .....	" 42,571	308	3,980	4,278
Lamps and Lampware—				
N.E.I., and Lanterns and Lamp Stoves, and all parts thereof.	.....	214	3,977	4,091
Safety Lamps, Miners' .....	.....	.....	14	14
Lead—Sheet and Piping .....	cwt. 28,793	22,304	12	22,316
Leaf and Foil—				
Gold and Silver .....	.....	.....	142	142
Tin and other .....	.....	.....	251	251
Machines and Machinery—				
Cash Registers, Computing Machines, and attachments.	.....	.....	658	658
Cream Separators, Testers and Pasteurisers .....	.....	12	2,251	2,263
Engines—Gas and Oil .....	.....	72	3,711	3,783
" Portable and Traction .....	.....	.....	450	450
" Other .....	.....	256	1,568	1,829
Mangles, Clothes Wringers and Washing Machines.	.....	.....	297	297
N.E.I. and parts thereof, including Boilers and Pumps.	.....	22,248	33,252	55,500
Press, and parts thereof .....	.....	107	5,224	5,241
Electrical and Appliances, n.e.i. ....	.....	123	4,701	4,824
Machinery Mining .....	.....	204	235	439
Printing Machines and Presses, and Machinery used exclusively for and in the actual process of Electrotyping, and Stereotyping, Aluminium Rotary Graining Machines, and Linotype, Monotype, Monoline, and other Type Composing Machines.	.....	10	4,736	4,746
Sewing, Stitching, and Knitting Machines .....	.....	30	9,297	9,306
Typewriters .....	.....	.....	3,487	3,487
Weighing Machines, Weighbridges and Scales, n.e.i. ....	.....	.....	919	919
Machine Tools .....	.....	176	5,146	5,322
Metals, Manufactures of—Axes and Springs. ....	.....	311	1,013	1,324
Bolts and Nuts .....	.....	393	1,091	2,084
Mixed Metal Ware .....	.....	563	150	713
Nails, Horseshoe .....	cwt. 122	12	259	271
Nails, Wire and Other Staples, Spikes, Brads, and Tacks.	" 2,015	691	2,281	2,972
Nails, Wire, and Other Staples, Spikes, Brads, and Tacks, n.e.i. ....	.....	17,345	31,148	48,493
Pipes and Tubes (Iron and Steel) .....	.....	1,499	8,572	10,071
Plated Ware and Plated Cutlery .....	.....	250	8,985	9,135
Tanks, containing Goods, or Empty .....	No. 298	254	526	780
Wire, Iron and Steel .....	cwt. 6,982	30	3,256	3,283
Wire, Barbed .....	" 2,147	.....	1,497	1,497
Wire, Netting .....	.....	5,692	391	5,908
Wire, n.e.i. ....	cwt. 405	.....	1,134	1,134
Free .....	.....	940	6,135	7,125
Platinum, Bars, Scales, Sheets, Plates, Retorts, Pans, Condensers, Tubing, or Pipes.	cwt. 1	.....	1,001	1,001
Printers' Materials, Circles, Clumps, Curves, Knives (Faring) Rules, Leads, Slugs and Type.	.....	1,882	2,768	4,650

Article.	Total Quantity.	Value		
		Australian Produce.	Other Produce.	Total.
DIVISION VI.—METALS AND MACHINERY.—contd.				
Bails, Fish-plates, Fish-bolts, Tie-plates, Switches, Points, Crossings, and Intersections for Railways and Tramways.	.....	757	11,779	12,536
Ships' Fittings	.....	153	765	918
Spelter, Concentrates, Dross, and Ashes	cwt. 60,206	15,245	.....	15,245
Tin, Plates, Plain	boxes 3,096	.....	2,485	2,485
Tools of Trade, not being Machines	.....	1,433	5,612	7,045
Zinc, Bar, Scrap, and Sheet, and Circles and Ingots, Bored and Unbored, for Cyanide Gold Process.	.....	4,093	522	4,615
TOTAL, DIVISION VI.	..... £	152,815	246,220	398,045
DIVISION VII.—OILS, PAINTS, AND VARNISHES.				
Backing, including Dressings, &c.	.....	918	638	1,556
Dyes	.....	81	3,328	3,409
Greases, Axle and Thickened or Solidified Oils, Solid or Viscous Compounds for Lubricating, in packages, not exceeding 4lb. in weight.	cwt. 2	2	....	2
Greases, n.e.i.	.....	1,251	535	1,786
Naphtha	gal. 12,733	.....	943	943
Naphtha, Wood	.....	106	26	26
Oils (in vessels not exceeding one gallon)—	.....	.....	.....	.....
Quarter-pints and smaller lines	doz. 90	.....	12	12
Half-pints and over Quarter-pints	.....	629	120	120
Pints and over Half-pints	.....	540	112	112
Quarts and over Pints	.....	130	102	102
Over a Quart	gal. 112	.....	33	33
Oils in Bulk—	.....	.....	.....	.....
Castor	.....	16,801	1,695	1,695
China	.....	6,850	820	820
Cocanut	cwt. 152,711	195,040	.....	195,040
Colza	gal. 1,689	2	261	263
Cotton Seed, in Bulk or otherwise	.....	2,319	313	313
Essential (non-spirituous)	.....	.....	146	908
Eucalyptus	.....	.....	14,136	14,136
Fish, including Cod, unrefined Seal and Whale.	gal. 10,442	.....	1,352	1,352
Kerosene	.....	627,444	21,106	21,106
Linseed	.....	21,278	3,137	3,137
Lubricating (Mineral) and Mineral, n.e.i.	.....	132,096	218	10,317
Neatsfoot	.....	571	68	68
Olive	.....	304	17	96
Solar and Residual	.....	66,387	823	823
Tallow	.....	153,663	13,918	13,918
Benzine, Benzoline, and Gasoline	.....	66,006	15	2,761
N.E.I.	.....	29,921	1,113	1,730
Oils (Free), including Coal Tar, Penguin, Degras, Sod, Mirbane.	.....	2,532	52	367
Paints and Colours—	.....	.....	.....	.....
Ground in Liquid	cwt. 2,438	7	3,031	3,038
Prepared for use	.....	2,435	463	2,981
Colours Dry: Dry White Lead and Patent Dryers.	.....	13,480	2,090	3,061
Putty	.....	63	20	33
Free	.....	.....	3	163
Sulphate of Copper	cwt. 33	.....	43	43
Turpentine	gal. 5,731	.....	1,034	1,034
Varnishes	.....	5,006	121	1,879
Whiting	cwt. 321	.....	51	51
Total, Division VII.	..... £	229,020	62,243	291,263

Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
DIVISION VIII.—EARTHENWARE, CEMENT, CHINA, GLASS AND STONE.		£	£	£
Bricks—				
Bath .....			17	17
Fire and Glazed .....	no. 38,620	162	64	216
Fire, for special use in Reverberatory Furnaces. ....	" 2,000		8	8
Other .....	" 208,067	442		442
Cement (Portland), Gypsum, &c. ....	cwt. 42,443	509	4,446	5,015
China, Parian and Porcelain Ware, and Mosaic Flooring. ....			881	881
Earthenware, Brownware, and Stoneware, n.e.i. ....		763	2,007	2,770
Earthenware, viz.: Spurns, Stilts, and Thimbles .....			130	130
Filters of all kinds .....		60	9	69
Fireclay Manufactures, n.e.i., and Fire Lumps .....		14	14	28
Gelatine Sheet .....	lb. 6,798		348	348
Glass—				
Bent, Bevelled, Heraldic, Sandblasted, Enamelled, Embossed, Etched, Silvered and Cut; Corners cut, bevelled or engraved; Panes, Prisms and all other framed with metal. ....		162	46	208
Polished Plate, n.e.i. ....	sup. ft. 5,451	9	265	274
Polished Plate, each plate not exceeding 7 superficial feet. ....	" 503		22	22
Polished Plate, each plate exceeding 7 superficial feet, and not exceeding 12 superficial feet. ....	" 317		15	15
Sheet .....	" 27,504		323	323
N.E.I., also Seltzogenes and accessories, Syphon Bottles. ....		4	263	272
Glassware—				
N.E.I. ....		4,029	1,987	6,006
Bottles, empty .....	doz. 482,515	7,343	4,993	12,336
Scientific Instruments and Apparatus .....			108	108
Glasses—				
Field, Marine, and Opera .....			588	588
Lenses, n.e.i., Locket, Brooch, and Watch. ....			20	20
Olue, Gelatine, n.e.i., and Cements, n.e.i. ....		236	366	602
Gums dry, Dextrine, Sandarach, and Mastic .....	cwt. 8,026	2,754	627	3,381
Lime .....	" 559	57		57
Plaster of Paris, and other like preparations. ....	" 1,861	19	362	381
Shellac .....	" 15		64	64
Stone (including Marble and Slate)—				
Monumental, Wrought .....		262	580	842
Wrought, n.e.i. ....		382	900	982
Unwrought Marble .....		52	530	582
Roofing Slates .....	No. 2,240		20	20
Slate Slabs, Unwrought .....		56	277	333
Grindstones .....		136	48	184
Oil and Whetstones, and Emery Stones. ....		1	63	64
Sawn or in the rough, n.e.i. ....		1,137	15	1,152
Tiles—				
Asphalt and Roofing .....		24	26	50
N.E.I. ....		193	106	299
Total, Division VIII .....		£ 19,806	20,098	39,903
DIVISION IX.—DRUGS AND CHEMICALS.				
Acids—				
Acetic .....	gal. 893		183	183
Boric and Salicylic .....	cwt. 46		128	128
Muriatic, Nitric, and Sulphuric .....	" 2,145	1,498	97	1,595
Tartaric .....	" 82		458	458
Other .....	" 209	7	911	918
Alkalies—				
Soda Ash .....	" 806		284	284

Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
<b>DIVISION IX.—DRUGS AND CHEMICALS.—contd.</b>				
<b>Alkalies—</b>				
Soda Bicarbonate and Carbonate (in powder form only)	cwt. 602	.....	218	218
Soda Caustic	" 1,057	.....	682	682
Soda Crystals	" 950	164	12	176
Soda Nitrate	" 22	.....	11	11
Soda Silicate	" 451	.....	202	202
Alum	" 67	.....	45	45
Ammonia, Carbonate of	" 9	.....	31	31
Calcium, Carbide of	" 2,064	.....	2,293	2,293
<b>Drugs and Chemicals—</b>				
Bisulphites and Sulphites of Potassium, Sodium, Calcium, and Magnesium, and Foaming Powders and Liquids.	.....	32	801	833
Potassium, Cyanide of	lb. 17,696	.....	716	716
Bacteriological Products and Serum	.....	.....	7	7
Cream of Tartar	cwt. 398	3	1,072	1,075
Food Preservatives	.....	1,068	785	1,853
Free	.....	33,827	9,765	43,592
Glycerine (unrefined)	lb. 606,021	9,741	.....	9,741
Insecticides, Sheep-washes, and Disinfectants, n.e.i.	.....	666	1,815	1,981
Medicines	.....	12,506	11,778	24,284
Perfumery	.....	854	2,681	3,485
Vinegar, including Extract, or Essence of	gal. 4,149	169	274	443
Total, Division IX	.....	£ 60,639	35,294	95,933
<b>DIVISION X.—WOOD, WICKER, AND CANE.</b>				
Furniture, n.e.i. (except Metal)	.....	8,816	5,742	14,558
Minor Articles for	.....	36	66	102
Hair—Curled	lb. 2,298	81	6	87
<b>Timber—</b>				
Architraves, Mouldings, and Skirtings of any material.	lin. ft. 30,146	146	9	155
Dressed, n.e.i.	sup. ft. 629,475	2,655	2,846	5,501
Undressed Oregon, in sizes of 12 in. x 6 in. (or its equivalent) and over.	" 220,399	.....	1,140	1,140
Undressed, n.e.i., in sizes of 12 in. x 6 in. (or its equivalent), and over.	" 4,592,331	30,661	306	30,967
Undressed, n.e.i., in sizes of less than 12 in. x 6 in. (or its equivalent).	" 104,735,267	696,700	7,701	694,461
Laths	No. 355,250	.....	396	396
Fallings	" 527,800	2,133	.....	2,133
Pickets—Dressed	" 11,830	140	.....	140
Undressed	" 500	4	.....	4
Shingles	" 64,734	.....	79	79
Doors of Wood, 1½ inches, and over	" 140	125	20	145
" over 1½ inches, and under 1½ inches.	" 239	98	41	134
" 1½ inch, and under	" 275	12	104	116
Hickory, Undressed	sup. ft. 1,974	.....	21	21
Logs, not sawn, and Spars in the Rough	" 3,129,276	22,606	604	23,300
Staves, Undressed or Roughly Dressed, but not shaped.	No. 230	16	.....	16
New Zealand Pine, Undressed	sup. ft. 67,291	.....	491	491
Other, Free	.....	8,982	126	9,068
<b>Wicker, Bamboo, Cane, or Wood—</b>				
Manufactures of	.....	13,298	3,783	17,081
Axe, and other unattached Tool Handles	.....	.....	626	626
Canes, Baskets, unmanufactured; Cane compressed in sheet, and unshaped, and Bamboo, clouded.	.....	8	536	544
Free	.....	287	112	399
Total, Division X	.....	£ 776,949	24,765	801,704

Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
DIVISION XI.—JEWELLERY AND FANCY GOODS.		£	£	£
Clocks and parts thereof, Time Registers, and Detectors.	.....	.....	640	640
Fancy Goods	.....	2,150	18,144	20,294
Gold—Bullion, Bar, Dust, Ingot, and Sheet	oz. 1,757,199	6,101,909	43,837	6,145,746
Instruments—				
Phonographs, Cameras, Magic Lanterns, and the like.	.....	26	2,506	2,532
Telescopes, Thermometers, Compasses, and the like.	.....	.....	1,339	1,339
Jewellery and Imitation Jewellery (25 per cent.)	.....	764	39,443	40,207
Jewellery (15 per cent.)	.....	.....	209	209
Cameos and Precious Stones, Unset	.....	78,511	999	79,510
Silver—Bullion, Bar, Ingot, Sheet	oz. 5,524,884	604,562	4,275	608,837
Watches and parts thereof, Pedometers, Pocket Counters, and Chronometers, n.e.i.	.....	.....	14,822	14,822
Total, Division XI	.....	£ 6,782,922	125,859	6,908,781
DIVISION XII.—LEATHER AND RUBBER.				
Belting—				
Composition	.....	39	1,092	1,131
Leather	.....	997	543	1,540
Boots and Shoes—				
Men's, Youths', Boys', Women's, and Girls', except partly or wholly of Lasting or Stuff, and Slippers (Leather).	.....	8,166	4,174	12,340
N.E.I.	.....	89	239	328
Rubber Sand Shoes	.....	.....	125	125
Infants' Boots, Shoes, and Slippers, sizes 0-6	.....	.....	100	100
Gum Boots	.....	.....	11	11
Minor Articles for	.....	.....	1,268	1,268
Cloths made Waterproof with India-rubber	.....	203	197	400
India-rubber—				
Hose or other Manufactures, n.e.i.	.....	19,283	6,357	25,640
Canvas or Tyre Fabric made waterproof	.....	.....	288	288
India-rubber and India-rubber Manufactures (free).	.....	21	1,040	1,061
Leather—				
N.E.I.	.....	520,211	6,856	527,067
Manufactures, n.e.i.	.....	5,635	1,069	7,294
Minor Articles for Harness, Saddles, Leatherware, and Whips (including Saddle Trees, Saddlers' Tacks and Nails), Snaps (Harness and Halter), Spurs, and Spur Boxes.	.....	220	106	326
Saddlers' and Harness Makers' Materials	.....	29	296	324
Total, Division XII	.....	£ 554,898	24,400	579,298
DIVISION XIII.—PAPER AND STATIONERY.				
Books (printed), Music, Periodicals, Newspapers, and Pamphlets, not advertising.	.....	17,468	24,896	42,364
Cards, Playing, in sheet, or cut	doz. packs 439	.....	80	80
Paper—				
Advertising Matter	lb. 87,776	2,449	1,181	3,590
Bags	cwt. 596	93	785	828
Browns and Sugar (Grey, Blue, and other Tints), Fruit Bag Paper.	„ 377	10	406	415
Cartridge and Blotting	.....	3	57	60
Millboard, Greyboard, Leatherboard, and Woodboard.	.....	.....	87	87



Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
<b>DIVISION XIII.—PAPER AND STATIONERY.—cont.</b>		<b>£</b>	<b>£</b>	<b>£</b>
Paper—				
Printing, uncoated .....			3,040	3,040
Strawboard .....	cwt. 347	29	127	156
Writing .....			652	652
Toilet .....		20	17	37
N.E.I. ....		98	941	1,039
Free .....		152	1,708	1,860
Paperhangings .....			298	298
Pictures, not being advertising .....		3,782	15,502	19,284
Spectacles .....			545	545
Stationery—				
Manufactured, dutiable .....		7,586	3,949	11,535
Manufactured, free .....		722	1,406	2,128
<b>Total, Division XIII.</b> .....		<b>£ 32,402</b>	<b>55,635</b>	<b>88,037</b>
<b>DIVISION XIV.—VEHICLES.</b>				
Vehicles—				
Bicycles, Tricycles, and similar Vehicles and Parts .....		397	5,980	6,377
Cycle Parts, n.e.l. ....		107	712	819
Cycle Parts, free .....		2	54	56
N.E.I. and Parts thereof, n.e.l., duty 20 per cent. ....		4,765	4,631	9,396
Barouches, Broughams, Waggon, &c., duty 25 per cent. ....	No. 189	3,364	1,161	4,525
Vehicle Parts, viz., Wheels, tyred and bolted, Bodies, Under-gears, Under-carriages, and Tops .....		453	605	1,058
Motors .....	No. 13	.....	1,300	1,300
<b>Total, Division XIV.</b> .....		<b>£ 9,088</b>	<b>14,443</b>	<b>23,531</b>
<b>DIVISION XV.—MUSICAL INSTRUMENTS.</b>				
Instruments, Musical, N.E.I. ....		.....	3,476	3,476
Military, Band and Orchestra, and Bagpipes .....		.....	346	346
Organs, other, and Harmoniums .....	No. 19	.....	316	316
Pianos .....	147	96	4,396	4,492
Piano Parts, n.e.l. ....		.....	79	79
Parts of, viz., Actions, Strings, Felts, Hammers, and Ivories .....		.....	4	4
<b>Total, Division XV.</b> .....		<b>£ 96</b>	<b>8,617</b>	<b>8,713</b>
<b>DIVISION XVI.—MISCELLANEOUS.</b>				
Arms, Ammunition, and Explosives—				
Caps, Percussion .....		.....	4	4
Cartridges, Military .....		.....	10,000	10,000
Cartridges, n.e.l. ....		41	2,681	2,722
Cartridge Cases (empty or capped) and Wads .....		2,000	24	2,024
Detonators .....		.....	232	232
Dynamite, Gellignite, Gelatine Dynamite, and Gelatine, blasting. ....	lb. 48,354	1,232	1,461	2,693
Explosives, n.e.l. ....		.....	242	242
Fireworks .....		.....	250	250
Fuse .....	Coil 64,445	1,218	430	1,648
Powder, blasting .....	lb. 23,730	.....	694	694
Powder, sporting .....	4,480	.....	337	337
Articles for the Commonwealth .....		42	.....	42
Articles for the Army or Navy—Military Stores .....		400	3,512	3,912
Art, Works of .....		434	152	586

Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
DIVISION XVI.—MISCELLANEOUS.—continued.		£	£	£
Bags, Baskets, Boxes, Cases or Trunks, including Fittings.	.....	1,034	1,187	2,221
Minor Articles for.....	.....	1	.....	1
Baskets, Carpenters'.....	.....	.....	1	1
Boats, Launches, and Yachts, including all Fittings.	No. 93	3,961	45	4,006
Brushware and Combs, Toilet.....	.....	13	496	509
Brushware, n.e.l., including Brooms, Mops, Crumb Trays, and Brushes.	.....	364	813	1,177
Other, free.....	.....	.....	12	12
Coke.....	tons 26,914	18,448	.....	18,448
Cordage and Twines—				
Twine and Yarn, Reaper and Binder.....	cwt. 422	153	569	722
Other articles manufactured from Cordage or Twine, including Halters, Nets, and Netting.	.....	53	35	88
Metal.....	" 2,880	.....	7,021	7,021
N.E.I.....	" 4,601	5,897	6,245	12,142
Engine Packing in rope form.....	.....	260	423	683
Sewing Silks, Twists, Threads and Cottons, and Crochet Cottons.	.....	.....	4,545	4,545
Corks, Bungs, and Net Floats.....	.....	16	3,363	3,369
Cork Mats and other manufactures of cork.....	.....	6	103	109
Instruments, Scientific and Apparatus, for use in universities, colleges, schools, or public hospitals.	.....	.....	1,086	1,086
Surgical and Dental, and Appliances.....	.....	3	2,394	2,397
Models of Inventions, &c., and Models and Casts for teaching purposes for universities, colleges or schools.	.....	402	30	432
Nets, Fishing, and Netting therefor.....	.....	110	146	256
Photographic Dry Plates, Sensitised Films, and Paper.	.....	1,729	2,270	3,999
Pipes (smoking), Cigar and Cigarette Holders, and Cases, &c.	.....	14	3,070	3,084
Specimens of Natural History.....	.....	3,730	115	3,835
Theatrical Costumes and Properties.....	.....	2,066	1,170	3,236
Yarns, other, including Coir.....	.....	.....	1	1
Total, Division XVI.....	.....	£ 44,334	55,549	99,883
FREE GOODS NOT SPECIALLY MENTIONED IN THE TARIFF.				
Alunite.....	cwt. 49,690	6,212	.....	6,212
Antimony, Metal.....	" 15	.....	38	38
Bark, Tanning.....	" 142,594	60,992	21	61,013
Bass.....	" 16	.....	22	22
Bismuth, Metal.....	" 189	6,910	.....	6,910
Black Lead.....	.....	.....	33	33
Bones, Hoods, and Horns.....	" 32,828	23,877	.....	23,877
Charcoal.....	" 2,347	1,169	.....	1,169
Coal.....	ton 2,020,686	1,053,908	.....	1,053,908
Cocoa Beans and Cocoa, Unmanufactured.....	lb. 1,334	.....	46	46
Copper Ingots.....	cwt. 413,324	1,278,947	.....	1,278,947
Contained in Matte.....	" 203,063	322,832	.....	322,832
Ore.....	" 61,569	76,888	.....	76,888
Cotton, Raw.....	lb. 3,706	.....	75	75
Waste.....	.....	.....	659	659
Fibre, Coir.....	cwt. 208	.....	143	143
Flax and Hemp, including Phormium Tenax.....	" 1	.....	2	2
Jute.....	" 11	.....	29	29
Flock.....	" 331	192	.....	192
Furs, Undressed.....	.....	1,259	.....	1,259
Glue-pieces and Sinews.....	cwt. 18,591	9,521	25	9,546

Article.	Total Quantity.	Value.		
		Australian Produce.	Other Produce.	Total.
FREE GOODS NOT SPECIALLY MENTIONED IN THE TARIFF—continued.		£	£	£
Gold Ore and Concentrates .....	cwt. 16,918	16,562	....	16,562
Mar, Free .....	lb. 500,734	19,186	44	19,230
Kapok .....	" 241,081	....	6,212	6,212
Lead, contained in Matte .....	cwt. 1,124	556	....	556
Ore .....	" 49,768	30,332	....	30,332
Pig .....	" 682,712	318,209	17	318,226
Scrap and Old .....	" 628	161	5	166
Oakum and Tow .....	" 282	....	227	227
Ores, Antimony .....	" 947	467	....	467
Bismuth .....	" 832	7,027	....	7,027
Chrome .....	" 39,622	7,342	....	7,342
Cobalt .....	" 8,094	1,570	10	1,580
Iron .....	" 860	89	....	89
Molybdenite .....	" 783	6,072	....	6,072
Scheelite .....	" 62	140	....	140
Wolfram .....	" 9,443	4,340	....	4,340
N.E.L., including Earths (Alkaline and Infusorial), Fireclay, Mica, Black and Moulding Sands. ....	" 99,300	20,397	101	20,498
Pearlshell .....	" 42,350	368,569	4,097	372,666
Personal and Household Effects, Passengers' .....	" .....	12,946	17,717	30,663
Pitch and Tar .....	cwt. 27,316	2,337	1,863	4,200
Plants, Trees, and Bulbs .....	" .....	9,981	820	10,751
Platinum Alloy .....	oz. 530	1,061	....	1,061
Plumbago .....	cwt. 343	253	4	257
Potash and Pearl Ash, Crude, and Caustic Potash in Bulk. ....	" 129	....	230	230
Pumice Stone .....	" 1	....	1	1
Quicksilver .....	lb. 392	....	49	49
Rags .....	cwt. 10,231	5,588	....	5,588
Resin .....	" 842	....	346	346
Saltpetre .....	" 108	....	110	110
Sandalwood .....	" 88,129	37,913	....	37,913
Shale Kerosene .....	ton 14,255	34,013	....	34,013
Shark Fins .....	cwt. 16	....	70	70
Silver, contained in Matte .....	oz. 1,033,920	106,419	....	106,419
Ore .....	cwt. 1,603,928	448,694	....	448,694
Silver Lead Bullion .....	" 553,308	622,064	....	622,064
Skins, Hides .....	No. 159,615	111,064	6,323	117,407
Rabbit and Hare .....	" 27,189,721	138,147	....	138,147
Sheep, with Wool .....	" 6,661,645	1,067,357	5,309	1,062,666
Sheep, without Wool .....	" 150,160	5,949	2,047	7,996
Other .....	" .....	389,241	....	389,241
Specie, Gold .....	" .....	11,022,324	1,328,960	12,251,274
Silver .....	" .....	....	11,478	11,478
Bronze .....	" .....	....	654	654
Sulphur, Brimstone .....	cwt. 552	....	306	306
Tin, Ingots .....	" 82,475	513,324	17	513,341
Ore .....	" 26,900	84,833	....	84,833
Tortoiseshell .....	lb. 6,331	1,576	1,955	3,531
Wool, Greasy .....	" 263,546,652	9,600,599	4,366	9,604,965
Scoured and Washed .....	" 61,143,820	4,398,684	....	4,398,684
All other Articles .....	" .....	11,646	4,351	15,997
Total Free Goods, &c. ....	2	32,257,954	1,298,772	33,556,726
Total Exports .....	2	45,578,935	2,591,229	48,170,164
SUMMARY OF EXPORTS.				
Merchandise .....		27,748,721	1,302,495	29,046,206
Specie .....		11,022,324	1,241,082	12,263,406
Bullion .....		6,812,890	47,632	6,860,522
Total .....	2	45,578,935	2,591,229	48,170,164

Of the total import of £37,811,471 there were retained for home consumption goods to the value of £35,220,242, the balance, £2,591,229, being re-exported. The re-export trade of Australia in manufactured goods is transacted chiefly with New Zealand and the South Seas; the raw material re-exported is mainly the produce of the same countries collected in the chief Australian seaports for shipment to Europe; £1,241,082 represents gold from New Zealand and New Guinea, sent to the mints of Sydney and Melbourne, and when coined despatched to various parts of the world.

A comparison of the volume of trade during each year, from 1891 onwards, is afforded by the following table:—

Year.	Imports.	Exports.	Excess of Imports.	Excess of Exports.
	£	£	£	£
1891	37,711,053	36,052,145	1,658,908	.....
1892	30,107,338	33,392,620	.....	3,285,282
1893	23,765,084	33,225,985	.....	9,460,901
1894	21,897,114	32,131,113	.....	10,233,999
1895	23,195,114	33,644,332	.....	10,449,218
1896	29,658,197	32,963,622	.....	3,305,325
1897	31,965,904	37,772,555	.....	5,806,651
1898	31,481,518	40,164,699	.....	8,683,181
1899	34,329,687	48,599,033	.....	14,269,346
1900	41,388,030	45,956,882	.....	4,568,852
1901	42,433,811	49,696,172	.....	7,262,361
1902	40,675,950	43,915,067	.....	3,239,137
1903	37,811,471	48,170,164	.....	10,358,693

If the omissions from the Customs returns referred to on page 228 had not been made, the excess of exports in 1903 would probably have been some £2,500,000 more than shown in the foregoing table, and would thus have amounted to nearly £13,000,000.

An excess of exports is now the normal condition of Australian trade, due to the circumstance that the interest and return on British and foreign investments in the Commonwealth largely exceed the return of Australian investments abroad. The question of the annual payments made to external creditors is discussed at some length in another part of this volume, and it is there shown that the payments on account of state and municipal borrowings, and the earnings of private capital in Australia, reached, in 1903, £15,558,000, and this sum, or thereabouts, should represent the excess of exports over imports, if there were no import or export of capital. Hardly a year passes, however, that one or other of the state governments does not raise a loan in London, and capital is constantly being invested in Australia by private persons. It, therefore, rarely happens that the full difference represented by the payments made to the British and foreign creditor is shown in the trade returns.

In the table just given there is an excess of £89,267,038 during the thirteen years, while the tribute paid by the Australian Governments and people to creditors outside the Commonwealth in the same period was certainly not less than 177 millions, so that the indebtedness of Australia to British and foreign creditors was apparently increased during the period by about 80 millions, allowing for some 7 millions sterling imported by immigrants.

COMPARISON OF TRADE WITH BRITISH POSSESSIONS AND FOREIGN STATES.

The external trade of the Commonwealth amounts to £85,981,635, and of this trade over 46 per cent. still remains with Great Britain, as the following statement shows :—

	Total trade (Imports and Exports).	Proportion of total
United Kingdom.....	39,817,843.....	46·31 per cent.
British Possessions.....	20,471,370.....	23·80 „
Foreign Countries .....	25,692,422.....	29·89 „
	85,981,635.....	100·00 „

The figures just given refer to the direct trade, but a considerable amount of goods is sent from foreign countries to Great Britain and thence exported to Australia. There are no means of ascertaining with exactitude the value of this trade, but a measure of it may be obtained from the British Board of Trade returns, which show an average export of foreign and colonial produce to Australia, during the last five years, of £1,966,730 per annum, while a somewhat larger quantity of Australian produce is exported from Great Britain to foreign countries. Neglecting this indirect trade, the following is a statement of the direction of the external trade of the Commonwealth during the last twelve years :—

Year.	Imports from—			Exports to—		
	United Kingdom.	British Possessions.	Foreign Countries.	United Kingdom.	British Possessions.	Foreign Countries.
	£	£	£	£	£	£
1891	26,453,841	4,329,271	6,927,941	25,498,010	2,829,414	7,724,661
1892	21,299,582	3,421,985	5,385,771	23,236,052	2,384,099	7,772,469
1893	17,295,694	2,884,988	3,584,402	23,576,751	2,997,495	6,651,739
1894	15,748,297	2,619,471	3,529,346	22,943,100	2,900,654	6,287,359
1895	16,610,697	2,659,782	3,924,635	23,767,173	2,978,232	6,898,927
1896	20,252,661	3,184,529	6,221,107	21,630,820	2,861,751	8,470,951
1897	21,174,031	3,422,759	7,369,114	25,823,931	3,043,812	8,904,812
1898	21,002,852	3,395,967	7,082,699	23,886,313	3,207,164	13,071,222
1899	21,230,913	4,035,066	9,063,718	26,564,690	7,586,084	14,448,259
1900	25,363,352	4,670,379	11,354,299	25,215,905	8,624,297	12,116,680
1901	25,236,677	4,758,795	12,438,339	25,196,441	12,007,527	12,492,204
1902	23,850,557	5,377,885	11,447,508	20,224,604	12,197,621	11,492,762
1903	19,856,340	4,980,880	12,975,251	19,962,503	15,490,490	12,717,171

The foregoing table shows that a considerable change is taking place in the direction of the Australian trade. The United Kingdom, though still the greatest factor in the trade of the Commonwealth, has diminished in importance both actually and relatively. Extending the period reviewed back to 1861, the importance of the change taking place will be more clearly apprehended. The following statement shows the volume of trade in quinquennial periods, commencing with 1861, and distinguishing the trade with the United Kingdom, British Possessions, and foreign countries.

Years.	Imports from—			Total Imports.
	United Kingdom.	British Possessions.	Foreign Countries.	
	£	£	£	£
1861-65	69,824,585	13,284,813	16,931,345	100,040,743
1866-70	60,392,217	18,068,939	14,537,213	92,998,369
1871-75	75,568,020	19,924,188	13,491,699	108,983,907
1876-80	89,020,970	18,327,973	15,766,484	123,115,427
1881-85	128,073,941	22,491,217	24,066,365	174,631,523
1886-90	122,729,684	21,329,451	23,849,366	172,908,501
1891-95	97,408,111	15,915,497	23,352,095	136,675,703
1896-1900	109,023,709	18,708,690	41,090,937	168,823,336
* 1901-1903	68,942,574	15,117,560	36,861,098	120,921,232

\* Three Years.

Stating the foregoing figures as percentages of the total imports in each quinquennium, the following results are obtained:—

Years.	Imports from—		
	United Kingdom.	British Possessions.	Foreign Countries.
	per cent.	per cent.	per cent.
1861-65	69·80	13·28	16·92
1866-70	64·94	19·43	15·63
1871-75	69·34	18·28	12·38
1876-80	72·30	14·89	12·81
1881-85	73·34	12·88	13·78
1886-90	70·98	12·34	16·68
1891-95	71·27	11·64	17·09
1896-1900	64·58	11·08	24·34
1901-1903	57·02	12·50	30·48

These figures show a remarkable diversion of trade, especially in recent years, from the United Kingdom to foreign countries. An explanation has been hazarded that the diversion is more apparent than real, being due to the carriage of goods direct from foreign

countries to Australia, whereas such goods were formerly sent *via* London, but this explanation only partly accounts for the change. Making allowance for foreign goods reaching Australia by way of London, the following would appear to be the percentages of foreign goods to total goods imported in the years named. It is unfortunately impossible to give the information for an earlier period :—

1886-90 .....	23·5
1891-95 .....	23·4
1896-1900 .....	30·0
1901-3 .....	34·0

One-third of all goods now imported into Australia may be said to be of non-British origin as compared with one-fourth ten years ago. The chief factor in bringing about this change is undoubtedly the establishment of direct and rapid communication between Germany, France, Belgium, Japan, the United States, and the Commonwealth. Twenty years ago it was difficult, if not impossible, to obtain goods direct from the continent of Europe or the eastern sea-board of the United States, now there is fortnightly communication with Hamburg and Bremerhaven by a line subsidised by the German Imperial Government, and with Marseilles, Havre, and Dunkirk by the Messageries Maritimes—a line heavily subsidised by the French Republic. Turning to the exports to the same countries it will be found that a change of a somewhat similar character has taken place.

Years.	Exports to—			Total Exports.
	United Kingdom.	British Possessions.	Foreign Countries.	
	£	£	£	£
1861-65	55,021,542	35,642,611	1,848,260	92,512,413
1866-70	66,410,385	29,303,470	1,588,398	97,302,253
1871-75	90,283,646	25,155,553	3,935,648	119,374,847
1876-80	89,422,429	26,599,992	4,503,977	120,526,398
1881-85	105,077,532	22,213,056	12,981,383	140,271,971
1886-90	101,809,218	11,721,583	19,423,090	132,953,891
1891-95	119,021,086	14,089,954	35,335,155	168,446,195
1896-1900	123,121,659	25,323,108	57,011,924	205,456,691
1901-03	65,383,448	39,695,838	36,702,137	141,781,423

## PERCENTAGE OF TOTAL.

1861-65	59·48	38·53	1·99	100
1866-70	63·25	30·12	1·63	100
1871-75	75·63	21·07	3·30	100
1876-80	74·20	22·00	3·80	100
1881-85	74·91	15·83	9·26	100
1886-90	76·57	8·81	14·62	100
1891-95	70·66	8·37	20·97	100
1896-1900	59·86	12·41	27·73	100
1901-03	46·11	28·00	25·89	100

As the table shows there was a remarkable decline in the percentage of exports to British Possessions in 1891 as compared with 1881. This was due to a large falling off in the exports of specie and bullion to India and Ceylon; of late years, however, these exports have been resumed.

From the above figures it is apparent that, as in the case of the imports, there has been a considerable modification in the direction of the export trade. The causes of the great advance in the proportion of trade taken by foreign countries have already been discussed. It will be observed that the percentage of exports to the British Possessions advanced considerably during the last three years, the increase being chiefly due to the demand for the produce of the Commonwealth occasioned by the war in South Africa.

It would be extremely interesting to trace the changes in trade with various countries, but the subject is too voluminous to be dealt with in this place, and for details the reader is referred to the Annual Statement of the Trade of the Commonwealth for 1903, published by the Department of Trade and Customs. In that volume will be found a detailed statement of the trade of the Commonwealth with the United Kingdom, British Possessions, and foreign countries for the five years 1899 to 1903.

#### TRADE WITH THE UNITED KINGDOM.

The following table shows the trade of the Commonwealth with the United Kingdom at decennial periods since 1861 and for the year 1903:—

Year.	Imports.	Exports.	Total.
	£	£	£
1861 .....	12,354,123	11,643,598	23,997,721
1871 ....	10,096,057	15,609,163	25,705,220
1881 ...	21,131,869	19,866,821	40,998,690
1891 .....	28,453,841	25,498,010	51,951,851
1901 .....	25,236,677	25,196,441	50,433,118
1903 .....	19,855,340	19,962,503	39,817,843

As the table shows, the trade reached its highest point in 1891, when it amounted in value to nearly 52,000,000 sterling. The year 1891 was, however, a record one as regards production in most of the states, while the effects of the unfavourable seasons since then experienced are reflected in the figures for succeeding years. In addition, as has been previously alluded to, the development of facilities for communication



has caused a great increase in trade with the British possessions and with foreign countries.

A classification of the principal articles imported into the Commonwealth from the United Kingdom during the year 1903 is given below:—

Article.	Value.	Article.	Value.
	£		£
Ale, Porter, and Beer, &c. ....	800,906	Instruments — Phonographs, Cameras, Magic Lanterns, and the like. ....	25,826
Apparel and Attire, n.e.i. ....	1,517,687	Instruments— Surgical and Dental Iron and Steel. ....	31,767
Arms, Ammunition, and Explosives. ....	524,248	Jewellery and Precious Stones ....	1,297,928
Blankets and Blanketing ....	67,986	Lamps and Lampware ....	340,146
Books (printed), Music, &c. ....	808,900	Leather ....	84,628
Boots and Shoes ....	224,148	Machines and Machinery. ....	127,634
Brushware (Toilet and other) ....	76,964	Machine Tools. ....	1,141,591
Carpets and Carpeting ....	90,533	Manures ....	41,553
Cement ....	37,036	Medicines ....	88,379
Cocoa and Chocolate (ground). ....	118,186	Metals, Manufactures of ....	183,613
Confectionery ....	76,855	Milk, Preserved ....	1,109,872
Copper ....	50,906	Oils ....	88,061
Cordage and Twines— Metal. ....	64,408	Oilmen's Stores, n.e.i. ....	100,708
Other ....	82,413	Paints and Colours ....	94,796
Corks, Bungs, and Net Floats ....	30,666	Paper ....	182,421
Codes, Cushions, Mantel and Furniture Drapery, Bedcovers and Furnishings, n.e.i. ....	103,583	Pickles, Sauces, &c. ....	878,897
Curtains ....	68,630	Piece Goods ....	65,482
Cutlery, n.e.i. ....	83,367	Pipes (Smoking), &c. ....	4,377,361
Drugs and Chemicals ....	817,703	Rails, &c., for Railways and Tramways. ....	66,787
Earthenware, Brownware, and Stoneware. ....	94,155	Sewing Silks, Threads, Cottons, &c. ....	442,755
Electrical Materials. ....	178,336	Spirits ....	245,851
Fancy Goods ....	140,137	Stationery ....	561,902
Fish (preserved) ....	188,625	Tobacco, Cigars, and Cigarettes ....	174,667
Floor Cloths and Coverings ....	191,981	Tools of Trade (exclusive of Machine Tools). ....	43,816
Furniture, n.e.i., except Metal ....	60,020	Trimmings— Mantle, Dress, Bonnet, and Hat, n.e.i. ....	124,490
Glass and Glassware ....	91,905	Varnishes ....	191,362
Gloves ....	148,708	Vehicles ....	42,061
Grain and Pulse— Malt ....	51,238	Watches, &c. ....	216,448
Hats and Caps ....	308,638	Yarns. ....	74,224
Implement and Machinery— Agricultural, Horticultural, and Viticultural. ....	62,299		62,038
Indiarubber Manufactures ....	159,709	Total, all Imports from United Kingdom. ....	£19,855,340

In order to make a useful comparison of the value of the Australasian trade to the United Kingdom, it is necessary to refer to the British Board of Trade returns, and these returns have been used in the ensuing comparisons. The figures relating to Australasia, especially for late years, approximate very closely to the local Customs statistics. From the table it will be observed that while in 1881 the produce of the Commonwealth of Australia and the colony of New Zealand formed 29·5 per cent. of the imports of the United Kingdom from her possessions, in 1891 the proportion was 31·4 per cent., but in 1903 it declined to 26·8 per cent.

The year 1903 was, however, an unfortunate one for some of the mainland states, and the diminished production was reflected in the decreased body of exports. In 1901 the proportion of imports into

the United Kingdom from Australia was 23 per cent., and from New Zealand 10 per cent., making a total of 33 per cent. :—

Year.	As returned by British Customs.				Proportion of Imports from Australasia to total from British Possessions.		
	Total Imports from British Possessions.	Imports from Australasia.			Common-wealth of Australia.	New Zealand.	Total.
		Common-wealth of Australia.	New Zealand.	Total.			
	£	£	£	£	per cent.	per cent.	per cent.
1881	91,539,660	21,837,709	5,125,859	26,963,568	23·9	5·6	29·5
1891	99,464,718	23,068,972	8,192,594	31,261,566	23·2	8·2	31·4
1901	105,684,880	24,217,669	10,594,587	34,812,256	23·0	10·0	33·0
1903	113,670,792	17,057,527	13,454,484	30,512,011	15·0	11·8	26·8

Although it is very little more than a century since the commencement of Australasian settlement, an examination of the trade statistics of the mother country with her numerous dependencies shows that the total trade of the Commonwealth and New Zealand with the United Kingdom is more than one and a half times that of Canada, and in a larger degree exceeds the trade of any other British possession, with the exception of India. In normal years the Australasian trade is even in excess of that of India, the amount of such excess in 1901 being considerably over a million sterling. The following table, which is also compiled from the returns of the Board of Trade, shows the total trade of the United Kingdom exclusive of specie and diamonds for the three years 1881, 1891, and 1903, with the most important of British possessions :—

Country.	1881.	1891.	1903.	Proportion of Trade of United Kingdom with British possessions.		
				1881.	1891.	1903.
	£	£	£	per cent.	per cent.	per cent.
India .....	63,682,398	64,783,005	67,621,964	35·7	35·6	29·0
British North America .....	20,808,159	20,806,357	40,479,569	11·6	10·8	17·4
Cape Colony and Natal .....	13,108,264	14,692,966	32,806,463	7·4	7·7	14·1
Straits Settlements .....	6,527,675	7,946,127	9,093,676	3·7	4·1	3·9
Hongkong .....	4,815,906	3,693,869	3,474,474	2·7	2·0	1·5
Australasia—						
Commonwealth of Australia ..	41,662,820	47,522,331	35,186,896	23·4	24·7	15·1
New Zealand .....	9,206,331	11,970,968	20,409,804	5·2	6·2	8·7
Total, Australasia ....	50,869,151	59,493,319	55,596,700	28·6	30·9	23·8

If, again, a comparison be made of the total trade transacted by the United Kingdom with all countries during the year 1903, it will be found that the trade with Australasia, amounting to £55,596,200, was only exceeded by that carried on with three countries, namely, the

United States, with a total of £163,717,858; France, with £72,493,914; and Germany, with £69,049,729. The amounts taken by other countries will be found below, and it must be noted that the values given do not include specie :—

Country.	1881.	1891.	1903.	Proportion of Total Trade of United Kingdom.		
				1881.	1891.	1903.
	£	£	£	per cent	per cent	per cent
France .....	70,009,848	69,114,186	72,493,914	10·1	9·3	8·0
Germany .....	52,927,199	56,976,104	69,049,729	7·6	7·7	7·6
Belgium .....	25,047,883	30,525,737	40,583,963	3·6	4·1	4·5
Holland .....	38,205,414	42,290,587	49,014,068	5·5	5·7	5·4
Spain .....	14,421,326	16,060,936	19,206,325	2·1	2·2	2·1
Italy .....	10,792,615	10,272,329	11,914,258	1·6	1·2	1·3
United States .....	139,990,876	145,475,197	163,717,858	20·2	19·5	18·1
Argentine Republic .....	4,000,490	7,817,256	27,745,985	0·6	1·0	3·1
Chile .....	5,417,363	5,916,225	7,929,943	0·8	0·8	0·9
Brazil .....	13,254,733	12,855,202	12,572,412	1·9	1·7	1·4
Uruguay .....	1,881,522	1,568,891	2,570,548	0·3	0·2	0·3
Australasia—						
Commonwealth of Australia .....	41,662,820	47,522,381	35,186,896	6·0	6·4	3·9
New Zealand .....	9,206,331	11,970,988	20,406,304	1·3	1·6	2·3
Total, Australasia ..	50,869,151	59,493,319	55,593,200	7·3	8·0	6·2

#### TRADE WITH BRITISH POSSESSIONS.

The following table shows the imports into the Commonwealth from the chief British possessions at decennial periods since 1861, and also for the year 1903.

Possession.	1861.	1871.	1881.	1891.	1901.	1903.
	£	£	£	£	£	£
Canada .....		4,637	27,268	149,836	330,788	352,989
Cape Colony .....	15,283	11,620	596	373	6,570	3,417
Ceylon .....	347,845	532,793	109,630	186,184	499,397	526,755
Fiji .....			63,190	154,824	45,423	161,918
Hong Kong .....	431,100	222,677	642,308	624,396	255,010	309,556
India .....	298,898	104,066	567,187	766,808	1,183,871	967,076
Mauritius .....	767,659	1,076,597	1,120,712	838,529	129,659	70,494
Total .....		41,862		1,789	307	638
New Zealand .....	173,969	2,468,607	1,227,265	1,793,088	1,814,687	2,301,792
Straits Settlement .....	11,105	12,065	54,546	178,516	320,584	116,028
Other .....	5,870	12,191	127,650	55,150	142,499	180,268
Total .....	2,050,599	4,543,105	3,940,352	4,298,333	4,768,795	4,980,880

As the table shows, imports from New Zealand, India and Ceylon, Canada, and Hongkong amounted in 1903 to £4,458,117, or about 90 per cent. of the total from all British possessions. From New Zealand, the imports comprised gold, £1,159,642; New Zealand pine, £239,456; oats, £216,193; butter and cheese, £112,012; hides, £60,675; and flax, £57,858. Amongst the chief imports from India were bags and sacks, £553,974; tea, £139,510; canvas, £61,743, and castor oil, £34,269. From Ceylon, tea to the value of £490,750 was

imported during 1903. The Indian and Ceylon teas have quite overmastered the Chinese article in the public estimation; the imports of the latter having decreased from £754,845 in 1890 to £62,131 in 1903, while the value of Indian and Ceylon teas, imported during the same period, advanced from £238,241 to £630,260.

Trade with Canada shows a considerable increase for each of the years given in the period. The chief imports in 1903 were flour, £108,558; agricultural implements, £49,897; and timber, £40,748. Hongkong furnished sugar to the value of £123,410, and opium, £30,660. Amongst the chief imports from other possessions may be mentioned sugar from Mauritius valued at £70,444, and from Fiji, £62,197; manures (guano) from Ocean Island, £67,925; and copra from Fiji, £68,262. From New Guinea gold to the value of £60,000 was imported during the year. The chief imports from the Straits Settlements comprised pepper and other spices, £28,501; tapioca, £16,473; and kerosene oil, £13,504.

The exports from the Commonwealth to the chief British possessions at the same periods were as shown below:—

Possession.	1861.	1871.	1881.	1891.	1901.	1903.
	£	£	£	£	£	£
Canada .....				40	37,543	24,837
Cape Colony .....	2,706	14,000	271,282	171,312	4,813,063	2,413,976
Ceylon .....	874,062	3,342,100	2,984,586	95,920	2,734,198	3,973,769
Fiji .....		155	157,913	122,430	209,741	329,921
Hongkong .....	343,398	121,783	359,984	484,363	413,711	390,544
India .....	1,302,030	224,677	219,349	899,067	543,016	5,601,972
Mauritius .....	464,374	64,725	95,475	107,146	60,572	25,961
Natal .....		4,760	133,150	97,193	1,520,532	843,477
New Zealand .....	1,367,829	1,239,065	1,341,189	680,213	1,464,963	1,743,483
Straits Settlements .....	11,412	4,688	88,767	151,143	113,528	107,657
Other .....	664,470	4,062	4,428	29,043	104,621	109,873
Total .....	5,030,311	5,020,725	5,555,973	2,817,880	12,007,527	15,400,400

## SUMMARY.

	£	£	£	£	£	£
Imports and Exports .....	7,080,910	9,563,830	9,496,325	7,116,213	16,766,322	20,471,370

From the above table it will be seen that the bulk of the exports is taken by India, Ceylon, Cape Colony, and New Zealand in the order named, these four possessions receiving nearly 89 per cent. of the total exports to all British possessions in 1903. The chief exports to India were gold specie, £3,761,300; gold bullion, £1,339,870; silver bullion, £213,804; horses, £81,251; copper ingots, £72,067; timber rough, £64,446; and coal, £24,115. Ceylon received in 1903 gold specie, £3,567,203; silver bullion, £338,590; and pig lead, £21,301. Amongst the principal exports to Cape Colony were gold specie, £1,500,000; chilled beef, £370,714; undressed timber, £139,061; fodder, £73,050; chilled mutton, £58,109; butter, £56,588; and wheat, £40,121. New Zealand received gold specie to the amount of £513,000; undressed

timber, £104,529; and coal, £114,819. Amongst exports to other British possessions may be mentioned the following, which were despatched to Natal during 1903,—chilled beef, £204,007; butter, £175,316; and chilled mutton, £131,152. The trade with South Africa, which assumed considerable proportions during the war, fell away largely in 1903, nevertheless the accessibility of its markets makes the possession a convenient outlet for Australia's exportable surplus of forage and foodstuffs. A remunerative market already exists for compressed fodder, which is well and favourably known, the exports in 1903 to Cape Colony and Natal amounting to about £84,000.

#### TRADE WITH FOREIGN COUNTRIES.

Every year steamers of greater tonnage and higher speed are visiting the Commonwealth of Australia and the colony of New Zealand from Europe, and a considerable expansion of commerce must of necessity take place, owing to the new outlets for trade which have been opened up thereby. The values of the imports into the Commonwealth from the principal foreign countries during the period 1861-1903 were as shown below:—

Country.	1861.	1871.	1881.	1891.	1901.	1903.
	£	£	£	£	£	£
Belgium .....			26,687	314,434	567,641	341,271
France and New Caledonia .....	136,063	158,573	321,238	359,951	430,780	506,667
Germany .....	90,686	8,899	219,893	1,707,175	2,799,387	2,353,553
Netherlands and Java .....	110,179	194,519	464,503	652,517	993,777	847,337
Italy .....			7,874	56,617	165,347	153,757
Sweden and Norway .....	23,006	106,720	259,147	459,046	506,454	318,508
China .....	327,347	342,087	1,231,765	680,328	159,489	244,172
Japan .....			23,150	52,887	238,216	330,121
South Sea Islands .....	25,978	84,913	104,932	12,792	67,650	75,371
United States .....	1,053,833	557,230	1,249,443	2,553,330	5,354,150	6,368,532
Other Foreign Countries .....	884,101	139,639	93,389	73,874	559,248	1,432,882
<b>Total .....</b>	<b>3,160,888</b>	<b>2,087,630</b>	<b>4,062,021</b>	<b>6,927,941</b>	<b>12,433,339</b>	<b>12,975,251</b>

As the table shows, the imports from the United States amounted, in 1903, to £6,368,532, or nearly half the total imports from all foreign countries. Next in order comes Germany with £2,353,553, followed by the Netherlands and Java with £847,337, and France with £506,667. The imports from the United States cover a long list, amongst the principal articles being boots and shoes, £87,000; barley, £109,000; wheat, £1,139,000; flour, £517,000; implements for husbandry, £320,000; leather, £108,000; machinery, £464,000; metal manufactures, £321,000; kerosene oil, £355,000; printing paper, £245,000; tobacco, £416,000; tools of trade, £118,000; vehicles, £139,000; and timber, £475,000. The chief imports from Germany comprised wearing apparel, £145,000; dynamite, £79,000; candles, £58,000; fancy goods, £67,000; pianos, £137,000; machinery, £149,000; metal manufactures, £303,000; piece goods, £143,000; manures, £45,000. From France the chief imports in 1903 were cream

of tartar, £81,000; piece goods, £90,000; spirits, £90,000; and wine, £56,000. Sugar was imported from Java to the amount of £720,000, and from Norway and Sweden timber of the value of £192,000 was received during the year. The Argentine Republic contributed maize to the value of £188,000, and wheat valued at £687,000.

For the same period the exports from the Commonwealth to the countries mentioned in the preceding table were as appended:—

Country.	1861.	1871.	1881.	1891.	1901.	1903.
	£	£	£	£	£	£
Belgium .....	.....	.....	100,487	1,484,073	1,506,635	1,800,760
France and New Caledonia ....	26,793	101,618	281,544	1,807,905	2,475,399	3,350,109
Germany .....	.....	.....	70,422	859,557	2,552,458	3,134,688
Netherlands and Java .....	3,907	39,517	52,192	92,645	322,970	230,762
Italy .....	.....	.....	152,914	27,966	139,166	132,623
Sweden and Norway .....	.....	.....	.....	.. ..	4,040	810
China .....	112,969	26,636	67,501	30,135	128,976	98,906
Japan .....	1,805	9,470	6,872	16,485	123,355	115,992
South Sea Islands .....	31,319	111,715	103,758	55,963	107,854	119,574
United States .....	66,602	271,800	943,118	2,754,053	3,373,916	2,625,399
Other Foreign Countries .....	483,457	3,133,350	363,458	581,286	1,768,435	1,098,793
Total ..	726,852	3,694,106	2,147,216	7,710,103	12,492,204	12,717,171

## SUMMARY.

	£	£	£	£	£	£
Imports and Exports .....	3,837,740	5,781,736	6,199,237	14,638,049	24,980,543	25,692,422

As the table shows, the bulk of the exports was consigned to France, Germany, the United States, and Belgium, these four countries taking over 85 per cent. of the total exports to all foreign countries. A classification of the chief articles of export to these countries is appended:—

Article.	France.	Germany.	United States.	Belgium.
	£	£	£	£
Coal .....	.....	.....	162,220	.....
Copper Ingots and Matte ....	.....	157,788	375,467	136,189
Gold Bullion .....	.....	.....	.....	26,520
Lead, Pig .....	.....	50,166	.....	17,263
Leather .....	.....	.....	.....	19,393
Silver Ore .....	28,344	41,584	.....	.....
Silver Lead Bullion .....	.....	225,839	.....	67,456
Sheepskins with Wool .....	452,574	55,176	.....	207,150
Skins, Other .....	.....	29,098	101,423	.....
Specie, Gold .....	.....	100,000	1,500,000	.....
Tin, Ingots .....	.....	.....	33,109	.....
Wool, Greasy .....	1,894,626	1,771,686	388,247	786,772
Wool, Scoured .....	781,956	570,933	.....	257,525

In addition to the above, Japan took scoured wool to the value of £61,682, and Chili, Hawaiian Islands, and the Philippines coal to the value of £273,868, £91,614, and £113,508 respectively. The Philippines received also chilled beef to the value of £93,751; the Netherlands kerosene shale valued at £24,430, and silver ore at £82,933; Italy took greasy wool to the value of £87,423; while undressed timber to the value of £144,360 was consigned to Portuguese East Africa.

Under present tariff conditions little extension of commercial intercourse with the United States can be looked forward to; but trade with the East, especially with China, Japan, and the Philippines, gives good promise for the future. As before mentioned, Japan has established a national line of steamers to foster the trade between that country and Australia, and during 1903 received from the Commonwealth goods valued at £115,992, the chief item being wool valued at £61,682, together with smaller quantities of other pastoral products, such as bones, manures, &c.

The total trade with China in 1903 was returned as £345,650; but these figures do not represent the whole volume of business transacted, as a fair proportion of the trade of Hongkong really belongs to China, the port of Hongkong being a distributing centre for the Empire. In view of this fact, the following table has been compiled, which shows the trade with the Chinese Empire and with Hongkong during the years 1891 and 1903:—

Trade.		With Chinese Empire.	With Hongkong.	Total.
1891	Imports.....	£ 680,328	£ 624,386	£ 1,304,714
	Exports.....	30,185	484,363	514,548
	Total .....	710,513	1,108,749	1,819,262
1903	Imports.....	244,172	309,555	553,727
	Exports.....	98,906	390,564	489,470
	Total .....	343,078	700,119	1,043,197

Trade with Java in 1903 amounted to £870,732, of which £766,198 represented imports and £104,534 exports. Sugar was imported to the value of £720,000. The chief exports comprised coal, £27,214; flour, £25,009; butter, £20,648; and horses, £6,330. Most of the requirements of the Dutch East Indies are met by America, but there is no doubt that judicious exploitation of the markets would result in a greatly increased demand for Australian products.

A fair amount of business is transacted with the South Sea Islands, the exports consisting chiefly of foreign goods re-exported from New

South Wales. The imports consist of island produce, the chief of these being copra. New Caledonia received exports from the Commonwealth to the amount of £133,583 during the year 1903, the bulk of which came from Sydney. The trade, however, has been adversely influenced by the operation of the French protective tariff, the exports from Sydney and Newcastle alone in 1892 amounting to over £184,000 as against £132,000 in 1903.

The commerce with foreign countries from the commencement of the period under review exhibits very satisfactory progress; the imports have increased by nearly ten millions sterling, and the exports by nearly twelve millions, while the expansion in the total trade was as much as 560 per cent. This remarkable growth is chiefly due to the development of the European continental trade, consequent on the diversion of part of the wool business from London, which was largely brought about by the display of local resources at the Sydney and Melbourne International Exhibitions of 1879 and 1880. The annual increase per cent. of the trade of Australasia with the four principal foreign countries with which it has commercial relations is shown below, the period covered being the twenty-two years extending from 1881 to 1903 :—

Country.	Imports.	Exports.	Total Trade.
	per cent.	per cent.	per cent.
Belgium .. .. .	14.26	13.50	13.67
France .. .. .	2.59	10.53	7.97
Germany .. .. .	12.87	18.65	14.58
United States .. .. .	6.77	4.39	5.83

As shown in a preceding table trade with these countries has now reached a fairly large volume, but its beginnings were small, hence the large percentage of increase exhibited by the above figures. Turning to individual countries, Germany exhibits the greatest progress, and Belgium ranks second. From Antwerp, in the latter country, a great portion of German and French manufactures is shipped. This port is also the distributing centre for a considerable part of the wool destined for the Continent, and large quantities of this product landed there ultimately find their way to Germany, France, and other countries. The French, early in 1883, were the first to establish direct commercial relations with Australia, the steamers of the Messageries Maritimes, a subsidised line, making their appearance for the first time in Australian waters in the year named. In 1887 the vessels of the Norddeutscher Lloyd Company, of Bremen, commenced trading with Australasia; and



in the latter part of 1888 a line of German cargo-boats opened up further communication between the great wool-exporting cities of Sydney, Melbourne, and Adelaide and the ports of Antwerp, Hamburg, and Dunkirk. Belgium has also established a line of steamships; and the latest foreign testimony to the growing importance of Australasia is the regular running of the Nippon Yusen Kaisha's steamers between Japanese ports and Sydney, and a line of steamers which runs between San Francisco and Sydney, calling at New Zealand. In addition to the companies mentioned, some British lines run their vessels direct to Continental ports.

The result of these efforts to establish commercial relations is evident from the increase of trade which the foregoing table discloses, and from the diversion, now rapidly being effected, in the channel by which the wool required for Europe reaches the market. The example of the South American Republics, the bulk of whose produce was shipped direct to Antwerp, Hamburg, Havre, and Dunkirk without passing through London, was not lost on Continental buyers. It was manifest that direct shipments of wool to Europe could as readily be made from Sydney or Melbourne as from Buenos Ayres or Monte Video; hence the presence in the local markets, in increasing numbers, of buyers representing Continental firms.

#### TRADE OF THE STATES, VIEWED AS INDEPENDENT COMMUNITIES.

In preceding tables the identity of the different states has been merged in that of the Commonwealth, but it is also interesting to view the trade of the states as if each state were a separate entity. The following series of tables shows the distribution of the total trade of the Australian Commonwealth, for the years 1881, 1891, and 1903, with the average value per head of population. The first table represents the imports :—

State.	Total Value of Imports.			Value per Inhabitant.		
	1881.	1891.	1903.	1881.	1891.	1903.
	£	£	£	£ s. d.	£ s. d.	£ s. d.
New South Wales .....	17,587,012	25,883,397	26,770,169	23 2 7	22 4 5	18 16 4
Victoria .....	16,718,521	21,711,608	17,856,171	19 4 8	18 19 2	14 15 0
Queensland .....	4,063,625	5,079,004	6,781,207	18 5 8	12 16 2	12 19 8
South Australia .....	5,820,549	10,051,123	6,718,819	19 4 8	31 8 4	18 5 11
Western Australia .....	404,881	1,280,098	6,766,922	13 14 8	25 14 8	30 14 9
Tasmania .....	1,481,144	2,061,964	2,598,610	12 5 0	13 15 6	14 10 8
Commonwealth .....	45,525,682	66,557,189	67,442,896	19 18 7	20 9 1	17 4 4

The values of the total exports for the same years were as given below :—

State.	Total Value of Exports.			Value per Inhabitant.		
	1881.	1891.	1903.	1881.	1891.	1903.
	£	£	£	£ s. d.	£ s. d.	£ s. d.
New South Wales .....	16,307,905	25,944,020	26,738,111	21 9 0	22 14 3	18 15 10
Victoria .....	16,252,103	16,006,743	19,707,070	18 13 6	13 19 7	16 5 8
Queensland .....	3,540,366	8,305,387	9,514,974	15 18 6	20 18 11	13 7 2
South Australia .....	4,508,754	10,642,416	8,443,243	16 5 7	33 0 0	22 19 11
Western Australia .....	502,770	799,466	10,324,732	17 0 8	16 1 2	46 17 7
Tasmania .....	1,555,576	1,440,818	2,843,108	13 6 3	9 13 6	15 18 7
Commonwealth .....	42,667,374	63,138,850	77,571,238	18 13 6	19 13 11	19 16 0

The total trade, similarly classified, was as follows :—

State.	Value of Total Trade.			Value per Inhabitant.		
	1881.	1891.	1903.	1881.	1891.	1903.
	£	£	£	£ s. d.	£ s. d.	£ s. d.
New South Wales .....	33,394,817	51,327,417	53,508,280	44 11 7	44 18 8	37 12 2
Victoria .....	32,970,624	37,718,351	37,566,241	37 17 9	32 18 9	31 0 8
Queensland .....	7,603,991	13,384,391	15,246,181	34 4 2	33 15 1	31 6 10
South Australia .....	9,329,303	20,093,589	15,162,062	35 9 10	64 3 4	41 5 10
Western Australia .....	907,601	2,079,550	17,094,664	30 14 11	41 15 5	77 12 4
Tasmania .....	2,866,720	3,492,782	5,436,718	25 11 3	23 9 0	30 9 3
Commonwealth .....	88,193,056	123,696,039	145,014,136	33 12 1	40 3 0	37 0 4

The point most notable in this series of tables is the very marked impetus which the trade of South Australia received during the period 1881-91—a trade of £64 3s. 4d. per inhabitant, the value transacted by that state during 1891, being almost without parallel in any important country. This huge trade was, however, not drawn altogether from its own territory, for in 1891 more than £5,731,000, or about £17 15s. per inhabitant, and in 1902, £1,986,700, or £5 8s. 7d. per inhabitant, was due to the Barrier District of New South Wales, of which South Australia is the natural outlet; and it must also be remembered that considerable quantities of goods on their way to Broken Hill are entered as imports in South Australia when they arrive in that state, and as exports to New South Wales when they cross the border. The large and increasing production of the gold-fields is the chief cause of the remarkable development in the trade of Western Australia, which will be noticed when comparing the years 1891 and 1903.

The trade of New South Wales in 1891 was valued at no less than £51,327,417. Five years later, owing in great measure to the same influences as affected the trade of Australia generally, the total had fallen to £43,571,859; but for 1901 the value stood at £54,279,342, the largest amount yet recorded. In 1902, owing to causes which have already been alluded to, there was a decline to £49,518,261, but the returns for 1903 show an increase to £53,508,280. If the figures for the years 1903 and 1891 be compared for the states comprising the Commonwealth, it will be found that, there is an increase of upwards of £1,885,000 in the total value of imports, and of £14,432,000 in the exports, while the value of the total trade advanced during the period in question from £128,696,039 to £145,014,136, representing an expansion of upwards of £16,318,000.

The extent to which the geographical position of a state enables it to benefit by the production of its neighbours is illustrated by the proportion which the non-domestic bear to the total exports. The following table shows the value of the total re-export trade and the proportion which it bears to the total export trade of each state in 1903; and it would appear that South Australia, New South Wales, and Victoria, in the order named, benefit largely by their position, the re-export trade of the other states being insignificant:—

State.	Total Re-exports.	Proportion to Total Exports.
New South Wales .....	£8,072,307	30·19 per cent.
Victoria .....	5,876,440	29·82 „
Queensland .....	427,120	4·49 „
South Australia .....	3,145,516	37·25 „
Western Australia .....	131,283	1·27 „
Tasmania .....	38,728	1·36 „
Commonwealth .....	£17,691,394	22·80 „

More than one-half of this re-export trade is external, the amount for the Commonwealth states being £10,626,143, as compared with £7,065,251 of interstate trade.

#### INTERSTATE TRADE.

The trade shown in the above series of tables represents, not only the business transacted with countries outside Australasia, but the trade maintained by the states of the Commonwealth with one another. This interstate trade forms a considerable proportion of the total which has just been dealt with, and reached an amount of £59,032,501 in 1903, equal to £15 1s. 4d. per head of the population.

The following figures represent the value of the interstate trade, as well as the value per inhabitant. It is obvious that the total interstate

trade which is shown by the table represents in reality twice the actual value of goods passing from one state to another, the same merchandise figuring in one place as exports, and in another as imports. The value of goods passing through a state on their way to foreign countries, as well as of goods imported from abroad and re-exported, is, of course, also included in the figures. The actual movement is therefore less than half of the values given below :—

Year.	Total.	Value per Inhabitant of Australia.
1861.....	£14,912,688	£12 18 5
1871.....	25,431,948	15 4 10
1881.....	34,166,233	15 3 4
1891.....	57,395,687	18 0 7
1901.....	54,088,459	14 6 10
1903.....	59,032,501	15 1 4

#### TRADE OF NEW ZEALAND.

The trade of New Zealand during the years 1891 and 1903 will be found below :—

Trade with—	Imports.		Exports.		Total Trade.	
	1891.	1903.	1891.	1903.	1891.	1903.
British Empire—	£	£	£	£	£	£
Commonwealth of Australia	1,018,549	2,154,966	1,705,561	2,233,966	2,719,110	4,388,932
United Kingdom .....	4,369,633	7,512,668	7,140,831	11,345,075	11,510,464	18,857,743
India and Ceylon .....	275,248	391,529	2,551	5,083	277,799	396,612
Canadian Dominion .....	1,941	46,120	.....	2,219	1,941	48,339
Cape Colony .....	9	195	100	118,616	109	118,811
Natal .....	.....	44	.....	336,321	.....	336,365
Fiji .....	177,707	461,968	43,896	61,717	221,603	523,705
Mauritius .....	70,650	.....	4	.....	70,654	.....
Hongkong .....	21,903	19,568	7,408	57,577	29,311	77,145
Straits Settlements .....	10,655	26,964	100	663	10,155	27,617
Other Possessions .....	671	34,110	8,330	5,466	4,001	39,576
Total.....	5,941,366	10,648,142	8,908,781	14,106,683	14,846,147	24,814,823
Foreign Countries—	£	£	£	£	£	£
France .....	9,084	42,765	27,879	13,435	36,963	56,200
Germany .....	66,102	274,297	4,258	17,584	70,360	291,881
Italy .....	1,867	20,501	43	11	1,910	20,512
Belgium .....	6,591	133,140	1,658	965	8,249	134,125
Sweden and Norway .....	308	17,759	.....	414	308	18,173
United States .....	361,795	1,441,358	515,208	669,649	877,003	2,111,007
Netherlands and Java .....	2,143	19,601	.....	1,616	2,143	21,217
South Sea Islands .....	65,493	15,787	98,407	95,314	158,900	111,191
China .....	18,815	5,005	564	330	19,379	5,335
Japan .....	8,309	86,192	98	2,070	8,402	88,262
Other Countries .....	21,836	84,128	19,506	42,267	41,332	126,415
Total.....	562,483	2,140,583	662,616	843,695	1,225,099	2,984,223
Total, British and Foreign	6,503,849	12,788,675	9,566,397	15,010,378	16,070,246	27,799,053

In spite of fluctuations in individual years, trade with the United Kingdom still comprises nearly three-fifths of the total, but the greatest increase in imports has taken place in the trade with foreign countries, which practically doubled itself during the period from 1891 to 1903. Amongst the chief countries contributing to this advance were the United States, the imports from which rose from £362,000 in 1891 to £1,441,000 in 1903, and Germany, from which the imports increased from £66,000 in 1891 to £274,000 in 1903.

Under the "Preferential and Reciprocal Trade Act of 1903," certain goods imported into New Zealand, not being the produce or manufacture of some part of the British dominions, were made subject to duty or to increased rate of duty. It is further provided by this Act that from and after the 31st March, 1904, no duty shall be leviable on tea grown in any part of the British dominions, except on tea in packets not exceeding 1 lb. in weight. Of the £12,788,675 worth of imports in 1903, the value of goods subject to the preferential tariff was £1,752.

The following table shows the volume and percentage of imports into New Zealand at intervals since 1861, distinguishing the trade with United Kingdom, British possessions, and foreign countries:—

Year.	Imports from—			Total.
	United Kingdom.	British Possessions.	Foreign Countries.	
	£	£	£	£
1861 .....	1,011,640	1,428,321	55,850	2,493,811
1871 .....	1,808,636	2,112,063	157,494	4,078,193
1881 .....	4,530,316	2,489,839	436,890	7,457,045
1891 .....	4,369,633	1,571,733	562,483	6,503,849
1901 .....	6,885,831	2,913,866	2,018,218	11,817,915
1903 .....	7,512,668	3,135,474	2,140,533	12,788,675

## PERCENTAGE OF TOTAL.

1861 .....	40·6	57·2	2·2	100
1871 .....	44·3	51·8	3·9	100
1881 .....	60·8	33·4	5·8	100
1891 .....	67·2	24·2	8·6	100
1901 .....	58·3	24·6	17·1	100
1903 .....	58·7	24·5	16·8	100

As the table shows, the proportion of trade with the United Kingdom increased up to 1891, since when there has been a decline, while the imports from British possessions fell away considerably during the period. The trade with foreign countries is now proportionately about three times as large as in 1881. Of the imports from British possessions,

nearly two-thirds are furnished by the Commonwealth, the other principal contributing possessions being Fiji, Hong Kong, and India and Ceylon. The bulk of the imports from Fiji consists of sugar, and from Ceylon, tea.

A similar statement regarding the exports for the same years is given below :—

Year.	Exports to—			Total.
	United Kingdom.	British Possessions.	Foreign Countries.	
	£	£	£	£
1861 .....	506,845	843,764	19,638	1,370,247
1871 .....	2,767,831	2,364,389	149,864	5,282,084
1881 .....	4,475,801	1,116,948	458,317	6,060,866
1891 .....	7,140,831	1,762,950	662,616	9,566,397
1901 .....	9,295,375	2,907,412	678,637	12,881,424
1903 .....	11,345,075	2,821,608	843,695	15,010,378

PERCENTAGE OF TOTAL.				
1861 .....	37.0	61.6	1.4	100
1871 .....	52.4	44.8	2.8	100
1881 .....	73.9	18.4	7.7	100
1891 .....	74.7	18.4	6.9	100
1901 .....	72.2	22.5	5.3	100
1903 .....	75.6	18.8	5.6	100

The proportion of exports from New Zealand to the United Kingdom has more than doubled since 1861, while to foreign countries it increased steadily up to 1881, but thereafter declined. With British possessions the proportion has fallen off greatly since the early years, partly in consequence of the increase in trade with the United Kingdom, and also on account of the increase in the quantity of goods shipped direct to London instead of by way of Sydney and Melbourne, as was the case formerly. The Commonwealth receives about 80 per cent. of the exports to British possessions, while a fair amount of trade is carried on with Hong Kong, and, since the war, with the South African colonies.

The United States of America is New Zealand's chief customer amongst foreign countries, the most important of the commodities despatched thereto in 1903 being kauri gum, valued at £362,890, and phormium, £125,425. The so-called kauri gum is in reality a resin, being the solidified turpentine of the kauri, and occurs in a fossil condition in large quantities in the northern portion of the North Island. The great bulk is used in the manufacture of oil varnishes, but the transparent, or semi-transparent, varieties are also employed as a

substitute for amber in the manufacture of mouthpieces for pipes and cigar-holders. From the "phormium tenax," or New Zealand hemp, a superior quality of fibre is obtained.

Details of the trade of New Zealand with the principal foreign countries are given below. The first table relates to imports.

Country.	1861.	1871.	1881.	1891.	1901.	1908.
	£	£	£	£	£	£
Belgium .....	.....	.....	26	6,591	68,083	133,140
France and New Caledonia ...	71	419	19,512	9,084	27,714	42,769
Germany .....	18,486	.....	5,779	66,102	198,521	274,297
Netherlands and Java .....	4,125	.....	1,941	2,143	100,730	19,601
Italy .....	.....	.....	.....	1,867	9,211	20,501
Sweden and Norway .....	.....	.....	9	868	11,963	17,769
China .....	.....	32,838	149,228	18,815	15,324	5,005
Japan .....	.....	.....	95	8,399	45,465	86,192
South Sea Islands .....	4,227	50,147	19,515	65,493	68,733	15,783
United States .....	26,790	59,845	343,645	361,795	1,415,260	1,441,358
Other Foreign Countries .....	2,151	14,745	11,555	21,826	62,214	84,128
Total .....	55,850	157,494	551,805	562,483	2,018,218	2,140,583

The exports from New Zealand to foreign countries for similar periods were as shown below.

Country.	1861.	1871.	1881.	1891.	1901.	1908.
	£	£	£	£	£	£
Belgium .....	.....	.....	.....	1,658	14	985
France and New Caledonia ...	.....	140	54,964	27,879	1,771	15,727
Germany .....	.....	.....	.....	4,258	10,470	17,584
Netherlands and Java .....	.....	.....	.....	.....	100	1,616
Italy .....	.....	.....	.....	43	.....	11
Sweden and Norway .....	.....	.....	.....	.....	692	414
China .....	1,180	2,501	11,098	564	15,407	330
Japan .....	.....	.....	.....	93	1,640	2,070
South Sea Islands .....	4,811	41,853	31,541	93,407	109,490	98,082
United States .....	9,552	95,561	355,787	515,208	519,079	669,649
Other Foreign Countries .....	4,095	9,809	9,993	19,506	20,004	42,227
Total .....	19,638	149,964	463,873	662,616	678,637	843,695

## SUMMARY.

	£	£	£	£	£	£
Imports and Exports .....	75,488	307,358	1,014,678	1,225,099	2,696,855	2,984,228

With the exception of the United States trade, to which reference has already been made, the only other exports of importance were to the South Sea Islands, the chief articles of New Zealand produce exported thereto being meats, butter, and coal. The trade with France consisted principally of wool, the export being valued at £13,000, while kauri gum, to the value of £14,670 was exported to Germany.

The following table shows the destination and value of the chief articles of export from New Zealand for the year 1903 :—

Article.	United Kingdom.	Commonwealth of Australia.	Natal.	Cape Colony.	Hong Kong.	United States of America.
	£	£	£	£	£	£
Butter .....	1,145,236	86,298	65,977	11,988	.....	.....
Cheese .....	167,667	24,676	1,676	.....	.....	.....
Coal .....	58,011	14,750	.....	.....	45,083	.....
Fruit Pulp .....	6,183	.....	.....	.....	.....	.....
Fungus .....	.....	.....	.....	.....	7,706	.....
Gold .....	983,763	1,104,812	.....	.....	.....	.....
Grain and Pulse—Barley .....	5,408	20,927	.....	.....	.....	.....
"    Peas and Beans .....	27,531	6,973	.....	.....	.....	.....
"    Oats .....	138,964	205,895	78,774	33,135	.....	.....
Gum, Kauri .....	238,083	13,643	.....	.....	.....	362,690
Hides .....	632	53,789	.....	.....	.....	795
Leather .....	90,576	2,828	.....	.....	.....	.....
Linseed .....	3,948	.....	.....	.....	.....	.....
Meat—Frozen Beef .....	199,183	10,972	47,572	13,089	.....	.....
"    Kidneys .....	12,934	.....	.....	.....	.....	.....
"    Lamb .....	1,120,716	.....	2,396	1,554	.....	.....
"    Mutton (Carcase) .....	1,447,436	6,018	96,941	43,348	.....	.....
"    "    (Joints) .....	69,083	.....	.....	.....	.....	.....
"    Rabbits .....	99,525	.....	.....	.....	.....	.....
"    Preserved, &c. ....	46,864	23,588	2,840	887	.....	.....
Phormium .....	395,519	71,073	.....	.....	.....	125,425
Sausage Skins .....	25,213	.....	.....	.....	.....	37,499
Seeds—Grass and Clover .....	58,469	31,577	.....	.....	.....	12,434
Silver .....	75,275	16,210	.....	.....	.....	.....
Skins—Rabbit .....	37,500	.....	.....	.....	.....	.....
"    Sheep, with Wool .....	98,286	11,133	.....	.....	.....	86,044
"    "    without Wool .....	264,350	11,523	.....	.....	.....	.....
Tallow .....	448,851	15,260	.....	.....	.....	.....
"    Oleomargarine .....	51,256	.....	.....	.....	.....	.....
Timber .....	25,080	204,401	.....	.....	.....	.....
Twine—Reaper and Binder .....	.....	19,522	.....	.....	.....	11,911
Wool .....	3,998,569	6,806	.....	.....	.....	22,390



## EXPORTS OF DOMESTIC PRODUCE.

The values of the exports of Australasia and of its various provinces have been given in the previous pages without respect to the states where the articles were produced. It is important to ascertain to what extent the exports have been the produce of each of the states whence they were shipped. The following table shows the value of the exports of domestic produce of each state as returned by the Customs for the years 1891, 1901, and 1903, and the value thereof per inhabitant :—

State.	Total Value.			Value per Inhabitant.		
	1891.	1901.	1903.	1891.	1901.	1903.
	£	£	£	£ s. d.	£ s. d.	£ s. d.
New South Wales .....	21,065,712	19,915,684	18,665,804	18 8 9	14 10 3	13 2 4
Victoria .....	13,098,496	14,134,023	13,330,630	11 7 6	11 14 11	11 8 6
Queensland .....	7,979,080	9,009,696	9,087,854	19 17 4	17 17 3	17 10 8
South Australia .....	4,810,512	4,392,364	5,297,727	14 17 10	12 1 11	14 8 7
Western Australia .....	788,873	3,216,718	10,193,449	15 9 7	43 16 4	46 5 8
Tasmania .....	1,867,927	2,933,373	2,804,380	9 3 8	16 18 0	15 14 3
Total .....	49,058,690	53,603,668	59,879,844	15 16 1	15 8 2	15 5 3
New Zealand .....	9,400,094	12,690,460	14,328,192	14 18 6	16 5 9	18 1 9
Australasia .....	58,458,624	71,293,028	74,718,036	15 4 4	15 11 1	15 15 5

The figures for 1891, must be regarded as approximate, as it is difficult to ascertain with exactitude the domestic exports of some of the states in the earlier years.

As the table shows, the largest values per inhabitant were returned by Western Australia and Queensland, with £46 5s. 8d. and £17 10s. 8d. respectively per head of population. The growth of the domestic exports of Western Australia has been extremely rapid, the total value rising from £1,273,638 at the end of 1895 to £10,193,449 for the year 1903, an increase of over 700 per cent. Of course, this great expansion is in the main due to the export of gold, the value of the total export of the precious metal being returned at £4,061,767 in 1903 as

against £879,748 in 1895. None of the other states, with the exception of South Australia, shows any improvement on the returns of the previous year, but now that an era of good seasons has apparently set in, a great increase in the export of articles of domestic produce may be confidently anticipated.

#### THE WOOL TRADE.

The following table shows the destination and value of the wool exported by the Commonwealth to countries outside Australia, with the proportion of the total amount taken by each during the period 1881-1903:—

Country.	Value.				Proportion.			
	1881.	1891.	1901.	1903.	1881.	1891.	1901.	1903.
	£	£	£	£	per cent	per cent	per cent	per cent
United Kingdom.....	12,819,808	15,769,976	9,797,001	7,806,423	97·3	79·2	53·4	52·6
Belgium .....	96,557	1,452,097	1,146,349	1,044,297	0·7	7·3	6·9	7·5
Germany .....	53,809	782,676	1,852,053	2,342,619	0·4	3·9	11·0	16·7
France .....	26,965	1,386,768	2,003,197	2,676,582	0·2	7·0	12·0	19·1
United States .....	127,138	514,243	273,933	338,274	1·0	2·5	1·6	2·3
Other Countries....	48,725	17,273	1,689,188	183,404	0·4	0·1	10·1	1·3
Total .....	13,178,062	19,923,033	16,761,721	14,001,599	100·0	100·0	100·0	100·0

The total under the heading of "Other Countries" includes for 1901 wool to the value of £90,177 sent to Italy, and £49,318 taken by Japan, and for 1903, £92,377 worth despatched to Italy, and £71,582 to Japan.

The table shows that, while the trade increased considerably during the period from 1881 to 1891, since the latter year there has been a heavy decline, the value of the external export in 1903 being only about £828,000 in excess of that of 1881. The decrease is accounted for by the series of unfavourable seasons experienced since 1891. In 1891, the sheep depastured in the Commonwealth numbered 106,420,000, but at the end of 1903, the total had fallen to 55,371,000; a decrease of 51,000,000. It will be observed that since 1881 the wool exported to the United Kingdom has decreased in value to the extent of £5,453,000, or from 97·3 to 52·6 per cent. France and Germany both show proportionate increases throughout the whole period, the proportion for France rising from 0·2 per cent. in 1881 to 19·1 per cent. in 1903, while the percentage for Germany rose from 0·4 per cent. in 1881 to 16·7 per cent. in 1903.

The export of wool from New Zealand for similar periods to those shown in the preceding table is given below :—

Country.	Value of Wool Exports to—			
	1881.	1891.	1901.	1903.
	£	£	£	£
United Kingdom .....	2,900,288	4,121,238	3,700,870	4,001,518
Belgium .....	.....	1,658	.....	.....
France .....	.....	.....	.....	13,189
United States .....	5,561	308	.....	22,330
Other Countries .....	8,197	6,482	6,516	7,186
	2,914,046	4,129,686	3,707,386	4,044,223

As the table shows practically the whole export is consigned to the United Kingdom, although a small trade was done with France and the United States in 1903. The figures given under the heading of "Other Countries" comprise chiefly exports to the Commonwealth States.

It is necessary to point out here that all the figures in the present chapter dealing with the export of wool are based on the Customs returns of the different states, and represent the values placed on the wool by the exporters. The figures relating to the value of the wool clip which are given in the chapter on the pastoral industry are less than those just given, the difference being made up in the cost of carriage and other charges from the sheep-runs to the ship's side.

The following table shows the total and proportionate value of the external shipments of wool from the Commonwealth States and New Zealand, for the years 1881, 1891, and 1903 :—

State.	Value.			Proportion.		
	1881.	1891.	1903.	1881.	1891.	1903.
	£	£	£	per cent	per cent	per cent
New South Wales..	4,485,295	7,917,598	7,785,997	27·9	32·9	43·2
Victoria..	5,327,971	7,070,661	3,147,829	33·1	29·4	17·4
Queensland .....	996,047	2,438,321	1,246,295	6·2	10·1	6·9
South Australia ...	1,747,696	1,888,107	1,258,782	10·9	7·8	7·0
Western Australia.	199,481	294,924	434,653	1·2	1·3	2·4
Tasmania ..	416,572	313,422	128,043	2·6	1·3	0·7
Commonwealth	13,173,062	19,923,033	14,001,599	81·9	82·8	77·6
New Zealand .....	2,914,046	4,129,686	4,044,223	18·1	17·2	22·4
Australasia ...	16,087,108	24,052,719	18,045,822	100·0	100·0	100·0

It will be seen from the table just given that Victoria was credited in 1881 with exporting wool to a considerable value in excess of that of New South Wales. In 1891 and 1903, however, the positions were reversed. The change is mainly due to the extension of railways, especially noticeable in New South Wales, where some lines are expressly designed to bring trade to Sydney.

In connection with this subject, a statement of the value of wool of its own production which each state exports direct and by way of the other states may not be without interest. The figures, which are given below, relate to the year 1903 :—

State.	Domestic Wool Exported.			Proportion of Export of Australasia.
	Direct.	By way of the other states.	Total.	
	£	£	£	per cent.
New South Wales .....	7,276,283	1,267,852	8,544,135	46·8
Victoria .....	1,818,102	30,823	1,848,925	10·1
Queensland .....	1,246,295	621,379	1,867,674	10·2
South Australia .....	1,172,536	154,154	1,326,690	7·3
Western Australia .....	434,653	9,090	443,743	2·4
Tasmania .....	128,043	46,046	174,089	1·0
New Zealand .....	4,034,468	*6,806	4,041,274	22·2
Australasia .....	16,110,380	2,136,150	18,246,530	100·0

\* Exports to Commonwealth States.

In the table given on the preceding page the value of the external export of wool is quoted at £18,045,822. The apparent discrepancy, however, is of no moment when it is remembered that about one-fifth of the clip of Australasia is subject to valuation first at the border of the state in which it is produced, and again at the port from which it is finally shipped to Europe or America. In the amount of £18,246,530 shown above is, besides, included the value of such wool as was exported during 1903 to one of the adjacent states, and there held over for the sales in January of the following year.

The following figures serve to illustrate the development of the local wool sales in those states where such sales are held, for the ten seasons from 1894-95 to 1903-1904. The seasons are taken as extending from

the 1st July to the 30th June. The number of bales sold during each period shown was as follows:—

Season.	New South Wales.	Victoria.	Queensland.	South Australia.	Tasmania.	New Zealand.	Total.
	bales.	bales.	bales.	bales.	bales.	bales.	bales.
1894-95 ...	425,135	328,142	.....	64,056	.....	82,547	899,880
1895-96 ..	415,538	315,543	.....	80,234	.....	82,965	894,280
1896-97 ...	401,048	310,835	.....	63,804	.....	82,515	858,202
1897-98 ...	444,808	296,625	.....	51,287	.....	100,514	883,234
1898-99 ...	447,517	278,482	10,925	60,531	.....	90,806	888,261
1899-1900	399,893	312,571	27,015	70,717	.....	108,846	919,042
1900-1901	388,946	273,641	13,453	42,637	.....	90,235	808,912
1901-1902	522,003	321,482	25,936	65,239	.....	100,860	1,035,520
1902-1903	383,506	270,107	14,754	60,782	.....	115,553	844,702
1903-1904	375,801	249,583	21,697	58,509	14,943	102,910	823,443

The importance of the pastoral industry to Australasia will be made clear in another part of this volume. Its value to each state varies considerably, as the statement of the exports of pastoral produce in the next table will show. In no state, however, Western Australia and Tasmania excepted, does the proportion of exports of this class fall below one-fourth of the total value of domestic produce exported. In the case of New South Wales it reaches 59 per cent., while in New Zealand it is 58 per cent., and in Queensland 48 per cent.

State.	Wool.	Other Pastoral Products.	Total.	Proportion of Exports of Pastoral Produce to Total Exports of Domestic Products.
	£	£	£	per cent.
New South Wales .....	8,544,135	2,512,576	11,056,711	59·2
Victoria .....	1,848,925	2,557,509	4,406,434	29·2
Queensland .....	1,867,674	2,474,061	4,341,735	47·7
South Australia .....	1,326,690	923,512	2,250,202	42·5
Western Australia .....	443,743	180,546	624,289	6·1
Tasmania .....	174,089	169,721	343,810	12·3
New Zealand .....	4,041,274	4,602,372	8,643,646	58·3
<b>Australasia—</b>				
All Domestic .....	18,246,530	13,420,297	31,666,827	41·0
External Domestic.	16,117,186	8,560,653	24,677,839	47·1

The proportion for Australasia, 41 per cent., is below the records of some of the earlier years, owing to the smaller exportable surplus of pastoral products occasioned by the unfavourable season.

## MOVEMENT OF GOLD.

The statement below shows the movement of gold during 1903 among the various states of the Commonwealth and New Zealand. Western Australia, Victoria, Queensland, and New Zealand are the largest exporters, these provinces producing the largest quantities of the precious metal.

State.	Import.		Export.		Net Export.	
	Interstate.	Oversea.	Interstate.	Oversea.	Interstate.	Oversea.
	£	£	£	£	£	£
New South Wales .....	3,519,335	528,975	153,056	4,773,207	*3,366,279	4,244,232
Victoria .....	393,391	674,412	693,024	4,727,950	299,633	4,063,538
Queensland .....	102,407	31,547	2,188,346	862,499	2,085,939	830,952
South Australia .....	295,336	10	183,625	128,941	*111,711	123,981
Western Australia .....	.....	.....	697,424	7,920,535	697,424	7,920,535
Tasmania .....	31,125	.....	129,480	.....	98,305	.....
Commonwealth .....	4,341,594	1,234,944	4,044,906	18,413,132	*296,689	17,178,188
New Zealand .....	.....	613,270	.....	2,074,460	.....	1,461,190

\* Net Import.

In the above table the movements between Australia and New Zealand are included in the "oversea" columns. New South Wales and Victoria were the largest importers of gold, both of these states receiving gold from New Zealand and Tasmania for purposes of coinage. New South Wales also received gold from Queensland for the same purpose. The imports from countries outside Australia came from New Guinea and New Zealand, the net import from each place being respectively £60,911 and £660,261. The countries beyond the Commonwealth to which gold was sent in large quantities, both in 1903, as well as in preceding years, were the United Kingdom, United States of America, Cape Colony, Natal, India, and Ceylon. Since 1899 the four last-mentioned countries have received between 4 and 5 millions per annum. In 1903 the net export to the United Kingdom was £5,672,038, to India and Ceylon £8,668,073, to Cape Colony and Natal £1,600,000, and to the United States £1,500,020. The imports into New Zealand consisted almost entirely of gold of its own production, received back from New South Wales and Victoria in the shape of specie. Of the exports, £1,104,293 were sent to New South Wales and Victoria, £933,763 to the United Kingdom, and £30,000 to the Argentine Republic.

It may not be out of place to give the net export of gold from each state since 1851, the year when gold was discovered in Australia, to

the present date. As shown in the following statement the total amounted to over 372 millions :—

State.	Net Export of Gold. 1851-1903. £
New South Wales .....	36,208,263
Victoria .....	241,587,034
Queensland .....	51,939,554
South Australia .....	1,136,787
Western Australia .....	37,467,224
Tasmania .....	3,701,857
Commonwealth ..	£372,040,719 .
New Zealand .....	£56,024,723

#### IMPORTS OF FREE AND DUTIABLE GOODS.

The imports for home consumption of dutiable goods of British and foreign origin, into the Commonwealth during 1903, amounted to £26,600,995. There were in addition free goods to the value of £10,357,632, making the total value of goods entered for home consumption £36,958,627. Dividing dutiable goods into stimulants, narcotics, and other, and comparing the values with the duties collected the following results are obtained :—

Description of Goods.	Imports for Home Consumption.	Duty Collected.	Average rate of duty.
	£	£	per cent.
Stimulants .....	1,368,307	2,068,407	151·17
Narcotics .....	632,768	952,513	150·53
Other dutiable goods .....	24,599,920	4,699,223	19·10
Free Goods .....	10,357,632	.....	.....

This statement shows that the average rate of duty on dutiable goods other than stimulants and narcotics was equivalent to an *ad valorem* rate of 19·1 per cent. Excluding as before, stimulants and narcotics, the average rate of duty on all goods, free and dutiable, was 13·4 per cent., and the proportion of free goods entered for consumption was 29·6 per cent. In 1902 the average rate of duty on dutiable goods was 19·7 per cent., and on all goods 13·5 per cent., while the proportion of free goods imported was 31·7 per cent.

It would be interesting to compare the amounts of oversea goods entered for home consumption into each state, but at present the

records will not permit of this, for although the amount on which duty is collected is given, the value of the goods on which interstate adjustments are made, and which has to be added to or subtracted from that amount, is not given; so that as regards New South Wales and Victoria the figures for home consumption are in excess of the truth, while in the other states the opposite is the case.

Comparing the Commonwealth tariff with that existing in the states in 1900, the year prior to the inauguration of the Commonwealth, it will be found that the proportion of goods on the free list was higher in all the states except Tasmania. On the other hand, all the states, with the exception of New South Wales and Western Australia, averaged a higher rate of duty. The following statement shows the averages for the year 1900 for each of the six states. Stimulants and narcotics are excluded :—

State.	Free List — Proportion of Goods on.	Average Rate of Duty, <i>ad valorem</i> .	
		On Dutiable Goods, Merchandise.	On all Merchandise other than Narcotics and Stimulants.
	per cent.	per cent.	per cent.
New South Wales . . . . .	87·6	10·3	1·3
Victoria . . . . .	53·4	36·2	17·0
Queensland . . . . .	36·0	20·5	13·1
South Australia . . . . .	35·7	21·8	14·0
Western Australia . . . . .	37·1	14·8	9·3
Tasmania . . . . .	9·0	24·2	22·0

It is difficult at the present time to determine, with any degree of definiteness, the effect which the tariff has had or is likely to have on the trade of the Commonwealth, but a measure of that effect may be obtained by comparing the volume of the trade before the imposition of uniform duties and subsequent thereto. The period shown in the following table is five years; but of these five years only the last two, 1902 and 1903, represent a full year under the Commonwealth tariff; 1901 was partly under Commonwealth tariff, partly under state tariffs. The preceding years were wholly under the state tariffs. It is also to be borne in mind that there was considerable loading-up of goods in anticipation of the imposition of the federal tariff in New South Wales, and, to a less extent, in Victoria, the existence of a free list of 87·6 per cent. in the one case, and 53·4 per cent. in the other holding out an irresistible temptation to pursue such a course.



The following table shows for each of the five years 1899 to 1903 the net import of British and Foreign produce into the Commonwealth.

Year.	Import as recorded.	Value of Goods transhipped.	Gross Import.	Re-export.	Net Import.
	£	£	£	£	£
1899	34,329,687	1,773,933	36,103,520	2,033,021	34,070,499
1900	41,388,030	2,069,400	43,457,430	2,268,655	41,168,775
1901	42,433,811	2,121,500	44,555,311	1,954,396	42,600,915
1902	40,675,950	1,546,924	42,222,874	2,646,306	39,576,568
1903	37,811,471	1,024,211	38,835,682	2,591,229	36,244,453

It will be observed that the third column gives the value of goods transhipped. These are the goods previously referred to on page 228, and the values given are those which it is estimated should be added to the imports recorded as coming from countries outside Australia, in order to arrive at the true gross import of oversea goods.

#### CUSTOMS AND EXCISE REVENUE.

The revenue received from Customs and Excise, the cost of collecting the duties, and the proportion which such cost bears to the total revenue received in each of the states during the last seven years are shown in the tables below. In the first table will be found the revenue from duties since 1898.

Year.	New South Wales.	Victoria.	Queens- land.	South Australia.	Western Australia.	†Tas- mania.	Common- wealth.
1898-9	1,608,859	2,234,442	1,504,968	629,229	867,520	427,963	7,272,981
1899-1900	1,736,377	2,267,131	1,602,985	645,074	933,717	448,120	7,633,404
*1900	939,336	1,202,191	787,695	337,371	500,845	490,916	4,258,354
†1901	1,019,008	1,356,099	710,830	351,953	491,371	†221,328	4,150,589
1901-2	2,812,731	2,376,525	1,297,662	698,647	1,335,614	373,140	8,894,319
1902-3	3,478,742	2,499,014	1,261,066	689,727	1,395,997	360,607	9,685,153
1903-4	3,229,786	2,443,505	1,131,761	699,792	1,258,725	342,189	9,105,758

\*Half year ended 31st December, except Tasmania.  
ended 31st December previous.

† Half year ended 30th June.  
|| Year ended 30th June.

‡ Year

In the next table will be found the cost of collecting the Customs and Excise duties during each year of the period, together with the proportion which such cost bears to the total receipts in each state and in the Commonwealth.

Year.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	†Tasmania.	Commonwealth.
1898-9	53,774	66,290	58,104	26,418	29,734	8,423	242,743
1899-1900	54,241	68,782	59,608	26,712	28,765	8,851	246,969
*1900	26,995	35,147	31,814	15,277	17,261	9,732	136,226
†1901	29,318	32,915	28,056	11,742	15,377	†4,898	122,306
1901-2	65,318	65,454	64,911	27,012	32,256	10,564	265,515
1902-3	73,324	67,175	67,284	26,583	35,201	11,019	280,586
1903-4	72,351	69,414	58,330	25,909	36,996	10,300	273,300

PERCENTAGE OF COST OF COLLECTION TO TOTAL RECEIPTS.

1898-9	3·3	3·0	3·8	4·2	3·4	2·0	3·3
1899-1900	3·1	3·0	3·7	4·1	3·1	2·0	3·2
*1900	2·9	2·9	4·0	4·5	3·4	2·0	3·2
†1901	2·9	2·4	3·9	3·3	3·1	†2·2	2·9
1901-2	2·3	2·8	5·0	3·9	2·4	2·8	3·0
1902-3	2·1	2·7	5·3	3·9	2·5	3·0	2·9
1903-4	2·2	2·8	5·2	3·7	2·9	3·0	3·0

\* Half year ended 31st December, except Tasmania.  
ended 31st December previous.

† Half year ended 30th June.  
|| Year ended 30th June.

Year

From the above statement it is apparent that under federal administration the cost of collection of the duties has greatly declined in the Commonwealth as a whole and in the various states, with the exception of Queensland and Tasmania. The greatest proportional decrease has taken place in New South Wales, the percentage falling from 3·3 in 1898-9 to 2·2 in 1903-4. The total collections in that state for the year first mentioned amounted to £1,608,859, the cost of collection being £53,774, while for 1903-4 the corresponding figures were £3,229,786 and £72,351. In other words an additional revenue of £1,620,927 was collected at an expense of £18,577, or a little over 1 per cent.

## LAND AND SETTLEMENT.

**I**N each of the Commonwealth States and New Zealand a different system has been adopted to secure the settlement of an industrial population upon the Crown lands, the conditions upon which land may be acquired being of a more or less liberal nature according to the circumstances in which the province has found itself placed. The legislation of Victoria, Queensland, and Tasmania, which at one time formed part of New South Wales, bears a strong resemblance to that of the mother state, practically the same form of conditional occupation with deferred payments being in existence in all four states. In the other provinces, however, the influence of New South Wales was not so directly felt, and new experiments were made. South Australia, for instance, was originally settled upon the Wakefield system—alike remarkable for its originality and its failure. In Western Australia and New Zealand, under pressure of a different set of circumstances, settlement was effected by legislation of a novel character. An attempt is made here to give a description of the Land Laws of Australasia, although the radical changes which are constantly being made render the task of giving a serviceable account of the various systems a somewhat difficult one. During the past ten years, numerous Acts affecting State lands have been placed on the statute book, so that it is impossible to say how long the information given in this chapter can be taken as representing the latest phases of land legislation in Australasia.

### NEW SOUTH WALES.

With the progress and development of the state, the Land Laws of New South Wales have naturally undergone considerable alteration. In the earliest period alienation was effected by grants, orders, and dedications, the power of disposal resting solely with the Governor. In August, 1831, the principle of sale by auction was introduced, the minimum price for country lands being fixed at 5s. per acre. This was raised to 12s. in 1839, and to 20s. in 1843, power being given in the latter year to select, at the upset price, country portions for which a bid was not forthcoming at auction, or upon which the deposit paid at the time of sale had been forfeited. This was the first appearance of the principle of selection in the laws of the state, but it was limited to lands which had been surveyed for sale by auction.

The discovery of gold in 1851, and the consequent rush of population to Australia, greatly altered the conditions of colonisation. As the

interest in gold-digging declined, so did the desire for settlement on the land increase, and the question had to be dealt with in an entirely new spirit, to meet the wants of the class of immigrants desirous of being placed upon the soil. The agitation which thus sprang up resulted in the passing of the Crown Lands Act of 1861, under the leadership of Sir John Robertson. This measure was designed to secure the establishment of an agricultural population side by side with the pastoral tenants. With this object in view an entirely new principle was introduced—that of free selection in limited areas before survey, coupled with conditions of residence and improvement—and country lands were sold at 20s. per acre, payable by annual instalments carrying interest.

The occupation of waste lands for pastoral purposes was at first allowed under a system of yearly licenses. Any person could apply for such a license, the extent of the run which it was desired to occupy being limited only by the boundaries of the surrounding stations. The fee was fixed at £10 per annum for a section of 25 square miles, with £2 10s. for every additional 5 square miles. This system of yearly licenses was succeeded by one under which the squatter was given fixity of tenure, the fee payable being calculated upon the stock-carrying capacity instead of upon the area of the run. Still another system was inaugurated by the Occupation Act of 1861, the period of tenure being limited to five years in all but first-class settled districts, and the whole of the pastoral leases left open to the operations of the free selectors. But such evils were found to result from this system that in 1884, in 1889, in 1895, in 1901, so far as the western division is concerned, and again in 1903, so far as the eastern and central divisions are concerned, Parliament was led to adopt amendments which are now in force, and which, while maintaining the principle of selection before survey, aim at giving fixity of tenure to the pastoral lessee and obtaining a larger rental from the public lands, while at the same time securing land to *bond-fide* settlers on terms and conditions within the reach of all.

For the purposes of land administration, the state is split up into three divisions, each of which is subdivided into land districts. In the eastern and central divisions one or more of these land districts form a local division, the administration of which is entrusted to a Local Land Board, comprising a chairman and not more than two assessors, the control of the western division being vested in the Western Land Board. The decisions of these Local Land Boards may be appealed against to the Land Appeal Court. This Court is composed of a President and two members appointed by the Executive, and its decisions in matters of administration have the force of judgments of the Supreme Court; but whenever questions of law become involved, a case may be submitted to the Supreme Court, upon the written request of the parties interested, or by the Land Appeal Court of its own initiative. The judgment given in this appeal is final.

Under the Acts at present in force, land may be acquired by the following methods :—(1) By conditional and additional conditional purchase with residence ; (2) by conditional purchase without residence ; (3) by classified conditional purchase ; (4) by the preferent right of purchase attached to conditional leases ; (5) by improvement purchases on gold-fields ; (6) by auction sales ; (7) by after auction sales ; (8) by special sales without competition ; (9) by way of exchange ; (10) by virtue of volunteer land orders ; and (11) by homestead selection.

Crown lands may also be let under the following systems, viz. :—Annual lease ; conditional lease ; lease as inferior lands ; occupation license ; pastoral lease ; scrub lease ; special lease ; residential lease on gold and mineral fields ; improvement lease ; settlement lease ; snow lands lease ; and working men's blocks.

The maximum area which may be conditionally purchased differs in the eastern and central divisions. In the western division land can only be occupied under lease, or alienated by auction.

#### *Conditional Purchases.*

Any vacant Crown lands in the eastern and central divisions of the state are available for conditional purchase, but only those specially set apart by proclamation in the *Government Gazette* under the definition of special areas are open in the western division. The fact that lands are held under annual lease or occupation license does not disqualify them from conditional purchase, but lands held under any other tenure may not be so acquired. Land under conditional lease in any division may be conditionally purchased, but only by the leaseholder. Lands within suburban boundaries or within population areas may be proclaimed as special areas, and are open to conditional purchase under the special conditions prescribed. The existence of improvements does not constitute a bar to conditional purchase, but the applicant is required to pay for them. Where such improvements are the property of the Crown, their value is determined by the Land Board, which also fixes the period within which they are to be paid for. Where the improvements are not Crown property, the parties make their own arrangements.

Any person of or over the age of 16 years, other than a married woman who has not been judicially separated from and is living apart from her husband, may take up a residential conditional purchase, but no one under the age of 21 years can select a non-residential conditional purchase. It is specially enacted that every conditional purchase must be made solely in the interest of the applicant, and any agreement to the contrary is void. Minors who become conditional purchasers have, in connection with their land, the rights and liabilities of persons of full age.

The area which may be selected depends on the division in which the land is situated, and whether it is taken up under residential or

non-residential conditions, or falls within a special area. The minimum and maximum areas allowed are as follows :—

Class.	Division.	Minimum Area.	Maximum Area.
		Acres.	Acres.
Residential .....	Eastern.....	40	640
" .....	Central.....	40	2,560
Non-residential .....	Eastern.....	40	320
" .....	Central.....	40	320
Special area.....	Eastern.....	....	320
" .....	Central.....	....	640
" .....	Western .....	....	640

With regard to special areas, both the minimum and maximum areas are subject to proclamation in the *Government Gazette*, and are therefore liable to limitation according to the circumstances of each case. It is open to any conditional purchaser to take up the maximum area at once, or by a series of purchases, at such intervals as may suit his convenience. With the exception of non-residential purchases, provision is made in the Crown Lands Amendment Act of 1903, that the maximum areas specified may be exceeded by allowing an applicant to acquire additional holdings, the area of which, together with all other lands held by the applicant other than under annual tenure, must not exceed such an area as, in the opinion of the Land Board, is sufficient for the maintenance of his home thereon in average seasons and circumstances. The additional holdings need not necessarily adjoin the original holding, but must, in the opinion of the Land Board, be situated within a reasonable working distance thereof.

An application for a conditional purchase must be accompanied by a declaration containing replies to questions—the object of which is to prove that the applicant is legally competent to apply—and must be lodged with the Crown Lands Agent of the district in which the land is situated, and a deposit and survey fee paid at the same time. The deposit is 2s. per acre on residential purchases, and 4s. per acre on non-residential purchases of ordinary land, while on special areas, and on lands within classified areas, it varies according to the prices fixed for the land. Under ordinary conditions the balance of purchase money, with interest at 4 per cent. per annum, is cleared off by thirty annual payments of 1s. per acre. The first instalment is not due until the expiration of three years from the date on which the land was applied for. In the case, however, of holdings brought under the Conditional Purchasers' Relief Act of 1896, the instalments may be reduced to 9d. per acre, and in some instances to 6d. per acre, thus extending the total period of repayment to 66 years, provided the holders of the conditional purchasers are and continue in residence. By the Crown Lands Act Amendment Act, of 1903, the rate of interest on the balance of

purchase money has been reduced to 2½ per cent. per annum for any conditional purchase applied for after the passing of that Act, and it is also provided that the same rate of interest may, in certain cases, be payable in respect of conditional purchases applied for before the passing of that Act.

The original conditional purchase must be resided upon continuously by the selector for a period of ten years, calculated from the date of application. Residence must be commenced within three months after the application has been confirmed by the Land Board, who may grant leave of absence for a period in special circumstances, such as sickness, drought, &c. Each additional conditional purchase or conditional lease is subject to the condition of residence indicated. The place of residence, may, however, be on any block of the series, so that no necessity exists for a change of residence, and the term may be reduced by the applicant's previous residence on the series, up to, but not exceeding five years.

The selector is required to enclose his land within three years after confirmation, with such a fence as the Land Board may prescribe; but he may, at his own option, substitute improvements in lieu of fencing. In such a case, permanent, fixed, and substantial improvements, of the value of 6s. per acre, but not exceeding £384, are required within three years from date of confirmation, and these improvements must be brought up to the value of 10s. per acre, but not exceeding £640, within five years from the date of confirmation. In the case of non-residential purchases the land must be fenced within one year after date of confirmation, and within five years from that date other improvements to the value of £1 per acre must be effected.

Any conditional purchases, or conditional leases of the same series, may be converted into a homestead selection, provided the holder has been in *bond fide* residence for at least six months, and in such case all moneys paid as interest or rent shall be taken as having been paid for the use of the land, and all moneys paid off the purchase money may be credited towards future rent of the selection.

#### *Auction Sales.*

Crown lands are submitted to auction under ordinary or deferred payment systems. Under the ordinary system the balance of purchase money is payable, without interest, within three months of the day of sale, while, under the deferred payment system, the balance is payable by instalments, with 5 per cent. interest, distributed over a longer period, but which cannot exceed five years. In either case 25 per cent. of the purchase money must be deposited at the time of sale. The only lands that may be sold under the deferred payment system are town and suburban lands, and country lands of a less area than 40 acres. Auction sales to the extent of not more than 200,000 acres in any one year, are permitted. The upset price is fixed by the Minister for Lands.

Town lands cannot be sold in blocks exceeding half-an-acre, or at a lower upset price than £8 per acre; suburban lands that may be offered at auction must not exceed 20 acres in one block, and the minimum upset price is £2 10s. per acre, and country lands may be submitted in areas not exceeding 640 acres at an upset price of not less than 15s. per acre. The value of improvements on the land may be added to the upset price. Town and suburban lands, and lands within population areas, or any portion of country lands of a less area than 40 acres, which have been offered at auction and not bid for, may be sold, subject to the Minister's approval, to any applicant at the upset price, and on the same terms and conditions as those under which the land was offered at the auction sale.

#### *Improvement Purchases.*

The holder of a miner's right or business license under the provisions of the Mining Act, which confers the right to occupy a small area within a gold field, is authorised under the Land Acts to purchase the lands so occupied, provided he has made certain improvements thereon. These improvements must include a residence or place of business, and be of the value of £8 per acre on town land, and £2 10s. on any other land. Not more than a quarter of an acre of town land, and not more than one acre of other land can be purchased, and a distance of three miles must separate any two or more portions purchased by the same applicant.

#### *Special Purchases.*

Any unnecessary road which bounds or intersects freehold land, may be closed and sold to the freeholder, and any unnecessary road which passes through land held under conditional purchase may be closed and added to the area of the same. In the former case the land is alienated in fee, at a price determined by the Land Board, while in the case of a conditional purchase the price is similarly determined and added to the balance owing on the conditional purchase, the conditional purchaser being required to pay deposit and instalment of purchase money at the same rate as for his original area.

Many crown grants of land having water frontage contain a reservation, usually of 100 feet from high water mark, and the title of the land so reserved is regarded as remaining in the Crown. It is, however, competent for the Crown to rescind the reservation, and convey the land to the holder of the adjoining land, and in such a case the price of the land is determined by the Land Board.

The owner in fee simple of land having frontage to the sea, or to any tidal water or lake, who desires to reclaim and purchase any adjoining land lying beyond or below high water mark, may, after depositing £10 in the Treasury, apply to the Under Secretary for Lands to do so, except in the case of Port Jackson, the control of which is vested in the Sydney Harbour Trust Commissioners. No reclamation is authorised which may



interrupt or interfere with navigation, and any approved reclamation must be completed to the satisfaction of the Minister, if the land is in the Metropolitan Land District, or to the satisfaction of the Land Board if situated elsewhere. The price to be paid for the land is appraised by the Land Board, on the basis of the enhanced value of the whole holding by reason of the land to be reclaimed having been reclaimed, and being held and enjoyed with the land in fee simple after allowing for cost of reclamation.

Land encroached upon by buildings erected on granted land, or land situated between granted land and a street or road, which forms, or should form, the way of approach to the granted land, or land to which no way of access is attainable, or land which is insufficient in area for conditional purchase, may, subject to the approval of the Land Board, be purchased by the owner in fee simple of the adjoining land, at a price determined by the Board.

#### *Volunteer Land Orders.*

Holders of certificates issued to such volunteers as had served efficiently for a certain period under the provisions of the Volunteer Force Regulation Act of 1867 are entitled to a free grant of 50 acres of land. These certificates, a few of which are still outstanding, entitle the holder to 50 acres of such land as may be open to conditional purchase, other than lands within a proclaimed special area.

#### *Homestead Selection.*

Among the special features of the Act of 1895 was the introduction of the principle of classification and measurement of lands prior to selection. Under this system suitable land is set apart and rendered available for the purposes of the selector. The appropriation of areas for homestead selection is a prominent feature of the Act, and the lands chosen for subdivision are good agricultural lands, which are measured into blocks, each large enough for one family. Where suitable lands are situated within easy access of towns, small blocks are set apart to suit the requirements of business people. The land becomes available for application after particulars relating to area, capital value, &c., are published in the *Gazette*, and the application must be made to the Crown Lands Agent of the district in which the land is situated. The maximum area that may be selected is 1,280 acres; but the selector is limited to a block as gazetted, which may be less than the maximum area. The tenure is freehold, subject to perpetual residence and perpetual rent. The selector is required to deposit one half year's rent and one-third of the survey fee with his application, the payment of the balance of the latter being spread over a period of two years. The rent until the issue of the grant, which cannot be issued for five years, or until the expiration of the first six years of the selection, if the grant is not previously issued, is  $1\frac{1}{2}$  per cent. of the capital value of the land, which capital value is determined according to the character and situation of

the land and the tenure of the holding. The gazetted capital value of the land may be subject to appraisal by the Land Board at the instance of the selector. The Crown Lands Act Amendment Act of 1903 provides that an additional holding may be acquired to make up an area which, with all other lands held by the applicant other than under annual tenure, would not be more than sufficient for the maintenance of the applicant's home in average seasons and circumstances. The additional holding need not necessarily adjoin the original holding, but must, in the opinion of the Land Board, be situated within a reasonable working distance thereof. Any person who is eligible to take up a conditional purchase may apply for a homestead selection. Any improvements on the land are appraised by the Land Board at their value to the incoming tenant, such value in no case to exceed the cost of making those improvements. Should the appraised value exceed by 20 per cent. the Board's estimated value as notified in the *Gazette*, the applicant is at liberty to withdraw his application and obtain a refund of all payments made. After the issue of the grant the rent is  $2\frac{1}{2}$  per cent., and the capital value of the land as unimproved is reappraised every ten years, the first valuation, however, holding good for the first fifteen years. The only expenditure required in improvements is £20 for a dwelling-house within the first eighteen months after confirmation of the application by the Land Board. The other condition is residence, which must commence within three months after confirmation, and is a perpetual obligation. The land cannot be transferred during the first five years, and each successive transferee is required to live on the land while he holds it. Tenant right in improvements is secured, and the holding may be so protected that it cannot by any legal procedure, or under any circumstances, be wrested from the selector. Holders of conditional purchases may convert their holdings into homestead selections.

#### *Conditional Leases.*

A conditional lease may be applied for by any holder of a conditional purchase, other than a non-residential one, or one within a special area in the Eastern Division, the application for which may have been made subsequent to the 1st January, 1885. Lands available for conditional purchase are also available for conditional lease, with the exception of lands in the Western Division, or within a special area or a reserve from lease. Applications are to be made to the Crown Lands Agent of the district, and must be accompanied by a provisional rent of 2d. an acre and a survey fee. The area of the conditional lease or leases applied for by virtue of any conditional purchase cannot exceed three times the area of the purchase, and cannot be less than 40 acres. The area which an applicant may apply for as conditional purchases and conditional leases is restricted to 1,280 acres in the Eastern Division and 2,560 acres in the Central Division; but the Land Board may allow these areas to be exceeded, provided that the area obtained,

together with all other lands held by the applicant under whatever tenure, other than annual tenure, does not exceed such an area as, in the opinion of the Board, is sufficient for the maintenance of the applicant's home thereon in average seasons and circumstances. The lease is for a period of forty years, at a rent determined by the Land Board, payable yearly in advance. The terms of the lease are divided into four periods of ten years each, and the annual rent for each period may, on the application of the lessee, or on a reference by the Minister, be determined separately. The conditions of fencing, or substitution of improvements in lieu of fencing, which attach to a residential conditional purchase apply equally to a conditional lease, and residence is required as in the case of an additional conditional purchase. The holder may convert the whole or part into an additional conditional purchase, which is freed from any residential condition if the lease was applied for before the 1st June, 1895. A conditional lease must be transferred whenever the conditional purchase upon which it depends is transferred.

#### *Settlement Leases.*

Another departure under the Act of 1895 is the provision for settlement leases for agricultural and grazing purposes. Under this form of tenancy, lands gazetted as available for settlement lease are obtainable on application, accompanied by a deposit consisting of six month's rent and survey fee. The maximum area of agricultural land which may thus be taken up is 1,280 acres; but in other instances, where it is apparent that the settler must combine agriculture with grazing, and must depend mainly upon the latter for a livelihood, the farms may comprise any area not exceeding 10,240 acres. These areas may be exceeded by means of additional holdings so long as the area obtained, together with all other lands held by the applicant under whatever tenure, other than annual tenure, does not exceed such an area as, in the opinion of the Land Board, is sufficient for the maintenance of the applicant's home thereon in average seasons and circumstances. The additional holding need not necessarily adjoin the original holding, but must, in the opinion of the Land Board, be situated within a reasonable working distance thereof. The lease is issued for a term of forty years, divided into four periods, each of ten years. The annual rent of the first period is that notified before the land is made available for lease; but the lessee may, if dissatisfied, require the rent to be determined by the Board. The annual rent for each succeeding period may, on the application of the lessee, or on reference by the Minister, be separately determined in like manner. Residence is compulsory throughout the whole term, and the land must be fenced within the first five years. Tenant right in improvements is secured to the outgoing lessee, and the lessee may apply at any time after the first five years of the lease for an area not exceeding 1,280 acres, on which his house is situated, as a homestead grant.

*Improvement Leases.*

Improvement leases may comprise any scrub or inferior land in the Eastern or Central Divisions, and can only be let by auction or tender; or, if not taken up, may be tendered for afterwards at the upset rental. The rent is payable annually, and is not subject to alteration; and the lease is for a period of twenty-eight years, with an area not exceeding 20,480 acres. Upon the expiration of the lease the last holder will have tenant right in improvements. During the last year of the lease the lessee may convert into a homestead selection 640 acres, on which his dwelling-house may be erected.

*Pastoral Leases.*

Provision is made in the Crown Lands Act Amendment Act of 1903, whereby the registered holder of any preferential occupation license or occupation license may apply for a lease of an area not exceeding one-third of the total area of the land comprised within the license. After consideration by the Land Board as to whether the land or any part of it is suitable for closer settlement, or is required to enable present holders not having a living area to add to their holdings, the application may be granted wholly or in part for a period not exceeding twenty-eight years, subject to such rent, conditions of improvement, and withdrawal for settlement as may be determined.

*Occupation Licenses.*

There are two forms of occupation license in existence, viz., preferential occupation licenses, comprising the area within the expired pastoral leases in the Eastern and Central Divisions, and ordinary occupation licenses, comprising the parts of the holdings formerly known as resumed areas. Occupation licenses extend from January to December, but may be renewed from year to year on payment of the rent in advance. The rent is determined by the Land Board, and is liable to reappraisal whenever the Minister deems such a course desirable. Any improvements effected by the licensee remain his property during the currency of the license. Any vacant Crown land suitable for occupation license is offered as such by auction or tender, and if not sold or tendered for is open for application at the upset rental specified in the proclamation.

*Western Division.*

The western division embraces an area of 79,970,000 acres, watered entirely by the Darling River and its tributaries. This part of the state is essentially devoted to pastoral pursuits.

The administration of the western division under the "Western Lands Act of 1901" is vested in a Board of three Commissioners, entitled "The Western Land Board of New South Wales," and all Local Land Boards constituted prior to the 1st January, 1902, cease to have jurisdiction within the area. The Commissioners, sitting in open Court, are empowered to exercise all the powers conferred upon Local Land Boards

by the Crown Lands Acts, and for all purposes of the Crown Lands Acts shall be a Local Land Board in all cases, as well as in any cases that may be or are required to be referred to any Local Land Board under the provisions of any Act, now or hereafter in force.

Subject to existing rights and the extension of tenure referred to in a subsequent paragraph, all forms of alienation, other than by auction, and leases, prescribed by the Crown Lands Acts, ceased to operate within the Western Land Division from the 1st January, 1902.

Before any Crown lands in the western division, not held under lease, shall become available for lease, the Commissioners must recommend the areas and boundaries of the land to be offered for lease and the rent to be charged therefor, and, should there be any improvements on the land, determine the amount to be paid for them. The Minister may, by giving thirty days' notice in the *Government Gazette*, declare such lands open for lease, and applications therefor must be made to the Commissioners on a prescribed form, accompanied by a deposit at the rate of 20 per cent. on the amount of the first year's rent, as notified in the *Government Gazette*, and the Commissioners may recommend a lease to such applicant as they shall consider most entitled to it. Upon the issue of a lease the notification thereof is published in the *Government Gazette*, and within one month therefrom the successful applicant must pay the balance of the first year's rent and execute the lease within the time and manner prescribed.

The registered holder of a pastoral, homestead, improvement, scrub, or inferior lease or occupation license of land in the western division, or in the event of any such holding being mortgaged, then any owner of the equity of redemption in the same, could apply before the 30th June, 1902, to bring his lease or license under the provisions of the "Western Lands Act of 1901." In cases where no application was made to bring the lease or license under the provisions of the Act, such lease or license is to be dealt with as if the Act had not been passed, and the Commissioners as constituted are to be deemed the Local Land Board to deal with such cases.

All leases issued or brought under the provisions of the "Western Lands Act of 1901" expire on the 30th June, 1943, except in cases where a withdrawal is made for the purpose of sale by auction or to provide small holdings, when the Governor shall, after report by the Commissioners, add to the remainder of the lease such term as may be considered reasonable as compensation, but in no case shall it exceed six years.

The rent on all leases current after the commencement of the Act is determined by the Commissioners for the unexpired portion of such leases. No rent or license fee is to be less than 2s. 6d. per square mile or part thereof, and in no case shall the rent or license fee be fixed at a higher rate than 7d. per sheep on the carrying capacity determined by the Commissioners. In the case of new leases, the rents are determined for periods not exceeding ten years, and in the case of leases extended

under the provisions of the Act for periods ending 30th June, 1930 and 30th June, 1943. The rent fixed in the case of existing leases, and for the first term in the case of new leases, cannot on reappraisement be either increased or decreased more than 25 per cent. on the first reappraisement, and the provision applies at each subsequent reappraisement to the rent last determined.

### *Labour Settlements.*

In the middle of 1893 an Act was passed to establish and regulate labour settlements on Crown lands, following the example set by New Zealand, and imitated by several other states. Under this Act the Minister may set apart certain areas for the purpose of establishing labour settlements. A settlement is placed under the control of a Board, which enrolls such persons as it may think fit to become members of the settlement; makes regulations concerning the work to be done; apportions the work among the members; and equitably distributes wages, profits, and emoluments after providing for the cost of the maintenance of the members. Any trade or industry may be established by the Board, and the profits apportioned among the enrolled members. A Board is constituted as a corporate body, with perpetual succession and a common seal; and the land is leased to the Board as such, in trust for the members of the settlement, for a period of twenty-eight years, with right of renewal for a like term.

When a Board has enrolled such a number of persons as the Minister for Lands may approve, it may apply for monetary assistance on behalf of the members of the settlement. The Minister has power to grant an amount not exceeding £25 for each enrolled member who is the head of a family dependent upon him; £20 for each married person without a family; and £15 for each unmarried person. On the expiration of four years from the commencement of the lease, and at the end of each year following, 8 per cent. of the total sum paid to the Board becomes a charge on its revenues, until the total amount advanced, with interest at the rate of 4 per cent. per annum, has been repaid.

On the 31st December, 1903, the only settlements in existence were those at Bega and Wilberforce. At Bega an area of 1,360 acres was attached to the settlement, and on the date specified there were 29 men enrolled, and a total population of 205. A sum of £2,421 has been advanced by the Government as a loan, and the value of improvements, exclusive of crops, is £2,296. At Wilberforce, an area of 882 acres was granted for a settlement, and on the 31st December, 1903, there were 11 men enrolled, the total population being 67. The loans from the Government amounted to £2,045, and the value of improvements, exclusive of crops, £2,340.

### VICTORIA.

During the earlier period of the colonisation of Victoria, then known as the District of Port Phillip, in New South Wales, the alienation of

Crown lands was regulated by the Orders in Council of the mother state, to which reference has already been made. In the year 1840, however, the upset price of country lands, which in New South Wales was limited to 12s. per acre, was specially raised to 20s. in the District of Port Phillip. The Orders in Council continued in force until 1860, when the system of free selection of surveyed country lands was inaugurated, the uniform upset price being fixed at £1 per acre. No condition was required to be fulfilled by the selector other than that of making a cash payment for the whole of his purchase—or for one-half only, the other half being occupied at a yearly rental of 1s. per acre, with right of purchase at the original price. In 1862 a new Act was passed. Large agricultural areas were proclaimed, within which land could be selected at a uniform price of £1 per acre. Modifications were introduced in the mode of payment; the maximum area which could be selected by one person was limited to 640 acres; and it was stipulated that certain improvements should be effected or part of the land placed in cultivation. This Act was amended in 1865, when the principle was introduced of leasing Crown lands within agricultural areas, with right of purchase after the fulfilment of certain conditions as to residence and improvements; and a new provision was added to meet the demand for land adjacent to gold-fields.

The legislation in force was, however, superseded by the Land Act of 1869 and the Pastoral Act of the same year. Until that time the free selection system in the state had been limited to certain lands proclaimed within agricultural areas, and to allotments previously surveyed, thus avoiding the conflict which was then beginning to take place in New South Wales between the selector and the pastoralist. Under pressure of a sudden increase in the demand for land arising from the enormous immigration into Victoria which had followed the discovery of gold, and the necessity for the people finding other means of employment and other and more permanent sources of income, the Victorian Legislature adopted the system in vogue in the neighbouring state, with modifications to suit the local conditions. The Act of 1869, which was amended in 1878, was further amended in 1884, the main tendency of the latter amendment being towards the restriction of the further alienation of the public estate by limiting the area which might be sold by auction, and substituting for the existing method of selecting agricultural land a system of leasing in certain defined areas, and at the same time conserving to the lessee the privilege of acquiring from his leasehold the fee-simple of 320 acres under the system of deferred payments. A portion of the public domain, known as the "Mallee Scrub," comprising some 11½ million acres wholly or partly covered with various species of stunted trees, was separately dealt with by the Mallee Pastoral Leases Act of 1883. The land legislation of 1869, and the special enactment just referred to, were again modified by the Acts of 1890, 1891, 1893, 1896, 1898, and 1900, the whole being consolidated as the "Land Act, 1901," which came into force on the 31st December, 1901.

During 1903, the "Land Act, 1903," was assented to, this measure modifying slightly some of the provisions of the consolidating act.

The Land Act of 1869 is inoperative as to future selections, but concessions as to payments of arrears of rent, the option of converting their present leases into perpetual leases, and of surrendering part of and obtaining new leases on better terms for the balance of their holdings, have been granted to selectors thereunder by the most recent legislation.

For the purposes of land administration, the state is divided into districts which are merely arbitrary divisions, and in each district there are land offices under the management of land officers. As occasion requires, the land officers hold board meetings to deal with applications for, and any matter pertaining to, Crown lands.

Unalienated Crown lands are divided into the following classes:—Good agricultural or grazing land; agricultural and grazing lands; grazing lands; inferior grazing lands; pastoral lands (large areas); swamp or reclaimed lands; lands which may be sold by auction (not including swamp or reclaimed lands); auriferous lands; State forest reserves; timber reserves; and water reserves. Provision is made for a reclassification of lands within the first, second, third, and fourth classes, where it is recognised that an inequality exists, and for this purpose Land Classification Boards are constituted, each Board to consist of three members who will be officers of the Lands Department or other competent persons. Provision is made in the "Land Act, 1903," that where it appears that the value of any unalienated Crown land is greater than the value fixed therefor in accordance with the provisions of the consolidating Act, power is given to the Governor-in-Council to increase the rates of any license fees, rent, or purchase money payable under the said consolidating Act, in respect of any such land which may thereafter be licensed or leased or sold by the Crown. Land may be acquired in the following manner:—(1) By the lessee of pastoral lands, by selection of a homestead up to 640 acres of land not superior to third-class land out of his leasehold at 10s. per acre; (2) by the lessee of a "grazing area" who is entitled to select thereout an agricultural allotment, obtaining a perpetual lease of the allotment in lieu of a license; (3) by licensee or lessee of an agricultural allotment on the surrender of his license or lease, obtaining in its stead a perpetual lease; (4) by the holder of a mallee allotment, eligible to select an agricultural allotment thereout, obtaining a perpetual lease instead of a license; (5) by perpetual leases of any Crown lands available as agricultural or grazing allotments, or mallee lands available as agricultural allotments, or swamp, or reclaimed lands; (6) by purchase at auction of town or country lands within specified areas; (7) by purchase at auction of detached portions of Crown lands of an area not exceeding 50 acres; (8) by the holder of a residential agricultural allotment under license within mallee territory; (9) by farm allotment under conditional purchase lease, within areas required for the purpose of closer settlement.



*Pastoral Lands.*

Pastoral leases are granted to the person first lodging an application after public notice has been given that the land is available, and expire on the 29th December, 1909. The maximum area is 40,000 acres, and the minimum 1,920 acres. Should more than one application be lodged; the right to a lease is sold by public auction, after at least one month's notice has been given in the *Government Gazette*, and the highest bidder by way of premium is, on payment of same, entitled to the lease. The annual rent reserved on every lease of pastoral lands is computed at 1s. per head of sheep, and 5s. per head of cattle, the number of such sheep or cattle to be determined by the grazing capacity of the area, and the rent must be paid in advance every six months. The lessee cannot assign, sublet, or subdivide without the consent of the Board in writing; he must destroy all vermin and noxious growths, and keep in good condition all improvements on the land; and he must not destroy growing timber, except for fencing purposes or for building on the land, without the Board's consent. The Crown has the right to resume any portion of the area required for any railway or public purposes, and may issue licenses to enter on the land to obtain timber, stone, earth, etc. The right is reserved to other pastoral lessees to pass over the area, and the Governor may at any time by proclamation grant to the public the use of any track leading to a public road or track. The lessee is also required to erect swing gates where there is a fence across any track required by any other pastoral lessee or the public. Upon compliance with all conditions, the lessee may select 200 acres of first-class, or 320 acres of second-class, or 640 acres of third-class land, or 960 acres of fourth-class land, as a homestead. Upon the expiration of a lease the lessee is entitled to payment from an incoming tenant for all fences, wells, reservoirs, tanks, and dams—but such payment shall be determined in the manner provided by the Lands Compensation Acts—and all other improvements revert to the Crown.

*Agricultural and Grazing Lands.—Grazing Areas.*

Agricultural and grazing lands are leased in "grazing areas" of first, second, third, or fourth class land, to any person of the age of 18 years and upwards, for any term of years expiring not later than 29th December, 1920. No such lease can be granted for more than 200 acres of first-class, or 640 acres of second-class, or 1,280 acres of third-class land, or 1,920 acres of fourth-class land; but the lease may comprise two or more "grazing areas," provided the total acreage does not exceed the maximum limit of any class. The rent is fixed at 3d. per acre for first-class, 2d. per acre for second-class, and 1d. per acre for third-class lands, and  $\frac{1}{2}$ d. per acre for fourth-class lands; but an additional rent of 4 per cent. per annum on the capital value of any substantial and permanent improvements on the "grazing area" at the date of the commencement of the lease is imposed. On the expiration of the lease the incoming tenant is required to pay to the late lessee the

value of all improvements effected during the currency of the lease calculated to increase its capacity for carrying sheep or cattle; but the sum to be paid in respect of such improvements must not be more than 10s. per acre of the "grazing area" if first-class, or 7s. 6d. per acre if second-class, or 5s. per acre if third-class land, or 2s. 6d. per acre if fourth-class land. All other improvements revert absolutely to the Crown, unless specially provided for in the lease of the "grazing area." The rent is payable half-yearly in advance, and the lessee cannot assign, sublet, or subdivide, without the consent of the Board; he must destroy all vermin and noxious growths and keep in good condition all improvements on the land. The lessee cannot ring or destroy, or, except for the purpose of fencing, or building, or domestic use on the land, cut down any timber thereon, without the consent of the Board, and he must enclose the land with a fence and keep it in good repair. The Crown may resume possession at any time of any of the land which may be required for public or mining purposes, or for removal of material or timber, or for industrial purposes, on payment of reasonable compensation. Every other lessee of a "grazing area" and his agents and servants have the right of ingress, egress, and regress to and from his "grazing area" through, from, and to any public road or track. The lessee, after the issue of the lease, may, if the "grazing area" consist of first-class land, select not more than 200 acres thereof as an "agricultural allotment"; if of second-class land, an "agricultural allotment of" of 320 acres; and if of third-class land a "grazing allotment" of 640 acres. A lessee of a "grazing area" in respect of which no rent is due, and who has reasonably and sufficiently fulfilled the conditions and covenants of his lease, may surrender any part of his "grazing area" in order that a new "grazing area" lease of such surrendered part may be granted to his wife or any eligible child, without public competition. The "Land Act, 1903," provides that any unalienated Crown land may before or after classification in any class be made available for selection and be taken up under a grazing area, but previous thereto, a plan of the projected subdivision is to be prepared, and a provisional valuation and classification indicated thereon. On the completion of the permanent survey of the grazing area, the value is determined by the Classification Board and the rent is fixed to accord with the value so determined.

#### *Agricultural Allotments.*

Residence licenses are issued to any person of the age of 18 years and upwards, who has not made a selection under the Land Acts, or who is not in respect of the license applied for or any part thereof an agent, servant, or a trustee for any other person, or who has not at any time entered into an agreement to permit any other person to acquire by purchase or otherwise the applicant's interest therein, to occupy an "agricultural allotment" not exceeding in the aggregate 200 acres of first-class or 320 acres of second-class land. The period of license is six years, and

the fee for occupation is 1s. per annum in the case of first-class land, or 9d. per annum in the case of second-class land for each and every one acre or part thereof, payable half-yearly in advance. The licensee cannot assign, transfer, or sublet; he must enclose the land with a fence and keep it in repair; and he must effect substantial and permanent improvements to the value of 20s. per acre, or fractional part of an acre, where the land is first-class, and 15s. an acre, or fractional part of an acre, where the land is second-class, during the currency of the license. The licensee must enter into occupation within twelve months from the issue of the license, and occupy the agricultural allotment for not less than five years during its currency. If a licensee satisfactorily prove that the home of his family is situate upon the land held by him under residential license, the Board may consent, for a specified period, to substituted occupation by the wife or any stated child over the age of 18 years; or, if he has no wife or child, by the father or mother of the licensee, provided he or she is dependent on him for support. A licensee may, in each and every year of the term of residence on residential license, apply to the land officer of the district to register a written notice of intention to absent himself from the agricultural allotment for a period or periods not exceeding on the whole three months, and any absence between the registered dates is not deemed a breach of the condition of occupation. If the conditions be complied with, the licensee is entitled at any time within twelve months after six years from the commencement of the license to obtain a Crown grant upon payment of the difference between the amount of rent actually paid and the entire sum payable for the purchase of the land, or obtain a lease for a term of fourteen years. The Crown may resume any portion of the land during the currency of the license that may be required for public or mining purposes, subject to the repayment of moneys paid by the licensee to the Crown or expended by him on the land resumed.

Non-residential licenses for a period of six years are issued to persons similarly qualified on identical conditions, with the exception that the improvements to be effected are 6s. 8d. per acre, or fractional part of an acre each year of the license on first-class land, and 5s. per acre, or fractional part of an acre for each of the first three years of the license in respect of second-class lands.

The "Land Act, 1903," provides that any unalienated Crown land may before or after classification in any class be made available for selection and be taken up as an agricultural allotment, but previous thereto, a plan of the projected subdivision is to be prepared and a provisional valuation and classification indicated thereon. On the completion of the permanent survey of the agricultural allotment, the value is determined by the Classification Board and the license fee is fixed to accord with the value so determined.

The licensee or lessee of an agricultural allotment may surrender his license or lease, and in its stead obtain a perpetual lease. The rent chargeable therefor to 29th December, 1909, is based upon the

unimproved value of the land, which is assumed at £1 per acre if first-class and 15s. per acre if second-class land ; thereafter the rent is fixed by the Board at the end of every successive ten years. The holder of an agricultural allotment who desires to establish and cultivate a vineyard, hop-garden, or orchard may, during the term of his license or lease, upon payment of the difference between the amount of rent actually paid and the entire purchase-money payable in respect of any part, not more than 20 acres, of his allotment, obtain a Crown grant of such part subject to such covenants, conditions, exceptions, and reservations as the Governor may direct.

#### *Grazing Allotments.*

Licenses, either residential or non-residential, are issued to persons, qualified in a similar manner to those entitled to hold agricultural allotments, to occupy an allotment of third-class land not exceeding 640 acres, or 960 acres of fourth-class land. The period of license is six years, and the rent payable 6d. per acre for third-class land, and 3d. per acre for fourth-class land, half-yearly in advance. In the case of a residential license, the licensee must enter into occupation within twelve months from the issue of the license, and occupy the grazing allotment for not less than five years during the currency of the license. If a licensee satisfactorily prove that the home of his family is situate upon the land held by him under residential license, the Board may consent, for a specified period, to substituted occupation by the wife or any stated child over the age of 18 years ; or, if he has no wife or child, by the father or mother of the licensee, provided he or she is dependent on him for support. A licensee may, in each and every year of the term of residence on residential license, apply to the land officer of the district to register a written notice of intention to absent himself from the grazing allotment for a period or periods not exceeding on the whole three months, and any absence between the registered dates is not deemed a breach of the condition of occupation. Substantial and permanent improvements must be effected to the value of 10s. per acre, or fractional part of an acre, on third-class lands, or 5s. an acre on fourth-class lands in respect of residential licenses, and 3s. 4d. each year of the first three years for each acre, or fractional part of an acre, in the case of non-residential licenses of third-class lands, or 1s. 8d. in the case of fourth-class lands. The licensee cannot assign, transfer, or sublet ; he is required to keep the land free from vermin, and must enclose the land and keep the fence in repair. The Crown may resume any portion of the land during the currency of the license that may be required for public or mining purposes, subject to the repayment of moneys paid by the licensee to the Crown or expended by him on the land resumed. If the conditions be complied with, the licensee is entitled, at any time within twelve months after six years from the commencement of the license, to obtain a Crown grant upon payment of the difference between the amount of rent actually paid

and the entire sum payable for the purchase of the land, or obtain a lease for a term of fourteen years, at a yearly rent of 6d. for each acre of third-class land, or 3d. per acre for fourth-class lands. The holder of a grazing allotment, who desires to establish and cultivate a vineyard, hop-garden, or orchard, may, during the term of his license or lease, upon payment of the difference between the amount of rent actually paid and the entire purchase-money payable in respect of any part, not exceeding 20 acres, of his allotment, obtain a Crown grant of such part, subject to such covenants, conditions, exceptions, and reservations as the Governor may direct. The "Land Act, 1903," provides that any unalienated Crown land may before or after classification in any class be made available for selection and be taken up as a grazing allotment, but prior thereto a plan of the projected subdivision is to be prepared and a provisional valuation and classification indicated thereon. On the completion of the permanent survey of the grazing allotment, the value is determined by the Classification Board and the license fee and purchase money are fixed to accord with the value so determined. Any person who is entitled to select a grazing allotment may apply for a perpetual lease of the allotment in lieu of the license.

#### *Perpetual Leases.*

Perpetual leases may be granted over any Crown lands available as agricultural or grazing allotments; over mallee lands available as agricultural allotments; and over swamp or reclaimed lands. They may also be granted to holders of grazing areas who are entitled to select thereout an agricultural or grazing allotment; to holders of mallee allotments or parts thereof eligible to select an agricultural allotment; to holders of permits or leases to occupy allotments on swamp lands; and to village settlers on other than swamp lands who may desire to surrender the same and obtain perpetual leases in lieu thereof. No person is allowed to hold by transfer or otherwise more than 600 acres of first-class, or 960 acres of second-class, or 1,920 acres of third-class land, or 2,880 acres of fourth-class land, outside the mallee country. The rent on every perpetual lease, outside mallee and swamp or reclaimed lands, to 29th December, 1909, is  $1\frac{1}{2}$  per cent. on the unimproved value of the land, which is deemed to be £1 per acre for first-class, 15s. per acre for second-class, 10s. per acre for third-class, and 5s. per acre for fourth-class land. For every successive period of ten years the value, exclusive of all improvements made by the lessee, will be such amount as may be fixed by the Board, and the annual rent will be  $1\frac{1}{2}$  per cent. of such value. The rent must be paid yearly in advance. The lessee must, within two years, destroy all vermin and keep the land free from vermin and noxious growths; he must enclose the land within six years, or sooner if called upon under the Fences Act, 1890; he must reside for six months on the land, or within 5 miles thereof during the first year, and eight months during each of the four following years. In the event of the cultivation by the lessee

of one-fourth of the area during the first two years, and one-half before the end of the fourth year, the residence covenant ceases to operate. Improvements must be effected to the value of 10s. per acre on first-class, 7s. 6d. per acre on second-class, and 5s. per acre on third-class land, or 2s. 6d. per acre on fourth-class land, before the end of the third year, and further improvements to a like value before the end of the sixth year of the lease. The lessee may not transfer, assign, mortgage, sublet, or part with the whole or any portion of the area within six years; and any portion required for railways, roads, mining, or other public purposes may be resumed on payment for non-removable improvements thereon or cost of removable improvements. A perpetual lessee whose rent is not in arrear may surrender his lease within six months after 29th December, 1909, or within six months after any successive period of ten years, with a view of obtaining an agricultural or grazing allotment license, either residential or non-residential. The improvements made will be credited to the licensee, and should there be a mortgage on the perpetual lease, the licensee may, after the issue of the license, give to the mortgagee a license lien on his improvements to the full amount due on the mortgage at the time of surrender.

#### *Lands within Auriferous Areas.*

Licenses to reside on or cultivate lands comprised within an auriferous area may be granted for a period not exceeding one year, and for areas not exceeding 20 acres, at an annual license fee of 1s. per acre. No person can hold more than one license. The license is subject to the following conditions:—Right to use surface of land only; licensee not to assign or sublet without permission of the Minister; licensee either to reside on or fence the land within four months from date of license and cultivate one-fifth of area, allowance being made for any portion occupied by buildings; miners to have free access to any part of the land without making compensation to the licensee for surface or other drainage; and notices to be posted on the land by the licensee indicating that it is auriferous.

Grazing licenses, renewable annually at the option of the licensee, are issued for a period expiring not later than 29th December, 1905, for areas not exceeding 1,000 acres, at a rent to be fixed by appraisalment. The licensee may, with the consent of the Minister of Mines, enclose the whole or any specified part of the holding with a fence, which may be removed by him upon or at any time before the expiration of his license; but such fence must be removed, without compensation, by the licensee when so ordered by the Board. Free access to such area must be allowed at all times to miners and other persons specially licensed to enter thereon; the ringbarking of the timber on the land by the licensee is strictly forbidden; and the licensee is subject to a penalty, not exceeding £20, if he fails to place upon the outside of the corner posts of the fence, if any, enclosing the lands such distinguishing marks as may be prescribed.

*Auction Lands.*

Lands comprised within certain areas notified in a schedule attached to the Act of 1891, and lands within proclaimed towns or townships, or within any city, town, or borough proclaimed before the passing of the Lands Act of 1884, may be sold at auction, the upset price for town lands being determined in the proclamation for sale, while that for country lands, is £1 per acre. The maximum area that may be sold in any one year is 100,000 acres. Of the price,  $12\frac{1}{2}$  per cent. must be paid in cash, and the balance in forty half-yearly instalments, carrying interest at 4 per cent. per annum. Where, in the opinion of the Board, it is undesirable that the residue of the price of any land should be paid for by instalments extending over twenty years, such residue may be made payable in any number of half-yearly instalments less than forty. Stringent provisions are enacted prohibiting agreements preventing fair competition at auction sales. Isolated portions of Crown lands not exceeding 50 acres and not adjoining other Crown lands, or any portion of Crown lands not exceeding 3 acres required as a site for a church or for any charitable purpose, may be sold at auction.

*Swamp Lands.*

The swamp or reclaimed lands comprise the areas known as Condah, Koo-wee-rup, Moe, Panyzabyr, Mokoan, Black Swamp, Borodomanin, and Branket, Greta, Kelfeera, and Pieracle Swamps, and any swamp or reclaimed lands that may be proclaimed as such in the *Government Gazette*. The lands are divided into allotments of an area not exceeding 160 acres, and may be leased for twenty-one years, or be leased under perpetual lease at a rental of 4 per cent. on the value of the land, or be leased under conditional purchase lease, or be disposed of by sale at public auction, subject to general conditions of sale. Every lease for twenty-one years, every perpetual lease, every conditional purchase lease, and every contract of sale for an allotment of swamp or reclaimed lands contains the condition that the lessee or purchaser shall make substantial improvements on the land to the extent of 10s. per acre in each of the first three years and keep open all canals and drains. The condition of residence is not obligatory in all cases. For determining the rent on the upset price the Board will fix the value of each allotment. Village settlers on swamp or reclaimed lands may surrender their permits or leases, and acquire in place thereof perpetual leases or conditional purchase leases. In the event of a perpetual lease being granted, the annual rent thereon till 29th December, 1909, will be 4 per cent. on the price of the land as fixed in the surrendered permit or lease, the improvements at time of surrender to be credited towards compliance with conditions of new lease. In the event of a conditional purchase lease being granted, the price to be paid will be that fixed in the surrendered permit or lease, carrying interest at  $4\frac{1}{2}$  per cent. per annum.

*Lands enhanced in Value.*

Where Crown lands are enhanced in value by the proximity of a railway, or of waterworks for irrigation purposes, etc., the Governor is empowered to increase the minimum sum per acre for which such lands may be sold, as well as the minimum amount of rent or license fee, by not less than one-eighth nor more than double the sum. But where lands have been sold, leased, or licensed at an enhanced price, and the works by reason of which the extra payment has been demanded have not been constructed within ten years from the date of the Order in Council fixing the enhanced price, the additional sum paid must be returned.

*Forest Lands.*

Land situated within the State forests, and timber and water reserves, cannot be alienated, except as hereinafter provided; and the administration of the Forest Domain of the Crown is placed in the hands of local Forest Boards, which are empowered to receive fees for licenses to cut or remove timber. Where any person has made his home, or the home of his family, for a period of five years on forest lands, whether permanently reserved or not, and has effected thereon improvements of the value of not less than £2 per acre, he may apply to purchase an area not exceeding 10 acres at a price to be determined by appraisalment; and if there be no mining or other valid objection a Crown grant may issue.

*Mallee Lands.*

The territory known generally as the "Mallee" is situated in the north-western district of the state, and comprises an area of about 10,000,000 acres. The mallee land bordering on the plain country is mostly of a light chocolate and sandy loam character, and in its natural state is covered with mallee scrub, interspersed with plains lightly timbered with box, oak, and pines. The scrub can be cleared at a moderate expenditure, and the land is well adapted for wheat-growing. The smaller areas are known as "mallee allotments," and the larger areas, extending further north and where the soil is more sandy in character, as "mallee blocks." The "blocks" are practically in their natural state, are many square miles in extent, and are used for pastoral purposes only.

*Mallee Blocks.*

The "mallee blocks" are of various sizes. One portion of a block may be held for five years under an occupation license, and the other under lease for a period expiring not later than the 1st December, 1903. The lease is granted for a period of twenty years. For the first five years the rent payable is at the rate of 2d. per head of sheep and 1s. per head of cattle depastured on the land; for the second five years twice this amount; and for the remainder of the term at an additional increase equal to one-half the amount payable during the second period of five years; but in no case may the yearly rent be less than 2s. 6d.



for each square mile or part of a square mile of land. Leases issued after the 20th February, 1896, have the rent fixed by the Board. The lessee cannot assign, subdivide, or cultivate any part without the consent of the Board of Land and Works; he must destroy the vermin upon the land, and fulfil certain other conditions. The Government retain the right of resuming the land after giving due notice, compensation for improvements effected being given on assessment. Licenses may be granted to enter on the block to obtain timber, stone, earth, etc., and other lessees may cross the area to get to any public road or track.

#### *Mallee Allotments.*

The mallee allotments are situated on the southern and eastern fringe of the mallee territory, and have a maximum area of 20,000 acres, and are leased for terms expiring not later than 30th November, 1903.

No assignment of the lease of a mallee allotment by operation of law can take effect without the consent of the Board, and the lessee without such consent cannot execute any mortgage or lien thereon. The lessee is required, within six months of the granting of the lease, to take up his residence on the land or within 5 miles thereof, and to remain there for at least six months in the first year, and nine months during each of the next four years; or, instead, to cultivate at least one-fourth of the allotment within two years, and at least one-half before the end of the fourth year. In the event of the insolvency or death of the lessee, residence is not obligatory on the assignee, executor, or administrator. Without the consent of the Board, the lessee cannot clear or cultivate any part of his allotment, and not more than five crops in succession may be raised, after which for one year the land must be allowed to lie fallow. A uniform rental of 1d. per acre per annum is now charged in all cases where the Board's consent has been obtained to clear and cultivate.

It is provided that the lessee may select out of his mallee allotment an agricultural allotment not exceeding 640 acres, either under license or perpetual lease. When this is done the remainder of the mallee allotment may be resumed, compensation being awarded for improvements only. Should the lessee have actually resided on the land and destroyed the vermin thereon, the period of six years for which the agricultural allotment license is issued may be so shortened as not to exceed the length of such residence, conditionally on the payment of the license fees.

#### *Agricultural Allotments under License or Perpetual Lease.*

Any person of the age of 18 years or upwards may select 640 acres of first-class, or 1,000 acres of second-class land, or 1,280 acres of third-class land, or 1,600 acres of fourth-class land, out of any area made available as an agricultural allotment under residential or non-residential license or perpetual lease. A similar concession is made to any holder of a mallee allotment who may make application at any time before the 30th

November, 1903, to select out of his mallee allotment a similar area in like manner. The period of residence attached to residential licenses is five years. When the area is first-class land, the purchase money in full for a residential license is £1 per acre, and the license is for a term of six years, at a yearly rent of 1s. per acre; the improvements at the expiration of the license must be of the value of £1 per acre. If all the conditions be complied with, the licensee is entitled, at the expiration of the license, to a lease for fourteen years at the same rent, or to a Crown grant at any time, on paying the difference between the amount paid and £1 per acre. If the applicant prefer, he may obtain a license at a reduced rental of 6d. per acre per annum for the term of six years, with a lease for thirty-four years at 6d. per acre yearly. When the area is second-class land, the purchase money in full is 10s. per acre, and the license is for a term of six years at a yearly rent of 6d. per acre, and the lease for fourteen years at the same rent, or a license may be issued, with conditions varied in these respects, that the rent shall be 3d. per acre yearly for six years, with a subsequent lease for thirty-four years at the same rent. The improvements at the end of the six years must be of the value of 10s. per acre. A non-residential license on first-class land is granted for a term of six years at 1s. per acre per annum, and the lease for a period of fourteen years at the same rent. Improvements to the value of 6s. 8d. per acre must be made in each of the six years. The period of non-residential license on second-class land is six years, at an annual rent of 6d. per acre, and the lease is for fourteen years at the same rent. Improvements to the value of 3s. 4d. an acre must be made during each of the first three years. Except for the purpose of building, fencing, or other improvements, the licensee may not cut or remove any live pine, box, or red gum, on the land.

Perpetual leases of mallee country are issued, in areas not exceeding 1,920 acres, at a yearly rental not to exceed 2d. per acre to 31st December, 1903, and thereafter as the Board may determine. The rent must be paid yearly in advance, and the lessee must destroy any vermin on the land, and within two years have made a complete clearance of such pests, while during the remainder of his lease he must see that the land is kept free from them. Within six months, the lessee must reside on or within 5 miles of the land, and do so for a period of eight months in each of the second, third, fourth, and fifth years. In the event of the lessee cultivating one-fourth of the area within two years, and at least one-half within four years, the residence condition ceases to operate.

#### *Vermin Districts.*

Under the Land Act of 1890, districts which are proclaimed as vermin-infested are, for the purpose of securing the extinction of these animal pests, administered by local committees appointed by the owners, lessees, and occupiers of the lands. In order to secure the erection of vermin-proof wire-fencing, a fencing rate may be levied, and the Minister has power to deduct 5 per cent. of the amount levied in vermin districts

for the purpose of erecting a vermin-proof fence between the mallee country and the mallee border.

#### *Wattle Cultivation.*

During 1890 legislation was enacted having for its object the granting of leases of any unoccupied Crown lands for the cultivation of wattle-trees, for any term not exceeding twenty-one years, at a rent of 2d. per acre per annum for the first seven years, 4d. per acre for the second seven years, and 6d. per acre for the remainder of the term. A lease is not granted for more than 1,000 acres; and the rent is payable half-yearly in advance. The lessee covenants not to assign, sublet, or divide the lease without the consent of the Board of Land and Works; to keep all improvements in repair during each of the first six years following the year after the granting of the lease; to sow or plant wattle-trees or any other approved tannin-producing trees or plants on at least one-fifth of the land leased, and within six years to occupy the whole area in a similar manner. He must within two years enclose a third, within three years two-thirds, and within four years the whole of the land leased; and he is required to keep the fence in good repair, and to destroy all vermin which may be upon the land. The lessee may select out of his lease an agricultural or grazing allotment under license or perpetual lease.

#### *Village Settlements.*

Under the Settlement on Lands Act of 1893 there may be set apart and appropriated for the purposes of village communities any lands not alienated from the Crown, provided they are not auriferous or permanently reserved for any purpose. Such lands are surveyed into allotments of 1 to 20 acres each, according to the quality of the soil and the situation. Subject to certain restrictions, any person of the age of 18 years may obtain a permit to occupy a village community allotment for a period not exceeding three years. The rent is merely nominal, but conditions are laid down with the object of ensuring *bona-fide* occupancy. On the expiration of the permit a lease may be obtained, provided the conditions of the permissive occupancy have been fulfilled. The lease is granted for a period of twenty years. The lessee must pay in advance, every half-year, rent equal to one-fortieth of what is regarded as the price of the allotment, which is to be not less than £1 per acre. Within two years from the date of the lease he must have brought into cultivation not less than one-tenth, and within four years, one-fifth of the land; and within six years, have effected substantial improvements of a permanent character to the value of £1 for every acre leased. He must also keep all improvements in good repair; and he cannot assign, transfer, or sublet the land, or borrow money on the security of his lease without the consent of the Board of Land and Works. He must reside personally on the land, and use it for agriculture, gardening, grazing, or other like purpose. Any person in occupation of an allotment under

permit or lease may surrender the same, and acquire the land under a perpetual lease, or a conditional purchase lease. In the event of the land being granted under perpetual lease, the rental thereon to 29th December, 1909, will be 250 per cent. on the price set out in the original permit or lease; should the land be granted as a conditional purchase lease, the price to be paid is that fixed in the surrendered permit or lease carrying interest at  $4\frac{1}{2}$  per cent. per annum. Since the inception of the Act a sum of £67,379 has been granted in aid of the settlements. The area occupied comprises 57,588 acres, and improvements to the value of £254,955 have been effected. The number of settlers actually residing on the 30th June, 1904, was 1,758, and the number not residing, but improving their holdings, 133, making a total of 1,891 in occupation. The number of souls, including wives and children, residing on the date indicated was 8,536.

#### *Homestead Associations.*

Areas of similar lands to the foregoing may also be set apart and appropriated for occupation by members of associations or societies; but no proclamation can remain in force for a longer period than three years in the case of a society, nor for more than six months in the case of an association, after the survey and subdivision of the block; and land in any block not occupied or leased at the expiration of these periods becomes unoccupied Crown land again. No block of land set apart for the purposes of associations or societies can exceed in area 2,000 acres. A block is subdivided into lots of not more than 50 acres each, and the number of persons to be located in each block must not be less than one for every 50 acres of its total area. A permissive occupancy of a section may be granted to any member of an association or a society for a period of three years. The rent is a nominal one, and after proof of fulfilment of conditions a lease may be obtained by the member, provided he is of the age of 18 years. The lessee covenants to pay the annual rent and the cost of survey; to repay all moneys advanced by the Board; to bring into cultivation within two years not less than one-tenth, and within four years not less than one-fifth of the land; and within six years to effect substantial improvements of a permanent character to the value of £1 for every acre leased. He must also keep the improvements in good repair; and he cannot assign, transfer, or sublet the land, or borrow money upon it without the consent of the Board of Land and Works. He must personally reside on his section or its appurtenant township allotment, and use the land for agriculture, gardening, grazing, dairying, or other like purpose. Adjoining to or within every block of land appropriated in this manner, an area of not more than 100 acres may be set apart for the purposes of a township, and the Board of Land and Works may subdivide it into allotments not exceeding 1 acre, in order to provide a township allotment for each homestead selection. Power is reserved to alienate the fee-simple of those allotments not required for the purpose; and every settler may, within one year from

the commencement of his permit or lease, obtain a lease of such an allotment, with the right to a Crown grant in fee on making the payment prescribed.

#### *Labour Colonies.*

Areas of similar land, not exceeding 1,500 acres in extent, may also be set apart for the purpose of labour colonies, to be vested in five trustees, appointed by the Governor. For the purpose of aiding the trustees, provision is made whereby persons subscribing to the funds of such a colony may annually elect a committee of management, consisting of four members. The joint body (trustees and committee) is empowered, on a day to be determined in each case by the Minister, to admit to such a colony any person who shall be entitled to such benefits as the rules of the colony may prescribe. The trustees and committee of each colony must establish and conduct the same; and they have all the powers and authority necessary to enable them to improve the position of the colony and make it self-supporting. They may establish and maintain any industry they please, and dispose of the proceeds thereof. A subsidy of £2 for every £1 received by the trustees and committee from public and private subscriptions is payable by the Government. The moneys received are to be disbursed in the payment of allowances for work to persons employed in the colony; in the construction and maintenance of necessary buildings; and in purchasing provisions, clothing, building materials, stock, seed, and agricultural implements.

Besides the foregoing provisions, there are numerous others, dealing with minor interests, which in a general statement of this kind it is not necessary to recapitulate.

#### *Acquisition of Land for Closer Settlement.*

The acquisition of private lands for the purpose of closer settlement is an entirely new feature in Victorian land legislation. The Board of Lands and Works may, subject to the approval of Parliament, purchase for the Crown, blocks of good agricultural private land in any farming district. The portion of the acquired land to be disposed of is to be subdivided into farm allotments of a value not exceeding £1,000 each, which are to be available under conditional purchase lease. Any person of the age of 21 years, who is not already the holder of land of the value of £1,000, or who would not thereby become the holder of land exceeding such value, may be granted a farm under conditional purchase lease. The price of the land to be disposed of is to be so fixed as to cover the cost of original purchase, cost of survey and subdivision, the value of lands absorbed by roads and reserves, and the cost of clearing, draining, fencing, or other improvements which the Board may effect prior to the disposal of the land as farm allotments. The purchase money, with interest at  $4\frac{1}{2}$  per cent. per annum, must be paid by sixty-three or a less number of half-yearly instalments. The conditional purchase lease may be for such a term of years (not exceeding

thirty-one and a-half) as may be agreed upon between the lessee and the Board. The lease is subject to the following conditions:—Improvements to be effected to the value of 10s. an acre, or if the Board so determines, to the value of 10 per cent. of the purchase money, before the end of the third year of the lease, and to the value of a further 10s. an acre, or if the Board so determines, to the value of a further 10 per cent. of the purchase money before the end of the sixth year of the lease; personal residence by the lessee, or by his wife, or any child not less than 18 years of age, on the allotment for eight months during each year of the first six years; lessee not to transfer, assign, mortgage or sublet within the first six years; and such other conditions and covenants relating to mining, cultivation, vermin destruction, and other matters as may be prescribed by regulation. Upon or at any time after the expiration of the first six years of the lease, provided all conditions have been complied with, the lessee may, on payment of the balance of the principal, acquire the fee-simple of his farm allotment.

#### QUEENSLAND.

The land legislation of New South Wales in force on the date when the Moreton Bay District was formed into the colony of Queensland, gave place soon after that event to a new system of settlement, better adapted to the requirements of the newly constituted province. Following to a certain extent the lines adopted by their neighbours, the Queensland legislators introduced into their regulations the principle of free selection before survey, and of sales under the deferred payment system. Having to dispose of a vast territory which, not being endowed with so temperate a climate, had not the same attractions as the southern provinces, it was considered necessary to exercise greater liberality in offering the land than was shown to settlers in the other states. Large areas and small prices were therefore features of Queensland land sales. Most liberal, also, were the provisions to facilitate the exploration and occupation for pastoral purposes of the vast interior country, and the Pastoral Act of 1869 led to the occupation by an energetic race of pioneers of nearly the whole of the waste lands of the province. The rapid development of the resources of the state, and the consequent increase of population, necessitated later on a revision of the conditions under which land might be alienated or occupied; but although the tendency has been to curtail the privileges of the pastoralists, the alienation of the public estate by selection—conditional and unconditional—has been placed under enactments of a still more liberal character than those which existed in the earlier days. Under pressure of the new social movement, Queensland has followed in the wake of New Zealand and South Australia, and has granted to the working classes great facilities for acquiring possession of the soil. The regulations at present in force are based upon the legislation enacted under the Crown Lands Act of 1884, and its subsequent amendments in 1886, 1889, 1891, 1893, 1897, 1900, and 1902.

Land may be acquired in the following manner :—(1) By conditional selection: agricultural homesteads from 160 to 640 acres, at prices ranging from not less than 20s. for 160 acres to less than 15s. per acre for 640 acres, and agricultural selections up to 1,280 acres, at a price determined by the proclamation rendering the land available for settlement—residence in both cases to be personal or by agent; (2) by unconditional selection, at prices one-third greater than those payable in respect of agricultural selections, the area being limited to 1,280 acres; (3) by grazing-farm selection up to 20,000 acres, the period of lease ranging from fourteen to twenty-eight years at a varying rental,  $\frac{1}{2}$ d. per acre being the minimum; (4) by scrub selection of areas not exceeding 10,000 acres for a term of thirty years, at rentals ranging from a peppercorn to 1d. per acre; and (5) by purchase at auction, of town lands at an upset price of £8 per acre, suburban lands at £2 per acre, and country lands at £1 per acre for land classed as agricultural, and 10s. per acre for any other.

The state is, so far as is necessary, divided into Land Agents' Districts, in each of which there are a Public Lands Office and a Government Land Agent with whom applications for farms must be lodged. Applications must be made in the prescribed form, and be signed by the applicant, but they may be lodged in the Lands Office by a duly authorised attorney. There is connected with the Survey Department, in Brisbane, an office for the exhibition and sale of maps, and there full information respecting lands available for selection throughout the state can be obtained on personal application. Plans can also be obtained at the District Offices.

The conditions under which country lands may be acquired for settlement by persons of either sex over 16 years of age—other than single girls under the age of 21 years, who are debarred from selecting an agricultural or grazing homestead, and married women, unless they are judicially separated or possess separate estate, or are living apart from their husbands, provided the husbands have never acquired a homestead of the character sought—are substantially as stated below.

#### *Grazing Farms.*

Areas of land already surveyed are available for selection as grazing farms over a great extent of territory within accessible distance of the seaboard. Intending settlers can obtain up to 60,000 acres on lease, for a term of fourteen, twenty-one, or twenty-eight years, at an annual rent varying according to the quality of the land,  $\frac{1}{2}$ d. an acre being the minimum. Where lands are open under different proclamations, and a total area exceeding 20,000 acres is applied for by the same person, a rental limitation of £200 per annum must be observed, as well as the maximum areas prescribed by the several proclamations. This rent is subject to reassessment by the Land Court after the first seven years, and subsequently at intervals of seven years, but it cannot be decreased at any reassessment, nor can it be increased by more than

one-half of the rent for the period immediately preceding. The applicant must first obtain an occupation license, which is not transferable, and which may be exchanged for a lease for the balance of the term of fourteen, twenty-one, or twenty-eight years as soon as the farm is enclosed with a substantial fence, which must be done within three years or such extended time not exceeding two years as the Land Court may allow. The lease may be transferred or mortgaged after the expiration of five years from the commencement of the lease, and the farm may be subdivided; or, with the consent of the Land Court, sublet. The land must be continuously occupied by the lessee or his agent for the whole term of the lease, and cannot be made freehold. The Commissioner may issue a license to a group of two or more selectors, enabling any one of the selectors to perform the condition of occupation in respect of any of the selections as well as on his own behalf, but the number of selectors personally residing is not at any time to be less than half the whole number interested. One-fifth of the cost of survey—ranging from about £30 for a farm of 2,560 acres to about £65 for 20,000 acres, subject to increase or decrease according to locality—must be paid with a year's rent when application is made for the farm, and the balance in equal instalments without interest.

#### *Grazing Homesteads.*

Lands available as grazing farms are also open for selection as grazing homesteads at the same rental and for the same term of lease. An application to select as a grazing homestead takes precedence of a simultaneous application to select the same land as a grazing farm. The conditions and other provisions mentioned in respect of grazing farms are applicable also to grazing homesteads, with the exception that during the first five years of the term of a grazing homestead the condition of occupation must be performed by the continuous personal residence of the selector on the land, while before the expiration of five years from the commencement of the term a grazing homestead may not be mortgaged, assigned, or transferred.

#### *Agricultural Farms.*

The more accessible lands near lines of railway, centres of population, and navigable waters, are set apart for agricultural farm selection in areas up to 1,280 acres. The period of license is five years, during which the selector must fence in the land, or expend an equivalent sum in effecting other substantial improvements. As soon as the improvement condition has been complied with, a lease is issued for a term of twenty years from the date of the license, with right of purchase at any time after continuous occupation of the lease for a period of five years. The annual rent is one-fortieth of the purchasing price specified in the proclamation declaring the land open, and varies according to the quality and situation of the land, its natural supply of water, etc. The selector must occupy the land continually, either in person or by an agent



—who must be a person qualified to select a similar selection—for the whole term of the lease; but if the selector is the holder of two or more agricultural selections each of which is at a distance not exceeding fifteen miles from the others, the residence of the selector or his agent on one of the selections is sufficient. The cost of survey, ranging from about £10 to £12 for a farm of 160 acres to £20 to £40 for a farm of 1,280 acres, must be borne by the selector.

#### *Agricultural Homesteads.*

When land is taken up as an agricultural homestead, the area is restricted to 160 acres, 320 acres, or 640 acres, according as the price specified in the proclamation is determined at not less than 20s., less than 20s. but not less than 15s., or less than 15s. per acre respectively. The selection must be enclosed within a period of five years, or permanent improvements effected at an expenditure dependent on the capital value of the land. The applicant is entitled to a lease for a period of ten years, at a rental of 3d. per acre; but he may acquire the fee-simple of the land on the terms prescribed in the proclamation, after the expiration of five years from the commencement of the lease.

Two or more selectors of agricultural homesteads may associate for mutual assistance under license from the Land Board. A selector may perform conditions of residence for himself and any other member of the association, provided that at least one-half of the whole number of selectors interested are in actual occupation; and any sum expended on permanent improvements on any one homestead in excess of the required amount may be credited to any other farm or farms in the group. In other respects the conditions are similar to those governing agricultural homesteads.

#### *Village Settlements.*

With regard to village settlement, special provision is made by law for the settlement of little communities, so that settlers may live together in townships for mutual convenience, on allotments not exceeding 1 acre in extent, and with farms of 80 acres in close proximity to their residences. The freehold of these farms may be secured generally on the same terms as those upon which agricultural farms not exceeding 160 acres in area may be acquired, with the additional privileges that residence on an allotment in the township is held to be equivalent to residence on the farm, and one-fifth of the required improvements may be made on the allotment.

#### *Unconditional Selection.*

Areas of land are also available for unconditional selection at prices one-third greater than those payable in respect of agricultural selections. The term of lease is twenty years, and the annual rent one-twentieth of the purchasing price, which may not be less than 13s. 4d. per acre. At any time during the currency of the lease the freehold may be acquired. As the term implies, no other conditions than the payment of the

November, 1903, to select out of his mallee allotment a similar area in like manner. The period of residence attached to residential licenses is five years. When the area is first-class land, the purchase money in full for a residential license is £1 per acre, and the license is for a term of six years, at a yearly rent of 1s. per acre; the improvements at the expiration of the license must be of the value of £1 per acre. If all the conditions be complied with, the licensee is entitled, at the expiration of the license, to a lease for fourteen years at the same rent, or to a Crown grant at any time, on paying the difference between the amount paid and £1 per acre. If the applicant prefer, he may obtain a license at a reduced rental of 6d. per acre per annum for the term of six years, with a lease for thirty-four years at 6d. per acre yearly. When the area is second-class land, the purchase money in full is 10s. per acre, and the license is for a term of six years at a yearly rent of 6d. per acre, and the lease for fourteen years at the same rent, or a license may be issued, with conditions varied in these respects, that the rent shall be 3d. per acre yearly for six years, with a subsequent lease for thirty-four years at the same rent. The improvements at the end of the six years must be of the value of 10s. per acre. A non-residential license on first-class land is granted for a term of six years at 1s. per acre per annum, and the lease for a period of fourteen years at the same rent. Improvements to the value of 6s. 8d. per acre must be made in each of the six years. The period of non-residential license on second-class land is six years, at an annual rent of 6d. per acre, and the lease is for fourteen years at the same rent. Improvements to the value of 3s. 4d. an acre must be made during each of the first three years. Except for the purpose of building, fencing, or other improvements, the licensee may not cut or remove any live pine, box, or red gum, on the land.

Perpetual leases of mallee country are issued, in areas not exceeding 1,920 acres, at a yearly rental not to exceed 2d. per acre to 31st December, 1903, and thereafter as the Board may determine. The rent must be paid yearly in advance, and the lessee must destroy any vermin on the land, and within two years have made a complete clearance of such pests, while during the remainder of his lease he must see that the land is kept free from them. Within six months, the lessee must reside on or within 5 miles of the land, and do so for a period of eight months in each of the second, third, fourth, and fifth years. In the event of the lessee cultivating one-fourth of the area within two years, and at least one-half within four years, the residence condition ceases to operate.

#### *Vermin Districts.*

Under the Land Act of 1890, districts which are proclaimed as vermin-infested are, for the purpose of securing the extinction of these animal pests, administered by local committees appointed by the owners, lessees, and occupiers of the lands. In order to secure the erection of vermin-proof wire-fencing, a fencing rate may be levied, and the Minister has power to deduct 5 per cent. of the amount levied in vermin districts

for the purpose of erecting a vermin-proof fence between the mallee country and the mallee border.

#### *Wattle Cultivation.*

During 1890 legislation was enacted having for its object the granting of leases of any unoccupied Crown lands for the cultivation of wattle-trees, for any term not exceeding twenty-one years, at a rent of 2d. per acre per annum for the first seven years, 4d. per acre for the second seven years, and 6d. per acre for the remainder of the term. A lease is not granted for more than 1,000 acres; and the rent is payable half-yearly in advance. The lessee covenants not to assign, sublet, or divide the lease without the consent of the Board of Land and Works; to keep all improvements in repair during each of the first six years following the year after the granting of the lease; to sow or plant wattle-trees or any other approved tannin-producing trees or plants on at least one-fifth of the land leased, and within six years to occupy the whole area in a similar manner. He must within two years enclose a third, within three years two-thirds, and within four years the whole of the land leased; and he is required to keep the fence in good repair, and to destroy all vermin which may be upon the land. The lessee may select out of his lease an agricultural or grazing allotment under license or perpetual lease.

#### *Village Settlements.*

Under the Settlement on Lands Act of 1893 there may be set apart and appropriated for the purposes of village communities any lands not alienated from the Crown, provided they are not auriferous or permanently reserved for any purpose. Such lands are surveyed into allotments of 1 to 20 acres each, according to the quality of the soil and the situation. Subject to certain restrictions, any person of the age of 18 years may obtain a permit to occupy a village community allotment for a period not exceeding three years. The rent is merely nominal, but conditions are laid down with the object of ensuring *bona-fide* occupancy. On the expiration of the permit a lease may be obtained, provided the conditions of the permissive occupancy have been fulfilled. The lease is granted for a period of twenty years. The lessee must pay in advance, every half-year, rent equal to one-fortieth of what is regarded as the price of the allotment, which is to be not less than £1 per acre. Within two years from the date of the lease he must have brought into cultivation not less than one-tenth, and within four years, one-fifth of the land; and within six years, have effected substantial improvements of a permanent character to the value of £1 for every acre leased. He must also keep all improvements in good repair; and he cannot assign, transfer, or sublet the land, or borrow money on the security of his lease without the consent of the Board of Land and Works. He must reside personally on the land, and use it for agriculture, gardening, grazing, or other like purpose. Any person in occupation of an allotment under

## SOUTH AUSTRALIA.

The settlement of the state of South Australia was the outcome of an attempt to put into actual practice one of those remarkable theories which logically seem founded upon apparently solid ground, but which are apt to weaken and give way when subjected to the pressure of hard practical facts. The policy, by which a wealthy colony was to be created in a few years on the edge of a supposed desert continent, was based upon principles enunciated by Edward Gibbon Wakefield, in a pamphlet published in England about the year 1836. The main idea of his scheme of colonisation was the sale of land in the new possession at a high price, and the application of the amount thus realised to the introduction of immigrants, whom the landowners would at once employ to reclaim the virgin forest, and create wealth and abundance where desolation existed. But although Wakefield had fairly calculated upon the results which would follow the action of man if left to himself, the part which Nature might be expected to play was not taken into consideration, and the scheme quickly proved an empty failure and a distressful speculation for the many whom its apparent feasibility had deluded into investing their means in the lands of the new colony. Had not the discovery of great mineral resources occurred at an opportune time, the exodus into the eastern colonies of the immigrants imported or attracted to South Australia would have emptied the province of its population, and considerably retarded the progress of a territory not inferior in natural resources to other portions of the Australian continent.

Steps were soon taken to modify the Wakefield system, but it was only in 1872 that an Act was passed more in conformity with the legislation of the neighbouring states, and giving to the poorer classes of the population an opportunity of settling upon the lands of the Crown under fair conditions. The Lands Act of 1872, adapted as it was to the needs of the time, gave way to other measures, and the regulations now in force are those of the Crown Lands Act of 1888, as amended in 1889, 1890, 1893, 1894, 1895, 1896, 1897, 1898, and 1899, the whole being consolidated as the "Crown Lands Act, 1903," assented to on the 30th October, 1903.

For the purposes of administration the state is divided into land districts, and while the principal control is vested in a Commissioner, a movable Land Board, consisting of four civil servants, who hold office for a period of twelve months and are eligible for reappointment, deals directly with specific matters, and in others may do so subject to the approval of the Commissioner.

*General Provisions.*

The law as it now stands gives power to the Government to alienate Crown lands in the following manner:—(1) By auction, town lands, suburban lands, any single section surrounded by alienated land and

any block not exceeding 100 acres required for the establishment of any industry, trade, or business ; (2) by perpetual lease ; (3) by lease for grazing and cultivation purposes or grazing purposes only ; for the purpose of working guano and other deposits ; by lease of lands resumed for water ; and for such other miscellaneous leases as are set out in section 80 of the consolidating statute.

### *Perpetual Leases.*

Crown lands, within any hundred, which have been previously surveyed or the boundaries thereof delineated on the public maps, are available for perpetual lease. The area and rent are determined by the Commissioner on the recommendation of the Land Board, and upon notification in the *Government Gazette*, application therefor, accompanied by 30 per cent. of the first year's rent, may be made to the Commissioner. All applications for the same land received up to and on the date named for receiving the same are treated as simultaneous, and are decided by lot by the chairman of the Board. Preference is given to the applicant who shall agree to take the block on condition of personal residence, involving continuous residence on the land for nine months in each year. A perpetual lease can only be granted for lands the unimproved value of which shall not exceed £5,000, or in such fashion that the lessee would hold lands under any tenure except pastoral lease, the aggregate unimproved value whereof would, in the opinion of the Board, not exceed £5,000. The exceptions are where the land to be included as a perpetual lease is, in the opinion of the Commissioner, suitable only for pastoral purposes, the carrying capacity thereof unimproved, and of all other lands held by the lessee under any tenure altogether not exceeding 5,000 sheep, while if the land is outside Goyder's line of rainfall, the limitation is increased to a carrying capacity of 10,000 sheep. The lessee is required to execute and deliver the lease within twenty-eight days, and pay the balance of the first year's rent and the prescribed fees. The land is vested in the lessee in perpetuity, and the rent is re-determined for each term of fourteen years, and in connection therewith the value of the improvements made by the lessee is not considered. The lessee is required to enclose the land with a cattle-proof fence before the end of the fifth year of the lease, and keep all crown improvements in good repair, and to insure and keep insured to the full insurable value all buildings the property of the Crown upon the land in the joint names of the Commissioner and lessee. He is further required to destroy and keep the land free from vermin during the lease. Every lease contains a reservation to the Crown of all minerals and mineral oils in or upon the land, and the land may be resumed by the Crown for mining or for any public work or purpose, full compensation being made to the lessee for his loss. Municipal and District Councils may apply for lands under perpetual lease.

*Leases with Right of Purchase.*

No lands may be leased unless they have been surveyed, or the boundaries thereof delineated on the public maps. No lease with right of purchase can be granted of lands of such value that the purchase money will exceed £5,000 unimproved value, or so that the lessee would hold lands under any tenure except pastoral lease, the aggregate unimproved value whereof would, in the opinion of the Board, not exceed £5,000, except where the land to be included is, in the opinion of the Commissioner, suitable only for pastoral purpose, the carrying capacity thereof unimproved, and of all other lands held by the lessee under any tenure altogether not to exceed 5,000 sheep. If the land is outside Goyder's line of rainfall, the limitation is increased to a carrying capacity of 10,000 sheep. The Commissioner, on the recommendation of the Land Board, determines the area of blocks and the price and annual rent at which each block may be taken up on lease with right of purchase. Applications must be made in writing to the Commissioner, and must cover a deposit equal to the first half-yearly instalment of the purchase money of the land and improvements which it is desired to take up.

All applications for the same land received up to and on the date named for receiving the same are treated as simultaneous, and are decided by lot by the chairman of the Board. Preference is given to the applicant who shall agree to take the block on condition of personal residence, involving continuous residence on the land for nine months in each year.

The purchaser covenants to purchase his block at the price fixed by the Land Board and to pay the purchase money and interest for land and improvements, if any, at not less than the rate of 2 per cent. per annum by sixty equal half-yearly instalments paid in advance. Having complied with the terms of the agreement, the purchaser has the option of completing the purchase of the block at any time after the expiration of six years on paying all principal due and all interest due up to the time of purchase. The rent of any renewed lease is fixed by the Land Board by revaluation at least twelve months before the expiration of the original lease, and the renewed lease contains a right of purchase exercisable at any time during the term of the renewed lease. In the determination of the purchase money and rent for a renewed lease, the value of improvements effected is not considered by the Land Board.

*Sale of Lands.*

Town lands, suburban lands, and any single section of Crown land which may be surrounded by lands sold or contracted to be sold, and any section or block of land belonging to or vested in the Crown, not exceeding 100 acres in area, which may be required for the establishment of any industry, trade, or business, or any purpose approved by the Governor, and any Crown land within hundreds which has been

offered for perpetual lease and not taken up within two years from the date first open, may be sold at auction for cash. The upset price of any land offered at auction is determined by the Commissioner, and 20 per cent. must be deposited at the time of sale and the balance within one month. The purchase money in respect of these sales is paid into a fund primarily applicable to the payment of such portion of the public liabilities as shall be specially charged thereon.

#### *Grazing and Cultivation Leases.*

Every miscellaneous lease under any of the Crown Lands Acts for grazing and cultivation purposes, or for grazing purposes only, is held to have been lawfully granted; and the power of resumption, if required for any purpose of public utility, is reserved to the Crown. Subject to the approval of the Commissioner, the lessee of any miscellaneous lease for grazing and cultivation purposes, existing at 30th October, 1903, may cultivate the whole of the land comprised within his lease without rendering it liable to forfeiture.

#### *Leases for Guano and other Deposits.*

Leases, on such terms and conditions as the Governor may prescribe, may be granted to any *bona fide* discoverer of any guano or other valuable substance or deposit, not being a metal or metalliferous ore, or coal, or petroleum, or other mineral oil, but the aggregate area held by any one person must not exceed 640 acres.

#### *Exchange of Lands.*

Crown lands may be exchanged for any other lands, notwithstanding the existence of any lease that may have been issued in connection with the former. The Crown lands proposed to be given in exchange may be granted in fee simple or under perpetual lease.

#### *Village Settlements.*

Notwithstanding the repeal of Part VII of the "Crown Lands Amendment Act, 1893," and sections 2 to 11 of "The Village Settlements and Reduction of Rents Amendment Act, 1895," and "The Village Settlements Act, 1901," the constitution and registration of the Lyrup, Pyap, Moorook, Kingston, Waikere and Rameo Village Associations remain confirmed, and each of such associations continues a body corporate, with the right and liability to sue and be sued, while the "Companies Act, 1892," does not apply to them.

The Commissioner is directed to set apart out of the reserved lands such land as he shall consider fit for (a) horticultural purposes, to be termed horticultural land; (b) agricultural purposes, to be designated commonage land; and (c) land whereon any irrigation works are situated. Horticultural land is to be subdivided into blocks of as nearly as practicable equal unimproved value and of about 10 acres in extent, and commonage lands into blocks of such area as the Commissioner

may deem desirable, and the lands set apart in each case form the district of the association. Upon subdivision, separate valuations are to be made of the irrigation works in each district, the improvements (if any) on each of the horticultural and commonage blocks, and all the personal estate belonging to each association. Where the Commissioner and an association do not forthwith, after subdivision, agree as to the valuation, the amount thereof is determined by arbitration, and no improvement is to be valued at a sum in excess of the value thereof considered solely in connection with its worth to the association at the time of valuation, and the amount of such valuations in respect of the district of each association, determined as indicated, is deemed to be the total indebtedness of the association to the Commissioner. Power is given to the Governor to determine the occupancy by any person or association of the reserved land in a district where the valuation is agreed to or fixed, and the land reverts to the Crown free from encumbrance. The Commissioner may forthwith lease such of the horticultural blocks within an area that has reverted to the Crown to individual members of the association on perpetual lease, or to a person not a member of the association, and thereupon such person becomes a member of the association. No person can hold more than two blocks, and each lessee is to hold his block for his individual use and enjoyment. Commonage lands can only be leased to and held by the association within whose district the lands are situated and on perpetual lease. The annual rent in respect of any lease, whether of horticultural blocks or commonage lands, is fixed by the Land Board, and commences at a date appointed by the Commissioner. The value of improvements on each horticultural block and interest thereon at the rate of  $4\frac{1}{2}$  per cent. per annum is a first charge upon the block, repayable by forty-two annual instalments. The value of irrigation works and of improvements on commonage lands and interest at the rate of  $4\frac{1}{2}$  per cent. per annum is a charge upon the property of the association, repayable in forty-two annual instalments, and in the event of an association defaulting the members are liable for their proportion of the unpaid balance. Subject to appeal, power is vested in the Commissioner to expel from an association any member; to control and direct the expenditure of any moneys by associations; to call upon a trustee to resign when the welfare of an association requires such action; to require an association to increase the number of its members; to make, amend, and repeal rules for the management of associations, for the regulation, maintenance, and control of irrigation works, for the supply of water for irrigation and other purposes, and for the payment of all expenses incidental thereto. No further advances or allowances are to be made to any of the associations. The commonage lands leased to each association are under the control of the association, subject to the direction of the Commissioner, and are to be worked for the common good and benefit of the members upon the principles of co-operation and equitable division. Each member of an association is required to



contribute such labour, or such sum in cash considered equivalent to such labour, as the Commissioner shall require towards the maintenance and working of the irrigation works and the care and cultivation of the commonage lands of the association. The association is required to prepare, once in every year, an account of the working of the commonage land, showing all expenditure and income in connection therewith, including the amount of the assessed value of the member's labour; and after making provision for rent, working expenses, depreciation, renewal of plant, tools, live stock, &c., the surplus (if any), after deducting 25 per cent. therefrom for a sinking fund for renewal of plant, may be divided among the then members in proportion to the amount of their respective credits in the books of the association for earnings.

During the year 1894, village settlements were established at Gillen, Holder, Kingston, Lyrup, Moorook, Mount Remarkable, Murtho, Nangkita, New Era, New Residence, Pyap, Rameo, and Waikere; but seven of these were abandoned at various periods between 1896 and 1903, and only Kingston, Lyrup, Moorook, Pyap, Rameo, and Waikere remain in existence at the present date. The settlers on settlements at present in operation number 84, and the total population 390. Since the establishment of this principle of settlement a sum of £102,116 has been advanced by way of loan to settlers, while the value of improvements effected is £41,869.

#### *Homestead Blocks.*

The Commissioner may cause any Crown lands or lands reserved for the use of the aboriginal inhabitants of the state, other than those at Point McLeay and Point Pearce, to be surveyed and offered as homestead blocks on perpetual lease, or lease with a right of purchase, and may, subject to the approval of Parliament, purchase, exchange, or otherwise acquire land suitable for homestead blocks, and lease it in a similar manner. Homestead blocks may be held in any area, provided the unimproved value of the fee-simple of the area does not exceed £100. The lessee or purchaser must personally reside on the land for nine months in every year of the term. On the application of the lessee, the Commissioner may endorse the lease or agreement with the words "Protected homestead block," and such endorsement has the effect that no subsequent encumbrance by the blockholder of the land or his interest therein has any validity; that the land is not liable to be seized or taken in execution for debt under the process of any court; or to vest in the trustee of his estate in the event of the owner's insolvency.

#### THE NORTHERN TERRITORY.

The Northern Territory of South Australia includes the whole of the lands situated to the north of the 26th degree of south latitude, bounded by Queensland on the east, Western Australia on the west, and the Ocean on the north. This portion of the Continent is under the administration of a Resident, appointed by the Government of South

Australia; and the alienation and occupation of lands within the Territory are conducted under regulations enacted by the South Australian Legislature, in accordance with the Northern Territory Crown Lands Consolidation Act of 1882.

It is provided that lands may be purchased for cash, without conditions, in blocks not exceeding 1,280 acres, for 12s. 6d. per acre. They may also be bought under the deferred payment system to the same maximum area, and at the same price, payable in ten years, together with an annual rent of 6d. per acre.

Leases for pastoral occupation may be issued for a term not exceeding twenty-five years, for blocks up to 400 square miles, the annual rental for the first seven years being 6d. per square mile, while 2s. 6d. per square mile is charged during the remainder of the term.

In order to encourage the cultivation of tropical produce, such as rice, sugar, coffee, tea, indigo, cotton, tobacco, etc., special provisions have been enacted. Blocks of 320 acres to 1,280 acres may be let for such purposes at the rate of 6d. per acre per annum. If, on the expiration of five years, the lessee can prove that he had cultivated one-fifth of his area by the end of the second year, and one-half by the end of the fifth year, he is relieved from all further payment of rent, and the amount already so paid is credited to him towards the purchase of the land in fee.

#### WESTERN AUSTRALIA.

The first regulations referring to land settlement in Western Australia were issued by the Colonial Office in 1829, at the time when Captain James Stirling was appointed Civil Superintendent of the Swan River settlement. The first special grants were made in favour of Captain Stirling himself for an area of 100,000 acres near Geographe Bay; and of Mr. Thomas Peel, for 250,000 acres on the southern bank of the Swan River and across the Channing to Cockburn Bay—Mr. Peel covenanting to introduce at his own cost 400 immigrants into the state by a certain date. Persons proceeding to the settlement at their own cost, in parties in which the numbers were in the proportion of five females to every six male settlers, received grants in proportion to the amount of capital introduced, at the rate of 40 acres for every sum of £3. Capitalists were granted land at the rate of 200 acres for every labouring settler introduced at their expense, but the grants were subject to cancellation if the land was not brought into cultivation or reclaimed within twenty-one years. These regulations were amended by others of a similar nature, issued on the 20th July, 1830. In 1832, however, the mode of disposing of Crown lands by sale came into force, the regulations issued in that year assimilating the system of settlement to that in force in the colonies of New South Wales and Van Diemen's Land. Other alterations were made from time to time, until in October, 1898, an Act amending and consolidating the laws relating to the sale, occupation, and management of Crown lands received assent.

For the purposes of administration, the state is divided into six divisions, namely, the South-west division, the Western division, the North-west division, the Kimberley division, the Eucla division, and the Eastern division. Land may be acquired in the following manner:—

(1) By auction of town and suburban lands in all divisions, at an upset price to be determined by the Governor ; (2) by conditional purchase—  
 (a) by deferred payments with residence within agricultural areas in all divisions ; (b) by deferred payments with residence on any land other than agricultural in the south-west division ; (c) by deferred payments with residence on any land within 40 miles of a railway within the eastern and Eucla divisions, at a price of not less than 10s. per acre, payable in twenty yearly instalments, and in areas not exceeding 1,000 acres nor less than 100 acres ; (d) by deferred payments without residence within an agricultural area, also over any other land within the south-west division, or within 40 miles of a railway within the eastern and Eucla divisions, which may from time to time be declared open to selection ; (e) by direct payment without residence within agricultural areas of not less than 100 acres nor more than 1,000 acres, at a price of not less than 10s. per acre, 10 per cent. of which is to be paid on application and the balance within twelve months of date of the commencement of the license, by four equal quarterly instalments ; (f) by direct payment without residence, for gardens, in all divisions, of areas of not less than 5 nor more than 50 acres, at not less than 20s. per acre ; (g) poison lands ; (h) working-men's blocks ; (i) free home-  
 stead farms ; (j) of grazing lands, second and third class lands.

#### *Auction Lands.*

Town and suburban lands in all divisions may be sold by public auction, at an upset price to be determined by the Governor-in-Council. Any person may apply to the Commissioner to put up for sale by auction any town or suburban lands already surveyed, on depositing 10 per cent. of the upset price, which is returned if such person does not become the purchaser. Should the purchaser not be the applicant, he must pay 10 per cent. on the fall of the hammer, and the balance of the purchase money, in the case of town lots, by two equal instalments at the end of three and six months ; in the case of suburban lots, by four equal quarterly instalments, subject to alteration by regulation, the Crown grant and registration fees being payable with the last instalment. All suburban land is sold subject to the condition that each lot shall, within two years from the date of sale, be enclosed with a fence of a prescribed description.

#### *Conditional Purchase.*

In all the divisions, agricultural areas of not less than 2,000 acres are set apart by the Governor-in-Council. The maximum quantity of land which may be held by any one person is 1,000 acres, and the minimum 100 acres. The price is fixed at 10s. an acre, payable in

twenty yearly instalments of 6d. an acre, or sooner, in the occupier's option. Upon the approval of an application, a lease is granted for twenty years. Within six months the lessee must take up his residence on some portion of the land; and make it his usual home without any other habitual residence, during, at least, six months in each year for the first five years. The lessee must within two years from the date of the commencement of his lease fence at least one-tenth of the area, and within five years enclose the whole of the land, and must, within ten years, expend upon the land, upon prescribed improvements, in addition to the exterior fencing, an amount equal to the full purchase money. After the lease has expired, provided that the fence is in good order, that the improvements have been maintained, and that the full purchase money has been paid, a Crown grant is given.

Land may be purchased outside agricultural areas in the south-west division, also within 40 miles of a railway within the eastern and Eucla divisions, by free selection on deferred payments with residence and otherwise subject to all the conditions required within agricultural areas as previously stated.

Under the fourth mode of purchase, the applicant is subject to all the conditions, except that of residence, imposed under the first mode, but he has to expend twice the amount on improvements in lieu of residence.

By the fifth mode, land of a minimum extent of 100 acres and a maximum of 1,000 acres, within an agricultural area, and not more than 5,000 acres outside an agricultural area, may be applied for at a price (not less than 10s. per acre) fixed by the Governor-in-Council. Within three years the land must be enclosed, and within seven years a sum equal to 5s. per acre must be spent on improvements, in addition to the exterior fencing.

For garden purposes, small areas of not less than 5 acres nor more than 50 acres (except in special cases) may be purchased within all divisions at 20s. per acre on condition that within three years the land shall be fenced in, and one-tenth of the area planted with vines or fruit-trees or vegetables.

Lands infested with poisonous indigenous plants, so that sheep or cattle cannot be depastured thereon, are available for conditional purchase, in areas of not more than 10,000 acres nor less than 3,000 acres, at a price not less than 1s. per acre, payable half-yearly, at the rate of one-thirtieth of the total purchase money per annum. Upon approval of the application, a lease for thirty years is granted, subject to the conditions that the lessee shall, within two years, fence one-tenth, and within five years enclose the whole area, with a fence of the prescribed description, and, during the term of his lease, eradicate the whole of the poisonous indigenous plants. At the expiration of the lease, or at any time during the currency of the same, provided all the conditions have been complied with, the fencing properly maintained, and the full balance of the purchase money and fees paid, and provided that the land has been rendered safe for depasturing cattle and sheep at all seasons,

and has continued so for a term of two years, a Crown grant of the land issues. A pastoral lessee has the first right to select land within his lease under these terms.

Every person who does not own land within the state in freehold, or under special occupation, or conditional purchase, or a homestead farm, who is the head of a family, or a male who has attained the age of 18 years, is entitled to obtain a lease of lands set apart for working-men's blocks. The maximum area that may be selected by one person is, if within a gold-field,  $\frac{1}{2}$  an acre, or 5 acres elsewhere. The price of the land is not less than £1 per acre, payable half-yearly, at the rate of one-tenth of the total purchase money per annum. The application is to be accompanied by a deposit of half a year's rent, and, on approval, a lease for ten years issues. Within three months from the date of the lease, the lessee must take personal possession and reside upon it during at least nine months in each of the first five years of the lease; possession and residence may, however, be performed by the lessee's wife or a member of his family. Within three years the land must be fenced and within five years an amount equal to double the full purchase money, in addition to his house and exterior fencing, must be expended on the land in prescribed improvements. At the expiration of the lease, or at any time after five years from commencement of lease, provided all the conditions have been complied with, and the fencing and improvements maintained, and the full purchase money and fees paid, a Crown grant issues.

Any person who does not already own more than 100 acres of land within the state, in freehold or conditional purchase, and being the head of a family, or a male who has attained the age of 18 years, may apply for a free homestead farm of not more than 160 acres, from lands declared open for such selection within the south-west division, and within 40 miles of a railway in the eastern or Eucla division, not being within a gold-field. The application is to be accompanied by a statutory declaration and a fee of £1, and, upon approval, an occupation certificate authorising the applicant to enter upon and take possession of the land for the term of seven years is issued. Within six months from the date of the occupation certificate, the selector must take personal possession of the land, and reside upon it for at least six months in each year for the first five years of the term. Within two years from the date of the certificate, a habitable house must be erected of not less than £30 in value, or the selector must expend £30 in clearing, or clearing and cropping, or prepare and plant 2 acres of orchard and vineyard. Within five years, one-fourth of the land must be fenced and one-eighth cleared and cropped. Within seven years, the whole must be enclosed, and at least one-fourth cleared and cropped. At the expiration of seven years, provided the conditions have been complied with, a Crown grant issues on payment of the usual fees.

Leases for thirty years of second and third class lands are granted, called grazing leases, but which are really another form of conditional

purchase. The maximum area allowed to be taken up is 3,000 acres of second-class, and 5,000 acres of third-class, land, and the minimum in both cases is 1,000 acres; and if one person selects two leases in different classes, the total quantity must not exceed 4,000 acres. The price of second class land is not less than 6s. 3d. per acre, and of third class land 3s. 9d. per acre, payable half-yearly at the rate of 2½d. and 1½d. per acre respectively. The lessee is required to pay one-half the cost of survey in ten half-yearly instalments. Within six months from the date of the commencement of the lease, the lessee must take possession of the land and reside upon it during at least six months of the first year, and nine months in each year of the next four years. Residence may, however, be complied with by the lessee's agent or servant. Within two years from the date of the commencement of the lease, the lessee is required to fence at least one-tenth of the area contained therein, and within five years to fence the whole of the land, and within fifteen years to expend upon the land in prescribed improvements an amount equal to the full purchase money in addition to the exterior fencing.

#### *Pastoral Lands.*

Pastoral lands are granted on lease, which gives no right to the soil or to the timber, except for fencing and other improvements on the land leased, and the lands may be reserved, sold, or otherwise disposed of by the Crown during the term. The following are the terms of pastoral leases in the several divisions; all leases expire on the 31st December, 1928, and the rental named is for every 1,000 acres:—South-west division.—In blocks of not less than 3,000 acres, at 20s. per annum for each 1,000 acres or part of 1,000 acres; if, however, the land is in that part of the division situated eastward of a line from the mouth of the Fitzgerald River in the direction of Mount Stirling, the rental is 10s. per annum for each 1,000 acres or part thereof. Western and north-west division.—In blocks of not less than 20,000 acres, at 10s. per annum for each 1,000 acres or part thereof. Eucla division.—In blocks of not less than 20,000 acres, at 5s. per annum for each 1,000 acres or part thereof. Eastern division.—In blocks of not less than 20,000 acres, at the following rental:—For each 1,000 acres or part thereof, 2s. 6d. for each of the first seven years, and 5s. for each of the remaining years of the lease. Kimberley division.—In blocks of not less than 50,000 acres when on a frontage, nor less than 20,000 acres when no part of the boundary is on a frontage, at a rental of 10s. per annum for each 1,000 acres or part thereof. Any lessee in the Kimberley Division, or in that part of the south-west division situated to the eastward of a line from the mouth of the Fitzgerald River in the direction of Mount Stirling may obtain a reduction of one-half the rent due for the remaining years of his lease, who at any time during its term shall have in his possession within the division ten head of sheep or one head of large stock for each 1,000 acres leased. Except in the south-western division, a penalty of double rental for the

remaining portion of the lease is imposed should the lessee within seven years have failed to comply with the stocking clause.

Any Crown land within a gold-field or mining district, not required to be reserved for any public purpose, may be leased for pastoral purposes in blocks of not less than 2,000 acres at a rental of 10s. per 1,000 acres. In the event of the land, or any portion of it, being taken for an agricultural area, the lessee is only entitled to three months notice.

#### *Miners' Homestead Leases.*

Any miner resident on a gold-field, being not less than 18 years of age, may apply for a miner's homestead lease of any Crown lands within the limits of a gold-field set apart for the purpose. The area which may be taken up is as follows:—Within 2 miles of the nearest boundary of any town site or suburban area, 20 acres; and beyond 2 miles from such boundary, 500 acres; the aggregate area applied for by any one person within the same gold-field shall in no case exceed 500 acres. Upon the approval and notification of the lease in the *Government Gazette*, the applicant is entitled to enter upon and occupy the land; but if at the expiration of six months he has not used or occupied the land, either by himself residing upon it, or by enclosing one-tenth part of it with a substantial fence, or by substantial improvements upon the land, or by carrying on some manufacture upon or in connection with the land, he is deemed to have abandoned it. The lessee is required, within three years from the date of survey of the land, to fence the whole of it with a substantial fence, not being a bush fence, sufficient to resist the trespass of great stock; and within five years from the said date to expend upon the land in prescribed improvements an amount equal to 10s. per acre. If the area does not exceed 20 acres, the annual rent is at the rate of 2s. for every acre or part of an acre; if the area exceeds 20 acres, the annual rent is at the rate of 6d. per acre or part of an acre, payable during the first twenty years of the lease, and thereafter an annual rent of 1s. The minimum annual rent for the first twenty years to be reserved by any lease shall not be less than 10s.

#### TASMANIA.

In the earlier period of the occupation of Tasmania, from 1804 to 1825, the island was administered as a part of New South Wales, and its settlement was subject to the regulations affecting the disposal of the Crown domain in that colony. After its constitution under a separate administration, the regulations issued from the Colonial Office for the settlement of the Crown lands in the mother colony were made applicable also to Tasmania. New measures were introduced after self-government had been granted to the province, but they became so complicated and cumbersome that in 1890 the necessity was felt of passing an Act consolidating into one comprehensive and general measure the twelve Acts then in force. Amendments of the 1890 Act have, however, been made

in 1895 and 1900, and the various statutes were further amended and consolidated by the Crown Lands Act, 1903, which came into operation on the 1st January, 1904.

The business of the Lands and Survey Departments is now transacted by virtue of the Crown Lands Act of 1903, under which, for the convenience of survey operations, the island is divided into fifteen districts. Lands of the Crown are divided into two classes—town lands and rural lands, the latter being further subdivided into first-class agricultural lands, second-class and third-class lands. Lands which are known to be auriferous, or to contain other minerals, and such lands as may be necessary for the preservation and growth of timbers, are dealt with under separate sections; and the Governor-in-Council is empowered to reserve such lands as he may think fit for a variety of public purposes.

Land may be acquired in the following manner:—(1) By selection of first-class agricultural rural lands of not less than 15 nor more than 200 acres, at an upset price of £1 per acre, with one-third added for credit; (2) by selection of second-class rural lands of not less than 30 nor more than 500 acres at an upset price of 10s. per acre; by selection of third-class rural lands of not less than 60 nor more than 1,000 acres at an upset price of 5s. per acre; by selection of lands within mining areas—if situated within 1 mile of a town reserve, of an area of not less than 1 nor more than 10 acres; and if at a greater distance than 1 mile, of not less than 10 nor more than 100 acres—the upset price of first-class lands being not less than £1 per acre, payable in fourteen years, and that for second-class lands not less than 10s. per acre, payable in ten years; (3) by auction—(a) of town lands at the upset price notified in the *Gazette*, (b) of first-class agricultural land at an upset price of £1 per acre in lots not exceeding 200 acres, (c) of second-class lands at an upset price of 10s. per acre in lots of not less than 30 nor more than 500 acres, (d) of third-class rural land at an upset price of not less than 5s. per acre, in lots of not less than 60 acres nor more than 1,000 acres; (4) as settlement areas by any persons, styled “the purchasing body,” in areas not exceeding 1,000 acres.

In the rural division any person of the age of 18 years may select by private contract at the price and upon the terms set forth hereunder:—

One lot of rural lands not exceeding 200 acres nor less than 15 acres.	£	s.	d.
100 acres at 20s. ....	100	0	0
Add $\frac{1}{3}$ for credit .....	33	6	8
<b>Payable as follows:—</b>	£	s.	d.
Cash at time of purchase .....	3	6	8
First year .....	5	0	0
Second year .....	5	0	0
Third year .....	10	0	0
And for every one of the eleven successive years to the fourteenth year inclusive at the rate of £10 per annum .....	110	0	0
	<hr/>	<hr/>	<hr/>
		133	6 8



The same proportions are allowed for any greater or smaller area than 100 acres; but credit is not given for any sum less than £15. Additional selections may be taken up, provided the total area held by one selector does not exceed 200 acres. Selection by agent is not allowed.

*Sales of Land on Credit.*

Any person of the full age of 18 years, who has not purchased under the Crown Lands Acts, may select and purchase one lot of first-class agricultural land of not more than 200 acres nor less than 15 acres. The purchase money, which is calculated on the upset price of £1 per acre, together with the survey fee, and with one-third of the whole added for credit, is payable in fourteen annual instalments. A condition of purchase is that the selector shall expend a sum equal to £1 per acre in effecting substantial improvements (other than buildings) on the land within a period of eight years, and reside habitually thereon for the term of at least five years, before a grant deed is issued. The condition of residence may be carried out by some member of the selector's family, or by some one employed by him on his behalf. Where a purchaser is unable to pay the instalments as they become due, they may be deferred for any period up to five years on payment of interest at the rate of 5 per cent., if all other conditions have been fulfilled; and the selector may take possession of his land as soon as his application has been approved by the Commissioner and the survey fee paid.

The conditions in connection with the credit system are as follow:—The purchaser must commence to make improvements on the expiration of one year from the date of contract, and during eight consecutive years must expend not less than 2s. 6d. per acre per annum, under penalty of forfeiture. Any surplus over 2s. 6d. per acre spent in any year may be set against a deficiency in another year, so that £1 per acre shall be spent in the course of the eight years. In the event of improvements to the full amount being made before the expiration of the eight years, the purchaser may pay off any balance due, discount being allowed. Payment of instalments may in certain cases be postponed, but under such circumstances interest must be paid at the rate of 5 per cent. per annum. In certain cases the time for making the improvements may be extended for two years. Should an instalment not be paid within sixty days after becoming due, the land may be put up to auction, the defaulter having the privilege of redeeming his land up to the time of sale by payment of the amount due, with interest and costs. If land sold at auction by reason of default should realise more than the upset price, the excess is handed to the defaulter. Land purchased on credit is not alienable until paid for, but transfers are allowed. For five years after alienation land is liable to be resumed for mining purposes, compensation being paid to the occupier. All grant-deeds contain a reservation by the Crown of the right to mine for minerals.

Second-class lands may be sold by auction at the upset price of 10s. per acre in lots of 30 to 500 acres, the latter being the maximum quantity which any one purchaser can hold under the Act on credit. One-half of the purchase money is to be expended in making roads.

The land must be occupied by the purchaser, or some member of his family, or by someone employed by him on his behalf, by habitually residing thereon for a period of at least five years before the grant is issued. Improvements, other than buildings, to the value of 5s. per acre are to be effected by the purchaser, beginning at the expiration of one year from the date of contract, and to be continued for the next five years at the rate of 1s. per acre per annum, the deed of grant issuing only when the amount of 5s. per acre has been expended. Non-fulfilment of the conditions entails forfeiture. Where the purchaser has fulfilled the conditions, but is unable to complete the purchase of the whole, a grant may issue for so much as has been paid for upon the cost of survey being defrayed. On approval of the application by the Commissioner, and payment of the survey fee, the selector may at once enter into possession.

Third-class lands may be sold by auction at an upset price of not less than 5s. per acre, and in lots of not less than 60 acres nor more than 1,000 acres. The land must be occupied by the purchaser or some member of his family, or by someone employed by him on his behalf, by habitually residing thereon for a period of at least five years before the grant is issued. Within one year from the sale of the land, the purchaser must begin to effect substantial improvements other than buildings on the land, and continue in each year during the five consecutive years thereafter to effect such substantial improvements to the value of 1s. for every acre of land so purchased.

Rural lands not alienated and not exempt from sale may be sold by auction. Town lands are sold only in this way. Ten shillings per acre is the lowest upset price, and agricultural lots must not exceed 320 acres. Lands unsold by auction may be disposed of by contract. No private lands may be sold by private contract within 5 miles of Hobart or Launceston.

#### *Mining Areas.*

Mining areas may be proclaimed, within which land may be selected or sold by auction, in lots varying with the situation—from 1 to 10 acres if within a mile from a town, and up to 100 acres if at a greater distance. In such cases residence for three years is required, and in default the land is forfeited to the Crown. Occupation licenses are granted to holders of miners' rights or residence licenses for cultivation or pasture within areas withdrawn from the operation of the Crown Lands Act, in lots of not more than 20 acres, for a period of two years at 5s. per acre, on terms prescribed by regulation, and an area not exceeding  $\frac{1}{4}$  of an acre may be sold by auction, the person in occupation having a preferential

right of private purchase at the upset price fixed by the Land Commissioner. A deposit of one-sixth of the purchase money must be made on the approval of the sale, the balance to be paid in eleven equal monthly instalments.

Land selected or bought within a mining area is open to any person in search of gold or other mineral, after notice has been given to the owner or occupier, to whom compensation must be made for damage done. Persons who occupy land in a mining town, under a business license, and who have made improvements to the value of £50, may purchase one quarter of an acre at not less than £10 nor more than £50, exclusive of the value of improvements and cost of survey and deed fee.

Residence licenses may be issued to mining associations for a period of 21 years at 10s. for each year of the term. The same party may hold two licenses if the areas are 5 miles apart.

#### *Grazing Leases.*

Grazing leases of unoccupied country may be offered at auction, but such runs are liable at any time to be sold or licensed, or occupied for other than pastoral purposes. The rent is fixed by the Commissioner, and the run is put up to auction, the highest bidder receiving a lease for fourteen years. The lessee may cultivate such portion of the land as is necessary for the use of his family and establishment, but not for sale or barter of produce. Should any portion of the run be sold or otherwise disposed of, a corresponding reduction may be made in the rent, which is payable half-yearly in advance. A lease is determinable should the rent not be paid within one month of becoming due. In the event of the land being required for sale or any public purpose, six months' notice must be given to the lessee, who receives compensation for permanent improvements. Leases for not more than fourteen years may be granted for various public purposes, such as the erection of wharfs, docks, etc. Portions of a Crown reserve may also be leased for thirty years for manufacturing purposes.

#### NEW ZEALAND.

The first settlements in New Zealand were founded upon land obtained from the various native tribes, and the task of distinguishing between the few *bona-fide* and the numerous bogus claims to the possession of land thus acquired was the first difficulty which confronted Captain Hobson when, in 1840, he assumed the government of the colony. Trading in land with the natives had, from 1815 to 1840, attained such proportions that the claims to be adjudicated upon covered 45,000,000 acres—the New Zealand Company, of which Mr. Edward Gibbon Wakefield, of South Australian fame, was the managing director, claiming an estate of no less than 20,000,000 acres in area. In the year 1840, the Legislature of New South Wales passed

a Bill empowering the Governor of that state to appoint a Commissioner to examine and report upon all claims to grants of land in New Zealand—all titles, except those allowed by Her Majesty, being declared null and void. This Bill, before receiving the Royal assent, was superseded by an Act of the local Council, passed in 1841, under which the remaining claims were settled, and new regulations were adopted for the future disposal of the Crown lands. When, later on, the colony became divided into independent provinces, each district had its own regulations, but in 1858 an Act was passed by the General Assembly embodying all the regulations under which land could be alienated or demised in the various provinces of the colony. This Act was repealed in 1876, and the enactments of 1885, 1887, and 1888 which followed have been superseded by the Lands Act of 1892 and its Amending Acts of 1893, 1895, 1896, 1897, and 1899, under which the Crown lands are now administered. For convenience the colony is divided into ten land districts, each being under the direction of a local Commissioner and a Land Board.

#### *Classification of Lands.*

Crown lands are divided into three classes:—1. Town and village lands, the upset prices of which are respectively not less than £20 and £3 per acre: such lands are sold by auction. 2. Suburban lands, being lands in the vicinity of any town lands, the upset price of which may not be less than £2 per acre; these lands are also sold by auction. 3. Rural lands, being lands not reserved for towns and villages, classified into first and second class lands, which may be disposed of at not less than £1 per acre for first-class, and 5s. an acre for second-class lands; such lands may be either sold by auction after survey, if of special value, as those covered with valuable timber, etc., or be declared open for application as hereafter described. Pastoral lands are included within the term "rural lands," and are disposed of by lease. No person can select more than 640 acres of first-class or 2,000 acres of second-class land, inclusive of any land already held; but this proviso does not apply to pastoral land.

#### *Mode of Alienation.*

Crown lands may be acquired as follows:—(1) At auction, after survey, in which case one-fifth of the price must be paid down at the time of sale, and the balance, with the Crown grant fee, within thirty days, and (2) by application, after the lands have been notified as open to selection, in which case the applicant must fill up a form and make the declaration and deposit required by the particular system under which he wishes to select. All applications, whether for surveyed or unsurveyed lands, are deemed to be simultaneous if made on the same day, and, if there be more than one applicant for the same land, the right of selection is determined by ballot.

*The Optional System of Selection.*

After lands have been notified as open under the optional system, they may be obtained on any of the three following tenures :—(a) Freehold, (b) occupation with the right of purchase, (c) lease in perpetuity.

*(a) Freehold.*

If the land is surveyed, one-fifth of the price is payable at the time of application, and the balance within thirty days ; or if the land is unsurveyed, the survey fee, which goes towards the purchase of the land, is deposited when the application is agreed to, and the balance within thirty days of notice that survey is completed. Freehold-tenure lands must be improved within seven years to an amount of £1 an acre for first-class lands, and 10s. an acre for second-class land. A certificate of occupation issues to the purchaser on the final payment being made, and is exchanged for a Crown grant so soon as the Board is satisfied that the improvements have been completed.

*(b) Occupation with Right of Purchase.*

After notification, lands may be selected for occupation, with right of purchase, under a license for twenty-five years. At any time subsequent to the first ten years, and after having resided on the land and made the improvements hereafter described, the licensee can, on payment of the upset price, acquire the freehold. If not purchased after the first ten and before the expiry of the twenty-five years of the term, the license may be exchanged for a lease in perpetuity. The rent is 5 per cent. on the cash price of the land. A half-year's rent must be deposited with the application, if for surveyed land, and this sum represents the six months' rent due in advance on the 1st day of January or July following the selection. If the land is unsurveyed, the cost of survey is to be deposited, and is credited to the selector as so much rent paid in advance, counted from the 1st day of January or July following thirty days' notice of the completion of survey.

Residence must commence on bush or swamp lands within four years, and be continuous for six years, and in open or partly open land it must begin within one year from the date of selection, and be continuous for a period of seven years. The land must be improved to an amount equal to 10 per cent. of its value within one year from the date of the license or lease ; within two years must be improved to the amount of another 10 per cent. ; and within six years to the value of another 10 cent., making 30 per cent. in all within the six years. In addition, the land must be further improved to an amount of £1 an acre for first-class land, and on second-class land to an amount equal to the net price of the land, but not more than 10s. per acre. Two or more persons may make a joint application to hold as tenants in common under this tenure. Land held on deferred payment may be mortgaged under the Government Advances to Settlers Act of 1894.

(c) Leases in Perpetuity.

Lands notified under the optional system may be selected on a lease for 999 years (or in perpetuity), subject to the undernoted conditions of residence and improvements. The rental is 4 per cent. on the cash price of the land. In the case of surveyed lands, the application must be accompanied by half a year's rent, which represents that due on the 1st day of January or July following the date of selection. In the case of unsurveyed lands, the cost of survey must be deposited, and is credited to the selector as so much rent paid in advance, dating from the 1st day of January or July after thirty days' notice of completion of survey. Two or more persons may make a joint application to hold as tenants in common under this tenure. The residence must be continuous for a term of ten years, and the conditions of improvements are similar to those imposed in connection with occupation with the right of purchase.

*Residence and Improvement Conditions.*

Residence is compulsory (with a few exceptions mentioned in the Act). The Board has power to dispense with residence in certain cases, such as where the selector resides on adjacent lands, or is a youth or an unmarried woman living with his or her parents. The term "residence" includes the erection of a habitable house to be approved of by the Board.

Improvements comprise the reclamation of swamps, the clearing of bush, cultivation, the planting of trees, the making of hedges, the cultivation of gardens, fencing, draining, the making of roads, wells, water-tanks, water-races, sheep-dips, embankments or protective works, or the effecting of any improvement in the character or fertility of the soil, or the erection of any building, etc. : and cultivation includes the clearing of land for cropping, or clearing and ploughing for laying down artificial grasses, etc.

*Special Settlement Associations.*

Under the existing regulations, any group of persons numbering not less than twelve may apply for a block of land of not less than 1,000 acres nor more than 11,000 acres in extent; but the number of members must be such that there shall be one for every 200 acres in the block, and no one may hold more than 320 acres, except of swamp lands, of which the area may be 500 acres. The price of lands within a special settlement is fixed by special valuation, but it cannot be less than 10s. an acre. The rental may not be less than 4 per cent. on the capital value of the land; the tenure is lease in perpetuity. Residence, occupation, and improvements are generally the same as required in connection with selections under the optional system of selection, and applications have to be made in the manner prescribed by the regulations.

*Improved Farm Settlements.*

Special regulations are in force for this class of settlement, and those who form settlements are selected from the applicants by the Commissioner,

preference being given to married men. The area of the farms may vary from 10 to 200 acres, according to locality, and no settler can select more than one farm. The land is leased for 999 years at a rental of 4 per cent. on the unimproved capital value, to which is added the amount advanced by Government for clearing, grassing, etc. Residence for the first ten years is compulsory, and the improvements to be effected are similar to those on leases in perpetuity.

#### *Village Settlements.*

Village settlements are disposed of under regulations made from time to time by the Governor, but the main features are as follow:—Such settlements may be divided into—(1) Village allotments not exceeding 1 acre each, which are disposed of either at auction or upon application as already described, with option of tenure, the cash price being not less than £3 per allotment; and (2) homestead allotments not exceeding 100 acres each, which are leased in perpetuity at a 4-per-cent. rental on a capital value of not less than 10s. per acre. Where a village-settlement selector has taken up less than the maximum area prescribed, he may obtain an additional area in certain cases without competition on the same tenure and terms as the original holding. Residence, improvements, and applications are the same as already described. The leases are exempt from liability to be seized or sold for debt or bankruptcy. The Governor is empowered in certain cases to advance small sums for the purpose of enabling selectors to profitably occupy their allotments.

#### *Grazing Areas.*

Small grazing runs are divided into two classes: first-class, in which they cannot exceed 5,000 acres; and second-class, in which they cannot exceed 20,000 acres in area. These runs are leased for terms of twenty-one years, with right of renewal for a like term, at a rent of  $2\frac{1}{2}$  per cent. on the capital value of the land, but such capital value cannot be less than 5s. per acre. The runs are declared open for selection, and applications and declarations on the forms provided have to be filled in and left at the Lands Office, together with a deposit of six months' rent, representing that due on the 1st day of March or September following selection. A selector may not hold more than one small grazing run, nor may he hold any freehold or leasehold land of any kind whatsoever over 1,000 acres, exclusive of the area for which he applies under this system. The lease entitles the holder to the grazing rights and to the cultivation of any part of the run, and to the reservation of 150 acres around his homestead through which no road may be taken; but the runs are subject to the mining laws. Residence is compulsory on bush or swamp land within three years, and on open land within one year; and it must be continuous to the end of the term, though this latter condition may in certain cases be relaxed. Improvements are necessary as follow:—Within the first year, to the amount of one year's

rent; within the second year, to the amount of another year's rent; and within the next four years, to the value of two years' rent;—making a sum equal to four years' rental to be spent on the run in six years. In addition to this, a first-class run must be improved to an amount of 10s. an acre, and a second-class run to an amount of 5s., if the land be under bush. After three years' compliance with these conditions, the run may be divided among the members of the selector's family who are of the age of 17 years and upwards, and new leases may be issued to them on the terms and subject to the conditions of residence and improvements contained in the original lease.

#### *Pastoral Leases.*

Purely pastoral country is let by auction for a term not exceeding twenty-one years; but, except in extraordinary circumstances, no run can be of a carrying capacity greater than 20,000 sheep or 4,000 cattle. Runs are classified from time to time into those which are suitable for carrying more than 5,000 sheep (let as above), and into pastoral-agricultural country, which may either be let as pastoral runs, generally for short terms, or be cut up for settlement in some form. Leases of pastoral-agricultural lands may be resumed without compensation at any time after twelve months' notice has been given. No one can hold more than one run unless it possesses a smaller carrying capacity than 10,000 sheep or 2,000 cattle, in which case the lessee may hold additional country up to that limit. Runs are offered at auction from time to time, and half a year's rent must be paid down at the time of sale, representing that due in advance on the 1st March or September following; and the purchaser has to make the declaration required by the Act. All leases begin on the 1st March; they entitle the holder to the grazing rights, but not to the soil, timber, or minerals. A lease terminates over any part of the run which may be leased for another purpose, purchased, or reserved. The tenant must prevent the burning of timber or bush, and the growth of gorse, broom or sweet-briar, and destroy the rabbits on his run. With the consent of the Land Board, the interest in a run may be transferred or mortgaged, but power of sale under a mortgage must be exercised within two years. In case it is determined again to lease any run, it must be offered at auction twelve months before expiry of the term, and if, on leasing, it is purchased by some person other than the previous lessee, valuation for improvements, to be made by an appraiser, must be paid by the incoming tenant, to an amount not greater than three times the annual rent, except in the case of a rabbit-proof fence, which is valued separately. Runs may also be divided with the approval of the Land Board. Where a lessee seeks relief, and the application is favourably reported on by the Board, the whole or part of one year's rent payable or paid may be remitted or refunded, or the lease may be extended, or a new lease or license issued in lieu thereof. The Minister may also



postpone payment of rent or sheep rate where a tenant has applied or signified his intention of applying for relief.

*Acquisition of Land for Settlement.*

The administration of the law in respect of the acquisition of land for settlement is vested in a Board styled the Board of Land Purchase Commissioners, and consisting of the Surveyor-General, the Commissioner of Taxes, and the Commissioner of Crown Lands for any district in which it is proposed to acquire land, the Land Purchase Inspector, and a member of the Land Board of the district. The duties devolving upon the Board are to ascertain the value of any lands proposed to be acquired, and to report to the Minister as to their character and suitability for settlement, and as to the demand for settlement in the locality. Land may be compulsorily taken for the purposes of the Act. The rent of land acquired and disposed of under the Act is at the rate of 5 per cent. on the capital value of the land, and the capital value is to be fixed at a rate sufficient to cover the cost of the original acquisition, together with the cost of survey, subdivision, and making due provision for roads. Where land acquired contains a homestead, a lease in perpetuity of the homestead and land surrounding it, not exceeding 640 acres, may be granted to the person from whom it was acquired, on conditions prescribed, at a yearly rental of 5 per cent. on the capital value of the land, such capital value to be determined in the manner set forth above.

A large area, principally in the North Island, remains in the hands of the native race, and this land may be acquired for settlement after a report upon its character, suitability for settlement, and value, has been made by a Board specifically appointed for the purpose. On notification, the land becomes Crown land, subject to trust for native owners.

AUSTRALASIAN SETTLEMENT.

The particulars given in the foregoing pages will have made the fact abundantly clear that the main object of the land legislation, however variously expressed, has been to secure the settlement of the public estate by an industrious class, who, confining their efforts to areas of moderate extent, would thoroughly develop the resources of the land; but where the character of the country does not favour agricultural occupation or mixed farming, the laws contemplated that the State lands should be leased in blocks of considerable size for pastoral occupation, and it was hoped that by this form of settlement vast tracts which, when first opened up, seemed ill-adapted even for the sustenance of live-stock, might ultimately be made available for industrial settlement. To how small an extent the express determination of the legislators to settle an industrious peasantry on the soil was accomplished will presently be illustrated from the records of several of the provinces; but in regard to pastoral settlement the purpose was fully achieved.—large areas, which were pronounced even by experienced explorers to be uninhabitable wilds, have since been occupied by thriving

flocks, and every year sees the great Australian desert of the early explorers receding step by step. The following statement shows the area of land alienated by each province, the area leased, and the area neither alienated nor leased at the close of 1903. The term "alienated" is used for the purpose of denoting that the figures include lands granted without purchase. The area so disposed of has not been inconsiderable in several provinces:—

State.	Area.	Area alienated or in process of alienation.	Area leased.	Area neither alienated nor leased.
	acres.	acres.	acres.	acres.
New South Wales .. ..	198,848,000	48,851,524	127,901,840	22,094,636
Victoria .....	56,245,760	24,526,255	9,516,372	22,203,133
Queensland .....	427,838,080	16,991,127	277,569,396	133,277,557
South Australia .....	578,361,600	14,149,171	189,531,955	374,680,474
Western Australia .....	624,588,800	10,548,057	135,678,028	478,362,715
Tasmania .....	16,778,000	5,040,413	1,581,937	10,155,650
Commonwealth ...	1,902,660,240	120,106,547	741,779,528	1,040,774,165
New Zealand .....	66,861,440	23,857,633	16,648,650	26,355,157
Australasia .....	1,969,521,680	143,964,180	758,428,178	1,067,129,322

The proportions which these figures bear to the total area of each province are shown below:—

State.	Area alienated or in process of alienation.	Area leased.	Area neither alienated nor leased.
	per cent.	per cent.	per cent.
New South Wales .....	24·57	64·32	11·11
Victoria .....	43·60	16·92	39·48
Queensland .....	3·97	64·88	31·15
South Australia .....	2·45	32·77	64·78
Western Australia .....	1·69	21·72	76·59
Tasmania .....	30·04	9·43	60·53
Commonwealth .....	6·31	38·99	54·70
New Zealand .....	35·68	24·90	39·42
Australasia .....	7·31	38·51	54·18

The figures in the foregoing table disclose many grounds for congratulation. Of 1,902 million acres which comprise the area of the Commonwealth, 862 millions, or 45·30 per cent., are under occupation for productive purposes, and of an extent of 1,969 millions, the area of Australasia, no less than 902 millions, or 45·82 per cent., are similarly occupied, and there is every probability that this area will be greatly added to in the near future. New South Wales shows the least area returning no revenue, for out of nearly 200 million acres only 22 million remain unoccupied, and much of this is represented by lands which the State

has reserved from occupation, and which are used for travelling stock or for various public purposes, including lands reserved for future settlement along the track of the great trunk line of railways. The State of Tasmania has nearly 61 per cent. of its area unoccupied, the western part of the island being so rugged as to forbid settlement. Settlement in Western Australia is only in its initial stage; much of the area of the state is practically unknown, and a large part of what is known is thought to be little worth settlement. Much the same thing was confidently predicted of western New South Wales and South Australia, though, as subsequent events proved, the forebodings were untrue. In South Australia, including the Northern Territory, only 35·22 per cent. is in occupation. New Zealand, favoured with a beneficent climate, has nearly half its area not utilised—a circumstance entirely due to the mountainous character of its territory.

The practice of sales by auction without conditions of settlement was a necessary part of the system of land legislation which prevailed in most of the provinces; but this ready means of raising revenue offered the temptation to the Governments, where land was freely saleable, to obtain revenue in an easy fashion. The result of the system was not long in making itself felt, for pastoralists and others desirous of accumulating large estates were able to take advantage of such sales, and of the ready manner in which transfers of land conditionally purchased could be made, to acquire large holdings, and in this manner the obvious intentions of the Lands Acts were defeated. Notwithstanding failures in this respect, the Acts have otherwise been successful, as will appear from the following table, as well as from other pages in this volume. It is unfortunate that detailed information regarding settlement can only be given for three of the states of the Commonwealth, viz, New South Wales, South Australia, Western Australia, and for New Zealand, and that in respect of Western Australia the information is deficient in regard to the area of the holdings. The figures given for Western Australia in the table refer to the year ended 28th February, 1903, for South Australia to the Census year of 1891, for New South Wales to the year ended 31st March, 1904, and for New Zealand to the year ending 31st March, 1903:—

Size of Holdings.	New South Wales.		South Australia.		Western Australia.	New Zealand.	
	Number of Holdings.	Area of Holdings.	Number of Holdings.	Area of Holdings.	Number of Holdings.	Number of Holdings.	Area of Holdings.
		acres.		acres.			acres.
1 to 100 acres .....	40,023	1,201,585	6,304	183,443	2,344	36,935	955,072
101 to 1,000 acres .....	23,016	9,880,761	10,613	4,711,060	3,054	24,234	7,844,288
1,001 to 5,000 acres .....	4,764	9,521,469	2,394	4,623,987	713	3,003	6,195,878
5,001 to 20,000 acres .....	961	9,580,933	481	4,787,253	115	583	6,747,062
20,001 acres and upwards..	359	17,422,864	58	1,974,996	42	279	15,146,147
Total .....	74,123	47,507,611	20,355	16,230,688	6,263	65,034	35,887,447

It will be seen that in the case of South Australia and New Zealand the area included in the foregoing table is greater than the area alienated as shown on page 342; the figures for these states must therefore include some Crown lands held under lease.

Out of the 47,507,611 acres set down to New South Wales in the foregoing, 43,661,856 acres are in the actual occupation of the owners, and 3,845,755 acres are held under rent. In New Zealand the proportion was not stated at the last Census. In South Australia only 5,510,289 acres are occupied by the owners, while 10,720,399 acres, or 66 per cent., are rented. The most remarkable feature of the table is that in New South Wales about one-half the alienated land is owned by 730 persons or institutions, in South Australia by 1,283, and in New Zealand by less than 500.

## AGRICULTURE.

**T**AKEN as a whole, Australasia may be said to be just emerging from the first phase of agricultural settlement; indeed, some of the states have not yet wholly passed from the pastoral stage. Nevertheless the value of agricultural produce, estimated at farm prices, is considerable, and amounts to over 50 per cent. of the value of the pastoral and dairy produce. The production from agriculture in each state for the year 1903, given below, is the largest yet recorded, and is over £5,000,000 in excess of the average for the five preceding years. The wheat crop alone was valued at over £12,000,000, of which some £5,000,000 worth was exported to countries outside Australasia during the first nine months of 1904.

State.	Total value of Crops in 1903.	Average Value of Produce per acre.	Proportion of Total Value.
	£	£ s. d.	per cent.
New South Wales .....	8,359,000	3 5 9	24·54
Victoria .....	10,156,000	2 19 11	29·82
Queensland .....	2,059,000	3 12 8	6·05
South Australia .....	4,030,000	1 15 9	11·83
Western Australia .....	923,000	3 5 1	2·71
Tasmania .....	1,265,000	4 17 5	3·72
Commonwealth .....	26,792,000	2 17 7	78·67
New Zealand .....	7,266,000	4 3 10	21·33
Australasia .....	34,058,000	3 1 8	100·00

From this estimate it would seem that the value of crops per acre cultivated is larger in Queensland and Tasmania than in the other states of the Commonwealth, a fact which is due to the proportionately large area under sugar-cane in the former state, while in Tasmania the area devoted to fruit accounts for the high average per acre which that province shows; in Western Australia, where the greater part of the

produce consumed is imported, prices are higher than in the eastern states, and the small area devoted to the plough returns on an average a better price per acre than in some of the states where agriculture has received greater attention. In point of gross value, Victoria occupies the first position among the members of the Commonwealth group, the produce of that province having a value of over one-fourth of that of all Australasia. The high position of Victoria is in great measure due to the large return from wheat, potatoes, oats, and hay. New Zealand produces over one-fifth while New South Wales, chiefly owing to its magnificent wheat harvest, occupies second place on the list with slightly under one-fourth of the total. The average value of the principal crops, and the percentage of each to the total production for 1903, are given in the following statement :—

Name of Crop.	Value.	Proportion to Total.
	£	per cent.
Wheat .....	12,016,000	35·3
Maize .....	1,073,000	3·2
Barley .....	460,000	1·4
Oats .....	3,072,000	9·0
Hay .....	8,194,000	24·0
Grass seed .....	230,000	0·7
Potatoes .....	1,190,000	3·5
Grapes .....	885,000	2·6
Hops ... ..	49,000	0·1
Tobacco... ..	13,000	0·0
Sugar-cane .....	787,000	2·3
Orchards .....	1,323,000	3·9
Market Gardens .....	906,000	2·7
Green forage.....	589,000	1·7
Other crops (other grain, root, &c.)...	3,271,000	9·6
Total .....	34,058,000	100·0

The principal crop is wheat, which returned 35·3 per cent. of the total value, hay coming next with 24 per cent. "Other" crops returned the large sum of £3,271,000—9·6 per cent.—to which, New Zealand alone contributed £2,521,000, the high value of the production in that province being due to the fact that there is an area of considerably over half a million acres devoted to the cultivation of turnips and other root crops, which are grown mostly as food for sheep.

The average value of agricultural produce per head of population in each of the Australasian provinces during the year 1903 is represented by the following figures. It will be seen that South Australia shows the highest value, followed in order by New Zealand, Victoria, Tasmania, and New South Wales. The lowest positions are occupied by Western Australia and Queensland with a value of less than half that of South Australia. Comparisons of this kind are however somewhat

misleading, as the main consideration is the extent of employment afforded by the industry and the return to the persons engaged therein.

State.	Average value per head.
	£ s. d.
New South Wales .....	5 17 6
Victoria.....	8 7 10
Queensland .....	3 19 5
South Australia .....	10 19 6
Western Australia .....	4 3 10
Tasmania .....	7 1 9
Commonwealth .....	6 16 9
New Zealand .....	8 17 2
Australasia .....	7 3 9

Below will be found the value of the agricultural production of the Commonwealth and New Zealand in the years 1871, 1881, and 1891. Comparing these figures with those given above, it will be seen that while the total production of Australasia now averages nearly £14,000,000 more than in 1881, the average value per head has declined 1s. 6d. whereas compared with 1891, the average shows an increase of £1 9s. 3d. per head. As subsequent tables will show, a decrease in prices, and not want of productiveness, was responsible for the decline in value since 1881. The fall in prices, especially of wheat, was very rapid down to 1895; for the next three years there was a very material increase; in 1899 they fell again to the 1895 level, but in 1901 there was a more or less general increase; while towards the close of 1902, and almost up to the close of 1903, the effects of the adverse season were acutely felt, and prices rose to double those of the previous year. At the end of 1903, when the heavy crops began to come in, prices again fell, but they were nevertheless higher than the 1901 level.

State.	1871.	1881.	1891.
	£	£	£
New South Wales.....	2,220,000	3,830,000	3,584,500
Victoria .....	3,300,000	5,894,000	7,009,100
Queensland .....	650,000	1,283,000	1,414,000
South Australia .....	1,789,000	3,283,000	3,045,000
Western Australia.....	258,000	248,000	380,900
Tasmania .....	724,000	981,000	1,046,500
Commonwealth .....	8,941,000	15,519,000	16,480,000
New Zealand .....	1,956,000	4,650,000	5,518,000
{ Total.....	10,896,000	20,169,000	21,998,000
Australasia {			
{ Per head ...	£ s. d. 5 12 8	£ s. d. 7 5 3	£ s. d. 5 14 6

Compared with the principal countries of the world, Australasia does not take a high position in regard to the gross value of the produce of its tillage, but in value per inhabitant it compares fairly well; indeed, some of the provinces, such as South Australia, New Zealand, and Tasmania, show averages which surpass those of the leading agricultural countries. This may be partly seen from the following table, which gives approximately for 1891-95 the value of agricultural production in the principal countries of the world, with the average amount per head of population :—

Countries.	Value in millions.	Per head.	Countries.	Value in millions.	Per head.
	£	£		£	£
United Kingdom .....	126	3·2	Holland .....	18	4·0
France .....	284	7·3	Belgium .....	29	4·6
Germany .....	262	5·1	Switzerland .....	9	3·0
Russia .....	370	3·5	United States .....	487	7·7
Austria .....	210	5·7	Canada .....	33	6·9
Italy .....	141	4·6	Cape Colony .....	2	1·3
Spain .....	94	5·5	Argentina .....	24	6·0
Portugal .....	18	4·0	Uruguay .....	2	2·7
Sweden .....	20	4·9			
Norway .....	3	1·7	Australasia (average for years 1898-1903)	30	6·5
Denmark .....	19	8·6			

#### AREA UNDER CULTIVATION.

The following figures, giving the total extent of land in cultivation in each of the Commonwealth states and New Zealand at different periods since the year 1871, will serve to illustrate the progress which agriculture has made. In this table, and in the others which follow, the period represented extends from the 1st April in the year named to the 31st March of the following year. It must be understood that the areas under grass for pasturage, whether indigenous or artificially sown, are not included amongst the acreage set down as under cultivation ;—

State.	1871.	1881.	1891.	1901.	1908.
	acres.	acres.	acres.	acres.	acres.
New South Wales .....	390,000	578,243	846,383	2,276,528	2,542,919
Victoria .....	881,354	1,435,446	2,118,654	2,965,681	3,389,069
Queensland .....	59,969	117,664	242,629	483,460	566,589
South Australia .....	837,780	2,156,407	1,927,689	2,236,552	2,256,824
Western Australia .....	51,724	53,353	64,209	216,824	283,752
Tasmania .....	155,046	148,494	168,121	232,550	259,611
Commonwealth .....	2,345,922	4,489,607	5,365,685	8,411,595	9,298,764
New Zealand .....	337,282	1,070,906	1,424,777	1,713,799	1,734,127
Australasia .....	2,683,204	5,560,513	6,790,462	10,125,394	11,032,891



The 1,734,127 acres under crop in New Zealand as shown above, include 77,167 acres of grass land cut for hay, and 68,041 acres of clover and grass cultivated for seed.

In 1861, the cultivated area in Australasia was 1,337,548 acres, so that the extent of land under crop is now over eight times as large as it was in that year. If, however, the land artificially grassed be included, the total for 1903 will reach 24,741,034 acres, or more than eighteen times the area in cultivation in 1861. A comparison of the acreage under crop on the basis of population, may perhaps best serve to give an idea of the progress of agriculture, and this is shown in the table given below. South Australia still holds, as it has done for many years, the first position, followed at a long interval by Victoria and New Zealand.

State.	1861.	1871.	1881.	1891.	1901.	1908.
	acres.	acres.	acres.	acres.	acres.	acres.
New South Wales .....	0·7	0·8	0·8	0·7	1·7	1·8
Victoria .....	0·8	1·1	1·7	1·8	2·6	2·8
Queensland .....	0·1	0·5	0·5	0·6	1·0	1·1
South Australia .....	3·2	4·5	7·5	5·9	6·2	6·1
Western Australia .....	1·6	2·0	1·8	1·2	1·2	1·3
Tasmania .....	1·8	1·5	1·2	1·1	1·3	1·5
Commonwealth.....	1·1	1·4	2·0	1·6	2·2	2·4
New Zealand.....	0·7	1·3	2·1	2·2	2·2	2·1
Australasia .....	1·1	1·4	2·0	1·7	2·2	2·3

For the whole of Australasia the decennial increase of agriculture as compared with population is shown in the following table:—

Increase of—	1861-71.	1871-81.	1881-91.	1891-1901.
	per cent.	per cent.	per cent.	per cent.
Acreage under crop.....	100·6	107·2	22·1	47·6
Population .....	55·6	43·2	38·1	21·3

Although during the period of forty-two years the population of Australasia was nearly quadrupled, the area of land devoted to agriculture increased over ninefold, and the rate of agricultural progress was more than twice that of the population. The chief progress was made during the twenty years from 1861 to 1881, and the ten years from 1891 to 1901. During the period intervening from 1881 to 1891 the population increased nearly twice as rapidly as the agricultural industry.

The progress in the seventies is what naturally might be expected, as the gold fever had altogether subsided about the end of the first period, and a large portion of the population was seeking employment of a more settled nature than was afforded by the gold-fields. It was not to be anticipated that the same rate of progress could be maintained, and the comparative decline in the eighties may be accounted for by the fact that most of the best land had been taken up. The earnest attempts of the state to assist the agriculturist in obtaining land on easy terms, however, together with the satisfactory advance in the price of wheat during the three years 1896-98, enabled the industry to show a substantial rate of progress during the ten years prior to 1902, when, although the area under crop was greater than in the previous year, the return was small.

In the following table will be found the proportion of land under crop to the total area of each state, and the same with regard to Australasia as a whole. In instituting comparisons between the several states, however, it must be borne in mind that circumstances other than the mere area in cultivation require to be taken into consideration. It would not be fair, for instance, to compare Tasmania, which has 6·85 persons per square mile, with Western Australia, which has only 0·23 inhabitant to the square mile. The table has a value chiefly because it shows how each province has progressed in cultivation of the soil during the periods quoted :—

State.	1861.	1871.	1881.	1891.	1901.	1908.
	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.
New South Wales .....	0·15	0·20	0·29	0·44	1·14	1·28
Victoria.....	0·73	1·51	2·55	3·76	5·27	6·03
Queensland .....	0·001	0·01	0·03	0·06	0·11	0·13
South Australia .....	0·07	0·15	0·37	0·33	0·39	0·39
Western Australia .....	0·006	0·008	0·009	0·01	0·03	0·05
Tasmania ..	0·97	0·92	0·88	0·99	1·39	1·55
Commonwealth .....	0·07	0·12	0·24	0·28	0·44	0·49
New Zealand .....	0·10	0·50	1·60	2·13	2·56	2·60
Australasia .....	0·07	0·14	0·28	0·34	0·51	0·56

Between the years 1870 and 1890 the area under crop in Tasmania remained almost stationary, the total in 1870 being 157,410, and in 1890, 157,376 acres. In the latter year the value of agricultural production was £962,751. From 1890 to 1903 the development of the agricultural industry has been rapid; in the latter year the area under crop had increased to 259,611 acres, and the value of production to £1,265,000; the acreage increasing by 102,235 acres, and the value of the yield by £302,000 during the period dealt with.

The subjoined table shows the proportion of cultivated area devoted to the principal crops in each province, during the year 1903. It will be seen that wheat forms the greatest percentage of the total tillage in Australasia as a whole, and in New South Wales, Victoria, Queensland, South Australia, and Western Australia. Maize and sugar-cane also form a large proportion of the total in Queensland, while the principal crop in New Zealand is oats. In Tasmania only 19 per cent. of the land cultivated was under wheat, the area cut for hay forming 25·8 per cent. of the total acreage. The proportion under orchards, 5·5 per cent., is higher than that shown by any other state. "Other crops" show a high proportion in the New Zealand returns, chiefly due to the extensive planting of turnips, rape, and other green crops as fodder for sheep.

Crop.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.
Wheat .....	61·3	58·1	24·4	75·8	48·6	19·0	59·8	13·3	52·5
Maize .....	8·9	0·4	23·5	.....	0·1	.....	4·0	0·6	3·5
Barley .....	0·4	1·4	4·0	1·3	1·3	3·1	1·3	2·0	1·4
Oats .....	2·0	12·8	0·5	2·6	5·1	23·4	6·7	22·6	9·2
Potatoes .....	0·8	1·4	1·2	0·4	0·6	11·2	1·2	1·8	1·3
Hay .....	19·5	21·6	13·8	16·4	38·4	25·8	20·0	16·7	19·4
Vines .....	0·4	0·8	0·4	1·0	1·2	.....	0·7	0·0	0·6
Sugar-cane ..	0·8	.....	19·7	.....	.....	.....	1·4	.....	1·2
Orchards .....	1·9	1·5	2·3	0·8	2·8	5·5	1·7	1·6	1·7
Other crops ..	4·0	2·0	10·2	1·7	1·9	12·0	3·2	41·4	9·2
Total .....	100·0	100·0	100·0	100·0	100·0	100·0	100·0	100·0	100·0

The position in which each of the principal agricultural products stood in relation to the total area under crop in Australasia, at various periods since the year 1861, may be ascertained from the following table. The figures should, however, be taken in conjunction with those giving the actual areas cultivated, for a decline in the proportion of land under any particular crop does not necessarily mean a falling-off in the area devoted to that product; on the contrary, in few instances has there been any actual retrogression. It is satisfactory to observe that there is a greater proportionate increase in the cultivation of the more valuable crops, and

that, despite checks from causes due to unfavourable seasons, the area devoted to vines, sugar-cane, orchards, and "other crops" formed 12·7 per cent. of the whole in 1903, as compared with 8·6 per cent. in 1861 :—

Product.	1861.	1871.	1881.	1891.	1901.	1903.
	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.
Wheat .....	53·6	51·4	60·7	55·0	52·7	52·5
Oats .....	10·6	13·5	7·9	8·4	8·7	9·2
Maize .....	4·6	5·3	3·0	4·3	3·3	3·5
Barley .....	2·2	2·3	1·9	1·4	1·0	1·4
Potatoes .....	4·2	3·0	1·8	2·0	1·4	1·3
Hay .....	16·2	11·9	15·1	16·0	17·6	19·4
Vines .....	0·5	0·7	0·3	0·7	0·6	0·6
Sugar-cane .....	.....	0·5	0·7	1·1	1·3	1·2
Other crops .....	8·1	11·4	8·6	11·1	13·4	10·9
Total .....	100·0	100·0	100·0	100·0	100·0	100·0

#### WHEAT.

With the exception of Queensland and Western Australia, all the states during 1901 produced sufficient wheat for their own requirements, and in good seasons there is a large and steadily increasing balance available for export, which finds a ready market in Great Britain, where Australian wheat is well and favourably known. For the season 1903-4, the crop was a record one, the total yield being over 82,000,000 bushels, which is slightly in excess of the last Canadian harvest. Taking Australasia as a whole, the wheat exports during the current year have reached about 35,000,000 bushels, valued at some £5,000,000.

The subjoined table shows the progress of wheat-growing during the period of the last forty-three years :—

State.	1861.	1871.	1881.	1891.	1901.	1903.
	acres.	acres.	acres.	acres.	acres.	acres.
New South Wales	123,468	154,030	221,888	356,666	1,392,070	1,561,111
Victoria .....	196,922	334,609	926,729	1,332,683	1,754,417	1,968,599
Queensland .....	392	3,024	10,958	19,306	87,232	136,096
South Australia ...	310,636	692,508	1,768,781	1,552,423	1,743,452	1,711,174
Western Australia	13,594	26,697	21,951	26,866	93,707	137,946
Tasmania .....	58,323	63,332	51,757	47,584	44,084	49,414
Commonwealth	703,825	1,273,200	3,002,064	3,335,528	5,114,962	5,566,340
New Zealand .....	29,531	108,720	365,715	402,273	163,462	230,346
Australasia ...	733,356	1,381,920	3,367,779	3,737,801	5,278,424	5,796,686

It will be seen that, during the twenty years extending from 1861 to 1881, all the states, with the exception of Tasmania, made considerable additions to the area under wheat, the increase for the whole of Australasia being 2,634,423 acres, or an advance of 359 per cent. From 1881 to 1903 the extension of this form of cultivation has not been so general, most of the increase in area having taken place during the last few seasons, in consequence of the rise in price of wheat which was taken advantage of by the agriculturists of all the states, excepting South Australia and Tasmania. In these two states there were decreases in acreage, although the falling-off was partly due to the unfavourable seasons. In Australasia, as a whole, the increase in area since 1881 amounts to 2,428,907 acres—but while New South Wales shows an extension of cultivation during the period amounting to 1,339,223 acres, and Victoria an increase of 1,041,870 acres, the total increase was reduced by the falling off mentioned above. At present more than one-half of the land in cultivation is devoted to wheat-growing, and in an ordinary season the produce of 1,000,000 acres is available for export to Europe.

The production of wheat at intervals since 1871 was as follows:—

State.	1871.	1881.	1891.	1901.	1903.
	bushels.	bushels.	bushels.	bushels.	bushels.
New South Wales .....	2,229,642	3,405,966	3,963,668	14,808,705	27,334,141
Victoria .....	4,500,795	8,714,377	13,629,370	12,127,382	28,525,579
Queensland .....	36,288	39,612	392,309	1,692,222	2,436,799
South Australia .....	3,967,079	8,087,032	6,436,488	8,012,762	13,209,465
Western Australia .....	345,368	153,657	288,810	933,101	1,876,252
Tasmania .....	847,962	977,365	930,841	963,662	767,398
Commonwealth .....	11,927,134	21,378,009	25,641,486	38,537,834	74,149,634
New Zealand .....	2,448,203	8,297,890	10,257,738	4,046,589	7,891,654
Australasia .....	14,375,337	29,675,899	35,899,224	42,584,423	82,041,288

The adverse weather conditions which prevailed over the greater part of Australia caused the wheat crop of 1902 to fall far below expectations; but the crop for 1903 exceeded all previous records. In New Zealand the harvest was also a good one, the yield being at the rate of over 34 bushels per acre, an increase of nearly 10 bushels on the average of the year 1901.

The greatest increase in production between 1881 and 1901 is shown by New South Wales, which in 1901 produced nearly 11,000,000 bushels more than in 1891, and from the following statement, which gives the proportion of the total crop produced by each state in 1881, 1891, and 1901, the progress made by New South Wales will be evident, for whereas in 1881 and 1891 it only produced 11 per cent. of the total crop, in 1901 it produced nearly 35 per cent. Victoria and New

Zealand show the largest declines during the period, the proportions falling from 38 per cent. and 28·6 per cent. in 1891 to 28·5 per cent. and 9·5 per cent. respectively in 1901 :—

State.	1891.	1901.	1901.
	per cent.	per cent.	per cent.
New South Wales .....	11·5	11·0	34·8
Victoria .....	23·4	38·0	28·5
Queensland .....	0·1	1·1	3·9
South Australia .....	27·2	17·9	18·8
Western Australia .....	0·5	0·8	2·2
Tasmania .....	3·3	2·6	2·3
New Zealand .....	28·0	28·6	9·5
Australasia.....	100·0	100·0	100·0

According to the latest estimates the world's production of wheat in 1903 reached 389,350,000 quarters, of which Australasia produced a little over 10,000,000 quarters. The figures for each country are appended :—

Country.	In Quarters of 480 lb.	Country.	In Quarters of 480 lb.
Europe—	000's omitted.	Africa—	000's omitted.
Russia .....	63,500	Algeria .....	3,000
France .....	42,000	Egypt .....	1,500
Hungary .....	21,700	Tunis .....	1,000
Germany .....	16,500	Cape Colony .....	500
Italy .....	20,000	Total .....	6,000
Spain .....	12,500		
United Kingdom .....	6,000	America—	
Austria .....	5,700	United States .....	79,800
Roumania .....	9,000	Argentine Republic..	16,000
Bulgaria .....	4,500	Canada .....	9,750
Turkey .....	5,000	Mexico .....	1,750
Belgium .....	1,500	Chili .....	1,500
Servia .....	4,500	Uruguay .....	1,000
Portugal .....	750	Total .....	109,800
Sweden and Norway..	500		
Holland .....	750	Australasia—	10,400
Switzerland .....	500		
Denmark .....	500	Grand Total .....	389,350
Greece .....	750		
Total .....	216,150		
Asia—			
India .....	36,750		
Asia Minor .....	4,250		
Syria .....	3,000		
Persia .....	3,000		
Total .....	47,000		

From the above figures it will be seen that Australasia is becoming an important factor in the world's wheat production, occupying the tenth place on the list of producers, and ranking a little higher than Canada. It is interesting, therefore, at this stage to note the requirements of the chief importing countries during 1903.

The following were the world's net imports of breadstuffs according to the latest reliable estimates :—

	Quarters 000's omitted.
United Kingdom.. .. .	26,985
Germany .....	8,150
Belgium.....	5,975
Holland.....	2,060
Italy .....	5,200
Sweden .....	1,075
France .....	2,600
Other European countries.....	4,110
	<hr/>
	56,155
Non-European countries .....	7,600
	<hr/>
Total .....	63,755

The average yields per acre for each state for 1903 and during the ten years 1894-1903 are shown below :—

State.	Average Yield per acre.	
	1903.	1894-1903.
	bushels.	bushels.
New South Wales .....	17·5	9·9
Victoria .....	14·5	7·2
Queensland .....	17·6	15·9
South Australia .....	7·7	4·4
Western Australia .....	13·6	11·0
Tasmania .....	15·5	19·8
Commonwealth .....	13·3	7·3
New Zealand .....	34·3	28·6
Australasia .....	14·2	8·3

A yield of 8·3 bushels per acre is a very small one compared with the following results obtained in some of the principal wheat-growing

countries of the world. The averages shown are mostly based on the yields during the last five years :—

Country.	Average Yield per acre.	Country.	Average Yield per acre.
	bushels.		bushels.
United Kingdom .....	31·99	India .....	10·44
Germany.....	27·12	Russia .....	9·14
France.....	19·72	Argentine Republic .....	11·30
Hungary.....	17·21	Canada (Ontario and Manitoba) and North-west Territories	19·70
United States .....	13·49		

A bare statement of averages, however, is somewhat misleading, since the relative cost of production must also be taken into consideration. Careful inquiries show that in New South Wales, taking all factors into account, such as the proportions of lands variously prepared and sown, the proportion of crops harvested by different methods, average railway and other freights, but excluding interest on capital, rent, &c., the cost of landing wheat in Sydney may be set down at 21½d. per bushel with a 10-bushel crop, and 16½d. with a 17-bushel crop. In the near future, with the increased use of improved machinery, the average cost is likely to be much reduced.

The following may be taken as representing the minimum cost of raising wheat on farms of large area where the disc plough and drill are used :—

	10-bushel crop per acre. s.d.	17-bushel crop per acre. s.d.
(A.) Expenses independent of returns, i.e., seed, bluestone, ploughing, harrowing, sowing, and rolling (if necessary) .....	7·3	7·3
(B.) Expenses dependent upon the crop—stripping, winnowing, and bagging .....	4·7	6·7
(C.) Expenses dependent upon the situation of the land, cartage, say, 6 miles road and 200 to 300 miles train .....	4·1	6·11
Total .....	15·11	20·9

The rapidly increasing use of artificial manures has an important bearing on the question of wheat growing. In New South Wales, for instance, during the season 1903-4, an expenditure of 2s. to 3s. per acre on fertilizers gave in many cases an increased yield of 6 to 8 bushels per acre, and although this result may have been partly due to exceptionally favourable circumstances, there can be no doubt that improved cultivation and manuring will considerably improve the returns.

In Victoria the practice of manuring wheat lands is increasing rapidly, and farmers are quickly realizing its beneficial results. Between 1898 and 1903 the number of farmers stated as using manure increased from 7,318 to 19,921, and the area manured from 925,830 acres to 1,205,443 acres.



In South Australia it is found that owing to favourable conditions of culture a yield of 7 bushels is financially a satisfactory crop ; in none of the other states would it be possible to grow wheat commercially on so low an average. In all the states the yield could be greatly increased if cultivation of a more scientific character were adopted. Progress in this direction is, however, being made yearly, but there is still ample room for expansion. Nevertheless, the tendency in former years simply to put the seed in the ground and await results has been outgrown, and better cultivation and the use of artificial fertilizers are becoming more general.

The Railway Departments of the various states afford great facilities to farmers in the direction of enabling them to bring their grain to the coast at cheap rates. In New South Wales freight averages about 3½d. per bushel. At country railway stations provision is made for the storage of 510,000 bags of grain, while the large storehouse at Darling Harbour, adjoining both rail and water, has a capacity of 300,000 bags. In addition seven large elevators have been built which remove the bags from the trucks and deposit them in the holds of the ships by means of telescopic shoots, and four gantry conveyors load wheat from the shed into the ships. The total delivery capacity of the various loading appliances is 510 tons per hour. The wharfage space alongside the shed has a length of 1,300 feet, and the depth of water at low tide is about 26 feet.

In South Australia nearly all the wheat is grown on the seaboard, and the average haulage of the grain is only about 50 miles, for which distance the freight is 3-3d. per bushel. Plots of land are leased at low rentals adjoining the railway stations for the stacking of grain, and in the dry climate which prevails in the state this is generally found to afford adequate protection without the erection of storage sheds. Elevators for handling the grain are not in use, but no difficulty is experienced in giving rapid despatch to ships. The state possesses an extensive seaboard with a large number of ports, and the rate for delivering grain to the ships may be taken as about 1,000 bags per hour.

In Victoria the railway rates per bushel for grain are :—

200 miles ... ..	4.28d.
400 „ ... ..	5.41d.

The Railway Department does not provide sheds for grain at country stations, but in some districts the farmers lease land from the Department and erect sheds thereon for storage purposes. At Melbourne the shed accommodation is limited, but at Williamstown there are five railway sheds with a total storage capacity of 190,000 bags. In addition to these, four sheds capable of holding altogether 100,000 bags of grain have been erected by shippers on sites in close proximity to the wharves. Grain elevators are not in use, but an electric conveyor was employed during 1903 to discharge grain from trucks to ships, and was found to be capable of delivering 45 tons per hatch per hour.

During the coming season it is the intention of the Commissioners to establish electric conveyors and chutes at Geelong, from which port large quantities of grain are shipped annually.

The value of the wheat crop for 1903 and the value of the return per acre in each state and in New Zealand are shown below:—

State.	Value of Production.	Value per Acre.
New South Wales.....	£3,975,000	£2 10 11
Victoria .....	4,160,000	2 2 3
Queensland .....	391,000	2 16 8
South Australia .....	1,926,000	1 2 6
Western Australia .....	308,000	2 4 8
Tasmania .....	105,000	2 2 7
Commonwealth .....	£10,865,000	£1 19 0
New Zealand.....	1,151,000	4 19 11
Australasia.....	£12,016,000	£2 1 5

The very high value returned in New Zealand is due to the heavy yield of grain, the area under cultivation being comparatively small and specially selected.

A detailed table of the value of the yield per acre during each of the last fourteen years is shown below for the three principal wheat-growing states—New South Wales, Victoria, and South Australia. The values are estimated on the basis of the market rates ruling in February and March of each year. It will be seen that a considerable decline took place between 1891 and 1895, due for the most part to the fall in prices rather than to any decrease of production. The effect of the rise in prices is seen in the more satisfactory results in New South Wales during the seasons ending March, 1896, 1897, and 1898; for Victoria and South Australia the drought is largely responsible for the low values in those years, also for the very low values shown in 1902–3 for Victoria and New South Wales:—

Year ending March.	Average Yield per acre.			Value of Average Yield per acre.					
	New South Wales.	Victoria.	South Australia.	New South Wales.		Victoria.		South Australia.	
	bushels.	bushels.	bushels.	£	s. d.	£	s. d.	£	s. d.
1891	10·9	11·1	5·6	2	0 10	1	19 9	0	19 7
1892	11·1	10·3	4·3	2	2 6	2	2 3	0	17 11
1893	15·1	11·0	6·1	2	5 2	1	14 0	0	19 3
1894	11·0	10·4	7·9	1	10 1	1	0 1	0	18 4
1895	10·9	8·3	4·9	1	4 6	0	13 6	0	8 0
1896	8·7	4·0	4·2	1	17 0	0	17 9	0	19 10
1897	10·2	4·5	1·7	2	3 5	1	3 8	0	8 7
1898	10·6	6·4	2·6	2	4 2	1	6 2	0	11 3
1899	7·0	9·1	4·9	0	19 0	0	19 9	0	13 7
1900	9·5	7·0	4·6	1	5 0	0	18 9	0	12 4
1901	10·6	8·9	5·9	1	6 9	1	1 0	0	16 2
1902	10·6	6·9	4·6	1	16 3	1	3 7	0	17 3
1903	1·2	1·3	3·6	0	7 11	0	7 10	1	1 7
1904	17·5	14·5	7·7	2	10 11	2	2 3	1	2 6

The rates just given, as well as elsewhere in this chapter, represent farm prices, and not values at the place of consumption.

The average consumption of wheat per head of population in each of the six states and in New Zealand for the last decade was as stated below. The large proportion of adult male population in Western Australia accounts for the high figures for that province:—

	Busbels
New South Wales .....	5·9
Victoria .....	5·4
Queensland .....	5·7
South Australia .....	6·3
Western Australia .....	7·6
Tasmania .....	6·7
New Zealand .....	6·6

For the whole of Australasia, the average consumption was 6 bushels per head, which is larger than the quantity consumed in any other part of the world for which records are available, with the exception of France and Canada.

The records for the six states which form the Commonwealth show that since 1879 there were only five years during which they were forced to import wheat from places outside their boundaries. These years were 1886, 1889, 1896, 1897, and 1903. In the first-named year the wheat crop was a partial failure in Victoria and South Australia, and almost a complete failure in New South Wales and Queensland. In 1889 there was a general failure in New South Wales and Victoria. In 1896 the crop failed in Victoria, and in the following year, that state for the first time in twenty-two years was compelled to import wheat, the net import, however, being only 61,160 bushels. In 1902 the crops of New South Wales, Victoria, and Queensland were almost a complete failure owing to the drought, while those in South Australia were also adversely affected, but during 1904 some 35,000,000 bushels of wheat were available for export. The following statement gives the figures for the Commonwealth since 1883:—

Year.	Wheat Crop. (Year ended 31st March.)	Net Export of Breadstuffs (Year ended 31st December.)	Year.	Wheat Crop. (Year ended 31st March.)	Net Export of Breadstuffs (Year ended 31st December.)
	bushels.	bushels.		bushels.	bushels.
1883 .....	21,492,505	4,742,290	1894 .....	37,143,040	11,916,782
1884 .....	35,714,456	17,130,843	1895 .....	27,856,015	6,774,377
1885 .....	30,559,080	11,583,644	1896 .....	18,262,348	(—) 4,347,168
1886 .....	20,165,988	(—) 603,532	1897 .....	20,880,479	(—) 3,641,306
1887 .....	28,899,220	4,265,924	1898 .....	23,241,409	1,341,596
1888 .....	35,930,697	10,643,673	1899 .....	41,417,853	11,584,688
1889 .....	19,757,509	(—) 2,107,136	1900 .....	39,977,568	13,960,187
1890 .....	34,039,289	8,838,170	1901 .....	48,353,402	24,799,745
1891 .....	27,118,259	10,646,298	1902 .....	38,661,619	10,329,319
1892 .....	25,675,265	4,126,538	1903 .....	12,363,080	(—) 9,736,931
1893 .....	32,759,693	8,829,941	1904 .....	*74,149,634	*41,000,000

(—) denotes excess of imports. \* Estimated.

In ordinary seasons Australasia ranks about sixth amongst the exporting countries; still, its contribution to the world's markets in 1903 did not form more than one-twenty-fifth of the demand, and it cannot, therefore, be said to form a factor of any great consequence in the trade.

To Australia, as an increasing wheat-producing country, it is, however, satisfactory to find that notwithstanding the rapid increase in the world's crops the consumption of wheat is advancing even more rapidly. According to Beerbohm the visible supply of wheat in the world on the 1st April compares as follows over a series of years.

1894.....	23,940,000 quarters.
1900.....	19,850,000    "
1902.....	18,770,000    "
1904.....	15,160,000    "

The United Kingdom is the largest importer of wheat, and the British demand largely influences the price throughout the world. The average London prices per quarter of 8 bushels during the last decennial period were as follow :—

Year.	Price per quarter.	Year.	Price per quarter.
	s. d.		s. d.
1894	22 10	1899	25 8
1895	23 1	1900	26 11
1896	26 2	1901	26 5
1897	30 2	1902	23 1
1898	34 0	1903	26 9

As showing the fluctuations in price, it may be mentioned that the highest weekly average in 1903 was 30s. 3d., and the lowest 24s. 11d.

During the past five years Great Britain imported on an average 5,227,800 tons of wheat and flour, the countries of origin being as follows :—

	tons.	per cent.
United States .....	2,962,000	56·66
Argentine Republic.....	573,600	10·97
Russia and Austria .....	397,600	7·61
Other Foreign Countries .....	202,800	3·88
<b>Total from Foreign Countries ...</b>	<b>4,136,200</b>	<b>79·12</b>
India .....	374,400	7·16
Canada .....	519,800	9·94
Australasia .....	197,400	3·78
<b>Total from British Possessions ...</b>	<b>1,091,600</b>	<b>20·88</b>
<b>Total .....</b>	<b>5,227,800</b>	<b>100·00</b>

In consequence of the favourable harvest in 1903, it is probable that Australasia will be in a position to supply about 16 per cent. of the British imports for the year. Amongst the foreign suppliers to the British markets the greatest falling-off is shown by the United States. In 1903 that country exported to Great Britain only 2,021,075 tons of wheat and flour, this quantity being nearly 1,000,000 tons less than that consigned in 1902, while a further shrinkage is noticeable in the supplies during 1904. The declining export is, of course, in great measure, due to the rapidly increasing home consumption.

### OATS.

The cultivation of oats, which come next to wheat in importance as a grain crop, is increasing in Australasia, as the following figures show:—

State.	1871.	1881.	1891.	1901.	1903.
	acres.	acres.	acres.	acres.	acres.
New South Wales.....	13,795	16,348	12,958	32,245	51,621
Victoria .....	175,944	146,995	190,157	329,150	433,638
Queensland .....	131	88	715	1,535	2,808
South Australia .....	3,586	3,023	12,637	34,860	57,558
Western Australia .....	1,474	827	1,301	9,641	14,568
Tasmania .....	29,631	27,535	28,360	54,089	60,663
Commonwealth.....	224,561	194,816	246,128	461,320	620,556
New Zealand.....	139,185	243,387	323,508	405,924	391,640
Australasia.....	363,746	438,203	569,636	867,244	1,012,496

During 1900 there was a considerable increase in cultivation of oats, owing to the demand for this cereal created by the South African war. The colony of New Zealand furnishes nearly one-half of the production. In New South Wales the cultivation has been comparatively neglected; in Victoria, however, it is next to wheat in importance; whilst in Queensland and Western Australia the climate is ill-adapted to the cultivation of the crop, and the yield is small and counts for very little in the total production of the grain. In 1903 the yield of oats in all the Commonwealth states was comparatively large.

The total yield in each state for the period covered by the preceding table was as follows :—

State.	1871.	1881.	1891.	1901	1903.
	bushels.	bushels.	bushels.	bushels.	bushels.
New South Wales ...	280,887	358,566	276,259	687,179	1,252,156
Victoria .....	3,299,869	3,612,111	4,412,730	6,724,900	13,434,952
Queensland .....		1,121	16,669	42,208	70,713
South Australia ....	38,894	32,219	80,876	469,254	902,936
Western Australia...	28,330	8,270	18,539	158,638	258,503
Tasmania .....	593,477	783,129	873,173	1,702,659	1,621,960
Commonwealth ...	4,241,477	4,793,416	5,678,246	9,784,838	17,541,210
New Zealand .....	3,726,810	6,924,848	11,009,020	15,045,233	15,107,237
Australasia .....	7,968,287	11,718,264	16,687,266	24,830,071	32,648,447

The average yields per acre in each state in 1903, and during the ten years 1894-1903 are shown below :—

State.	Average yield per acre.	
	1903.	1894-1903.
	bushels.	bushels.
New South Wales .....	24·3	18·6
Victoria .....	31·0	19·8
Queensland .....	25·2	20·3
South Australia .....	15·7	11·2
Western Australia .....	17·7	16·6
Tasmania .....	26·7	29·4
Commonwealth .....	28·3	20·0
New Zealand .....	38·6	36·9
Australasia .....	32·2	27·9

In all the provinces which grow oats to any extent, with the exception of Tasmania, the yield last year was above the decennial average. New Zealand had the high average of 38·6 bushels per acre, which compares very favourably with the averages which prevailed during 1894-1903 in the following principal oat-growing countries of the world :—

Country.	Average yield per acre.	Country.	Average yield per acre.
	bushels.		bushels.
United Kingdom ...	41·3	United States .....	28·8
Germany .....	37·9	France .....	26·4
Canada .....	37·4	Austria .....	23·1
Hungary .....	27·2	Russia, in Europe.	15·6

The average value of the oats crop and the return per acre, in each of the Commonwealth states and New Zealand, for 1903, will be found below :—

State.	Value. £	Value per acre. £ s. d.
New South Wales .....	125,000	2 3 6
Victoria .....	1,276,000	2 18 10
Queensland .....	8,000	2 15 5
South Australia .....	84,000	1 9 0
Western Australia .....	29,000	1 19 11
Tasmania .....	152,000	2 10 3
Commonwealth .....	£1,674,000	£2 13 11
New Zealand .....	1,398,000	3 11 5
Australasia .....	£3,072,000	£3 0 8

The net import or export of oats by each of the states is given in the following table. New Zealand was the only province which exported this cereal to any considerable extent in 1903, although Tasmania and South Australia also exported small quantities. Owing to the late war in South Africa, a large demand for oats as horse-feed was created, and for the year ended 31st March, 1903, no less than 3,988,000 bushels of oats, valued at £511,558, were exported to that country by New Zealand alone. With the termination of the war the trade has, of course, decreased, but during the following year 1,335,972 bushels, valued at £116,909, were despatched. The total export of oats from New Zealand amounted to £453,702, of which a quantity valued at over £77,000 was sent to New South Wales. Tasmania also took advantage of the shortage on the mainland, and exported oats to the value of £90,885, of which an amount of £75,266 was consigned to New South Wales.

State.	Net Imports.	Net Exports.
New South Wales .....	1,379,690 bushels.	..... bushels.
Victoria .....	507,067 „	..... „
Queensland .....	134,442 „	..... „
South Australia .....	..... „	142,953 „
Western Australia .....	648,503 „	..... „
Tasmania .....	..... „	776,285 „
Commonwealth ...	1,750,464 „	..... „
New Zealand .....	..... „	4,954,068 „
Australasia .....	..... „	3,203,604 „

In ordinary years the Commonwealth produces sufficient oats for its own consumption, and has a fair quantity available for export.

According to a carefully-compiled estimate of the average production in the principal countries growing oats throughout the world, the yield of this grain in 1903 was as follows :—

	Quarters.
Europe .....	277,771,000
America .....	119,730,000
Africa .....	812,000
Australasia.....	4,081,000
Asia .....	8,962,000
Total .....	411,356,000

### MAIZE.

Maize is one of the most important products of New South Wales and Queensland. In the other states the climate is not suited to its growth, and the cultivation of the cereal extends to only about 23,000 acres. The following figures show that fair progress has been made since 1861 in the area devoted to this crop :—

State.	1871.	1881.	1891.	1901.	1903.
	acres.	acres.	acres.	acres.	acres.
New South Wales	119,956	117,478	174,577	167,333	226,834
Victoria .. .. .	1,709	1,783	8,230	10,020	11,810
Queensland .....	20,329	46,480	101,598	116,983	133,099
Other States.....	113	36	23	530	163
Commonwealth	142,107	165,777	284,428	294,866	371,906
New Zealand .....	.....	3,177	5,447	12,503	11,156
Australasia ...	142,107	168,954	289,875	307,369	383,062

The production in the same years was as follows :—

State.	1871.	1881.	1891.	1901.	1903.
	bushels.	bushels.	bushels.	bushels.	bushels.
New South Wales	4,015,973	4,330,956	5,721,706	3,844,993	6,836,740
Victoria .....	30,833	81,007	461,447	615,472	904,239
Queensland .....	508,000	1,313,655	3,077,915	2,569,118	1,923,623
Other States .....	2,000	648	483	5,611	2,487
Commonwealth	4,556,806	5,726,266	9,261,551	7,035,194	9,667,089
New Zealand .....	.....	127,257	238,746	571,834	530,291
Australasia ...	4,556,806	5,853,523	9,500,297	7,607,028	10,197,380

It will be seen from the tables given above that although there has been an increase in cultivation amounting to over 90,000 acres since 1891, the production has only increased by some 700,000 bushels.



The following table shows the average yield of each state and of Australasia for 1903, and for the ten years ended 1903 :—

State.	Average yield per acre.	
	1903.	1894-1903.
	bushels.	bushels.
New South Wales .....	30·1	27·2
Victoria .....	78·6	59·8
Queensland .....	14·5	20·8
Western Australia .....	15·3	16·4
Commonwealth .....	25·9	26·0
New Zealand .....	47·5	43·0
Australasia .....	26·6	26·7

The averages for Victoria and New Zealand are of little value, as the area under maize in those provinces is small and very favourably situated; while Western Australia, during the period, has never had more than 250 acres under this crop—the average yield for ten years being less than 17 bushels per acre under cultivation.

The value of the crop for 1903, and the average return per acre, will be found below :—

State.	Value of crop. £	Average value per acre. £ s. d.
New South Wales .....	712,100	3 2 10
Victoria .....	89,506	8 8 6
Queensland .....	220,460	1 13 1
Western Australia.....	300	1 15 8
Commonwealth .....	1,022,300	2 15 0
New Zealand .....	51,100	4 11 7
Australasia .....	1,073,400	2 16 1

The net import or export of maize by each state during 1903 was as follows :—

State.	Net Imports. bushels.	Net Exports bushels.
New South Wales .....	1,476,704	.....
Victoria .....	.....	198,452
Queensland .....	42,918	.....
South Australia .....	6,380	.....
Western Australia.....	7,023	.....
Tasmania .....	2,434	.....
Commonwealth .....	1,337,007	.....
New Zealand .....	.....	17,364
Australasia .....	1,319,643	.....

Of the maize imported by New South Wales and Queensland, over 1,250,000 bushels, valued at £188,000, were shipped by the Argentine Republic.

It is rather curious that the only state which imports maize to any extent is New South Wales, where it is principally grown. In Australasia, this grain does not enter into consumption as an article of food as it does in other countries, and particularly in America, which produces and consumes nearly 80 per cent. of the whole maize crop of the world. The following statement shows the world's production of maize during the past two years :—

	1902. Quarters, 000's omitted	1903. Quarters, 000's omitted.
North America .....	308,278	262,169
Europe.....	57,750	70,290
Argentina .....	7,770	10,799
Australasia .....	700	1,275
Africa and elsewhere.....	5,315	6,016
Total.....	379,813	350,549

In 1901, owing to the low yields in the United States, the world's production of maize was the smallest in recent records. This shortage was responsible for a marked decrease during 1902 in the American exports of bacon and hams, the exports to Great Britain alone showing a decline of 150,000,000 lb. on the figures of the previous year. In 1903 the yield in the States was again comparatively low.

#### BARLEY.

Of the cereal productions of Australasia, barley is grown on the smallest acreage. The area under this crop at different periods was as follows :—

State.	1871.	1891.	1901.	1901.	1903.
	acres.	acres.	acres.	acres.	acres.
New South Wales.....	3,461	6,427	4,459	6,023	10,057
Victoria .....	16,772	43,652	45,021	32,423	47,760
Queensland.....	971	256	739	11,775	22,881
South Australia.....	17,225	11,953	11,481	15,517	23,697
Western Australia .....	5,083	3,679	3,738	2,719	3,609
Tasmania .....	4,275	4,597	2,650	6,104	8,084
Commonwealth.....	47,787	75,564	68,068	74,561	121,088
New Zealand .....	13,305	29,808	24,268	26,514	34,681
Australasia.....	61,092	105,372	92,336	101,075	155,769

It will be seen that in New South Wales, Queensland, and South Australia the acreage shows a marked increase since 1891. This is especially the case in Queensland, which has now nearly 23,000 acres under barley, as compared with less than 1,000 acres in 1891. The increase during the period for the Commonwealth was nearly 100 per cent.

The production for a similar period was as stated below :—

State.	1871.	1881.	1891.	1901.	1903.
	bushels.	bushels.	bushels.	bushels.	bushels.
New South Wales.....	55,284	135,218	93,446	106,361	174,147
Victoria .....	335,506	927,566	830,741	693,851	1,218,003
Queensland.....	11,836	3,207	21,302	277,037	510,557
South Australia.....	164,161	137,165	107,183	243,362	487,920
Western Australia .....	5,083	36,790	48,594	35,841	53,227
Tasmania .....	76,812	102,475	71,686	167,485	212,459
Commonwealth .....	648,682	1,342,421	1,172,952	1,523,937	2,656,313
New Zealand .....	287,646	664,093	688,683	855,993	1,160,504
Australasia.....	936,328	2,006,514	1,861,635	2,379,930	3,816,817

The average yield of barley per acre in each state for 1903, and for the ten years ended 1903, is given in the following table :—

State.	Average Yield per Acre.	
	1903.	1894-1903.
	bushels.	bushels.
New South Wales .....	17·3	15·2
Victoria .....	25·5	17·5
Queensland .....	22·3	20·3
South Australia .....	17·0	13·7
Western Australia .....	14·7	12·1
Tasmania .....	26·3	24·1
Commonwealth .....	21·9	17·1
New Zealand .....	33·5	31·9
Australasia .....	24·5	21·0

As in the case of the other three cereals which have just been dealt with, New Zealand had a far larger yield of barley per acre than any of the Commonwealth states, and compares favourably with the following countries, which averaged during 1898-1903—United Kingdom, 34·0 bushels per acre; Germany, 31·3; United States, 24·2; and France, 22·1 bushels per acre. Barley is not cultivated in these states to the extent it deserves, and to the total world's production of 940,108,000 bushels in 1903 Australasia contributed only a little over 3,800,000

bushels. In fruitful seasons Australasia produces sufficient barley, exclusive of that required for malt, for home requirements, and a small surplus for export; but if the combined trade in barley and malt be considered, all the provinces, with the exception of South Australia, Tasmania, and New Zealand, were dependent in 1903 upon external sources. The trade in barley and malt for the Commonwealth and New Zealand in 1903 was as follows:—

State.	Barley.		Malt.	
	Net Imports.	Net Exports.	Net Imports.	Net Exports.
	bushels.	bushels.	bushels.	bushels.
New South Wales .....	223,728	.. .....	304,733	.....
Victoria .....	534,110	.....	.....	180,890
Queensland .....	78,726	.....	86,144	.....
South Australia .....	.....	63,967	.....	22,626
Western Australia .....	11,168	.. .....	85,405	.....
Tasmania .....	.....	28,224	3,790	.....
Commonwealth .....	755,541	.....	276,496	.....
New Zealand .....	.....	152,683	1,977	.....
Australasia .....	602,858	.....	278,473	.. .....

The average value of the barley crop and the return of this cereal per acre during 1903 will be found below:—

State.	Average value of barley crop.	Average value per acre.
	£	£ s. d.
New South Wales .....	22,000	2 8 3
Victoria .....	145,000	3 0 7
Queensland .....	70,000	8 1 4
South Australia .....	56,000	1 19 4
Western Australia .....	8,000	2 0 11
Tasmania .....	25,000	3 1 9
Commonwealth .....	326,000	2 13 9
New Zealand .....	134,000	3 17 4
Australasia .....	460,000	2 19 0

Owing to the rapid progress of the brewing industry in Australia, increased attention is now being given to the cultivation of barley for malting purposes. Several of the larger malting companies are offering special inducements to farmers to cultivate the crop, and it is expected that the area devoted to it will show a considerable advance in the near future. In Queensland especially, increased attention is being given to the cultivation of barley for malting purposes. It will be seen that the area reaped amounted to 22,881 acres, as compared with

430 acres in 1902, and 11,775 acres in 1901. The greater part of the crop was produced in the Darling Downs district, and bulk samples of the grain consigned to the London and San Francisco markets were most favorably commented upon.

POTATOES.

The cultivation of the potato is not confined to any particular state. Victoria, New Zealand, and Tasmania have the largest areas under this crop, but New Zealand shows the greatest production. The largest area under potatoes was recorded in 1899, when no less than 176,381 acres were cultivated. Of this area New South Wales, Victoria, and New Zealand supplied 127,421 acres as against 96,409 acres in 1900. The decrease is accounted for chiefly by the circumstance that in the two states last mentioned, this crop was abandoned to a certain extent in favour of oats for which a large demand was created by the South African war. The following table shows the acreage under potatoes in each state :—

State.	1871.	1881.	1891.	1901.	1903.
	acres.	acres.	acres.	acres.	acres.
New South Wales .....	14,770	15,943	22,560	26,158	20,851
Victoria .....	39,064	39,129	57,334	40,058	48,930
Queensland .....	3,121	5,086	9,173	13,338	6,732
South Australia .....	3,156	6,136	6,892	6,248	8,616
Western Australia .....	494	278	532	1,829	1,823
Tasmania .....	8,154	9,670	16,393	25,444	29,160
Commonwealth...	68,759	76,242	112,884	113,075	116,112
New Zealand.....	11,933	22,540	27,206	81,269	31,778
Australasia .....	80,692	98,782	140,150	144,334	147,890

The production for each state during the same years was as follows :—

State.	1871.	1881.	1891.	1901.	1903.
	tons.	tons.	tons.	tons.	tons.
New South Wales .....	44,758	44,323	62,283	39,146	56,743
Victoria .....	125,841	134,290	109,786	125,474	167,736
Queensland .....	6,585	11,984	25,018	39,530	17,649
South Australia .....	10,989	18,154	27,824	15,059	31,415
Western Australia .....	1,457	556	1,596	5,665	4,542
Tasmania .....	22,608	33,565	63,100	114,704	171,298
Commonwealth...	212,238	242,872	289,607	339,578	449,383
New Zealand.. .....	42,130	121,890	162,046	206,815	208,787
Australasia .....	254,368	364,762	451,653	546,393	658,170

The average production of potatoes per acre is next given, for 1903, and for the ten years ended 1903. New Zealand, it will be seen, shows a considerably larger return than any of the other provinces :—

State.	Average Yield per Acre.	
	1903.	1894-1903.
	tons.	tons.
New South Wales .....	2·7	2·3
Victoria .....	3·4	3·1
Queensland .....	2·6	2·2
South Australia .....	3·7	2·6
Western Australia .....	2·5	3·0
Tasmania .....	5·9	4·2
Commonwealth .....	3·9	3·1
New Zealand .....	6·6	6·2
Australasia .....	4·5	3·7

Tasmania and Victoria were the only states which were able to export considerable quantities of potatoes in 1903. The surplus in Victoria, though at one time considerable, has now very much decreased. The following were the imports or exports of potatoes by each state and New Zealand in 1903 :—

State.	Net Imports.	Net Exports.
	tons.	tons.
New South Wales .....	62,083	.....
Victoria .....	.....	18,910
Queensland .....	25,969	.....
South Australia .....	.....	7,980
Western Australia .....	14,560	.....
Tasmania .....	.....	82,652
Commonwealth .....	.....	13,930
New Zealand .....	.....	3,008
Australasia .....	.....	16,938

The average value of the potato crop and the return per acre for the past five years will be found below :—

State.	Value of crop. £	Average value per acre.		
		£	s.	d.
New South Wales .....	106,000	5	2	0
Victoria .....	299,000	5	13	3
Queensland .....	35,000	5	5	3
South Australia .....	55,000	6	6	5
Western Australia .....	10,000	5	5	1
Tasmania .....	323,000	11	1	9
Commonwealth .....	828,000	7	2	7
New Zealand .....	362,000	11	7	11
Australasia .....	1,190,000	8	0	11

These values are comparatively low, and are due to the fact that the markets were glutted by the heavy supplies.

#### HAY.

Considerable quantities of wheat, oats, barley, and lucerne are grown for the purpose of being converted into hay, but the area cut varies, of course, according to the season. The area cut for hay has largely increased since 1881, as will be seen from the table appended :—

State.	1871.	1881.	1891.	1901.	1903
	acres.	acres.	acres.	acres.	acres.
New South Wales .....	51,805	146,610	163,863	442,163	496,017
Victoria .....	103,206	212,150	369,498	659,239	733,353
Queensland .....	3,828	16,926	30,655	63,055	78,393
South Australia .....	97,812	333,467	304,171	369,796	370,152
Western Australia .....	*14,342	24,445	28,534	92,964	109,002
Tasmania .....	31,578	34,790	45,445	61,495	66,947
Commonwealth ...	302,571	768,388	942,166	1,688,712	1,853,864
New Zealand .....	30,717	68,423	46,652	244,169	289,858
Australasia .....	333,288	836,811	988,818	1,932,881	2,143,722

\* In 1880.

In New Zealand, for all the years prior to 1901, the areas shown only include the extent of sown grasses cut for hay. It is not possible to quote for the earlier years the area under wheat, oats, &c., cut for

this purpose. Similarly, the production shown below prior to 1901 only includes the quantity of grass cut :—

State.	1871.	1881.	1891.	1901.	1903.
	tons.	tons.	tons.	tons.	tons.
New South Wales.....	77,460	198,532	209,417	472,621	816,810
Victoria .....	144,637	238,793	506,246	884,369	1,233,063
Queensland .....	6,278	19,640	58,842	122,039	136,117
South Australia.....	98,266	240,827	193,317	346,467	479,723
Western Australia .....	14,288	24,445	28,534	91,517	121,934
Tasmania .....	30,891	44,957	66,006	100,383	115,513
Commonwealth...	371,820	767,194	1,082,352	2,026,396	2,903,160
New Zealand.....	35,674	89,081	67,361	295,581	362,322
Australasia.....	407,494	856,275	1,129,713	2,321,977	3,265,482

The average yield of hay per acre will be found in the next table, the periods covered being the year 1903 and the ten years which closed with 1903 :—

State.	Average yield per acre.	
	1903.	1894-1903.
	tons.	tons.
New South Wales .....	1·6	1·0
Victoria .....	1·7	1·3
Queensland .....	1·7	1·8
South Australia .....	1·3	0·9
Western Australia .....	1·1	0·9
Tasmania .....	1·3	1·4
Commonwealth .....	1·6	1·1
New Zealand .....	1·3	1·3
Australasia .....	1·5	1·1

The greater portion of the hay is produced from wheat, although in New South Wales, Victoria, Queensland, and New Zealand there are large areas under oaten and lucerne hay, which are in great demand



and readily sell at remunerative prices ; in fact, so profitable is the return from oaten hay, that in New South Wales and Queensland the cultivation of oats for threshing is practically neglected for the sake of hay. For the most part, hay is grown in each province in quantities sufficient for its own requirements, New South Wales, Queensland, and Western Australia ordinarily being the only states which import to any extent.

The net import or export of hay and chaff by each state and New Zealand during the year 1903 was as follows :—

State.	Net Imports. tons.	Net Exports. tons.
New South Wales .....	116,242	.....
Victoria .....	.....	64,654
Queensland .....	11,969	.....
South Australia .....	.....	70,656
Western Australia .....	1,549	.....
Tasmania .....	.....	21,182
Commonwealth .....	.....	26,732
New Zealand .....	.....	2,299
Australasia .....	.....	29,031

The value of the return from hay in 1903-4 was higher than that of any crop except wheat ; the value in each state and the return per acre will be found below :—

State.	Total Value of Hay Crop. £	Average Value per Acre. £ s. d.
New South Wales .....	2,122,000	4 5 6
Victoria .....	3,031,000	4 2 8
Queensland .....	387,000	4 18 10
South Australia .....	1,148,000	3 2 0
Western Australia .....	355,000	3 5 2
Tasmania .....	281,000	4 3 11
Commonwealth .....	7,324,000	3 19 0
New Zealand .....	870,000	2 4 7
Australasia .....	8,194,000	3 16 5

#### GREEN FORAGE AND SOWN GRASSES.

The cultivation of maize, sorghum, barley, oats, and other cereals for green food in addition to lucerne and grass is confined chiefly to the districts where dairy farming is carried on. The following table shows the area under such green food in 1891, 1901, and 1903, and it will be seen that there have been large developments in most of the states especially in New South Wales.

The return from the cultivation of green forage in all the states during the season 1903 is estimated at £589,000, or nearly £2 an acre.

State.	Green Food.			Artificially Sown Grasses.		
	1891.	1901.	1903.	1891.	1901.	1903.
	acres.	acres.	acres.	acres.	acres.	acres.
New South Wales..	32,138	110,215	77,093	333,238	467,339	552,501
Victoria .....	9,202	32,795	33,165	174,982	162,954	962,665
Queensland .....	10,727	39,793	26,576	20,921	34,679	15,639
South Australia ..	6,416	13,695	19,241	17,519	23,510	24,118
Western Australia	238	1,024	672	.....	11,132	2,952
Tasmania .....	1,101	4,082	3,100	208,596	314,422	343,284
Commonwealth	59,822	201,604	159,847	755,256	1,014,536	1,901,159
New Zealand .....	118,484	199,508	146,166	7,357,229	11,620,178	11,803,963
Australasia ...	178,306	401,112	306,013	8,112,485	12,634,714	13,705,122

In Victoria, Tasmania, and New Zealand various areas of sown grasses are cut for seed, chiefly rye grass and cocksfoot, the total quantity of grass seed produced in 1903 being 9,824 tons, valued at £275,521. The production in Victoria was 318 tons; in Tasmania, 796 tons; and in New Zealand, 8,710 tons. The acreage on which this grass seed was produced is not included in the total given above for sown grasses, and amounted to 2,749 acres in Victoria, 5,364 acres in Tasmania, and 68,041 acres in New Zealand. The prosperity of New Zealand is largely due to its rich meadow lands, which have been created by human industry and were not the free gift of nature. Last year nearly 12,000,000 acres were under artificial grasses in the colony, or over six times the area devoted to the crop in the Commonwealth. The productiveness of these pastures is very great.

In the Victorian returns "sown grasses" show an increase of some 800,000 acres on the figures for 1901. This is accounted for by the fact that the total now includes bush land on cultivated holdings on which imported grass, clover, &c., has spread without cultivation, also burnt-off scrub land on which grass has been sown without ploughing.

#### THE VINE.

The history of the vine in Australia dates from the year 1828, when cuttings from the celebrated vineyards of France, Spain, and the Rhine Valley were planted in the Hunter River District of New South Wales, forming the nursery for the principal vineyards of that state. Years afterwards the vine was planted in the Murray River District and other parts of New South Wales, and was afterwards introduced

into Victoria and South Australia, and is now cultivated in all the provinces of the Australian continent. In South Australia a large number of Germans are employed in the industry of wine-making.

The climate and soil of Australia are peculiarly adapted to the successful cultivation of the vine, and with an increasing local demand, and the opening up of a market in England, where Australian wines have obtained due appreciation, the future expansion of wine-growing appears fairly assured. The fact that the vineyards in these States have suffered comparatively little from the ravages of phylloxera, which have had such a disastrous effect on immense areas of the European vineyards, is an additional reason why the vine-growers of Australia should look forward to largely-increased operations for their industry.

The progress of vine cultivation since the year 1861 is illustrated by the table subjoined. The areas given include the vines producing table-fruit, as well as those cultivated for wine-making, also the young vines not yet in bearing :—

State.	1871.	1881.	1891.	1901.	1908.
	acres.	acres.	acres.	acres.	acres.
New South Wales .....	4,152	4,027	8,281	8,606	8,940
Victoria .....	5,523	4,923	24,483	28,592	28,513
Queensland .....	568	1,212	1,988	1,990	2,069
South Australia.....	5,455	4,202	12,314	20,860	22,617
Western Australia .....	692	527	1,004	3,724	3,324
Australia .....	16,390	14,891	48,070	63,772	65,463
New Zealand.....	.....	.....	.....	543	749
Australasia.....	.....	.....	.....	64,315	66,212

At present the area devoted to vines is much larger in Victoria and South Australia than in the other states ; in the former state 4,030 and in the latter 10,303 acres have been added to the vineyard area since 1891. This is not great progress compared with Algeria, for example, which has already 419,177 acres under vines, although systematic planting dates only from 1849, or the Argentine with 109,700 acres ; nevertheless it is a hopeful sign in Australia, where patient waiting for the harvest to be gathered years hence is not a characteristic of the agriculturist. The progress of New South Wales has been very slight, the area under vines in 1903 being only 659 acres more than in 1891. The outbreak of phylloxera in the county of Cumberland, where most of the table grapes are grown, greatly retarded the industry ; but recently the Government has propagated a large number of phylloxera-resistant stocks, which are being disposed of to vigneronns at a nominal price, and better progress may be expected in the near future.

Vine-growing has never been carried on to any extent in Tasmania or New Zealand, although there are numerous localities in the latter colony suited for growing vines for the manufacture of both wine and raisins. The area under vines in New Zealand in 1901 was returned at 543 acres, and in 1903 at 749 acres.

The following tables show the progress made in wine-growing during the last thirty-three years :—

State.	1871.	1881.	1891.	1901.	1903.
	gallons.	gallons.	gallons.	gallons.	gallons.
New South Wales.....	413,321	513,688	913,107	868,479	1,086,820
Victoria .....	713,569	539,191	1,554,130	1,981,475	2,551,130
Queensland.....	.....	72,121	168,526	148,835	28,558
South Australia.....	852,315	813,000	861,835	2,077,923	2,345,279
Western Australia .....	.....	99,600	166,664	119,500	200,000*
Australia .....	1,979,225	1,537,600	3,604,262	5,196,212	6,221,798

The production of table-grapes during the same period is shown below :—

State.	1871.	1881.	1891.	1901.	1903.
	tons.	tons.	tons.	tons.	tons.
New South Wales.....	508	1,108	3,604	3,475	4,213
Victoria .....	1,545	740	2,791	5,110	3,902
Queensland.....	.....	285	1,169	1,814	797
South Australia.....	1,692	1,498	4,590	12,608	13,027
Western Australia .....	.....	.....	.....	400	450*
Australia....	3,745	3,596	12,244	23,407	22,349

\* Estimated.

Among other produce of the vineyards may be mentioned 20,101 gallons of brandy in New South Wales, while Victoria and South Australia produced respectively 13,063 cwt. and 10,406 cwt. of raisins and currants. Victoria produces much more brandy than any of the other states, but it is not wholly made from grapes, and the figures cannot be ascertained.

It is impossible to tabulate the average wine-yield of all the states, as in many instances the acreage under cultivation for wine-making purposes cannot be separated from young unproductive vineyards or areas cultivated for table varieties of the grape only. Making due allowance for this fact, it would appear that the average production for the season

1903 was about 213 gallons in New South Wales, 114 gallons in Queensland, and 204 gallons in Victoria. Taking an average year, the production for Australia may be set down at 190 gallons.

Compared with the wine production of other countries, that of Australia is certainly trifling. In 1903 the world's production was estimated at 2,647,000,000 gallons, to which Australia contributed only 6,500,000 gallons; while in 1901 the production of Australia was returned at 5,000,000 gallons.

The following table illustrates the progress made in the export of Australian wine to countries outside of the Commonwealth since 1881. It will be noticed that in 1901, the trade with foreign countries had grown to ten times the value in 1881, while the number of gallons exported had also increased very largely. The 1901 figures are exclusive of Queensland, 39 gallons, valued at £19; Western Australia, 173 gallons, valued at £116; and Tasmania, 2 gallons, valued at £1:—

State.	1881.		1891.		1901.	
	Quantity.	Value.	Quantity.	Value.	Quantity.	Value.
	gallons.	£	gallons.	£	gallons.	£
New South Wales..	15,761	4,767	13,429	3,463	29,239	8,101
Victoria .....	9,610	4,041	152,570	29,220	340,353	43,327
South Australia ....	8,334	2,346	249,686	45,768	485,671	67,136
Australia ...	33,705	11,154	415,685	78,451	855,263	118,564

In 1903 the export of Australian wine to countries outside of the Commonwealth was 708,976 gallons, valued at £97,981.

Including the inter-state as well as the foreign trade, the exports of each state during the same years are shown below. The figures for 1901 are exclusive of Queensland, 39 gallons, valued at £19; Western Australia, 185 gallons, valued at £122; and Tasmania, 42 gallons, valued at £16.

State.	1881.		1891.		1901	
	Quantity.	Value.	Quantity.	Value.	Quantity.	Value.
	gallons.	£	gallons.	£	gallons.	£
New South Wales..	22,377	7,233	54,143	11,644	39,651	12,256
Victoria .....	12,544	5,368	160,962	32,516	364,413	50,950
South Australia .....	54,001	12,637	285,107	58,282	593,357	91,548
Australia ...	88,922	25,258	500,232	102,442	997,421	154,754

In 1903 the inter-state and foreign exports had increased to 1,031,053 gallons, valued at £166,543.

It is interesting to note that of the 570,098 gallons of Australian wine imported into the United Kingdom during 1903, 569,179 gallons did not exceed 30 degrees of proof spirit, and so carried the minimum rate of duty.

The total value of the grape crop and the average return per acre in the Australian states, for the year 1903, will be found below:—

State.	Total value of crop.	Average value per acre—	
		Of Total Area under Vines.	Of Productive Vines.
	£	£ s. d.	£ s. d.
New South Wales .....	128,000	14 5 6	16 3 3
Victoria .....	364,000	12 15 8	14 4 1
Queensland .....	13,000	6 8 4	8 8 8
South Australia .....	322,000	14 4 11	16 9 8
Western Australia .....	47,000	14 2 2	16 19 4
Commonwealth .. .....	874,000	13 7 2	15 5 3
New Zealand .....	11,000	14 4 11	.....
Australasia .....	885,000	13 7 5	15 5 3

The average value per acre of productive vines cannot be shown for New Zealand, as the area is not distinguished.

The removal of the border duties has had a remarkably invigorating effect upon the South Australian inter-state wine trade. During the five years which preceded federation, South Australian inter-state exports averaged only 48,000 gallons; while last year the total reached 200,309 gallons. The progress of the trade with New South Wales is especially noticeable, the exports to that state during 1903 being over 98,000 gallons. Victorian growers have also taken advantage of the removal of the border duties, and during the last four years the inter-state trade has increased from 5,000 to 108,676 gallons.

Vignerons in the county of Cumberland in New South Wales, who depend upon table grapes for their chief returns, have suffered severely in recent years owing to the refusal of New Zealand to admit their produce, through fear of introducing phylloxera, and the loss of this market has probably depreciated the value of table grapes in Cumberland and Camden at least 30 per cent.

#### SUGAR-CANE.

The growth of the cane and the manufacture of sugar are important industries in Queensland and New South Wales; but whilst in the former state the industry if not increasing very rapidly has so far maintained its position, in the latter the area under crop has declined by nearly one-third

since 1896. The area under cane in each state at various periods since 1865 was as follows :—

Year.	Queensland. acres.	New South Wales. acres.
1865.....	94	22
1872.....	9,581	4,394
1882.....	28,026	12,167
1892.....	50,948	22,262
1897.....	83,093	32,927
1903.....	111,516	20,219

The conditions of cultivation in the two states are not precisely the same. In New South Wales, taking one year with another the area under cane is usually twice as great as the area from which cane is cut, but in Queensland the proportion of productive area is, as a rule, very much larger. This will be seen from the following statement :—

Year ended 31st March.	Total Area.		Area from which Cane was cut.		Yield of Cane per acre.	
	Queensland.	New South Wales.	Queensland.	New South Wales.	Queensland.	New South Wales.
	acres.	acres.	acres.	acres.	tons.	tons.
1899	110,657	22,517	79,435	9,435	14·8	18·1
1900	108,535	22,114	72,651	10,472	11·7	19·0
1901	112,031	20,809	78,160	8,790	15·1	21·4
1902	85,338	20,301	59,102	8,899	10·8	20·9
1903	111,516	20,219	60,375	10,368	13·6	21·9

The figures regarding the areas cultivated, which are taken from the Statistical Registers, do not agree with those furnished by the Customs Department ; but this may be partly accounted for by the fact that in Queensland the areas cut for fodder, though planted for sugar, are not included in the Statistical Register with the acreage cultivated.

For the five years the average for Queensland was 13·7 tons per acre of cane cut, as against 20·2 tons in New South Wales. This does not by any means prove the superiority of the land in New South Wales for cane-growing, for if the whole area under cane be taken into account different results are arrived at. The following figures cover five years :—

Yield of cane from total area under crop—

Queensland .....	8·8 tons per acre.
New South Wales .....	9·2 „ „

In New South Wales cane is cut every second year, but in the northern state a crop is obtained from the greater part of the cane area yearly, hence the difference in the yields and the apparently large unproductive area in New South Wales. A noticeable feature in last year's crops in Queensland was the large area of "stand-over" cane, the acreage cut being but little in excess of that of 1902, though the area

planted was some 26,000 acres greater. In connection with the returns for 1902, however, allowance must be made for the fact that over 15,000 acres of cane were cut for stock feed, and were not included in the area under cane for sugar.

The quantity of sugar obtained from the cane-fields has varied during the last ten years from 77,752 to 192,844 tons per annum, the average being 127,387 tons, of which 104,555 tons were produced by Queensland, and 22,832 tons by New South Wales. The yield of sugar per ton of cane varies, of course, with the density of the juice, and in an ordinary season may be set down at 9.75 per cent. Until recent years little attention was given in Queensland to the question of irrigating sugar-cane plantations, but last year 8,600 acres were irrigated, being an increase of 4,000 acres on the figures for 1901.

The greater part of the field-work on the plantations in Queensland has hitherto been performed by coloured labour, chiefly South Sea Islanders. In New South Wales the work was formerly done entirely by white labour, but latterly there has been a considerable proportion of coloured persons, chiefly Hindoos, employed on the cane-fields. In Queensland the number of coloured labourers during 1901 was about 8,850, and as the area cut was 78,160 acres, the employment of coloured labour was in the proportion of one man to every 8.8 acres. In New South Wales the coloured labourers numbered about 1,010, and the area cut being 8,790 acres, the proportion was one man to every 8.7 acres. From this statement it would appear that there was little difference between the states in regard to the employment of coloured labour compared with the area cropped. Regard must be had to the circumstance, however, that in Queensland the law restricted the employment of Kanakas to the field-work of a cane plantation; in New South Wales no similar restriction exists, and coloured labour is employed in several occupations reserved for white labour in Queensland. This, of course, refers to the conditions obtaining anterior to recent federal legislation.

In 1901 the Federal Parliament passed an Act which greatly affects the sugar industry, especially in Queensland. Under the provisions of this measure, which is entitled the Pacific Island Labourers Act, a limited number of Pacific Islanders were allowed to enter Australia up to the 31st day of March, 1904, but on and after that date their coming is prohibited. All agreements for their employment terminate on the 31st December, 1906, and after that date any Pacific Islander found in Australia will be deported.

On the 1st September, 1904, there were 8,201 islanders in Queensland, a decrease of 253 on the figures for December, 1903. The arrivals during 1903 numbered 1,037, viz., 998 males and 39 females; while from the 1st January, 1904, up to the 31st March of that year there were 78 arrivals, of whom 76 were males and 2 females. Between 1st January, 1903, and 1st September, 1904, 1,433 islanders returned to their homes, of whom 1,367 were males and 66 females.



The following table shows the number of islanders who arrived in, and departed from, Queensland during the past eleven years :—

Year.	Arrivals.	Departures.
1893 .....	1,211	1,282
1894 .....	1,859	803
1895 .....	1,305	743
1896 .....	782	608
1897 .....	934	884
1898 .....	1,178	693
1899 .....	1,522	923
1900 .....	1,743	940
1901 .....	1,726	874
1902 .....	1,139	1,775
1903 .....	1,037	1,065
Total.....	14,436	10,590

Of the 1,037 islanders who arrived in Queensland during 1903, 312 had served a previous term in the state. The island groups at which these labourers were recruited were as follows :—

New Hebrides.....	345
Banks .....	21
Torres .....	8
Solomon .....	663
	1,037

The numbers assigned to the various districts were :—Ayr, 230 ; Bundaberg, 149 ; Cairns, 161 ; Childers, 38 ; Geraldton, 229 ; Ingham, 104 ; Maryborough, 19 ; Mackay, 69 ; and Port Douglas, 15. Two died on board ship before allotment, while 21 were rejected as physically unfit.

On the 31st December, 1903, there were 4,449 Pacific Islanders possessing deposits in the Savings Bank, and the amount standing to their credit was £34,375.

The following figures will be of interest, as illustrating the relative positions of the sugar industry in New South Wales and Queensland :—

	New South Wales.	Queensland.
Cane crushed at mills .....	227,511 tons	823,375 tons
Raw sugar made at mills.....	22,297 "	91,828 "
Area cut—white grown cane .....	8,961 acres	17,080 acres
" black " .....	1,387 "	43,296 "
Quantity of cane white grown .....	200,765 tons	222,537 tons
" black " .....	26,746 "	601,338 "
Bounty paid .....	£40,153	£50,617

The above figures refer only to the areas actually cut in Queensland last season; in 1904 an area of not less than 56,289 acres was registered by the owners as destined to be placed under cane for cultivation

entirely by white labour, and hence eligible for the bounty on the produce. It will be some time, however, before this area is all available for cutting; meanwhile the bounty estimated to be paid on the 1904 crop is set down in the Treasurer's Financial Statement at £62,800 in Queensland and £37,200 in New South Wales. The principal districts in which white labour is employed in Queensland are Maryborough, Bundaberg, and Mackay, where 39,155 acres were registered as being worked under these conditions in 1903.

The duty on imported cane sugar is £6 per ton, while the excise duty is fixed at £3 per ton, but a bounty of from 4s. to 5s. per ton of cane, calculated according to its sugar contents (equal to £2 per ton of sugar), is allowed on Australian sugar grown by white labour, the bounty being paid to the grower. The employment of white against black labour is thus protected to the extent of £2 per ton of sugar, equal to about 4s. 5d. per ton of cane.

In New South Wales in 1902, 93 per cent. of the sugar produced was white grown and 7 per cent. black, while in Queensland the figures were reversed, 84 per cent. being black and 16 per cent. white grown. In 1903 New South Wales shows 88 per cent. white grown and 12 black, as compared with 73 per cent. black and 27 per cent. white grown in Queensland.

The cost of growing cane may be set down at from 2s. 11d. to 3s. 5d. per ton of cane, according as black or white labour is employed, the lower figures representing the cost of black labour.

In New South Wales the cost of harvesting the cane is somewhat as follows, the average being for areas on which white labour is employed:—

	s.	d.
Cutting.....	3	3
Carting to riverside .....	1	0
Transfer to Mills .....	0	9
Sundry Expenses .....	0	3
	<hr/>	<hr/>
	5	3
Average price paid for standing cane .....	10	5
	<hr/>	<hr/>
Total, per ton .....	15	8

It will be seen, therefore, that in the case of New South Wales cane the return to the grower would, including the bonus, amount to about 14s. 5d. per ton.

In Queensland the plantations are more favourably situated in regard to the mills, and the cost delivered to the mill is about 12s. 2d. per ton, or 3s. 6d. per ton less than in New South Wales, and at the rate of 9 tons of cane per ton of sugar the comparison is 31s. 6d. per ton in favour of Queensland. From Dr. Maxwell's report to the Federal Premier it would appear that the wages of coloured labourers, after making all necessary allowances, average about 2s. 4½d. per day; the weekly wage of white labourers is from 27s. 6d. to 32s. 6d., with rations.

A fairly correct estimate of the consumption of sugar in the states of the Commonwealth may be gathered from the statement below, which shows the average quantities on which import duty and excise were paid during the year 1903 after allowing for inter-state adjustments:—

State.	Apparent consumption.	Consumption per head of population.
	tons.	lb.
New South Wales.. .. .	66,806	105·2
Victoria .....	54,738	101·4
Queensland.....	23,259	100·5
South Australia.....	16,062	97·8
Western Australia .....	10,443	106·2
Tasmania .....	8,170	103·1
Commonwealth .....	179,478	102·7

The apparent consumption for the Commonwealth was therefore 179,478 tons, or 102·7 lb. per head of the population. Of the total quantity of sugar consumed during the year specified, 45·8 per cent. consisted of foreign-grown sugar, and 54·2 per cent. was the produce of locally-grown cane. The experience of a number of years shows the average consumption of sugar in the Commonwealth to be 106·4 lb. per head, and the consumption has therefore declined.

The Federal Treasurer estimates the requirements of the Commonwealth for 1904–5 at 187,000 tons, or slightly over 104 lb. per head of the population.

In New Zealand the net import of sugar in 1903 was 42,389 tons, or 118·2 lb. per head of population.

In 1898, Queensland produced 163,734 tons of sugar, which is the highest output recorded for that state; 1,542,090 tons of cane were crushed, yielding sugar at the rate of 1·99 tons per acre. In 1903, 823,875 tons were crushed, but the juice attained a high degree of density, and 91,828 tons of sugar were produced, only 8·97 tons of cane being required to make a ton of sugar. Of the 823,875 tons of cane produced in Queensland in 1903—

5 per cent. was grown in the	(1) Brisbane district.
19    "                   "	(2) Maryborough, Bundaberg, and Rockhampton districts.
32    "                   "	(3) Mackay, Bowen, and Townsville districts.
44    "                   "	(4) Dungeness, Geraldton, Cairns, and Port Douglas districts.

The amount and rate of the bonus paid for white-grown cane in the above districts was as follows :—

	Rate per ton.	1902.	1903.
No. 1 district .....	5s.	£4,274	£9,578
No. 2 „ .....	4s.	16,345	24,811
No. 3 „ .....	4s. 4d.	2,974	8,728
No. 4 „ .....	4s.	917	7,500
		<hr/> £24,510	<hr/> £50,617

The Commonwealth consumes annually about 181,000 tons of sugar ; the crop of 1903 was 113,614 tons, but in an average year the production may be put down at about 25,000 to 30,000 tons higher. This leaves about 40,000 tons to be imported, or for a further cultivation of, say, 30,000 acres of productive cane. It must not be forgotten, however, that in exceptionally prolific years, such as 1898, when the production of Queensland and New South Wales amounted to 192,844 tons, the out-put exceeded the consumption. With a succession of good seasons, therefore, it will be seen that, even with a slight extension of cultivation, consideration would have to be given to the question of establishing an export trade.

The country of origin of 91,529 tons of the sugar which was imported into Australia from abroad during 1903 was as shown below. The quantity shown as imported from Europe was probably beet sugar :—

Country of Origin.	Quantity Imported.
Mauritius .....	4,792 tons
Fiji .....	5,953 „
Java .....	67,545 „
Hong Kong .....	7,552 „
Europe .....	48 „
China .....	4,822 „
United States .....	815 „
India, Natal, New Zealand, Straits Settlements .....	2 „
<hr/> Total .....	<hr/> 91,529 „

The re-export of foreign sugar from Australia amounted to 779 tons, valued at £11,163 ; while 1,586 tons of Australian sugar, valued at £22,079, were exported outside the Commonwealth, £18,479 worth of which went to New Zealand.

The total value of the cane crop in the sugar-growing states of Australia for the year 1903 was :—

State.	Value of Cane grown.
New South Wales ... ..	£196,000
Queensland .....	591,000
<hr/> Total .....	<hr/> £787,000

These amounts are inclusive of rebate on white-grown sugar amounting to £40,153 in the case of New South Wales, and £50,617 in the case of Queensland. The value of the sugar manufactured during the year was about £1,800,000 sterling.

Large sums of money have been expended on machinery, buildings, and land in connection with the manufacture of raw sugar. In Queensland the total value of the mills amounted in 1903 to £2,136,682. Out of 60 mills in the state during last year, 42 were in active operation. In New South Wales, 6 mills were in operation during 1903, the value of the plant, buildings, and land being returned as £507,452.

The following statement shows the variation in the Sydney wholesale price of two of the leading brands of sugar at various intervals since the 1st January, 1898 :—

Date.	1A, per ton, duty paid.	No. 2 or 1C, per ton, duty paid.
	£ s. d.	£ s. d.
*1st January, 1898 .....	20 5 0	19 0 0
†1st July, 1898 .....	19 5 0	18 0 0
‡27th September, 1898.....	18 5 0	17 5 0
†2nd November, 1898 .....	18 5 0	16 15 0
†1st August, 1899 ... ..	18 5 0	17 0 0
†6th September, 1899 .....	18 10 0	17 5 0
†16th November, 1899 .....	18 10 0	17 10 0
†1st January, 1900 .....	18 10 0	17 10 0
†25th January, 1900 .....	18 15 0	18 0 0
†22nd March, 1900 .....	19 0 0	18 10 0
†24th July, 1900 .....	19 10 0	19 0 0
29th October, 1901 .....	21 10 0	21 0 0
8th November, 1901 .....	21 0 0	20 10 0
1st July, 1902 .....	20 0 0	19 15 0
8th October, 1902 .....	19 10 0	19 5 0
17th November, 1902 .....	20 0 0	19 15 0
9th December, 1902.....	20 10 0	20 5 0
7th February, 1903 .....	20 15 0	20 10 0
22nd October, 1903 .....	20 5 0	20 0 0
30th June, 1904 .....	19 17 6	19 12 6
12th September, 1904 .....	20 7 6	20 2 6
29th September, 1904.....	21 0 0	20 15 0
11th November, 1904 .....	21 10 0	21 5 0

\* Duty 24 per ton. † Duty £3 per ton. ‡ Imposition of Federal Tariff.

#### SUGAR-BEET.

The question of cultivating beet-root for the production of sugar has attracted attention in these states, principally in Victoria, where experiments were made in this direction over thirty years ago. The results obtained were not considered satisfactory enough to induce growers to cultivate this particular crop, and it was not until the year 1896 that a systematic attempt was made to establish the industry

On the 6th March, 1896, the Victorian Parliament passed an Act empowering the Government to assist in the establishment of the sugar-beet industry by granting loans to duly registered public companies which might be formed for the purpose of erecting mills and equipping them with the necessary machinery and plant for the extraction of sugar from the roots. The company applying for aid had to satisfy the Treasurer of the state as to certain conditions, and if he were of opinion that these conditions were likely to be fulfilled, and it was shown that the company had a paid-up capital of not less than £20,000, he was authorised to advance a sum not exceeding twice the amount raised by the shareholders.

As a result of these concessions a company was formed in Victoria, and erected a factory at Maffra, with a capacity of 420 tons per day. The first campaign in 1898 created disappointment, though the factory had at its disposal 9,109 tons of roots, grown on 1,287 acres. In the second year, the supply of beets had fallen to 6,271 tons from over 1,500 acres under crop. The industry had the misfortune to start with two very bad seasons, the average yield of beet being only 7·08 and 4·15 tons per acre. The low yield in these years was, however, due not only to unfavourable seasons but to want of experience on the part of the growers. The cultivation was further persevered with until May, 1900, when the factory was closed down. The percentage of sugar produced during the three seasons was as follows :—

1897-98.....	14·0 per cent.
1898-99.....	11·8 „
1899-1900.....	14·6 „

while the sugar produced had a standard of purity of 80 per cent., 76 per cent., and 85 per cent. respectively, these figures comparing favourably with the United States yields, which vary from 12·9 in the case of the Oxnard Company, Grand Island, Nebraska, to 15 per cent. at the works of the Western Company, Watsonville, California, where over 30,000,000 lb. of sugar are produced annually.

The Government expenditure on plant and machinery at Maffra amounted to £60,000, and altogether upwards of £100,000 of public money was laid out in connection with the venture. Although the industry so far has been a failure, it is well known that there are large areas of Victorian soil suitable for the cultivation of beet, but before the factory can be re-started vigorous efforts will have to be put forward in the direction of securing a good and plentiful crop each year.

In New South Wales, although, as already stated, portions of the soil, particularly in the New England district, have been demonstrated to be admirably adapted to the cultivation of beet of excellent saccharine properties, no systematic effort has yet been made towards the establishment of the sugar-beet industry on a commercial basis.

It must not, however, be forgotten that the abolition of the border duties and the stoppage of any system of state bounties in aid of such an enterprise will compel the beet sugar to compete on level terms with the cane sugars of Queensland and New South Wales.

TOBACCO.

The cultivation of the tobacco-plant has received attention in the three eastern states. The following table shows the area and production of tobacco at various periods :—

Year.	New South Wales.		Victoria.		Queensland.		Australia.	
	Area.	Production.	Area.	Production.	Area.	Production.	Area.	Production.
	acres.	cwt.	acres.	cwt.	acres.	cwt.	acres.	cwt.
1861	224	2,647	220	2,562	..	.....	444	5,199
1871	567	4,475	299	2,307	44	.....	910	6,782
1881	1,625	18,311	1,461	12,876	68	521	3,154	31,708
1888	4,833	55,478	1,685	12,855	123	1,418	6,641	70,251
1891	898	9,314	545	2,579	790	7,704	2,221	19,597
1892	848	8,244	477	668	818	3,806	1,643	12,810
1893	854	10,858	1,057	3,952	475	4,577	2,386	24,287
1894	716	8,182	1,412	7,155	915	9,571	3,043	24,858
1895	1,231	10,548	2,029	15,223	1,061	7,511	4,371	33,282
1896	2,744	27,468	1,284	7,890	904	8,629	5,002	43,987
1897	2,181	19,718	522	3,419	755	5,708	3,458	28,840
1898	1,405	12,708	78	190	617	3,276	2,100	16,172
1899	546	6,641	155	1,365	745	6,551	1,446	14,567
1900	199	1,906	109	311	685	4,082	978	6,243
1901	182	1,971	103	345	768	5,848	1,053	3,164
1902	317	2,604	171	781	722	1,818	1,210	5,308
1903	407	5,320	129	848	772	617	1,308	6,785

Owing to over-production and the want of a foreign market, the area devoted to tobacco-culture greatly declined from 1888 to 1892, after which it showed signs of development until 1896, but since then consistently declined until 1901, when the acreage showed a slight increase over that of the previous season. The Australasian tobacco-leaf has not yet been prepared in such a way as to find acceptance abroad, and until such is accomplished it will be useless to expect the cultivation of the plant to become a settled industry. The soil and climate of Australia appear to be suitable for the growth of the plant, but sufficient care and skill have not been expended upon the preparation of the leaf. The quantity of 70,251 cwt. of leaf produced in 1888 was so greatly in excess of local requirements that very low prices only could be obtained, and a large portion of the crop was left upon the growers' hands. The result was that many farmers abandoned the cultivation of tobacco, so that the area under this crop during 1889 was only 3,239 acres in New South Wales, and 955 acres in Victoria, producing respectively 27,724 cwt. and 4,123 cwt. of leaf—less than half the crop of the previous year. In 1891 the area showed a further decline in the case of New South Wales and Victoria. In the mother state this decline continued

until 1894; but in Victoria and Queensland the smallest area devoted to the crop was during the season 1892. The year 1895 saw a great increase in the cultivation of tobacco in all three states, and in New South Wales in 1896 there was again a large extension of the area under the plant, although in Victoria and Queensland the advance made in 1895 was not maintained. Since that year the area under cultivation and the production have both steadily declined in each state until, in 1900, the total production was only 6,248 cwt., the lowest since 1861. The production in 1903 was very small, being only about 7,000 cwt. In 1898 the crop in Victoria was almost a complete failure.

The average production per acre of tobacco in 1903, and during the ten years ended 1903, were as shown below:—

State.	Average Production per Acre.	
	1903.	1894-1903.
	cwt.	cwt.
New South Wales .....	13·1	9·8
Victoria .....	6·6	6·3
Queensland .....	0·8	6·7
Australia .....	5·2	7·9

The Agricultural Department of Queensland is endeavouring to assist the tobacco-growers by the importation of American seed of first quality, suited to the Queensland climate, and, following the example set by Victoria and New South Wales, the services of an American expert have been secured. At Texas and Inglewood, to which districts is practically confined the production of tobacco in Queensland, leaf of fine quality has been raised, which realises a high price in the Sydney markets. In 1903, however, owing to repeated attacks of blue mould, only 31 tons were produced. The price obtained for the leaf averaged about 6½d. per lb. From the 750 acres of land under tobacco harvested between March and May, 1904, it is estimated that 370 tons of leaf have been obtained, and it is anticipated that the area under crop will be slightly increased during the current season.

The combination of a number of manufacturing companies in Australia has had the effect of greatly decreasing the quantity of tobacco manufactured in Queensland, the trade having been largely transferred to the southern States. The effect of this may be seen in the amount of excise paid—which decreased from £32,480 in 1901 to £16,834 in 1903—the quantity of tobacco manufactured in different forms declining in value during the same period from £85,681 to £28,151. New Zealand, also, has commenced the cultivation of tobacco, but so far only in the nature of an experiment; and a small area has been planted in the Northern Territory of South Australia. In 1897 the Victorian



Government decided to grant a bonus of 3d. per lb. on all tobacco-leaf of approved quality grown in the state, and cured and shipped under the supervision of the tobacco expert. The bonus was only payable to the actual grower of the leaf, and 3 tons were assigned as the maximum quantity for which payment was to be made to any one grower or association. The bonuses have now lapsed, and seeing that only 129 acres are at present under crop, it does not appear as if the Government offer of assistance has had a very stimulating effect on the industry.

The annual consumption of tobacco in the Commonwealth is about 11,000,000 lb., and in New Zealand 2,300,000 lb., or a total of 13,300,000 lb. The proportion of waste in the manufacture of tobacco is about one-third, so that the quantity of leaf represented above may be set down as 17,700,000 lb. Applying the decennial average of 7.9 cwt. per acre, it would appear that the produce of 20,000 acres is required annually to supply the demand for tobacco in Australasia. The total value of the tobacco crop for 1903 in Australia was only £12,701, returning an average value of £9 14s. 2d. per acre.

#### ORCHARDS.

The cultivation of fruit in Australasia does not attract anything like the attention it deserves, although the soil and climate of large areas in all the provinces are well adapted to fruit-growing. Still, some progress has been made, especially in recent years. In 1903 the proportion of the total cultivation allotted to fruit was 1.5 per cent., as compared with 1.2 per cent. in 1881. The area per 1,000 persons, in 1903, was 36.1 acres; in 1891, 36 acres; and in 1881, 29.4 acres. In the earlier years, however, the areas under market gardens were included, hence the increase in the acreage under Orchards is considerably greater than appears. Oranges, apples, pears, and peaches are the principal fruits grown; but with an unlimited area suitable for fruit-cultivation, and with climatic conditions so varied, ranging from comparative cold in New Zealand and on the high lands of New South Wales and Victoria to tropical heat in Queensland, a large variety of fruits could be cultivated. The industry, however, languishes partly on account of the lack of skill and care on the part of the grower—good fruits commanding high prices, while those placed within the reach of the multitude are generally of lower quality—and partly owing to the lack of means of rapid transit to market at reasonable rates. The inferior quality of much of the fruit produced was due to the ravages of fruit pests. The pests were almost wholly imported from Europe and America on fruit and cuttings, and as the orchards of Australia were threatened, and the industry likely to be seriously interfered with, Acts have been passed in all the states prohibiting the importation of diseased fruit. The result of this legislation has been wholly beneficial, and if supplemented by legislation aimed at eradicating diseases existing in the orchards themselves, the future of the fruit industry would be assured.

Fruit-drying is a growing industry, and promises before long to attain considerable dimensions. At Mildura, on the left bank of the Murray, in Victoria, 8,386 acres are under intense culture, the crops raised including currants, sultanas, peaches, and citrus fruits. About 2,509 acres are under gordos, 2,141 acres under sultanas, and 299 acres under currants, as compared with 1,931, 870, and 148 respectively four years ago. On the other hand, a falling off is noticeable in the area under fruit-trees, especially in the case of apricots and peaches. The total area under fruit is now 1,961 acres, as compared with 3,225 acres in 1900. The rainfall is only about 9 inches per annum, but a plentiful supply of water is obtained by pumping from the Murray, and the channels command an irrigable area of about 15,317 acres. Last year the returns from the sale of fruits amounted to about £100,000. Included in the output were 1,200 gallons of olive oil, 1,688 tons of raisins, 745 tons of sultanas, and 90,000 cases of citrus fruits.

At Renmark, in South Australia, somewhat similar work is being carried on. Some 3,600 acres are under irrigation, and maintain a population of nearly 1,000 persons. The value of the fruits and olive oil sold amounted to £15,000 in 1903.

The area under orchards and gardens in 1881 and 1891, and under orchards only in 1903, was as follows:—

State.	1881.		1891.		1903.	
	Acres.	Percentage to total area under Crops.	Acres.	Percentage to total area under Crops.	Acres.	Percentage to total area under Crops.
New South Wales .....	24,565	4·3	40,116	4·7	48,832	1·9
Victoria .....	20,630	1·4	37,435	1·8	50,357	1·5
Queensland .....	3,262	2·8	9,758	4·0	12,873	2·3
South Australia .....	9,864	0·4	14,422	0·7	18,725	0·8
Western Australia .....	.....	.....	.....	.....	7,938	2·7
Tasmania .....	6,717	4·5	10,696	6·4	14,134	5·5
Commonwealth.....	65,038	1·5	112,427	2·1	152,850	1·6
New Zealand .....	16,360	1·5	29,235	2·0	26,792	1·6
Australasia .....	81,398	1·5	141,662	2·1	179,651	1·6

With the extension of artificial irrigation, and the increased facilities for export afforded by the adoption of cool chambers for the preservation of fruit during long voyages, the orchardists of Australasia are now enabled to compete with foreign states in the fruit supply for the English market, which averages about £11,000,000 in value annually. The Tasmanian fruit trade with England has passed the experimental stage, and every season large steamers visit Hobart to receive fruit for the home market. During the year 1903, Tasmania exported £111,229

worth of apples to Great Britain, while Victoria sent £15,640 worth; but, as that country imports annually some £2,000,000 worth of such fruit, there is ample scope for increasing the exports from Australia.

The following table shows the import and export trade of each state in green fruit and pulp for 1903, from which it will be seen that in Tasmania, Queensland, and South Australia the exports of domestic produce are now well above the imports, while in Victoria also they were slightly in excess of the imports during 1903 :—

State.	Imports.	Exports of Domestic Produce.
	£	£
New South Wales .....	306,903	142,381
Victoria .....	99,029	109,367
Queensland .....	81,388	119,331
South Australia .....	16,146	64,467
Western Australia .....	40,699	15
Tasmania .....	27,704	270,718
Commonwealth.....	571,869	706,279
New Zealand .....	116,123	7,058
Australasia .....	687,992	713,337

The average value of the produce of orchards, and the average return per acre, during 1903 were as given below :—

State.	Average Value of Crop.	Average Value per Acre.
	£	£ s. d.
New South Wales .....	336,000	8 1 9
Victoria .....	272,000	6 3 3
Queensland .....	127,000	9 19 7
South Australia ..	132,000	7 1 6
Western Australia .....	68,000	8 12 2
Tasmania .....	198,000	14 0 0
Commonwealth .....	1,133,000	7 8 2
New Zealand .....	190,000	7 1 6
Australasia .....	1,323,000	7 7 2

The average returns per acre have but little value for purposes of comparison, as much depends on the proportion of the areas under certain kinds of fruit which tends to increase or decrease, as the case may be, the general average of a state. It will be seen that New South Wales shows the largest return from this class of cultivation, the total value of the produce being £336,000, equal to an average of £8 1s. 9d. per productive acre. Considerable difficulty arose in arriving at the correct returns for the Victorian orchards. Accepting the growers' returns of the fruit gathered, and the average prices realised, the

total return amounts to £371,649, or an average of £6 3s. 3d. per acre. There is an opinion in official circles that these returns are considerably under the actual results, but conclusive evidence has not been adduced in support of this view. Assuming that the supposed understatement extends to 20 per cent., the value of the Victorian orchard crop would be £326,000, or £7 7s. 11d. per acre.

The bonuses offered by the Government of Victoria caused increased attention to be devoted to the fruit industry. Under the planting bonus of £3 an acre offered for trees planted after the 8th May, 1890, over 8,000 acres were cropped during the period of eleven years up till 1901. A sum of £25,000 was set apart for payment of these allowances, but the amount has now been expended and the payment of further bonuses is dependent upon the will of the Federal Parliament. The export trade also benefited by the system of bonuses. Prior to 1896 the amount was 2s. per case, but from that date, up to 1901, when the bonuses ceased, it was at the rate of 1s. per case.

In New South Wales the average production is small, though slightly in excess of Victoria. This latter feature is to be accounted for by the greater area under citrus fruits, which are on the whole more remunerative than deciduous fruits, the produce of which in a great number of instances, owing to lack of facilities for disposing of the crop, does not reach the markets, and in some cases is not even gathered.

In Tasmania, English fruits, such as apples and pears, are principally grown, and the excellent facilities for exporting these fruits to England makes the industry a very paying one. The average return per acre amounted to £14, while the total export of domestic fruit was as high as £270,718, or more than the domestic exports of New South Wales and Victorian fruit combined.

In Queensland the fruit industry is making good progress. The area under bananas increased by 1,311 acres during 1903, when 6,577 acres were under this crop. The Mourilyan district furnishes 54 per cent. of the total area planted with bananas. The area under pineapples is also increasing, 1,493 acres being under crop in 1903 as compared with 1,101 acres in 1902. Experiments have been made with a view of discovering the best means of keeping pineapples for export, and arrangements are in progress for canning the fruit.

In South Australia, Western Australia, and New Zealand there are extensive areas of land in every way adapted for fruit culture, and the industry in all the states shows fair progress. The fruit crop of New Zealand, however, has to be supplemented by considerable imports, the bulk of which comes from Fiji and the Commonwealth.

#### MARKET GARDENS.

In all the states considerable areas are devoted to market gardens, but except as regards New South Wales complete returns of acreage and production are not readily available. The following table, however,

gives a fair approximation of the value of the industry in the different states :—

	Area under crop.	Value of Production.
	acres.	£
New South Wales .....	8,754	213,000
Victoria .....	8,455	211,000
Queensland .....	2,563	47,000
South Australia.....	9,964	218,000
Western Australia.....	3,315	91,000
Tasmania.....	1,685	39,000
Commonwealth .....	34,736	819,000
New Zealand .....	3,869	87,000
Australasia ... ..	38,605	906,000

It may be noted here that of the area under cultivation for vegetables for local consumption, a considerable proportion in all the States is in the hands of the Chinese, who succeed in obtaining large returns from their gardens. In the Sydney metropolitan area about two-thirds of the market gardens are worked by the Chinese, the average return per acre being £43, as compared with £25 per acre for European gardens.

#### MINOR CROPS.

Besides the crops already specifically noticed, there are small areas on which are grown a variety of products, chiefly rye, onions, beans, peas, turnips, mangold wurzel, pumpkins, and hops ; but they are not sufficiently important to warrant special mention, except turnips in New Zealand, where no less an area than 408,659 acres were planted with this crop last year. The area under minor crops in each province in 1903 was as follows :—

State.	Acres.
New South Wales .....	15,204
Victoria.....	21,611
Queensland .....	28,211
South Australia .....	10,080
Western Australia .....	1,392
Tasmania .....	21,060
Commonwealth .....	97,558
New Zealand .....	508,152
Australasia .....	606,710

*Cotton.*—The recent agitation amongst British manufacturers in favour of increased supplies of cotton grown within the Empire led to a visit to these shores of a representative of the British Cotton-growing Association of Manchester, who reported very favourably regarding the climatic conditions and suitableness of large areas in New South Wales and Queensland for the cultivation of this crop. Extensive experiments have fully demonstrated that cotton of the finest quality can be produced in these States. In New South Wales the crop has not, so

far, been grown commercially; but in Queensland, under the stimulus of a Government bonus, 717 acres were planted in 1892, from which a production of 212,370 lb. of ginned cotton was obtained. Since that year, however, the area under crop has dwindled to comparative insignificance.

*Coffee.*—The cultivation of coffee promises to become of some importance in the near future, especially in Queensland. In 1903, 394 acres were under cultivation, of which 318 acres were bearing, the yield being 83,632 lb. The coffee-tree thrives well throughout almost the whole of the Queensland coastal districts; but the best average yield, 615 lb. per acre, was obtained at Herberton. The requirements of Australia approximate 2,300,000 lb. annually, so that there is ample scope for expansion in the local industry.

#### DISSEMINATION OF AGRICULTURAL KNOWLEDGE.

Although considerable progress has of late years been made in some directions, yet it must be admitted generally that agriculture in Australasia has only now passed the tentative stage. The typical Australian agriculturist, relying largely on a bountiful Nature, does not exercise upon his crops anything approaching the same patience, care, and labour that are bestowed by the European cultivator, nor as a rule does he avail himself of the benefits of scientific farming and improved implements to the extent that prevails in America and Europe. Improvements are, however, already noticeable in this respect, and the efforts made by the Governments of the various States for the promotion of scientific farming are beginning to bear good fruit. In most of the provinces, agricultural colleges and model farms have been established, and travelling lecturers are sent to agricultural centres. In New South Wales the Hawkesbury Agricultural College provides accommodation for 120 resident students. The farm attached to the institution comprises 3,430 acres, of which 597 acres were under crop in 1903. Instruction in dairying is made a speciality, and the butter and cheese factory is one of the most completely equipped in the state. Experimental farms are also established in various districts of the state, and the instruction is adapted to the climatic conditions. These farms are situated at Wagga, Wollongbar, Bathurst, Berry, Grafton, Coolabah, Cowra, Glen Innes, Pera Bore, and Moree. At the four first mentioned, accommodation is provided for students, who receive instruction in the practical farming work suited to the respective districts. The fees are small, amounting, as a rule, to about £25 per annum, which sum covers tuition and board, while at the Hawkesbury College and the farms several bursaries are awarded to specially deserving students.

In Victoria, the Dookie Agricultural College has accommodation for 60 resident students. It is situated in a healthy and picturesque part of the north-east district of the state, on the outskirts of the rich Goulburn Valley district. Attached to the college is a farm of

4,846 acres, which is equipped with modern dairy buildings, poultry runs, wine cellars, shearing shed, carpenters' shop, &c., and the education embraces the leading branches of agricultural, viticultural, and pastoral pursuits. Experimental farms are carried on at Longerenong and Framlingham, and at Rutherglen there is an extensive vineyard for the propagation of phylloxera-resistant stocks. At the horticultural gardens, situated at Burnley, near Melbourne, male and female students receive a thoroughly practical training in general horticultural work.

In 1897 the Queensland Government established an agricultural college and experimental farm at Gatton, about 58 miles west of Brisbane. Accommodation is provided for 60 residential students, and of the 1,692 acres of land attached to the college, 343 acres are at present under crop. State experimental farms are also in operation at Westbrook, Hermitage (near Warwick), Biggenden, and Gindie, while there is a State nursery at Kamerunga, near Cairns, and a Government tobacco farm at Texas. Extensive experiments are also carried on in connection with the sugar-growing industry, and at the central Government station at Mackay special modes of cultivation are tested, and experiments carried on in manuring, irrigation, &c. In order that the actual work of the central station may be brought before the cane-growers, 14 sub-stations conducted by farmers' associations have been established, where the most successful experiments conducted at the central station are repeated upon a small scale. In this way farmers become co-operators, and are brought into actual touch with the scientific work carried on by the Government experts.

New Zealand possesses an agricultural college and an experimental farm of 800 acres, at Lincoln, in Canterbury. During 1903, 37 students were on the roll, and this number is considered quite sufficient, in view of the size of the farm, to permit of each student acquiring practical experience in the various branches of work carried on.

South Australia has an agricultural college and experimental farm at Roseworthy; and a central agricultural bureau in Adelaide, with about one hundred branch bureaus in the country, assists the farmers by disseminating valuable information, publishing papers, introducing new economic plants, and improving the breed of dairy cattle. A state school has been established in Adelaide for the purpose of affording instruction to "secondary agricultural pupils." The fees paid by the scholars, who must be over 13 years of age and have passed the compulsory examination, are at the same rate as those paid in the ordinary state schools. In Tasmania, the Council of Agriculture gives valuable advice to farmers concerning improved methods of agriculture, extermination of insect pests, etc.

Western Australia possesses four experimental farms, situated at Narrogin, on the Great Southern line; Chapman, on the Geraldton-Northampton line; Hamel, on the S.-W. line; and Nangeenan, on the Eastern line. At the first two farms, students are admitted at nominal fees, the instruction being confined to practical work on the farm, with

the exception of occasional lectures by the scientific staff of the Agricultural Department. There are also sixty-five Agricultural Halls, erected by settlers, assisted by the Government, where lectures are delivered by officers of the Department, and, in addition, seventy-five Agricultural Societies in receipt of Government subsidy, through whose agency agricultural literature is distributed.

In Victoria, South Australia, and New Zealand, the Governments have established export depôts, where consignments of meat, butter, and other produce are inspected by Government experts, and graded and branded according to their quality. By this means little but produce of prime quality is exported, and the Colonies are gaining a high name in Great Britain for the excellence of the goods despatched.

#### STATE ADVANCES TO FARMERS.

The oldest system by which advances of money are made to farmers is probably that which was established, as early as 1770, by the German "Landschaften Bank"; and the principle, assuming different forms according to the circumstances of the countries into which it was introduced, was gradually extended to the other great countries of Europe, with the exception of the United Kingdom, where an unwieldy system of land transfer, and the growing accumulation of large estates, form obstacles in the way of its successful application. Since 1849, mainly by the efforts of Raiffeisen, the German Land Credit Banks have taken the form of purely co-operative institutions, and in this respect they have been followed by Sweden, the Baltic provinces of Russia, and Poland, as well as, to some extent, by Austria-Hungary; but in most of the European countries the institutions may be classed as partly state and partly co-operative. In France alone is the system exclusively administered by the state; and it is the French *Credit Foncier* which has been adopted in Australasia wherever the idea of rendering financial aid to agriculturists has been carried into effect, namely, in the states of New South Wales, Victoria, South Australia, Western Australia, Queensland, and New Zealand; while in Tasmania the system has received consideration.

It was not till very recently that New South Wales adopted the principle of advances to settlers. Act No. 1, of 1899, was passed to assist settlers who were in necessitous circumstances, or who were financially embarrassed owing to the droughts. Under this Act a Board was appointed to consider applications for relief, and determine whether such relief should be granted. No advance to any settler was to exceed £200, to be repaid in ten years at 4 per cent. per annum. An Amending Act (No. 1 of 1902) was passed, giving to the Board power to advance up to £500, and providing that the advances with interest thereon should be repaid within thirty-one years. Up to the 30th June, 1904, 9,572 applications had been received for advances, the amount applied for being £1,420,001. Of these applications, 4,415



have been refused or withdrawn. The number of applications approved is 5,194, representing advances to the amount of £502,828. Repayments of principal amount to £110,083, in addition to which £31,620 has been received in interest. The Government has in contemplation the introduction of a scheme somewhat on the lines followed in Victoria, in which the system will be carried on in connection with the Savings Bank.

In Victoria, a section of the Savings Banks Act of 1890 empowered the Commissioners to entertain applications for loans, and to lend sums of money on security by way of mortgage of any lands and hereditaments held in fee-simple free of all prior charges, quit-rents excepted, at such rate of interest as might, from time to time, be fixed by them. The conditions were not very liberal, but they endured for a number of years. Five per cent. was the rate of interest charged, and 2 per cent. was payable annually in redemption of the principal. Opportunity was taken in the Act for the amalgamation of the Savings Banks, assented to on the 24th December, 1896, to definitely grant advances to farmers under the land-credit system. Under the new Act the Commissioners of Savings Banks are empowered to assist farmers, graziers, market-gardeners, or persons employed in agricultural, horticultural, viticultural, or pastoral pursuits, by making advances, either by instalments or otherwise, upon the security of any agricultural, horticultural, viticultural, or pastoral land held by them, either in fee-simple, or under a lease from the Crown in which the rent reserved is taken in part payment of the purchase money of the land demised by such lease. The Commissioners have the option of making such advances either in cash or in mortgage bonds; and it is provided that all advances, together with interest at the rate of  $4\frac{1}{2}$  per cent. per annum, are to be repaid in sixty-three half-yearly instalments, or such smaller number as may be agreed upon by the Commissioners and the borrower. From the commencement of the Act to the 30th June, 1904, advances to the amount of £1,749,409 had been made. The total number of loans in existence on that date was 3,074, representing the sum of £1,340,551, averaging £436 each. The actual advances made during the financial year 1903-4 amounted to £159,925, of which £145,062 was advanced to pay liabilities, £4,187 to pay Crown rents, and £10,676 to improve resources of land, and to carry on. To enable them to make the necessary advances the Commissioners had sold Treasury bonds and debentures to the nominal value of £1,875,500, of which £471,475 have been redeemed, leaving a balance of £1,404,025. Up to 30th June, 1904, 8,278 applications were received, for an aggregate amount of £4,030,613. Of these, 6,409 applications, for a total sum of £3,187,489, were submitted to valuation. The Commissioners authorised 5,278 advances, amounting to £2,363,305, the amount applied for being £2,653,778, but 852 applicants declined the partial advances offered to them, amounting to £437,560, so that the net advances authorised up to 30th June, 1904, numbered 4,426,

and amounted to £1,925,745, of which £176,336 was in course of settlement. Of the applications valued, 1,131 were declined by the Commissioners, the amount of these being £533,711

In Queensland the Agricultural Bank Act, assented to on the 31st December, 1901, empowered the Government to establish a bank for the purpose of promoting the occupation, cultivation, and improvement of the agricultural lands of the state. The amount to be raised must not exceed £250,000, and may be advanced to farmers and settlers in sums not greater than £800. Applications for advances not exceeding £200 are to be given priority over those of a greater amount, and no advance must exceed 13s. in the £ of the fair estimated value of the improvements to be made. Interest at the rate of 5 per cent. per annum is to be paid on advances for a period of five years, and thereafter the advances must be repaid within twenty years by half-yearly instalments of £4 0s. 3d. for every £100 advanced. During the year 131 applications were received for advances, amounting in the aggregate to £17,173, while 26, aggregating £3,896, had been held over from 1903, awaiting the reports of the valuers. Of these, 116 were approved for £12,195, while 31 applications, for £3,850, remain to be dealt with as soon as the holdings have been inspected. The whole of the interest due to the bank on 1st January, 1904, was paid, while at the end of July interest in arrear, on which a penalty has been incurred, amounted to £142. The average of advances approved was £105. It has been pointed out by the authorities charged with the administration of the act that it would be desirable to extend the scope of the measure in the direction of allowing advances for such purposes as purchasing seed wheat, dairy stock, &c.

The South Australian Parliament, on the 20th December of that year, passed the State Advance Act of 1895, providing for the establishment of a State Bank for the purpose of making advances to farmers and producers, to local authorities, and in aid of industries, on proper security, consisting either of lands held in fee-simple or under Crown lease; the funds for this purpose to be raised by the issue of mortgage bonds guaranteed by the state. The rate of interest was to be a matter of arrangement between the bank and the borrower, the maximum being 5 per cent. per annum. To the 31st March, 1904, the South Australian State Bank, thus established, had advanced £889,976, and received repayments to the amount of £287,334. On that date there were arrears of interest to the amount of £1,880 outstanding. In order to enable these advances to be made, mortgage bonds had been sold to the amount of £874,230, of which £286,250 had been repurchased, leaving the amount current at £587,980. The advances made during the last financial year amounted to £95,967, and the repayments of advances made during the same period amounted to £55,072.

In Western Australia the Agricultural Bank Act of 1894 authorised the establishment of a bank for the purpose of assisting persons in the occupation, cultivation, and improvement of agricultural lands. Under

the provisions of the Act the manager of the bank is empowered to make advances to farmers and other cultivators of the soil on the security of their holdings in fee-simple, or under special occupation lease, or under conditional purchase from the Crown, or under the Homestead Farms Act of 1893. The advances are granted either for the purpose of making improvements on unimproved holdings, or of making additional improvements on holdings already improved, and, under the original Act, could not exceed in amount one-half of the fair estimated value of the improvements proposed to be made. The maximum rate of interest chargeable was fixed at 6 per cent. per annum, payable half-yearly, and it was provided that the largest sum to be advanced to any one person was to be £400. Repayment is made in half-yearly instalments of one-fiftieth of the principal sum, to commence on the 1st January or the 1st July next following the expiration of five years from the date of the advance, until the whole amount is repaid with interest. Arrangements can, however, be made for the repayment of advances at shorter intervals, and in larger instalments. For the purposes of the Act, improvements were defined as clearing, cultivating, and ringbarking; but by an Amending Act passed in 1896 the term was extended so as to include fencing, drainage works, wells of fresh water, reservoirs, buildings, or any other works enhancing the value of the holding. The same Act raised the largest sum which can be advanced to £800, reduced the maximum rate of interest to 5 per cent., made provision for the acceptance of pastoral leases as security, and allowed advances to be made up to three-fourths of the estimated value of the proposed improvements. A further Amending Act, passed in 1902, empowers the manager to advance up to two-thirds the value of improved agricultural, and one-half the value of improved horticultural, properties, the maximum grant to any one person being raised to £1,000. At least one-third of any sum borrowed under this Act must be expended in further improvements; the balance may be applied to the liquidation of liabilities, or to the purchase of stock, plant, or other farm requisites. Where portion of an advance is made to pay off liabilities, the repayment of so much of the advance begins after the expiration of one year from the date of the advance. The capital allotted to the bank is £300,000, and to the 30th June, 1904, loans to the value of £310,650 had been approved; while repayments to the value of £25,373 had been made. During the financial year 1903-4, loans were advanced to 768 applicants, the total granted being £10,945. The transactions of the bank for the same period resulted in a net profit of £2,036.

In New Zealand the Government Advances to Settlers Act of 1894 provided for the establishment of an Advances to Settlers Office, empowered to lend money on first mortgages of land occupied for farming, dairying, or market-gardening purposes, urban and suburban lands used for residential or manufacturing purposes being expressly excluded from the scope of the Act. At that time one class of loans

only was contemplated, viz., loans on mortgage security, which were repayable by seventy-three half-yearly instalments, subject, however, to redemption at any time; but by an Amending Act passed in 1896 authority was given for the granting of fixed loans for any term not exceeding ten years. These loans are chiefly granted on freehold lands, and are repayable without sinking fund at the end of the period for which they are made. The amount advanced on fixed loan is not to exceed one-half the estimated value of the security; while under the instalment system the Board of Control has power to grant loans up to 60 per cent. of the realisable value of freehold securities, and up to 50 per cent. of the lessee's interest in leasehold securities. In both cases interest is fixed at the rate of 5 per cent. per annum, and the amount advanced cannot be less than £25 nor more than £3,000—the maximum under the 1894 Act having been £2,500. Instalment loans are repayable in 36½ years, in half-yearly payments, at the rate of 5 per cent. for interest and 1 per cent. in redemption of the principal sum. The first meeting of the General Board for the purpose of considering applications for loans was held on 23rd February, 1895; and up to 31st March, 1904, the Board had authorised 14,413 advances, amounting to £4,854,040. The total amount applied for in the 14,413 applications granted in full, or in part, was £5,478,020. 1,877 applicants declined the partial grants offered to them, amounting to £844,520; so that the net advances authorised at 31st March, 1904, numbered 12,536, and amounted to £4,009,520. The security for the advances authorised was valued at £8,704,640. The number of applications received up to 31st March, 1904, was 18,285, and the amount applied for, £6,630,981. The 1 per cent. sinking fund in the hands of the Public Trustee amounts to £158,520.

#### WATER CONSERVATION.

The necessity of providing water for stock in the dry portions of the interior of the Australian continent induced the Governments of the states to devote certain funds to the purpose of sinking for water, and bringing to the surface such supplies as might be obtained from the underground sources which geologists stated to exist in the tertiary drifts and the cretaceous beds which extend under an immense portion of the area of Central Australia, from the western districts of New South Wales to a yet unknown limit into Western Australia.

In New South Wales the question of the existence of underground water had long been a subject of earnest discussion, but doubts were set at rest in 1879 by the discovery on the Kallara run, at a depth of 140 feet, of an artesian supply of water, which, when tapped, rose 26 feet above the surface. The Government then undertook the work of searching for water, and since the year 1884 the sinking of artesian wells has proceeded in a scientific and systematic manner, under the direction of specially-trained officers. Private enterprise, which had shown the way, has also followed up its first successes.

Up to 30th June, 1904, the Government of New South Wales had undertaken the sinking of 125 wells; of these, 119 have been completed, and 6 are in progress. Of the total number of wells, 80 are flowing, 24 are sub-artesian, yielding pumping supplies, and 15 have been failures; these wells represent 205,238 feet of boring, while with the uncompleted wells the total depth bored has been 216,059 feet. From the completed Government wells about 49,300,000 gallons of water flow every day to the surface. The deepest bore completed is that at the Dolgelly, on the road from Moree to Boggabilla, where boring has been carried to a depth of 4,086 feet; this well yields a supply of approximately 682,000 gallons per diem. The largest flow obtained in the state is from the Milchomi Bore, near Pilliga, which was completed in February, 1904; the depth of this well is 2,029 feet, and the estimated flow about 1,728,000 gallons per diem. The bore at Walgett, with a depth of 2,036 feet, has a daily flow of some 948,000 gallons. Another important bore is that at Pera, 8 miles from Bourke, on the Wanaaring road, where at a depth of 1,154 feet a flow of 116,600 gallons per diem is obtained. At this bore the most extensive system of irrigation by artesian water as yet undertaken in the state is being carried out. An area of 57 acres has been set apart for experimental cultivation by the Government, and certain fruits and other products indigenous to the temperate and torrid zones are being grown with success. The Pera No. 2 Bore, gives an average daily flow of 100,000 gallons. Equally good results have been obtained at Native Dog, Barrington, Enngonia, and Belalie bores, on the road from Bourke to Barrington. Lucerne, maize, wheat, tobacco, millet, planter's friend, sugar-cane, date palms, pineapples, bananas, and many other fruits and vegetables of tropical and sub-tropical character have been found to thrive there exceedingly well.

On the road from Wanaaring to Milparinka, once a waterless track, successful boring operations have been carried on. Eight bores have been completed. Four of these give a pumping supply, and four are flowing, yielding an aggregate supply of 3,150,000 gallons daily. A remarkable flow has also been obtained at the Moree bore, amounting to 837,250 gallons daily. This bore has been carried to a depth of 2,792 feet, through formations of the same age as the Ipswich coal measures (*Trias Jura*), thus demonstrating the fact that water can be obtained in other than the lower cretaceous formation. An experimental farm has been established at this site, where sub-tropical fruits and plants are grown. Among other important Government Bores that have been sunk may be mentioned that at Warren with a daily flow of 294,000 gallons, Coonamble 636,000 gallons, Old Gnomery, near Goodooga, 1,046,000 gallons, and Tuon, near Barrington, 600,000 gallons, per diem. No reliable figures can at present be given as to the total flow of private wells, but the information is being collected and will shortly be available. It is possible, however, that the discharge from the private bores exceeds that from the Government wells.

Much has been done in the way of artesian boring by private enterprise. As far as can be ascertained, 166 private bores have been undertaken in New South Wales, of which 16 were failures, 2 were abandoned, and 4 are in progress. Amongst the most important are two wells on Lissington Holding, one at Cuttabulla (Lila Springs), one at Toulby, and one at Goondabluie.

The average depth of the 103 wells completed by the Government is 1,724 feet 8 inches, with a range from 165 to 4,086 feet, while the temperature of the water varies from 80 to 139 degrees Fah. The total cost of the wells (including actual boring, casing, carriage, and incidental expenses) was £345,916, or an average of £2,906 17s. 1d. per bore, or £1 13s. 8d. per foot.

In Queensland up to the 30th June, 1903, there were 960 completed bores, of which 70 were Government, 32 Local Government, and 858 private bores. Since that date little information has been compiled by the Queensland authorities regarding artesian wells. It is known, however, that subsequent to the time mentioned one additional Government bore has been completed, the depth being 2,361 feet and the flow 954,462 gallons per diem; also, that three other Government bores are in progress.

Of the Government bores, 26 are artesian, 18 sub-artesian, and 27 were abandoned as failures. The daily flow of water from the successful bores amounts to 11,782,800 gallons. The Local Government bores included 11 artesian and 19 sub-artesian, while 2 were abandoned. From the successful bores a daily flow of 6,346,300 gallons is obtained. Of the private bores, 540 were artesian, 174 were sub-artesian, and 135 were failures or uncertain. It is estimated that the daily flow of water from private bores amounts to no less than 368,331,200 gallons. The large proportion of abandoned Government bores is due to the fact that many of them were sunk for experimental purposes in order to ascertain the prospects of obtaining artesian water. Others were put down by the old methods of boring, by which depths over 1,000 feet could not be penetrated in the swelling clays of Queensland. The total expenditure by the Government up to the 30th June, 1903, amounted to £368,629 on water conservation, of which £124,039 was expended on artesian bores. The deepest Government bore is at Winton, and reaches 4,010 feet, while the most copious supply, namely, 3,000,000 gallons per day, is obtained at the Charleville bore. The deepest private bore, and also the deepest bore in the state, is the Whitewood on the Bimerah run, and reaches 5,045 feet. The largest supplies are obtained from the Longlands bore, which yields 6,000,000 gallons daily; Corio-Cunnamulla East, 4,500,000; Burrumbilla and Gooia, Cunnamulla West, 4,000,000; Boatman, 3,500,000; and Savannah Downs yielding 3,400,000 gallons daily. The total depth bored in search of artesian water up to 30th June, 1903, was 1,171,461 feet, the average depth per bore being 1,220 feet. At Helidon water of so low a temperature as 60 degrees Fah. was flowing; while at Elderslie No. 2 the water had a

temperature of 202 degrees. Extensive areas are served by the water from the bores for irrigation purposes; in 1903 there were 14,786 acres irrigated, as compared with 6,526 acres in 1901. In addition several stations, which did not furnish returns, also used the water for purposes of irrigation. Some of the bore waters contain soda in various forms, and these it is impossible to use, except for a limited period, and in small quantities. Of the 14,786 acres irrigated, 3,952 acres—or 27 per cent.—are served with water from artesian bores; 2,760 acres being irrigated with artesian water at Cunnamulla.

At the end of 1903 the Water Conservation Department of South Australia had completed 107 bores, of which, however, only fifty were successful. These are spread over widely-distant parts of the territory, successful bores existing at Nullarbor Plains, on the boundary of Western Australia; at Oodnadatta, the present terminus of the Northern Railway system; and at Tintinara, in the south-eastern extremity of the state. The bore at Tintinara has proved that the marine tertiary area is water-bearing. The south-western portion of the great artesian basin lies under the north-east corner of South Australia proper, and a portion of it is under the south-eastern corner of the Northern Territory. This portion of the basin covers an area of 120,000 square miles, and towards its southern and western fringe occur the well-known mound springs, naturally indicating the existence of artesian water. Of the Government borings in this basin, there are eight flowing artesian wells under 1,000 feet in depth, ten from 1,000 to 3,000 feet, three between 3,000 and 4,000 feet, and one from 4,000 to 5,000 feet. It will therefore be seen that the South Australian Government has had considerable difficulties to overcome in prosecuting the work of opening up these sources of national wealth. The sea basin, which at one time existed within what is now South Australia, was of great depth, and many of the bores pierced through a thickness of strata varying from three-quarters of a mile to nearly a mile before striking the artesian water. The daily flow from the bores ranges from 4,000 to 1,200,000 gallons. The quality of the water varies considerably. Most of the bores furnish excellent drinking water, but towards the fringe of the basin, where there is little or no circulation, the supply is too salt for domestic use, and is only fit for cattle. The average increase in the temperature of the water has been found to be 1 degree Fah. to every 27 feet in depth. From certain of the deep borings, the water flows over the surface at a temperature of about 200 degrees Fah. Some very successful bores have also been put down on pastoral holdings. In some other parts of South Australia there are comparatively small local artesian basins from which good supplies have been obtained. Four successful bores have been put down in these districts by the Government, and the artesian areas have also been tapped by private persons. The depth of the private bores, however, is seldom over 200 feet. In parts of the state, where flowing supplies are not obtainable, the Government has for

many years carried on boring operations, and in a fair number of cases sub-artesian water has been struck.

The results from Government bores up to 31st December, 1903, are as follows :—

Flowing artesian wells .....	27
Sub-artesian wells (water good for stock) .....	23
Salt, or otherwise unsuccessful bores .....	57
	—
Total .....	107

In addition to these, two deep borings are in progress. The total expenditure by the Government on boring has been £271,441, of which £11,190 was expended during the year 1903.

The Government of Western Australia, following the example set by those of the eastern states has sunk 30 bores in various parts of the state, and 14 bores have been sunk by private owners. Of the Government bores, 25 have been successful, and yield a daily supply of 8,469,000 gallons, and 5 were failures. All the private bores yield supplies of water with the exception of two—the daily flow being 2,414,000 gallons. The deepest flowing bore is at Carnarvon, and reached a depth of 3,011 feet; while the largest supply is obtained from the municipal bore at Guildford, and amounts to 1,120,000 gallons daily. Up to the 31st December, 1903, the Government had expended £55,835 on artesian boring, while £9,819 had been spent by private owners. Amongst the most important bores completed during 1903 was the No. 1 bore, at Eyre. This is one of a series of bores put down for the purpose of ascertaining whether a supply of artesian water would be available for the suggested Trans-continental Railway. It has resulted in a flow of 31,000 gallons of stock water per day at a depth of 2,101 feet.

The total expenditure on water supply has amounted to £3,383,795, included in which is a sum of £2,672,165 for the Coolgardie Water Supply scheme.

In Victoria the attempts to obtain water by means of artesian boring have not been successful. Up to the 30th June, 1904, 46 bores had been sunk, 16 of which were driven to bed-rock, but none yielded artesian supplies. The expenditure on these bores amounted to £68,864, and the cost of water conservation, including Government expenditure on Melbourne Water Supply, was £8,803,314.

#### EMPLOYMENT IN AGRICULTURAL PURSUITS.

The following table shows the number of persons engaged in agricultural pursuits in Australasia during the years 1891 and 1901. The figures relate to the direct producers who were employed on holdings at the end of March in each year, and are exclusive of persons engaged in



the manufacture of raw materials, as well as of casual hands who may have been employed at other periods of the year than that stated.

State.	1891.			1901.		
	Males.	Females.	Total.	Males.	Females.	Total.
New South Wales .....	67,576	7,022	74,598	75,884	1,735	77,619
Victoria .....	79,090	6,028	85,118	78,539	17,381	95,920
Queensland .....	33,891	6,089	39,980	38,260	2,081	40,341
South Australia .....	27,961	886	28,847	33,039	1,147	34,186
Western Australia .....	4,378	164	4,542	8,322	285	8,607
Tasmania .....	14,584	1,447	16,031	17,348	2,074	19,422
Commonwealth .....	227,480	21,636	249,116	251,392	24,703	276,095
New Zealand .....	56,671	2,387	59,058	65,723	2,089	67,812
Australasia .....	284,151	24,023	308,174	317,115	26,792	343,907

A classification of the returns for 1901 according as the persons employed in agricultural pursuits were engaged therein as proprietors and managers, relatives assisting, or servants, is given below for all the states except Queensland, where the information has not been published.

State.	Proprietors and Managers.			Relatives assisting.			Servants.		
	Males.	Females.	Total.	Males.	Females.	Total.	Males.	Females.	Total.
New South Wales ..	32,466	1,607	34,073	10,271	111	10,382	83,147	17	33,164
Victoria .....	33,533	3,031	36,564	17,609	18,625	31,234	27,547	725	28,272
South Australia .....	13,796	691	14,487	4,108	240	4,348	15,135	216	15,351
Western Australia ..	2,747	181	2,928	1,426	139	1,565	2,149	15	2,164
Tasmania .....	7,028	371	7,399	3,373	1,206	4,578	6,947	498	7,445
New Zealand .....	29,840	1,091	30,931	12,301	841	13,142	24,082	187	24,269

With regard to Victoria it appears that females engaged in domestic duties, who also gave some assistance in farming, were classified as relatives assisting in agricultural pursuits, whereas, in other states, these were included in the category of dependents performing domestic duties.

In proportion to population the persons engaged in agricultural pursuits numbered 8·9 per cent. in 1891, compared with 7·6 in 1901. The decrease in the latter year is accounted for partly by the rapid extension of the dairying industry which has absorbed many of those formerly engaged in agriculture, and partly by the increased cultivation of wheat, which does not require such a large proportion of labour as other miscellaneous crops.

## PASTORAL RESOURCES AND DAIRY INDUSTRY.

**N**OTWITHSTANDING the fact that the soil, climate, and indigenous herbage of Australasia are admirably adapted to the sustenance of animal life, no attempt was made to test the capabilities of the land as a feeding-ground for flocks and herds on a large scale until the example of Captain Macarthur had demonstrated beyond doubt that Nature favoured the production in Australasia of a quality of wool which was unsurpassed by that grown in any part of the world. Then the settlers began to understand and utilise the natural resources of the country ; and as the indomitable spirit of exploration gradually opened up the apparently boundless plains of the interior, pastoralists extended their domain, and sheep and cattle in increasing numbers spread over the face of eastern Australia. At the present time the pastoral industry has attained such dimensions that its products constitute the chief element in the wealth of Australia. Since 1851 the export of wool from Australia has reached the enormous sum of £610,000,000 sterling, or over £230,000,000 in excess of the value of the gold produced during the same period. More extended reference to the value of production from the pastoral industry will be found in succeeding pages.

The beginnings of pastoral enterprise in Australia were very humble. The live stock of the community which accompanied Captain Phillip comprised only 1 bull, 4 cows, 1 calf, 1 stallion, 3 mares, 3 foals, 29 sheep, 12 pigs, and a few goats ; and although the whole of the present flocks and herds of Australasia have not sprung from these animals alone, yet the figures show the small scale on which the business of stock-raising was first attempted. No systematic record of the arrival of stock seems to have been kept in the early days of settlement ; but it would appear that during the period between Governor Phillip's landing and the year 1800 there were some slight importations, chiefly of sheep from India. In 1800 the stock in Australasia comprised 6,124 sheep, 1,044 cattle, 203 horses, and 4,017 swine ; while at the end of the year 1901, there were no less than 92,358,824 sheep, 9,827,433 cattle, 1,905,172 horses, and 1,171,381 swine.

The following figures give the number of stock in Australasia at various dates up to 1851 :—

Year.	Sheep.	Cattle.	Horses.	Swine.
1792.....	105	23	11	43
1800.....	6,124	1,044	203	4,017
1810.....	33,818	11,276	1,114	8,992
1821.....	290,158	102,939	4,564	33,906
1842.....	6,312,004	1,014,833	70,615	66,086
1851.....	17,326,021	1,921,963	166,421	121,035

The increase in the number of each kind of live stock since the year 1861 is illustrated in the following table :—

Year.	Sheep.	Cattle.	Horses.	Swine.
1861.....	23,741,706	4,039,839	459,970	362,417
1871.....	49,773,584	4,713,820	782,558	737,477
1881.....	78,063,426	8,709,628	1,249,765	903,271
1891.....	124,991,920	11,861,330	1,785,835	1,154,553
1901.....	92,358,824	9,827,433	1,905,172	1,171,381
1903.....	73,652,026	8,698,242	1,845,959	1,077,147

The average number of sheep, cattle, horses, and swine per head of the population of Australasia at the same periods was as follows :—

Year.	Sheep.	Cattle.	Horses.	Swine.
1861.....	18·8	3·2	0·4	0·3
1871.....	25·3	2·4	0·4	0·4
1881.....	27·7	3·1	0·4	0·3
1891.....	31·8	3·0	0·5	0·3
1901.....	20·2	2·1	0·4	0·3
1903.....	15·3	1·8	0·4	0·2

It will be seen that in 1861 there were 18·8 sheep for every person in Australasia, and that this number had increased to 31·6 in 1891. In consequence of the continued dry seasons, and the demands made upon the flocks for the export trade, the average for 1903 has fallen to 15·3 per inhabitant. The average number of cattle depastured during last year per inhabitant was 1·8, as against 3·2 forty-two years ago. The breeding of horses and swine has about kept pace with the population.

#### SHEEP.

The suitability for pastoral pursuits of the land discovered in the early days was undoubtedly the means of inducing the infant colony of New South Wales to take its first step on the path of commercial progress, and, looking backward, it is not a little surprising to find how steadily some of the settlers, in the face of the almost insurmountable difficulty of transport which existed a century ago, availed themselves of the opportunities at their disposal. The importation of valuable specimens of sheep from England or the Cape of Good Hope prior to the introduction of steam was at all times attended with great risk, and it frequently happened that many of these costly animals died during the tedious voyage. These enterprises were, however, on the whole successful, and thus the flocks and herds of the colonists surely, if at first slowly, increased and multiplied.

By the year 1795, Captain Macarthur, one of the first promoters of sheep-breeding in New South Wales, had accumulated a flock of 1,000 sheep, which were held in great estimation, and gradually increased in value until, as recorded by an entry in his journal ten years later, the market price of a fat wether had risen to £5. Not satisfied with the natural increase of his flocks, Macarthur sought to improve the quality of his fleeces, by which means he could see opening before him the promise of great wealth and the prospect of establishing important commercial relations with Great Britain. With these ends in view, he procured from the Cape of Good Hope, at great cost and trouble, a number of superior rams and ewes. A happy circumstance favoured his enterprise; for he had the good fortune to secure three rams and five ewes of very fine Spanish breed, which had been presented by the King of Spain to the Dutch Government. These animals, out of a total of twenty-nine purchased at the Cape, arrived in Sydney in 1797, and were disposed of to various breeders. With the exception of Macarthur, however, those who had secured sheep of the superior breed made no attempt to follow up this advantage, being probably amply satisfied with the larger gains from the sale of an increased number of animals. Macarthur, on the other hand, thought little of present profits, and still less of breeding entirely for human consumption. He attentively watched the results of crossing his imported rams with the old stock, and by systematically selecting the finer ewes which were the offspring, for further mingling with the sires, he gradually improved the

strain, and in a few years obtained fleeces of very fine texture which met with the ready appreciation of English manufacturers. It has been asserted that Macarthur was not the first to introduce merino sheep into Australia; but whether this be so or not, there is no doubt that to him is due the credit of having been the first to prove that the production of fine wool could be made a profitable industry in New South Wales.

Prior to the present century the production of the finest wool had been confined chiefly to Spain, and woollen manufactures were necessarily carried on in England upon a somewhat limited scale, which was not likely to improve in face of certain restrictions which the operatives endeavoured to place upon their employers. These men, in support of their contention that the woollen trade could not be expanded on account of the limited supply of raw material, argued that fine wool was obtainable only in Spain; and it was at this favourable period that Macarthur arrived in England with specimens of the wool obtained from his finest sheep, conclusively proving the capabilities of Australia as a wool-producing country. In this way he opened up with English manufacturers a small trade which, as Australasian wool rose in public estimation, gradually increased until it reached its present enormous dimensions. During his visit to England, Macarthur purchased an additional stock of ten rams and ewes of the noted Spanish breed, nearly equal in quality to those which in 1797 he had procured from the Cape of Good Hope. That these animals were the finest obtainable in Europe may be gathered from the fact that they also had formed portion of a present from the King of Spain to George III. After his return to New South Wales, Macarthur patiently continued for many years the process of selection, with such success that in 1858, when his flock was finally dispersed, it was estimated that his superior ewes numbered fully 1,000. Victoria secured a considerable portion of his flock, and the process of breeding proceeded simultaneously in that and other adjacent states.

Although the increase in the numbers of the finer sheep was satisfactory, yet the importation of superior stock was not discontinued, and the stock of the states was augmented in 1823 and 1825 by the further introduction of Spanish sheep. Sheep-breeding was about this period commenced in the Mudgee district of New South Wales; the climate of that region had a more favourable effect upon the quality of the fleeces than that of any other part of the state, and it was thence that the finest merinos were for a long time procured. As was to be expected, the climate has in some respects changed the character of the Spanish fleece. The wool has become softer and more elastic, and while it has diminished in density it has increased in length, and the weight of the fleece has considerably increased. Thus, on the whole, the quality of the wool has improved under the beneficial influence of the climate, and if no further enhancement of its intrinsic value can be reasonably hoped for, there is at least every reason to believe that Australasian wool will maintain its present high standard of excellence.

The following table shows the number of sheep in each state at intervals of ten years since 1871 :—

State.	Number of Sheep.				
	1871.	1881.	1891.	1901.	1903.
New South Wales	16,278,697	36,591,946	61,831,416	41,857,099	28,656,501
Victoria.....	10,002,381	10,287,265	12,928,148	10,841,780	*8,774,731
Queensland .....	7,403,334	8,292,883	20,289,633	10,030,971	8,392,044
South Australia....	4,412,055	6,810,856	7,745,541	5,060,540	5,350,253
Western Australia	670,999	1,267,912	1,962,212	2,542,844	2,600,633
Tasmania.....	1,305,489	1,847,479	1,664,218	1,792,481	1,597,053
Commonwealth .	40,072,955	65,078,341	106,421,168	72,125,725	55,371,220
New Zealand....	9,700,629	12,985,085	18,570,752	20,233,099	18,280,806
Australasia .....	49,773,584	78,063,426	124,991,920	92,358,824	73,652,026

\* Estimate.

In all the states the number of sheep depastured had prior to 1903 largely increased during the period shown above with the exception of Tasmania. In that state, however, more attention is directed towards the breeding of stud sheep than to raising immense flocks, and the stud farms of the island have gained considerable distinction, and are annually drawn upon to improve the breed of sheep in the other states.

In South Australia the area adapted to sheep is limited, and no great expansion in sheep-farming can be looked for. As regards Victoria, the important strides made in agriculture and kindred pursuits afford sufficient explanation of the diminished attention paid to sheep farming. The statement given below shows, for 1903, the proportion of sheep in each state to the total flocks of Australasia, the Victorian figures being an approximation in the absence of official returns. New South Wales, with 38·9 per cent. of the total flock, comes first, and New Zealand, with 24·8 per cent., second, while Victoria, with 11·9 per cent., and Queensland, with 11·4 per cent., are next in order. The other three states together possess only 13 per cent. of the whole.

State.	1903. per cent.
New South Wales .....	38·9
Victoria .....	11·9
Queensland .....	11·4
South Australia.....	7·3
Western Australia .....	3·5
Tasmania .....	2·2
New Zealand .....	24·8
Australasia .....	100·0

In order to show the increase or decrease in sheep during the last nineteen years, the following table has been prepared, giving the numbers in the various states at the end of each year since 1885. It will be

seen that returns were not collected in some years in Victoria, South Australia, and New Zealand, and that the figures for those states are therefore incomplete:—

Year.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	New Zealand.
1885	37,820,906	10,681,837	8,994,322	*	1,792,719	1,648,627	16,564,596
1886	39,169,304	10,700,408	9,690,445	*	1,809,071	1,699,046	*
1887	46,965,152	10,623,085	12,926,158	*	1,909,940	1,547,242	*
1888	46,503,460	10,818,375	13,444,005	*	2,112,392	1,430,065	15,468,800
1889	50,106,768	10,882,231	14,470,095	6,482,401	2,366,681	1,551,429	15,503,263
1890	55,986,431	12,692,843	18,007,234	7,050,544	2,524,913	1,619,256	18,128,186
1891	61,831,416	12,928,148	20,289,083	7,745,541	1,962,212	1,664,218	18,570,752
1892	58,080,114	12,965,306	21,708,310	7,209,500	1,685,500	1,623,338	19,880,369
1893	56,980,688	13,098,725	18,697,015	7,325,008	2,290,642	1,535,047	20,230,829
1894	56,977,370	13,180,043	19,557,091	*	2,132,311	1,727,300	19,826,604
1895	47,617,687	*	19,856,959	*	2,295,832	1,523,846	19,138,493
1896	45,318,790	*	19,593,096	6,402,593	2,248,976	1,650,567	19,687,954
1897	43,952,497	*	17,797,883	5,092,078	2,210,742	1,578,611	19,673,725
1898	41,241,004	*	17,552,008	5,076,696	2,251,548	1,493,638	19,348,506
1899	36,213,514	*	15,226,479	5,721,493	2,282,306	1,672,068	19,347,346
1900	40,020,506	*	10,339,185	5,283,247	2,431,661	1,638,956	19,356,195
1901	41,857,099	10,841,790	10,030,971	5,060,540	2,542,844	1,792,481	20,233,099
1902	36,640,424	*	7,213,065	4,922,662	2,697,897	1,679,518	20,342,727
1903	28,656,501	13,774,731	8,392,044	5,350,258	2,690,683	1,597,053	18,280,806

\* Returns not collected.

† Estimated.

The number of sheep depastured in the Commonwealth increased with great regularity each year until 1891, when it reached 106,400,000; since that year, up to 1903, there was an almost continuous succession of unfavourable seasons in New South Wales and Queensland, the two states chiefly interested in pastoral pursuits, with the result that the number of sheep depastured in these states decreased by about 44,000,000 during the ten years 1893–1902. In Queensland the number fell from 15,226,000 in 1899, to 10,339,000 in 1900, a decrease of 4,887,000 in one year, and at the present time the number is only just over 8,392,000. In New South Wales the returns place the number of sheep depastured in December, 1903, at 28,656,501, which, with the exception of 1902, is lower than in any year since 1884. The other states did not suffer to the same extent from adverse seasons, although the number of sheep in both Victoria and South Australia has decreased considerably since 1891. In Western Australia there was an increase in the numbers, while in New Zealand, the figures show a small reduction on the number in 1891, consequent on the heavy demands of the frozen meat trade. The weather conditions in the Commonwealth considerably improved during 1903, and the flocks are steadily increasing.

During the last ten years there has been a tendency towards dividing the sheep into smaller flocks. This is especially noticeable in New South Wales and Queensland. In the former state there are now 17,361 sheep-owners as compared with 14,033 in 1893, while the average size of the flocks in 1903 was about 1,650, as against 4,050 in the former year. Of the flocks in the state no less than 10,557 number 500 sheep and under, including 5,492 flocks of 100 and under.

In Queensland, at the present time, there are 1,914 sheep-owners as compared with 1,440 in 1893, the average size of the flocks in 1903 being 4,385 as compared with 12,984 in 1893.

Adverse seasons during the period had, of course, the effect of considerably diminishing the number of sheep in each state, but, when full allowance has been made on this score, it will be found that the size of the flock has greatly decreased.

In New Zealand there are at the present time 18,761 flock-owners, as compared with 12,293 in 1891; while 12,428 persons possess flocks of 500 sheep and under, as against 8,272 in 1891. There are now only 110 flocks of 20,000 and upwards, as compared with 169 in 1891.

Of the 537,149 stud sheep in New Zealand in April, 1903, the proportions of the various breeds were as follows:—

	Per cent.
Romney .....	21·9
Lincoln .....	21·0
English Leicester .....	15·8
Merino .....	13·7
Border Leicester .....	11·5
Shropshire .....	7·9
South Devon .....	2·1
Other .....	6·1
Total .....	100·00

Out of a total of 18,417,404 flock sheep there were 86·6 per cent. crossbreds and other long wools, while 13·4 per cent. were merinos.

The total number of sheep (including lambs) slaughtered in the various states from which the information is available during the eight years ended 1903 is shown below. For South Australia no slaughtering returns are available, while the figures for Tasmania refer to the numbers killed in Hobart and Launceston only.

Year.	New South Wales.	Victoria.	Queensland.	Western Australia.	Tasmania (Hobart and Launceston).	New Zealand.
1896	6,196,749	2,559,088	1,726,125	420,952	102,766	.....
1897	5,790,103	2,434,519	1,902,735	505,091	107,223	.....
1898	5,665,763	2,352,694	1,262,313	433,867	104,303	4,749,720
1899	4,795,259	2,557,858	1,497,546	.....	93,913	5,248,431
1900	4,359,513	2,371,415	860,648	445,046	91,829	4,855,135
1901	4,519,133	2,469,797	554,705	428,234	101,627	5,234,138
1902	4,635,850	2,627,938	772,349	482,907	114,900	5,988,578
1903	3,277,120	2,652,569	483,592	412,484	122,223	6,864,622



The value of the sheep depastured in Australasia, on the basis of the average prices ruling in 1903, was £50,439,000, thus distributed among the various states :—

	£
New South Wales .....	19,617,000
Victoria .....	6,022,000
Queensland .....	5,665,000
South Australia .....	3,603,000
Western Australia .....	1,791,000
Tasmania .....	1,149,000
Commonwealth .....	37,847,000
New Zealand .....	12,592,000
Australasia .....	£50,439,000

It is a difficult task accurately to estimate the number and proportion of merino sheep in the flocks of the world, but it may be affirmed with a considerable degree of confidence that at present Australia has no serious rival in the position of chief supplier of the finest merino wool. As regards the total number of sheep possessed by any one country, it will be seen from the table on page 414 that the Argentine apparently occupies pride of place, but according to the returns the flocks of that country comprise only a small proportion of pure merinos. Prior to 1888 the merino class predominated, but thenceforward increased attention was given to the breeding of long-woolled sheep, and at present long-woolled crossbreds, famed alike for their mutton as well as for their wool yielding qualities, comprise about 70 per cent. of the Argentine flocks. The wool imported into Great Britain from the Argentine during the year 1903 was made up of 65 per cent. crossbred and 35 per cent. merino. Of the total quantities produced by the colonies and the Argentine in 1903, the proportions of crossbred and merinos were respectively 51·3 and 48·7 per cent., these figures showing that an entire change has taken place in the character of the wool produced since 1895, when the proportion of crossbred wool was 31·7 per cent., while the merino was no less than 68·3 per cent.

Prior to the year 1870, more than four-fifths of the sheep in the United States were either pure-bred or grade merinos, but with the increase of population in the states east of the Mississippi meat became of more importance than wool, and mutton breeds gradually gained the supremacy. At present the number of merinos and the English type of sheep is about equal, the former predominating in the range states and the latter in the farming states.

As illustrating the predominance of the merino in Australia and the crossbred in New Zealand it is interesting to note that of the Australasian crossbred wools catalogued in London in 1903, only 15 per cent. came from Australia, while New Zealand furnished 85 per cent.

Of the flocks in Russia it is estimated that about 15,000,000, or nearly 20 per cent., are merinos, the Rambouillet being a favourite breed.

The following table shows the total number of sheep in various countries of the world, based on the latest available returns :—

	Number of Sheep.
British Possessions—	
United Kingdom .....	29,658,863
Australasia .....	73,652,028
South Africa .....	14,290,778
India .....	17,736,199
Canada .....	3,100,614
Other British Possessions .....	1,230,851
Foreign Countries—	
Algeria .....	8,724,700
France .....	19,669,682
*Russia in Europe.....	60,174,600
Spain .....	13,359,473
Other European Countries.....	47,055,373
Argentina .....	100,000,000
United States .....	51,630,144
Other American States .....	21,048,978
Other Countries .....	13,466,600
Total .....	474,796,881

\* Including goats.

The Argentine authorities give the number of sheep in that country as 120,000,000, but these figures appear considerably over the mark, and it is probable that the total does not exceed 75,000,000. In support of this lower figure it may be stated that the total imports of River Plate wool into Europe and North America during 1903 amounted to only 558,000 bales as compared with 1,451,000 bales from Australasia, while the British Consular Reports give the export of wool from Argentine ports during 1903 at 471,954 bales. Taking into consideration the fact that the local consumption of wool is small, it would appear that the lower figure referred to above is a sufficiently liberal estimate.

#### CATTLE.

Except in Queensland, cattle-breeding in the Australasian States is secondary to that of sheep. Indeed, in New South Wales in 1903 the number of the herds was even less than in 1861, the decrease amounting to 391,345. The lowest point was reached by that state in 1885, when the herds only numbered 1,317,315, the result partly of continuous bad seasons, but principally of the more profitable character of sheep-farming, which had induced graziers on many runs to substitute sheep for cattle. From that period up till 1894, when the herds numbered 2,465,411, there was a gradual improvement, which seemed to indicate a disposition on the part of pastoralists in some parts of the state to devote more attention to cattle-breeding. The serious droughts which have been experienced, however, have militated against the expansion of the cattle industry, and the numbers again fell away until the year 1899, but increased slightly during the next two years, when the adversity of the season was responsible for a shrinkage of over 300,000. The progress of Victoria in

the breeding of cattle was steady until 1894, but since that year the numbers have decreased. In Queensland the number reached 7,012,997 in 1894, but owing to the combined effects of drought and tick fever, the herds have since diminished greatly, and in 1903 there were but 2,481,717. New Zealand, after having neglected the cattle industry for a long time, has during recent years largely increased its herds, the increase being the result of the special attention bestowed upon the dairy industry.

The following table shows the number of cattle in each state at ten-year intervals since 1861 :—

State.	Number of Cattle.					
	1861.	1871.	1881.	1891.	1901.	1903.
New South Wales .....	2,271,923	2,014,888	2,597,348	2,046,347	2,047,454	1,880,578
Victoria .....	628,062	799,609	1,286,677	1,812,104	1,602,884	*1,522,265
Queensland .....	580,196	1,168,236	3,618,513	6,192,769	3,772,707	2,481,717
South Australia .....	265,494	143,463	314,918	676,933	479,868	536,580
Western Australia .....	33,796	49,693	63,009	133,690	394,530	497,617
Tasmania .....	87,114	101,640	130,526	167,666	163,661	186,968
Commonwealth .....	3,846,554	4,277,228	8,010,991	11,029,499	8,466,649	7,104,695
New Zealand .....	193,286	436,692	698,687	831,831	1,561,784	1,593,547
Australasia .....	4,039,839	4,713,920	8,709,678	11,861,330	9,827,433	8,698,242

\*Estimated.

The statement below shows the proportion of cattle in each state to the total herds in Australasia, at the end of 1903 :—

State.	Per cent.
New South Wales .....	21·6
Victoria .....	17·5
Queensland .....	28·5
South Australia .....	6·2
Western Australia .....	5·7
Tasmania .....	2·1
New Zealand .....	18·4
Australasia .....	100·0

In spite of vast losses in recent years, Queensland has still the largest number of cattle, but the extent of its losses will be realised when it is remembered that out of a total of 11,049,065 in 1899, nearly 46 per cent. were in Queensland, while in 1903, out of a total of 8,698,242 only 28·5 per cent. were in that state.

It is interesting to note, however, that the northern territory of Queensland suffered less severely from the drought than most other portions of Australia, and large numbers of cattle were despatched from the Gulf Country to the southern states. During the latter half of 1903, the numbers travelling on the stock routes to the south had never been exceeded, while during the first six months of 1904, some 80,000 head (valued at nearly £500,000) were sent from the district. The value of live cattle exported from Queensland in 1903 was £642,000.

A clearer idea of the changes which late years have brought about in the cattle industry is afforded by the next table, showing the number in the various states at the close of each year since 1885. As will be seen, returns were not collected in three of the states—Victoria, South Australia, and New Zealand—for several of the years under review :—

Year.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	New Zealand.
1885	1,317,315	1,290,790	4,102,663	*	70,408	133,642	853,353
1886	1,367,844	1,303,265	4,071,563	*	88,254	143,665	*
1887	1,575,437	1,333,373	4,473,716	*	93,544	147,092	*
1888	1,622,907	1,370,660	4,654,932	*	95,322	142,019	853,353
1889	1,741,592	1,394,309	4,372,416	531,296	119,571	150,004	896,461
1890	2,091,229	1,732,881	5,558,264	574,082	130,970	162,440	831,831
1891	2,128,838	1,812,104	6,192,759	676,933	133,690	167,788	*
1892	2,221,459	1,824,704	6,591,416	631,522	162,836	170,085	831,801
1893	2,269,852	1,817,291	6,606,200	675,234	173,747	169,141	886,265
1894	2,465,411	1,833,900	7,012,997	*	187,214	177,033	964,034
1895	2,150,057	*	6,822,401	*	200,091	162,801	1,047,991
1896	2,226,163	*	6,507,377	638,591	199,793	157,736	1,133,572
1897	2,065,096	*	6,069,013	540,149	244,971	157,486	1,202,165
1898	2,029,516	*	5,571,292	613,894	269,947	149,754	1,203,024
1899	1,967,081	*	5,053,836	526,524	297,081	160,204	1,210,439
1900	1,933,116	*	4,078,191	472,423	333,665	165,516	1,256,680
1901	2,047,454	1,602,384	3,773,707	479,863	394,580	168,661	1,361,734
1902	1,741,226	*	2,543,471	519,163	437,558	173,365	1,460,083
1903	1,880,578	1,522,265	2,481,717	530,580	497,617	135,938	1,593,547

\* Returns not collected.

The number of cattle (including calves) slaughtered during each of the seven years ended 1903 is shown in the following table for all the states except South Australia and New Zealand, which do not furnish returns. The Tasmanian figures represent the numbers killed in Hobart and Launceston only :—

Year.	New South Wales.	Victoria.	Queensland.	Western Australia.	Tasmania (Hobart and Launceston).
1896 .....	351,246	245,477	474,946	30,664	9,393
1897 .....	365,898	240,958	498,533	41,665	10,615
1898 .....	364,042	244,319	572,735	33,203	10,029
1899 .....	383,948	249,177	640,898	38,577	10,276
1900 .....	399,992	248,797	503,223	40,950	9,114
1901 .....	335,323	251,477	377,433	39,424	8,365
1902 .....	288,131	233,206	366,977	43,914	9,793
1903 .....	275,199	235,284	274,666	40,501	9,842

The value of the cattle in Australasia, on the basis of the average prices ruling in 1903, was £53,533,000, thus divided amongst the various states :—

	£
New South Wales .....	11,924,000
Victoria .....	10,275,000
Queensland .....	11,168,000
South Australia.....	3,380,000
Western Australia .....	3,807,000
Tasmania .....	1,506,000
Commonwealth.....	42,060,000
New Zealand.....	11,473,000
Australasia .....	£53,533,000

### HORSES.

Australasia is eminently fitted for the breeding of most descriptions of horses, and attention has long been directed to this industry. At an early period the stock of colonial-bred horses was enriched by the importation of some excellent thoroughbred Arabians from India, and to this cause the high name which was acquired by the horses of Australia was largely due. The abundance of good pasture everywhere obtainable also contributed to this result. The native kangaroo-grass, especially when in seed, is full of saccharine matter, and young stock thrive excellently upon it. This plenitude of natural provender permitted a large increase in the stock of the settlers, which would have been of great advantage had it not been that the general cheapness of the animals led to a neglect of the canons of breeding. In consequence of the discovery of gold, horses became very high priced. Under ordinary conditions this circumstance would have been favourable to breeding, and such was actually the case in Victoria. In New South Wales, however, it was far otherwise. The best of its stock, including a large proportion of the most valuable breeding mares, was taken by Victoria, with the result that for twenty years after the gold rush the horses of the mother state greatly deteriorated. One class of stock alone escaped—the thoroughbred racer, which was probably improved both by the importation of fresh stock from England, and by the judicious selection of mares.

The states are specially adapted to the breeding of saddle and light-harness horses, and it is doubtful whether these particular breeds of Australasian horses are anywhere surpassed. The bush horse is hardy and swift, and capable of making very long and rapid journeys when fed only on the ordinary herbage of the country; and in times of drought, when the grass and water have become scanty, these animals often perform astonishing feats of endurance. Generally speaking, the breed is improving, owing to the introduction of superior stud horses and the breeding from good mares. Where there has been a deterioration in the

stock, it has been due to breeding from weedy mares for racing purposes and to the effects of drought.

The following table shows the number of horses in each state at ten-year intervals since 1861. In 1903, New South Wales possessed the largest number of horses, followed by Queensland and Victoria :—

State.	Number of Horses.					
	1861.	1871.	1881.	1891.	1901.	1902.
New South Wales ....	233,220	304,100	398,577	459,755	496,716	458,014
Victoria .....	84,057	181,643	278,195	440,696	392,237	*376,548
Queensland .....	28,983	91,910	194,217	399,364	462,119	401,984
South Australia .....	52,597	78,125	159,678	202,906	178,199	192,411
Western Australia ..	10,720	22,698	31,755	40,812	73,830	82,747
Tasmania .....	22,118	23,054	25,607	31,262	32,399	35,541
Commonwealth...	431,695	701,530	1,088,029	1,574,795	1,625,500	1,547,245
New Zealand.....	28,275	81,028	161,736	211,040	279,672	298,714
Australasia .....	459,970	782,558	1,249,765	1,785,835	1,905,172	1,845,959

\* Estimated.

There is at present a considerable demand in India for Australian horses, especially for those of a superior class, and although the speculation of shipping horses to that country is attended with some risk, owing to the dangers of the voyage, there is reason to believe that in the near future the trade will assume considerable dimensions, as Australia is the natural market from which supplies may be derived. The number and value of the horses exported to India during 1903 from each state and New Zealand was as follows :—

State.	Number.	Value.
New South Wales .....	1,249	£21,309
Victoria .....	1,274	22,843
Queensland .....	3,120	32,259
South Australia .....	251	4,840
New Zealand.....	150	2,325
Australasia .....	6,044	£83,576

The export from Australasia to India in 1901 consisted of 5,672 horses, valued at £80,313, and in 1902 of 5,785, valued at £80,972.

The war in South Africa created a demand for Australian horses as army remounts, and in 1901 no less than 24,995 horses, valued at £320,152, were exported from Australasia to South African ports. In 1902 there was naturally a considerable falling off, the horses exported only numbering 11,491, valued at £159,040, while in 1903 only 739 horses were sent, valued at £18,001, of which New South Wales furnished 145, valued at £7,775, and Victoria 572, valued at £9,165.

The number exported to South Africa from each state during 1901 and 1902 was as follows :—

State.	1901.		1902.	
	Number.	Value.	Number.	Value.
		£		£
New South Wales ...	6,300	81,204	2,918	38,116
Victoria .....	6,857	129,642	2,977	56,747
Queensland .....	11,069	96,841	4,105	36,178
South Australia .....	15	355	455	5,821
Western Australia ...	472	7,080	5	265
Tasmania .....	280	5,000	.....	.....
Commonwealth...	24,993	320,122	10,460	137,127
New Zealand.....	2	30	1,031	21,913
Australasia .....	24,995	320,152	11,491	159,040

The following table shows the proportion of horses in each state to the total number in Australasia, at the end of 1903 :—

State.	Per cent.
New South Wales.....	25·2
Victoria .....	20·4
Queensland.....	21·7
South Australia.....	10·3
Western Australia .....	4·4
Tasmania .....	1·9
New Zealand .....	16·1
Australasia.....	100·0

The value of horses in 1903, in the various states, is estimated as follows :—

New South Wales .....	£4,506,000
Victoria ...	4,067,000
Queensland .....	3,125,000
South Australia .....	1,828,000
Western Australia .....	951,000
Tasmania .....	384,000
Commonwealth .....	£14,871,000
New Zealand .....	3,764,000
Australasia .....	£18,635,000

#### ANGORA GOATS.

The breeding of the Angora goat, with a view to the production of mohair, has recently attracted attention in Queensland and New South Wales, and considerable numbers of pure-bred animals have been

imported from the United States. It is found that the Angora thrives admirably in the warm dry climate existing in a great portion of the states mentioned, and, with the steady demand for mohair, it is confidently expected that the export of the product will in time form an important element in the trade of the Commonwealth.

The number of goats depastured in 1903 in those states from which returns were received was as follows :—New South Wales, 27,062 ; South Australia, 11,650 ; and Western Australia, 14,120.

#### CAMELS.

Camels are employed in some of the states in the carriage of wool and other produce. The latest returns show that 835 are used in the Western Division of New South Wales. In Western Australia there are 2,031.

#### STOCK-CARRYING CAPACITY OF AUSTRALASIA.

None of the states is stocked to its full capacity ; indeed, in the large territory of Western Australia and in the Northern Territory of South Australia the process has only begun. A clear idea of the comparative extent to which each state is stocked cannot be given unless the different kinds of animals are reduced to a common value. Assuming, therefore, that one head of large stock is equivalent to ten sheep, and expressing cattle and horses in terms of sheep, it will be found that the number of acres to a sheep in each state is as follows :—

State.	No. of acres per sheep.
New South Wales.....	3·8
Victoria .....	2·3
Queensland.....	11·5
South Australia.....	45·4
Western Australia .....	74·3
Tasmania .....	4·4
New Zealand .....	1·8
Australasia.....	11·0

The most closely-stocked of the Commonwealth states is Victoria, with 2·3 acres per sheep, but this is by no means the limit to the carrying-capacity of that state ; on the contrary, there is still a considerable tract to be brought under the sway of the pastoralist. New Zealand is stocked to a slightly heavier extent, but neither that colony nor New South Wales, which averages 3·8 acres per sheep, can be said to have reached its full carrying-capacity. If the 1901 average of New South Wales, viz., 3 acres to a sheep, be taken as the possible limit to which Australasia may be stocked, there is room in these states for nearly 450,000,000 sheep, or 45,000,000 cattle more than were then depastured. That Australasia could carry 1 sheep to 3 acres, however, is an improbable supposition ; in almost every state the best land is under occupation,



and the demands of the farmer must diminish the area at present at the disposal of the grazier. This will more especially prove true of Victoria, New Zealand, and Tasmania. On the other hand, by resisting the temptation to overstock inferior country, and by increasing the natural carrying-capacity by water conservation and irrigation and by the artificial cultivation of grasses, the states in which agriculture has made most progress will be able to carry stock in even larger numbers than they have hitherto attempted. Taking all circumstances into consideration, it may be fairly estimated that under the present system the states are capable of maintaining, in ordinary seasons, stock equivalent to 390,000,000 sheep—that is, about 180,000,000 sheep, or their equivalent in cattle, more than depastured in 1901.

The evil effects of the adverse seasons experienced in the Commonwealth during recent years have caused renewed attention to be devoted to the questions of water conservation and irrigation. Movements are on foot at the present time in New South Wales for the utilisation of the natural reservoirs such as that at the head of the Murrumbidgee and other suitable places where, at a comparatively small cost, supplies of water could be conserved to feed the rivers in time of drought. It is not alone the actual loss of stock that makes a drought so disastrous, but the fact that, even with the return of good seasons, a considerable period elapses before the country regains its full carrying-capacity. That much can be done in the direction of providing fodder during the dry season was shown in isolated instances during 1902. At Forbes, in New South Wales, 22 acres of irrigated lucerne maintained nearly 1,600 sheep in good condition for a period of four months prior to the breaking up of the drought. At Rodney in Victoria, the farmers who utilised the waters of the Goulburn for irrigation purposes were able to send fat stock to the Melbourne and Bendigo markets, in addition to supplying the squatters of Riverina with lucerne and other fodder for their starving stock. With proper provision for water conservation, it may be safely said that the Commonwealth was not overstocked in 1896, when there were over 90,000,000 sheep and 11,000,000 head of cattle, whereas in 1903 there were but 55,371,000 sheep and 7,105,000 cattle.

It is a difficult task satisfactorily to estimate the losses occasioned by adverse seasons, but a careful computation shows that during the last six years the Commonwealth has carried on an average about 24,000,000 sheep and 2,400,000 head of cattle less than in 1896. It is to be hoped that the lesson of 1902 has been taken to heart in those parts of the continent liable to drought conditions, and that no similar disaster will ever occur again.

The wonderful recuperative powers of the states were amply evidenced in 1903 and 1904 by the bountiful harvest and prolific growth of herbage over the major portion of the districts which were most keenly affected by the adversity of the season in the year before. The lambing returns have been excellent, while the weight and quality of the fleeces

have surpassed expectations. During 1903 Australia again resumed its position as the foremost pastoral country of the world.

The expenditure on water conservation of a moiety of the sum represented by the losses of the season of 1901-2 would go far towards solving the problem of how to utilise to their best advantage the fertile but comparatively rainless districts of the interior. Outside of a system of water conservation the only other alternative appears to be the construction of light lines of railway in the pastoral districts to enable the stock to be moved quickly from place to place in periods of drought, although these would not be of much avail in some seasons.

The number of stock in Australasia, expressed in terms of sheep, the number of acres per sheep, and the number of sheep per head of population, at various dates since 1861, were as given below :—

Year.	Sheep.	Cattle, in terms of Sheep.	Horses, in terms of Sheep.	Total.	Acres per Sheep.	Sheep per head of Population.
1861	23,741,706	40,398,390	4,599,700	68,739,796	28·7	54
1871	49,773,584	47,138,200	7,825,580	104,737,364	18·8	53
1881	78,063,426	87,096,280	12,497,650	177,657,356	11·1	63
1891	124,547,937	118,613,300	17,858,350	261,019,587	7·5	67
1901	92,358,824	98,274,330	19,051,720	209,684,874	9·4	46
1903	73,652,026	86,982,420	18,459,590	179,094,036	11·0	38

#### VALUE OF PASTORAL PROPERTY AND PRODUCTION.

The total value of pastoral property in Australasia—that is, of improvements, plant, and stock—was estimated a few years ago at £242,000,000. This estimate does not include land, but merely the stock, other than swine, depastured, and the improvements effected in the grazing area. It is difficult if not impossible to assign an exact value to the lands devoted to pastoral purposes, for though much purchased land is used for depasturing stock, the larger area comprises lands leased from the state, so that a statement which omitted to take into account the value of the state lands would be misleading.

The annual return from pastoral pursuits in 1903 was £33,196,930, the share of each state in the total production being as follows :—

New South Wales .....	£12,776,780
Victoria .....	4,409,674
Queensland .....	4,439,444
South Australia .....	2,230,457
Western Australia .....	1,206,469
Tasmania .....	557,500
Commonwealth .....	25,620,324
New Zealand .....	7,576,606
<b>Australasia .....</b>	<b>£33,196,930</b>

The products of dairy cattle and swine are not included in the foregoing statement, the figures being given in another place. It should be understood that the values quoted are those at the place of production. The value of the return from each class of stock may be approximately reckoned as follows :—

Sheep.....	£24,157,257
Cattle .....	6,049,049
Horses .....	2,990,624
Total .....	£33,196,930

### WOOL.

As might be supposed, the greater part of the value of production from sheep is due to wool. Thus, out of the £24,157,257 shown above, £17,961,055 is the value of wool, viz :—£17,686,055 for wool exported, and £275,000 for wool used locally. The value of the wool exported, according to the Customs returns, was £18,093,155—that is to say, £407,100 more than the figures shown above. The excess represents the charges for freight, handling, etc., between the sheep-walks and the port of shipment.

The price of wool, which in 1899 was much higher than for many years previously, declined almost as suddenly as it had advanced, and as the production for 1901 did not show much increase, except in New Zealand, the total value compared unfavourably with preceding years, and fell short of that of 1899 by £6,165,000. In 1903 wool again rose considerably in value, and though the production was some 100,000,000 lb. less than in 1901, owing to the increased price the receipts only fell in value to the extent of 5 per cent.

The following figures show the chief sources of origin of the wool imported into Europe and North America during the period 1900-03.

Year.	Total Sales.	Australasian.	Cape.	Argentine.
	bales.	per cent.	per cent.	per cent.
1900	2,064,000	70·55	6·78	22·67
1901	2,494,000	69·97	8·70	21·33
1902	2,445,000	69·49	9·57	20·84
1903	2,243,000	64·69	10·43	24·88

Nearly all the wool produced in Australasia is exported, the home consumption being small, amounting to only 2·6 lb. greasy, per head of population; while in Europe and America the quantity of wool available for consumption by the industry amounts to about 5 lb. per head. During the last two quinquennial periods the consumption of wool in Europe and America has averaged as follows :—

1891-94 .....	5·12 lb. per head of population
1895-99 .....	5·19 lb.     "     "

The quantity, in the grease, of wool produced by each state at decennial periods since 1871 was as follows :—

State.	1871.	1881.	1891.	1901.	1908.
	lb.	lb.	lb.	lb.	lb.
New South Wales...	74,401,390	161,022,900	321,416,000	301,942,000	227,004,320
Victoria .....	63,641,100	67,794,300	69,205,800	74,879,300	54,608,582
Queensland .....	36,553,200	34,275,300	83,118,100	70,141,800	62,983,899
South Australia...	28,242,100	46,013,900	50,151,500	39,951,700	46,066,517
Western Australia..	1,883,000	4,654,600	9,501,700	14,049,000	13,306,106
Tasmania .....	6,687,800	10,525,100	10,102,900	8,939,000	5,916,897
Commonwealth	211,413,500	324,286,100	543,495,800	509,902,800	399,886,321
New Zealand .....	46,192,300	69,055,600	117,733,500	164,011,500	177,575,197
Australasia .....	257,605,800	393,341,700	661,229,300	673,914,300	577,461,518

The great fall in production is seen from the above table, which shows that the only states where an increase has taken place since 1891 are Western Australia and New Zealand, all the others showing a large decline. The increase in New Zealand has taken place in spite of the heavy demands upon the resources of the colony for the supply of sheep to meet the requirements of the London market in frozen mutton.

The weight of wool per sheep has been increasing regularly in each of the states, as will be seen from the following table, which shows the weight of clip per sheep at each decennial interval since 1861. It is manifest that the Victorian figures are unreliable, because there is no reason to suppose that there was a decline in the weight of the fleece in 1891; on the contrary, it is known to have been steadily improving. The Western Australian and Tasmanian results also show irregularities, and are omitted from the table. The figures for New South Wales and Queensland best represent the increase in the weight of the fleece on the mainland, and the New Zealand returns are also believed to be correct. In South Australia the weight of wool per sheep has been consistently higher than in the other states, but the results are derived from the official statistics, and it would appear that the number of sheep in that state has been under-estimated.

State.	1861.	1871.	1881.	1891.	1901.
	lb.	lb.	lb.	lb.	lb.
New South Wales.....	3.28	4.57	4.47	5.74	7.2
Victoria .....	4.52	6.17	6.87	5.68	6.9
Queensland .....	3.40	4.73	4.50	4.73	7.1
South Australia.....	4.69	6.41	6.93	6.85	7.9
New Zealand .....	3.48	4.76	5.32	6.42	8.1

The values of the excess of exports over imports in each state for the period 1871-1903 were as follows. A careful examination of the figures proves rather conclusively that less care than might have been expected has been taken in stating the values, except in New South Wales and New Zealand, but they are obtained from the official records, and are given for what they are worth :—

State.	Excess of Exports over Imports.				
	1871.	1881.	1891.	1901.	1903.
	£	£	£	£	£
New South Wales ...	4,705,820	7,173,166	10,927,487	9,050,884	8,522,999
Victoria .....	4,483,461	2,562,769	3,792,938	2,510,219	1,804,407
Queensland .....	1,158,833	1,331,869	3,453,548	2,130,778	1,867,652
South Australia .....	1,113,825	1,573,313	1,540,079	1,021,283	1,239,744
Western Australia ...	122,637	256,690	329,365	378,135	443,743
Tasmania .....	293,160	498,400	418,460	279,022	173,222
Commonwealth ...	11,882,736	13,396,207	20,461,877	15,370,321	14,051,767
New Zealand .....	1,606,144	2,914,046	4,129,686	3,669,642	4,041,388
Australasia .....	13,488,880	16,310,253	24,591,563	19,039,963	18,093,155

Western Australia was the only state to show an increase in the value during the year over that obtained in 1891.

The Customs figures are not necessarily a reliable guide as to the value of the wool clip in any particular year, since the returns show the exports up to the 31st December only, whereas the wool year does not close until six months later. Consequently, if the clip be late, as was the case last season, a large proportion of the quantity exported appears in the Customs returns for the following year. The figures for 1903 are therefore considerably less than they would have been under ordinary conditions.

According to the London returns, the imports of Australasian wool into Europe and America during the 1903 wool season comprised 1,451,000 bales, which at an average of £13 10s. per bale represents a total value of £19,588,500. For the previous season the imports were 1,699,000 bales, averaging £11 16s. 7d., equivalent to a total value of £20,097,754, so that notwithstanding the smaller import in 1903 the returns for that year were only £500,000 below those of the previous season.

Wool realised a high price in Australia at the sales closing in June, 1904, the average per bale being £12 7s. 3d., as against £11 18s. 4d. for the preceding year. In a comparison between London and Australian

prices it may be taken that freight and other charges add from 15s. to £1 per bale to the Australian rates, while the former returns include also New Zealand wool, which is not so valuable as that grown in Australia. The shipments of wool from Australasia during the twelve months ending June, 1904, show a decrease of 73,780 bales on the totals for the preceding year. The quantity shipped by the Commonwealth fell off by 19,972 bales, and the exports from New Zealand by 53,808 bales. There was a slight expansion in the Queensland, South Australian, and Western Australian trade. From present indications the current season will be a phenomenal one so far as concerns the yield of wool per sheep. The pastures throughout almost the whole of the Commonwealth are in good condition, the lambing has been excellent, and the growth of wool heavy but sound, and the staple well-developed. It seems not unlikely that on many large runs the flocks will yield an average of from 9 to 10 lb. of wool per head, which at present prices is equivalent to a return of about 7s. per head of sheep shorn. It is probable that the growth of wool has never been exceeded, and indications are so favourable that the net return of wool will very considerably exceed the returns for last year, while the quality of the product is excellent. The continental demand for last season's clip was very keen, and of the 720,421 bales sold in Australian markets no less than 63 per cent. was taken by continental buyers, while 24 per cent. was secured by Great Britain, 4 per cent. by America, and the remaining 9 per cent. by local manufacturers and Japanese and Eastern buyers. Of the 1,685,000 bales of Australasian and South African wool consumed in England, the Continent, and America during 1903, the respective proportions taken by each were 38·5 per cent., 58 per cent., and 3·5 per cent., as compared with 42·5 per cent., 54 per cent., and 3·5 per cent. in 1902.

The price per lb. obtained for wool in grease in London at the end of each year from 1890 was as follows :—

Year.	New South Wales. (Average Merino.)	Victoria. (Good Average Merino.)	New Zealand. (Average Cross-bred.)
	d.	d.	d.
1890 .....	8½	10	10
1891 .....	7½	9	9½
1892 .....	7	8½	9½
1893 .....	7	8½	9½
1894 .....	6	7½	8½
1895 .....	7½	9½	9½
1896 .....	7	9	8½
1897 .....	7½	9	8½
1898 .....	7½	9½	7
1899 .....	13	15½	10½
1900 .....	7	9	7½
1901 .....	7½	10	5½
1902 .....	10	13	7½
1903 .....	9½	12	9

Taking the last sixteen years, the highest prices were realised for New South Wales and Victorian wools during 1899, namely, 13d. per lb. and 15½d. per lb. respectively. The maximum price for New Zealand wool, 11½d. per lb., was obtained in 1889. The lowest prices—6d. for New South Wales, and 7½d. for Victoria—were experienced in 1895, while owing to the heavy fall in the value of cross-breeds, New Zealand wool realised as little as 4½d. per lb. during 1901. The average prices realised during the whole period were 9½d. per lb. for New South Wales average merino, 11½d. for good average Victorian merino, and 8½d. for average New Zealand cross-bred medium. From these figures it will be seen that Victorian wool averages about 2d. per lb. higher than New South Wales wool. The figures must be taken with some qualification. Much of the New South Wales wool, the product of the Riverina districts, is exported *via* Melbourne and sold as Port Phillip wool, and brings a price considerably in excess of the average given in the table for the state of which it is the produce. The quantity of wool sold at the local sales in the Australasian States is increasing. Particulars of these sales will be found in the chapter on "Commerce."

#### THE FROZEN-MEAT TRADE.

In view of the large increase in the live stock of Australasia during favourable seasons, the question of the disposal of the surplus east has become a matter of serious consequence. In New South Wales especially, and in the Riverina district in particular, it was found necessary to have recourse to the old method of boiling down, which a fortunate rise in the price of tallow made it possible to carry on with a margin of profit. The price of tallow during the last few years has, however, been low, and offered little inducement to pastoralists, while the loss of stock will prevent the trade being of much importance to Australia for some considerable time.

In New Zealand a much better solution of the question of disposal of the surplus cast was found, and a trade in frozen mutton with the United Kingdom has been established on a thoroughly payable basis—an example which some of the other states are endeavouring to follow, although considerably handicapped by the want of cross-bred sheep and the prejudice of the English consumer against merino mutton.

The first successful attempt at shipping frozen mutton to England was made by New Zealand in 1882, and since then the trade has attained great proportions, to the immediate benefit of the colonial producer as well as the English consumer. In 1882 the exports amounted to 1,700,000 lb., at that time regarded as a considerable quantity, but in 1903 the total was no less than 228,000,000 lb., and there is every prospect of a further increase in 1904. The value of the trade in frozen and preserved meat has risen from £1,281,000 in 1895 to £3,209,000 in 1903, or by £1,928,000. The bulk of the trade was carried on with

Great Britain, the exports thereto in 1903 being valued at £2,902,000, an increase of over £440,000 on the exports of the previous year. A market is also being opened up in South Africa, to which New Zealand consigned frozen and preserved meat to the value of £216,000 in 1903, being an increase of £76,000 on the figures for 1902. The trade initiated by the New Zealand Land Company has been extended by the formation of numerous joint stock companies, which now own twenty-one meat-freezing works in the two islands, having an aggregate capacity for freezing about 4,000,000 sheep per year. The sheep are generally killed in the country, and transported by rail to the freezing works. Several fleets of steamers are engaged in the trade, and the freight rates charged enable the companies to realise satisfactory profits. The growth of the frozen and preserved meat industries of New Zealand since 1881 is shown in the following table. The shipments are almost exclusively made to the United Kingdom:—

Year.	Frozen or Chilled Meat.						Preserved Meat.	
	Beef.	Mutton.	Lamb.	Mutton and Lamb.	Total Weight.	Total Value.	Weight.	Value.
	cwt.	carcases.	carcases.	cwt.	cwt.	£	lb.	£
1881	.....	.....	.....	.....	.....	.....	1,074,840	22,391
1882	.....	.....	.....	.....	15,244	19,339	2,913,904	54,397
1883	987	.....	.....	86,996	87,982	118,261	3,668,480	72,778
1884	1,644	.....	.....	252,422	254,066	345,081	3,103,744	59,224
1885	9,170	.....	.....	236,961	236,131	373,326	4,047,904	81,401
1886	9,391	.....	.....	386,406	345,796	428,566	2,592,464	47,436
1887	6,630	656,823	110,816	421,406	428,085	454,942	4,706,016	79,246
1888	44,613	886,843	94,681	507,306	551,919	629,110	4,912,544	86,128
1889	68,298	990,486	118,794	588,524	656,822	783,374	5,325,152	106,772
1890	98,234	1,330,176	279,741	798,625	896,869	1,084,992	6,702,752	136,182
1891	103,007	1,447,583	838,344	899,012	992,019	1,185,122	5,447,904	111,128
1892	55,020	1,316,758	290,966	806,304	861,324	1,021,838	3,939,712	69,430
1893	11,059	1,355,247	475,366	888,455	899,514	1,078,427	2,656,416	46,601
1894	912	1,633,213	459,948	1,001,342	1,002,254	1,162,770	3,368,736	57,326
1895	12,090	1,632,580	735,254	1,078,640	1,090,730	1,214,774	4,124,400	66,157
1896	25,905	1,506,969	792,037	1,065,292	1,091,197	1,239,969	5,006,848	78,661
1897	50,044	1,653,170	1,038,316	1,291,582	1,341,626	1,512,286	5,046,216	78,235
1898	95,218	1,719,282	1,168,868	1,338,175	1,433,393	1,568,543	6,246,792	97,197
1899	172,346	2,102,633	1,272,525	1,657,439	1,729,784	1,966,564	5,882,272	90,919
1900	312,291	1,585,238	1,351,145	1,354,730	1,667,021	1,962,610	4,973,024	94,624
1901	221,211	1,906,671	1,513,017	1,499,124	1,720,326	2,116,860	3,946,896	87,688
1902	286,699	2,068,622	1,852,050	1,708,738	1,996,437	2,561,327	6,087,096	124,633
1903	206,205	2,602,612	2,212,905	2,039,500	2,244,706	3,060,933	4,434,304	96,362

Amongst the states of the Commonwealth the export of meat has reached the largest dimensions in Queensland, although of course it consists chiefly of beef, the trade in mutton being proportionately very small. Of the total exports of frozen and preserved meat, amounting to £950,486 in 1903, South Africa took £589,855 worth, or more than one half, while of the remainder, £167,480 worth went to the United Kingdom. Four years previously Queensland exported over £750,000 worth of frozen beef to England. Existing contracts with South Africa and Manilla will keep the meat works in operation for some considerable time, and with the return of good seasons it is hoped



that much of the British trade will be recovered. So far as they can be given, the figures showing the growth of the Queensland frozen-meat trade, as well as the exports of preserved meat, will be found below:—

Year.	Frozen or Chilled Meat.				Preserved Meat.	
	Beef.	Mutton.	Total Weight.	Total Value.	Weight.	Value.
	cwt.	cwt.	cwt.	£	lb.	£
1881	.....	.....	.....	.....	2,276,409	39,956
1882	.....	.....	.....	.....	5,689,189	119,343
1883	.....	.....	1,951	2,151	6,729,721	151,001
1884	.....	.....	8,082	11,240	2,298,696	57,101
1885	.....	.....	3,926	5,003	8,306,432	171,432
1886	.....	.....	9,289	12,103	130,658	1,586
1887	.....	.....	.....	.....	5,272,170	99,653
1888	.....	.....	.....	.....	3,964,419	77,887
1889	8,745	15,542	24,287	62,240	853,621	16,743
1890	30,253	23,799	54,052	75,908	2,769,881	44,040
1891	52,609	53,698	106,307	161,345	3,333,317	59,032
1892	123,196	51,595	174,791	276,113	6,035,035	96,828
1893	204,349	21,898	226,247	377,039	8,001,788	143,146
1894	301,837	32,187	334,024	498,652	15,544,826	250,646
1895	461,733	28,221	489,954	580,489	25,941,400	393,492
1896	434,683	31,874	466,557	501,498	21,583,658	330,728
1897	529,162	31,162	560,324	659,260	15,699,098	241,189
1898	511,629	10,935	522,564	672,970	13,188,836	217,684
1899	651,029	32,529	683,558	833,733	25,148,815	383,899
1900	689,423	16,239	705,662	976,878	25,250,226	427,062
1901	675,221	19,208	694,429	1,016,038	13,310,615	221,709
1902	770,423	39,841	810,267	1,207,345	12,838,507	257,858
1903	534,045	20,687	554,732	829,671	4,331,703	96,495

Next to New Zealand, the largest exporter of frozen mutton is New South Wales. During the last few years greater efforts have been made in this State to expand the trade, and the exports show a considerable increase, although a temporary check was experienced during the last five years in consequence of the unfavourable seasons. But New South Wales has laboured under the disadvantage of possessing few cross-bred sheep for export, and the food qualities of the merino are scarcely appreciated in the English market, where New Zealand mutton is favourably known, and brings on an average 1½d. per lb. more than Australian. A great expanse of New South Wales, however,

is suited to the breeding of large-carcase sheep, and the pastoralists have become alive to the importance of securing a share of the meat trade of the United Kingdom. Attention is being directed to the introduction of British rams, and a large increase in the cross-bred flocks has already taken place. The following table shows the growth of the frozen-meat trade of New South Wales; the exports of preserved meat consist almost wholly of tinned mutton :—

Year.	Frozen or Chilled Meat.				Preserved Meat.	
	Beef.	Mutton.	Total Weight.	Total Value.	Weight.	Value.
	quarters.	carcases.	cwt.	£	lb.	£
1881	.....	.....	9,980	8,554	.....	*176,721
1882	.....	.....	13,782	22,910	.....	*143,601
1883	.....	.....	34,911	43,100	.....	*221,912
1884	.....	.....	13,309	12,321	.....	*161,477
1885	.....	.....	6,271	6,064	.....	*166,561
1886	.....	.....	4,852	4,671	.....	*77,756
1887	.....	.....	21,831	19,310	9,761,154	150,714
1888	.....	.....	52,262	44,537	4,528,269	69,481
* 1889	.....	.....	37,868	33,426	2,877,303	52,321
1890	.....	.....	72,304	71,534	4,655,523	74,329
1891	.....	.....	105,013	101,828	6,581,713	87,632
1892	.....	.....	223,074	169,425	8,620,747	105,922
1893	4,773	364,958	220,584	141,640	13,092,942	164,592
1894	9,538	533,995	339,404	193,760	16,382,597	206,054
1895	88,719	1,021,006	607,818	380,107	22,384,285	302,828
1896	16,286	1,372,373	642,188	343,397	16,351,936	218,292
1897	28,529	1,065,990	503,925	275,118	10,903,611	147,165
1898	39,593	1,095,568	539,495	330,325	13,930,801	227,288
1899	32,855	956,222	459,553	331,904	11,453,332	185,804
1900	86,948	951,891	540,426	541,395	11,966,326	221,604
1901	72,662	963,614	510,148	578,923	12,398,011	260,455
1902	12,130	510,466	221,126	263,170	10,884,786	242,915
1903	6,988	334,533	143,892	199,675	4,709,976	97,063

\* Including Extract of Meat.

With the probable rapid increase in the cattle and sheep flocks of the state, the question as to the disposal of the surplus is again becoming of interest.

The total capacity per annum of the boiling-down works in New South Wales is stated at 751,200 head of cattle or 17,700,000 sheep; of chilling works, 285,000 head of cattle or 4,965,000 sheep; of freezing works, 123,000 head of cattle or 4,050,000 sheep; and of meat-preserving works, 111,000 head of cattle or 5,265,000 sheep.

The only other state in which the meat-export trade has reached dimensions of any importance is Victoria, although its exports fall far below those of the states already dealt with. A statement of the Victorian trade from 1881 to 1903 will be found below :—

Year.	Frozen or Chilled Meat.				Preserved Meat.	
	Beef.	Mutton.	Total Weight.	Total Value.	Weight.	Value.
	cwt.	cwt.	cwt.	£	lb	£
1881	.....	.....	.....	.....	4,026,072	102,306
1882	.....	.....	18,522	18,969	1,274,066	30,705
1883	.....	.....	9,944	12,220	3,225,657	76,015
1884	.....	.....	41,373	53,196	2,667,866	63,707
1885	.....	.....	39,107	61,617	1,486,849	38,244
1886	.....	.....	39,384	70,319	616,652	17,868
1887	.....	.....	15,245	27,270	629,054	14,291
1888	.....	.....	.....	.....	714,856	16,115
1889	.....	.....	.....	.....	805,580	16,156
1890	.....	.....	.....	.....	893,114	20,197
1891	.....	.....	.....	.....	1,052,887	19,230
1892	.....	.....	.....	.....	1,982,151	51,624
1893	.....	.....	1,907	1,838	777,953	14,349
1894	53	27,182	27,235	25,370	2,267,791	40,082
1895	268	24,563	24,831	31,673	2,917,730	43,408
1896	127	23,634	23,761	25,827	4,335,511	71,576
1897	62	21,416	21,478	20,248	5,498,315	84,914
1898	233	7,556	7,789	9,101	2,852,191	38,516
1899	1,458	74,960	76,418	86,087	4,760,047	50,174
1900	2,814	79,507	82,321	112,040	4,776,979	67,265
1901	3,931	85,053	88,984	131,529	3,856,381	63,284
1902	5,210	118,700	123,910	195,674	2,216,862	47,959
1903	14,125	117,427	131,552	216,371	2,976,513	51,770

There are at present depastured in Australasia 73,652,026 sheep and 8,698,242 cattle, of which 18,280,806 sheep and 1,593,547 cattle are in New Zealand. In that colony the industry of sheep and cattle raising has now reached such a stage that practically the whole of the stock available for market is used up every year either locally or for export, and as a consequence the number of sheep is declining, while that of cattle remains about stationary. In the states of the Commonwealth a different state of things prevails. In New South Wales there is usually a large surplus of sheep beyond the state's requirements; while the "cast" of cattle is below the local demand, and is supplemented

by the importation of stock from Queensland, the net import from that state for the past five years being 350,521 head. The other four states have each a deficiency of cattle and sheep.

It is estimated that in an average year the "cast" of cattle is 10-25 per cent.—that is to say, that percentage of all the cattle depastured would be of marketable age, could they be made fit for slaughtering. Assuming this as the basis of calculation it is estimated that in the Commonwealth there are, in an ordinary season, 250,000 head of cattle in excess of those required for food and independent of those preserved or frozen.

The year 1902 was a disastrous one to sheep and cattle breeders in the Commonwealth, and especially to those of Queensland and New South Wales, but owing to the copious rains which fell in 1903, the pastures are again abundant, and the lambing returns during 1904 have proved to be very satisfactory. Nevertheless it will be some time before there is any great quantity of meat available for export. This is unfortunate in view of the export trade which has been so patiently built up; but as it is now an established fact that Australian meat is greatly appreciated in England, there are strong elements of hope for future progress now that better seasons are being again experienced.

During the years 1894 and 1895 several attempts, more or less successful, were made to place live cattle and sheep in the English market. A great difficulty in the way of establishing such a trade was the wildness of the cattle, the mortality in some of the shipments being sufficiently high to provoke strong criticism in England as to the cruelty to which the stock were subjected by being shipped on such a long voyage. It is to be feared, however, that these expressions of opinion were prompted, not altogether by the alleged sufferings of the cattle, but to a large extent by the interests of the English producer and the American exporter. At the same time, it is clear that a permanent and profitable trade cannot be established until the cattle have been handled sufficiently to bring them into a tractable condition, for the present system of depasturing followed in Australia renders the stock too wild to endure a long stay on shipboard. As regards the United States, any increase in the export of live cattle from that country cannot be anticipated, in view of the large and increasing home demands.

The trade of the Argentine Republic with Great Britain in chilled and frozen beef has increased during the last four years from £200,000 to £2,053,000. The increase was partly due to the temporary stoppage of the export of live cattle owing to disease, and partly to the falling off in Australian exports, and at the present time more than one-fourth of the British imports of chilled and frozen beef comes from the Argentine.

The following statement shows the number of cattle and sheep in the United Kingdom at the end of the years 1894 and 1903; for comparative purposes the population figures are also inserted. With the growth of population and general advance in the standard of living

among the middle and lower classes, the home supplies of meat become yearly more inadequate to meet demands, and there is consequently an annual increase in the imports from abroad :—

	Population.	Cattle.	Sheep.
1891 .....	38,858,306	10,789,400	30,037,700
1903 .....	42,371,216	11,409,000	29,658,800

## DAIRY-FARMING.

Dairy-farming has of late years made fair progress in Australasia, especially in New South Wales, Victoria, New Zealand, and, more recently, in Queensland. The introduction of the factory system at convenient centres and the use of the cream-separator have done much to cause the extension of the industry. The number of dairy cows at the end of 1903, and the estimated quantity of milk produced in each state during that year, were as follow :—

State.	No. of Dairy Cows.	Quantity of Milk produced (estimated).
New South Wales .....	480,108	131,997,000 gallons
Victoria .....	516,000*	142,431,000 "
Queensland .....	119,000*	29,836,000 "
South Australia .....	83,348	23,914,000 "
Western Australia .....	27,232	5,171,000 "
Tasmania .....	45,018	10,560,000 "
Commonwealth .....	1,270,706	343,909,000 "
New Zealand .....	468,125	150,000,000 "
Australasia .....	1,738,831	493,909,000 "

\* Estimated; actual figures not available.

The estimated value of the milk and its products, butter and cheese, and of the return obtained from swine, together with the total value of dairy produce for each state in 1903, will be found below :—

State.	Value of Milk, Butter, and Cheese.	Value of Return from Swine.	Total Value of Dairy and Swine Produce.
	£	£	£
New South Wales .....	2,027,000	399,000	2,426,000
Victoria .....	2,289,000	623,000	2,912,000
Queensland .....	486,000	160,000	646,000
South Australia .....	395,000	173,000	568,000
Western Australia .....	120,000	120,000	240,000
Tasmania .....	230,000	108,000	338,000
Commonwealth .....	5,547,000	1,583,000	7,130,000
New Zealand .....	2,314,000	361,000	2,675,000
Australasia ..	7,861,000	1,944,000	9,805,000

The production of butter and cheese in each state during 1903 is estimated to have been as follows :—

State.	Butter.	Cheese.
New South Wales .....	38,727,000 lb.	4,748,000 lb.
Victoria .....	46,686,000 „	5,682,000 „
Queensland .....	7,717,000 „	1,480,000 „
South Australia .....	5,996,000 „	941,000 „
Western Australia .....	352,000 „	8,000 „
Tasmania .....	1,200,000 „	800,000 „
Commonwealth .....	100,678,000 „	13,659,000 „
New Zealand .....	45,400,000 „	14,000,000 „
Australasia .....	146,078,000 „	27,659,000 „

The states having a surplus of butter and cheese available for exportation during 1903 are shown in the following table :—

State.	Butter.	Cheese.
New South Wales .....	7,825,069 lb.	.....
Victoria .....	30,166,645 „	1,634,847 lb.
South Australia .....	883,544 „	194,184 „
New Zealand.....	31,926,272 „	8,373,110 „
Tasmania .....	.....	91,883 „
Total .....	70,601,530 „	10,294,024 „

The net imports of butter and cheese during 1903 are shown below :—

State.	Butter.	Cheese.
New South Wales .. .....	.....	811,745 lb.
Queensland.....	313,417 lb.	528,305 „
Western Australia ... ..	6,215,687 „	1,252,174 „
Tasmania .....	679,862 „	.....
Total .....	7,208,966 „	2,592,224 „

From the foregoing figures it will be seen that those states which produce a surplus of butter and cheese have, after providing for the deficiency of the other states, a balance available for exportation to outside countries, this balance in 1903 amounting to 63,392,564 lb. of butter and 7,701,800 lb. of cheese. The export of butter was more than double that of the previous year, while the export of cheese also increased considerably. An export trade in butter and cheese has

long been maintained by New Zealand, while of late years Victoria, New South Wales, and South Australia, and, more recently still, Queensland, have sent successful shipments to the London markets. In the last-mentioned state, the industry seems destined to become of prime importance; the exports of butter to Great Britain during the past season reaching a total of 40,000 cwt. Much of the coastal belt possesses rich soil with a fairly copious rainfall, while the climatic conditions are apparently favourable to the production of large quantities of milk. The industry is also making considerable progress in the Darling Downs district; the monthly payments to the suppliers at Warwick often reaching as high as £1,500. Efforts were put forward recently in the direction of having Brisbane made a port of call for the mail steamers, but up to the present these have not been crowned with success. Special concessions are made as regards harbour dues in favour of companies sending vessels to Brisbane equipped with refrigerating machinery, and one of the large lines has inaugurated a monthly service between the port and Great Britain.

The dairying industry has shown more than any other the marvellously recuperative powers possessed by the Commonwealth. As shown previously, the export of butter in 1903 was double that of the previous year despite the fact that the export season hardly opens before September, by which time the effects of the good season had not completely manifested themselves. For the 1904 season the export so far has exceeded all previous records, and bids fair to be over 100 per cent. in advance of the returns for 1903.

The rapidity with which the trade is growing may be gauged from the following table, which shows the quantity of butter exported to the United Kingdom during the fifteen years ended 1903:—

Year.	Exporting State.				
	New South Wales.	Victoria.	Queensland.	South Australia.	New Zealand.
	lb.	lb.	lb.	lb.	lb.
1889	284,251	505,478	.....	.....	2,363,088
1890	599,160	1,286,583	.....	10,850	2,976,848
1891	391,180	3,778,775	.....	23,864	3,246,768
1892	1,532,782	6,446,900	.....	.....	4,648,980
1893	2,846,989	13,141,423	1,064	357,087	5,864,656
1894	4,333,927	22,139,521	.....	1,233,539	6,590,640
1895	1,852,360	21,127,025	31,420	1,017,629	6,181,728
1896	1,741,272	16,452,649	.....	242,872	6,730,304
1897	5,431,109	15,450,857	407,199	16,240	8,943,088
1898	5,309,811	13,548,293	628,296	389,836	9,051,168
1899	7,006,701	26,045,210	741,308	894,992	13,608,224
1900	8,477,617	26,185,679	872,244	707,448	18,577,552
1901	5,965,784	17,180,468	208,740	162,456	19,141,136
1902	121,672	1,424,460	.....	.....	19,063,184
1903	7,461,575	15,908,342	951,501	453,666	27,889,792

In average years the price obtained for Australian butter in London is higher than the rates ruling in the local market; and as there can hardly be a limit placed to the capacity of Australasia to produce butter and cheese, it is probable that these higher prices will have the effect of greatly stimulating the industry throughout all these states. The value of the butter, cheese, and eggs imported into the United Kingdom during 1903 was £20,798,707, £7,054,710, and £6,617,599 respectively. The supply is chiefly drawn from the Continent of Europe and from America, and of the total amounts mentioned, the only imports from Australasia were butter to the value of £1,826,279, and cheese to the value of £168,071, the whole of the cheese, and £1,245,022 worth of butter from New Zealand being included in the Australasian figures.

In one or two of the states the export has helped to maintain prices in the local markets, and tended to restrict home consumption. Under present conditions some of the states are using largely various substitutes for butter, and by this means obtaining an exportable surplus. Improved industrial conditions may bring back the use of butter, and if a season of great prosperity visits Australia there will be a very large increase in the local demand, with a consequent limitation in the supply available for export, so that it may be concluded that in any case the prospects of the industry are encouraging. The present consumption is as follows:—New South Wales, 31,102,038 lb. (21·9 lb. per head); Victoria, 16,726,774 lb. (13·8 lb. per head); Queensland, 8,030,742 lb. (15·5 lb. per head); South Australia, 5,112,212 lb. (13·9 lb. per head); Western Australia, 6,567,572 lb. (29·7 lb. per head); Tasmania, 1,879,862 lb. (10·6 lb. per head).

It is interesting to note that the imports of dairy produce and margarine into the United Kingdom during 1903 reached a total value of £31,948,000, the highest yet recorded. The following figures show the percentages of imports of butter contributed by the various countries from which supplies were drawn during the last six years. It will be seen that Denmark maintains the leading position, while Russia occupies second place, having more than doubled its contribution.

Year.	Denmark	Russia.	France.	Holland.	Sweden.	Canada.	New Zealand.	Australia	Other Countries
	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.
1908	45·65	5·02	12·99	8·39	9·19	4·89	2·18	5·21	5·88
1899	42·19	4·10	10·44	8·40	7·25	7·33	3·29	7·79	9·16
1900	43·99	6·21	9·53	8·37	6·80	4·09	4·85	10·45	4·71
1901	43·13	10·22	8·42	8·07	4·87	5·82	4·52	6·70	8·25
1902	42·85	12·32	10·42	9·90	4·82	7·19	3·98	2·02	6·50
1903	40·26	11·35	10·15	7·22	4·96	4·51	7·23	8·99	5·23

One of the most satisfactory features in the above table is the growth of the colonial imports, which last year amounted to over 20 per cent. of the total, as compared with 13 per cent. in 1902, and 17 per cent. in 1901. During 1904 much larger supplies have been exported, both



from the Commonwealth and from New Zealand, and the proportion for the year should be considerably increased.

The import from the Argentine amounting to 4,435 tons, or 2·06 per cent. of the total is included in the column "Other Countries," the figures showing a substantial increase on those recorded at the beginning of the decennial period, when only 7 tons were received from that country.

In the table below will be found the average prices realised for Australian butter in the London market during the last ten years. Owing partly to the large increase in the supplies the price in 1904 was comparatively low :—

	s.	d.			s.	d.
1895 .....	101	4	per cwt.	1900 .....	104	6 per cwt.
1896 .....	107	2	„	1901 .....	108	5 „
1897 .....	104	4	„	1902 .....	109	6 „
1898 .....	100	4	„	1903 .....	107	11 „
1899 .....	104	0	„	1904 .....	99	11 „

The increase in the Colonial supplies will be apparent from the following table, which shows the total consumption of butter and cheese in Great Britain for the years 1895 and 1904, together with the proportions of local, foreign, and Colonial production entering into consumption in each year :—

	Butter.		Cheese.	
	1895.	1904.	1895.	1904.
	tons.	tons.	tons.	tons.
Consumption .....	214,189	307,894	251,340	288,662
Sources of Supply—				
United Kingdom .....	37·2	28·9	54 6	53·0
Colonies .....	8·3	14·7	24·5	35·5
Foreign Countries .....	54·5	56·4	20·9	11·5

During the last decade the average yearly increase in the quantity of butter imported into the United Kingdom was about 8,500 tons. This is partly accounted for by the rapid growth of the population generally, but more by reason of the fact that the increasing population of the towns is drawing more and more new milk from the churn and leaving less for butter and cheese making. Moreover, the number of cows per head of the population is decreasing rapidly, and at the present time there are 5·2 cows less per 1,000 inhabitants than was the case five years ago.

## SWINE.

The breeding of swine is usually carried on in conjunction with dairy-farming, and the following table shows the number of swine in each state at ten-year intervals since 1871 :—

State.	Number of Swine.				
	1871.	1881.	1891.	1901.	1908.
New South Wales ...	213,193	213,916	253,189	265,730	221,502
Victoria .....	177,447	239,926	286,780	350,370	315,333*
Queensland .....	32,707	56,438	122,672	121,641	117,553
South Australia .....	95,642	120,718	83,797	89,875	89,331
Western Australia .....	14,265	22,530	25,930	61,025	50,209
Tasmania .....	52,863	49,660	73,520	58,716	56,538
Commonwealth ..	586,017	703,188	845,888	947,357	850,556
New Zealand .....	151,460	200,083	308,812	224,024	226,591
Australasia .....	737,477	903,271	1,154,700	1,171,381	1,077,147

\* Estimated.

The production of swine should be an important adjunct to dairy-farming, but the increase in the number of pigs has not been so large as might have been expected. In Queensland, Tasmania, New South Wales, and New Zealand the number of swine is at present less than in 1891. Victoria possesses the largest stock, with 29·2 per cent. of the total, followed by New South Wales and New Zealand with 20·5 per cent. and 11·7 per cent. respectively; Queensland had 10·8 per cent. of the total; South Australia, 8·2 per cent.; Western Australia, 4·5 per cent.; and Tasmania, 5·1 per cent.

The products of the swine—bacon, ham, lard, and salt pork—are, as a rule, exported by all the states with the exception of New South Wales and Western Australia. The following table shows the excess of exports or imports in each state for the year 1903 :—

State.	Bacon and Ham.	Salt and Frozen Pork.	Lard.	Net Value exported.
	£	£	£	£
New South Wales .....	*26,047	*34,515	*10,343	*70,905
Victoria .....	134,428	*8,761	9,273	134,940
Queensland .....	*5,992	*6,802	951	*11,843
South Australia .....	14,129	.....	1,054	15,183
Western Australia .....	*138,347	*2,968	*13,283	*154,598
Tasmania .....	*3,547	.....	*2,074	*5,621
Commonwealth .....	*25,376	*53,046	*14,422	*92,844
New Zealand .....	14,616	9,426	180	24,222
Australasia .....	*10,760	*43,620	*14,242	*68,622

\* Excess of imports.

The production of bacon and hams for the various states in which the returns are collected is shown below :—

State.	Bacon and Ham made.
New South Wales .....	7,864,771 lb.
Victoria ..	12,504,851 „
Queensland .....	4,145,900 „
Western Australia .....	178,557 „

#### POULTRY AND MINOR INDUSTRIES.

An estimate is given below of the value of the production of poultry and eggs, together with that from bee-farming, in each state for the year 1903 :—

State.	Poultry and Eggs.	Honey and Beeswax.
New South Wales ... ..	£820,700	£23,500
Victoria .....	719,900	11,500
Queensland .....	316,800	6,100
South Australia .....	319,800	4,500
Western Australia .....	199,800	2,500
Tasmania .....	108,900	4,100
Commonwealth .....	£2,485,900	£58,200
New Zealand .....	500,200	16,200
Australasia .....	£2,986,100	£74,400

The most remarkable feature is the trade in eggs between South Australia as supplier and the other states as buyers. The returns for 1903 show that during that year South Australia exported eggs to the value of £116,182 to the other states.

The exports of frozen poultry, rabbits, and hares from New South Wales amounted in 1903 to £39,944, the bulk of which consisted of hares and rabbits, valued at £37,553. In this state the Government has provided cold storage chambers where suppliers may store their produce at a nominal rate. The facilities are largely availed of, and during 1903, 151,128 doz. eggs were stored, principally in September and October, in anticipation of the Christmas market. The deliveries from the Government stores in 1903 comprised 8,628 fowls, 2,936 ducks, 40 geese, 789 turkeys, 42,528 hares, and 651,467 pairs of rabbits.

In Victoria the export of rabbits and hares has reached much larger dimensions, over 3,501,000 pairs, valued at £168,000, being sent away in 1903. In addition to this there was an export of over £11,000 worth of frozen poultry and game. In this state, as in New South Wales, a large number of persons find remunerative employment in trapping hares and rabbits.

From New Zealand during 1903 no less than 2,230,487 pairs of rabbits and hares, valued at £100,088 were exported, the whole of which excepting £71 worth went to the United Kingdom. In addition, there was an export of 19,289 pairs of frozen poultry, valued at £4,257, consigned chiefly to South Africa.

## PASTORAL AND DAIRY PRODUCTION.

The total value of pastoral and dairy production, including that from poultry and bee farming, during the year 1903, in each state and in the whole of Australasia, together with the value per inhabitant, were as shown in the following table:—

State.	Total Value of Pastoral and Dairy Production.	Value per Inhabitant.		
	£	£	s.	d.
New South Wales .....	16,053,000	11	5	6
Victoria .....	8,053,000	6	13	0
Queensland .....	5,409,000	10	8	6
South Australia .....	3,123,000	8	10	0
Western Australia .....	1,649,000	7	9	6
Tasmania ..	1,008,000	5	13	0
Commonwealth .....	35,295,000	9	0	2
New Zealand .....	10,769,000	13	2	6
Australasia .....	46,064,000	9	14	6

The following table gives similar information for the last four census periods. It will be seen that the only states which show increases since 1891 are Western Australia, and New Zealand:—

State.	1871.	1881.	1891.	1901.
	£	£	£	£
New South Wales .....	8,709,000	13,151,000	17,460,000	15,598,000
Victoria .....	7,260,000	7,499,000	9,321,000	9,242,000
Queensland .....	1,959,000	4,186,000	7,561,400	6,670,000
South Australia .....	1,800,000	3,178,000	3,148,525	2,936,000
Western Australia .....	274,000	431,000	647,350	1,344,000
Tasmania .....	734,000	1,093,000	1,117,550	1,100,000
Commonwealth .....	20,736,000	29,538,000	39,255,825	36,880,000
New Zealand .....	3,210,000	7,096,000	9,153,225	9,970,000
Australasia { Total... ..	23,946,000	36,634,000	48,409,050	46,860,000
Per head.	£ s. d. 12 7 7	£ s. d. 13 3 11	£ s. d. 12 12 0	£ s. d. 10 4 6

On reference to the above table, it will be seen that although the total production has been nearly doubled since 1871 the value per head

has decreased considerably. In 1903 the value of pastoral and dairy production was £2,345,000 less than in 1891; but to a great extent this was due to diminished production caused by a succession of dry seasons—the cast of both sheep and cattle being much reduced as compared with 1891. On the other hand, the production of butter was larger, and also the export of meat, as will be seen below:—

Produce.	1891.	1903.
Wool, as in grease .....	Lb. 661,229,000	571,261,000
Cast of sheep .....	No. 17,000,000	8,500,000
Cast of cattle .....	No. 1,216,000	887,000
Butter produced .....	Lb. 70,628,000	146,078,000
Meat export.....	Cwt. 1,454,000	3,285,844

The movement in prices will be seen from the following tabulation, which is based chiefly on an analysis of the New South Wales trade. The prices of 1903 are represented by 1,000:—

Price Levels of—					
Year.	Wool.	Butter.	Cattle.	Tallow.	Hides.
1891	748	1,102	398	828	805
1892	735	1,110	392	845	688
1893	658	1,028	323	936	609
1894	609	851	248	869	562
1895	678	739	245	804	731
1896	724	1,039	407	725	613
1897	698	1,030	318	683	807
1898	742	1,095	420	774	858
1899	1,048	1,135	390	927	973
1900	851	1,092	484	1,006	1,029
1901	773	1,129	621	968	1,138
1902	895	1,316	858	1,157	1,004
1903	1,000	1,000	1,000	1,000	1,000

The price of wool, which advanced suddenly in 1899, declined again during 1900 and 1901, but there was an advance in 1902, which was continued in 1903 almost to the high level of 1899, and this advance has partly compensated for the small clip.

#### EMPLOYMENT IN PASTORAL AND DAIRYING PURSUITS.

The following tables show the total number of persons engaged in pastoral and dairying pursuits in Australasia for the years 1891 and 1901. In each case the figures include only the direct producers who were working on holdings in March of the respective years, and do

not take into account persons employed in butter factories, or casual hands engaged at other periods of the year :—

## PASTORAL.

	1891.		1901.	
	Males.	Females.	Males.	Females.
New South Wales.....	26,176	334	31,312	596
Victoria .....	5,660	1,881	11,650	1,602
Queensland .....	12,530	198	16,714	180
South Australia .....	3,582	317	4,112	81
Western Australia.....	1,530	98	1,633	52
Tasmania .....	1,859	142	957	26
New Zealand.....	6,486	90	12,014	156
Total .....	57,823	3,060	78,392	2,782
Total—Males and Females : 60,883			81,174.	

## DAIRYING.

	Males.		Females.	
	Males.	Females.	Males.	Females.
New South Wales.....	4,996	4,758	15,850	2,285
Victoria .....	4,850	2,933	11,701	5,877
Queensland .....	1,121	455	3,170	826
South Australia .....	419	1,014	839	2,029
Western Australia.....	175	72	350	144
Tasmania .....	181	265	561	337
New Zealand.....	2,793	180	7,586	1,654
Total .....	14,535	9,677	40,057	13,152
Total—Males and Females : 24,212			53,209.	

From the above table it will be seen that there has been an increase equal to 58 per cent. in the number of persons engaged in pastoral and dairying pursuits during the last ten years. This is chiefly owing to the rapid expansion of the dairying industry, especially in the three larger provinces, where the increase in this branch was more than double that of the first year of the period. Comparing the number of persons employed with the total stock expressed in terms of sheep, it will be found that the proportion in 1901 was 1 person to every 1,552 sheep, as against 1 to every 3,070 sheep in 1891. The decreased proportion in 1901 is of course partly attributable to the loss in stock from unfavourable seasons, but it arises chiefly from the greater amount of employment in the dairying industry, as well as from the tendency previously mentioned to divide the sheep into smaller flocks.

## INDUSTRIAL PROGRESS.

### THE PERIOD PRECEDING THE GOLD DISCOVERIES.

THE discovery of gold in 1851 divides the industrial history of Australia into two periods, the main characteristics of which are absolutely dissimilar. Prior to the discoveries of the precious metal, Australia appeared to be destined for a purely pastoral country. Its distance from the world's markets, and the fewness of its population, militated against any decided progress in agriculture; but the people were encouraged to devote their attention to a fuller development of the pastoral industry by the circumstance that a local market was not necessary. Moreover, the products of both sheep and cattle were so valuable that the heavy cost of carriage to England could be borne, and an ample margin still left to compete successfully with Russia, Germany, Spain, Portugal, and America, the great wool-growing countries of that epoch. This one-sided development of the country's resources was manifestly dangerous to industrial stability, as a succession of drouthy seasons might have had the effect of disturbing the business of the whole country; and this, indeed, was what from time to time actually happened.

Other industries would doubtless have followed in the wake of the great pastoral industry as time went on, and there were not wanting signs that, with an assured market, attention would be given to agriculture, and the manufacture of certain articles of local consumption.

The development of the industries of Australia along their natural lines must undoubtedly have been attended with ultimate success, but the colonists were not content to grow prosperous in such a humdrum way, and early in the forties there was intense speculation in land allotments in towns. Large and small country areas also were disposed of, and redispensed of, at prices far beyond what was warranted by any return that could be obtained from their immediate or prospective use, and many persons grew rich by the tossing backwards and forwards of title deeds. The business of land jobbing was, moreover, encouraged by the action of the local Government which from time to time disposed of considerable areas of land, and frequently altered its policy in regard to the public estate.

Land speculation, carried to excess, has tended on more than one occasion in Australia to a commercial crisis, and the disasters of 1842 and 1843 were undoubtedly attributable to this cause. They were accelerated, however, by the unwise action of the Government in

regard to its financial operations. Having sold much land, the Government was possessed of considerable funds, which were placed with the banks, at one time fully £350,000 being deposited, and the highest rates of interest exacted therefor. The banks accepting these deposits were obliged, on their part, to reissue equivalent sums in discounts, in order to pay the interest demanded of them. They, therefore, readily entered into the spirit of the times, and their willingness to lend stimulated amazingly the dealings in land purchase. It thus happened that business was transacted in a vicious circle. The Government, by selling land, thereby accumulated an amount of money, which was deposited with the banks, the money so deposited being loaned by the latter to their customers for the purpose of buying more land from the Government, the latter depositing the sums paid to them, which again were loaned for the purpose of land buying; and by this means the business of speculation was kept alive so long as the Government maintained its balance with the banks. The immigration policy of the Government, however, made large calls upon it, and the Treasury found itself compelled to withdraw its deposits upon very short notice. To meet this sudden call, the banks were compelled, to the utmost inconvenience of their customers, immediately to restrict their discounts and curtail advances, and it was this sudden contraction of credit that gave the initial downward impulse to the money market. The issue could hardly have been otherwise than as happened, and a financial crisis immediately resulted. The year 1842 was one of acute financial distress. In Sydney, property of all kinds became unsaleable, and many business houses, including some of the principal ones, became insolvent. For nearly two years the failures were at the rate of from fifty to sixty a month. A similar condition of affairs prevailed in Melbourne, and the distress was also keenly felt in Adelaide and Tasmania. The local prices of all descriptions of produce were ruinously low, and were still further depressed by reason of the large number of bankruptcies involving forced sales of real property, stock, wool, furniture, ships—indeed, of everything which promised a return, however small. Historians of that period relate cases of enforced sales at which sheep brought very small prices—as little as 6d. being obtained for them; while cattle occasionally realised only 7s. 6d., and valuable horses only £3 each. Boiling down, meat canning, and other devices were resorted to in order to revive the commerce of the country from the stagnation and lethargy into which it had fallen; yet, notwithstanding all expedients, the outlook steadily became more gloomy, prices continued seriously to decline, and speculation was at a standstill. South Australia was the first to emerge from the all-pervading depression. In 1844, copper arrived in Adelaide from the Kapunda Mine, and in 1845 the famous Burra Burra Mine was discovered. Other finds came in quick succession. Population was speedily attracted, and as the mines yielded beyond all expectation a season of prosperity at once ensued. The discovery of copper in South Australia proved to be of advantage to the rest



of Australia. Labourers and others were attracted to Adelaide from the neighbouring provinces, though not in such large numbers as would have relieved the labour markets. The men employed in the copper mines were able to earn 7s. per day, which at the time was considered a very high wage. Skilled mechanics were not so well remunerated; plasterers were paid from 4s. to 7s., very few getting the higher wage; painters' wages ranged from 4s. to 5s. 6d.; blacksmiths' from 4s. to 5s.; wheelwrights' 5s. to 5s. 6d. Carpenters' wages ranged from 5s. 6d. to 6s. 6d. per day—the highest rates paid to mechanics; bricklayers and masons earned from 5s. 6d. to 6s. per day. Farming hands were paid 10s. to 12s. per week with rations and sleeping accommodation, and were in much request. Domestic servants were in demand at wages varying from £14 to £22 per annum with board and lodging, and the supply was insufficient. The wages quoted were greatly in excess of those obtained prior to the discovery of copper and about 20 per cent. higher than for similar employment in New South Wales.

The average wages paid in New South Wales prior to 1851 were as indicated in the accompanying statement. Inferior workers, of whom there was naturally a considerable proportion, considering the origin of a large part of the population, did not receive within 20 per cent. of the rates quoted:—

Trade or Calling.	1843.	1844.	1845.	1846.	1847.	1848.	1849.	1850.
<i>Males, per day, without board and lodging.</i>								
Carpenters .....	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.
Smiths .....	5 0	4 0	4 0	5 2	5 6	5 3	4 9	4 6
Masons .....	5 0	4 0	4 3	5 2	5 6	5 3	4 9	4 6
Bricklayers .....	5 0	4 0	4 0	5 2	5 6	5 3	4 9	4 6
Wheelwrights .....	5 0	4 0	4 0	5 2	5 6	5 3	4 9	4 6
	4 0	3 6	3 3	4 8	5 0	5 3	4 9	4 6
<i>Males, per annum, with board and lodging.</i>								
	£	£	£	£	£	£	£	£
Farm labourers .....	15	15	18	20	23	21	18	18
Shepherds .....	14	14	17	20	23	21	18	18
<i>Females, per annum, with board and lodging.</i>								
	£	£	£	£	£	£	£	£
Cooks .....	15	15	18	20	22	21	17	17
Housemaids .....	15	15	15	17	17	17	14	13
Laundresses .....	12	12	15	17	19	18	15	15
Nursemaids .....	10	10	12	15	16	14	9	9
General servants .....	12	12	16	16	18	16	12	14
Farm-house servants .....	10	10	12	16	17	16	12	11
Dairy-women .....	10	10	12	16	17	16	12	11

These rates show a great reduction on those obtaining in 1841, in which year mechanics' wages stood at 7s. 6d. to 8s. per day, and those of farm servants at £25 a year. In the Port Phillip district wages

were generally higher than in Sydney, as also were those of Tasmania. A schedule of the latter is given below. The fall in wages was in a measure compensated for by a lowering of the price of provisions. During this period the average price of beef in the Australian cities ranged from 2½d. to 6½d. per lb., and of mutton from 2d. to 3d. per lb. The price of flour ranged from 14s. to 24s. per 100 lb. These prices were very greatly below those paid prior to the crisis. Bread, for example, in 1839 sold at 11½d. the 2 lb. loaf; in 1843 the price was 3½d., and thereafter it did not rise higher than 5d. until after the gold discoveries. House rents, however, continued high.

Throughout the period the demand for pastoral and agricultural labour was always fairly keen, and the stream of bounty-paid immigrants was maintained in spite of the fall in wages and the restriction in employment. The immigrants, however, were mainly of the agricultural class—shepherds, gardeners, and useful mechanics for country employment,—who were readily absorbed by the community. The condition of the mechanics who clung to the towns was one of great distress. Inferior men could not earn more than 2s. 6d. per day, and at no time was the average for good men more than 5s., while even at those rates employment was at times difficult to obtain.

In Tasmania wages were maintained at a higher level than in New South Wales, and in the undermentioned trades the ruling rates per day were :—

Year.	Bricklayers.	Carpenters.	Masons.	Quarrymen.
	s. d.	s. d.	s. d.	s. d.
1839	7 6	7 6	7 6	5 6
1840	7 6	7 6	7 6	5 6
1841	6 6	6 6	7 0	5 1
1842	7 0	7 0	8 0	5 6
1843	7 0	7 0	7 0	5 0
1844	5 0	5 0	4 6	3 0
1845	6 0	6 0	5 0	4 0
1846	5 6	5 6	5 6	3 0
1847	4 11	4 10	4 10	3 0
1848	4 10	4 8	4 10	3 2
1849	6 0	6 0	6 0	3 6
1850	5 6	5 6	5 6	3 4

The financial crisis of 1842 did not affect Tasmania in the same degree as it did New South Wales, since in the island colony there had been less land jobbing and riotous speculation. The fall in wages in 1844 was accompanied, and, in a measure, brought about, by a fall in the cost of living. It is difficult to determine the retail prices of the various commodities in common use, and to account for the causes of the great variation apparent from year to year. The price of flour, for example, seemed to have a very ill-defined relation to the price of wheat. In 1839, wheat was sold throughout the year at 26s. per bushel, and

flour at 24s. per cwt.; in 1840 the prices were: Wheat 9s. per bushel, and flour 30s. per cwt.; and in 1841, wheat 7s. per bushel, and flour 21s. per cwt. The price of tea was 1s. 6d. per lb. in 1839, and 2s. 6d. and 3s. 3d. in the two following years, and similarly with regard to other articles.

The following were the market prices of six of the leading commodities:—

Year.	Fresh Meat.	Sugar.	Tea.	Rice.	Wheat.	Potatoes.
	per lb.	per lb.	per lb.	per lb.	per bushl.	per cwt.
	d.	d.	s. d.	d.	s. d.	s. d.
1838 .....	5½	3½	1 5	3	8 9	6 0
1839 .....	4½	3½	1 6	3	26 0	10 0
1840 .....	6½	3½	2 6	2½	9 0	10 0
1841 .....	6½	3½	3 3	2½	7 0	10 0
1842 .....	4½	3½	2 0	2	6 6	7 0
1843 .....	2½	3	2 6	1½	3 6	5 0
1844 .....	2½	2½	1 6	1½	3 3	4 0
1845 .....	2½	3	1 6	3	3 3	4 6
1846 .....	2½	4	2 3	1½	5 0	3 0
1847 .....	2½	4	2 4	3½	4 10	5 10
1848 .....	2½	3½	2 0	3½	3 6	4 4
1849 .....	2½	3½	1 9	3½	4 1	3 0
1850 .....	2½	3½	1 10	4	4 9	4 0

About the year 1849, the labour market in Sydney was relieved in some measure by the emigration to California which commenced immediately on the announcement of the discovery of gold in that country. But as an amount of ready cash was needed before a person could emigrate, the most distressful part of the local population was little affected by the Californian mines, and it is difficult to imagine what would have happened had not the discovery of gold, in 1851, occurred so opportunely. In an instant the face of everything was changed, as if by the wand of a magician, although the full influence of the discoveries was not felt until the following year.

During the period anterior to the gold discoveries agriculture was entirely subsidiary to sheep and cattle raising, being confined to supplying the wants of the handful of persons scattered round the coastal fringe who then comprised the population of these states. The country was, therefore, dependent upon outside sources for the supply of the greater part of the food stuffs required for ordinary consumption. Signs were not wanting, however, of an early extension of the cultivation of wheat, particularly in South Australia. The plains around Adelaide yielded magnificent crops of the cereal, and when a method of harvesting was discovered which enabled the farmers to gather the crops, in spite of the looseness of the grain in the ear and the extreme brittleness of the straw, the future of the industry at once became more hopeful.

Naturally the manufacturing industries did not make much progress. Manufacturing for export was out of the question, handicapped as the infant settlements were by distance from the centres of civilisation. What industries there were had been called into being by the isolation of the country. The largest number of establishments of any kind were flour mills, of which there were in 1848 about 223; of these 87 were worked by steam, 53 by water, 42 by wind, and 38 by horse-power. The next in importance were establishments for the treatment of leather; then came breweries and distilleries, soap and candle works, iron foundries, brick-works and potteries, and ship and boat building, in the order named. As late as 1848 the industrial establishments of Australia were as comprised in the following list, and the employment afforded did not in all probability exceed 1,800 hands:—

Distilleries .....	2	Blacking manufactories .....	2
Rectifying and compounding .. ...	2	Meat preserving and salting works .....	5
Breweries .....	51	Potteries .....	9
Sugar refineries .....	2	Glass works.....	1
Soap and candle works .....	30	Copper smelting works .....	1
Tobacco and snuff factories.....	5	Iron and brass foundries, &c. ....	27
Woollen mills .....	8	Gas works .....	1
Hat manufactories .....	4	Ship and boat building, repairing	12
Rope works .....	7	Flour mills .....	223
Tanneries.....	62	Oatmeal, groat mills.....	1
Salt works .....	5		
Starch manufactories .....	2		

Of the 479 establishments, 272 were in New South Wales, 41 in the Port Phillip district, 99 in Tasmania, and 67 in South Australia. There were possibly a few others in Western Australia, information in regard to which has not been recorded.

Whale-fishing, although now almost unknown in Australian waters, at one time held a very important place amongst the industries of the country. From 1791 onwards there are records of the take of vessels engaged in the industry. In the twenties there were whaling stations belonging to Sydney merchants in various parts of the southern seas, and whale-fishing was afterwards carried on from a Tasmanian base at Frederick Henry Bay and from Portland Bay, Victoria. The colonists of Western Australia had also engaged in the whale fishery, which appears to have been continued by them until the whales had practically disappeared from local waters. The practice of Australian whalers of killing the calves, in order to secure the capture of the mothers, did great damage to the fishery by wastefully thinning out the product, and in 1843 the animal was remarked as becoming somewhat shy and scarce in southern seas. By the year 1847, the industry was declining in southern waters generally, and Australian shipping was engaging more exclusively in the carrying trade, and in time the whaling industry was prosecuted mainly by American vessels. The value of the total quantity of whale oil exported from New South Wales has been estimated at about £3,000,000, and from Tasmania at about £1,200,000.

The principal exports during the year preceding the gold discoveries were wool, tallow, oil, skins, bark, and salt beef. Wool has been one of the staple products of the country from the earliest days of the century, although in some years the product of the fisheries was equally important. Trade was almost wholly confined to the United Kingdom, and in ten years, 1841-50, the quantity of wool exported to that country was:—

	lb.		lb.
1841.....	12,959,671	1846.....	26,056,815
1842.....	17,433,780	1847.....	30,034,567
1843.....	17,589,712	1848.....	35,774,671
1844.....	24,150,687	1849.....	39,018,221
1845.....	21,665,270	1850.....	41,426,655

The value of the wool trade for the year 1850 was £1,992,369, and the shares of the present states, according to quantity and value, were:—

	lb.	Value. £
New South Wales .....	14,270,622	788,051
Victoria .....	18,091,207	826,190
South Australia .....	2,841,131	113,259
Western Australia .....	368,595	16,000
Tasmania .....	5,855,100	248,869
Total.....	41,426,655	1,992,369

Sperm oil was principally exported from Sydney and Hobart, the value of the trade in 1850 being £65,499, a slightly larger quantity being despatched from Hobart than from Sydney. The value of tallow exported was £311,900, of which £167,858 was sent from Sydney, and £132,863 from Melbourne. In 1850 South Australia was already a copper producing country of some importance, and its export of metal and ore had reached £275,090. Flour was also becoming an item of export worth considering in South Australia and Tasmania, the former having exported in 1850 wheat and flour to the value of £41,491, and the latter £34,565, besides providing for the local consumption.

In 1850 the export of domestic produce, including products of fisheries, from each division of Australia was:—

	£
New South Wales .....	1,158,858
Victoria .....	1,022,064
South Australia .....	570,816
Western Australia.....	30 000
Tasmania.....	558,000

#### INDUSTRIAL PERIOD—1851-8.

##### *The Gold Discoveries.*

The attention of the people of Australia during the period extending from the year 1851 to 1858 was chiefly directed to gold-seeking. The whole period was one of rapid growth and great change. It is chiefly

interesting politically on account of the initiation of responsible government in New South Wales, Victoria, South Australia, and Tasmania, and commercially, because of the construction of the first railroads and the establishment of steam communication with Great Britain.

The discovery of gold not only put an end to the depression of the previous period, but it effected a revolution in all industrial relations. According to contemporary evidence, the supply of labour in many occupations speedily became exhausted, and there were more persons desirous of hiring labourers than there were labourers to be hired. The diggings drained not only Melbourne and Sydney, but Adelaide, Hobart, and every other Australian centre. Most branches of industry and all public works were at a standstill. In New South Wales the sheep and cattle stations were deserted by their hands very shortly after the first great discoveries were made, and for a time it was impossible, in some parts of the colony, to care for the flocks except by the employment of aborigines. In South Australia, during 1852 and 1853, the crops would have remained unharvested if it had not been for the assistance of the blacks, so great was the exodus of farming hands. In Victoria, where the greatest quantity of gold was found, for a brief period no other occupation than gold seeking was thought of, until it was discovered by the reflecting part of the population that trade offered even greater and surer prizes, and there as well as elsewhere every department of industry received a direct stimulus. In Tasmania the people became so infected with the epidemic that there was danger of the island becoming depopulated. The able-bodied men left by every boat, and Bass's Straits became in a brief period a populous waterway from the home of hardship and toil to the visionland of wealth. So great was the exodus that some of the country districts were utterly deserted by the male inhabitants.

The eight or nine years characterised by the rage of the gold fever exercised a very great economic effect on the condition of the working classes ; for had there been no discovery of gold it is not improbable that, with respect to both the standard of living and the remuneration of labour, the conditions existing prior to 1850 would have long remained without any great change for the better. In those days the standard of labour in England was the practical test of the condition of the working classes in Australia, who were thought well off simply because their earnings enabled them to enjoy comforts beyond the reach of their fellows in the Old World. Since the gold era this has been changed, and the standard now made for themselves by Australian workers has no reference to that of any other country. The attractions of the gold-fields had also a marked subsequent effect upon industries of an absolutely different character. Many men, of all sorts of trades and professions, who were drawn to these shores by the prospect of acquiring enough of the precious metal to ensure their independence, remained in the country, and pursued less exciting and less precarious callings, while gold-miners themselves in many cases ceased the exploitation of

the mineral which was to have made them rich, and turned their attention to the winning of silver, copper, tin, coal, and other minerals.

Another effect of the gold rush must not be lost sight of. Although Australia had ceased to be a place open to the reception of British convicts, yet the old settled parts were permeated with social and economic ideas begotten of the transportation era. The men who had been convicts, or who were born of convict parents, were a considerable element in the population, while the employers had, for the most part, at one period or other of their career, been masters of bond labour. A few years changed all this. It was as if Australia had been newly discovered. Certainly the country was recolonised, and the bond population and their descendants became a small minority of the population which every year made more insignificant, until at the present day it is only in out of the way corners that there is anything to remind the observer that any part of Australia was at one time a penal settlement.

The gold fever brought to Australia not only young, stalwart, enterprising men of great endurance, and capable of adapting themselves to almost any conditions of life, but also multitudes of others whose chief idea was that wealth could be acquired almost without exertion. Unable to endure the hardships of the digger's lot, without trade or profession, and capable of only the lightest manual labour, they mostly drifted back to the chief towns; and there was speedily presented the strange spectacle of thousands of unemployed clamouring for government work, while the more stalwart labourers were earning extraordinary wages in the gold-fields.

At the height of the gold discovery the earnings of miners in some cases were prodigious. The Gold Commissioners of New South Wales estimated the average earnings of diggers to have been about £1 per day; and a comparison of the gold yield with the numbers of licenses issued confirms this calculation. In Victoria the average was probably much higher, and a contemporary calculation fixes the earnings at £42 10s. per month for each miner licensed to dig. Making allowance for illicit digging, there seems ample proof that in the first half of 1852 the average of all miners could hardly have been less than 30s. per day. At one period 50,000 persons held licenses in Victoria and 31,000 in New South Wales; and if allowance be made for the great number of persons who evaded payment of the license fee, the number of gold diggers could scarcely have been less than 100,000 in a total male population in Victoria and New South Wales of 229,562.

The effect of the discoveries on wages was immediate and extraordinary. Governor La Trobe of Victoria, in a despatch, under date 12th January, 1852, remarks on the difference in the wages payable immediately before and after the gold discoveries. The wages of shearers rose from 12s. in 1850 to 20s. in 1851; of reapers, from 10s. to 20s. and 25s. per acre; of common labourers, from 5s. to 15s. and 20s. per day; of coopers, from 5s. to 10s.; of shipwrights, from 6s. to 10s.; of wool-pressers, from 3s. 6d. to 7s. and 8s. per day; sailors, from

£4 to £9 a month (from £50 to £100 being offered for the run to England); stokers, from £12 to £20 a month; men cooks, from 20s. and 25s. to £2 and £3 a week; waiters at hotels, from 20s. to 40s. and 50s. a week; ostlers and stable-men, from 21s. to 50s. a week; men servants in town, from £25 and £30 to £50 and £70 per annum, and none to be had even at these wages; men servants in the country, from £20 and £25 to £35 and £40; salesmen, shopmen, &c., from 25s. and 35s. to 40s. and 70s. a week; porters, from 12s. and 15s. to 25s. and 35s. a week; the increase in the wage of female servants was 25 per cent.; of clerks in banks and mercantile houses, 20 to 50 per cent.; but the figures given by the Governor denoted only the beginning of the advance in wages. Prices rose in response to the altered conditions. From December, 1850, to December, 1851, the prices of provisions, etc., had risen as follows:—Bread, 4 lb. loaf, from 5d. to 1s. 4d. and 1s. 8d.; butter, from 1s. 2d. to 2s. and 2s. 6d.; cheese, from 8d. and 1s. 4d. to 2s. and 3s.; fresh meat doubled; salt meat rose from 1½d. to 2½d.; ham, from 8d. and 1s. to 1s. 6d. and 2s. 6d.; bacon, from 6d. and 8d. to 2s. per lb.; fowls and ducks, from 3s. and 3s. 6d. to 5s. and 6s. a couple; potatoes, from 8s. to 12s. and 15s. a cwt.; tobacco, from 2s. 6d. and 4s. to 7s. and 8s. a lb.; groceries generally, 25 per cent.; vegetables, from 50 to 100 per cent; spirits, wine, beer, etc., from 30 to 50 per cent.; confectionery, 50 per cent.; fruit, 100 per cent. The following are the percentage rates of increase on the prices of some of the supplies furnished under contract for the Government service of Victoria:—Candles, 60 per cent.; fresh beef, 33½ per cent.; salt pork, 25 per cent.; bread, 50 per cent.; tea, about 21 per cent.; sugar, 10 per cent.; soap, 20 per cent.; milk, 75 per cent.; new horse-shoes, 150 per cent.; cost of removing old ones, 350 per cent.; printing, 100 per cent.; saddlery, 75 per cent.; for boots and shoes no tender could be obtained. "Old furniture," remarks the Governor, "sells at about 75 per cent. advance upon the former price of new. Scarcely any mechanic will work; those few who do, receive an advance on former wages of from 200 to 350 per cent."

The condition of things just described may be looked upon as chaotic, but every month saw the prices of commodities and the remuneration for labour more systematised. As the gold discoveries continued, the wages continued to rise, but there was an essential difference between the conditions of 1851 and 1853. In the former year, men's ideas of the amount of the wages they should receive were, on the one hand, tempered by the remembrance of the wages paid in England and in the colonies before the discovery of gold, and on the other they were excited by the boundless possibilities of easily acquired wealth which loomed before the successful digger, and their demands rose and fell according to the exigencies of the employer. In 1853 the condition of things became more settled. Wages on the average were higher than in previous years, but there was a recognised scale for the payment of the principal classes of labourers and mechanics. In 1853, carpenters, wheelwrights, and bricklayers received, in Melbourne, 15s. per day with



board and lodging; masons, without board and lodging, 26s. 9d. per day; bricklayers, 25s. per day; smiths and wheelwrights, 22s. 6d. per day. This would seem to fix the cost of board and lodging at about £3 10s. per week. In the following year the wages of wheelwrights reached 30s. per day; bricklayers, 30s. per day; but the pay of carpenters and other mechanics remained about the same. In the next table the wages given are those ruling in Sydney during the period named. It must be remembered, however, that in some instances the wages quoted were merely nominal, as, owing to the dearth of labour, there was a suspension of many trades which flourished before the gold discoveries, and prices quoted are those paid to the remnant who remained in town:—

Trade or Calling.	1851.	1852.	1853.	1854.	1855.	1856.	1857.	1858.
<i>Males, per day, without board and lodging.</i>								
Bricklayers .....	s. d.	s. d.	s. d.	s. s.	s. s.	s. s.	s. s.	s. s.
Blacksmiths .....	6 0	9 0	15 6	25 to 30	18 to 25	16 to 18	12 to 16	10/6 to 11/6
Carpenters .....	6 8	9 0	12 9	20 to 25	14 to 16	8 to 13	10 to 14	10/6
Coppers .....	6 5	9 0	12 6	15 to 20	12 to 15	12 to 15	10 to 12	10 to 11
Cabinetmakers .....	.....	.....	.....	15 to 20	10 to 12	12 to 14	12 to 14	.....
Furriers .....	.....	.....	.....	15 to 20	12 to 15	12 to 15	12 to 14	.....
Plumbers and glaziers .....	.....	.....	.....	12 to 15	10 to 12	9 to 12	10 to 12	.....
Joiners .....	.....	.....	.....	16 to 20	12 to 15	12 to 15	12 to 15	.....
Ironfounders .....	.....	.....	.....	17 to 20	12 to 15	12 to 14	12 to 15	.....
Locksmiths .....	.....	.....	.....	16 to 20	14 to 18	12 to 14	11 to 13	.....
Quarrymen .....	.....	.....	.....	18 to 22	16 to 18	12 to 15	10 to 13	.....
Shoemakers .....	.....	.....	.....	18 to 21	16 to 18	12 to 15	14 to 16	.....
Wheelwrights .....	6 4	9 0	15 0	.....	14 to 22	12 to 14	10 to 12	.....
Plasterers .....	.....	.....	.....	18 to 20	14 to 16	12 to 14	12 to 14	10 to 11
Painters .....	.....	.....	.....	25 to 30	14 to 18	16 to 17	18 to 15	.....
Stone-masons .....	7 8	9 0	16 0	13 to 16	8 to 13	14 to 10	12 to 8	12 to 15

*Females, per annum, with board and lodging.*

	£	£	£	£	£	£	£	£	£
Cooks .....	16 to 25	13 to 25	24	28	28	25	28	28	26
Housemaids .....	14 to 18	14 to 19	17	22	22	21	17	23	23
Laundresses .....	7 to 12	15 to 18	20	28	28	24	23	26	26
Nursemaids .....	9 to 15	16 to 18	17	18	18	18	18	19	19
General servants .....	14 to 18	16 to 18	18	28	23	22	23	25	25
Farm-house servants .....	13	14	15	25	22	20	19	25	25
Dairy-women .....	13	14	16	25	22	20	19	25	25

In Adelaide, from the time of the discovery of gold, wages were not only daily advancing, but some industries came to a complete standstill. In wheat farming, for example, it was impossible to procure white labour at all, and, as already remarked, settlers were glad to hire the aborigines to gather in their crops, and for this work they were paid at the rate of 10s. an acre. As mentioned elsewhere, Tasmania lost a large portion of its adult population to Victoria, but those who remained behind prospered exceedingly. Everything the island produced found a ready market and at highly remunerative prices.

Prices of articles of ordinary consumption in Victoria have already been alluded to. All over Australia the prices of provisions and of all articles of clothing were, during this golden era, largely increased; indeed, there was hardly a commodity in the market, whether of use or

of luxury, the price of which might not be described as "fancy." In 1853 bread sold in Sydney at  $3\frac{1}{2}$  to 4d. per lb. and potatoes at 13s. per cwt., but certain lines of provisions were fairly reasonable; for instance, tea was quoted at 1s. 4d. per lb., sugar at 3d., fresh meat at 3d., butter at 1s. 5d., brandy at 23s. per gallon, and imported beer at 5s. per gallon; flour, however, was quoted at 3d. per lb., the price per ton ranging between £20 and £27. House rents, of course, rose with the influx of population. In Melbourne, the sudden increase of population raised house rents to an unparalleled height, and for a considerable time a large proportion of the community lived in tents. This, of course, gave an extraordinary stimulus to building, and partly from this reason, and partly on account of the mercantile failures consequent on the over-trading of 1853 and 1854, the year 1855 witnessed a heavy fall in rents, so that in that year they did not exceed half the amount paid three years previously.

In Sydney, the number of persons requiring house room was so much in excess of the accommodation available in habitable dwellings that the census of 1856 enumerates no fewer than 709 houses as being in occupation although still in the hands of the builder. As illustrative of the exigencies of the time in this particular, it is interesting to note that out of 39,807 dwellings 1,709 were tents, 31 were drays, and 64 were ships used as residences. Of the total number of habitations in New South Wales, 23,709 were built of wood, and of such inferior materials as bark, slabs, wattle and daub, and the like, and 225 of iron, while more than one-third of the dwellings were roofed with bark and thatch. Owing to the dearth and dearness of skilled labour, a large number of houses were imported in pieces, ready to be put together with little or no carpentering work beyond making the foundations and driving the nails. Some of these were still to be seen in the vicinity of Sydney and other towns until within recent years.

The discovery of gold had an almost immediate effect in establishing Melbourne as the largest city of Australia, and Victoria as the most important state. The total trade of Victoria, New South Wales, and South Australia with places outside their boundaries during the eight years was as given in the following table. The preponderance of Victoria is evident.

Year	New South Wales.		Victoria.		South Australia.		Tasmania.		Western Australia.	
	Imports.	Exports.	Imports.	Exports.	Imports.	Exports.	Imports.	Exports.	Imp.	Exp.
	£	£	£	£	£	£	£	£	£	£
1851	1,563,981	1,796,912	1,056,437	1,422,909	960,777	602,087	641,609	665,790	54,506	26,579
1852	1,900,436	4,604,034	4,069,742	7,451,549	798,811	1,787,741	860,488	1,509,883	97,304	24,181
1853	6,342,397	4,523,546	15,842,637	11,061,544	2,836,290	2,241,814	2,378,397	1,756,316	128,738	31,645
1854	5,981,063	4,050,126	17,659,051	11,775,204	2,147,107	1,322,832	2,604,630	1,423,081	128,390	34,169
1855	4,638,519	2,884,130	12,007,939	13,493,838	1,370,938	968,215	1,559,797	1,423,623	106,250	46,314
1856	5,460,971	2,430,890	14,962,269	15,469,760	1,306,529	1,035,740	1,442,106	1,207,802	122,982	44,749
1857	6,729,498	4,011,952	17,256,209	15,079,512	1,623,022	1,968,572	1,271,087	1,354,655	94,533	59,947
1858	6,059,366	4,186,277	15,108,249	13,989,209	1,769,351	1,512,186	1,323,612	1,151,609	144,987	78,649

The excess of the imports is very marked in the years immediately following the discoveries, and indicates the inflow of capital accompanying the immigrants who poured into the country from Europe and elsewhere. During the eight years included in the foregoing table the excess of arrivals over departures was at least 450,000, probably more; and if each of these immigrants brought with him not more than £25, their capital alone would represent £11,250,000. The imports comprised manufactured goods and articles of luxury, and the exports were almost exclusively gold and wool, and other raw material, the produce of the pastoral industry. As already mentioned, the product of the southern fisheries had greatly fallen off by the beginning of the period, and the export of oil, etc., averaged for five years between £25,000 and £30,000 per annum. In 1858 the exports of the fisheries had fallen to £1,450; in 1859 to £532; and in 1860 to £136. With the last-named year, the industry, around which cluster so many historical associations, and which is so peculiarly reminiscent of the early days of Australian settlement, practically disappears, although a few trifling essays have, from time to time, been made to revive it in southern waters, and small quantities of oil are still exported.

The actual export of gold from Australia cannot now be stated with exactness. The figures given in the following table show the exports in excess of the imports registered in the Customs houses, but doubtless there was a large export of which no account was rendered to the authorities, for, though the influx of population was great, the departures were also numerous, and every ship that left Melbourne carried with it more or less gold in the possession of returning diggers.

Year.	Net Export of Gold from—	
	Victoria.	New South Wales.
	£	£
1851	508,013	468,336
1852	6,912,415	2,660,946
1853	11,090,643	1,781,172
1854	9,214,093	773,209
1855	11,070,270	654,594
1856	11,943,458	689,174
1857	10,967,591	674,477
1858	10,107,836	1,104,175

The figures for Victoria are from the Customs returns, and in the earlier years are probably far below the actual amounts. Competent authorities estimate the yield of 1852 at fifteen millions, or about eight millions in excess of the official returns.

The foregoing table explains the tremendous attraction which the southern colony possessed for the population of the Australasian group. The imports into Victoria during 1854 were no less than £17,659,051; it is therefore easy to understand how it happened that, for a period, the parent colony was quite eclipsed by the growth of its own off-shoot, and that the commerce of the South Pacific gravitated to Melbourne. During a single month as many as 152 ships arrived in Port Phillip, conveying thither 12,000 immigrants.

Agriculture was greatly neglected during the days of the gold fever. In New South Wales about one-third of the area went out of cultivation, the acreage falling from 198,000 acres in 1850 to 131,000 acres in 1852; in Victoria there was a reduction from 52,000 acres to 34,000 in the same period; in Tasmania and South Australia there were also considerable reductions in the area cropped. The check to the industry was, however, only temporary, as the ultimate effect of the gold discoveries upon agriculture was extremely stimulating. In Victoria, especially, there was a great expansion. In 1853 the breadth of land cropped was 34,000 acres; in six years this had been increased to 419,000 acres. In 1857 the cultivated area in Victoria exceeded that of New South Wales by 50,000 acres, a superiority which was afterwards greatly added to and is maintained to this day.

The progress of agriculture in each state may be seen from the following figures:—

AREA UNDER CROP.

Year	New South Wales.	Victoria.	South Australia.	Western Australia.	Tasmania.	Total.
	acres.	acres.	acres.	acres.	acres.	acres.
1850	198,056	52,341	64,728	7,419	168,820	491,364
1854	131,857	54,905	128,692	13,979	127,732	458,165
1858	223,295	298,960	264,462	20,904	229,489	1,037,110

The principal crops grown were wheat, oats, potatoes, and hay, chiefly wheaten and oaten; but there were signs of attention being paid, especially in Victoria and Tasmania, to fruit-growing and other forms of culture requiring less land and more labour.

The influence of the gold discoveries on the pastoral industry was twofold—on the one hand retarding its development by depriving it of labour, and on the other, encouraging it by the creation of a demand for carcase meat. Before the discoveries, fat sheep sold in the Melbourne market at 10s. to 12s., in 1852 the price was 30s., and higher prices were subsequently obtained. During the whole period the value of the

carcase steadily gained on that of the wool, and it is not surprising, therefore, that the increase of the flocks was arrested. This was especially the case in Victoria, where the number of sheep depastured fell from 6,589,923 in 1851 to 4,577,872 in 1855. In New South Wales the number of sheep fluctuated according to the requirements of the southern districts, but there was no tendency for the flocks to increase. In 1859 the number of sheep depastured fell to 5,162,671, or three millions below the figures of some previous years, a result brought about by the demand for restocking in Victoria, and the opening up of new country in Queensland.

In the first years of the colony's history the coastal belt only was available for settlement, but with the crossing of the Blue Mountains, in 1813, a new horizon stretched before the pastoral imagination, and with each successive discovery by Oxley or Cunningham or Mitchell or Hume, plain was added to plain of pasture, and the paths of the explorers were dotted with chains of squattages. In the earliest years of pastoral settlement it was customary for stock-breeders to drive their herds to the nearest unoccupied good country when they increased beyond the grazing capabilities of their pasturages. In this manner the river-courses in the western districts became stocked, and the country bordering them occupied. The practice came into vogue when cattle were decreasing in value, and when, therefore, it was absolutely necessary to breed them at the least expense. These herds were, however, inferior in strain. They frequently became wild and unmanageable, and it was only with the influx of population during the gold fever days, when high prices were paid for meat, that they acquired any value. The cattle, nevertheless, showed that the interior country was good for stock-grazing, and proved that land which had hitherto been regarded as a desert was very fattening pasture; for they had discovered "salt-bush," a fodder plant which retains its vitality when other kinds of herbage have long withered away. The grazing value of the river country, or Riverina, has never since been challenged.

There were in effect three great waves of pastoral settlement which swept over Australia. The first is that just alluded to, which flowed over the inland plains between the colonies of New South Wales, Victoria, and South Australia. The second rolled farther north, and beyond the occupied country, as far as the central basin of the continent. The third went still northward to the downs of Queensland. The first migration of stock arose from the demands for meat made by the gold-diggers. The success of this pioneer movement inspired the second experiment, which was prompted by the demand for wool. The third essay in pastoral settlement was occasioned by the maintained and increasing value of all squatting property.

The first of these migrations alone concerns the industrial history of the gold period, and began immediately the first fever of discovery had abated, and was the chief factor in producing the agrarian agitation which marked the following decade.

The following is a statement of the values of the chief articles of pastoral produce exported in the years named :—

Year.	Wool.	Tallow and Lard.	Skins and Hides.
	£	£	£
1851	1,979,527	237,402	32,284
1855	3,170,640	152,376	69,602
1859	4,236,693	48,085	271,349

The actual number of stock depastured in Australia was as follows :—

Year.	Sheep.	Horned Cattle.	Horses.	Swine.
1851	17,515,798	1,924,482	167,220	109,911
1852	18,002,140	2,075,256	186,092	132,093
1853	17,191,146	2,141,526	183,360	123,033
1854	17,249,581	2,256,639	208,133	112,062
1855	17,065,979	2,697,390	231,066	131,431
1856	16,193,035	3,054,592	262,448	212,582
1857	17,091,798	3,180,042	289,027	217,352
1858	17,205,653	3,217,600	332,331	196,636
1859	15,443,617	3,275,850	353,338	245,367

Upon the manufacturing industry the first effect of the gold rush was disastrous ; but there was an immediate change, especially in Victoria, where the camps of the diggers soon became thriving towns. It was to the population attracted to the country by the gold discoveries that the manufactories owed their subsequent revival and the labour required to operate them. The statistics of these states are not complete enough to enable a statement of the progress of the manufacturing industry to be given ; but it is evident, from the rapid increase, after the year 1855, in the number and variety of establishments, that the ultimate effect of the gold discoveries upon the manufacturing industry was extremely stimulating.

Reference has already been made to the opening up of steam communication with England in 1852, during which year the "Chusan," the "Australia," and the "Great Britain"—the last-named the largest ship afloat at that time—visited Australia. In 1856 a steam service, of anything but a satisfactory character, was carried on by the Peninsular and Oriental Company and the Royal Mail Company ; but the days of efficient ocean communication were still to come. These early essays, however, had no small effect in encouraging the colonists to agitate for something better, and proposals were made for the establishment of a line of mail-packets *via* Panama, but they did not bear fruit until the year 1866.

The history of railway construction is elsewhere dealt with. It was not until 1846 that the people of Australia began to awaken to the

advantages of railroad communication, and not until two years afterwards that a company was formed to construct a railway from Sydney to Parramatta and Liverpool. This line was commenced in 1850 and partly completed in 1855. Meanwhile, the discovery of gold had been made, and attention was directed to railway construction in Melbourne, and in 1854 the first line in Australia was opened for traffic; it ran from Melbourne to Port Melbourne, and was  $2\frac{1}{2}$  miles long. For some years railway construction languished, the enthusiasm of its advocates being doubtless considerably damped by the reflection that the short line from Sydney to Parramatta—only 14 miles in length—cost £700,000, or £50,000 a mile. The progress of railway construction is shown by the following figures, which give the length of line open for traffic in the years named :—

Years.	Miles.	Years.	Miles.
1854 .....	$2\frac{1}{2}$	1857 .....	117
1855 .....	$16\frac{1}{2}$	1858 .....	132
1856 .....	$32\frac{1}{2}$	1859 .....	171

With steam communication to other parts of the world, and the introduction into Australia of the railway system, new markets were being created for the trade in coal, although it was not before the subsidence of the gold fever that they began to be availed of. The quantity of coal raised in 1852 was 67,404 tons, and in 1858 over three times as much, viz., 216,397 tons. In 1850 and 1851 the price of coal ranged from 9s. to 10s. per ton; in 1852 it had risen to over 80s. per ton, although it did not remain for an extended period at this high figure. The quantity and value of the production of this mineral during the period under review were as follow :—

Year.	Quantity raised.	Average price per ton.	Approximate total value.
	tons.	s. d.	£
1852	67,404	10 11	36,885
1853	96,809	16 2	78,059
1854	116,642	20 6	119,380
1855	137,076	13 0	89,082
1856	189,960	12 5	117,906
1857	210,434	14 1	148,158
1858	216,397	15 0	162,162

The whole of this coal was mined in New South Wales.

During the whole of this period considerable activity was shown in testing the navigable waters of the Continent, and repeated efforts were

made to open up communication by way of the rivers Murray and Darling, which, of course, had a corresponding influence on the great pastoral industry by affording means of cheap transit for the leading staple of the interior. In 1853, W. R. Randall, in his small steamer, the "Mary Anne," was the first to proceed up the Murray, and eventually he reached Maiden's Punt, as the crossing from Echuca to Moama was then named. In the same year Captain Cadell proceeded in a steamer up the Murray to near Albury "with the greatest ease and success." This voyage attracted marked attention, and was the cause of the inauguration of regular steam-service on the river. Captains Cadell, Johnson, and Robertson, and Mr. Randall, subsequently followed up the original essays in the direction of inland river navigation by steaming up the courses of the Murrumbidgee, the Darling, the Barwon, and the Edwards, thus making accessible to population, and opening up to the wool-growing industry, an enormous expanse of territory. In the north, A. C. Gregory (in search of Leichhardt), Dalrymple, and other explorers, were successively unlocking to the squatters, who followed closely in their wake, the broad areas of pasturage, whose almost immediate occupation advanced the northern congeries of squatting localities, known as the Moreton Bay District, in rapid strides to the dignity of the Colony of Queensland. It is noteworthy, and distinctly characteristic of the period, that by the year 1854 the purchase of land for agricultural purposes had almost ceased, territory being taken up instead in large tracts by pastoral lessees for grazing purposes.

The population of Australia in 1850 was 480,120; in 1855 it had risen to 821,452, and in 1860 to 1,141,563. The tendency to crowd into the cities was already visible; in 1861 Melbourne held 139,916 people, and Sydney 95,789, or together 235,705, a total representing one-fifth of the population of the continent.

#### INDUSTRIAL PERIOD—1859-62.

The three years, 1860-62, may be regarded as a transition period, during which the country was undergoing the process of recovery from the days of excitement and dreams of chance, when the wealthy speculator of one moment became the beggared adventurer of the next, and the outcast of many years the millionaire of as many months. The community was vaguely restless, as though beginning to realise that the golden era of its recent experience was drifting into a prosaic period of sterner conditions and slower and more arduous growth. There were many, however, still in the daily expectation of hearing of new discoveries as rich as those of the previous decade, and these refused to accept the conditions of settled industry, while the rumour of a new find was sufficient to entice them away from the employment they clanced at the time to be following.

The production of gold in 1859 was nearly ten and a half millions, of which one and a quarter million was from New South Wales, and the



balance from Victoria. The following was the yield during the four years embraced in this period :—

Year.	Victoria.	New South Wales.	Other Districts.	Total.
	£	£	£	£
1859	9,122,868	1,259,127	780	10,382,725
1860	8,626,800	1,465,373	.....	10,092,173
1861	7,869,812	1,806,171	.....	9,675,983
1862	6,633,124	2,467,780	12,442	9,113,346

It will be seen that, in spite of the improvement in New South Wales, the total gold won was steadily declining. The earnings of the working miner were diminishing in even a greater ratio than the foregoing figures indicate, with the natural and immediate result that there was a return of gold-seekers to their original or other pursuits. Agriculture naturally received more attention, but many successful miners made investments in squattages, and both for farming and grazing there arose a persistent demand for the acquisition of state lands on more equitable terms than had hitherto prevailed in Victoria and New South Wales.

The renewal of attention to agrarian pursuits was general throughout Australia. Victoria and South Australia had about equal areas under tillage, although the value of crop was, perhaps, greatest in the first-named. Victoria had benefited most by the gold discoveries, both directly and indirectly, and was now in all important respects the leading state. It was the chief financial centre, and had the largest population, trade, acreage under tillage, and mining yield, as well as a larger number of sheep, and perhaps sheep of a better class than possessed by any of its neighbours. New South Wales stood first in regard to the possession of cattle and horses; Queensland and South Australia had already large interests in live stock, especially in sheep and cattle; and Tasmania depastured more sheep than it does at the present time, while the number of cattle and horses in the state was considerable. The following were the numbers of stock of each class at the close of the year 1862 :—

State.	Sheep.	Cattle.	Horses.
New South Wales .....	6,145,651	2,620,383	273,389
Victoria .....	6,764,851	576,601	86,067
Queensland .....	4,553,353	637,296	38,532
South Australia .....	3,431,000	258,342	56,251
Western Australia .....	295,666	36,887	12,099
Tasmania .....	1,616,225	83,143	20,742
Total .....	22,806,746	4,212,632	495,080

The area under crop at the close of the year 1862 was 1,549,255 acres. In South Australia the acreage was 494,511; in Victoria, 465,430; in New South Wales, 302,138; and in Tasmania, 253,050. The beginning of an important industry was made in Queensland, though the area in crop was only 6,067 acres, while in Western Australia the cultivated area was 28,059 acres. The importance already assumed by South Australia is very noticeable, and from this period that state and Victoria continued to make, for twenty years, rapid and almost equal progress, until in 1892 the superiority in agricultural interests fell to Victoria, where it has remained. Although New South Wales had many advantages over the southern states, its agricultural progress was astonishingly slow; in point of fact, its position was little in advance of Tasmania so far as concerned acreage, and probably below it in point of value.

The permanent effect of the gold discoveries on the industries of Australia is best seen in the trade returns, and especially in the figures relating to exports. In 1850 the total value of exports from Australia was £3,584,000; in 1856, when the gold production was at its height, the value was £21,794,000; in 1861 it was £23,166,607; and thereafter the figures showed a constant tendency to increase. The phrase that the gold discoveries "precipitated Australia into nationhood" is no poetic exaggeration, but an actual fact.

The progress made in railway construction during this period was far from satisfactory. The Governments of the different states were not wanting in enterprise, but it was difficult to obtain money at a rate of interest sufficiently low to warrant them in borrowing; and even if loans at moderate rates could be raised, the prospect of sufficient traffic being obtained to make the railways pay was not assured. In 1862 the length of line open for traffic was 368 miles, viz., 214 miles in Victoria, 98 miles in New South Wales, and 56 in South Australia.

Allusion has been made to the demand for land which set in after the more easily worked gold deposits had been exhausted and erstwhile gold-seekers were compelled to look round for other means of livelihood. The beginning of the sixties marks the inception of the agrarian legislation and agitation for cheap land that has persisted in every state to the present day. New South Wales led the way by passing a law, under the provisions of which land was obtainable by free selection before survey. Sir John Robertson's Land Act—the measure referred to—came into operation in 1861, and the new principle it initiated had lasting, if not immediately apparent, effect on the condition of the working classes, giving them opportunities for employment not previously open to them. The main principle of the measure, which did so much to assist recovery from the dead level of conditions that prevailed at the time, is embodied in the following clause:—"Any person may, upon any Land Office day, tender to the Land Agent for the district a written application for the conditional purchase of any such lands, not less than 40 acres nor more than 320 acres, at the price of 20s. per acre,

and may pay to such Land Agent a deposit of 25 per centum of the purchase money thereof. And, if no other application and deposit for the same land be tendered at the same time, such person shall be declared the conditional purchaser thereof at the price aforesaid."

The free selector of any portion of Crown lands had three years' credit for the payment of the remainder of his purchase-money. Should he, after that time, be unable or disinclined to make payment, liberty was granted him to defer instalments for an indefinite period on paying 5 per cent. interest per annum on the principal amount remaining unpaid. It was also provided that the purchaser of any area of land from 40 to 320 acres should be entitled to three times the extent of his purchase for grazing ground, so long as it should not be claimed by any other free selector. Certain conditions were imposed regarding residence, which came to be more honoured in the breach than in the observance.

No other state dealt so lavishly with its waste lands as did New South Wales. The amendments made by Victoria were more cautious, and it was not until 1869 that the principle of free selection, as in vogue in New South Wales, was adopted. The pressure of population from abroad was not so great in Tasmania, South Australia, and Western Australia as to compel agrarian legislation of a revolutionary character, and in each of these states the amendments in the law, though frequent, were such as to conserve the public estate. In the period under review Queensland was only beginning its career as an independent state, and having a vast territory to dispose of, which did not offer the same attractions as were offered by the southern provinces, its land legislation was marked by extreme liberality to the intending settler.

The period 1859-62 was peculiarly one of transition so far as wages were concerned; there were no recognised trade rates, and even in the same year there were occasional variations, sometimes as many as four in the daily wages of artisans. An example of this may be given for the year 1861. In that year the daily wages of masons working in Melbourne fell from 14s. in April to 13s. in July and 12s. in October, and the wages of bricklayers were, in the same months, 12s., 11s., and 10s. per day. Other trades were somewhat similarly affected. The following were the current wages in the closing months of the years named, in Melbourne and Sydney:—

Trade or Calling.	1860.		1861.		1862.	
	Melbourne	Sydney.	Melbourne	Sydney.	Melbourne	Sydney.
	s. d.	s. d.	s. d.	s. d.	s. d.	s. d.
Masons .....	14 0	11 6	12 0	10 0	10 0	10 0
Plasterers .....	11 0	10 6	10 0	11 0	8 0	10 0
Bricklayers .....	12 0	10 6	10 0	11 0	8 0	13 0
Carpenters .....	11 6	10 6	10 0	10 0	8 0	10 0
Blacksmiths .....	11 0	10 6	10 0	10 0	10 0	10 0
General Labourers .....	7 6	6 0	6 0	6 0	5 6	6 0
	per week.	per week.	per week.	per week.	per week.	per week.
General Servants (female)	10 0	8 6	11 0	9 0	12 0	10 0

The wages of female servants were in addition to board and lodging. The figures just given mark the transition from the high rates of the gold-discovery period to those payable under modern conditions. There was, naturally, considerable reluctance on the part of wage-earners to accept the new conditions, and there was considerable fluctuation in wages before a distinct understanding was arrived at between employers and employed.

The prices of commodities fell with the decline in wages, although not to so great an extent, but rents were adjusted to the new conditions. It is not easy to give average prices in each part of Australia at this period; for, although price lists are available, it is difficult, if not impossible, to be certain that the goods mentioned therein are identical with those quoted in similar lists for other places. Speaking generally, the prices of agricultural and dairy produce were lower in Melbourne than in Sydney; agricultural produce was also of lower price in Adelaide than in Sydney. Beef and mutton were cheaper in Sydney than elsewhere. Imported goods were, on the whole, of lower price in Melbourne than in the other capital cities—that is to say, in the retail shops,—the wholesale prices being much the same. The following are the average prices of some of the principal articles of consumption in the retail shops of Sydney during the year named:—

Article of Consumption.	1860.	1861.	1862.
	s. d.	s. d.	s. d.
Wheat, per bushel .....	8 0	6 6	7 0
Bread, 1st quality, per lb.....	0 3½	0 4	0 2½
Flour, " per lb.....	0 3½	0 3	0 3
Rice, per lb.....	0 5	0 4	2d. to 4d.
Oatmeal, per lb.....	0 6	0 6	0 5
Tea, per lb.....	2 3	2 4	1/6 to 2/6
Coffee, per lb.....	1 6	1 6	1/4 to 1/6
Meat, fresh, per lb.....	0 4	0 3	0 4
Butter, fresh, per lb.....	1 6	1 8	2 3
Cheese, English, per lb.....	1 6	1 7	1 6
Potatoes, per cwt.....	7 6	7 3	8 0

#### INDUSTRIAL PROGRESS—1863-1872.

During this period of Australia's history the industrial and social conditions now obtaining were gradually evolved. The El Dorado dreams of ten years before almost entirely faded from men's minds, and although large discoveries of gold were made both during this period and afterwards, the impulse towards gold-seeking never again became a dominating passion amongst any large class in the community. All the states had, owing to the increased demand for freehold land consequent upon the large influx of population at the time of the gold discoveries, altered their laws with the avowed object of affording men of small

means the opportunity of acquiring land on easy terms, and in the ten years following the passing of the Robertson Lands Acts 11,260,547 acres were disposed of by the six Australian states. Victoria sold 3,507,791 acres, New South Wales 3,969,273 acres, South Australia 2,250,552 acres, and Tasmania 542,061 acres.

It is interesting to note that, taking Australia as a whole, about one-eighth of the land sold by the states was placed under cultivation. The proportions, however, were very different in the different states. In Victoria, it was about one-seventh, in South Australia one-fourth, while in New South Wales it was less than one-thirtieth. These proportions give an indication of the lines upon which the states were progressing. Victoria and South Australia were becoming important agricultural communities, Tasmania was developing grazing and agriculture together, while New South Wales, neglecting agriculture, paid more and more attention to sheep-farming. Gold-mining still maintained a position of great importance in Victoria, but even in that state, at the middle of the period, the industry, measured by the value of its production, ranked below both agriculture and stock-rearing. In 1866 Queensland appears for the first time as a gold producer, and small quantities were obtained in South Australia and Tasmania. The value of the gold exported from Australia in 1859 was £10,382,725; in 1866 it had fallen to £7,108,667.

During this period the coal-mining industry of New South Wales was beginning to obtain some importance. In 1858 the quantity of coal raised barely exceeded 100,000 tons; in 1862 it reached about 300,000 tons; and from 1866 to the end of the period the quantity varied from 500,000 to 600,000 tons.

South Australia was helped very much by its copper industry. In the days preceding the gold discoveries the value of copper won did not fall far short of £400,000. The immediate effect of the gold discoveries, as already indicated, was to deprive South Australia of its able-bodied men, especially its miners. By 1854 the value of copper won had fallen below £100,000. With the subsidence of the first excitement of the gold discoveries, labour again returned to the province. In 1856 the output reached £400,000, and remained between that figure and £450,000 up to the year 1861. From 1861 onward the industry received considerable impetus, and the output in 1866 reached the large total of £824,000. Although the following years do not show so valuable a production, the output declining in 1868 to £624,000, the actual quantity of copper won had not diminished, the fall being due to a decline in the price of the metal.

The climatic conditions of the period in some of the states were not such as to encourage the progress of rural occupation. This was especially the case as regards New South Wales. The year 1862 was one of drought and bush fires. The drought persisted till February, 1863, and was succeeded by heavy rains which deluged the eastern portion of the continent. Floods were recorded from Rockhampton on

the north to Gippaland on the south, and in the Hawkesbury Valley the water rose 27 feet above its normal level. In New South Wales the floods were succeeded by a long spell of dry weather, which lasted into the opening month of 1865. Farmers petitioned the Government to be released from claims for seed-wheat advanced during the previous year; crops in many parts of the interior were totally destroyed by rust and drought, and in the north by continued rain—for floods were again submerging many districts,—and efforts were being made to provide accommodation for the houseless poor. The floods, which covered a period of six months, extending from February to July, caused rivers to overflow their banks, swept bridges away, and destroyed a vast amount of property. The year 1866 was normal as regards the seasons, but unsettled conditions again prevailed in 1867. In this year the floods were attended by loss of life as well as by destruction of property. Lines of railway were closed in consequence of the heavy rains, and public works in some districts were greatly damaged. The distress of the settlers who had been “washed out” called so loudly for relief that public meetings were held for the purpose of raising subscriptions. The Colonial Secretary and others hastened to the inundated districts with succour, and the butchers and bakers of Sydney sent meat and bread to those who had been rendered destitute. Dry weather supervened from October, 1867, to January, 1868, followed by heavy rains which inundated the valleys of the Hawkesbury and the Hunter. The year 1869 began with a severe drought, and the 13th February was proclaimed by the Government a day of humiliation and prayer for rain. The pastoral industry was severely affected, and the whole country suffered. In 1870 floods prevailed throughout the state; traffic was stopped and much property destroyed. A Flood Relief Committee was formed, and, notwithstanding the presence of many unemployed in Sydney, great efforts were made to send succour to the “washed-out” settlers. The month of November in this year was specially fraught with disaster from floods. The calendar was simply a record of inundations which were general throughout the state.

The effect of the vicissitudes of the seasons is seen in the returns of the acreage cropped in the states chiefly affected. In New South Wales, from 1861 to 1864 the increase of cultivation was barely 20,000 acres; there were large increases in the two succeeding years, but the area was not retained in cultivation, and the year 1871 showed less tillage than 1866. From 1861 to 1865 the seasons in Victoria were on the whole adverse to the farmer, but subsequent years up to the end of the period under review were distinctly favourable. Tasmania is not subject to adverse seasons, but from 1861 to 1865 the climatic conditions were such that no progress was made as regards area under crop. In Queensland little progress is observable up to 1865, in which year the area cropped did not exceed 15,000 acres. Contrary to the experience of the eastern states, South Australia enjoyed a succession of fair seasons, interrupted by a few that were exceptionally good, and the area devoted

to tillage made regular progress, being checked only in one year (1868) of the period between 1861 and 1871. As will be seen from the table in regard to acreage under crop, the position of South Australia was higher even than that of Victoria. The following is a statement of the area cropped in each state in the years named :—

Year.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Total. Commonwealth States
	acres.	acres.	acres.	acres.	acres.	acres.	acres.
1861	260,798	439,895	4,440	486,667	27,018	163,385	1,382,203
1866	451,225	592,915	24,433	739,714	43,159	167,866	2,019,312
1871	417,801	937,220	59,969	1,044,656	58,324	154,445	2,672,415

The progress of the sheep-breeding industry was continuous up to the year 1868, the seasons which proved so adverse to the farmer being, on the whole, favourable to the grazier; but from 1868 to 1871, which were good farming years, the seasons were against sheep rearing. The most important economic change observable in the period is the reversal of the positions of New South Wales and Victoria. In 1865 the number of sheep depastured in Victoria exceeded that of New South Wales by about three-quarters of a million; in 1871 the superiority was with the last-mentioned state to the extent of six and a quarter millions. The following is a statement of the numbers of sheep and cattle depastured in the years named :—

State.	Sheep.			Cattle.		
	1861.	1866.	1871.	1861.	1866.	1871.
New South Wales....	5,615,054	11,562,155	16,278,697	2,271,923	1,771,809	2,014,888
Victoria .....	6,239,258	8,883,139	10,002,381	628,092	598,968	799,509
Queensland .....	4,098,381	7,278,778	7,403,334	590,196	919,414	1,168,235
South Australia .....	3,038,356	3,911,600	4,412,055	265,434	123,890	143,463
Western Australia ..	279,576	481,040	670,999	33,795	41,323	49,593
Tasmania .....	1,714,498	1,722,304	1,305,489	87,114	88,870	101,540

In spite of the large fall in the gold returns, the exports of the states increased considerably during the period. There was a steady improvement in the quantity of wool and other pastoral produce exported, and the prices obtained were well sustained. Victoria held the first place in regard to the value of the trade, both of imports and exports, although at the end of the period its advantage over the mother state was very greatly reduced. It was in this period that Victoria adopted the policy of Protection, which, in subsequent years, it strictly adhered to, though that policy was not adopted without a severe legislative struggle. The

customs tariff of February, 1867, imposed duties on a number of articles with a view of affording protection to native industries, and four years later (May, 1871) the duties were increased upon many articles with the view of affording further protection.

The position of Melbourne at the end of the period under review was undoubtedly imposing. The population, 206,780, was far greater than that of any other city in Australia, its nearest rival, Sydney, having a population of only 137,776. But Melbourne's superiority was founded on a stronger basis than that of mere population. Early in the sixties the city became the financial centre of Australia. The enormous sums won at the gold-fields were poured into its banks, and filled their coffers to repletion, and fields for investment were eagerly sought after. The Riverina district of New South Wales first attracted attention, and speedily became the property of Melbourne residents, either absolutely or by way of mortgage. From New South Wales their enterprise extended to Queensland and across the sea to New Zealand, until Melbourne was without a rival in the field of Australian finance. The gradual working out of the gold-fields did not alter Melbourne's position. The gains derived from its investments, and the profits flowing to it as the financial centre of the continent, were greater even than those flowing from the gold-fields in the days of their highest production.

The position acquired by Melbourne was not at the expense of Sydney. It is true that the latter was the chief seat of Australian enterprise in the days preceding the gold discoveries; but it lost nothing by those discoveries, although its position was now second to Melbourne.

The climatic disturbances affecting New South Wales have been alluded to; but it must not be supposed that no progress was achieved during the period. Agriculture, it is true, made only slight advance, and no beginning had yet been made of manufacturing on a large scale, but the great pastoral industry had thriven, in spite of adverse seasons, and Sydney, on its part, had greatly benefited thereby. The stoppage of immigration was severely felt in some of the industries of the state, and immigration lecturers were sent to England to attract attention to the resources of New South Wales. There was, as is frequently the case in Australia, a demand for labourers in some pursuits in excess of the supply, while there was a dearth of employment in other branches of industry. All the trades connected with the pastoral industry were fully employed; those connected with the building industry, depending for their expansion upon an increase of population, were in a very different condition, especially in Sydney. In 1866 there was very keen distress amongst mechanics; and the Government of the state established relief works at Haslem's Creek, where considerable numbers of men were employed clearing and forming a large area to serve as a cemetery. Later in the same year rumours of rich gold discoveries in the Waddin Mountains attracted many of the workers away from the city, and so relieved the tension of the labour market. Queensland was troubled about the same time with a large



number of persons willing to work, for whom no employment was available; but the Queensland difficulty differed from that of New South Wales, both as to its origin and the class affected. The want of employment arose from a neglect of the ordinary canons of good government. It was the credit of the Government that was impaired, general business remaining unaffected. A brief description of the position of affairs at this period will be found in the historical sketch of Queensland in the early part of the volume for 1901-2. The persons who felt the crisis most acutely were the unskilled labourers discharged from public works by reason of the inability of the Government to pay its way. A return to the principles of sound finance, which of course was not accomplished in a moment, removed the cause of the crisis and with it the labour difficulty.

Wages for like employment were fairly level throughout Australia during the whole period, the tendency being for the rate for skilled tradesmen to fall to 8s. per day, and that for general labourers to 5s. per day. The following tables show the wages in some of the principal mechanical trades, and for day labourers and general servants, paid in 1861 and 1871 in the cities of Melbourne, Sydney, Adelaide, and Hobart. It will be seen that a considerable range is shown for most of the rates paid in Melbourne. There were two reasons for this: First, there was a greater range in the quality of the workmen than in the other cities; and, secondly, the Melbourne artisan resisted the inevitable fall in wages more strenuously than did his fellows in the other cities.

Class of Workers.	1861.				1871.			
	New South Wales.	Victoria.	South Australia.	Tasmania.	New South Wales.	Victoria.	South Australia.	Tasmania.
	s. d.	s. s.	s. d.	s. d.	s. d.	s. s.	s. d.	s. d.
Carpenters .....	10 0	8 to 10	9 0	7 0	8 6	8 to 10	8 0	6 6
Blacksmiths ...	10 0	8 to 12	10 0	9 6	8 6	8 to 10	8 0	6 6
Bricklayers .....	13 0	8 to 12	10 0	8 6	9 0	8 to 10	8 0	6 0
Masons .....	10 0	8 to 12	9 0	7 9	8 6	8 to 10	8 0	6 6
Day labourers ...	5 6	5/7	6 0	7 0	5 0	5/-	5 6	4 0

The lower rates shown for 1871 were not accepted without demur and meetings were held at various places to protest against the reduction in wages; but protests were unavailing when there were large numbers of qualified men unable to obtain employment even at the rates objected to.

The ratio of wages of female servants was well maintained during this period, the slight fall observable in 1866 being more than recovered. Farm labourers and shepherds suffered a slight reduction in wages towards the end of the period, as large numbers who had quitted their employment on the sheep and cattle stations for the gold-fields returned

to their former pursuits. The following are the weekly wages, the rates being in addition to board and lodging provided by the employers :—

	1861.		1866.		1871.	
	s.	d.	s.	d.	s.	d.
Farm labourers .....	13	0	11	6	10	9
Shepherds.....	13	0	13	0	11	9
Cooks (female).....	11	0	10	0	11	6
Housemaids.....	9	0	9	0	9	0
Laundresses.....	11	0	10	0	10	9
Nursemaids.....	8	0	7	0	8	0
General servants (female).....	10	0	9	0	9	0
Farm house-servants and dairywomen ...	8	6	9	0	9	0

The year 1861 is notable in labour matters, as witnessing a crucial stage in the agitation against the admission of the Chinese to Australia—an agitation which for many years has been an important factor in determining the trend of domestic and industrial legislation. The discovery of gold brought to Australian shores great numbers of these aliens. In 1852 they began to arrive, for prior to that year their presence, except at the seaports, was practically unknown. Victoria was the first place of settlement chosen by them. Although their number at the census of 1854 was not greater than 2,000, the local Legislature took alarm, and passed an Act limiting the number of Chinese to be brought into the country to one for every 10 tons of a vessel's cargo. Five other Acts were passed between 1855 and 1864, regulating the influx of these Asiatics. In 1856 the number in Australia was 26,000, and of these 24,000 were in Victoria, the rest being in New South Wales. In 1859 the Chinese inhabitants in New South Wales and Victoria numbered 37,000, or about  $4\frac{1}{2}$  per cent. of the population. The Chinese were almost wholly adult males, and if this number be compared with the adult male population of the two states it will be found that the proportion in the year named was not less than  $11\frac{1}{2}$  per cent. Victoria had the largest share of these aliens. In 1861 there were about 38,000 Chinese in New South Wales and Victoria, viz., 12,988 in the first-named, and 24,732 in the latter state. Thenceforward the Chinese population of Victoria rapidly declined, and the majority of those leaving crossed the Murray into New South Wales.

The arrival of Chinese was at no time viewed with equanimity by the whites; but with large numbers of disappointed gold-seekers in the country there was a growing feeling of resentment, and in 1861 matters in regard to this class of immigration reached a crisis. The gold-field opened up at Burrangong, in New South Wales, proved extraordinarily rich; a great rush set in to that place, and large crowds of the Chinese flocked to the diggings there. The miners received this influx of Asiatic fossickers with very bad grace, and convened a public meeting for the purpose of deciding whether "Burrangong was a European or a Chinese territory." They likewise addressed a petition to the Assembly, complaining of the swamping of the field by thousands of Chinese. This agitation against the alien miners resulted in continuous riotings. The unfortunate foreigners were ejected from their claims, their tents were

burned, and they were generally ill-used. The Government, determined to uphold order at any cost, despatched to the scene of the riots—a place called Lambing Flat—a mixed force of artillerymen, with two 12-lb. field-pieces, some men of the 12th Regiment, and some members of the mounted police force. The Premier, Mr. (afterwards Sir) Charles Cowper, also visited the field and addressed a monster meeting of the miners, sympathising with their grievances, but informing them that no redress could be obtained until riot and confusion had entirely ceased. When the Premier had returned to Sydney the excitement rapidly ceased. A new rush to a locality named Tipperary Gully lured away 6,000 miners from the scene of their former disputes, and the Chinese departed to other fields. Thus ended the first labour conflict between the Europeans and the Chinese, who from that date onward became a growing menace to the character of the settlement of the Australian States.

At the beginning of the period a Select Committee was appointed by the Parliament of New South Wales to inquire into and report upon the state of the manufacturing and agricultural industries. On the 12th December, 1862, this Committee brought up a report which stated that, from the evidence taken, it was shown that manufactures had not increased during twenty years; that many which had flourished in the past were not in existence; and that in consequence thousands of youths were wandering about the streets in a state of vagrancy, instead of learning some useful trade. This statement is, however, too sweeping to be accepted literally, and is not supported by any evidence of value. It may be taken, however, as indicating the popular opinion of the day, and perhaps as a tribute to the superior condition of affairs on the Victorian side of the Murray and in South Australia. The slight progress made in agriculture in New South Wales, and the more rapid development of Victoria and South Australia, have already been noticed. In regard to manufactures, none of the states could claim a strong position. If there were nothing else against the manufacturers, there was the absence of a local demand for the products, without which the maintenance of industries in their early stages is always difficult, and sometimes impossible. Owing to the imperfection of the statistics it is impossible to speak with exactness of the amount of employment afforded by the manufacturing industries of 1861. So far as the records now existing enable an estimate to be made, the persons employed in the year 1862, in what are now classified as manufacturing industries, were:—

New South Wales.....	12,225
Victoria .....	6,405
Queensland.....	4,966
South Australia.....	5,066
Western Australia .....	373
Tasmania.....	3,372

The chief industries in New South Wales were the grinding or dressing of grain, sugar-making, distilling, and boat-building. In

Victoria, flour and grain mills gave employment to 552 persons, no other industries being on a like scale. In 1871 a very considerable change is observable. Victoria is no longer a minor state, and as regards manufactures it is in every important respect superior to New South Wales. It is still difficult to speak with certainty as to the number of persons employed, but the following may be taken as a fair approximation:—

New South Wales	...	...	...	...	13,583
Victoria	...	...	...	...	19,569
Queensland	...	...	...	...	5,518
South Australia	...	...	...	...	5,629
Western Australia	...	...	...	...	414
Tasmania	...	...	...	...	3,747

In Victoria the largest employment was afforded by breweries, clothing factories, saw-mills and joinery works, boot factories, tanneries, iron foundries and engineering establishments, and potteries and brick-works; but there were many others of growing importance. In New South Wales the industries on the largest scale were tobacco factories, sugar-mills, tanneries, brick-works, saw-mills, iron foundries and engineering establishments, clothing factories, flour-mills, and coach-building establishments. The state of the industries throughout Australia cannot, however, be gauged from a mere enumeration of hands employed. Most of the industries were on a small scale. In the four less populous states, the average number of hands to each establishment was not more than three or four, and only in the capital cities was there a considerable employment of machinery.

The prices of the principal articles of consumption were greatly reduced in this period as compared with those of previous years following the gold discoveries; rents also showed a great reduction. Taking the seven articles in common use, prices for which have been given for other periods, the following were the averages for Sydney:—

## RETAIL PRICES IN SYDNEY.

Year.	Bread per 2 lb. loaf.	Rice per lb.	Beef per lb.	Sugar per lb.	Beer (Col.) per gal.	Butter per lb.	Potatoes per cwt.
	d.	d.	d.	d.	s. d.	s. d.	s. d.
1859	6	4½	4	5	4 0	1 10	8 0
1860	6½	5	4	5½	3 6	1 6	7 6
1861	6½	4	3	5½	3 6	1 8	7 3
1862	4½	3	4½	4½	2 0	2 3	8 0
1863	4	3	4½	4½	1 6	1 6	7 0
1864	5½	3	4	4½	2 0	1 6	5 0
1865	7½	3	3	4½	2 0	1 9	8 0
1866	6½	4	3	4	2 0	1 3	6 0
1867	3½	3½	2½	4	1 6	1 6	7 0
1868	4	4	3½	4	2 0	1 3	9 0
1869	3½	3	2	4	1 4	1 6	4 0
1870	3½	3	3½	4	1 4	1 3	5 0
1871	3½	2½	2½	4	2 3	1 3	4 0

The prices stated above are for articles of good quality. Cheaper articles of low quality went into consumption, but not to any very considerable extent. Bread, for example, was retailed in some places at one penny per loaf less than quoted, while low grade sugar was also retailed at about one penny per pound less than shown. The same remarks apply to the following statement of prices for Melbourne during the same period. The figures in most cases are approximate, as it is difficult in dealing with prices to determine if the quality of the articles is the same in each year compared. Further, it must be understood that the prices given have reference to the total quantity entering into consumption. In some years there was an extraordinary range in the figures quoted. Thus, in 1859, potatoes sold at 37s. 4d. per cwt., and in 1860 at 32s. 8d. per cwt. for a short period; but it is probable that very little entered into consumption at these prices, especially as bread was, weight for weight, much cheaper.

## RETAIL PRICES IN MELBOURNE.

Year.	Bread per 2 lb. loaf.	Rice per lb.	Beef per lb.	Sugar per lb.	Fresh Butter per lb.	Potatoes per cwt.
	d.	d.	d.	d.	s. d.	s. d.
1859	7	4	7 to 10	4½	2 10	9 4
1860	6	3½	4½ „ 6	4	2 6	9 4
1861	5	3½	3½ „ 4½	4	1 6	9 4
1862	4	3½	3 „ 6	4½	2 3	4 8
1863	4	3½	4 „ 7	4½	2 6	9 4
1864	6	3½	4 „ 6½	4½	1 3	4 8
1865	6	3½	4 „ 9	5½	3 0	4 8
1866	4½	3½	4 „ 9	5½	3 0	4 8
1867	4½	4	2 „ 7	4½	1 8	4 8
1868	5	3½	2 „ 6½	4½	1 7	9 4
1869	4½	3½	3 „ 7	4½	2 2	10 0
1870	3½	3½	3 „ 6	4½	1 9	4 8
1871	3½	3½	4 „ 8	4½	0 10	8 2

The prices of commodities in the Adelaide market were, on the whole, less than in Melbourne, but wages ruled higher in the latter city, although, as affairs became settled after the gold rushes had subsided, prices tended to become level in the great centres of population. Bread was usually cheaper in Adelaide than elsewhere, and meat cheaper in Sydney, while potatoes and other vegetables, as well as butter and cheese, were, towards the end of the period under review, of less price in Melbourne. Imported goods varied in price with the duties payable; nevertheless importers continued to keep a semblance of equality in quotations in the various cities by adapting the quality of the goods to the prices obtainable.

The following statement refers to Adelaide:—

RETAIL PRICES IN ADELAIDE.

Year.	Bread per 2 lb. loaf.	Rice per lb.	Beef per lb.	Sugar per lb.	Fresh Butter per lb.	Potatoes per cwt.
	d.	d.	d.	d.	s. d.	s. d.
1859	6	3	5½	5	2 1	8 10
1860	5½	3	6	5	1 8	8 9
1861	3½	3	4½	5	0 11	6 0
1862	3½	3	4½	5	1 0	8 0
1863	3½	3	4½	5	1 0	10 0
1864	5	3	5	5	1 0	7 3
1865	5	3	7½	5	1 8	8 0
1866	4	3	7½	5	2 1	7 10
1867	3	3	4½	5	1 1	5 8
1868	4½	3	3½	5	1 3	5 0
1869	3½	3	4	5	1 6	8 3
1870	4	3	5	5	1 0	4 9
1871	3½	3	4	5	0 10	3 10

The monetary position during the period was very peculiar. Up to 1861 interest allowed on deposits for twelve months by the banks was 5 per cent. In the year named the rate was reduced to 4 per cent., and remained unchanged until 1865, when it was increased to 6 per cent. for some and 6½ per cent. for other banks, private companies offering as much as 7 per cent. These high rates continued till August, 1867, when the interest fell to 5 per cent., and during the following year was reduced by successive stages to 3½ per cent. In the succeeding year the rate was increased, first to 4½ per cent. and then to 5 per cent., at which figure it remained until 1871, when there was again a reduction to 4 per cent.

The money market was much disturbed owing to the necessities of some of the state Governments. There was a large amount of New Zealand Government debentures bearing interest at 8 per cent. on sale in Sydney, and the New South Wales Government was so pressed for money that, at one time, it found itself compelled to place its 5 per cent. debentures at £70 per £100 of stock, allowing for redemption in twenty-eight years at par. This was equal to paying nearly 7½ per cent. interest.

The Governments of several of the states favoured the policy of assisted immigration, and during the ten years 1861–1870, 135,702 persons arrived in Australia, wholly or partly at the public expense. Of these, 18,165 came to New South Wales, 46,594 to Victoria, 56,586 to Queensland, 13,730 to South Australia, and 627 to Tasmania. The total accession of population from abroad during the same period was 173,277, viz., 68,191 to Queensland, 45,539 to New South Wales, 38,935 to Victoria, 17,949 to South Australia, and 5,891 to Western Australia; Tasmania, however, lost 3,228 persons by emigration. Though the country badly needed opening up, little progress was made during this period in railway extension, the average length of line opened being rather less than 80 miles a year.

During this period business was very much disturbed in New South Wales owing to the depredations of the bushrangers. From 1860 to 1870 was the great bushranging epoch in the state's history, which memorised such unworthy names as those of Frank Gardiner, the Clarkes, Dunn, Johnnie Gilbert, Ben Hall, Morgan, Power, "Thunderbolt," and O'Malley. The existence of this dangerous bushranging pest was a source of keen embarrassment to the Government, and a standing challenge to every Ministry which accepted office.

#### INDUSTRIAL PERIOD—1872-1893.

The twenty-two years from 1872 to 1893 do not call for such lengthened notice as former epochs, inasmuch as the statistics to be found in various parts of this volume give a detailed illustration of the progress made during the period. The preceding period had closed somewhat tamely. Population was not being attracted in any great numbers; the demand for land was not by any means so great as might have been expected from a consideration of the facilities afforded for its purchase, nor was there any extensive cultivation upon the land which was bought. The efforts that were made for the development of the country were not well sustained, except, perhaps, in Victoria, while railway construction was almost suspended. Expenditure by the Government on public works, either from revenue or from the proceeds of loans, was small, while little private capital found its way to the country. In such circumstances the industrial condition could not be said to have been hopeful. Nevertheless, causes were at work which were to affect materially the progress of Australia, especially of the eastern states.

The great discoveries of gold during the early fifties had given strength to the opinion that mining would speedily and permanently oust pastoral pursuits from the first position amongst the industries of the country. This expectation was soon disproved. From 1872 to 1893 the position of Australia as a gold-producing country greatly declined. In Victoria, the chief producer, the yield of the precious metal fell away from over £5,000,000, at the beginning of the period, to a little over £2,300,000 towards its close. In New South Wales the industry, which seemed very promising in 1872, in which year it yielded £1,644,000, fell away to less than one-fifth of that quantity in 1888. Queensland, on the other hand, began to display the richness of its gold mines. In 1872 the mines of that state already showed the respectable yield of £500,000; this was rapidly increased, and in 1878 the value of gold obtained exceeded a million sterling, and ten years later it was two and a half millions. This satisfactory condition of things was due to large discoveries of the precious metal at Rockhampton and Gympie, and subsequently to the wonderful deposits found at Mount Morgan. Tasmania could scarcely be called a gold-producing country at the beginning of this period; but in 1877 the famous quartz reef, afterwards worked by the Tasmanian Gold Mining Company, was

discovered, and in 1879 the yield reached a quarter of a million sterling, and, although it fell away in subsequent years, the discovery was most opportune. The gold discoveries in Western Australia do not belong to this period, but the long-accepted dictum that the country was without minerals was fully disproved, and in 1893, the year which closes the epoch under review, the gold won was valued at £421,000.

The chief coal-fields in the vicinity of Newcastle, New South Wales, yielded in 1872 about 1,000,000 tons; this was increased in 1891 to over 4,000,000 tons; and as 370 tons represents the employment of one man in or about the mines, the benefit of the additional output may be estimated. Queensland, Victoria, and Tasmania also began during the period to open up their coal-fields, but the value of the combined output of the three states, in 1893, was under £200,000.

Valuable deposits of other minerals were also worked to a considerable extent. In New South Wales, tin and copper were mined for during the whole period, the greatest value of production being £568,000 for tin in 1881, and £473,000 for copper in 1883. The quantity of these metals obtained was largely influenced by the weather conditions, which in some years were most unfavourable, while the extraordinary fluctuations in the price of the metals in the European markets also adversely affected their production.

Mining for silver became an important industry in New South Wales in 1885, and for the following year the yield of silver and lead, the two metals being found in conjunction, was about half a million sterling; in 1891 the value of the output was £3,600,000, and in 1893 it was still over £3,000,000.

In South Australia, copper-mining was an important industry, and added much to the wealth of the state, although towards the close of the period the output was greatly diminished, chiefly through labour disturbances. Queensland produced large quantities of tin and copper in the earlier years, but towards the end of the period, both metals being affected by a fall in price, the output, especially of copper, was considerably smaller. In Tasmania, there was an opportune discovery of tin at Mount Bischoff in 1871, when the island stood badly in need of an impetus to trade, and this important find marks the beginning of a new era in the mining and industrial history of the state. The discovery of gold in Tasmania has already been alluded to. Valuable lodes of silver-lead and copper were found in the western parts of the island, notably silver-lead at Mount Zeehan in 1885, gold and copper at Mount Lyell in 1886, and silver and lead at Heazlewood in 1887.

Taking Australia as a whole, agriculture made great progress from 1873 onwards. In 1872 the area under crop, exclusive of that devoted to grass, was 2,491,023 acres; in 1880 this had been increased to 4,583,894 acres; in 1890 to 5,430,221 acres. Of the larger states, the least progress was made by New South Wales, if progress be measured by acres under crop. In the ten years, from 1872 to 1882, the breadth of land devoted to the plough was increased by 247,689 acres, as



compared with 709,479 acres in Victoria, and 1,267,482 acres in South Australia. The smallness of the population in Western Australia precluded any attempt at cultivation on a large scale, while Tasmania, with its small home market, and entrance barred to the markets across the straits, made very little progress, the area under crop in 1893 being only 179,000 acres, as compared with 156,000 acres twenty years previously. So early as 1852, South Australia had produced sufficient wheat for its own requirements, and was exporting its surplus, part to Great Britain, and part to New South Wales and other states with deficient production, while, so far as foodstuffs were concerned, Victoria also became independent of outside assistance in 1877. The value of the country's production, however, is not to be estimated merely by the acreage under crop. The maize and sugar crops of New South Wales, estimated by their yield, would represent four times their area in wheat land. A more exact idea of the condition of the agricultural industry may be obtained from the figures relating to the value of production. Judged by this standard, the production of Victoria stood easily first during the whole period, while New South Wales and South Australia, with almost equal values, were second and third. In 1871 the return from agriculture in the Commonwealth States was £8,941,000, equivalent to £5 7s. 2d. per inhabitant; in 1881 the value had increased to £15,519,000, or £6 17s. 9d. per inhabitant; while in 1891 the production reached £16,480,000, or £5 3s. 6d. per inhabitant. This satisfactory result was obtained in spite of a fall of about one-third in the prices of agricultural products. Further details in regard to agriculture will be found in the chapter dealing specifically with this question.

When the development of the pastoral industry during this period is considered, it will be readily understood how it happened that certain states, well fitted for agriculture, showed comparatively little progress in the breadth of land brought under tillage. Leaving aside for the present the question of prices, and considering only the volume of production, it will be found that this period was the one, of all others, most favourable to the pastoral industry. Taking Australia as a whole, the following figures, giving the number of cattle and sheep and the weight of the wool clip at various periods, illustrate the position of the industry :—

Year.	Cattle.	Sheep.	Wool.
	No.	No.	lb.
1871	4,277,223	40,072,955	211,413,500
1881	8,010,991	65,078,341	324,286,100
1891	11,029,499	106,419,751	543,495,800
1893	11,546,823	99,799,759	601,083,000

The favourable position of the pastoral industry was maintained almost throughout the period in spite of a considerable fall in the prices

of the staple articles of production. This was especially the case in New South Wales and Queensland. In New South Wales the wool-clip in 1871 weighed about 74,000,000 lb.; in 1892 it was nearly five times that weight. In Queensland the chief interest was cattle-grazing, and the number of cattle increased nearly sixfold in twenty years—that is to say, from 1,168,000 in 1871 to 6,192,000 in 1891. The first check to this prosperous state of affairs was brought about by the fall in prices. High prices for all classes of local produce obtained in 1875; but from that year to 1877 there was a reduction equal to about 14 per cent. Nevertheless, at the reduced prices the industry was highly profitable, especially as the flocks tended to increase largely in numbers. Good prices prevailed until 1884, but there was a further fall of 16 per cent. in the ensuing two years. In 1886 the country began to feel the effects of price reduction, which almost counterbalanced the larger returns due to the increase in the number of stock depastured. From 1886 to 1890 prices continued with little change, but from 1890 to 1894 there was a steady decline, the fall in the four years being equal to 30 per cent. During the nineteen years, 1875 to 1894, the total decline was equivalent to 49 per cent., and affected all descriptions of pastoral products; and as there was no corresponding reduction in the cost of production, and little in the cost of transport, the reduced prices proved a very severe blow to the staple industry of the country.

The various manufacturing industries prospered over the greater portion of this period. The number of hands employed in Victoria in 1873 was 24,495; in 1880 the number had increased to 38,141; in 1885 to 49,297; and in 1889 to 57,432. This was the year of greatest prosperity in Victoria. Thenceforward the manufacturing industry greatly declined, and in 1893 the number of hands employed was 39,473, or no greater than in the year 1883. In New South Wales, also, there was considerable impetus given to the manufacturing industry, which in 1889 gave employment to 45,564 persons; but, influenced by the same causes that affected Victoria, the number of persons employed fell away in 1893 to 38,918.

In the earlier years of the period the expenditure of borrowed money by the states was very moderate; but as money became easier to obtain in the London markets, the various Governments availed themselves of their opportunities to the fullest extent. The public debt of New South Wales in 1871 stood at about 10½ millions; in 1881 it was still below 17 millions; from 1881 to 1891 it rose to 53 millions, showing an increase of 36 millions in ten years. During the greater part of this period New South Wales had an abundantly large land revenue, which was expended for current purposes; this, added to a huge loan expenditure, rarely less than £4,000,000 a year, gave the state a predominating influence in the labour market of the continent.

In Victoria there was much the same condition of affairs, except that the Government had not any considerable revenue from the sale of its

public lands. In 1871 the public debt in Victoria stood at 12 millions; in 1881 at 22½ millions, and in 1891 at 43½ millions. In some years, considering the number of the population, the loan expenditure was prodigious, although never on so lavish a scale as in New South Wales. The largest outpouring in any one year from loan funds was in 1890, when £4,134,000 was expended. Queensland also indulged in borrowing on a scale much beyond its requirements. From 1872 to 1882 the expenditure from loan funds was nearly £900,000 a year. From 1882 to 1892 it averaged between one and two millions. In South Australia the state expenditure from loans during the period 1872 to 1892 was scarcely ever less than one million a year, in some years rising to as much as 1½ million. Western Australia was the only state in which the loan expenditure was kept within reasonable proportions, its total debt in 1891 being only £1,613,000. In Tasmania, from 1880 to 1890, 4½ millions was added to the public debt, expenditure slackening off after 1891.

In the eastern states the year 1892 was the first to show a restricted loan expenditure, the total for the five states, which in 1889 had been over 11 millions, and in 1890 about 10 millions, falling to less than 3 millions—equivalent to a shrinkage of at least 7 millions. This sudden contraction of expenditure had a most serious effect upon the labour market, and at least 40,000 men, accustomed to look to the Government or to contractors working under the Government for their employment, were thrown upon the labour market, which immediately became disorganised. Indeed, so far as New South Wales was concerned, the labour market was disorganised even in 1888, a state of affairs which did not altogether result from the cessation of expenditure on public works. Large numbers of persons had been attracted from the other states by the extravagant expenditure and vigorous immigration policy of preceding years, and on the Government reducing their expenditure from extravagance to moderation, thereby involving a decrease of about three millions sterling, some 15,000 men were left without employment. To mitigate the distress consequent upon the inability of the community to absorb so much labour thus thrust upon it, the Government started relief works, still further attracting the unemployed to the vicinity of Sydney, and an expenditure of nearly £400,000 was incurred upon useless works before they were abandoned.

As affecting the industrial condition of the country, the importation of private capital for investment, in addition to that brought by persons taking up their abode in the state, was almost as important as the introduction of money by the various state Governments and by the local governing bodies. During the twenty-two years under review, the amount of private capital sent to New South Wales for investment, in excess of what was withdrawn, amounted to some 19 millions, and the money brought by persons coming to the country was over 23 millions. The bulk of the capital sent for investment came within the five years 1886–1890, and with the assistance of what was expended by the state

during the same period and the preceding one, helped to bring about the industrial inflation so characteristic of those years. The investments made during 1871-1885 in Victoria by persons outside that state were very moderate in their amounts, and were probably not greater than the investments of Victorians in other states. During the years 1886-1890, entirely different conditions prevailed. In the short period of five years the private capital introduced or withdrawn from investments outside the state exceeded £31,500,000—a prodigious sum when the population of the state is considered; and when it is remembered that during the same five years the borrowings of the state Government and of the local bodies exceeded 17 millions, it is easy to understand the extraordinary inflation which arose, especially in Melbourne and the surrounding district. Every branch of industry was affected by the large amounts of capital available in the Melbourne market, and wages, rent, and the price of land reached very high figures. Speculation was carried on to the point where it became gambling, and all classes of real property assumed fictitious values. As illustrative of this, it may be mentioned that the rental value of Melbourne and suburbs during the boom period was £6,815,315, which became reduced when the boom collapsed in 1893 to £5,847,079. In Sydney the inflation brought rental values of the metropolitan district to £6,067,882, which was reduced by the year 1897 to £5,022,910. All the states except Western Australia and South Australia were the recipients of the attention of the British investor. Queensland received nearly nine millions of private capital in the five years 1881-85, large investments being also made in the immediately preceding quinquennial period. From 1885 onwards, however, there was a tendency in Queensland to withdraw capital. Tasmania received about one million pounds during the five years 1871-1875 for investment on private account, and in the subsequent five-yearly periods the amount invested varied between £400,000 and £500,000. These sums were not larger than the island state could readily absorb. There can be no doubt whatever that during many years Australia received more capital, both public and private, than could be legitimately utilised, and no small portion of it was necessarily devoted to purposes purely speculative. Many persons became suddenly rich by land speculation; on the other hand, as the land which they sold had a productive value far short of the interest represented by the purchase money, many of the purchasers, of whom there were thousands, became embarrassed, and it was some years before they could free themselves from their difficulties. The financial institutions, which had greatly assisted to promote the speculations, became involved also, and by the failure of their customers to redeem mortgages, these institutions, including several of the banks, became the possessors of a large amount of property on which advances had been made beyond all possibility of recovery. There was, however, an evil of greater consequence than the temporary inflation of values. It will be readily conceived that the introduction of capital within the limits of absorption,

and the application of it to productive purposes, are conducive to true progress ; while, on the contrary, the over-introduction of capital, however applied, means arrest of progress. An example of this may be taken from the history of New South Wales during this period. Of the twenty-two years comprising this industrial period, 1885 and 1886 witnessed the largest introduction of capital, namely, £11,470,000 in the former, and £10,028,000 in the latter year. It is therefore not astonishing to find that the value of domestic produce exported in those two years, when compared with the population, was less than in any other period since the discovery of gold. It must not, however, be supposed that the money introduced by the state or by private persons was to any large extent absolutely wasted. The states carried out many public works of a remunerative character and highly beneficial to the community generally, and the foundations of many important industries were laid by private enterprise during the period. It is true many private investors suffered great loss by the fall in prices which subsequently occurred, but this was a private evil and not a national one. The most detrimental effect produced by the "boom," as it is called, was the withdrawal of large bodies of men from productive pursuits and the derangement in the labour market which immediately ensued.

An interesting discussion has been raised as to the effect of the import of capital on the productive enterprises of the country, and a close study of the question undoubtedly supports the opinion that although Australia is capable of absorbing yearly a certain amount of capital to the advantage of the Commonwealth and of persons who make the investment, the amount is strictly limited, and has been frequently over-passed. It will be seen from the facts set out in the chapter relating to Private Property and Incomes that, in some years, the various state Governments have hardly set bounds to the importation of money to forward their state enterprises, while the importation of capital on private account has also been, at times, unduly large. If the figures in the different parts of this volume be brought together, it will be clear that the years in which an undue importation of capital took place compare unfavourably as regards production with years in which there was a more moderate import, and that the lowest point of production was reached in the years when the largest amount of capital was brought to the country, and the highest in those years in which a very reduced amount reached these shores.

Although New South Wales cannot be regarded as the worst example of over-importation of money, its experience may be taken as typical of Australia. Going back thirty years, it will be seen that from 1870 to 1881 there was a gradual increase in the area of land devoted to the plough. During this period, the annual importation of capital on public and private account was about £1,500,000 per annum, and although it must be confessed that, in some years, especially towards the close of the period, more money was brought to the country than

could be conveniently absorbed, this was the exception and not the rule. During the whole period fair progress was made in rural pursuits, and in 1882 the area under crop was 660,000 acres. For the ensuing ten years the importation of capital averaged about £5,120,000 per annum, a prodigious sum considering the population of the state at that period ranged from 750,000 to about 1,000,000 persons. There can be no question but that £51,200,000 in ten years was more than New South Wales could conveniently absorb, and although there was a considerable increase of population the immigrants did not find employment in rural pursuits to any large extent, while many men engaged in farming and grazing were enticed from these primary industries to railway construction and works connected with city industries. The consequence is reflected in the returns relating to agriculture, for at the end of the ten years, the breadth of land devoted to crops had increased to 846,000 acres, that is by 186,000 acres or 28 per cent., which must be regarded as a very insignificant result, seeing that in the interval the land sales were enormous, and population had increased nearly 50 per cent. For the year 1892 there was a falling off in the importation of money, and the bank crisis of 1893 put a stop to the importation of capital on private account, although the Government continued to borrow moderate sums until the year 1899. Taking the eight years from 1892 to 1899, the importation of capital of all kinds fell to an average of £1,300,000 per year, a sum well within the absorbing capacity of the country, while the breadth of land devoted to crops was increased three-fold. The year 1899 showed a total area of 2,439,000 acres under the plough, which is the maximum area that the state can show. Since 1899, there has been considerable borrowing by the state Government, and agriculture has slightly retrogressed; this is partly due to the adverse character of the seasons, but also, it must be confessed, to the alluring effect that an expansive public works policy has had on the minds of persons engaged in agricultural industries. Nor does the curtailment of expenditure have the effect of sending workers back to the land, for the common experience of Australia is, that men who have been enticed away from rural industries to the towns evidence great reluctance in returning to their former pursuits.

From the point of view of wages and cost of living, the greater part of this period was an extremely prosperous one, improving year by year from 1872 onwards. At no period, except in the five golden years, 1853-7, were wages so high, and at no previous period was the purchasing power of money so great. The tide of improvement reached its highest level just before 1885, and in 1886 the signs of a reaction were visible. This was unfortunately coincident with the fall in prices already spoken of. The profits of capital became reduced and employers immediately attempted to reduce wages. In 1886 and the five years following, many strikes and trade disputes occurred. In New South Wales, in 1886-87, work in some of the southern district collieries was suspended for nearly twelve months by strikes and disputes; in 1888 the coal

miners in the northern districts were on strike for several months ; and in 1888 and 1889 the completion of various large public works threw out of employment some 12,000 men—no inconsiderable proportion of the unskilled labour of the country. In 1890 the maritime and pastoral industries were disturbed by strikes and disputes, very hurtful to the community in general and the working class in particular ; and in 1892 another disastrous strike occurred, causing the silver-mines at Broken Hill to remain idle for nearly three months.

The bulk of the production of Australia is for export, and a very small proportion of the produce of the pastoral industry, with the exception of meat, is consumed in the country. The mineral products are also almost entirely exported, and there is a surplus production of bread stuffs. The prices, therefore, which the Australian producer can obtain for his produce are determined by prices and conditions in Europe or America, over which he can exercise little or no control. As a consequence, with a fall in prices of staple produce, employers almost invariably seek to balance their accounts by a reduction in wages ; and under existing conditions it is practically necessary, if production is to continue, that the employees' wages should fall with the prices obtained for the commodity produced. In 1891 and the following years, Australia as a whole was face to face with a falling off in the quantity of production, and a decline in prices. The wage-earners were slow to concede the necessity of wages sharing in the general decline, and this was the root difficulty which caused the labour troubles preceding the crisis of 1893. It has been attempted in some quarters to fix upon the Labourers' Unions the responsibility for the events of that year. When it is remembered that the country was entirely over-capitalised, that land values had risen exorbitantly in the principal cities, and that the banks and financial institutions were largely concerned in maintaining the position of speculators, and were themselves, contrary to the spirit of the law and of their charters, the holders, either as mortgagees in possession or directly, of large squattages and landed properties in the cities and towns, it is easy to conceive that if the working classes had obediently acquiesced in all the demands for a reduction of wages, the crisis would still have happened. In the light of subsequent events, it must be confessed that the crisis was by no means the disaster which has been pictured. On the contrary, as will be seen from other parts of this volume dealing with the progress of production, all the producing interests of the state can look back to this time as a period of general awakening, and general production has made far greater progress since 1893 than ever before, in spite of adverse seasons and persistently low prices.

The flourishing condition of the pastoral industry throughout the greater portion of this period gave a marked impetus to the export trade. In 1872 the total value of the exports of the six states amounted to £32,212,000 ; this was an extremely large showing for a population of only 1,708,502. In 1875 the value of exports had grown to

£38,704,000, representing £20 11s. 3d. per head of population; in 1880 it reached £42,671,000 or £19 6s. 8d. per head of population; in 1885 it was £44,722,000 or £16 15s. 1d. per head; and in 1891 the total reached the enormous figure of £63,138,800, which is equivalent to £19 14s. per head of the population. These figures of course include re-exports and interstate trade; but when every allowance is made on these accounts it will still be found that the production of Australia, as measured by its exports, compared very favourably with that of any country in the world. The year 1891 represented the summit of Australian trade up to that time. In the following year there was a considerable falling off. This, however, was due more to the decline in prices than to any failure in production. The imports into Australia represent the return for the exports in addition to the proceeds of loans raised by the states and the investments made by foreign capitalists, less the interest and earnings of investments held by persons living outside its boundaries. The value of the imports fluctuates considerably, and in years of heavy borrowing shows very large figures; thus, in 1885 the imports exceeded the exports by £11,179,000, in 1889 by £9,305,000, and similarly in respect to other years.

After a long period of neglect the Governments of the various states began in 1873 to attend to the expansion of their railways. In 1873 the mileage in operation was 1,122; in 1874 it had risen to 1,346, and from this time onwards progress was rapid. Within four years the mileage open for traffic was doubled, and in ten years was quadrupled, the mileage in 1884 amounting to 5,694; and by the end of the period under consideration—that is, the year 1893—the length open for traffic exceeded 10,300 miles.

The expansion of general business during the same period may be gauged with considerable accuracy from the extension of the banking facilities. During the twenty-two years under review, banks were opened in every important centre of Australia, and it is estimated that in 1893 there was one bank or branch in operation for every 3,000 of the population. The deposits in 1872 were 23 millions; in three years they had increased 50 per cent; in seven years they had doubled; and in eleven years the increase was threefold—that is to say, in 1884 the sum on deposit reached £69,936,000. In 1891 the business of the banks reached its highest point, and the amount of money deposited was, in round numbers, 100 millions, equivalent to £31 4s. 2d. per head of population. This enormous sum, however, was not derived wholly from the Australian people, as large amounts were obtained in the United Kingdom and transmitted to Australia for investment. After 1891 the banking business slackened off, and in 1893 the great financial crisis occurred, of which mention has been made so frequently, and was accompanied by a very large withdrawal of deposits, chiefly by persons resident in the United Kingdom. In 1895 the amount on deposit was reduced to 86 millions, which included a considerable sum, estimated at about 54 millions, locked up in reconstructed banks. The



crisis of 1893 involved the suspension of thirteen banks, of which six had their head-quarters in Victoria, two in New South Wales, three in Queensland, and two in London. Coincident with the increase in the money placed with the banks of issue was a very large increase in the deposits in the Savings or people's banks. In 1872, the sum on deposit was £3,810,000; in 1880 it had risen to £5,867,000; in 1885 to £10,199,000; and in 1891 to £15,477,000. From this point it leaped to £18,100,000 in 1893, but the increase was not entirely due to working class deposits, as it represented to some extent money withdrawn from the banks of issue at the time of the crisis. At the highest point in the period, namely, the year 1893, the total deposits represented £5 9s. 5d. per inhabitant; and although this figure has since been greatly exceeded, it was considered at the time, and justly so, a tribute to the earning capacity of the Australian working population and an index of its material condition.

During the twenty-two years from 1872 to 1893 the population of Australia was practically doubled. The greater portion of the increase was due to births, the excess of persons arriving over those departing, though important in some of the states, being not very considerable for Australia, taken as a whole. Several of the states, notably New South Wales and Queensland, maintained the policy of assisted immigration during the larger portion of this term, and in New South Wales alone nearly 50,000 persons were introduced in the ten years preceding 1886, and in Queensland the average number per annum brought to the country at the public expense from 1873 to 1892 was 9,746. Various important changes took place in the positions of the states in regard to population. During nearly the whole of this period Victoria had the premier position, but at the close of 1891 New South Wales took the lead and South Australia yielded the third place to Queensland in 1884. Western Australia was still far in the rear. Established before any of the other states except New South Wales and Tasmania, the population of this huge province did not in 1893 amount to more than 65,000—a condition of affairs due almost entirely to its isolation and the absence of mineral discoveries. Western Australia was on the eve of reaping great benefits from its gold discoveries, but the record of these and of the great influx of population which resulted therefrom belongs to the succeeding period.

It is impossible within the limits of this chapter to give a statement of the wages paid in all industries, or even in the leading industries of the various states. The illustrations given are therefore confined to the rates paid in certain well-known trades, and these it is thought will indicate sufficiently well the general condition of wages in the other trades. In considering these examples it should be remembered that wages in Australia do not always indicate the condition of the productive industries of the country; and especially is this the case when, as from 1882 to 1889, the Governments of the states are large borrowers and large employers of labour. Wages, generally speaking, rose rapidly

after 1872, and reached a high level in 1874, thenceforward remaining stationary till 1883, when there was a distinct rise, and continuing fairly level at the advanced rates until 1889. From a labour point of view, these seven years may be considered amongst the best Australia has experienced. During this period carpenters received 11s. a day in Sydney, and from 10s. to 12s. in Melbourne; blacksmiths from 10s. to 14s. in Melbourne and 10s. in Sydney; bricklayers, 12s. 6d. in Sydney and from 10s. to 12s. in Melbourne; stonemasons, 11s. 6d. in Sydney and from 10s. to 12s. in Melbourne; plasterers, 12s. in Sydney, and about the same in Melbourne, and 11s. in Adelaide; painters, 11s. in Sydney, 10s. in Melbourne, and 9s. in Adelaide; boilermakers, up to 14s. in Melbourne; and navvies employed on public works, 8s. in New South Wales, 7s. in South Australia, and from 6s. to 7s. in Victoria. In 1890 wages made their first decided move downwards, and, compared with the previous year, there was a fall equivalent, on an average, to 1s. per day. Consequent on the financial crisis of 1893, wages again fell, and continued falling, until, so far as most trades were concerned, they touched their lowest point in 1895, although for some workers—notably navvies and common labourers—the period of acute depression lasted a year or two longer.

The following is a statement of the average daily wage paid in the four leading cities from 1872 to 1879:—

Trade.	Average daily wage paid in—			
	Melbourne.	Sydney.	Adelaide.	Brisbane.
	s. d.	s. d.	s. d.	s. d.
Carpenter.....	9 9	9 11	8 8	10 3
Bricklayer.....	10 0	10 10	9 0	10 4
Mason.....	10 9	10 7	9 2	9 0
Plasterer.....	10 0	10 11	9 10	10 0
Painter.....	9 0	9 3	9 0	9 10
Blacksmith.....	11 2	10 3	8 10	10 3
Boilermaker.....	11 0	9 6	9 0	10 6
Navvy or common labourer.....	6 3	7 1	6 9	6 0

Taking the wages as a whole, those paid in Sydney and Brisbane average about the same figure. In the building trades the wages paid

in Sydney and Brisbane were superior to those in Melbourne; but in the iron trade, such as blacksmithing, boilermaking, and the like, the wages in Melbourne were higher than in any of the other cities. Throughout the whole of this period the wages paid in South Australia were distinctly lower than in the other states, except navvies' wages, which were very nearly equal to those paid in New South Wales.

From 1880 to 1891 the average wages in Melbourne, Sydney, and Brisbane were fairly uniform, but in Adelaide the ruling rates were some 10 per cent. below those of the neighbouring states. Navvies and others employed on public works in New South Wales received on an average about 8s. per day throughout the whole period of thirteen years extending from 1879 to 1891. Considering the cost of living, this is the highest wage ever paid in Australia for this description of labour. In Victoria and Queensland the rates touched 7s. 6d.; in South Australia, 7s. The following represent the average wages from 1880 to 1891 :—

Trade.	Average daily wage paid in—			
	Melbourne.	Sydney.	Adelaide.	Brisbane.
	s. d.	s. d.	s. d.	s. d.
Carpenter.....	10 7	10 3	8 6	11 0
Bricklayer.....	10 9	11 4	9 0	11 0
Mason.....	10 10	10 10	9 2	9 10
Plasterer ..	10 9	11 3	10 6	10 0
Painter .....	9 0	9 10	8 10	10 0
Blacksmith.....	11 8	10 6	9 6	11 0
Boilermaker.....	11 10	9 10	9 6	11 0
Navvy or common labourer.....	6 9	8 0	6 6	6 0

From 1892 to 1896, which was a period of great disturbance, wages remained higher in South Australia than in any of the other states, the reduction from the average of the previous years in the case of this state not being very great; whereas in Victoria, in New South Wales, and in Queensland the reduction in some cases was as much as 25 per cent., and work was much more difficult to procure. The iron trades in Victoria, in spite of the general fall, maintained a strong position during

this period, but the building trades generally reached a very low level. Carpenters in Melbourne received 7s. 5d., compared with 8s. 11d. in New South Wales and 8s. 4d. in Queensland. Bricklayers received 7s. 6d. in Victoria, 9s. 8d. in New South Wales, 9s. in South Australia, and 9s. 3d. in Queensland; blacksmiths, however, were paid 10s. in Victoria, 8s. 6d. in New South Wales, and about the same in South Australia and Queensland. Navvies were paid at the rate of 6s. a day in all the states.

Trade.	Average daily wage paid in—			
	Melbourne.	Sydney.	Adelaide.	Brisbane.
	s. d.	s. d.	s. d.	s. d.
Carpenter .....	7 5	8 11	8 6	8 4
Bricklayer .....	7 6	9 8	9 0	9 3
Mason .....	8 6	8 11	9 0	11 2
Plasterer .....	7 8	8 6	8 10	8 10
Painter .....	6 8	8 0	8 0	7 6
Blacksmith .....	10 0	8 6	8 6	8 4
Boilermaker .....	10 6	9 0	10 0	8 4
Navvy, or common labourer .....	6 0	6 0	6 0	6 0

The approach of the crisis of 1893 was heralded by many signs. Deposits were shifted from bank to bank; there was a run on the Savings Bank at Sydney, an institution guaranteed by the state; mortgagees required additional security from their debtors; bankruptcies became frequent; and some of the banks began to accumulate gold against the evil day. The building societies and financial institutions in receipt of deposits, or so many of them as were on an unsound footing, failed at an early period of the depression; so also did the weaker banks. There was distrust in the minds of the depositors, especially those whose holdings were small; and the banks, even long before the crisis arrived, were subjected to the strain of repaying a large proportion of their deposits as they fell due. The crisis, however, was by no means a sudden crash; even when the failures began to take place they were spread over some considerable period, the time between the failure of the first bank and that of the last being sixteen weeks.

The first noticeable effect of the crisis was a great scarcity of employment. Wages fell precipitously, as also did rents. There was almost a complete cessation of building, and large numbers of houses in the chief cities remained untenanted, the occupants apparently moving to lodgings, or more than one family living in a single house. Credit became greatly restricted, with the result that all descriptions of speculative enterprise came to an end; and by reason of the lowering of wages and decline in profits, the demand for most articles of domestic

consumption declined also. This is seen from the fact that in 1894 there was a reduction in the imports into Australia of £4,300,000. The manufacturing industry was the first to feel the effects of the crisis, and there was a reduction in the average number of persons employed in the two leading states which may be set down at not less than 25,000. This reduction, however, was spread over four years. The closing of the factories was not general; the establishments were kept open, but there was a dismissal of workmen and a restriction of output. Lack of employment in the factories had an immediate effect on the coal-mining industry, the output of coal being about one-fourth less in 1893 than in the previous year.

The crisis was felt in the large cities more keenly than in the country districts, and in Melbourne more severely than in any other capital. The change of fortune proved disastrous to many families, previously, to all appearances, in opulent circumstances; but by all classes alike their reverses were borne with the greatest bravery. In its ultimate effects the crisis was by no means evil; on the contrary, its true meaning was not lost upon a business community that required the chastening of adversity to teach it a salutary lesson, and a few years after its first effects had passed away business was on a much sounder footing than had been the case for very many years.

The banks of issue showed large withdrawals of deposits, practically the whole of the money received from the United Kingdom being withdrawn as it became due; so that in 1898 the Australian banks had on deposit £17,175,000 less than in 1891, their highest point before the crisis occurred. There were also large withdrawals of local deposits, but the bulk of these found their way into the Post Office and other Government Savings Banks.

#### INDUSTRIAL PERIOD 1893-1904.

The compensations which followed the crisis were many, and the country would have recovered with surprising quickness from the blow which the credit of the community and of all its financial institutions had received, were it not for the adverse seasons which afflicted the great pastoral industry.

Prior to the crisis the extent of credit given to storekeepers and other tradespeople was on the whole much greater than sound experience warranted, and one of the first results was to put trade on a sound basis, and to abolish most of the abuses of the credit system. Attention was almost immediately attracted to productive pursuits, and the recovery made by the country as a whole, though slow at first, owing to the depression in the pastoral industry, was steady. Renewed attention was given to agriculture, especially in New South Wales, where, in 1901, 1,450,000 acres were devoted to the plough in excess of the area cultivated in 1893. In Victoria there was an increase of 870,000 acres, in Queensland 210,000 acres, and some slight extensions in the other states.

There was also a complete revival in the mining industry. The production of gold in New South Wales was almost doubled, and was largely increased in Victoria, Queensland, and Tasmania. In Western Australia the great gold discoveries which have placed that state at the head of Australian gold-mining, and amongst the leading gold producers of the world, were made subsequent to the crisis. Taking Australia as a whole, the output of gold in 1893 was £6,215,472; in 1903 it reached a total of £16,294,000, notwithstanding the unfavourable conditions affecting production in several states.

It was unfortunate that this time of financial distress should have been succeeded by a period of low prices for articles of local production, and that the great pastoral industry should have suffered from untoward seasons. The sheep depastured in Australia in 1893 numbered 99,800,000; in 1899 the total was reduced to 74,300,000; and in 1903 to 55,000,000.

During the years 1894 and 1895 prices reached their lowest level, but a slight recovery took place in the following two years, and this was succeeded by still further improvement, so that at the present time the average level is about equal to that of 1891.

In 1894 the total value of the imports into Australia was £41,930,720, equivalent to £12 6s. 8d. per inhabitant. These figures are far below those recorded in previous years. The imports in 1889, for example, were valued at £62,551,992, or at the rate of £20 13s. 7d. per inhabitant. It must be borne in mind, however, that extensive borrowing took place during 1889, and a considerable proportion of the imports was due to loan money brought to the country by the states, and to deposits in the banks, which were subsequently withdrawn during the financial crisis. From 1895 onward a material expansion took place in the trade of the states, and in 1900 the value of the exports was higher than at any previous period, thus showing that the country had completely recovered from the financial paralysis of 1893. It must be conceded that from every point of view sound industrial progress has been made during the last few years, and this is all the more gratifying when consideration has been given to the fact that, in some part or other of the continent, the main industries—those of sheep and cattle raising—were during the greater portion of the period seriously hampered by adverse weather conditions.

The progress of the manufacturing industries is dealt with at some length in another portion of this volume, and need not be further referred to here. It may be stated, however, that the ground lost during the financial crisis has been more than recovered, and the amount of employment afforded is now greater than ever before in the history of these states.

The movement in wages from 1896 to 1901 was distinctly upward. Carpenters, for example, were in 1896 paid 8s. per day in Sydney, while in 1900 their wages were 9s. 6d., in 1901, 10s., and in 1902, 9s. 6d. Though wages in Melbourne at these periods were lower than in Sydney,

their upward movement has been even greater, for in 1896 carpenters' wages in Melbourne ranged between 6s. and 7s. per day, the greater number being employed at the lower figures, while in 1900 the accepted rate was 8s. 3d., in 1901, 10s., and in 1902, 9s. As regards other trades connected with building, there has also been a marked improvement, and the rates of 1903 approach very closely those paid in 1891—that is to say, before the changes accompanying the financial crisis began to be felt.

The building trades suffered more heavily than any others during the period of financial disaster, and their recovery was also more protracted. Over-speculation in business was in part responsible for the crisis; and even after its immediate effects had passed from sight, there was still great reluctance to embark capital in this form of investment, although a reasonable return seemed to be fairly assured. Building operations being therefore carried on only in cases of necessity, and when exceptional profits were looked for, the wages of the artisans employed were less affected by the return of better times than might otherwise have been expected. In other branches of industry there was a marked revival, and wages shared in the upward movement.

Federation undoubtedly is a strong force in the direction of increased production and larger employment of capital, and an expansion of industrial activity should follow in its train; but the pastoral industry, which is the key to the industrial condition of Australia, was seriously affected during 1902 by the adverse climatic conditions which prevailed over a great part of the continent. Although the year 1903 opened under most favourable conditions the rains came too late to save the harvest, and the returns from cultivated lands for the season 1902-3 were the worst on record. Abundant rains fell throughout 1903, and a very large area was ploughed and sown, while the harvest returns were most bountiful, far exceeding any previous yields. The price obtained for wool and other staples during 1904 was very satisfactory, and the lambing was exceptionally good, so that the prospects of the great primary industries at the time of writing are very encouraging. There is, however, a feeling of unrest in business circles, for which there does not seem to be any adequate material reason, as well as a general absence of speculation and a tendency to restrict credit. This condition of affairs has been variously explained according to the point of view of the person offering the explanation—moral, political, and economic reasons have all been given—but there can be no question that the present is simply a repetition of previous experience. There have been bad seasons in Australia before those of 1900-2, followed also by excellent seasons and rapid recuperations. The beginning of the recuperative period is almost always one of liquidation and lack of enterprise, and it would seem that the present period of recovery is being marked by like signs to those that distinguished its predecessors. The period of stagnation has never been of long duration, and is not likely to be so at the present time.

## RECENT INDUSTRIAL LEGISLATION.

The conditions of labour in Australia and New Zealand have, since the year 1894, been affected by certain new elements which have the promise of very powerfully influencing the industrial position in the near future, and in order to understand rightly the working of these elements it will be necessary to describe in rough outline the factory, shop, conciliation, and arbitration laws of these states.

Although the condition of workers in factories received attention in England so far back as the year 1802, and comprehensive legislation dates from 1844, it was not until 1873 that there was any Australian enactment on the subject. In the year named the Parliament of Victoria passed a statute, which, amongst other provisions, enacted that no woman or girl should work in a factory for more than eight hours a day. New Zealand followed immediately with an Act, which was practically a transcript of the Victorian measure.

The factory system did not, until recent years, play an important part in the industrial life of Australia; but there have been factories in all the principal towns for many years, and it is a world-wide experience that where there are factories working uncontrolled by legislation there will always be more or less disregard of cleanliness and sanitation. This was sufficiently demonstrated by the Victorian Royal Commission of 1882, which followed upon a vivid exposure of the evil conditions of local factories made by the *Age* newspaper. The Commission did most useful work, and from its report came the Factories and Shop Act of 1885. Under that enactment the number of persons technically required to form a legal factory was fixed at six, including apprentices, and provision was made for ensuring cleanliness, air space, sanitation, the requirements of decency, and for safeguarding the health of workers and their safety in life and limb. Inspectors were appointed, and under the operation of the law the old dilapidated workshops disappeared, and the well-built, well-lit and roomy factories, now found everywhere in Melbourne, took their place. The law remained practically unchanged until 1893, when the number of persons constituting a factory was reduced to four. This, however, was only a preliminary step to further and more radical changes. In 1896 the law was further expanded, and the term factory was extended to every place in which furniture was manufactured, to every place in which a Chinese was engaged in laundry work, and to all laundries in which four persons were employed, excepting laundries carried on by charitable institutions. Powers of prosecution were given to inspectors after a factory or work-room was found to be in an insanitary condition. The Chief Inspector of Factories was empowered to condemn any factory or workroom which was, in his opinion, dilapidated, unsafe, or unfit for use. It was also provided that no portion of a factory or workroom could be used as a sleeping-place unless such sleeping-place were separated from the factory by a substantial wooden partition extending



from floor to ceiling. No child under 13 years of age was allowed to work in a factory, and no female whosoever and no boy under 16 years of age could be employed in a factory for more than ten hours in a day or after 9 o'clock at night. It had already been provided that such persons could not be employed for more than forty-eight hours a week. In furniture factories and laundries where a Chinese was working, it was provided that no person was to work before 7.30 o'clock in the morning or after 5 o'clock in the evening, or on Saturday after 2 o'clock or on Sunday at any time whatever. All persons in charge of boilers and steam engines were required to hold certificates of competence, and very special and extensive powers were given to the Department administering the Act to enforce cleanliness, ventilation, and sanitation. These were the main provisions in regard to the work of the factories, but the Act of 1896 introduced most important provisions regarding wages, which will be referred to later on.

New South Wales was very slow in taking steps for the proper regulation of work in factories. Various bills had been prepared and one had been introduced into the Legislature, but no serious attempt was made to deal with the matter on behalf of the Government, and, apart from the Government, legislation would have been impossible. In the year 1890 the Census and Industrial Returns Act was passed, under which the Government Statistician was empowered to report on the condition of the factories of the state, and pursuant to the authority contained in the Act, the officers of the Statistical Department made an exhaustive examination of factories and workshops in the large centres of population, and a series of reports was drawn up indicating the condition of the workers. The chief abuse found to exist was the almost uniform absence of due provision for sanitation and for the preservation of decency. Though sweating was not found to exist to any large extent, home workers were found to be grossly underpaid, and in many respects a strong case was made out for the necessity of passing a proper Factories Act on the lines of legislation in force in other states. Parliamentary action, however, was not taken until the year 1896, when the Factories and Shops Act was passed on the lines of the Victorian Act of 1885. Good work has been accomplished under the Act, but the powers conferred on the administration are limited compared with those found in the existing Acts of other states.

In South Australia nothing of importance was accomplished in the way of regulating employment in factories until the year 1894. The Act of 1894 did not, however, go far enough to cope successfully with the evils that had arisen, and in 1900 the law was changed, and an Act based on the Victorian model was passed, but going even farther than the original, for a factory was declared to be any workroom where anyone was working in an owner's employ.

In Queensland work in factories remained unregulated until 1896, when tentative legislation on the lines of the New South Wales Act was passed; this legislation proved insufficient, and gave way in 1900

to a carefully framed and comprehensive Factories and Shops Act as far-reaching in its provisions as that of any other state.

In Tasmania there is as yet no legislation regarding employment in factories, but there is a law for the protection of persons using machinery.

In Western Australia the factory legislation is much like that of the more advanced eastern states, the most recent legislation on the subject having been passed in 1903.

Although New Zealand cannot claim to be the pioneer of Australian legislation in regard to factories, this being an honour which is due to Victoria, it may be claimed on behalf of that colony that Victorian legislation was closely followed from the outset. In 1873 the Victorian Act was adopted by New Zealand under the title of "The Workshops Act." Like its prototype this Act made but a small advance upon the road to factory legislation. In 1890 a Royal Commission was appointed to inquire into the state of labour and industry, and consequent upon the report of this Commission the Government of the day introduced and passed a Factories and Shops Act somewhat on the lines of the Victorian Act of 1885 ; but the law was almost immediately amended in 1891 and again in 1894, when one of the most radical measures, dealing with employment in factories, was passed. In 1901 an act was passed superseding all previous enactments, and this remains law in the colony to the present time. New Zealand has been divided into factory districts under the charge of a Chief Inspector and 150 local inspectors. As a "factory" or "workroom" includes any place in which two or more persons are engaged in working for hire or reward in any handicraft, there are few operatives who do not come within the scope of the Act. Children under 14 years of age are not allowed to be employed, and the hours of labour, holidays, etc., of women and youths under 16 are strictly regulated. Good ventilation, sanitary accommodation, and general cleanliness of buildings are insisted upon ; machinery has to be properly guarded and fire-escapes provided, while dangerous occupations are specially classified. In order to assist the system of free general education which prevails in the colony, young persons are not allowed to work in factories till they have passed the fourth standard of the state schools, or an equivalent examination, while still further to discourage their employment it is provided that young children shall not be employed without wages, and the amending acts give a rate of wages on an ascending scale for their payment, this scale being continued up to the age of 21 years. To prevent the introduction of the great evil of "sweating," articles made or partly made in private dwellings or unregistered workshops, have to be labelled when offered for sale, in order that goods so manufactured (likely enough in unsanitary premises), may not be placed in the market for competition with work done in properly inspected factories. Any person removing such labels is liable to a heavy fine. The factory inspectors also

exercise supervision over the sleeping accommodation provided for shearers in country districts. A female inspector of factories gives her assistance in the duties of the department, travelling from place to place, and particularly inquiring into the working conditions of the operative women and girls. There are other provisions directed towards preventing the employment of children of tender years, and punishing parents who endeavour to evade the Act in regard to their own children. This Factories Act is one of a long series of other acts passed by the New Zealand Parliament and termed the "Labour Laws." The New Zealand Year Book gives a list of thirty-five acts which come under this category.

Besides the regulations governing employment in factories, there is, in the majority of the states, the corollary of this legislation, viz., laws dealing with the hours during which shops may remain open for the sale of goods. As in the matter of factory legislation, so in regard to the compulsory closing of shops the credit of initiation belongs to Victoria. The Act of 1885 to which allusion has already been made, declared that the hours for closing shops in towns generally should be 7 o'clock in the evening on five days a week, and 10 o'clock on Saturday nights, shops dealing with certain classes of food and perishable products being exempted from the operation of the law. In order that there should be an intelligent application of the law, the various municipal councils were authorised to pass by-laws allowing other classes of shops than those enumerated in the Act to remain open after the hours named, and at the same time the councils were empowered, if they thought fit, to close the shops earlier than 7 o'clock. Penalties for breach of the law were also left to the determination of the councils. The beneficent intentions of the framers of the law failed owing to the perfunctory way in which the municipal councils carried out their duties in regard to early closing, and a very unsatisfactory condition of things prevailed until the amending Factories and Shops Act was passed in 1896, to which allusion will be made later on.

Meanwhile New Zealand had taken the matter in hand, and the Shops and Shop Assistants Act of 1894 was passed. The main provisions of this Act, as amended in 1895, 1896, and 1901, are as follows :—

All shops in towns and boroughs are to be closed for one afternoon in each week, but a few shops, such as those of fishmongers, fruiterers, and eating-house keepers, are exempted on account of their convenience to the general public. The assistants in such establishments and in the bars of hotels and in country stores must, however, have a half-holiday allowed them in each week. Very small shops carried on by Europeans without paid assistants are also exempt from closing on a general half-holiday, but these shops must be closed on one afternoon in each week. The hours of work for women and young persons are defined. Sitting accommodation must be provided in all shops, and the necessary time for meals shall be given to all workers and sufficient sanitary accommodation

provided. The Act goes still further, and enumerates the working hours, holidays, and such like of clerks employed in banks and mercantile and business offices.

The Victorian Act of 1896 passed to remedy the defects found in the Act of 1885 did not go so far as the New Zealand Act—the initiative of closing was left with the shopkeepers, and considerable power still remained in the hands of the municipal councils. The Victorian Act, however, was an early-closing law, which the New Zealand Act was not. In 1900 the Parliament of Victoria passed an Amending Act, restricting the hours of all males employed in shops to fifty-two, carters, porters, and night watchmen alone being excepted. The law does not, however, apply to the whole state.

The Early Closing Act of New South Wales was passed in December, 1899. This Act provides for the compulsory closing of shops at 6 o'clock on four days in the week, 1 p.m. on one day, and 10 p.m. on one day. The Act, however, does not specify when shops may be opened. It applies to the Metropolitan district and Newcastle; country shop districts, which include all municipalities in the state other than Sydney and Newcastle, may be brought under the Act by proclamation, and this has been done.

In the year 1900 early-closing laws were enacted in South Australia and in Queensland; in both cases the Acts were close copies of that of New South Wales. In 1897, an Early Closing Act was passed in Western Australia; Tasmania, therefore, is the only state in which there is no law regulating shop hours.

The disastrous strikes which have been spoken of as occurring between 1886 and 1895 were symptoms of an industrial unrest spreading over the whole of the Eastern States and New Zealand. The expenditure of public money on a lavish scale had attracted to these states a larger number of unskilled workers than work could be provided for in ordinary seasons, and even many of the skilled trades were largely overmanned. Under the existing conditions of industrial remuneration a fall in wages was inevitable. The trades unions, however, made a brave stand against any reduction in the wages of their own members, and there can be no question but that up to the year 1888, and in some trades for a year or two longer, their efforts were in the main successful. But the number of workers enrolled in the unions was small compared with the total number of persons following gainful pursuits. The trades unions, too, had an advantage from the fact that the trades which they controlled were skilled trades which required long apprenticeship to learn, and which in the case of a strike could not be swamped by unskilled or partially skilled labour. About the year 1888 the trade unions and others who sympathised with the labour movement, and persons desirous of avoiding further labour conflicts, began to consider very earnestly whether some means might not be taken to regulate the relations of employers and the employed, and so avoid the wasting effects which inevitably follow in the train of

strikes. Several distinct methods of arriving at the same desirable end presented themselves, namely :—

Conciliation, in which the parties to a dispute were brought together without legal compulsion.

Compulsory arbitration.

The regulation of wages by a board representing the employers and employed, with an impartial chairman ;

and each of these systems has been tried in these states since 1888.

The question of conciliation and voluntary arbitration has been before the Australian public for some considerable time. In 1882 Mr. (afterwards Sir George) Dibbs introduced into Parliament a bill for the establishment of a council composed of members of the New South Wales Employers' Union and the Trades and Labour Council, in which conciliation was provided for on the lines of the *Conseils de Prud'hommes* existing in France ; but there was so little parliamentary response that the bill was shelved. In 1887 a scheme based upon English precedent was promulgated by a joint committee of the Victorian Trades Hall Council and the Employers' Union for the establishment of a Board of Conciliation. A similar scheme was drawn up by the joint committee of the New South Wales Employers' Union and the Trades and Labour Council, but was rejected. In the building trade of New South Wales there was for some years a representative Board of Conciliation without any provision for arbitration, and this board is reported to have done very excellent work. In 1887 Mr. J. H. Carruthers introduced a Trades Conciliation Bill, in which the machinery provided was purely voluntary. The measure did not, however, get beyond the stages of a bill. Other schemes of conciliation were proposed, notably one drawn up by the Honorable C. J. Langridge, of Victoria. In South Australia a bill to encourage the formation of industrial unions and associations, and to facilitate the settlement of industrial disputes, was introduced into Parliament by the Hon. C. C. Kingston in December, 1890. This measure is the parent of all the conciliation and arbitration laws now in operation in Australia ; the bill met with strong opposition, and it was not until late in 1894 that it was finally passed into law, having been twice rejected by the Legislative Council.

Meanwhile the matter of conciliation had been before the New South Wales Parliament. A commission had been appointed to inquire into the question of strikes, and a report was drawn up and a bill based on the recommendations was drafted and introduced by Sir Henry Parkes on the 5th of August, 1891, but the Government resigned before the bill could become law.

About the same time a measure was before the Victorian Parliament ; it consisted of twenty-three clauses, and did not go much farther than to permit the establishment of councils of conciliation under license from the Crown, as no award could be taken into, or enforced by, any court of law. This measure became law at the commencement of 1892, and has, therefore, the distinction of being the first legislative enactment.

of its kind on the statute books of Australia. The Act, however, was not followed by any consequences, good or bad, being entirely ignored by all parties. When Sir George Dibbs succeeded Sir Henry Parkes as Premier of New South Wales he took up the question of trades disputes, and on 31st March, 1892, his Trades Disputes Conciliation and Arbitration Act was assented to. This Act was in force for four years, when it lapsed, very little use being made of it in spite of the strenuous exertions of the officials in charge of its administration.

In New Zealand a Conciliation and Arbitration Bill was introduced in 1892 by the Minister for Labour, the Hon. W. P. Reeves, and was twice rejected by the Legislative Council; it was, however, presented a third time, and became law on the 31st August, 1894. The following is a short epitome of its leading provisions:—

The object of the Act, as declared in the preamble, is to encourage the formation of industrial unions and associations, and to facilitate the settlement of industrial disputes by conciliation and arbitration.

A society of not less than seven persons, associated for the purpose of protecting or furthering the interests of employers or workmen, may be registered as an industrial union by complying with certain provisions of the Act. Full and detailed information as to constitution, rules, names of officers and members, etc., must be sent to the Registrar, who will issue a certificate of registry and incorporation. The effect of registration will be to render the industrial or trade union so registered subject to the jurisdiction of the Board and Court appointed under the Act.

The parties to industrial agreement may be—(1) trade unions, (2) industrial unions, (3) industrial associations, (4) employers. Every industrial agreement shall be for a specified time not exceeding three years, and is to be filed in the Supreme Court office within thirty days of making. It is binding on both sides, and if any association or person thus bound fails in carrying it out there is a penalty not exceeding the amount fixed by the agreement, or, if no amount is fixed, not exceeding £500.

“Industrial districts” are to be constituted and gazetted, and for every such industrial district a Board of Conciliation and a Clerk of Awards is to be appointed. The Act defines the powers of the Court and Board and the duties of the Clerk, and provides that, when a dispute is referred to Board or Court, no strike or lock-out may take place until the decision is given. A Board of Conciliation is to consist of not more than six or less than four persons, chosen by the industrial unions of employers and of workmen in the respective districts, and a chairman is to be elected outside the members of the Board. Should a Conciliation Board fail to effect settlement, the dispute may be referred to the Court of Arbitration. There is to be one Court of Arbitration for the whole colony, consisting of three members, one appointed on the recommendation of the council of associations of employers, one on the

recommendation of the council of associations of workmen, and the third a judge of the Supreme Court; every member to hold office for three years, and to be eligible for re-appointment. If any party to a proceeding before the Court fail to appear without cause the Court may proceed *ex parte*. The award is to be made within one month, and may include costs and expenses; but no costs will be allowed for agents, counsel, or solicitors appearing for any party, and it shall be framed in such manner as to express the decision of the Court whilst avoiding technicalities. The award may be enforced in the same manner as a judgment of the Supreme Court. The amount for which an award may be enforced against an association is limited to £500.

The fourth part of the Act provides that the Railway Commissioners and the Amalgamated Society of Railway Servants may be respectively registered, and may refer any industrial dispute between them to the Court of Arbitration, but Boards of Conciliation are to have no jurisdiction in these cases.

So novel a piece of legislation could not be expected to work quite smoothly in the first instance; Amending Acts elucidating the provisions of the original measure were therefore passed in 1895, 1896, and 1898, and the law was consolidated and further amended by the Acts of 1900 and 1901. The amendments of the original Act extend the scope of the jurisdiction of the tribunals of arbitration, and carry the principle of compulsion further than contemplated by the Act of 1894. Non-unionist workmen are brought within the jurisdiction of the Arbitration Court in certain circumstances, as well as clerical employees. Conciliation Boards are made courts of first instance; awards are made permanent in default of a further dispute, and, subject to certain safeguards, awards may have force throughout New Zealand.

It has been mentioned that Mr. C. C. Kingston, when Premier of South Australia, introduced his bill to facilitate the settlement of industrial disputes in December, 1890. Various causes tended to delay the passing of the measure, so that it was not until December, 1894, that it passed both Houses of Parliament and received the Royal assent. In point of time the South Australian measure was introduced before that of New Zealand, but it became law a few months later. The South Australian Act has not been availed of to any large extent, for, unlike the New Zealand law, it allows only registered bodies to appear before the Arbitration Court, and as the trade unions of the state have not registered under the Act, they have consequently remained outside its jurisdiction. South Australia, however, is a state in which trade disputes have not been by any means very virulent, and it is probable that the failure of industrial bodies to invoke the aid of the Arbitration Court has been due to the mildness of the disease and not to the inefficacy of the remedy.

The movement to provide means of settling disputes was felt also in Queensland, where a bill, on the lines of the *Conseils de Prud'hommes*, was introduced by Sir S. W. Griffith. It was not, however, a

measure dealing with industrial disputes between employers and bodies of employees.

Western Australia passed a Conciliation and Arbitration Act in 1900. The law, however, was superseded in February, 1902, by one approximating very closely to the latest New Zealand law, and this is now in active operation. On 1st January, 1904, there were 17 unions of employers registered under the Act, and 132 unions of workers representing 15,294 persons. The funds at disposal of workers' unions amounted to £13,250.

With the example of New Zealand and South Australia before it, the New South Wales Parliament at the instigation of Mr. B. R. Wise, the Attorney-General, undertook the passing of an Arbitration Act. The first bill was introduced in the middle of 1901, but was rejected by the Council. The bill was afterwards re-introduced, and became law on the 10th December, 1901, an amendment by the Council limiting the law until 1908 being assented to by the Assembly. The New South Wales Act in some respects bears a close resemblance to that of New Zealand, but in other ways there are radical differences. The matter of conciliation was laid great stress upon by the framers of the New Zealand law as it originally stood, and the best exponents of the principle in New Zealand still view it with favour, but the Amending Act of 1891 gave power to either party to an industrial dispute to pass by the Board of Conciliation and go direct to the Court. This permission is invariably acted upon, and has had the effect of practically abolishing the Conciliation Boards. Such being the New Zealand experience the New South Wales Act does not attempt to introduce the principle. The Act provides for the registration of industrial unions of employers and of employees. Any employer or association of employers employing fifty or more hands may be registered as an industrial union, but employees must first register as trade unions, as only trade unions can become industrial unions under the Act. Any dispute in regard to industrial matters, whether between industrial unions, or between an employer and an industrial union of employees, or between an employer and a trade union, may be referred to the Court of Arbitration. It is provided, however, that no person or body of persons other than an industrial union (or in certain cases the Registrar) may refer such dispute to the Court, so that the Act has had the effect of fostering the organisation both of employers and employees, and the formation and registration of industrial unions. The provision for restricting the right of approaching the Court to industrial unions in conjunction with the clause making the passing of a resolution by the members of a union a condition precedent to the referring of a dispute, was intended to protect the Court from being burdened with trivial cases. Before seeking the intervention of the Court, employers must be registered; but they may be cited before the Court as defendants although unregistered. The Court consists of a Supreme Court Judge appointed by the Governor, and two members



elected respectively by the industrial unions of employers and the industrial unions of employees. The prohibition of strikes and lockouts during the reference of any dispute to arbitration is similar to the New Zealand law. The persons who strike or lockout after a dispute has arisen are, in certain circumstances, guilty of a misdemeanour. The Arbitration Court specifically grants the power of fixing the minimum wage, and has also statutory power to give preference to unionists over non-unionists, other things being equal, when men of both classes offer their labour at the same time. The distinctive feature of the New South Wales Act is the provision regarding the common rule. In New Zealand the process of arbitration is for the court to proceed to district after district, citing all the employers in the industry under review before it. Its decisions in a district are confined only to that district. The decisions therefore bind certain specific employers, whereas in New South Wales the decision of the court can be made to apply to all industries of the state, and the court has power to declare that any custom, regulation, agreement, condition, or dealing in relation to any industrial matter shall be a common rule of the industry.

Another important provision not contained in the New Zealand law is that any industrial dispute may be referred to the court by the Registrar, where the parties—or some or one of them—are not industrial unions.

The description of the various Acts in force in reference to conciliation and arbitration must be taken as the merest outline. The student of this important question who is desirous of getting a clear knowledge of the working of the Acts must consult the original authorities on the subject. The descriptions here given are only intended to illustrate a phase of the industrial position which the student of Australian affairs must not lose sight of.

One of the first decisions of the Arbitration Court of New Zealand was to award preference to unionists where such was practicable, and to declare that where preference was not granted employers should not discriminate against unionists. The power of the Court to grant preference was disputed by the employers, but all doubt in regard to the matter was removed by the passing of a specific enactment by the Legislature enjoining preference, the conditions of such being that a union should be practically open to every person employed in the trade who wished to join it, and that there are members of the union unemployed and seeking employment who are equally qualified with non-members to perform the work required to be done. In New South Wales also the general principle of preference to members of unions over non-members is embodied in the law, and such preference has been granted by the Court almost from the outset. In such circumstances the number of members belonging to trades unions became an extremely interesting fact in connection with the working out of the principles of arbitration. In New Zealand on 31st March, 1904, there were 336 workers' unions registered with a membership of

25,354. In Western Australia there were, at the close of 1903, 132 unions of workers with a membership of 15,294.

In New South Wales the number of unionists is much greater than in New Zealand, and allowing for difference of population, is also proportionately greater. The following are the figures for the three years the Act has been in operation :—

INDUSTRIAL UNIONS OF EMPLOYERS.			INDUSTRIAL UNIONS OF EMPLOYEES.	
Year.	Number.	Membership.	Number.	Membership.
1902	109	2,302	85	57,638
1903	119	2,916	124	72,367
1904	118	3,163	128	70,635

The total number of workers in the state in 1904 was 362,396, counting only those of the full age of 21 years and upwards, so that the number of unionists to workers is about 19 per cent. This bare statement of fact is, however, likely to mislead, as there are a large number of workers so placed that no industrial combination has, so far, been possible amongst them. Even amongst trades which are represented by unions membership is often confined to workmen who live in towns. Excluding occupations not represented by unions there are 70,635 unionists to 218,189 adult workers, or 32·4 per cent; but even this statement needs qualifying, for amongst the 218,189 workers are included 37,468 common labourers who would find difficulty in joining a union of fellow workers, and 57,580 agricultural and pastoral labourers to whom the Australian Workers' Union—which is practically a shearers' union—is alone open. Excluding these the number of unionists is reduced to 53,528, and the adult workers corresponding to 123,141. Some of the unions contain every man following the trades they represent, but these are small unions. Amongst the most successful of the larger unions are the various coal miners' unions which have a membership of 9,000 out of 11,000. At the other end of the scale is the grooms' and coachmen's union with a membership of 45 out of 5,223 grooms and coachmen in the state.

The aim of the Conciliation and Arbitration Acts is primarily the prevention of strikes and lockouts. In Victoria the amelioration of the industrial situation was approached in an entirely different manner. It was thought that as the Factories Act provided for the protection of the worker, so far as sanitation, working hours, and the surroundings of the workshop were concerned, if his remuneration was determined by an agreement between the employer and the employed, the occasion for strikes would be avoided. In the Factories Act of 1896, to which allusion has already been made, a bold attempt was made to deal with the difficult problem of industrial remuneration.

In addition to the provisions regarding workshops, the Factories and Shops Act of 1896 enacted that special boards might be appointed to fix wages and piecework rates for persons employed either inside or outside factories in making clothing or wearing apparel, or furniture, or in breadmaking or baking, or in the business of a butcher or a seller of meat, or maker of small goods. The appointment of special boards was also authorised for any process, trade or business usually or frequently carried on in a factory or workroom, provided a resolution has been passed by either House declaring it to be expedient that such a board should be appointed. Special boards, it was provided, might consist of not less than four and not more than ten members with a chairman, the period of office being two years. Half the members were to be elected by the employers as representing their interests, and half by employees. The right of appointment of a chairman of a board rested with the board itself, the chairman not being an elective member, but in the absence of appointment by the board, the Governor-in-Council has power to appoint the chairman. An exception to the principle of election was made in the case of the furniture trade, where the whole of the members of the board were appointed by the Governor, as it was thought undesirable that the election should be made by the trade itself, as the great majority of the workmen in the furniture trade were Chinese. The boards were given power to fix either wage rates or piece work, or both, as well as the hours for which the wage rate was determined and the rate of pay for overtime; to the boards also was given power to determine the proportion of apprentices or improvers to skilled workmen employed in any process, trade or business, as well as the wage to be paid to them. When a board had determined the minimum wage, manufacturers were allowed to fix the piece-work rates, provided that these rates were based on such minimum wage, and as a check on imposition, it was provided that the Chief Inspector of Factories should have the right to challenge any piece-work rate and submit the matter to the board. Provision was also made for the granting of licenses to aged and infirm workers, who were permitted to work at less than the minimum wage fixed by the board. Agreements in contravention of the decision of the board were held to be null and void, and an employee might sue for his wages as determined by the Wages Board, any agreement to the contrary with his employer notwithstanding. It was further enacted that any person employed in a factory should receive at least 2s. 6d. a week, and that no premium or bonus was to be charged directly or indirectly for engaging or employing any female apprentice or improver in making articles of clothing or wearing apparel.

The Act was not a permanent enactment; it was first passed in 1896, re-enacted with some amendments in 1900, and continued until September, 1902, when it lapsed on the dissolution of Parliament. At the time of the expiry of the Act there were thirty eight special boards in existence. When Parliament met after the elections, amongst the first

bills introduced was one to revive and continue in force the *Factories and Shop Acts* and all regulations thereunder, as well as the determinations of the special boards. The lapsed laws, with some modification in regard to special boards, were continued until the 31st October, 1903, and before that date an Act was passed continuing the then existing law until the 31st December, 1905. The Act continued the old laws but modified them in certain important particulars, and constituted a court, consisting of a Supreme Court judge, to hear appeals against determinations of special boards, and for dealing with references in regard thereto by the Minister. Under the amended Act a resolution of both Houses of Parliament is required for the establishment of a special board, not, as originally provided, the resolution of either House. As regards the boards themselves, an important provision has been introduced to the effect that the representatives of employers shall be actual employers, and the representatives of employees shall be actual employees, in the trade concerned, and the term of office was made three years instead of two, as in the original enactment. The principles of future determination as to wages and rates were laid down as follows :

- (a) The board shall ascertain as a question of fact the average prices or rates of payment (whether piece-work prices or rates or wages prices or rates) paid by reputable employers to employees of average capacity ;
- (b) The lowest prices or rates as fixed by any determination shall in no case exceed the average prices or rates as so ascertained ;
- (c) Where the average prices or rates so ascertained are not in the opinion of the special board sufficient to afford a reasonable limit for the determination of the lowest prices or rates which should be paid, they may so report to the Minister, who shall in such case refer the determination for the consideration of the Court, and the Court in that event may fix the lowest prices or rates to be paid without having regard to the provisions of subsection (b) ;
- (d) Where it appears to be just and expedient, special wages prices or rates may be fixed for aged, infirm, or slow workers.

The effect of the provisions of the *Factories and Shops Act* in regard to the industrial conditions of Victoria has been much discussed. For detailed information on the subject the enquirer should consult the Reports of the Chief Inspector of Factories, and the Report of the Royal Commission on the operation of the factories and shops law of Victoria, dated February 19th, 1903. The apparent results so far as concerns the wages of operatives are considerable. Taking the operatives in trades in respect of which determination as to wages were arrived at, and confining the comparison to persons 20 years of age and upwards, it will be found that there has been a substantial increase as between the wages of 1895, the year preceding the passing of the provisions of the law relating to wages boards, and those of 1902, which is the last complete year during which these provisions were in full operation.

Seventeen trades are shown in the following list; in fifteen of these wages were increased substantially. The greatest proportionate advance was in the furniture trade, the earnings of Europeans having been advanced from £1 9s. 3d. per week to £2 8s. 7d., or by 66 per cent., and of Chinese from £1 1s. 10d. per week to £2 7s. 11d., or by 119 per cent. There were large increases also in the following employments, viz., engraving and die-sinking, brickmaking and pottery, harness and saddlery, jewellery and electroplating, boots and shoes, and bread, biscuit, and confectionery, and smaller, though still important, increases in printing, stationery, &c., brushmaking, clothing, cooperage, and malting. Two industries show a slight reduction in the average wages paid.

It will be understood, in considering these figures, that they are based upon the actual payments made by the factories of the state, and not upon the decisions of the various wages boards, which cannot be translated into percentages of increase or decrease; in any circumstance the decision of a wage tribunal determines only the minimum wage, and the average wages paid may perchance be something quite different.

Taking the seventeen trades enumerated, the average movement of wages in the seven years was from £1 18s. 4d. to £2 6s. 5d., that is to say, an increase of 8s. 1d., or 21 per cent. The trades comprised in this and the following lists are those wherein over fifty hands were employed at each period.

MALES 20 YEARS AND UPWARDS—INDUSTRIES UNDER SPECIAL BOARDS.

Class of Trade.	Average weekly wage.		Movement.	
	1895.	1902.	Increase per cent.	Decrease per cent.
	£ s. d.	£ s. d.		
Boots and shoes.....	1 15 10	2 3 5	21	.....
Bread, biscuit, and confectionery .....	1 15 2	2 5 7	30	.....
Brewing .....	2 4 9	2 1 6	.....	7
Brickmaking and pottery .....	1 12 4	2 6 1	43	.....
Brush and broom-making .....	1 14 6	1 19 2	14	.....
Clothing .....	2 1 1	2 8 9	14	.....
Cooperage .....	2 0 11	2 6 6	14	.....
Engraving, die-sinking .....	1 17 10	3 4 9	71	.....
Furniture (European) .....	1 9 3	2 8 7	66	.....
„ (Chinese) .....	1 1 10	2 7 11	119	.....
Harness, saddlery .....	1 15 4	2 5 3	28	.....
Jewellery, electroplating.....	2 2 9	2 13 11	26	.....
Malting .....	2 1 2	2 6 11	14	.....
Printing, stationery, bookbinding.....	2 5 0	2 13 8	19	.....
Shirt-making .....	2 3 1	2 0 0	.....	7
Tanning .....	1 16 0	1 19 11	11	.....
Woolen manufactures.....	1 15 7	1 19 1	10	.....

In eight industries comparison may be made as to the wages paid to females, of 20 years and upwards, employed in trades working under special boards. This the following table affords. It will be seen that in four trades there have been substantial increases, in two trades wages have remained practically stationary, and in other two there have been large reductions. Grouping the eight trades together, the movement of wages in the seven years was from 17s. 9d. to 20s. 1d., or 13 per cent.

Class of Trade.	Average weekly wage.		Movement.	
	1895.	1902.	Increase per cent.	Decrease per cent.
	£ s. d.	£ s. d.		
Boots and shoes .....	0 16 9	1 1 0	25	.....
Bread, biscuits, confectionery .....	0 18 6	0 14 9	.....	20
Brushes, brooms, &c. ....	0 15 11	0 15 5	.....	3
Clothing .....	0 18 1	1 1 9	20	.....
Furniture (European) .....	0 18 2	1 1 6	18	.....
Printing trades .....	0 15 0	0 15 8	4	.....
Shirt-making .....	0 18 8	0 16 1	.....	14
Woollen mills.....	1 0 3	1 3 4	15	.....

Taken as a whole, the trades not placed under special boards showed higher average remuneration for adult male workers in 1895 than did the trades that were so placed. Taking twenty-six trades included in the list given hereunder, the average wages in 1895 was 40s. 1d., as compared with 38s. 4d. paid, in the same year, to trades placed under special boards; in 1902 the comparison was 42s. 3d. as against 46s. 5d., the advantage being on the side of trades working under special boards. In thirteen out of the twenty-six trades shown in the list, wages remained stationary, or were within less than 5 per cent. of what they had been in 1895; in three cases there were reductions, and in ten cases there were increases; the whole movement, however, represented an advance of 2s. 2d., or 5 per cent. The most substantial increases appear in works for preserving meat or fruit, in which the advance was 47 per cent., and in ice and refrigerating, 17 per cent.; as regards the former, it is possible the increase is merely apparent, as establishments where fruit is preserved were omitted from the official returns of 1902.

The largest decrease was in works for making chemical manures, and in bone-mills.

MALES 20 YEARS AND UPWARDS—INDUSTRIES NOT UNDER SPECIAL BOARDS.

Class of Trade.	Average weekly wage.		Movement.	
	1895.	1902.	Increase per cent.	Decrease per cent.
	£ s. d.	£ s. d.		
Ammunition .....	2 14 3	2 9 5	.....	9
Aerated waters .....	1 13 2	1 13 10	2	.....
Bacon-curing .....	2 1 11	2 2 10	2	.....
Candles—soap and tallow .....	1 15 9	1 17 9	6	.....
Carriages, waggon, &c. ....	1 16 10	2 1 7	13	.....
Chaff-cutting .....	1 14 1	1 17 1	9	.....
Chemicals, gum refining, &c. ....	1 17 1	1 18 0	2	.....
Chemical manures, bone mills, &c. ....	2 13 1	1 19 7	.....	25
Electric light .....	2 4 10	2 7 9	6	.....
Fellmongeries .....	1 15 11	1 19 6	10	.....
Flour mills .....	2 2 4	2 5 1	6	.....
Iron foundries, brass and copper works, ovens, &c. ....	2 1 11	2 4 9	7	.....
Glass bottles .....	2 6 1	2 4 3	.....	4
Grocers' sundries .....	1 18 1	1 17 10	.....	1
Hosiery .....	2 2 0	2 1 9	.....	1
Ice and refrigerating .....	2 4 3	2 11 10	17	.....
Hats and caps .....	2 9 0	2 10 8	3	.....
Leather fancy goods .....	1 17 2	1 17 1	.....	.....
Preserving works—meat, fruit, &c. ....	1 11 9	2 6 9	47	.....
Rope and twine .....	1 17 2	1 18 8	4	.....
Sugar refining .....	2 4 6	2 5 6	2	.....
Tinware .....	1 15 10	1 16 11	3	.....
Umbrellas .....	2 2 0	2 2 7	1	.....
Waterproof clothing .....	1 16 1	2 0 7	12	.....
Wireworks .....	1 18 0	1 16 1	.....	5
Tobaccos, cigars, cigarettes .....	1 18 10	1 19 6	2	.....

A comparison of the wages paid to women working in industries not under special boards for the years 1895 and 1902 shows considerable advances in some industries: for example, wages have increased 20 per cent. in the tobacco industry, and from 15 to 17 per cent. in the hatting industry, hosiery, and umbrella making. Other industries have held their own, excepting establishments making mantles, millinery and underclothing, in which wages have declined 15 per cent. Ten classes of industries are enumerated in the following list; the movement of wages for all taken together is from 17s. 6d. per week in 1895, to 17s. 10d. in 1902. It will be seen, therefore, in working out an average, that the employment in establishments making mantles, millinery, and

underclothing is so extensive that a decline of 15 per cent. in the wages of women employed therein counterbalances the increases in other trades.

FEMALES 20 YEARS AND UPWARDS—INDUSTRIES NOT UNDER SPECIAL BOARDS.

Class of Trade.	Average weekly wage.		Movement.	
	1895.	1902.	Increase per cent.	Decrease per cent.
	£ s. d.	£ s. d.		
Ammunition .....	0 13 6	0 13 11	3	.....
Dressmaking .....	0 15 11	0 16 11	6	.....
Grocers' sundries .....	0 14 6	0 14 9	2	.....
Hosiery .....	0 14 9	0 17 5	17	.....
Hats and caps .....	0 17 1	0 19 7	15	.....
Mantles, millinery, underclothing, &c. ....	1 1 7	0 18 5	.....	15
Rope, twine, &c. ....	0 13 8	0 14 0	2	.....
Umbrellas ..	0 15 9	0 18 5	17	.....
Waterproof clothing.....	0 18 8	0 19 9	6	.....
Tobacco, cigars, and cigarettes .....	0 17 6	1 1 1	20	.....

It will be seen that the wages determined for male workers by the special boards are uniformly lower for boys and youths than in the non-regulated factories; but for adult workers the wages are higher, and for females the regulated wages are in every case higher. For all male workers the average in regulated trades is £1 15s. 9d., compared with £1 11s. 1d. in other trades, showing a difference of 4s. 8d. per week; this is higher than an inspection of the figures in the foregoing table would lead one to expect, and is due to the fact that in the regulated trades three-fourths of all workers are adults, whereas in other trades the proportion is not more than three-fifths.

The amendments in the minimum wage law of Victoria made by the Act of October, 1903, will probably modify in some degree the tendency of Special Boards to raise wages, but the law even as it now stands embodies so much that is novel and important in industrial legislation that its working is being watched with very keen interest both in Australia and in Europe and America. Nor is the interest lessened by the fact that while in Victoria and South Australia the principle of the legal establishment of the minimum wage is in operation, side by side as it were, in New South Wales, Western Australia, and New Zealand the essentially different system of conciliation and compulsory arbitration is at work to prevent the occurrence of strikes and lockouts, and regulate the earnings of all classes of labour.

The admirable publications of the New Zealand Statistical Department show the wages in various trades at intervals since 1891, and



from these the following summary has been deduced, which gives the average weekly earnings of employees in the various factories and works of the colony at the last three census periods :—

Year.	Weekly Earnings.	
	Males.	Females.
	s. d.	s. d.
1891 .....	29 0	13 4
1896 .....	29 9	11 6
1901 .....	31 5	12 5

It will be seen that the average earnings both for males and females is less in New Zealand than in New South Wales and Victoria. In the absence of the ages of the workers in New Zealand, however, it is impossible to go beyond the statement of the average earnings. As the table shows, the average rate for males has increased by 2s. 5d. per week, which is equivalent to  $8\frac{1}{2}$  per cent.; the earnings of females, on the other hand, are slightly lower than they were in 1891.

A comparison of the average wages paid to workers of various ages (a) in trades regulated by Special Boards in Victoria, and (b) other factory workers, is interesting reading.

Age of Worker.	Trades under Special Boards.		Other Trades.	
	Males.	Females.	Males.	Females.
Years.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
13	0 6 1	0 4 0	0 6 6	0 3 7
14	0 6 6	0 4 4	0 7 6	0 4 3
15	0 7 7	0 5 1	0 8 9	0 4 5
16	0 9 0	0 6 5	0 10 8	0 5 6
17	0 11 8	0 8 4	0 13 0	0 7 1
18	0 14 8	0 11 4	0 16 4	0 8 10
19	0 18 7	0 12 8	0 19 4	0 10 7
20	1 2 11	0 15 4	1 2 8	0 11 10
21 and upwards	2 4 3	0 19 9	2 1 11	0 17 5
All ages .....	1 15 9	0 15 11	1 11 1	0 12 8

As already explained, the Arbitration Act of New South Wales has not been in force sufficiently long to admit of statistics being obtained as to its probable effect upon wages; but the average weekly rates of pay for males and females engaged in the various manufactories and works of the state in the years 1900 to 1903 are given below:—

Age.	1900.	1901.	1902.	1903.
<b>Males.</b>				
13 years .....	£ s. d. 0 6 5	£ s. d. 0 6 9	£ s. d. 0 6 11	£ s. d. 0 6 2
14 „ .....	0 6 9	0 7 5	0 7 3	0 7 4
15 „ .....	0 7 9	0 8 2	0 8 6	0 8 6
16 „ .....	0 9 3	0 9 10	0 10 1	0 10 2
17 „ .....	0 11 8	0 12 7	0 12 5	0 12 7
18 „ .....	0 15 4	0 16 4	0 16 0	0 16 4
19 „ and over .....	2 0 2	2 2 0	2 2 8	2 2 11
<b>Females.</b>				
13 years .....	£ s. d. 0 4 7	£ s. d. 0 4 4	£ s. d. 0 5 0	£ s. d. 0 5 5
14 „ .....	0 4 0	0 4 1	0 4 8	0 4 5
15 „ .....	0 4 3	0 4 9	0 4 10	0 4 10
16 „ .....	0 5 10	0 6 7	0 6 6	0 6 4
17 „ .....	0 7 5	0 8 2	0 8 7	0 8 5
18 „ .....	0 9 4	0 10 5	0 10 5	0 10 7
19 „ and over .....	0 15 9	0 17 2	0 17 4	0 17 7

It will be seen that in the interval of three years there has been an upward movement of wages, both for males and females. This movement cannot, however, be attributed to the operation of the Arbitration Act, seeing that it was chiefly effected in 1901, the year preceding the passing of that Act.

As schemes of industrial conciliation and arbitration are only workable in connection with trade unions, it is interesting to know the membership of trade unions throughout Australia and New Zealand. Returns have been received from the registries of trade unions in each state setting forth, as far as possible, the membership of trade unions existing on the 1st January, 1904. These are shown in the following list, which is official for all the states except South Australia, and for this last state, an unofficial estimate has been made:—

New South Wales	...	...	...	...	70,622
Victoria	...	...	...	...	7,942
Queensland	...	...	...	...	4,681
South Australia	...	...	...	...	7,300
West Australia	...	...	...	...	10,047
Tasmania	...	...	...	...	34
Commonwealth	...	...	...	...	100,626
New Zealand	...	...	...	...	25,354
Australasia	..	...	...	...	123,981

It will be seen that only in New South Wales, Western Australia and New Zealand is there any large registration of trade unions, and it is in these states that the principles of compulsory arbitration are in force. The vivifying effect of compulsory arbitration upon trade unions is exemplified by the case of New South Wales, where, prior to the passing of the compulsory Arbitration Act, the total number of persons belonging to unions was less than 20,000, as compared with 70,000 at the present time. The figures refer to registered trade unions. There may be other unions which have not taken advantage of the law to register themselves, but the membership of such non-registered trade unions cannot be very great in the states where compulsory arbitration is in force. In Victoria the number of registered unions is only 7, and the membership 7,942. The total strength of the unions is, however, much greater, for registration is the exception and not the rule in that state. According to the report of the Trades Hall Council there were, on the 30th June, 1904, 77 trades societies belonging to or affiliated to the Council, and there were in addition to these the Trades Councils of Ballarat and Bendigo, which are independent bodies, unconnected with the Melbourne Council.

Towards the close of the year 1904 an Act was passed by the Federal Parliament to give effect to the powers of the Constitution (section 51, sub-section 35) with respect to conciliation and arbitration for the prevention and settlement of disputes extending beyond the limits of any one state. "Industrial dispute" is defined as a dispute in relation to industrial matters extending beyond the limits of any one state, including disputes in relation to employment on state railways, or to employment in industries carried on by or under the control of the Commonwealth or a state or any public authority constituted under the Commonwealth or a state, but it does not include a dispute relating to employment in any agricultural, viticultural, horticultural, or dairying pursuit. Preference to unionists may be given where, in the opinion of the Court, the application for such preference is approved of by a majority of those affected by the award who have interests in common with the applicants.

It will probably be some little time before the Act can be put into operation, and its effect on the industrial situation will be most keenly watched

## PRIVATE PROPERTY AND INCOMES.

**T**HE first century of Australasian history closed on the 26th January, 1888, and though it is impossible to trace step by step the progress made during that period, as the data for the purpose are for the most part wanting, sufficient material is available from which a comparative statement of the wealth of the states at different periods may be deduced. In the following figures the private property of the people has alone been considered, the value of the unsold lands of the state, as well as the value of public works, having been omitted. The table shows the value of private property for the whole of Australasia, and the increase thereof at intervals of twenty-five years from the date when this territory was first colonised :—

Year.	Value of Private Property.
1788 .....	Country first colonised.
1813 .....	£1,000,000
1838 .....	26,000,000
1863 .....	181,000,000
1888 .....	1,015,000,000
1903 .....	1,204,042,000

Though Australasia has but the population of a province of some of the great European powers, in the wealth and earnings of its people it stands before most of the secondary states, and as regards wealth and income per head of population it compares very favourably with any country.

The plan adopted in valuing the elements of private wealth is given in detail in previous issues of this work, and has not been greatly varied on this occasion. Land, houses, and other improvements thereon, represent more than two-thirds of the private wealth. There are now ample data for assessing the value of these, for besides the municipal returns which are available for each state, there are complete land-tax returns for New South Wales, New Zealand, and South Australia. From the information thus to hand, there has been no difficulty in arriving at the value of land separately from its improvements. For all Australasia, the value of land in private hands is £461,255,000,

out of a total wealth of £1,204,042,000; this represents a proportion of 38 per cent., varying in each state, as follows:—

State.	Value of Land.	Proportion of Value of all Property.
New South Wales .....	£136,417,000	38·99 per cent.
Victoria .....	126,078,000	40·66 "
Queensland .....	41,400,000	34·66 "
South Australia .....	35,957,000	41·66 "
Western Australia .....	11,996,000	24·45 "
Tasmania .....	21,832,000	45·21 "
Commonwealth .....	373,679,000	38·05 "
New Zealand .....	87,576,000	39·44 "
Australasia .....	461,255,000	38·31 "

The value of land and improvements together amounts to £836,770,000, or 69·5 per cent. of the total value of property. The following is a statement of the values for each state:—

State.	Value of Land and Improvements.	Proportion of Value of all Property.
New South Wales .....	£264,492,000	71·72 per cent.
Victoria .....	234,057,000	75·48 "
Queensland .....	72,040,000	60·31 "
South Australia .....	59,176,000	68·55 "
Western Australia .....	19,272,000	39·28 "
Tasmania .....	34,907,000	72·29 "
Commonwealth .....	683,944,000	69·65 "
New Zealand .....	152,826,000	68·82 "
Australasia .....	836,770,000	69·50 "

The improvements on the lands of the Commonwealth and New Zealand are valued at £375,515,000, which sum represents 81·41 per cent. of the value of land, ranging between 93·88 per cent. in New South Wales and 59·89 per cent. in Tasmania.

Distributing the total value of private property into the ten subdivisions usually adopted in the classification of the elements of private wealth, the following results are arrived at:—

Classification.	Commonwealth States.	New Zealand.	Total.
	£	£	£
Land .....	373,679,000	87,576,000	461,255,000
Houses and permanent improvements .....	310,265,000	65,250,000	375,515,000
Live stock .....	98,915,000	28,384,000	125,309,000
Furniture and household goods and effects .....	30,899,000	5,661,000	36,560,000
Personal effects .....	12,464,000	2,498,000	14,962,000
Machinery and implements of trade, excluding mining machinery .....	33,495,000	6,725,000	40,220,000
Shipping .....	6,359,000	1,944,000	8,303,000
Mining properties and plant .....	32,199,000	3,911,000	36,110,000
Merchandise and produce on hand .....	59,640,000	14,915,000	74,555,000
Coin and bullion .....	26,064,000	5,189,000	31,253,000
Total .....	981,979,000	222,063,000	1,204,042,000

The foregoing gives an average of £252 per inhabitant for Australasia, and £249 for the Commonwealth, which figures show a considerable reduction on those of 1890, when the average was not less than £309 per inhabitant. The results fall somewhat short of the truth, inasmuch as they do not take into account property rights, the value of which is not represented by land, buildings, machinery, etc. The case of gas companies may be cited as an example. The total value of the shares of and interests in these companies throughout Australasia is approximately £6,900,000, but in the statement of values of properties given above, the actual property of gas companies appears as value of land, machinery, plant, etc., £4,350,000, no note being taken of value of goodwill and other items which form an appreciable proportion of the value of these works. The actual selling value of the gas undertakings of Australasia is therefore £2,550,000 in excess of the value of their tangible assets, and there are many other cases where a like anomaly exists. For New South Wales it is found that the sum of £18,000,000 might be added to the valuation on this score, and probably a like amount for Victoria, but the data even for these states are imperfect, and it has not been considered desirable to take into consideration an item about which there is any uncertainty.

The distribution of the property amongst the various states is as follows :—

State.	Value of Property.	
	Total.	Per Inhabitant.
	£	£
New South Wales .....	368,778,000	258
Victoria .....	310,074,000	256
Queensland .....	119,454,000	229
South Australia .....	86,320,000	234
Western Australia .....	49,065,000	216
Tasmania .....	48,288,000	269
Commonwealth .....	981,979,000	249
New Zealand .....	222,063,000	267
Australasia .....	1,204,042,000	252

These figures must be taken with some qualification. The foregoing table shows the state wherein the property lies, but gives no indication as to the place of residence of the owners. As is well known, residents in Great Britain have very large interests in Australia and New Zealand, and persons residing in one state have large holdings in other states : thus residents of Victoria and South Australia have large investments in New South Wales, Queensland, and Western Australia, while residents of Victoria and New South Wales are largely interested in Queensland properties. If it were possible to locate the actual ownership of property throughout Australasia it would probably be found that the actual distribution is very different from the apparent distribution as shown above.

The figures available to illustrate the amount of property possessed by persons not living within the state in which their property is situated are by no means complete; indeed details of any kind are obtainable only for New South Wales, Victoria, and New Zealand.

An analysis of the information gathered by the Stamps Office in Sydney for the purpose of assessing the values of the estates of deceased persons shows that the ownership of the £38,442,357 on which stamp duty was paid during the last eight years was as follows:—

	Total. £	Proportion per cent.
New South Wales .....	30,743,268	80·0
Europe, including Great Britain .....	4,090,809	10·6
Victoria .....	2,373,900	6·2
Other States of Australia and New Zealand .....	1,076,400	2·8
Elsewhere .....	157,980	0·4
	<hr/> £38,442,357	<hr/> 100·0

It may, therefore, be assumed that 20 per cent. of the property in New South Wales is owned by persons who live outside its boundaries, about 10½ per cent. being held in Great Britain and 6 per cent. in Victoria.

In regard to Victoria, there is no direct evidence of ownership available, but the place of residence of the persons who pay income tax affords indirect evidence of great value. During the last five years for which information is available the incomes of persons paying taxation in respect of incomes exceeding £200 per annum derived from property in Victoria were £20,566,000, and of this amount £3,134,700 was enjoyed by persons who resided out of Victoria. This gives about 15½ per cent. as the apparent proportion of absentee incomes.

So far as New Zealand is concerned, there is both direct and indirect evidence. In the year 1888 the value of property assessed for property tax was £135,881,176, and of this sum £24,313,706, or 18 per cent., was returned as belonging to persons not residing in the colony. Since then the proportion of property held by absentees has greatly declined. There has of late years been no great import of capital into the colony, while during some years there have been considerable withdrawals; on the other hand, the total value of property has largely increased, so that at the present time the proportion of New Zealand property held by absentees is only about 4 per cent.

The proportion for Queensland and Western Australia is probably greater than in the other states; for South Australia and Tasmania it is probably less. Adopting a reasonable estimate for these states, it may be said that, apart from Government stock held in London, the value of property in Australia belonging to non-residents of the states in which such property is situated, is not less than £152,000,000, and in New Zealand £9,000,000. In the case of Australia, a considerable portion of this property is held by persons residing in other states than those where the property is situated, and, if allowance be made on this account, it will be found that the value of

property belonging to other than Australian residents is approximately £110,000,000. The question of the indebtedness of the Australasian states is referred to at length in another part of this chapter, and for further information the reader is referred to page 522.

#### DISTRIBUTION OF PROPERTY.

It is a somewhat prevalent practice amongst statisticians to make the valuations for probate purposes the basis of their estimates of the wealth of a country, but no reliance whatever can be placed upon the returns of values of estates assumed for probate purposes, for such returns at best only profess to give the apparent amount of property left by deceased persons, without any allowance for debts. The assumption that the average amount left by each adult who dies (during a given period) is the average amount owned by each adult alive ignores the important facts (a) that the average age of adults who die is much greater than that of those who are alive, and (b) that the accumulated wealth of an individual increases with years and is usually greatest at death. There is, however, some show of reason for using the valuation of estates for stamp-duty purposes. These valuations are far below the values for probate purposes, for while during the thirteen years ended with 1903 the probate returns in New South Wales give a total of £73,888,000, the sworn valuation of the very same estates for stamp duty was £57,991,000, or a little more than 78 per cent., and there can hardly be any doubt that all the other states would show similar discrepancies. Much greater reliance could be placed upon estimates depending upon the amount of stamp duty paid, if the ages of the persons dying were taken into consideration; but information on this point is not procurable, except at excessive trouble, and the idea of using the valuations for stamp duty for estimating the amount of wealth in the country cannot, therefore, be resorted to.

The probate returns, however, are not without considerable statistical value, as will presently appear, and the returns for the eight years ended with 1903 are, therefore, given below :—

State.	Number of Estates.	Total Value of Estates.	Average Value of Estate left by each Deceased Person leaving Property.	Corrected values to allow for overstatement of Probate Returns.
		£	£	£
New South Wales .....	20,092	48,360,869	2,407	1,877
Victoria .....	29,524	51,154,370	1,733	1,352
Queensland .....	4,886	13,588,412	2,781	2,169
South Australia .....	6,927	13,864,601	2,002	1,562
* Western Australia .....	2,002	3,240,967	1,619	1,263
* Tasmania .....	1,579	2,468,356	1,576	1,229
Commonwealth .....	65,010	132,697,665	2,041	1,592
New Zealand .....	10,223	18,568,183	1,816	1,416
Australasia .....	75,233	151,265,848	2,011	1,590

\* Seven years only.



On the preceding page it is pointed out that the probate returns in New South Wales over-state the actual value of property by some 22 per cent. : assuming that there is an equal over-statement in all the states, of which, however, there is no certainty, the figures shown in the last column of the foregoing table would represent the true average values of the estates of persons having property in each state.

By comparing the number of persons who leave property at death with the number of persons dying some idea is obtained of the proportion of the whole population possessing estates sufficiently valuable to become the objects of specific bequest. This has been done for each year since 1880, and the following table shows the number of persons per hundred dying who were possessed of property :—

State.	Proportion of Estates per 100 deaths of total population.				
	1890-94.	1885-89.	1890-94.	1895-1900.	1901-3.
	per cent.	per cent.	per cent.	per cent.	per cent.
New South Wales.....	11·0	11·6	13·2	15·15	16·69
Victoria .....	12·7	13·1	17·3	21·63	24·55
Queensland .....	6·6	8·8	10·2	10·17	10·40
South Australia .....	12·3	15·3	17·4	19·95	22·52
Western Australia .....	10·8	10·7	12·0	11·56	*12·35
Tasmania .....	9·6	11·5	11·9	10·72	*12·31
Commonwealth.....	11·1	12·0	14·1	17·23	.....
New Zealand.....	.....	.....	9·4	15·97	16·76
Australasia.....	.....	.....	14·0	16·75	.. ...

\* Two years only.

These figures show a distribution of property not to be paralleled in any other part of the world ; and in a country where so much is said about the poor growing poorer and the rich richer, it is pleasing to find that in the whole population one in six is the possessor of property, and that the ratio of distribution has been increasing with fair regularity in every province of the group. Victoria has the widest diffusion of wealth of the individual states ; South Australia comes next to Victoria ; then come New Zealand, New South Wales, Western Australia, Tasmania, and lastly, Queensland. Too much stress, however, may be laid on the apparently wider distribution of wealth in one state than in another, for it is obvious that a province with a stationary or decreasing population will naturally come out of a comparison of this kind more favourably than another with a rapidly-increasing population.

To show the wide distribution of property in these states, the following statement is even more useful than the figures just given. The comparison is made as for every hundred deaths of adult males, and for the same number of deaths of adult males and females. This latter method

is undoubtedly the proper basis of comparison, as large numbers of females are possessors of a substantial amount of property :—

State.	Proportion of Estates per 100 deaths of adult males.					Proportion of Estates per 100 deaths of adult males and females.				
	1880- 1884.	1885- 1889.	1890- 1894.	1895- 1900.	1901- 1903.	1880- 1884.	1885- 1889.	1890- 1894.	1895- 1900.	1901- 1903.
	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.	per cent.
New South Wales .....	34·6	37·5	41·2	43·4	46·1	22·3	23·8	25·8	26·3	27·9
Victoria .....	38·3	39·7	40·8	58·8	64·1	23·4	24·2	30·2	34·3	37·0
Queensland .....	18·3	23·1	28·6	26·2	25·2	13·8	16·9	20·2	18·2	17·2
South Australia .....	50·0	53·5	59·4	62·7	65·4	29·1	30·9	32·3	34·2	36·2
Western Australia .....	29·5	29·3	31·2	27·0	30·9*	19·8	19·6	21·1	20·4	22·5*
Tasmania .....	26·0	31·6	33·2	29·5	34·8*	15·8	19·4	20·1	17·2	19·3*
Commonwealth .....	34·6	37·0	42·1	46·6	..	22·0	23·4	26·1	23·5	..
New Zealand .....	..	..	27·3	42·1	44·5	..	..	16·7	25·5	26·7
Australasia .....	..	..	41·6	46·0	..	..	..	25·8	28·1	..

\* Two years only.

There is the same weakness in these figures as in those representing the values. Taking the last eight years it has been ascertained that in New South Wales three in each hundred estates, for which probate or letters of administration are granted, prove to be without assets; it is possible a like condition obtains in other states, and the proportion of persons having property is therefore somewhat overstated.

Taking the returns of estates subject to stamp duties as the basis of comparison, and making allowance for those escaping duty, such as the circumstances seem to warrant, the following table gives for each state the number of adults with property sufficiently large to be made the subject of specific bequest :—

State.	Number of Estates.
New South Wales .....	193,900
Victoria .....	230,000
Queensland .....	44,000
South Australia .....	64,500
Western Australia .....	29,800
Tasmania .....	16,300
Commonwealth .....	578,000
New Zealand .....	110,600
Australasia .....	688,600

The figures for some of the states may appear to be extraordinarily large, but they find strong support in the banking returns, especially those of the Savings Banks, given elsewhere in this chapter.

The statement that there is a wide distribution of property in Australia is to be understood in a comparative sense. The state returns, except those relating to New South Wales, are not in sufficient detail

to enable the question of distribution to be adequately discussed ; but for the state named there is much information of a very interesting character. During the year 1903 the number of adults in the state was 735,589, and of these 190,617 were possessors of property, and 544,972 were without property. As regards the distribution amongst the 190,617 property-owners, the following table throws much interesting light :—

Categories.	Number of persons with property.	Proportion of total adults in each category per 10,000.	Total value of property.	Percentage of property belonging to persons in each category.
£			£	
50,000 and over .....	987	13	130,521,100	35·4
25,000 to 50,000 .....	1,099	15	38,261,700	10·4
12,500 to 25,000 .....	2,397	33	41,125,900	11·2
5,000 to 12,500 .....	6,041	82	46,228,000	12·5
200 to 5,000 .....	120,798	1,648	107,315,600	29·1
Under £200 .....	59,295	809	5,327,700	1·4
No property .....	544,972	7,400	.....	.....
Total adults .....	735,589	10,000	368,778,000	100

It would thus appear that 987 persons—that is to say, 0·13 (about one-eighth of one) per cent.—were possessed of £130,521,000, or 35·4 per cent. of the whole property of the community ; 2,086 persons held £168,782,800, or 45·8 per cent. of the total ; and probably half the property of the state is in the hands of 3,000 persons.

There is a general assumption in dealing with this branch of statistics that few women possess property, and in dealing with property and incomes the position of women is often lost sight of. Full information regarding women's property is obtainable for New South Wales, and the following comparisons are interesting ; the figures refer to the eight years 1896 to 1903 :—

	Males.	Females.
Number of persons dying who had property	13,927	5,091
Number residing in the State of New South Wales .....	13,006	4,872
Number residing elsewhere .....	921	219
Value of property devised .....	£33,448,000	£4,994,300
Average value of estates .....	£2,402	£961
Proportion of total adult population with estates .....	31 per cent.	18 per cent.

#### IMPORTATION OF CAPITAL.

Australasia ranks among the debtor nations. In June, 1904, its people owed to persons outside its boundaries, or, more correctly speaking, there was invested in it by non-residents, and owing by its various Governments, a sum approximating to £407,290,000, or

£85 per inhabitant. Of this large sum, £156,875,000 represents the private investments, and £250,415,000 the outstanding liabilities of the states and local governing bodies. More important in some respects than the corpus of the debt are the annual payments made in respect thereof. These can be stated with some exactitude. The yearly interest paid on account of state debts to other than Australasian creditors amounts to £8,698,456, and on account of local government debts, £654,000, while the income from private investments may be stated at £8,350,000, and the absentee incomes and return on shares held in London, £400,000. These various sums make up a total of £18,102,500, which is the tribute paid yearly by Australasia to London.

It has been stated above that the gross amount of investments by non-residents is £407,290,000. This sum may be divided into what was received prior to 1871, and what was received subsequent to that date, for 1871 may be conveniently taken as the opening year of latter-day Australasian finance. At the opening of 1871 these states stood indebted to Great Britain as follows :—

	Commonwealth States.	New Zealand.	Total.
	£	£	£
On account of State and Municipalities	26,520,000	7,842,000	34,362,000
Private investments.....	33,090,000	5,504,000	38,594,000
Total .....	59,610,000	13,346,000	72,956,000

From 1871 to 1903 the increase of indebtedness was :—

	Commonwealth States.	New Zealand.	Total.
	£	£	£
On account of State and Municipalities	170,046,000	46,007,000	216,053,000
Private investments .....	114,282,000	3,999,000	118,281,000
Total .....	284,328,000	50,006,000	334,334,000

At the middle of 1904 the indebtedness of Australasia to British and foreign creditors therefore stood as follows :—

	Commonwealth States.	New Zealand.	Total.
	£	£	£
On account of State.....	188,345,000	48,049,000	236,394,000
On account of Municipalities.....	8,221,000	5,800,000	14,021,000
Private investments.....	147,372,000	9,503,000	156,875,000
Total .....	343,938,000	63,352,000	407,290,000

The figures just given are irrespective of the money brought by persons taking up their abode in Australasia; the amount of such money is very considerable, as will presently appear.

The interests of the various states are so intertwined that there is not a little difficulty in accurately determining the amount of capital imported on private account, in which each stands indebted to Great Britain. In former editions of this work such a distribution was made, but the changes that have taken place since 1893, in which year the bank crisis occurred, have been so many and so extensive, that a separation of the respective interests of the various states is well-nigh impossible.

In considering the question of the annual payment made by Australasia to Great Britain—which is almost its sole creditor—it is important to have distinctly in view the fact that part of this income is payable irrespective of production, and part only arises when there has been antecedent production. In the first of these categories is the charge on state and municipal borrowings to the amount already stated (£9,352,000), and from two-fifths to a half of the income from private investments, or, in round figures, £3,500,000—the two taken together making a sum of £12,852,000, or £2 13s. 6d. per inhabitant, which must be exported entirely irrespective of the condition of productive industry. It may here be remarked that there is another source of drainage from these states to be considered in estimating the tributary stream flowing from Australasia to England—that is, the income of absentee colonists, which for 1903 probably reached £400,000, a figure very greatly below that of previous years. The total payments to outside creditors or investors during 1903 may be summarised as follow:—

	£
Payments on account of state or municipal borrowings, and on account of private investments on which interest must be paid irrespective of the condition of production .....	12,852,000
Return dependent on antecedent production .....	4,850,000
Absentee incomes .....	400,000
<b>Total...</b> .....	<b>£18,102,000</b>

Of the sum just given, £15,508,000 is paid by the states of the Commonwealth, and £2,594,000 by New Zealand.

From these figures it will be gathered that for the states to pay their way there ought to be an excess of exports over imports equal to the interest on loans outstanding and the earnings of investments—that is to say, if no capital were introduced and none withdrawn. But equilibrium in this respect is not to be looked for. Even now there is a stream of capital coming here in excess of what is withdrawn; and in the worst years several thousand persons arrive in Australasia with the intention of settling, a large proportion of whom bring with them some little capital with which to begin their career in their new home. In the foregoing pages the expression “capital

introduced" must be taken in a qualified sense. Under the condition of equilibrium between the introduction and withdrawal of capital, as already demonstrated, Australasia would show an excess of exports representing the interest on state and other public loans and the tribute due to private investors. This excess for 1903 was about £18,000,000, and it is therefore plain that Australasia might increase its indebtedness to the extent of over eighteen millions in any one year and at the same time show an equality between its imports and exports. With this explanation in mind it will not be difficult to understand how, in spite of the fact that during the last thirty-three years the indebtedness of Australasia was increased by £334,334,000, the balance of trade during the same period was against the country to the extent of £23,279,000. Such is the operation of interest as affecting a debtor country. In further explanation of this view, it may be mentioned that out of loans aggregating £216,053,000 a sum of only £16,683,000 reached Australasia, the balance of £199,370,000 being retained in London to meet interest charges, as a set-off against a similar sum which otherwise it would have been necessary to remit from Australasia. The figures in regard to private borrowings are still more striking:—

Private borrowings in excess of withdrawals .....	£118,281,000
Capital introduced by persons taking up their abode in Australasia .....	27,341,000
Total inflow of capital .....	£145,622,000
Earnings of investments of non-residents and incomes of absentees in excess of income derived by residents in Australasia from investments abroad .....	191,902,000
Excess of outflow over inflow .....	£46,280,000

Leaving out of consideration the capital introduced by immigrants, it will be seen that since 1871 the return to investors, together with absentee incomes, has exceeded by seventy-three and a half millions the amount invested in Australasia, although of the principal sum, £118,281,000 still remains due. It may be difficult to conceive how such a result has been possible, but the difficulty will be lessened when it is remembered that at the beginning of the period embraced in the tables the Australasian states were already paying an annual tribute to private investors of £3,517,000, and, therefore, on account of debts incurred and investments made prior to 1871 something like 116 millions might have been paid away during the last thirty-three years without any reduction in the principal owing.

#### MOVEMENT OF CAPITAL.

The movement of capital towards Australasia up to the end of 1870 presented no features of unusual importance, for the total sum received, though large, representing as it did rather more than £38 per inhabitant, was not larger than might reasonably have been expected to be introduced into a country so rapidly adding to its population and so fertile in resources. During this period the investments on private account

and by the various Governments were almost equal in amount, but in the thirty years that followed, the borrowing operations of the Governments far outstripped private investments. The following table shows the borrowings of the state and on private account up to the end of 1870, and in five-year periods subsequent to that date :—

Period.	Money raised by Government or Local Bodies.	Private Investments, excluding Immigrants' Capital.	Total.
	£	£	£
Prior to 1871	34,362,000	38,594,000	72,956,000
1871-75	20,999,000	*2,392,000	18,607,000
1876-80	32,804,000	11,407,000	44,211,000
1881-85	46,944,000	37,186,000	84,130,000
1886-90	53,374,000	49,077,000	102,451,000
1891-95	28,653,000	*1,322,000	27,331,000
1896-1900	21,982,000	18,400,000	40,382,000
1901-1903	11,297,000	5,925,000	17,222,000
Total	250,415,000	156,875,000	407,290,000

\* Excess of withdrawals over investments.

In the foregoing table the importation of capital by immigrants has been neglected; if this be taken into consideration, the figures given in the next table show the full amount for the period subsequent to 1870 :—

Period.	Total Capital Introduced.
1871-75 .....	£23,010,000
1876-80 .....	48,959,000
1881-85 .....	90,504,000
1886-90 .....	107,088,000
1891-95 .....	30,705,000
1896-1900 .....	42,847,000
1901-1903 .....	19,350,000
Total .....	£362,463,000

The total indebtedness of Australasia to British investors is set down in the foregoing pages at £407,290,000, and the annual return therefrom, excluding absentee incomes, £17,702,000. The capital sum represents a weight of £84 15s. 7d. per inhabitant, and the annual return £3 13s. 8d. The apparent interest earned is, therefore, over  $\frac{1}{4}$  per cent., a rate which must be considered very favourable, seeing that £250,415,000, or three-fifths of the total, comprises Government and Municipal securities. The indebtedness of the states of the Commonwealth to British creditors amounts to £343,938,000, or £86 16s. 3d. per inhabitant, of which £188,345,000 is due by the central governments, and £8,221,000 by local bodies, while £147,372,000 represents private investments. The indebtedness of New Zealand is £63,352,000, or £75 4s. 5d. per inhabitant, of which £48,049,000 is owing by the central government of the colony, £5,800,000 by local bodies, and £9,503,000 represents private investments.

From the table given above showing the total amount of money including that brought to the country by immigrants introduced during each quinquennial period since 1870, it will be seen that the net introduction of capital during the first period was £23,010,000, and of this New Zealand received £10,707,000, or nearly one-half, principally the proceeds of Governmental borrowings, the withdrawals of private capital being nearly as large as the amount introduced. Queensland and New South Wales had, during the period, an accession of capital to the extent of £4,329,000 and £4,321,000 respectively; in the one case the sum obtained by the state was £2,389,000, and by the public, £1,940,000, while in the other case the sum introduced by the state was £2,861,000, and by private persons something less than £1,460,000. The net sum introduced into Victoria was £2,982,000, the state having imported £3,352,000, while the export of private capital was some £370,000. Tasmania received in all £1,210,000, of which £220,000 was introduced by the state, and nearly one million by private persons, which must be reckoned a very considerable sum in view of the smallness of the population of the island. Nearly the whole sum introduced into Western Australia (£400,000) was by the Government. South Australia, even so far back as 1871-75, was in a very different position to the other states in regard to private investments. During the five years the state introduced £1,722,000, but £2,661,000 was withdrawn by lenders or sent out of the state for investment. Speaking generally, the period 1871 to 1875 was marked by large public borrowing, with a very moderate influx of private capital. During this interval the importation by the various Governments amounted to £2 per inhabitant yearly, the private investments being not more than 4s. per inhabitant.

The period from 1876 to 1880 showed a net importation of capital to the amount of £48,959,000, or more than twice the sum received during the preceding five years. Of the sum named, New Zealand received £15,396,000, or slightly less than one-third, although its population was only one-eighth of the whole of Australasia. The larger portion of the money brought to New Zealand was in the shape of Government loans, which amounted to £10,884,000, the net sum received on account of private investment being £4,512,000. New South Wales stood next as regards the amount of capital received, but the borrowing by the state and local bodies only amounted to £5,458,000, or half the sum raised by New Zealand, while the private investments amounted to about £8,168,000, of which nearly two millions were received with immigrants taking up their permanent abode in the state. The total capital imported into New South Wales during the five years was £13,628,000. Queensland received £8,028,000 during the period—an enormous sum, considering that the population was not more than 150,000. The money imported by the Government was £4,980,000, and that invested by private persons, £3,048,000. The Victorian Government imported £5,229,000, while the sum sent to the state by private



investors, over and above the amount withdrawn, was £1,949,000. The South Australian Government borrowed largely during the five years, the sum raised being £5,217,000, but, as in the previous period, the sum withdrawn by investors or sent to other states for investment exceeded the capital introduced by £1,644,000. Both Tasmania and Western Australia received less capital from abroad from 1876 to 1880 than in the previous five years, the amounts being £954,000 and £204,000 respectively. The Government borrowings were £671,000 in the one case and £365,000 in the other; but in Tasmania there was an investment of £283,000 by private persons, and a withdrawal of £161,000 in the case of Western Australia. Taking Australasia as a whole, the public borrowings during 1876-80 were large, amounting to £32,804,000, or a yearly sum of about £2 12s. per inhabitant. The import of private-money continued on a more extended scale, the sum received in excess of withdrawals being £16,155,000, but nearly five millions of this sum were brought in by immigrants.

The facility with which New Zealand had been able to obtain money on loan during the five years 1876-80 was an object lesson not lost on the Australian states, for during the five years from 1881 to 1885 the sum of £46,944,000 was raised by the various Governments and local bodies; while private investors, banks, and financial institutions poured in money at an almost equal rate, the net sum received on private account being, in round figures, £43,560,000. These sums represent yearly amounts of £3 2s. 4d. and £2 18s. 1d., or together over £6 per inhabitant—a rate of increase in indebtedness quite unparalleled in any country except in the next succeeding five years of Australasian history. Of the large sum of £90,504,000 received by these states, the share of New South Wales was £30,473,000. In the light of this statement it is easy to understand how, during this same period, though one of drought and restricted production, the industrial life of the state was marked by increasing wages, shorter hours, and full employment. The importation by the state amounted to £16,066,000, and by private investors to £14,407,000, but of the sum last quoted £2,719,000 represented the money brought by immigrants and entailed no burthen on the state for future interest to be exported. This period was, so far as New South Wales is concerned, the one marked by the most lavish borrowing by the state, though it yields to the subsequent quinquennium in regard to the importation of private capital. Queensland was next to New South Wales in receipt of most money during the period under review, the Government of that state having obtained £7,094,000, while private investments amounted to £12,505,000—enormous sums for a population of a quarter of a million. Included in the private investments, however, is the sum of £1,927,000 introduced by immigrants taking up their abode permanently in the state. The imports of capital into New Zealand during the quinquennium were still very heavy, amounting to £7,442,000 by the Government, and £10,475,000 on private account, or £17,917,000 in all. Of the private

importation, £587,000 accompanied the owners who settled in the colony. The capital received by Victoria, which in the two preceding periods amounted to very moderate sums, now rose to £13,002,000, viz., £8,519,000 on account of the Government, and £4,483,000 by private investors. The South Australian Government in 1881-85 was still a large borrower, £5,895,000 being raised and expended during that time, while, contrary to the experiences of previous periods, there was an importation on private account of £1,000,000. Tasmania, also, considerably increased its borrowings, the state raising £1,465,000 in the five years, while £425,000 was sent for investment or was received with the owners. The borrowing of the Western Australian Government for 1881-85 amounted to £463,000, but not more than £265,000 was received for private investment, or in all £728,000.

The next period, 1886-90, was marked by very extraordinary features. The average population of Australasia was 3,540,000, yet during the short space of five years the various states governing these people raised and expended £53,374,000, while an additional sum of £53,714,000 was received for investment on private account, or was introduced into the country by persons who made it their abode. But even more astonishment will be evinced on considering the detailed figures for each state. Of the large total received by the various states, considerably more than one-half—£54,690,000—was obtained by Victoria, and, as the population during the five years under review was 1,070,000, the inflow of capital amounted to over £51 per inhabitant. The state and local bodies borrowed and disbursed £16,987,000, which was the largest expenditure from the proceeds of loans that any state contrived to crowd into the short space of five years. The private capital introduced was £35,792,000, and the sum brought by persons taking up their abode in the country was £1,911,000. These figures afford a sufficient clue to the astounding impetus which trade received during these years, and the corresponding rise in land values. New South Wales, though not the recipient of so much money as its southern neighbour, nevertheless contrived to obtain £28,145,000—a far larger sum than could be conveniently absorbed in five years, especially as in the like preceding period £30,000,000 was absorbed. The capital introduced represented £11,571,000 of Government borrowings, £15,187,000 of private investments, and £1,387,000 brought by persons making New South Wales their home. The Queensland Government was also a large borrower, its loan expenditure during the five years, 1886-90, being not less than £9,581,000. The private capital introduced, however, fell off largely. The sum received, allowing for withdrawals to the amount of £3,360,000, was £1,574,000. The flow of private money to New Zealand practically ceased during the period now under consideration, amounting only to £632,000, as compared with £10,475,000 in the preceding five years; but Government borrowings still continued, and a sum of £6,560,000 was raised and expended. South Australia occupied an exceptional position, for though the Government introduced some £5,693,000, there

was a large withdrawal of private capital, or, as it may be, an export of capital for investment in other states, so that the net import on public and private account amounted to £1,345,000. Tasmania, with its population of 150,000, was well in the struggle for British investments, the State importation being £2,557,000, and the investment by private persons, £570,000 ; of this last sum £85,000 was introduced by persons taking up their abode in the state. It was about this period, too, that Western Australia began to attract attention as a field for investment, for over and above the sum of £425,000 introduced by the Government, about £1,009,000 was invested by private persons, perhaps one-fifth of the amount being accompanied by the investors themselves.

The recitation of borrowing just given brings the financial history of the Australias down to the close of 1890. Two years more of credit and investment remain to be traced, after which came the collapse of credit, and the events of May, 1893, still fresh in the public memory. That two years elapsed after the close of 1890 before Australasian public credit in London finally collapsed is true only of Victoria, and in a modified sense of New South Wales, Western Australia, and Tasmania. These states continued to be the recipients of British money, but private investments were—excepting in the case of Victoria—on a minor scale. Victoria received fresh capital to the extent of £8,834,000, of which amount only £464,000 was brought in by immigrants. New South Wales received from private investments over £3,000,000, but the withdrawals were also extensive, so that the net amount of capital invested was only £1,711,000. Western Australia received £952,000, of which £408,000 was accompanied by the owners. Tasmania received £792,000, and of this about £271,000 was introduced by permanent residents. Withdrawals of private capital were already in progress before the close of 1890, and were continued from South Australia, but to a less extent than in the preceding period. New Zealand ceased to receive any private money, while Queensland, for the first time in its history, showed a net withdrawal of capital, the amount of which during the two years was £2,011,000, but as the state had introduced £1,917,000, there was an actual withdrawal of £3,928,000. During the two years 1891 and 1892 the total capital imported into Australasia was £25,083,000, and of this £18,786,000 was introduced by the various Governments and local bodies.

During the three years which followed there was a withdrawal of private capital from Australasia to the extent of £7,619,000, so that in spite of the importation during the years 1891 and 1892, the quinquennium showed a net withdrawal of £1,322,000. There was during the period a movement of £20,088,000 apparently introduced, and £21,410,000 withdrawn ; but this movement was mainly between the states themselves, and not between Australasia and Great Britain. Looking at the figures in detail, it would seem that there was an importation in excess of withdrawals of £14,686,000 into Victoria, and

£2,382,000 into Western Australia. So far as Victoria is concerned, this introduction of money was not by way of investment; it was merely the recall by the large financial institutions of their capital from other states. This withdrawal affected New South Wales and Queensland most largely; £10,162,000 was withdrawn from the latter province during the five years, and it is a great tribute to its resources and stability that this withdrawal should have been effected with so little disturbance to its financial position. New South Wales lost £4,481,000, part of which represents deposits gathered in London and withdrawn during the panic, and part transference of capital by branch institutions to the head offices in Melbourne. From New Zealand £2,143,000 was withdrawn, and from South Australia £1,698,000. The withdrawal in nearly all cases was a silent one; and it was only when a financial institution absolutely failed and the courts were invoked to consent to the removal of assets that the community at large realised the process that had been going on.

Taking the whole period of five years the net amount introduced was £30,705,000, the various governments obtaining £28,653,300 from abroad, while private investors withdrew £1,322,000, but as immigration did not entirely cease it is estimated that £3,374,000 was introduced during the period by persons who took up their permanent abode in the country. The respective shares of the state Governments in the money obtained in London on loan was as follows :—

New South Wales .....	£11,655,000
Victoria .....	5,430,000
Queensland .....	2,996,000
South Australia .....	638,000
Western Australia .....	2,291,000
Tasmania .....	1,835,000
Commonwealth .....	24,845,000
New Zealand .....	3,808,000
Australasia .....	£28,653,000

The withdrawal from Australia practically ceased in 1895, but during the next five years the movement of capital between the States and Europe was much involved, and cannot be traced very definitely. In 1896 and 1897 there was a considerable amount of money introduced into Western Australia, where the gold-fields claimed much attention from British mining speculators. In the same years, about £1,000,000 of private capital was brought to New South Wales; a large part of this, however, was money that had been withdrawn during the period following the bank crisis. In 1898 and the two following years, considerable sums were also brought to New South Wales, so that in the five years ending with 1900 the State received altogether some £10,000,000 of private capital. During these five years the imports and exports of Victoria were practically equal in amount, and as the payments on behalf of the Government in London exceeded its borrowings by £7,350,000, and as there were also large

payments on private account, this equality could only have been brought about by private borrowing. Careful estimates place the money so introduced at about £10,600,000. This money, however, may not have been required for investment in Victoria, as Melbourne is the headquarters of many important financial institutions, whose interests extend over the whole of Australia. A certain amount was also sent to Tasmania for investment during these five years; on the other hand the process of withdrawing capital from Queensland was continued, and it is probable that an average of £1,500,000 a year left that state. During the five years, 1896-1900, the various state Governments increased their indebtedness to outside creditors by £14,735,000, more than half of which (£7,600,000) was obtained by Western Australia. New South Wales obtained £2,650,000; Queensland, £2,900,000; South Australia, £985,000; and Victoria, £600,000. The New Zealand Government also borrowed freely, and increased its indebtedness to the London market, including small sums borrowed by local bodies, by £7,187,000. Owing to its exceptionally prosperous condition, the colony was able to repay £4,450,000 to its private creditors. It has been claimed in some quarters that this withdrawal of capital from New Zealand was the voluntary act of investors dissatisfied with the trend of New Zealand legislation. Be that as it may, the fact remains that at the present time the indebtedness of New Zealand to various non-resident creditors is less than £10,000,000 sterling, and during the whole period over which the process of withdrawal has extended, the industries of the colony have undergone rapid expansion.

Taking Australia and New Zealand together, during the five years 1896-1900 the introduction of money on government account amounted to £21,982,000; besides this £18,400,000 was invested by persons living outside Australia in excess of money withdrawn, while the introduction of capital by immigrants amounted to £2,465,000.

During the two years, 1901-1902, the governments of the Australian States obtained £7,695,000 from the London market, New South Wales, Western Australia and Queensland being the chief borrowers. In these two years also considerable sums were sent to the country for investment, the introduction of capital in excess of withdrawals amounting approximately to £7,570,000, while the money brought by immigrants during the same period was estimated to have been £1,140,000. In 1903 the New South Wales Government obtained £2,200,000 from London, and Queensland £750,000. No private capital was introduced into the Commonwealth during the year, and there was an excess of emigration to the extent of 7,065 persons, the capital withdrawn by these amounting probably to £400,000. The New Zealand Government continued its borrowing policy and £4,390,000 was obtained by it in London. The repayment of British money on private investment continued, and it is estimated that £1,645,000 was withdrawn from the colony during the two years on this account. In 1903 the only

capital introduced into New Zealand was that brought with them by the 11,300 immigrants who came to the colony during the year. This capital has been estimated at £550,000. There were no withdrawals.

In speaking of the British capital invested in Australasia no mention has been made of the amount lost by the owners in unprofitable speculations, of which there have been not a few. From the nature of the case the sum total of these losses cannot be stated with any degree of accuracy; but there is no reason to suppose that the proportion is greater than would have occurred in like investments if made in the British Isles.

#### INCOME.

The incomes received by the people of Australasia can be determined with considerable accuracy, as the information available for such an estimate is fairly extensive. For New South Wales, Victoria, South Australia, and New Zealand there are income-tax figures, for Queensland and Tasmania particulars of collections under dividend and income-tax acts, and for several of the states very full returns relating to land-values. Besides these direct sources of information there are official estimates of incomes for New South Wales and New Zealand. Excluding the revenues of the various state governments, the yearly income derived from Australasia amounts to £227,882,000, and of this sum local residents draw £209,780,000, and British investors and absentees £18,102,000, and of this last-mentioned sum £9,352,000 represents income derived from Government or municipal stocks, and £8,750,000 the amount from private sources. Of the total income (£227,882,000) the states of the Commonwealth claim £186,771,000, and New Zealand £41,111,000, the incomes of non-residents in each case being £15,508,000 and £2,594,000.

Leaving out of consideration the income drawn by debenture-holders in England, it would appear that the income derived from private sources for each of the states was:—

State.	Total.	Per Inhabitant.
New South Wales .....	£64,387,000	£45·2
Victoria .....	54,169,000	44·8
Queensland .....	21,035,000	40·6
South Australia .....	14,448,000	39·3
Western Australia.....	17,631,000	79·7
Tasmania .....	7,893,000	44·5
Commonwealth .....	£179,563,000	£45·8
New Zealand .....	38,967,000	47·5
Australasia .....	£218,530,000	46·1

The amount of income derived from private sources (that is to say, all incomes except payments made by the various governments and local bodies to their debenture-holders), is thus £218,530,000, and of this amount £8,750,000, or slightly over 4 per cent., is drawn by non-residents.

Dividing the incomes into two categories, viz., those below and those above £200 a year, very interesting results are obtained; the figures do not include the sum of £9,352,000 paid to non-resident debenture-holders and holders of local government stock :—

State.	Total Incomes £200 and over.	Total Incomes under £200.
New South Wales .....	£19,236,000	£45,151,000
Victoria .....	17,305,000	36,884,000
Queensland .....	5,356,000	15,679,000
South Australia .....	3,957,000	10,491,000
Western Australia .....	4,364,000	13,267,000
Tasmania .....	2,192,000	5,701,000
Commonwealth .....	£52,410,000	£127,153,000
New Zealand .....	9,021,000	29,946,000
Australasia .....	£61,431,000	£157,099,000

The incomes of the various states depend in a very large measure upon the number of adult male workers in those states, and the variations in the rates per inhabitant disclosed by the foregoing table, are largely due to the different proportions which these workers form of the general population. Amongst the Australian States Victoria and Western Australia stand at the extremes, the former with 307 adult males per thousand of the population, and the latter with 477 per thousand, and it is, therefore, easy to understand how, in such circumstances, the revenue per head of population in Western Australia so greatly exceeds that of Victoria.

In the edition of this work, published in 1900, attention was directed to the smallness of the aggregate incomes in Victoria subject to taxation—that is, incomes in excess of £200. In the year then reviewed the total of such incomes was £10,080,000, and the opinion was hazarded that the amount was greatly under-stated. Confirmation of this opinion was given by the increase, in the year immediately following, of the amount of taxable incomes, and in the present calculation the Victorian incomes over £200 have been set down at £17,305,000, which is an increase of nearly 71·7 per cent.

The incomes drawn from investments by persons non-resident amount to £8,350,000, and about £400,000 is spent by Australians resident in Europe. Of the first-mentioned amount, £2,565,000 is drawn from New South Wales, or nearly 4 per cent. of the total incomes of the state apart from payments to debenture-holders; £1,600,000 is drawn from Victoria, or nearly 3 per cent.; £1,100,000 from Queensland, or 5½ per cent.; £375,000 from South Australia, or 2½ per cent.; £2,300,000 from Western Australia, or 13 per cent.; and £360,000 from Tasmania, or 4½ per cent. The total drawn from the Commonwealth States was £8,300,000, or 4½ per cent. of the total incomes apart from payments to debenture holders. From New Zealand the amount was £450,000 or less than 1½ per cent. As

pointed out elsewhere in this volume the people of New Zealand are rapidly paying off their private indebtedness to the British moneylender, and as the process of repayment has been accompanied by an increase in the private wealth of the colony and in the output of its industries, it must be accepted as a satisfactory evidence of progress. In the case of some of the states the absentee income derived from them, is largely counterbalanced by incomes derived from other states. This is especially true of South Australia and Victoria. The absentee incomes of the first-named are equalled, if not exceeded, by the revenue which its residents derive from investments in Western Australia, New South Wales, and Queensland; while as regards Victoria there is evidence that New South Wales makes to the southern state an annual payment of from £480,000 to £600,000, according to the character of the season, while Queensland and Western Australia also make large payments, so that the excess of absentee incomes over the earnings of Victorian capital abroad is not very great.

The detailed figures of the incomes of the people, read with those in regard to property and production, admit of several very interesting comparisons as to the relation of one to the other. The following table shows the percentage which the incomes drawn in each state bear to the value of private wealth, the incomes being distinguished into total incomes and those over £200 a year:—

State.	Percentage which Total Incomes bear to value of private property.	Percentage which Incomes over £200 bear to private property.
New South Wales .....	17·5	5·2
Victoria .....	17·5	5·6
Queensland.....	17·6	4·5
South Australia .....	16·7	4·6
Western Australia .....	35·9	8·9
Tasmania .....	16·4	4·5
Commonwealth .....	18·3	5·3
New Zealand.....	17·6	4·1
Total .....	18·2	5·1

Taking Australia as a whole, the assessment placed upon private property appears to be about five and a half times the annual income; Western Australia being the only state which departs in any marked degree from this proportion. In that state the assessment is about two and four-fifths times, and this low ratio is accounted for by the circumstance that a large proportion of the private property of the state is represented by gold-mines, and the value of a gold-mine is rarely large compared with the payments made for wages and other services connected with its working.

As the fair distribution of the income of a country is of more importance to the population at large than the aggregate amount of all incomes, it is interesting to know what proportion of the population enjoys large incomes, and if the incomes of the great mass of the



population are affected by the accumulation of large incomes in few hands. In the present condition of statistics no great amount of light can be thrown upon the question, although some interesting facts may be gleaned from the particulars already given. The unit for the most useful comparison in regard to incomes is the bread-winner; but as there are both male and female bread-winners it is necessary to take into account the less commercial and productive value of women's work compared with men's. Taking the productive employments of New South Wales and Victoria as a basis, it is found that the earnings of thirty-six men equal those of one hundred women, and if this wage efficiency holds good throughout Australia the work of the 1,560,784 male and 422,123 female bread-winners at the census of 1901 would be equivalent to that of 1,712,748 male bread-winners alone; and comparisons of earnings should therefore be made on the basis of this last number and not on the total 1,982,907 of male and female bread-winners taken together. There is, however, another consideration. Australia has not yet developed a class of independent women workers. It is true there are considerable numbers of women who are the main bread-winners of their families, but as a rule the earnings of the woman go to supplement the earnings of the head of the family, usually the house-father, and there are some cogent reasons why the comparison of earnings and population should be made on the basis of the number of families to be supported. This, for practical purposes, may be taken as indicated by the number of male bread-winners, and on such basis the following table has been compiled. The calculations refer to the incomes and population of the census year :—

State.	Average income Male Bread-winners whose income is less than £200 a year.	Average income Male Bread-winners whose income exceeds £200 a year.	Proportion of Male Bread-winners whose income exceeds £200 a year.
	£	£	
New South Wales.....	103	658	6·6 per cent.
Victoria .....	103	645	6·1 "
Queensland.....	103	569	4·5 "
South Australia.....	97	317	11·3 "
Western Australia .....	137	726	5·9 "
Tasmania.....	104	561	6·6 "
Commonwealth .....	105	530	7·2 "
New Zealand.....	107	575	5·3 "

This statement forms a corrective to the table on page 530 giving the average income per inhabitant. In that table South Australia shows the smallest incomes of any of the states, viz., £39·3, as compared with an average of £45·3 for New South Wales and £40·6 for Queensland; it would now appear that compared with the male bread-winners the average income below £200 a year is equal in Victoria to what it is in Queensland and in New South Wales, viz., £103, while in South Australia it is £97. As regards incomes over £200, the

return for Victoria (£645) is largely in excess of the average for the Commonwealth; but for South Australia the average (£317) is much below that of the other states, although there is compensation in the fact that such incomes are widely distributed; thus in South Australia 11·3 per cent. of all incomes exceed £200 as compared with 4·5 in Queensland, 5·9 in Western Australia, and 6·6 in New South Wales and Tasmania, and the comparison would be still more favourable to South Australia if the absentee incomes drawn from the other states could have been brought into consideration and added to the incomes of the creditor states, while being correspondingly deducted from the debtor states. In any case, it must be a source of great satisfaction to South Australia that so large a proportion of its breadwinners enjoy superior incomes.

As the income of every country depends largely upon its production, a comparison of incomes and production is interesting. No general law can be laid down as to the relation between the two, but it will be found that the more various and developed the industries the greater will be the income which results from production.

The following is the ratio of the incomes obtained in each state to the value of production in that state, as set out on page 1018. It will be seen that in each case the incomes exceed the production: in Western Australia, however, the excess is only 14 per cent., whereas in the case of Victoria the excess is nearly 74 per cent. The low percentage of income given off by production in the case of Western Australia is explained by the fact that of the total production of £15,497,000, the value of gold won reached nearly £8,771,000, and the income given off, so to speak, by this production is not very great. The winning of gold in some instances costs as much as the gold is worth, and there is a heavy expenditure on the development of mines before any yield is obtained. Further, there is very little income derived from the carriage, handling, and shipment of gold, whereas in most other forms of produce the charges attendant on all these processes are considerable, and make up the large margin which is sometimes found between the cost at the point of production and the export value of the same commodity.

State.	Percentage which Total Incomes bear to value of pro- duction.	Percentage which Incomes over £200 bear to production.
New South Wales .....	158·2	47·3
Victoria .....	173·5	55·4
Queensland .....	144·0	36·7
South Australia .....	136·3	37·3
Western Australia .....	113·8	28·2
Tasmania .....	157·0	43·6
Commonwealth .....	152·6	44·5
New Zealand .....	129·6	30·0
Australasia .....	147·9	41·6

## DEFENCE.

THE colonists of Australasia have always manifested an objection to the maintenance of a large standing army, and shown a disposition to rely mainly upon the patriotism and valour of the citizens for their own defence. As the Commonwealth, however, possesses a more or less complete system of fortifications armed with expensive ordnance, which requires a more regular and constant attendance than could well be bestowed by those who devote only a portion of their time to military affairs, it is necessary that there should be in each of the states a small permanent military force, consisting for the most part of artillery and submarine miners, whose chief duty is to man the fortifications and keep the valuable armaments therein in a state of efficiency, to be ready for any emergency. At the same time, it is expected that they will prove the nucleus for an effective defence force if ever hostilities should unfortunately occur. The responsibility for the defence of Australia now lies with the Federal Government, and, since it assumed control the forces have been reconstructed and reorganised, while the expenditure has been considerably reduced.

Under the present scheme, which is in accordance with the provisions of the Defence Act of 1903, which came into operation on the 1st March, 1904, the organisation of the forces is as follows:—

1. A Permanent Cadre Force, which includes an administrative and instructional staff, the Royal Australian Artillery Regiment and small detachments of Engineers, Army Medical Corps, and Army service Corps, &c. The senior officers are the principal commanders, administrative staff, and instructors during peace, and will be the chief leaders and staff officers in war. This force will also serve as a valuable stiffening in time of war.

- (2) A Field Force comprising six brigades of light horse and three brigades of infantry, who, in a national emergency, will undertake active operations in the field for the defence of the Commonwealth as a whole. These troops are militia, and are divided among the six states on a population basis.

- (3) A Garrison Force which provides the necessary garrisons, and a small district reserve for the local defence of each of the six states.

The troops comprising this branch are mainly volunteers and are unpaid. It is proposed, however, that all the Light Horse Artillery, Engineers, and Departments allotted to garrison service, who are not already militia, shall be termed militia, and be paid accordingly. Under the system as outlined above, the permanent staff will be reserved mainly for administrative and staff duties in peace, and for special duties in time of war. The principle is throughout aimed at that the militia and volunteer officers should carry out in times of peace the duties which would be thrust on them in time of war. Under the Act it is provided that members of the military forces, unless they voluntarily agree to do so, shall not be liable to serve outside the limits of Commonwealth territory.

The following table shows the strength of the military forces maintained in each state as at 30th June, 1904. The total number of men of military ages (from 20 to 40 years) in Australia was ascertained at the Census of 1901 to be 644,500; the total forces shown below (19,880) amount to 3·1 per cent. of the number capable of bearing arms, which is an extremely small proportion. In New Zealand the proportion is 10·1 per cent.

State.	Paid.	Militia or Partially Paid.	Volunteers.	Total Forces.
Headquarters Staff .....	26	.....	.....	26
New South Wales.....	491	4,537	2,257	7,285
Victoria .....	374	4,360	1,000	5,734
Queensland .....	230	2,439	161	2,830
South Australia.....	55	1,175	469	1,699
Western Australia .....	60	425	769	1,254
Tasmania .....	42	.....	1,010	1,052
Commonwealth .....	1,278	12,936	5,666	19,880
New Zealand .....	544	.....	12,634	13,178
Australasia .. .....	1,822	12,936	18,300	33,058

Included in the 544 paid in New Zealand there are 189 officers of the New Zealand Militia Active List who have nearly all seen service in South Africa. There is no partially-paid force in the colony, but, subject to certain limitations, all males of ages 17 and upwards may be called upon for service in time of national emergency.

The relative strength of the various arms in the Commonwealth states may be summarised as follows:—

Staff, administrative and educational .....	272
Artillery—	
Field .....	1,073
Garrison .....	1,858
Engineers .....	663
Mounted troops .....	4,478
Infantry .....	10,627
Army Service Corps .....	204
Army Medical Corps .....	528
Veterinary department .....	16
Ordnance department .....	117
Pay department .....	44
Total.....	19,880

The Defence Act provides that the reserve forces shall consist of (a) members of rifle clubs constituted in the manner prescribed, and (b) persons who, having served in the active forces or otherwise as is prescribed, are enrolled as members of the reserve forces. Power is also given for the establishment and maintenance of Cadet Corps consisting of (a) Boys over twelve years of age who are attending school, and (b) Youths between fourteen and nineteen years of age who are not attending school, and who will form a Senior Cadet Corps. Cadets are not liable for active service. All military cadet corps in a military district are under the orders of the District Commandant of that district. In March, 1904, under instructions from the Minister of Defence, a special committee was appointed to report on the organisation of the cadet system. The committee recommended that the cadets should be organised under the Commonwealth military system, but in conjunction with the Education Departments of each state. The full development of the system is, however, at present retarded by lack of funds. The following table shows the strength of reserves, rifle clubs, and cadet corps on the 30th June, 1904:—

State.	Reserve of Officers and Unattached List.	Rifle Clubs.	Cadets.
New South Wales.....	199	2,931	3,969
Victoria .....	198	18,436	4,068
Queensland .....	94	2,867	901
South Australia.....	54	3,412	...
Western Australia .....	26	1,075	.....
Tasmania .....	49	.....	164
Commonwealth .....	620	28,721	9,102
New Zealand .....	77	2,546	2,826
Australasia.....	697	31,267	11,928

In addition to the military forces enumerated, there are in four of the states small corps of Naval Volunteer Artillery, or partially-paid forces of a similar character, capable of being employed either as light artillery land forces or on board the local war vessels. The strength of these marine forces on the 30th June, 1904, was as follows:—

State.	Permanent Forces.	Militia.	Total.
New South Wales.....	3	335	338
Victoria .....	102	97	199
Queensland .....	37	353	390
South Australia.....	20	105	125
Commonwealth .....	162	890	1,052

Under the Defence Act of 1904, members of the Naval Forces may be required to serve either within or beyond the limits of the Commonwealth for the purpose of training, or in time of war for the defence and protection of the Commonwealth and of the several states.

Including the reservists and members of rifle clubs, the combined forces of the Commonwealth would be about 50,000 strong, and of these about three-fifths could be mobilised in a very short time in any one of the states of Queensland, New South Wales, Victoria, or South Australia. As shown above, some of the states have also cadet companies, consisting of youths attending school, who are taught the use of arms so as to fit them, on reaching manhood, for taking a patriotic share in the defence of their country.

The outbreak of hostilities with the Boers in October, 1899, served to demonstrate the strength of the loyalty of these states to the mother country. From all parts of Australasia members of the various defence forces, as well as civilians, volunteered for service with the Imperial troops in South Africa. The total number of men despatched in the various contingents was 22,928. The table below shows the number of men and horses sent from each state:—

State.	Officers.	Non-commissioned Officers and Men.	Horses.
New South Wales .....	327	6,000	5,877
Victoria .....	183	3,393	3,878
Queensland .....	143	2,756	3,065
South Australia .....	78	1,450	1,524
Western Australia .....	63	1,160	1,044
Tasmania .....	35	827	725
Commonwealth .....	829	15,586	16,133
New Zealand .....	342	6,171	6,662
Australasia .....	1,171	21,757	22,795

In addition to the above, several special service officers were, at the request of the colonial Governments, attached to the British troops for the purpose of gaining experience, and 14 nurses were despatched from New South Wales.

The states again offered to assist Great Britain on the outbreak of hostilities in China. The Imperial Authorities accepted the offer, and contingents of naval volunteers were despatched from New South Wales and Victoria numbering 260 and 200 men respectively, while South Australia equipped and sent the gunboat Protector.

#### NAVAL DEFENCE.

The boundaries of the Australian Naval Station have been defined as follow :—From 95° E. long. by the parallel of 10° S. lat. to 130° E. long. ; thence north to 2° N. lat., and along that parallel to 136° E. long. ; thence north to 12° N. lat., and along that parallel to 160° W. long. ; thence south to the Equator, and east to 149° 30' W. long. ; bounded on the south by the Antarctic Circle ; and including the numerous groups of islands situated within the limits specified.

The defence of Australasia and its trade is entrusted to ships of the Imperial navy, under an agreement entered into between the British Government and the Governments of the Commonwealth and New Zealand. The agreement provides that the naval force on the Australian Station shall consist of not less than—

- 1 Armoured cruiser, first-class ;
- 2 Second-class cruisers ;
- 4 Third-class cruisers ;
- 4 Sloops ;

and of a Royal Naval Reserve of 25 officers and 700 seamen and stokers.

This force is under the control and orders of the Naval Commander-in-Chief on the Australian Station. One of the ships is to be kept in reserve, and three are to be partly manned and used as drill ships for training the Royal Naval Reserve, the remainder being kept in commission and fully manned. The three drill ships and one other vessel are to be manned by Australians and New Zealanders as far as procurable, paid at special rates, and enrolled in proportion to the relative population of the Commonwealth and New Zealand, but the vessels are to be officered by officers of the Royal Navy and of the Royal Naval Reserve. In order to insure the inclusion of Australian-born officers in the Royal Navy, 8 nominations for cadetships are to be given annually in the Commonwealth and 2 in New Zealand. In consideration of the services rendered, the Commonwealth is to pay five-twelfths and New Zealand one-twelfth of the total annual cost of maintenance, provided that the total amount to be paid in one year shall not exceed £200,000 and £40,000 respectively. In reckoning the total annual cost, a sum equal to 5 per cent. on the prime cost of the ships composing the naval

force is to be included. The agreement covers a period of ten years, and only terminates if notice to that effect shall have been given two years previously, viz., at the end of the eighth year, or at the end of any subsequent year, and then two years from such date. In time of peace one drill ship and one other cruiser are to be stationed in the waters of New Zealand as their headquarters, but they may be temporarily removed if any emergency arises to justify such a course. The base of the naval force is to be the ports of Australia and New Zealand, and their sphere of operations the waters of the Australia, China, and East Indies Stations where the Admiralty believe they can most effectively act against hostile vessels which threaten the trade or interests of Australia and New Zealand. No change in this arrangement can be made without the consent of the Governments of the Commonwealth and New Zealand, and nothing in the agreement shall be taken to mean that the naval force named therein shall be the only force used in Australasian waters should the necessity arise for a larger force. The agreement was embodied in the Naval Agreement Bill and passed by the Commonwealth Parliament, being assented to on the 28th August, 1903. It has also been passed by the New Zealand Parliament. Prior to this agreement the defence of the Australasian coast was entrusted to the British ships on the Australian Station and the Australasian Auxiliary Squadron.

The vessels of the fleet which are on service are detailed below.

Name.	Date of Launch.	Load Displacement.	Draught.	Length.	Beam.	Indicated Horse-power.	Measured Mile Speed.	Armament.	Boat Complement.
Euryalus ..	Year. 1901	Tons. 12,000	ft. 26 9	ft. 440	ft. 60 6	21,000	knots. 21.5	Two 9.2-in., 12 6-in (14 12-pr., 3 3-pr.) q., 2 M., 28 T.	745
Phoebe ....	1890	2,575	15 6	265	41 0	7,500	19.3	(Eight 4.7, 8 3-pr.) q., 1 L.M., 4 M., 4 T.	219
Katoomba ..	1889	2,575	15 6	265	41 0	7,500	19.3	(Eight 4.7-in., 8 3-pr.) q., 1 L.M., 4 M., 4 T.	216
Mildura ....	1889	2,575	15 6	265	41 0	7,500	19.3	(Eight 4.7-in., 8 3-pr.) q., 1 L.M., 4 M., 4 T.	216
Tauranga ...	1889	2,575	15 6	265	41 0	7,500	19.3	(Eight 4.7-in., 8 3-pr.) q., 1 L.M., 4 M., 4 T.	216
Walleroo ...	1890	2,575	15 6	265	41 0	7,500	19.3	(Eight 4.7-in., 8 3-pr.) q., 1 L.M., 4 M., 4 T.	216
Psyche ....	1893	2,135	15 10	309	36 6	5,000	20.3	(Eight 4-in., 8 3-pr.) q., 3 M., 2 T.	219
Pylades ....	1884	1,420	16 11	300	38 0	1,510	12.6	Fourteen 5-in., 1 L.M., 4 M., 4 T.	171
Clio .....	1903	1,070	11 6	125	33 0	1,400	13.5	(Six 4-in., 4 3-pr.) q., 3 M., 4 T.	113
Mutine .....	1900	990	13 1	150	33 0	1,400	13.4	(Six 4-in., 4 3-pr.) q., 2 M., 4 T.	105
Torch .....	1894	960	13 1	180	32 6	1,100	13.4	(Six 4-in., 4 3-pr.) q., 2 M., 4 T.	102
Cadmus .....	1903	1,070	11 6	125	33 0	1,400	13.5	(Six 4-in., 4 3-pr.) q., 3 M., 4 T.	110
Penguin.....	1876	1,130	14 0	180	38 0	700	10.1	One L.M., 2 M., 4 T.	137

The Euryalus is classified as a first-class armoured cruiser. The other vessels are unarmoured, those in the list from the Phoebe to the Pylades being classed as third-class cruisers. The Clio, Mutine, Torch, and Cadmus are sloops, while the Penguin is a surveying vessel.



Sydney is the headquarters of the fleet, and ranks as a first-class naval station, extensive repairing yards and store-houses having been provided for the accommodation of ships of war.

The Commonwealth possesses a number of vessels which are available for harbour defence in Victoria, Queensland, and South Australia. The names and classes of the vessels in Victoria are :—

Name.	Class.	Displacement.	Armament.
Cerberus .....	Armoured turret ship (twin screw).	tons. 3,480	Four 10-in. 18-ton M.L.R., six 6-pdr. Q.F., four 1-in. Nordenfeldt—4 barrels.
Countess of Hopton.	First-class steel torpedo boat.	120	Three 14-in. Mark IX R.G.F. torpedoes, and two 2-barrel Nordenfeldt 1-in. M. guns.
Childers .....	do do ..	63	Two 14-in. Flume torpedoes, and two 1-pdr. Hotchkiss Q.F. guns.
Nepesin .....	Second-class steel torpedo boat.	12	Two 14-in. Mark IV Flume torpedoes.
Lonsdale .....	do do ..	12	do do do
Gordon .....	Wooden torpedo boat ..	12	Two 14-in. Mark IV Flume torpedoes, three 2-barrel 1-in. Nordenfeldt guns.

There are two vessels available for harbour defence in Queensland, and particulars of their armament are shown below :—

Name.	Class.	Displacement.	Armament.
Gayundah .....	Steel gunboat (twin screw)	Tons. 300	One 8-in. B.L., one 6-in. B.L. Armstrong, two 8-pdr. 1½-in. Nordenfeldt, one 1-in. four-barrelled Nordenfeldt, one Maxim.
Paluma .....	do ..	300	One 6-in. B.L.; two 5-in. B.L.; two 1½-in. Q.F. Nordenfeldts; one 1-in. four-barrelled Nordenfeldt; one 0·45-in. five-barrelled Nordenfeldt.

In South Australia one twin-screw steel cruiser, the Protector, of 920 tons, is available. The armament of the Protector consists of one 8-in. 12-ton B.L., five 6-in. 4-ton B.L., and four 3-pdr. Q.F. This vessel has lately seen service in the war with China, and was reported by the Commander-in-Chief of that station to be "an efficient and well-kept man-of-war, reflecting credit on captain, officers, and men." There are also some large arms available in South Australia, comprising two 6-in. 5-ton B.L. guns, intended for use in an auxiliary gun-vessel, and five Gatling machine guns for boat or land service, while in Tasmania there is one torpedo boat with dropping gear for Whitehead torpedoes. New Zealand possesses three Thorneycroft torpedo boats and two steam launches fitted for torpedo work.

## COST OF DEFENCE.

The following table shows the expenditure by the Commonwealth Government on naval and military defence, exclusive of expenditure under the Naval Agreement Act, for the year ended 30th June, 1904 :—

State.	Amount. £	Per head. s. d.
New South Wales .....	270,331	3 10
Victoria.....	228,768	3 9
Queensland .....	100,339	3 10
South Australia .....	66,323	3 7
Western Australia .....	43,093	3 11
Tasmania .....	33,677	3 9
Commonwealth .....	£742,531	3 9

The expenditure in each state, for the same period under the terms of the Naval Agreement Act, is given below :—

State.	£
New South Wales .....	88,375
Victoria .....	41,947
Queensland .....	18,030
South Australia.....	22,832
Western Australia .....	13,961
Tasmania .....	11,081
Commonwealth.....	£196,226

The annual contribution is £200,000. The amount paid includes an adjustment for arrears and over-payments under the old agreement. For New South Wales, South Australia, Western Australia, and Tasmania there were arrears of £23,180, £6,052, £3,559, and £2,939 respectively, while in Victoria and Queensland the sums overpaid amounted to £13,085, and £5,377.

In all the states, with the exception of Western Australia, a certain amount of money has been spent out of loans for purposes of defence. The amounts expended in 1903-4 were as follow :—

Queensland .....	£ 9,408
South Australia .....	1,157
Commonwealth .....	10,565
New Zealand.....	38,724
Australasia .....	£49,289

The total loan expenditure in each state for defence purposes to the end of the financial year 1903-4 was as follows :—

State.	Amount. £	Per head.		
		£.	s.	d.
New South Wales .....	1,109,491	0	15	7
Victoria .....	149,324	0	2	10
Queensland .....	386,505	0	14	11
South Australia .....	293,840	0	16	0
Tasmania .....	128,180	0	14	4
Commonwealth .....	2,067,340	0	10	7
New Zealand .....	772,563	0	18	10
Australasia .....	£2,839,903	0	12	0

The figures are exclusive of a sum of £312,485 expended in connection with the naval station at Port Jackson. Had this amount been taken into consideration, the total outlay in New South Wales would have reached about £1 per head, and for the Commonwealth 12s. 2d.

The above does not represent the whole cost of the fortifications, as large sums have from time to time been expended from the general revenues of the states in the construction of works of defence; the amount of such payments, however, it is now impossible to determine.

## LAW AND CRIME.

## CRIME.

In all the states proceedings against a person accused of an offence may be initiated either by the arrest of the culprit or by summoning him to appear before a magistrate. Serious offences, of course, are rarely dealt with by process of summons; but, on the other hand, it is not uncommon for a person to be apprehended on a very trivial charge, and this circumstance should not be forgotten in dealing with arrests by the police, which are unusually numerous in some of the states. Unfortunately, it is not easy to say how far the police of one state are disposed to treat offenders with such consideration as to proceed against them by summons, and how far those of another state are content to adopt similar action; for in most of the provinces the records do not draw a distinction between the two classes of cases; and in the table given on page 546, showing the number of persons charged before magistrates in each state during the year 1902, offenders who were summoned to appear are included with those arrested. It is likewise difficult to make a true comparison between the various states in the matter of the prevalence of crime, for there are a number of circumstances which must considerably affect the criminal returns and modify their meaning. The first of these, of course, is the question of the strength of the police force and its ability to cope with lawlessness, which must be decided chiefly by the proportion of undetected crime which takes place in the states. The policy adopted by the chief of police in regard to trivial breaches of the public peace and other minor offences against good order must also be taken into consideration; and then there are considerable differences between the criminal codes of the states, and in the number of local enactments, breaches of which form a large proportion of the minor offences taken before the Courts. Also, when the returns of the lower Courts are laid aside and the convictions in superior Courts taken up, the comparison is affected by the jurisdiction of the magistrates who committed the prisoners. In New South Wales, for example, the jurisdiction of the lower Courts is limited to imprisonment for six months, except in regard to cases brought under one or two Acts of Parliament, such as the Chinese Restriction Act, prosecutions under which are very few; while in Victoria a large number of persons are every year sentenced in Magistrates' Courts to imprisonment for terms ranging from six months

to three years. It is apparent, therefore, that in any comparison drawn between the number of convictions in the superior Courts of New South Wales and of Victoria, the former state must appear to great disadvantage.

An investigation into the differences between the law of New South Wales and of Victoria in respect to the jurisdiction of magistrates discloses some important results. Under the Victorian Crimes Act of 1890, 54 Victoria No. 1,079, it is provided by section 67 that Justices may try persons under sixteen years of age for the offence of simple larceny or for any offence punishable as simple larceny no matter what the value of the property in question may be, and persons over sixteen years of age where the property said to have been stolen is not of greater value than £2; and it is further provided by the same section that if upon the hearing of such a charge the Justices shall be of opinion that there are circumstances in the case which render it inexpedient to inflict any punishment, they shall have power to dismiss the charge without proceeding to a conviction. This provision, it is needless to say, is likely to reduce materially the number of convictions for larceny in Victoria. In New South Wales, on the other hand, the law does not give Justices any such power. In every case where the offence is proved they must convict the accused person, although in the case of offenders under the age of sixteen years they may discharge the convicted person on his making restitution, or in other cases deal with him under the First Offenders' Act and suspend the sentence; but in all such cases the conviction is placed on record and is accounted for in the criminal statistics of the state. Section 69 of the same Victorian Act gives Justices power to deal with any case of simple larceny, or of larceny as a clerk or servant, or of stealing from the person, when the accused pleads guilty, the punishment being imprisonment for any term not exceeding twelve months; while in New South Wales the law does not give Justices the power to deal with such cases when the property alleged to have been stolen exceeds the value of £20. This section must therefore tend materially to reduce the number of cases committed for trial in Victoria for the offences mentioned, although in all such cases the Justices may commit the accused person if they think fit to do so. Furthermore, it is provided by section 370 of the Crimes Act of 1890 that suspected persons who have been convicted of capital or transportable felony elsewhere and are found in Victoria may be arrested and sentenced to imprisonment for three years in the case of a male, and for one year in the case of a female. Such a protective provision is in force in some of the other provinces as well as in Victoria; but it was not until towards the close of 1903, when the Influx of Criminals Prevention Act was passed that New South Wales was similarly protected. These statements all go to show in what important respects the criminal statistics of the states must differ from each other, and how great care must be taken in making comparisons.

The number of persons arrested during the year 1902, together with the proportion per 10,000 of the population for four of the Commonwealth states, is given below. The returns from the other states do not show apprehensions separately.

State.	No. of Arrests.	Per 10,000 of Population.
New South Wales .....	28,341	201
Victoria .....	24,720	205
Queensland .....	16,235	315
Tasmania .....	1,705	96

Taking into consideration only the more serious crimes, such as offences against the person and against property, including forgery, the rates for New South Wales, Victoria, and Tasmania, were respectively 41, 27, and 26 per 10,000 of the population.

During the year 1902, so far as can be gathered, 184,041 persons were charged before magistrates in Australasia, 147,271 being summarily convicted and 32,985 discharged, while 3,785 were committed. The returns of each of the Commonwealth states and New Zealand will be found below. It should be explained that in the case of New Zealand each charge is counted as a separate person—a proceeding which, of course, tells against the colony; if the New South Wales experience be applied a reduction of about 10 per cent. on the total charges should be made to arrive at the actual number of persons concerned:—

State.	Persons charged.	Summarily dealt with.		Committed.
		Discharged.	Convicted.	
New South Wales.....	60,373	8,326	50,776	1,271
Victoria .....	45,198	11,096	33,461	641
Queensland.....	21,115	3,001	17,625	489
South Australia.....	6,608	843	5,556	209
Western Australia ...	16,443	3,355	12,753	335
Tasmania .....	6,228	1,178	4,975	75
Commonwealth ...	155,965	27,799	125,146	3,020
New Zealand .....	28,076	5,186	22,125	765
Australasia.....	184,041	32,985	147,271	3,785

Taking the whole of Australasia, rather more than thirty-nine persons out of every thousand were charged before magistrates during the year 1902—a figure somewhat in excess of the average for preceding years from the fact that, prior to 1902, it was not found possible to obtain information respecting summons cases in Victoria. Only three states—Western Australia, Queensland, and New South Wales—exceed the average amount of disorder and crime as disclosed by the police court returns. The very large proportion of adult males in the population of the first-named state, and its present industrial conditions,

place it, of course, in quite an exceptional position; while in Queensland and New South Wales there are greater floating populations, from the ranks of which a large percentage of offenders is drawn, than in the other states which have better records. The province with the least disorder and crime is South Australia, where the persons answering to charges in the lower Courts only form 18·06 per thousand of the population. Next come Tasmania with 35·17 per thousand; Victoria, 37·49; and New Zealand, with 39·21; while, as before stated, Western Australia, New South Wales, and Queensland have the highest proportions, namely, 76·43, 42·89, and 41·01 per thousand respectively. In the case of Western Australia, the returns leave little doubt that there has been a large influx of criminals from the eastern states, because the rate is over one and three-fifths in excess of that of New South Wales, the next state. The rate is, however, unduly increased by including the charges brought against the aborigines, and also from the fact that as stated before, each offence is counted as a separate person; but in the absence of any exact statistical information, there is no option but to use the figures presented. In New South Wales and Victoria, about every ninety persons charged are accused of 100 offences, and assuming the same ratio to hold in Western Australia, it is estimated that if these two mentioned factors were excluded, the rate in Western Australia would be about 68 per 1,000. The New Zealand rate is also affected by the last-mentioned circumstance. The following table shows the proportion of persons charged before magistrates in each state during the year; also the percentages of the persons discharged, convicted, and committed of the whole number charged:—

State.	Persons charged per 1,000 of Population.	Percentages of total persons charged.			
		Discharged.	Convicted.	Summarily dealt with.	Committed.
New South Wales .....	42·89	13·79	84·10	97·89	2·11
Victoria .....	37·49	24·54	74·04	98·58	1·42
Queensland .....	41·01	14·21	83·47	97·68	2·32
South Australia .....	18·06	12·76	84·08	96·84	3·16
Western Australia .....	76·43	20·40	77·56	97·96	2·04
Tasmania .....	35·17	18·92	79·88	98·60	1·20
Commonwealth .....	40·13	17·82	80·24	98·06	1·94
New Zealand .....	34·75	18·47	78·81	97·28	2·72
Australasia .....	39·21	17·92	80·02	97·94	2·06

It will be seen from the above table that out of every hundred persons charged before magistrates in Australasia in 1902, 97·94 were summarily dealt with, 17·92 being discharged and 80·02 convicted, while only 2·06 were committed to higher courts. The state with the highest percentage of cases summarily disposed of and the smallest proportion of

committals was Tasmania; while South Australia, which shows by far the lowest rate of charges in comparison with the population, has nevertheless the highest percentage of committals. The increase in the rate of charges, and also in the percentage of cases summarily disposed of in Victoria, is owing to the circumstance previously alluded to, that summons cases were included in the returns of that state for the first time in 1902.

As shown above, Victoria and Western Australia have by far the largest proportion of discharges, and if the theory be dismissed as untenable that the police in those states are more prone to charge persons on insufficient grounds than in the other states, it must be concluded that the magistrates of Victoria and Western Australia deal more leniently with accused persons than is the case elsewhere; indeed, so far as Victoria is concerned, it has already been shown that the Crimes Act of 1890 provides for the discharge without conviction of persons found guilty of certain offences. The lowest proportion of discharges is to be found in South Australia, New South Wales, and Queensland, and the figures testify to the stringency with which the criminal laws are administered in those states.

Of the 184,041 persons brought before magistrates during the year 1902, only 28,782 were charged with offences which can fairly be classed as criminal, the overwhelming majority being accused of drunkenness and other offences against good order, and of breaches of Acts of Parliament, which have a tendency to multiply to a great extent. For present purposes the accused persons may be divided as in the table given below, offences against the person and against property being regarded as serious crime. Of course, amongst the other offenders are to be found a few charged with grave misdemeanours, but against these may be put trifling assaults, which are included with crimes against the person:—

State.	All Offenders.	Serious Offenders.			Minor Offenders.
		Against the Person.	Against Property.	Total.	
New South Wales .....	60,373	4,183	6,023	10,206	50,167
Victoria .....	45,198	2,212	3,245	5,457	39,741
Queensland .....	21,115	1,908	2,375	4,283	16,832
South Australia .....	6,603	379	635	1,014	5,589
Western Australia .....	16,443	845	1,901	2,746	13,697
Tasmania .....	6,228	248	631	879	5,349
Commonwealth.....	155,965	9,775	14,810	24,585	131,380
New Zealand .....	28,076	1,309	2,888	4,197	23,879
Australasia.....	184,041	11,064	17,696	28,782	155,259

This examination into the nature of the offences explains in some measure the comparatively unfavourable position of New South Wales



as shown by the previous tables; for of the 60,373 accused persons in that state, the minor offenders numbered 50,167, or 83·1 per cent. No doubt the large number of trivial cases in New South Wales is accounted for by the greater strictness of police administration. Victoria shows 87·9 per cent. of minor offenders, but in consequence of a difference in the tabulation of the returns its position is not nearly so favourable as it appears to be on the surface. In New South Wales, and, it is to be presumed, in most of the other states, a person accused of two or more offences is entered as charged with the most serious in the eyes of the law; while in Victoria he is entered as charged with the first offence committed, any others, however serious, arising out of his capture, being left out of consideration. For example, if a person is arrested for drunkenness, and he assaults his captors while on the way to the station, he is entered in the returns of New South Wales, as they are here presented, as charged with an offence against the person, and thereby helps to swell the amount of serious crime; but in Victoria he is entered as charged with drunkenness and disorderly conduct, and the charge of assault, on which he may be convicted and sentenced to a term of imprisonment, is not disclosed. This fact must therefore be taken into account in comparing the proportions of the various classes of offenders per thousand of population, which are appended:—

State.	Per 1,000 of Population.				
	All Offenders.	Serious Offenders.			Minor Offenders.
		Against the Person.	Against Property.	Total.	
New South Wales .....	42·89	2·97	4·28	7·25	35·64
Victoria .....	37·49	1·83	2·69	4·52	32·97
Queensland .....	41·01	3·71	4·61	8·32	32·69
South Australia .....	18·06	1·03	1·74	2·77	15·29
Western Australia .....	76·43	3·93	8·84	12·77	63·66
Tasmania .....	35·17	1·43	3·57	5·00	30·17
Commonwealth .....	40·13	2·52	3·81	6·33	33·80
New Zealand .....	34·75	1·62	3·57	5·19	29·56
Australasia .....	39·31	2·36	3·77	6·13	33·08

It will be seen that, relatively to population, the state with the largest number of serious offenders was Western Australia, which had a proportion of 12·77 per thousand. Queensland followed with a proportion of 8·32, while New South Wales and New Zealand occupied third and fourth positions with 7·25 and 5·19 per thousand respectively. The rate of Tasmania was 5·00 per thousand, while that of Victoria is set down at 4·52, and South Australia closes the list with 2·77. It would be interesting to compare the crime of the principal states on the basis of the number of males of such ages as contribute to the ranks of offenders; but the records unfortunately do not give sufficient data to enable such a comparison to be made. In explanation of the position of Western Australia, it is well known to the police of Victoria and New South Wales—and, indeed, the fact is proved by the records of the prisoners received into Fremantle gaol—that a large number of criminals have left those states for the west during the last few years.

An examination of the criminal records of the Commonwealth shows that there has been a considerable decrease in the volume of serious offences during the last ten years. Taking the apprehensions and summons cases for offences against the person and against property, the average charges for the quinquennial period 1893–7 amounted to 26,668, or 7·62 per 1,000 of the population; while, as the table below indicates, the charges for the period 1898–1902 averaged 24,868, or 6·59 per 1,000. The returns for New Zealand show a rate of 5·56 per 1,000 for 1893–7, the proportion for 1898–1902 being almost identical, viz., 5·54 per 1,000. The figures for the Commonwealth are given below:—

Period.	Average number of Offences against Person and Property.	Rate per 1,000 Persons.
1893–7 .....	26,668	7·62
1898–1902 .....	24,868	6·59

About two-fifths of the minor offenders of Australasia are charged with drunkenness. From the table given below it will be seen that in all the states 60,576 cases of drunkenness were heard during the year 1902, convictions being recorded in 54,829 cases, or 90·51 per cent. of the total number. The state with the highest number of cases relatively to population was Queensland, the rate of which was 15·78 per thousand persons, followed by Western Australia with 15·56, New South Wales with 15·33, and Victoria with 12·06, while Tasmania was last with a rate of only 3·59 per thousand. Turning to the record of convictions it will be seen that the lowest percentage is shown by Victoria. This is accounted for by the fact that in that state it is

customary to discharge first offenders as well as those who were arrested on Saturday and detained in custody till the following Monday. In some cases also offenders admitted to bail after arrest are discharged on promising to place a donation in the poor box.

State.	Charges of Drunkenness.	Convictions.		Per 1,000 Persons.	
		Total.	Percentage of Charges.	Charges.	Convictions.
New South Wales .....	21,577	21,472	99·51	15·33	15·25
Victoria .....	14,540	9,394	64·61	12·06	7·79
Queensland .....	8,123	8,102	99·74	15·78	15·74
South Australia.....	2,431	2,394	98·43	6·65	6·54
Western Australia .....	3,347	3,283	98·09	15·56	15·23
Tasmania .....	636	602	93·24	3·59	3·40
Commonwealth.....	50,654	45,247	89·32	13·03	11·64
New Zealand .....	9,922	9,582	96·57	12·28	11·86
Australasia .....	60,576	54,829	90·51	12·91	11·68

Experience has shown that the present method of dealing with the dipsomaniac by fine or imprisonment is hopelessly futile, the same faces reappearing at the Magistrates' Courts sometimes over a hundred times in the course of a few years. In New South Wales some attempt has been made to segregate the drunkard and vagrant class from the professionally criminal; but the folly of allowing persons with non-criminal tendencies, but with their faculties weakened by the effects of drink, to associate with the professional malefactor, does not seem to be fully appreciated in all the states.

A return showing only the number of cases of drunkenness is not, however, a safe index of the abuse of alcoholic liquors, for a great deal depends on the state of the law and the manner in which it is administered, and it is evident that the maintenance of the law intended to preserve public decency will always be less strict in sparsely-settled country districts than in larger centres of population where the police are comparatively more numerous, if not in proportion to the population, at least in proportion to the area they have under their supervision; and further, will vary according to the diverse nature of the duties performed by the police. The quantity of intoxicants consumed per head is another index of the habits of communities living under like conditions; but comparisons so based should not be pushed to extremes, for, as has often been pointed out, the larger part of the alcohol which enters into consumption is that consumed by the population who are not drunkards. The average quantity of intoxicants used in each state during the three years ended 1902, is given below, wines and beer being reduced to their equivalent of proof spirit. The consumption of the various kinds

of intoxicants will be found in the chapter on "Food Supply and Cost of Living":—

State.	Proof Gallons of Alcohol per head population.
New South Wales .....	2.44
Victoria .....	2.74
Queensland .....	2.57
South Australia .....	1.95
Western Australia .....	5.13
Tasmania .....	1.75
Commonwealth .....	2.61
New Zealand .....	2.00
Australasia .....	2.50

The record of cases heard before a Court of Magistrates cannot be regarded as altogether a trustworthy indication of the social progress of Australasia, because, as has been pointed out, it includes many kinds of offences which cannot fairly be classed as criminal, and the number of these has a tendency to increase with the increase of local enactments. The committals for trial, taken in conjunction with the convictions for crime in the Superior Courts may be regarded as much more conclusive on the question of the progress of society or the reverse. In some respects even this evidence is misleading, for, as already shown, in the less populous provinces there are no Courts intermediary between the Magistrates' and the Supreme Courts, so that many offences which in New South Wales, for example, are tried by a jury, are in some of the other provinces dealt with by magistrates; and even in Victoria, where there are Courts of General Sessions, magistrates have a much wider jurisdiction than in New South Wales. But for the purpose of showing the decrease of serious crime in Australasia as a whole, the proportion of committals and of convictions in Superior Courts may fairly be taken; and this information is given below. It will be seen that during the forty-two years, from 1861 to 1902, the rate of committals per thousand of population has dropped from 2.2 to 0.7, and of convictions from 1.3 to 0.4:—

Year.	Per 1,000 of Population.	
	Committals.	Convictions in Superior Courts.
1861 .....	2.2	1.3
1871 .....	1.4	0.8
1881 .....	1.2	0.7
1891 .....	1.1	0.6
1902 .....	0.7	0.4

In noting these facts and comparing the results with those obtained in Great Britain during the same period, it must not be forgotten that some of the provinces of Australasia have been compelled gradually to reform a portion of their original population, and that in the case of states such as Victoria and Queensland, not originally peopled in any degree by convicts, the attractions of the gold-fields have drawn within their borders a population by no means free from criminal instincts and antecedents. Viewed in this light, the steady progress made cannot but be regarded as exceedingly satisfactory, and the expectation may not unreasonably be entertained that the same improvement will be continued until the ratio of crime to population will compare favourably with that of any part of the world.

Below will be found the number of convictions in the Superior Courts of each state, at decennial periods from 1861 to 1902 :—

State.	1861.	1871.	1881.	1891.	1901.	1902.
New South Wales .....	437	628	1,066	964	730	775
Victoria .....	846	511	332	729	393	381
Queensland .....	24	91	92	232	285	249
South Australia .....	62	91	213	90	134	100
Western Australia .....	35	65	61	44	162	165
Tasmania .....	127	74	51	63	39	23
Commonwealth .....	1,531	1,460	1,815	2,122	1,743	1,696
New Zealand .....	100	162	270	276	328	312
Australasia .....	1,631	1,622	2,085	2,398	2,071	2,010

The following table gives a classification of the offences for which the accused persons were convicted during 1902 ; also the rate of convictions and of committals per 1,000 of population. It will be seen that the rate of convictions in the Superior Courts of Victoria is 0·32 per thousand ; but if the persons who received sentences of over six months' imprisonment at the hands of magistrates were taken into account, the proportion would be as high as that of most of the other states. Tasmania and South Australia for the period in question show a smaller

proportion of convictions in Superior Courts than Victoria ; but in those two provinces, as already pointed out, no intermediate Courts exist:—

State.	Convictions in Superior Courts.					Committees per 1,000 of Population.
	Classification of Offences.			All Convictions.	Per 1,000 of Population.	
	Against the Person.	Against Property.	Other.			
New South Wales .....	146	598	31	775	0·55	0·87
Victoria .. .....	81	283	17	381	0·32	0·55
Queensland .. .....	86	150	13	249	0·48	0·92
South Australia .....	13	86	1	100	0·27	0·57
Western Australia.....	54	105	6	165	0·77	1·56
Tasmania.....	7	11	10	28	0·16	0·37
Commonwealth....	387	1,233	78	1,698	0·44	0·78
New Zealand .....	82	202	28	312	0·39	0·53
Australasia .....	469	1,435	106	2,010	0·43	0·74

The punishment of death is very seldom resorted to except in cases of murder, though formerly such was not the case. Thus the number of executions steadily declined from 151 during the decade 1841-50 to 66 during the ten years 1881-90. In South Australia the extreme penalty has been most sparingly inflicted, there having been only 11 executions in the thirty-one years which closed with 1902. The following table shows the number of executions in each province during each decade of the 50 years ended 1890, also those which took place in 1891-95, 1896-1900, and 1901-2. Queensland was incorporated with New South Wales until the end of 1859, though Victoria became a separate colony in 1851. It will be noticed that the returns are defective so far as Western Australia is concerned :—

State.	1841-1850.	1851-1860.	1861-1870.	1871-1880.	1881-1890.	1891-1895.	1896-1900.	1901.	1902.
New South Wales .....	68	38	34	27	23	15	7	3	...
Queensland .....			14	18	15	16	1	5	...
Victoria .....			41	19	13	12	4	...	2
South Australia .....			7	12	6	2	1	...	...
Western Australia.....	...	...	...	...	...	6	10	...	1
Tasmania .....	83	32	15	3	5	1	...	...	...
New Zealand.....	...	...	...	12	8	1	5	1	...
Total.....	151	124	116	85	66	53	28	9	3

The returns relating to the prisons of the states are in some cases very incomplete. The prisoners in confinement at any specified time

may be divided into those who have been tried and sentenced, those who are awaiting their trial, and debtors. The returns of five of the states allow of this distinction being made. The number and classification of prisoners in confinement on the 31st December, 1902, were as follow :—

State.	Tried and Sentenced.	Awaiting Trial.	Debtors.	Total.
New South Wales.....	1,698	137	5	1,840
Victoria .....	1,016	55	.....	1,071
Queensland .....	590	23	.....	613
South Australia .....	261*	13	.....	274
Western Australia ...	492	42	1	535
New Zealand.....	602	51	.....	653
Total .....	4,659	321	6	4,986

\* Including debtors.

The returns of Tasmania do not enable the distinction made in the above table to be drawn, but there were 80 prisoners in Tasmanian gaols at the end of 1902; so that the total number of persons in confinement in the gaols of Australasia, at the close of 1902, may be stated as 5,066, equal to 1·08 in every thousand of the population.

#### POLICE.

The strength of the police force in each of the states and New Zealand at the end of 1902 is given below. These figures show the importance which must be attached to police administration when studying the question of drunkenness.

State.	Police.			Inhabitants to each Police Officer.	Area to each Constable in Country Districts.
	Metropolitan.	Country.	Total.		
	No.	No.	No.	No.	Sq. miles.
New South Wales .....	950	1,272	2,222	621	244
Victoria .....	824	671	1,495	806	131
Queensland.....	228	695	923	558	962
South Australia.....	192	219	411	890	4,125
Western Australia .....	156	366	522	412	2,666
Tasmania .....	43	212	255	723	123
Commonwealth.....	2,393	3,435	5,828	667	865
New Zealand .....	135	470	605	1,335	222
Australasia.....	2,528	3,905	6,433	730	788

A comparison of the cost of the police forces of the various states will be found below. The greater number of mounted troopers in those

states where very large and thinly-populated districts have to be controlled, tends to make the average cost somewhat higher than in the other provinces :—

State.	Total Cost of Police Force.	Average Cost per Constable.	Average Cost per Inhabitant.
	£	£ s. d.	£ s. d.
New South Wales...	415,980	187 4 2	0 5 10
Victoria .....	268,118	179 6 10	0 4 4
Queensland .....	173,833	188 6 8	0 6 9
South Australia...	84,291	205 1 9	0 4 7
Western Australia .....	128,830	246 16 0	0 11 8
Tasmania.....	36,139	141 14 5	0 4 1
Commonwealth ...	1,107,191	189 16 1	0 5 8
New Zealand .....	123,804	204 12 8	0 3 0
Australasia .....	1,230,995	191 7 1	0 6 5

#### EXPENDITURE ON JUSTICE, &c.

The cost of the administration of justice, the police, and the penal services of the Commonwealth during the last five years was at the rate of £1,825,108 per annum or 9s. 7d. per inhabitant. This large sum is made up of £536,883 for the administration of justice, £227,993 for prisons, and £1,060,232 for police. For each of these five years the expenditure was :—

Year.	Justice. £	Prisons. £	Police £
1899 .....	519,770	231,943	1,007,642
1900 .....	523,473	220,901	1,028,210
1901 .....	543,598	226,615	1,068,332
1902 .....	545,162	225,960	1,089,785
1903 .....	550,414	234,547	1,107,191

The expenditure varies greatly in the different states, the range per inhabitant being from 7s. 7d. in Tasmania to 21s. 3d. in Western Australia. The distribution of the expenditure for 1903 amongst the six states was :—

State.	Justice.	Prisons.	Police.	Total.
	£	£	£	£
New South Wales ...	236,732	102,014	415,980	754,726
Victoria .....	123,590	56,270	268,118	447,978
Queensland .....	72,854	26,339	173,833	273,026
South Australia .....	22,140	16,069	84,291	122,500
Western Australia ...	66,079	28,223	128,830	223,132
Tasmania .....	24,019	5,582	36,139	65,740
Total .....	550,414	234,547	1,107,191	1,892,152



In explanation of the large sum expended on justice administration in New South Wales, it has been stated by the department that the clerks of petty sessions perform many duties such as those of electoral registrars, registrars of births, deaths, and marriages, crown lands agents, mining registrars, &c., which, in the other states, are performed by separate officers, while many of the magistrates act as mining wardens, wardens' clerks, and mining registrars, &c. Then, again, there are in New South Wales 54 Courts of Quarter Sessions as compared with 30 in Victoria, and the expenditure on administration and on jurors' and witnesses' fees is of necessity higher in the mother state. The charges incidental to the Coroners' Courts also form a heavy item in the New South Wales expenditure. Further, there are in New South Wales 62 magistrates and 91 clerks of petty sessions, these officers in Victoria numbering 19 and 57 respectively. The foregoing items, however, only partly explain the high expenditure in New South Wales, and there is still much to be accounted for.

The expenditure per inhabitant in each state, and in the Commonwealth, for the year 1903 was as follows:—

State.	Justice.	Prisons.	Police.	Total.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.
New South Wales.....	0 3 4	0 1 5	0 5 10	0 10 7
Victoria .....	0 2 2	0 0 11	0 4 4	0 7 5
Queensland.....	0 2 10	0 1 0	0 6 9	0 10 7
South Australia.....	0 1 3	0 0 10	0 4 7	0 6 8
Western Australia .....	0 6 0	0 3 7	0 11 8	1 1 3
Tasmania .....	0 2 8	0 0 8	0 4 1	0 7 7
Total .....	0 8 0	0 1 2	0 5 8	0 9 10

It will be seen that, in proportion to population, the total cost, as well as the expenditure per head on each service, was much higher in Western Australia than in any of the other states. This of course is only to be expected, if regard be paid to the peculiar industrial conditions of that state, and also to the fact that the provision for efficient police protection must necessarily entail a heavy expenditure in a large and sparsely-peopled country. In considering the above figures, allowance must be made for the fact that the functions of the justice officials are not identical in all the states, but in compiling the above table, so far as it was possible, all expenditure not directly connected with the administration of justice has been eliminated.

## RAILWAYS.

TO the proper development of a country like Australasia, ill-supplied with navigable rivers, railway construction is absolutely essential. This has been recognised from an early period, and for the last forty years the Governments of the principal states have been fully alive to the importance of carrying on the work. For a long time, however, they were hampered in their efforts by the difficulty of borrowing money in London at a reasonable rate of interest ; but since the year 1871 considerable progress has been made in the work of construction ; indeed, by far the greater portion of the public debt of Australasia has been contracted for railway purposes. As the area of the six states and New Zealand almost equals that of Europe or the United States of America, while the population numbers a little over four and a half millions, it is almost needless to say that many of the lines run through districts very sparsely peopled. This is particularly the case in the states of Queensland, South Australia, and Western Australia, where there are vast tracts of territory in which little in the nature of permanent settlement has yet been accomplished, and in none of the states can it be said that the railway lines traverse thickly-settled areas. Indeed, if a fault may be found with the state policy pursued in the past, it is that in some cases expensive lines have been laid down in empty country the requirements of which could have been effectually met for many years to come by light and cheap lines, and that in consequence the railway administrators find themselves heavily burdened with a number of unprofitable lines. A few of these have been closed, and the remainder are worked at a loss. Notwithstanding these drawbacks, however, the railways of the Commonwealth of Australia collectively yield a net return equal to 3·08 per cent., and those of Australasia 3·15 per cent. on the cost of construction.

### HISTORY OF RAILWAY CONSTRUCTION.

An agitation for the introduction of the railway into the colony of New South Wales was afoot as early as 1846, and in August of that year it was decided at a public meeting held in Sydney to survey a line to connect the capital with Goulburn. But no decided step was taken towards construction until September, 1848, when the Sydney Railroad and Tramway Company was formed for the purpose of laying down a line between Sydney and Parramatta and Liverpool, to be afterwards extended to Bathurst and to Goulburn. The first sod was turned by the Hon. Mrs. Keith Stewart, daughter of Sir Charles Fitzroy, the Governor of the colony, on the 3rd July, 1850. Although started during a period of trade depression, when there was an abundant supply of

labour, the scheme was only well under weigh when the discovery of gold caused a stampede from the city, and the company was left without workmen to carry on the undertaking. Undeterred, however, by the difficulties into which the changing conditions of the country had plunged the Sydney Railroad and Tramway Company, private enterprise in 1853 essayed the further task of constructing a line between Newcastle and Maitland; but this project proved no more successful than the other, and in the following year the Government was forced to step in and carry out the schemes for which the two companies had been promoted. From that time the work of construction was vigorously pressed forward; and on the 26th September, 1855, the line from Sydney to Parramatta, 14 miles in length, was opened to traffic; and on the 11th April, 1857, Newcastle was connected with East Maitland. The extension to Goulburn of the Sydney line was completed on the 27th May, 1869.

While the Sydney Railroad and Tramway Company was endeavouring to surmount the obstacles that had arisen in its path, the work of railway construction was begun in the neighbouring state of Victoria, no fewer than three private companies being promoted in 1853 for that purpose. Material assistance in the shape of land grants and guarantee of interest was afforded by the Government; and on the 13th September, 1854, the first completed railway in Australasia, a line extending from Flinders-street, Melbourne, to Port Melbourne, was opened to traffic. It had been begun nearly three years after the line to connect Sydney with Parramatta, but was only  $2\frac{1}{2}$  miles long. No further mileage was brought into operation until May 13, 1857, when the Melbourne and Hobson's Bay Railway Company, which had constructed the first line, effected communication with St. Kilda; and on the 17th June of the same year a line from Williamstown to Geelong, 39 miles in length, which had been built by another company, was declared open. Meanwhile the Government of the state had not remained inactive. In addition to assisting private enterprise with liberal concessions, it had taken over in 1855 an unfinished line started by the third of the companies referred to, and was carrying on the work of construction on its own account. By the year 1863 it had acquired all the lines in the state with the exception of those owned by the Melbourne and Hobson's Bay Company, which were not purchased until the year 1878.

Although a line from Goolwa to Port Elliot, 6 miles in length, over which the locomotive now passes, was opened on the 18th May, 1854, it was at that time merely a horse tramway; and the first railway in South Australia was a line connecting the city with Port Adelaide,  $7\frac{1}{2}$  miles long, which was thrown open to traffic on the 21st April, 1856. The following year saw a railway constructed as far north as Gawler; while on the 1st October, 1889, a line from Palmerston to Pine Creek, in the Northern Territory, which had been built by the South Australian Government, was opened, the length being  $145\frac{1}{2}$  miles.

The northern state of Queensland had enjoyed the privilege of self-government for several years when, early in 1864, a line to connect

Ipswich with Grandchester was commenced, and on the 31st July of the same year it was opened.

Although the Tasmanian Parliament granted a sum of £5,000 in 1863 for the survey of a line to connect Hobart with Launceston, the first railway in the island was one between Launceston and Deloraine, 45 miles in length, which was opened on the 10th February, 1871, having been commenced three years before. It was built by a private company, to whose capital, however, the Government had subscribed eight-ninths of the total amount of £450,000, on condition that the interest should be a first charge on the net receipts, and on the 3rd August, 1872, the line passed entirely into the ownership of the state. Communication between Hobart and Launceston was effected in 1876 by the completion of a line, connecting the southern city with Evandale Junction, which was constructed by an English company. The last of the states comprised in the Commonwealth to introduce the railway was Western Australia, where a line from the port of Geraldton to Northampton was begun during 1874 and opened in 1878. The commencement of railway construction in New Zealand was due to an agitation on the part of the settlers of Canterbury, who were desirous of facilitating communication between the city of Christchurch and the port of Lyttleton. The first portion of the line, as far as Ferrymead Junction, was brought into use on the 1st December, 1863.

The progress of railway construction, except, perhaps, in the state of Victoria, was anything but rapid during the earlier years. This was in a great measure owing to the sparseness of the population and the natural fear that the return would not justify the expenditure which would have to be incurred in making lengthy extensions of the lines. It was also due, as previously pointed out, to the low estimation in which Australasian securities were held in London, and the consequent high rate of interest at which money for railway construction had to be borrowed. Since the year 1871, however, all the states and New Zealand have made satisfactory progress. In the following table will be found the length of line opened during each year, excluding coal, timber, and other lines which are not open to general traffic, and the total mileage at the close of the working year :—

Year.	Miles opened.					
	Total.			During each year.		
	Common-wealth.	New Zealand.	Australasia.	Common-wealth.	New Zealand.	Australasia.
1854	2½	.....	2½	2½	.....	2½
1855	16½	.....	16½	14	.....	14
1856	32½	.....	32½	16	.....	16
1857	117	.....	117	84½	.....	84½
1858	132	.....	132	15	.....	15
1859	171	.....	171	39	.....	39
1860	215	.....	215	44	.....	44

## RAILWAYS.

561

Year.	Miles opened.					
	Total.			During each year.		
	Common-wealth.	New Zealand.	Australasia.	Common-wealth.	New Zealand.	Australasia.
1861	243	.....	243	28	.....	28
1862	373	.....	373	130	.....	130
1863	395	5	400	22	5	27
1864	469	5	474	74	.....	74
1865	490	5	495	21	.....	21
1866	519	5	524	29	.....	29
1867	711	7	718	192	2	194
1868	788	7	799	71	.....	71
1869	911	7	918	129	.....	129
1870	994	46	1,040	83	39	122
1871	1,030	195	1,185	36	59	95
1872	1,168	105	1,373	189	.....	138
1873	1,353	145	1,498	185	40	225
1874	1,491	209	1,700	138	64	202
1875	1,602	542	2,144	111	333	444
1876	1,961	718	2,679	359	176	535
1877	2,493	954	3,447	532	236	768
1878	2,906	1,070	3,976	413	116	529
1879	3,222	1,171	4,393	316	101	417
1880	3,675	1,288	4,933	453	87	540
1881	4,192	1,324	5,526	517	76	593
1882	4,704	1,465	6,169	512	131	643
1883	5,107	1,490	6,587	403	15	418
1884	5,855	1,570	7,425	749	99	898
1885	6,227	1,654	7,881	372	84	456
1886	6,859	1,810	8,669	632	156	788
1887	7,657	1,841	9,498	798	31	829
1888	8,365	1,865	10,230	708	24	732
1889	9,162	1,912	11,074	797	47	844
1890	9,757	1,956	11,713	595	44	639
1891	10,163	2,011	12,174	406	55	461
1892	10,394	2,011	12,405	231	.....	231
1893	10,698	2,108	12,796	294	97	391
1894	10,974	2,168	13,142	286	90	346
1895	11,600	2,190	13,790	626	22	648
1896	11,641	2,190	13,831	41	.....	41
1897	11,970	2,185	14,155	329	(-) 5	324
1898	12,170	2,222	14,392	200	37	237
1899	12,702	2,257	14,959	582	35	567
1900	12,995	2,271	15,266	293	14	307
1901	13,497	2,300	15,797	592	29	531
1902	13,821	2,323	16,144	324	23	347
1903	13,720	2,404	16,124	(-) 91	81	(-) 10
1904	14,114	2,431	16,545	384	27	411

It will be seen from the foregoing table that the lines opened in the Commonwealth and Australasia averaged 30 miles in length during each year from 1854 to 1861; from 1862 to 1871 the annual average was 82 miles in the Commonwealth and 89 in Australasia; from 1872 to 1881, 312 miles in the Commonwealth and 439 in Australasia; from 1882 to 1891, 597 miles in the Commonwealth and 665 in Australasia; and from 1892 to 1904, 304 miles in the Commonwealth and 337 in Australasia. It is now the established policy of each state to keep the railways under state control, and only in exceptional circumstances is that policy departed from. Excluding coal, timber, and other lines which are not open to general traffic, there are within the Commonwealth only  $640\frac{1}{2}$  miles of private lines, equal to but 4·54 per cent. of the total mileage open; and in Australasia only  $728\frac{1}{2}$  miles, or 4·40 per cent. of the total mileage open. In Victoria the railways are entirely in the hands of the Government; while in Western Australia there are 277 miles of private lines, or 15·23 per cent. of the total mileage of the state; in New South Wales,  $81\frac{1}{2}$  miles; in Tasmania, 160 miles, and in South Australia, 20 miles. A departure from the ordinary policy of the state has also been made in Queensland, where the construction of the railway from Mareeba to Chillagoe, a distance of 102 miles, has been carried out by private enterprise. The private lines of New Zealand have a total length of 88 miles. Except in the case of Western Australia, none of these private railways are trunk lines, the most important of them being primarily intended to facilitate the development of important mines, and not for general traffic.

The divergence of the policy of Western Australia from that pursued by the other states was caused by the inability of the Government to construct lines when railway extension was urgently required in the interests of settlement. Private enterprise was therefore encouraged by liberal grants of land to undertake the work of construction; but the changing conditions of the state have modified its policy, and on the 1st January, 1897, the Government acquired the Great Southern Railway, 243 miles in length, one of the two trunk lines in private hands. This railway, which was owned by the West Australian Land Company, Limited, was built on the land-grant system, the state concession being 12,000 acres for every mile of line laid down, of which the original concessionaire retained 2,000 acres. The total price paid by the Government for the railway, with all the interests of the company and of the original concessionaire, was £1,100,000, of which £800,000 is set down as the capital sum on which the railway authorities are expected to provide interest, exclusive of the amount invested in rolling stock. The other trunk line is the Midland Railway, 277 miles in length, owned by the Midland Railway Company of Western Australia, Limited. In this case the land granted by the state was also 12,000 acres per mile of line. In 1891 the Government granted some slight assistance to the company, and in the following year guaranteed £500,000 of 4 per cent. debentures, the security being a first charge

upon the railway and its equipment, and 2,400,000 acres selected land. At three months' notice, the state may foreclose should the company be indebted to it to the amount of £20,000.

The following statement shows the gauge and length of the private railways of Australasia, excluding coal, timber, and other lines which are not open to general traffic :—

Line	Gauge. ft. in.	Length. miles.
<b>New South Wales—</b>		
Deniliquin-Moama .....	5 3	45
Cockburn-Broken Hill.....	3 6	35½
Warwick Farm .....	4 8½	½
<b>Queensland—</b>		
Mareeba to Chillagoe .....	3 6	102
<b>South Australia—</b>		
Glenselg Railway Co.'s lines :		
Holdfast Bay.....	5 3	7
Victoria Square .....	5 3	7
Sidings, loops, &c. ....	5 3	6
<b>Western Australia—</b>		
Midland : Midland Junction-Walkaway Junction .....	3 6	277
<b>Tasmania—</b>		
Emu Bay-Waratah-Guildford Junction-Zeehan .....	3 6	98
Lyell-Strahan .....	3 6	22
Gormanston to Kelly's Basin.....	3 6	33
Dundas-Zeehan .....	3 6	7
<b>New Zealand—</b>		
Wellington-Manawatu.....	3 6	84
Kaitangata-Stirling .....	3 6	4

A proviso has been inserted in the charters of the companies owning the private lines in New South Wales, whereby after a certain date the Government can, if so disposed, acquire the lines at a valuation. Similar conditions are found in most of the charters granted by the other states permitting the construction of private lines.

In the construction of railways during the last working year the state of Queensland displayed most activity, 217 miles of new line having been opened for traffic during the year.

The following table shows the extent of railway mileage in each state since 1861 :—

State.	1861	1866	1871	1876	1881	1886	1891-2	1898-2	1903-4
New South Wales..	73	143	358	554	1,040	1,341	2,266	2,107	2,302
Victoria .....	114	270	276	718	1,247	1,754	2,903	3,302	3,381
Queensland .....	*	50	218	296	800	1,433	2,320	2,908	3,030
South Australia.....	56	56	138	308	845	1,226	1,823	1,901	1,901
Western Australia...	*	*	*	38	92	202	687	1,090	2,170
Tasmania .....	*	*	45	45	168	308	425	618	620
Commonwealth	243	519	1,080	1,961	4,192	6,859	10,304	12,521	14,464
New Zealand .....	*	5	106	718	1,334	1,819	2,011	2,323	2,412
Australasia .....	243	524	1,185	2,679	5,526	8,680	12,406	16,144	18,576

\* Railways not in existence.

In 1883 a junction was effected between the New South Wales and Victorian lines at the river Murray ; three years later direct communication was established between Victoria and South Australia ; and in 1888 the last mile of line connecting Sydney with the northern state of Queensland was completed, thus placing the four capitals, Brisbane, Sydney, Melbourne, and Adelaide, in direct communication with each other. A few years ago proposals were made to the Government of Western Australia to construct a railway upon the land-grant system, connecting the eastern districts of the state with South Australia. It was proposed to extend the lines to Eucla, close to the South Australian border, and when that state had extended its railways to the same point, Perth would be connected with all the capitals of the Australian states. In June, 1897, the South Australian Railways Commissioner, in a report to the Commissioner of Public Works, estimated the cost of construction and equipment of a line to the Western Australian border, a distance of 553 miles, at £1,903,000. When the railways of the two states shall have been connected, as they will possibly be at no far distant date, the European mails will, in all likelihood, be landed at Fremantle, and sent overland to all parts of the continent.

The following table shows the length of Government railways in course of construction on the 30th June, 1904 :—

	Miles.
New South Wales .....	170
Victoria .....	95
Queensland .....	19
South Australia .....	100
Western Australia .....	23
Commonwealth .....	407
New Zealand .....	138
Australasia .....	545



Notwithstanding the energetic expansion of the railway systems throughout Australasia since 1871, there is still room for considerable extension. In the state of South Australia construction is entirely confined to the south-eastern corner and to the extension of the Northern Line, which has its present terminus at Oodnadatta, 686 miles from Adelaide. It is proposed eventually to extend this line as far north as Pine Creek, the southern terminus of the Port Darwin line. In the course of the year 1896 offers were made on behalf of various syndicates for the construction of the transcontinental railway, with the acquisition of the section from Palmerston to Pine Creek; but the Government was not prepared to recommend to Parliament the acceptance of any offer based on the land grant or guarantee system. When this railway is completed, direct overland communication will be established between the northern and southern portions of the continent. The length of the gap between the terminus at Oodnadatta and that at Pine Creek is 1,140 miles on the telegraph route.

In New South Wales the railway extensions will be chiefly confined to perfecting the various systems already constructed. At the present time several lines of what is termed the "pioneer" class are in course of construction in level pastoral country. These are of a light and cheap kind, on which the produce of the settlers may be conveyed to the trunk lines at a reasonable speed and at a cheaper rate than carriage by road. In Queensland, with its vast expanse of partly-settled territory and extensive seaboard, the railways are being constructed in separate systems. The lines commence from each of the principal ports and run inland, but there is no doubt that not many years will elapse before these systems will become branches of a main trunk-line which, in all likelihood, will be the Brisbane-Charleville line extended as far as Normanton on the Gulf of Carpentaria. In this state a system has been introduced by which railways are constructed under a guarantee given by the local authority on behalf of the ratepayers of the district. Details of this system are given on a subsequent page. In Victoria, Tasmania, and New Zealand the railway systems are well developed compared with the area of territory, and any future extensions will hardly be on so large a scale as in the other states. Western Australia has accomplished much useful work in the direction of extending the lines to the gold-fields, and also to the south-western portion of the state.

#### CONTROL OF STATE RAILWAYS.

The states of Victoria, South Australia, New South Wales, Queensland and Western Australia have found it expedient to place the management and maintenance of railways under the control of commissioners. Victoria, in 1883, was the first state to adopt this system; four years later South Australia made the change, while New South Wales and Queensland followed in 1888, and Western Australia in 1902. Each of these states (with the exception of Western Australia,

where there is only one commissioner) appointed three officials as commissioners, and conferred upon them large executive powers, amounting to almost independent control, the object aimed at being to obtain economical management of the lines free from political interference. Subsequently Queensland, Victoria, and South Australia reduced the number of commissioners to one; but in New South Wales, where the administration has been most successful, no changes in the system have been made. On the 1st June, 1903, the control of the railways in Victoria was again vested in three commissioners. The control of the New Zealand railways was also handed over to a body of three commissioners in 1887; but at the beginning of 1895 the Government resumed charge of the lines, a general manager being appointed, responsible to a Minister for Railways.

In New South Wales and Victoria all proposals for new lines are submitted to committees selected from members of the Houses of Parliament. These committees take evidence regarding the suitability of the route suggested, the probable cost of construction, the financial prospects of the line, and the grades to be adopted; and thereupon advise Parliament to adopt or reject the schemes proposed. This supervision of railway development may be said to have been attended with success, although lines that are not likely to be commercially successful have been recommended by the committee and sanctioned by Parliament.

#### DIVERSITY OF GAUGE.

Unfortunately for interstate communication, railway construction in Australia has proceeded without uniformity of gauge, and the accomplishment of this work, which it is everywhere admitted must be secured, becomes more formidable as the years roll on. In 1846 Mr. Gladstone advised that the 4-ft. 8½-in. gauge should be adopted for any lines constructed in New South Wales; and two years later this gauge was adopted as the standard by the Royal Commission appointed for the purpose of determining a uniform gauge for England and Scotland. In 1850, however, the Sydney Railroad and Tramway Company decided to adopt the 5-ft. 3-in. gauge, and in 1852 an Act was passed which provided that all railways in the state should be laid down to that gauge. But in 1853 the company mentioned, having changed their engineer, altered their views on the gauge question, and applied to have the 4-ft. 8½-in. gauge substituted for the 5-ft. 3-in., succeeding in repealing the Act and in passing another which made the narrower gauge imperative. This step was taken without the concurrence of the other states, and feeling ran very high in Victoria in consequence, as two of the railway companies in that state had already given large orders for rolling-stock on the 5-ft. 3-in. gauge. Until the lines of the two states met on the boundary no discomfort was, of course, experienced; but since then the break of gauge, with the consequent change of trains, has been a source of irritation and inconvenience. The South Australian

Government adopted at the outset the 5-ft. 3-in. gauge of Victoria ; but finding that the construction of lines of this class involved a heavier expense than they were prepared to face, the more recent lines were built on a gauge of 3 ft. 6 in. In that state there are 507 miles laid to the 5-ft. 3-in. gauge, and 1,229 $\frac{1}{4}$  to that of 3-ft. 6-in., which is also the gauge of the 145 $\frac{1}{2}$  miles of railway in the Northern Territory. The line joining Adelaide with the Victorian border, as well as several of the other trunk-lines, has been constructed on the wide gauge, so that the line from Melbourne to Adelaide is uniform. The private line which prolongs the South Australian system into New South Wales as far as Broken Hill is on the 3-ft. 6-in. gauge. All the Queensland lines are built on the gauge of 3 ft. 6 in., so that transshipment is necessary on the boundary between that state and New South Wales. Tasmania, Western Australia, and New Zealand have adopted the 3-ft. 6-in. gauge. The first line laid down in Tasmania was on the 5-ft. 3-in. gauge, but it was soon altered to 3 ft. 6 in. On the west coast of that island an experiment is being made in the construction of a 2-ft. gauge line, at one-fourth the cost of a line laid down to the Tasmanian standard gauge. The advisableness of constructing lines of this class is also being considered in Victoria. The total length of line in Australasia laid down to a gauge of 5 ft. 3 in. is 3,888 $\frac{1}{4}$  miles ; there are 3,280 $\frac{3}{4}$  miles on the 4-ft. 8 $\frac{1}{2}$ -in. gauge, and 8,633 $\frac{1}{4}$  miles on the 3-ft. 6-in. gauge.

As far back as May, 1889, Mr. Eddy urged the Government of New South Wales to take action with the object of securing a uniform gauge for the states, and frequently since that date the Railway Commissioners have directed attention to the urgency of dealing with this important question before the states incur greater expenditure in railway construction. They have suggested that the settlement of the difficult question of the adoption of a standard gauge should be approached from the standpoint of which of the two gauges, 4 ft. 8 $\frac{1}{2}$  in. and 5 ft. 3 in., can be adopted at the least cost and with the smallest amount of inconvenience to the country ; and that the whole of the railways of New South Wales and Victoria, with that part of the South Australian lines laid to the 5-ft. 3-in. gauge, as well as the line to Cockburn, and all the lines in Queensland south of Brisbane leading to New South Wales, shall be altered to the standard, the cost of altering the railways and the rolling stock necessary to work them to be a national charge.

#### COMPARISON OF RAILWAY FACILITIES.

The population and area of territory per mile of line open vary considerably in the different states and New Zealand. In comparison with population, Western Australia, Queensland, and South Australia—the most extensive states—have the greatest mileage ; but in proportion to the area of territory, Victoria, Tasmania, and New Zealand take the lead. The annexed table shows the relation of the railway mileage

to population and to the area of each state and New Zealand for the year 1903-4 :—

State.	Per Mile of Line Open.	
	Population.	Area.
	No.	sq. miles.
New South Wales .....	426	93
Victoria .....	357	26
Queensland .....	172	221
South Australia* ..	194	475
Western Australia .....	105	459
Tasmania ..	289	42
Commonwealth .....	272	206
New Zealand .....	345	43
Australasia .....	282	182

\* Including Northern Territory.

In the following table are given the average population and area of territory per mile of line open in the principal countries of the world. Of course a fair comparison can only be made between Australasia and other young countries in process of development :—

Countries.	Length of Railway.	Per Mile of Line Open.	
		Population.	Area.
	miles.	No.	sq. miles.
United Kingdom .....	22,152	1,913	5.5
France .....	24,249	1,607	8.5
Germany .....	32,878	1,714	6.4
Austria-Hungary .....	22,911	1,982	10.5
Belgium .....	2,843	2,354	4.0
Netherlands .....	1,772	3,018	7.1
Switzerland .....	2,727	1,216	5.9
Sweden .....	7,588	685	22.8
Norway .....	1,461	1,533	84.9
Russia (exclusive of Finland) .....	30,341	3,417	64.3
Spain .....	8,880	2,222	22.2
Italy .....	9,980	3,309	11.1
India (inclusive of Native States) .....	25,931	11,352	69.1
Canada .....	18,868	285	191.8
Cape Colony .....	3,139	797	70.5
Argentine Republic .....	11,000	457	103.3
Brazil .....	9,370	1,530	343.4
Chili .....	2,800	1,124	109.9
United States of America .....	208,132	356	17.5
Commonwealth of Australia .....	14,464	272	206
Australasia .....	16,876	282	182

## COST OF CONSTRUCTION.

At the close of the year 1903-1904, the cost of construction and equipment of the state railways completed and open to traffic in the Commonwealth was, in round figures, £131,930,000, or 57·96 per cent. of the public debts of the states comprised in the Federation, after deducting sinking funds. The construction and equipment of the railways of Australasia cost £152,623,700, or 53·52 per cent. of the public debt of Australasia, after deducting sinking funds. To what extent the states have contributed to this expenditure will be apparent from the subjoined table, showing the total cost and the average per mile :—

State.	Year.	Length of line open.	Gauge.	Total cost of Construction and Equipment.	Average cost per mile.
		miles.	ft. in.	£	£
New South Wales .....	1904	3,280½	4 8½	42,288,517	12,890
Victoria .....	„	3,381	5 3	41,216,703	12,191
Queensland .....	„	2,928	3 6	20,887,585	7,134
South Australia .....	„	1,736½	{ 5 3 3 6 }	13,517,727	7,785
Northern Territory.....	„	145½	3 6	1,180,574	4,057
Western Australia .....	„	1,541	3 6	8,955,929	5,812
Tasmania .....	1903	461½	3 6	3,883,729	8,411
Commonwealth .....	.....	13,474½	.....	131,930,764	9,791
New Zealand .....	1904	2,328	3 6	20,692,911	8,888
Australasia .....	.....	15,802½	.....	152,623,675	9,658

It will be seen that the lines which have been constructed most cheaply are those of Western Australia, where the average cost per mile has only been £5,812, as compared with an average of £9,791 for the Commonwealth and £9,658 for the whole of Australasia. In that state there have been few engineering difficulties to contend with, and the lines laid down have been of a light kind. In New South Wales, the average cost, given as £12,890, has been somewhat reduced lately, in consequence of the construction of light "Pioneer" lines, built

at an expenditure of £2,019 per mile. The Minister for Public Works has constructed 16, and is constructing 2 new lines by day labour, as the Railway Construction Department has had a somewhat unfortunate experience in regard to claims for extras to contracts, and expensive litigation in resisting such claims. In Victoria the average cost has been reduced from £13,153 to £12,191 since 1891. At that date it was decided to apply the "butty-gang" system to the construction of railways in the state, and to build all new country lines as cheaply as possible, and this principle has been strictly adhered to. Fairly substantial permanent-way has been laid down, with reduced ballast; unless absolutely necessary, fencing and gatehouses have been dispensed with; and only a skeleton equipment for stations and water supplies has been provided. As settlement progresses and traffic is developed, it is intended to raise these lines to the requisite standard of efficiency.

It would hardly be fair to institute a comparison between the cost of construction per mile in Australasia and in the densely-populated countries of Europe, for while in Europe the resumption of valuable ground is perhaps the heaviest expense in connection with the building of railways, in the states and New Zealand this item of expenditure is not of leading importance. The cost per mile in certain sparsely-settled countries is as follows :—

Canada .....	£12,409
Cape Colony .....	10,367
United States .....	12,819
Argentina.....	10,213
Mexico .....	9,417
Chili .....	10,103
Brazil .....	14,355

while for the Commonwealth of Australia it is £9,791, and for New Zealand £8,888.

#### REVENUE AND WORKING EXPENSES.

The avowed object of state railway construction in Australasia has been to promote settlement, apart from considerations of the profitable working of the lines; but at the same time the principle has been kept in view that in the main the railways should be self-supporting, and some of the states have, with more or less success, handed them over to Commissioners to be worked according to commercial principles, free from political interference. With the exception of South Australia, so

far as the Palmerston-Pine Creek line in the Northern Territory is concerned, in all the states the revenue derived from the railway traffic exceeds the working expenses. During 1898-9 the states of New South Wales and Western Australia derived a profit from the working of the lines; and for the year ended 30th June, 1900, the states of South Australia proper and Western Australia were similarly favoured. In 1900-1, the lines of New South Wales and Western Australia, and for the years ended 30th June, 1902, 1903, and 1904 those of Western Australia, not only paid working expenses and interest but left a slight margin of profit. Even in New South Wales, where the Commissioners have achieved most commendable results during the term of their administration, there is a fairly large deficiency for the year ended 30th June, 1904, when it is borne in mind that the average price received for the loans of the state is but £96·45 per £100 of stock, and the interest payable is calculated accordingly. The net sum available to meet interest charges during the last two working years will be found in the following table, showing the earnings and working expenses:—

State.	Working year, 1902-1903.			Working year, 1903-1904.		
	Gross Earnings.	Working Expenses.	Net Earnings.	Gross Earnings.	Working Expenses.	Net Earnings.
	£	£	£	£	£	£
New South Wales.....	3,314,893	2,266,299	1,048,594	3,436,413	2,258,940	1,177,473
Victoria .....	3,046,858	2,032,087	1,014,771	3,438,141	2,022,403	1,415,738
Queensland .....	1,234,230	863,382	370,848	1,305,552	811,951	493,601
South Australia .....	1,076,612	624,511	452,101	1,160,630	675,395	485,244
Northern Territory ....	11,298	12,812	(—) 1,514	17,006	13,219	3,787
Western Australia ....	1,558,485	1,247,878	306,612	1,588,084	1,179,624	408,460
Tasmania* .....	233,210	173,292	59,918	247,683	160,355	81,328
Commonwealth ..	10,470,596	7,220,256	3,250,330	11,193,518	7,127,887	4,065,631
New Zealand† .....	1,974,038	1,343,415	630,623	2,189,641	1,438,724	741,917
Australasia .....	12,444,624	8,563,671	3,880,953	13,374,159	8,566,611	4,807,548

\* Years ended 31st December, 1902 and 1903.

† Years ended 31st March, 1903 and 1904.

The proportion of gross earnings absorbed by working expenses during each of the last five years will be found below :—

State.	Percentage of Gross Earnings absorbed by Working Expenses.				
	1899-1900.	1900-01.	1901-02.	1902-03.	1903-04.
New South Wales .....	55·93	57·17	61·80	63·37	65·74
Victoria .....	62·89	62·17	64·31	66·69	58·82
Queensland .....	64·78	80·34	71·82	69·95	62·19
South Australia .....	56·37	58·95	63·54	58·01	58·19
Northern Territory .....	164·47	182·59	276·70	113·40	77·73
Western Australia .....	68·40	77·19	82·58	80·33	74·23
Tasmania* .....	79·10	79·07	84·26	74·31	67·16
Commonwealth .....	61·46	64·66	67·41	68·96	63·68
New Zealand† .....	64·80	65·30	66·80	68·05	65·98
Australasia .....	61·94	64·75	67·33	68·73	64·05

\* Years ended 31st December, 1899-1903.

† Years ended 31st March, 1900-04.

It will be seen from this table that the percentage of working expenses for the states comprised in the Commonwealth has increased from 61·46 to 63·68 in the course of the five years; the increase for Australasia as a whole being from 61·94 to 64·05. In each state of the Commonwealth and New Zealand, with the exception of Victoria, Queensland, Northern Territory and Tasmania, the working expenses have increased during the quinquennial period. In New South Wales, the increase was 9·81 per cent.; in South Australia proper, 1·82 per cent.; in Western Australia, 5·88 per cent.; and in New Zealand, 2·11 per cent.; while the reduction in Victoria was 4·07 per cent.; in Queensland, 2·59 per cent.; in the Northern Territory, 86·74 per cent.; and in Tasmania, 11·94 per cent. At the present time the proportion of gross earnings absorbed by working expenses is smallest in South Australia proper, and, setting aside the Northern Territory railway, highest in Western Australia.

The following statement gives an analysis of the working expenses for the year 1904 for all the states except Tasmania, where the figures refer to the year 1903, distinguishing the expenditure on maintenance, locomotive power, repairs and renewals, traffic expenses, and general charges. The distribution under the various heads is that made by the railway authorities, and, so far as can be seen, like charges have been



grouped together in every case. For New South Wales and Victoria the table shows an item "Pensions and Gratuities"; in the other states expenditure under this heading is included with general charges. The item of "Compensation" can be given for all the states with the exception of Queensland, Tasmania, and New Zealand, where it is not separately shown. The important distinction of repairs to carriages and waggon and of maintenance of locomotive power is unfortunately not observed by Western Australia and Tasmania, the manner in which such repairs are carried out precluding the possibility of an exact distribution of the outlay. It is not proposed to enter into a comparison of the various branches of expenditure, since the differences disclosed by the table arise not from exigencies of working, but from the needs of the treasurers of the states, and the freedom of control, or otherwise, allowed to the managers. In a subsequent part of this chapter which deals with the railway systems of the states individually, an analysis is given of the working expenses for ten years.

Expenditure on—	New South Wales.	Victoria.	Queensland.	South Australia (Proper).	North-east Territory.	Western Australia.	Tasmania.	New Zealand.
<b>Maintenance—</b>								
Total.....£	512,880	545,013	277,913	164,066	7,087	264,480	51,967	490,819
Per train mile.....d.	11.99	16.37	14.36	10.53	53.54	13.82	18.4	20.72
Per mile open.....£	163.1	102.09	98.3	94.40	42.40	172.3	110.3	212.94
<b>Locomotive Power—</b>								
Total.....£	572,547	465,544	168,540	100,921	2,205	336,708	62,374	306,785
Per train mile.....d.	13.24	11.98	8.71	12.82	17.46	17.50	16.0	13.96
Per mile open.....£	199.1	135.14	50.6	115.00	15.78	219.3	133.0	128.00
<b>Rolling Stock Repairs and Renewals—</b>								
Total.....£	480,621	287,488	140,219	143,606	1,225	244,947	Included under Locomotive Power.	219,371
Per train mile.....d.	11.69	7.53	7.71	9.22	9.32	12.79		9.23
Per mile open.....£	150.9	86.28	52.3	89.74	8.42	150.6		95.17
<b>Traffic Expenses—</b>								
Total.....£	601,084	577,799	196,806	151,697	2,300	306,998	42,820	374,247
Per train mile.....d.	13.88	15.11	10.18	9.74	17.90	16.04	11.0	15.80
Per mile open.....£	189.0	122.40	60.0	87.37	18.64	209.0	91.3	163.41
<b>Compensation—</b>								
Total.....£	5,750	8,216	....	1,571	2	3,940	....	....
Per train mile.....d.	0.13	0.21	....	0.10	0.01	0.21	....	....
Per mile open.....£	1.9	2.44	....	0.91	0.91	2.5	....	....
<b>Pensions and Gratuities—</b>								
Total.....£	6,708	100,836	....	....	....	....	....	....
Per train mile.....d.	0.15	2.63	....	....	....	....	....	....
Per mile open.....£	2.1	29.82	....	....	....	....	....	....
<b>General Charges—</b>								
Total.....£	71,291	47,897	19,473	14,574	309	22,601	9,292	67,402
Per train mile.....d.	1.66	1.24	1.01	0.94	2.74	1.17	3.4	1.75
Per mile open.....£	22.4	14.18	6.9	8.39	2.48	14.7	19.6	20.56
<b>Total Expenses—</b>								
Total.....£	2,253,940	2,023,403	811,961	675,395	13,219	1,176,094	166,355	1,433,784
Per train mile.....d.	52.12	52.92	41.24	43.85	100.67	61.63	42.3	60.48
Per mile open.....£	700.5	599.96	237.2	348.99	90.91	768.4	254.7	624.17

## INTEREST RETURNED ON CAPITAL.

In establishing the financial results of the working of the lines, it is the practice of the railway authorities to compare the net returns with the nominal rate of interest payable on the railway loans outstanding, ignoring the fact that many loans were floated below par and that the nominal is not the actual rate of interest. A true comparison, of course, is afforded by taking the rate of interest payable on the actual sum obtained by the state for its outstanding loans. On this basis the only state which shows out advantageously during the year ended 30th June, 1904, was Western Australia, where the lines returned a profit of 1·07 per cent. after defraying interest charges on the capital cost. In New South Wales the receipts were adversely affected by the previous unfavourable season, and the interest returned only reached 2·78 per cent., while the actual rate payable on outstanding loans was 3·68 per cent., so that there was a deficiency of 0·90 per cent. on the year's transactions. Victoria suffered less from the effects of the adverse season, the net receipts being 3·43 per cent. on the capital cost, while the actual rate of interest on outstanding loans was 3·78 per cent., there being thus a shortage of 0·35 per cent. on the year's working. For the Queensland lines the return was at the rate of 2·36 per cent. on the capital cost, while the interest charge on the loans of the state was equal to 3·92 per cent., the loss on the year's business being therefore 1·56 per cent. In South Australia proper, the net return for the year was equal to 3·59 per cent. on capital cost, and according to the method of comparison above adopted, this represents a loss of 0·10 per cent. for the year. As explained in subsequent pages, the lines in the Northern Territory are handicapped to such an extent that until the year just closed they did not pay even working expenses, the interest returned on capital cost being at the rate of 0·32 per cent., and this figure deducted from 5·30, the actual rate of interest payable on outstanding loans gives a deficiency of 4·98 per cent. on the year's transactions. The Tasmanian railway revenue showed a return equal to 2·09 per cent. on the capital cost, an improvement on the figures of previous years, but as the actual rate of interest on loans outstanding was 3·76 per cent., there was a deficiency equal to 1·67 per cent. For New Zealand lines the net revenue for the year was 3·58 per cent. on capital cost. No data exist on which a comparison can be made with actual rate of interest on outstanding loans, but the interest paid on the loans without taking into consideration the price received for the stock was 3·83 per cent., and on this basis the year shows a loss of 0·25 per cent.

The rate of return on capital represents the interest on the gross cost of the lines. In some cases the nominal amount of outstanding debentures is less than the actual expenditure on construction and equipment, owing to the fact that some loans have been redeemed; but as the redemption has been effected by means of fresh loans

charged to general services, or by payments from the general revenue, and not out of railway earnings, no allowance on this account can reasonably be claimed.

The table given below shows the rate of interest returned on the capital expenditure for each of the last five years, with the sum by which such return falls short of the actual rate of interest payable on cost of construction. In the case of New Zealand, only the nominal loss is shown; the actual loss was somewhat higher :—

State.	1890-1900.	1900-01.	1901-2.	1902-3.	1903-4.
	Per cent.	Per cent.	Per cent.	Per cent.	Per cent.

INTEREST RETURNED ON CAPITAL EXPENDITURE.

New South Wales .....	3·62	3·93	3·45	2·52	2·78
Victoria .....	2·83	3·14	2·96	2·47	3·43
Queensland .....	2·67	1·31	1·93	1·48	2·36
South Australia .....	3·91	3·86	2·98	3·08	3·59
Northern Territory .....	(—)0·82	(—)0·98	(—)1·99	(—)0·13	0·32
Western Australia .....	5·81	4·35	3·54	3·75	4·56
Tasmania* .....	1·12	1·16	0·85	1·56	2·09
Commonwealth .....	3·25	3·14	2·88	2·51	3·08
New Zealand .....	3·42	3·48	3·43	3·31	3·58
Australasia .....	3·27	3·18	2·95	2·61	3·15

NET LOSS ON WORKING LINES.

New South Wales .....	0·14	+0·19	0·23	1·15	0·90
Victoria .....	1·06	0·62	0·76	1·39	0·35
Queensland .....	1·35	2·67	2·01	2·44	1·56
South Australia .....	+0·02	0·01	0·83	0·66	0·10
Northern Territory .....	4·86	5·03	6·36	4·50	4·98
Western Australia .....	+2·29	+0·83	+0·07	+0·27	+1·07
Tasmania* .....	2·69	2·62	2·91	2·20	1·67
Commonwealth .....	0·59	0·65	0·86	1·26	0·67
New Zealand .....	0·37	0·30	0·33	0·40	0·25
Australasia .....	0·55	0·60	0·80	1·14	0·62

\* Years 1899 to 1903.

† Net profit.

In 1881 the New South Wales railways yielded 5·31 per cent.—a higher rate of interest on the capital cost than was ever reached before or since. In the same year the Victorian lines yielded a return of 4·04 per cent., which is the highest on record in that state, with the exception of 4·18 in the year 1886. The decline in the net profits was largely due to the extension of the lines in sparsely-populated districts; but

with the adoption of a more prudent policy in the matter of construction, rendered necessary by the severe financial pressure to which the states were subjected, and with more careful management, the returns, as will be evident from the foregoing table, are again showing improvement.

#### EARNINGS AND EXPENSES PER MILE.

The gross earnings, expenditure, and net earnings per average mile worked during the last two years were as follow :—

State.	Gross Earnings.		Expenditure.		Net Earnings.	
	1902-03.	1903-4.	1902-03.	1903-4.	1902-03.	1903-4.
	£	£	£	£	£	£
New South Wales..	1,093	1,079	747	709	346	370
Victoria .....	913	1,020	609	600	304	420
Queensland .....	444	462	311	287	133	175
South Australia ...	620	668	360	389	260	279
Northern Territory	78	117	88	91	(—) 10	26
Western Australia..	1,063	1,034	870	768	213	266
Tasmania* .....	498	528	370	384	128	174
Commonwealth	811	841	559	535	252	306
New Zealand .....	873	943	594	622	279	321
Australasia...	815	859	561	550	254	309

\* 1902 and 1903.

For the states comprised in the Commonwealth the gross earnings per average mile worked during 1903-4 were £30 higher than in the previous year, and the working expenses were less by £24, leaving the net earnings at £306 in 1903-4, as compared with £252 in 1902-3. For the whole of Australasia the gross earnings per average mile worked during 1903-4 were £44 more than in the previous year, and the working expenses were reduced by £11, leaving the net earnings at £309 in 1903-4 as against £254 in 1902-3. On the next page will be found a table giving the returns per train mile. The states of New South Wales, Victoria, Queensland, and South Australia proper,

and Western Australia, show a reduction in the train mileage during 1903-4, in comparison with that of the previous year :—

State.	Gross Earnings.		Working Expenses.		Net Earnings.	
	1902-03.	1903-4.	1902-03.	1903-4.	1902-03.	1903-4.
	d.	d.	d.	d.	d.	d.
New South Wales.....	68·89	79·30	47·10	52·13	21·79	27·17
Victoria .....	71·09	89·95	47·41	52·92	23·68	37·03
Queensland .....	59·87	67·43	41·88	41·94	17·99	25·49
South Australia .....	68·53	74·49	39·75	43·35	28·78	31·14
Northern Territory.....	89·13	129·38	101·07	100·57	(-)11·94	28·81
Western Australia.....	80·85	82·96	64·95	61·62	15·90	21·34
Tasmania* .....	61·99	63·79	46·06	42·84	15·93	20·95
Commonwealth.....	69·62	80·13	48·01	51·04	21·61	29·09
New Zealand.....	87·02	91·75	59·23	60·48	27·79	31·27
Australasia .....	71·90	81·88	49·48	52·44	22·42	29·44

\* 1902 and 1903.

#### FINANCIAL RESULTS OF FOREIGN RAILWAYS.

The interest on capital cost, the proportion of working expenses to the gross revenue, and the return per train mile for the railways of some of the principal countries of the world are given below. The figures for the countries other than Australasia refer in most cases to the year 1903 or 1902, but in some instances there was no later information than for the year 1901.

Country.	Capital Cost.			Working Expenses : Proportion to Gross Revenue.	Per Train Mile.		
	Total.	Per Mile Open.	Return Per Cent.		Gross Revenue.	Working Expenses.	Net Revenue.
	£	£	p. cent.	per cent.	d.	d.	d.
United Kingdom .....	1,245,028,917	55,500	3·40	61·80	67·6	41·8	25·8
France .....	670,360,000	23,768	3·77	56·27	66·9	37·0	29·9
Germany .....	666,527,000	31,696	5·05	66·47	73·0	47·7	25·3
Belgium .....	81,266,844	2,826	3·84	66·77	54·5	37·0	17·5
United States .....	2,435,031,000	197,237	6·31	64·86	86·5	56·0	30·6
Canada .....	235,624,901	12,409	2·50	70·25	78·5	55·1	23·4
Cape Colony .....	24,081,778	2,818	6·29	71·42	108·1	73·6	29·5
Commonwealth of Aus- tralia .....	131,930,764	9,791	3·08	63·68	80·1	51·0	29·1
Australasia .....	152,623,675	9,668	3·15	64·06	81·9	52·5	29·4

The figures given above for Cape Colony are for state lines only, and as regards Belgium, the gross revenue, working expenses, and net revenue per train mile relate to the state lines only.

## COACHING AND GOODS TRAFFIC.

The following table shows the number of passengers carried on the lines of the various states during the years 1881, 1891-2, 1901-2, and 1903-4. The number of journeys on the Victorian lines during the year ended 30th June, 1902, approximates to those of 1888-9, 1889-90, and 1890-91, and though, in common with the rest of the states, a great reduction occurred in 1893-94, the traffic, since the latter year, has manifested an upward movement. All the states have experienced the effects of the diminished spending power of the people, following on the financial crisis, but in every case a recovery has taken place. The number of passenger journeys in Tasmania in 1903 shows a small increase compared with the returns for 1891:—

State.	Passengers carried.			
	1881.	1891-2.	1901-2.	1903-4.
New South Wales .....	6,907,312	19,918,916	30,885,214	33,792,689
Victoria .....	18,964,214	55,148,122	57,465,077	54,282,003
Queensland* .....	247,284	2,370,219	4,636,174	4,144,314
South Australia .....	3,032,714	5,744,487	9,497,222	9,747,412
Northern Territory .....	.....	4,541	3,755	3,653
Western Australia.....	67,144	456,631	8,158,299	10,225,976
Tasmania. ....	102,495	704,531	777,445	814,483
Commonwealth .....	29,321,163	84,347,447	111,423,186	113,010,530
New Zealand .....	2,911,477	3,555,764	7,356,136	8,306,383
Australasia .....	32,232,640	87,903,211	118,779,322	121,316,913

\* Exclusive of journeys of season ticket-holders.

The amount of goods tonnage is shown in the subjoined table. In the period from 1881 to 1891 there was an increase of about 102 per cent., varying from 44 per cent. in New Zealand to 747 per cent. in Tasmania, while from 1891-2 to 1901-2, the increase has varied from 4 per cent. in South Australia to 1,401 per cent. in Western Australia,

with an average of nearly 63 per cent. for the Commonwealth, and 64 per cent. for the whole of Australasia.

State.	1881.	1891-2.	1901-2.	1908-4.
	tons.	tons.	tons.	tons.
New South Wales .....	2,033,850	4,296,713	6,467,552	6,656,759
Victoria .....	1,366,603	2,720,886	3,433,627	3,439,203
Queensland.....	161,008	768,527	1,725,620	1,572,226
South Australia.....	646,625	1,337,859	1,392,257	1,515,621
Northern Territory .....	.....	2,633	2,436	6,209
Western Australia .....	27,816	135,890	2,040,092	2,281,764
Tasmania .....	21,043	178,224	314,628	418,701
Commonwealth .....	4,256,945	9,440,732	15,376,112	15,890,483
New Zealand .....	1,437,714	2,066,791	3,529,177	3,918,261
Australasia.....	5,694,659	11,507,523	18,905,289	19,808,744

The percentage of receipts from coaching traffic to the total receipts is somewhat less in the states of the Commonwealth and New Zealand than in the United Kingdom, where for the year 1903 the coaching receipts formed 46·53 per cent. of the total obtained from goods and passenger traffic. The figures for each state are given below :—

State.	Coaching Traffic. per cent.	Goods Traffic. per cent.
New South Wales.....	41·98	58·02
Victoria .....	47·73	52·27
Queensland.....	37·94	62·06
South Australia.....	32·56	67·44
Northern Territory .....	19·10	80·90
Western Australia .....	31·06	68·94
Tasmania ..	46·52	53·48
Commonwealth.....	40·96	59·04
New Zealand.....	38·63	61·35
Australasia.....	40·59	59·41

#### AVERAGE WEIGHT OF TRAIN LOAD.

The useful comparisons that may be made between the railway systems of the various states are very limited, and greater uniformity in the presentation of the reports is extremely desirable in view of the provisions of the Commonwealth Act for the possible control of the railway systems by the central government. An example of want of uniformity in an important particular is the absence of

information which would enable the average train load to be ascertained. This information can only be given for two states—South Australia and New South Wales—and for the latter state, complete returns are available for three years only. The figures for South Australia show a considerable variation in the average weight during the last nine years; but, for the years 1899, 1900, 1901, and 1904, the average is uniformly high when compared with that for each of the preceding three years. In 1902 there was a considerable decline, consequent on a falling off in tonnage carried without a commensurate reduction in mileage; a slight improvement, however, was manifested during 1903. The figures quoted do not include the business of the Northern Territory:—

Year.	Goods mileage.	Ton mileage.	Average weight of train.
			tons.
1896	2,089,911	134,846,696	64·52
1897	2,265,277	159,454,588	70·34
1898	2,273,537	157,143,651	69·11
1899	2,426,477	191,041,569	78·73
1900	2,569,958	197,079,956	76·68
1901	2,686,789	202,649,157	75·42
1902	2,468,326	170,523,167	69·08
1903	2,311,250	165,357,307	71·54
1904	2,247,003	178,443,372	79·41

The average tonnage for goods trains is 72·9 tons, which is 5·1 tons higher than in New South Wales, the only other system with which a comparison can be made. The New South Wales figures, with the exception of those for the years 1900, 1901, 1902, 1903, and 1904, are unsatisfactory, inasmuch as the goods mileage relates to the year ended 30th June, while the ton mileage is for the year ending 31st December following. There are no returns for 1899:—

Year.	Goods mileage.	Ton mileage.	Average weight of train.
			tons.
1896	4,001,164	255,621,932	63·9
1897	4,244,385	273,400,624	64·4
1898	4,260,368	314,996,969	73·9
1900	4,610,343	320,364,852	69·5
1901	5,836,587	404,740,360	69·4
1902	6,586,032	436,814,308	66·3
1903	6,405,756	399,578,918	62·4
1904	5,304,660	393,094,107	74·1

The average for the period was 67·8 tons. The figures for New South Wales and for South Australia compare very favourably with the



returns of the British railways, but are very far behind those of the American and Canadian lines, as the following figures show :—

## BRITISH RAILWAYS.

Year.	Goods mileage.	Ton mileage.	Average weight of train.
			tons.
1870	82,423,000	4,622,000,000	56·10
1880	116,908,000	7,006,215,000	59·93
1890	145,206,000	8,311,183,000	57·74
1899	178,579,000	10,307,520,000	57·71
1900	181,048,000	10,665,240,000	58·91
1901	173,951,000	10,486,954,000	60·26
1902	170,602,000	10,392,400,000	63·84
1903	160,803,000	11,099,057,000	69·02

The particulars for the Canadian Pacific Railway for the years 1901 and 1902 are as follows :—

Year.	Goods mileage.	Ton mileage.	Average weight of train.
			tons.
1901	10,415,531	2,383,633,945	228·85
1902	12,828,159	3,247,922,167	253·19

The railways of the United States appear to great advantage compared with the British lines ; the average weight of train for the last eight years available was :—

Year.	Goods mileage.	Ton mileage.	Average weight of train.
			tons.
1895	491,410,820	88,567,770,801	180·23
1896	497,248,296	93,885,853,634	188·81
1897	500,326,372	97,842,569,150	195·56
1898	542,824,509	114,566,173,191	211·06
1899	534,391,846	126,991,703,110	237·64
1900	513,667,388	141,162,109,413	274·81
1901	505,468,619	148,959,303,492	294·70
1902	508,210,140	156,624,166,024	308·19

## ROLLING STOCK.

The following table gives the different classes of rolling stock in the possession of the several Australasian Governments at the end of the

year 1903-4, and although the numbers in each class are considerable, they could with advantage be largely increased in most of the states :—

State.	Engines.	Coaching Stock.	Goods Stock.
New South Wales .....	620	1,126	11,505
Victoria .....	550	1,613	10,025
Queensland .....	347	453	7,250
South Australia .....	339	432	6,071
Northern Territory .....	6	7	134
Western Australia .....	329	269	5,632
Tasmania .....	75	179	1,329
Commonwealth ...	2,266	4,079	41,946
New Zealand .....	377	809	13,433
Australasia .....	2,643	4,888	55,379

#### RAILWAY ACCIDENTS.

The persons meeting with accidents on railway lines may be grouped in three classes—passengers, servants of the railways, and trespassers; and the accidents themselves might be classified into those arising from causes beyond the control of the person injured, and those due to misconduct or want of caution. The following table shows the number of persons killed and injured on the Government railways during 1903-1904 in those states for which returns are available :—

State.	Passengers.		Railway Employees.		Trespassers, &c.		Total.	
	Killed.	Injured.	Killed.	Injured.	Killed.	Injured.	Killed.	Injured.
New South Wales .....	4	24	22	681	18	47	44	752
Victoria .....	2	316	7	328	19	37	28	681
South Australia .....	..	1	1	18	5	7	6	26
Northern Territory .....	..	.....	1	.....	..	.....	1	.....
New Zealand .....	10	16	2	13	..	2	12	31

The railways of Australasia have been as free from accidents of a serious character as the lines of most other countries. In order to obtain a common basis of comparison it is usual to find the proportion which the number of persons killed or injured bears to the total passengers carried. There is, however, no necessary connection between the two, for it is obvious that accidents may occur on lines chiefly devoted to goods traffic, and a more reasonable basis would be the accidents to passengers only compared with the number of passengers carried. The data from which such a comparison could be made are wanting for some countries. As far as the figures can be given they are shown in the

following table, which exhibits the number of passengers killed and injured per million carried. The figures are calculated over a period of ten years and brought down to the latest available dates :—

Country.	Number of Passengers.		Average per million passengers carried.	
	Killed.	Injured.	Killed.	Injured.
Germany.....	724	3,063	0·11	0·45
Austria-Hungary.....	209	2,069	0·12	1·19
Belgium.....	136	2,082	0·12	1·85
Sweden.....	23	45	0·15	0·29
France.....	699	3,500	0·19	0·95
Norway.....	10	18	0·13	0·23
Holland.....	30	153	0·11	0·58
Switzerland.....	83	438	0·16	0·86
Russia.....	638	2,761	0·93	4·02
United Kingdom.....	130	5,623	0·01	0·52
Spain.....	155	924	0·55	3·27
Canada.....	160	1,137	0·89	6·33
New South Wales.....	53	452	0·20	1·71
Victoria.....	26	1,694	0·05	3·57
South Australia.....	11	29	0·15	0·40
New Zealand.....	53	207	0·99	3·89

#### NEW SOUTH WALES.

The progress of railway construction during the twenty years which followed the opening of the first line was very slow, for in 1875 the length of line in operation had only reached 435 miles. From 1876 to 1889, greater activity prevailed, no less than 1,748 miles being constructed during the period, but this rate of increase was not continued, and only 14 miles were opened during the next three years. Subsequently there was renewed activity, and the length of line opened to 30th June, 1904, was 3,280½ miles, the amount expended thereon for construction and equipment being £42,288,517, or at the rate of £12,890 per mile.

The railways of the state are divided into three branches, each representing a system of its own. The southern system, which is the most important, serving as it does the richest and most thickly-populated districts, and placing Sydney, Melbourne, and Adelaide in direct communication, has several offshoots. From Culcairn, there are two branch lines, one connecting with Corowa on the Murray River, and the other with Germanton; from The Rock a line extends to Lockhart; from Junee a branch extends as far as the town of Hay in one direction, and Finley in another, and places the important district of Riverina in direct communication with Sydney. From Cootamundra a southerly branch carries the line to Tumut, and another

in a north-westerly direction through Temora to Wyalong. From Murrumburrah a branch has been constructed to Blayney, on the western line, thus connecting the southern and western systems of the state. From Koorawatha a branch has been laid down to connect Grenfell with the railway system. Nearer the metropolis, the important town of Goulburn is connected with Cooma, bringing the rich pastoral district of Monaro into direct communication with Sydney. From Goulburn, a branch line has also been opened to Crookwell. Another line that forms part of the southern system has been constructed to Nowra, connecting the metropolis with the coastal district of Illawarra, which is rich alike in coal and in the produce of agriculture. The western system of railways extends from Sydney over the Blue Mountains, and has its terminus at Bourke, a distance of 503 miles from the metropolis. Leaving the mountains, the western line, after throwing out a branch from Wallerawang to Mudgee, enters the Bathurst Plains, and connects with the metropolis the rich agricultural lands of the Bathurst, Orange, and Wellington districts. Beyond Dubbo it enters the pastoral country. At Blayney, as before stated, the western line is connected with the southern system by a branch line to Murrumburrah; at Orange a branch connects that town with Forbes on the Lachlan River, and from Parkes, one of the stations on this branch line, an extension to Condobolin on the Lachlan River has been constructed. Further west, at Dubbo, a branch line extends to Coonamble, and from the main line at Nevertire, a short line extends to the town of Warren, and at Nyngan a branch line connects the important mining district of Cobar with Sydney. From Byrock a line branches off to Brewarrina. The western system also includes a short line from Blacktown to Richmond on the Hawkesbury River. The northern system originally commenced at Newcastle, but a connecting line has been constructed, making Sydney the head of the whole of the railway systems of the state. This connecting line permits of direct communication between Adelaide, Melbourne, Sydney, and Brisbane, a distance from end to end of 1,808 miles, or altogether between the terminus of Oodnadatta, in South Australia, and Cunnamulla, in Queensland, there is one continuous line of railway, 3,100 miles in length. The northern system comprises a branch from Werri Creek, *via* Narrabri and Moree, to Inverell, thus placing the Namoi and Gwydir districts in direct communication with the ports of Newcastle and Sydney. There is also under construction a line from Narrabri to Walgett, with a branch to Collarenebri, and during the year just closed, the portion from Narrabri West to Burren Junction, a distance of  $51\frac{1}{2}$  miles, was opened for traffic. A portion of the North Coast railway has also been constructed from Murwillumbah, on the Tweed River, to Casino on the Richmond River, and an extension to Grafton is now in course of construction. A short line branches off the main northern line at Hornsby, and connects with the north shore of Port Jackson at Milson's Point.

Up to October, 1888, the control of the railways was vested in the Minister for Works, the direct management being undertaken by an officer under the title of Commissioner. It was, however, recognised that political influence entered unduly into the management of this large public asset, and, as a consequence, the "Government Railways Act of 1888" was passed, with the object of removing the control and management of the railways from the political arena, and vesting them in three railway Commissioners, who were required to prepare for presentation to Parliament an annual report of their proceedings, and an account of all moneys received and expended during the preceding year. While the avowed object of state railway construction has been to promote settlement, apart from consideration of the profitable working of the lines, the principle has nevertheless been kept in view that in the main the railways should be self-supporting. It will be seen, from subsequent pages, that, despite the fact that the Commissioners are hampered by a large number of unprofitable lines, they have succeeded in placing the railways of the state in a satisfactory financial position.

*Revenue and Working Expenses.*

The net sum available to meet interest charges during the last decennial period is set forth in the following table, and the returns show that the Commissioners have achieved most important results during their term of administration. A reference to the table on page 589 will show that on two occasions during the last decennial period the railways returned a small profit after meeting the charges for working expenses and interest on capital, while, with the exception of the last two years, there has been a considerable reduction in the percentage of average loss during the ten years. Owing to the adverse season, the year 1903 was financially the worst in the history of the railways of the state.

Year.	Gross Earnings.	Working Expenses.	Net Earnings.	Proportion of Working Expenses to Gross Earnings.
	£	£	£	per cent.
1895	2,878,204	1,567,589	1,310,615	54·46
1896	2,820,417	1,551,888	1,268,529	55·02
1897	3,014,742	1,601,218	1,413,524	53·11
1898	3,026,748	1,614,605	1,412,143	53·34
1899	3,145,273	1,690,442	1,454,831	53·75
1900	3,163,572	1,769,520	1,394,052	55·93
1901	3,573,779	2,043,201	1,530,578	57·17
1902	3,668,686	2,267,369	1,401,317	61·80
1903	3,314,893	2,266,299	1,048,594	63·37
1904	3,436,413	2,258,940	1,177,473	65·74

In the foregoing table will be found ample evidence of the economical working of the state railways under their present management, for, despite the somewhat unfavourable conditions, the net earnings for the

financial year ended 30th June, 1904, were 34·26 per cent. of the total earnings, as against 33·31 per cent. when the Commissioners took office. The financial depression of 1893, which brought about a great change in the character of the coaching traffic, and the continued unfavourable character of the seasons, adversely affected the earnings of several years; the fall in earnings, however, was met by a reduction in working expenses, so that the satisfactory results of the railway management were not greatly affected. The year 1900 compares somewhat unfavourably with the three years immediately preceding. This is due to the fact that, notwithstanding a much larger tonnage carried, the merchandise and live stock traffic showed a decrease in freight earned, clearly indicating that the traffic from these sources had been carried at less profitable rates than hitherto. The traffic in wool and hay also showed a large falling off, but there was no further diminution in the net earnings for the year 1901, the total, £1,530,578, being the largest for the period shown in the table. The revenue exceeded that of the previous year by £410,207, towards which all classes of traffic contributed. The increased traffic, the greater cost of coal and materials, and the more liberal advances granted to the wages staff, were responsible for the rise of £273,681 in the working expenses. For the year ended 30th June, 1902, however, a considerable falling off in the net earnings occurred. The rise from 57·17 to 61·80 in the percentage of working expenses to gross earnings was due to the increased volume of traffic carried at exceptionally low rates, largely contributed to by the concessions made in the carriage of starving stock and fodder. The increased cost of fuel, the additional repairs to the rolling stock and permanent way, the necessity for hauling water for locomotive and other purposes, and the increments granted to the staff, also contributed to the reduction in net earnings. As previously pointed out, the year ended June, 1903, was the most disastrous in the history of the railways of New South Wales. Owing to the long-continued dry weather, water had to be despatched by train to several remote parts of the state, and large quantities for locomotive uses had also to be transported for long distances. The latter, of course, was carried free, while merely a nominal rate was charged for the former, the working expenses being thereby heavily burdened, with practically no corresponding gain to revenue. During the year live stock was carried at greatly reduced rates from the drought-stricken areas to places where feed was obtainable, while fodder for starving animals was carried at an extremely low charge. Exclusive of terminal charges, the average rate on all fodder carried fell to 0·04d., and on all live stock to 1·23d. per ton per mile, without taking into consideration the amount of empty, and consequently unprofitable, running involved.

The revenue for the year ended 30th June, 1904, shows an increase of £121,520 over that of the previous year, while there was a decrease of £7,359 in expenditure. All classes of traffic, with the exception of general merchandise, wool, and live stock, contributed to the improved result. The falling off in general merchandise is greater than the

actual figures indicate, as the earnings for the previous year showed a reduction of £33,540. The shortage in wool and live stock tonnage in conjunction with the falling off in the carriage of general merchandise indicate that the recent disastrous seasons are still affecting the volume of traffic.

The cost of working has steadily increased over the last four years of the decade, and this has in great measure been brought about by the increased cost of fuel, the heavier expenditure on stores, and the large outlay on wages. Much of the additional charge under the last-mentioned heading has been necessitated by the adoption of eight hours instead of nine hours per day for the running staff. Renewals and replacement of old stock also added a heavy burden to the total expenditure. For the last quinquennial period the average charge for maintenance amounted to £483,752, as against £366,573 for the preceding five years, the capital account having been debited only with expenditure on new lines and the outlay necessary to meet the heavy growth of passenger and goods traffic.

The proportion of working expenses to earnings is less in New South Wales than in any other state, with the exception of South Australia, as the following figures, which are the average of the five years 1900-4, will show :—

	Per cent.
New South Wales .....	61·81
Victoria.....	62·89
Queensland .....	69·74
South Australia .....	60·16
Western Australia .....	76·83
Tasmania .....	76·31
New Zealand .....	66·25

An analysis is given hereunder of the working expenses of the New South Wales railways for the ten years, 1895-1904; in this statement the total expenses as well as the expenses per train mile and per mile of line in operation, are given. It will be seen that there has been a general reduction in the expenditure per train mile, and this reduction is visible in all the details included in the total, with the exception of the expenditure upon locomotive power, which has slightly increased during the ten years. In regard to the working expenses generally, it may be said that the condition of affairs revealed by the table is satisfactory. When the Commissioners took over the management of the railways in 1888, large renewals of rolling stock were needed, while additional expenditure had to be incurred on permanent way and buildings. The result of this will be seen in the high outlay per train mile and per mile open in the earlier years of the decade. By the year 1896, the lines were in thorough working order, and have been so maintained since that date. The rolling stock has been very greatly improved; the tractive power of the engines has been increased, and

types of locomotives adapted to the special and general needs of the traffic introduced.

Year ended 30th June.	Maintenance of Way, Works, and Buildings.	Locomotive Power.	Rolling Stock Repairs and Renewals.	Traffic Expenses.	Compensation.	Pensions and Gratuities.	General Charges.	Total.
	£	£	£	£	£	£	£	£
1886	399,879	347,769	277,664	441,798	33,233	8,446	59,001	1,567,569
1886	350,964	362,069	321,239	437,591	15,248	3,875	60,879	1,551,896
1897	358,057	374,322	352,818	444,857	2,894	5,208	63,067	1,601,218
1898	363,969	378,504	358,112	455,545	3,296	4,504	60,075	1,614,906
1899	370,197	415,399	361,638	471,532	5,451	2,652	63,523	1,690,442
1900	406,044	418,113	390,234	478,818	4,164	4,250	67,347	1,769,529
1901	484,750	498,612	443,491	537,227	11,111	4,764	69,246	2,043,201
1902	521,983	585,767	474,047	583,938	20,234	6,296	70,104	2,267,369
1903	486,596	625,027	464,802	606,210	7,070	3,126	69,468	2,236,239
1904	519,389	573,547	480,621	601,634	5,750	6,708	71,291	2,256,940

## PER TRAIN MILE.

	d.	d.	d.	d.	d.	d.	d.	d.
1886	12·63	10·99	8·77	13·98	1·06	·27	1·87	69·54
1886	10·91	11·26	9·99	13·60	·47	·12	1·89	43·24
1897	10·57	11·06	10·41	13·13	·09	·15	1·86	47·26
1898	10·18	10·89	10·30	13·11	·10	·13	1·75	46·46
1899	10·09	11·33	9·86	12·85	·14	·07	1·73	46·07
1900	10·96	11·29	10·53	12·92	·11	·11	1·83	47·76
1901	10·81	11·00	9·37	11·96	·25	·10	1·55	45·56
1902	10·75	12·07	9·76	12·13	·42	·13	1·45	46·71
1903	10·11	12·98	9·66	12·53	·15	·17	1·45	47·10
1904	11·99	13·24	11·09	13·83	·13	·15	1·65	52·13

## PER MILE OPEN.

	£	£	£	£	£	£	£	£
1886	168·9	138·2	110·4	175·6	13·3	3·4	23·4	623·1
1886	188·6	148·0	126·9	172·9	6·0	1·5	24·1	613·0
1897	189·0	146·4	137·0	172·7	1·1	2·0	24·5	621·7
1898	183·1	142·3	134·7	171·3	1·3	1·7	22·8	607·2
1899	136·9	153·6	133·8	174·4	2·0	1·0	23·5	625·2
1900	147·9	152·3	142·2	174·5	1·5	1·7	24·7	644·3
1901	174·5	177·7	159·3	193·2	4·1	1·7	25·0	735·5
1902	179·2	201·1	162·7	202·2	6·9	2·2	24·1	778·4
1903	160·4	206·0	153·2	192·5	2·4	2·7	22·3	747·0
1904	163·1	180·1	150·9	189·0	1·9	2·1	22·4	769·5

*Interest returned on Capital.*

In establishing the financial results of the working of the lines it is the practice of railway authorities to compare the net returns with the nominal rate of interest payable on the railway loans or on the public debt of the state. As previously pointed out, an accurate comparison can only be made by taking the average rate of interest payable on the actual sum obtained by the state for its outstanding loans. On this basis, the lines of the state have met the interest on construction and equipment during five years only, viz., 1881, 1882, 1883, 1899, and 1901. In 1901 the lines yielded a net sum of £74,000 after paying working expenses, interest, and all charges, but the year 1902 showed a loss of £91,000, and 1903, a further loss of £480,000, while for the year ended 30th June, 1904, the loss was £380,000. The



following table shows the average loss for each year during the period 1895-1904 :—

Year.	Interest returned on Capital.	Actual Rate of Interest payable on Outstanding Loans.	Average Loss.
	per cent.	per cent.	per cent.
1895	3.58	3.94	0.36
1896	3.44	3.86	0.42
1897	3.78	3.81	0.03
1898	3.74	3.78	0.04
1899	3.83	3.75	*0.08
1900	3.62	3.76	0.14
1901	3.93	3.74	*0.19
1902	3.45	3.68	0.23
1903	2.52	3.67	1.15
1904	2.78	3.68	0.90

\* Average gain.

The fluctuation of the profits is partly owing to the extension of the lines in sparsely-populated districts; but as a result of more economical working the returns show an improvement during the period, with the exception of 1903 and 1904, the position of those years being due to the special circumstances dealt with in preceding pages. Regard must be paid to the fact, moreover, that there are twenty-five branch lines on which over thirteen millions sterling have been expended which do not pay their way, the loss on these lines being about £250,000 per annum.

#### *Earnings and Expenses per Mile.*

Two important facts which demonstrate the financial position of the railways and the character of the management are the earnings per train mile and per average mile open. Although the returns now being realised cannot be compared with those of 1875, when the net earnings per train mile fell little short of 52d., and per mile open of £775, the earnings, with the exception of those for the years 1902, 1903, and 1904 are in every way encouraging. The falling off in 1902 was largely due to the increased volume of traffic carried at exceptionally low rates, the average revenue derived from all descriptions of merchandise and live stock traffic, exclusive of terminal charges, having decreased from 1.13d. to 1.07d. per ton per mile. Under the control of the Commissioners the net return per train mile during that year was increased from 27.4d. to 28.9d., or 5.5 per cent.; while per mile of line open for traffic the advance has been from £374 to £481, or 28.6 per cent. During the year ended 30th June, 1903, the adverse circumstances already alluded to brought about a considerable reduction, and the net earnings per train mile fell to 21.79d., and per mile open for traffic to £346. While the results for 1904 show an improvement on those of the previous year, the net earnings per train mile having increased to 27.17d., and per mile open for traffic to £370, there is a substantial decrease in the tonnage of

general merchandise, wool, and live stock, thus showing that the recent disastrous seasons are still adversely affecting the traffic. The gross earnings, expenditure, and net earnings per train mile for the past ten years are shown in the following table:—

Year.	Gross Earnings per train mile.	Expenditure per train mile.	Net Earnings per train mile.
	d.	d.	d.
1895	90·96	49·54	41·42
1896	87·68	48·24	39·44
1897	88·99	47·26	41·73
1898	87·10	46·46	40·64
1899	85·72	46·07	39·65
1900	85·36	47·75	37·61
1901	79·69	45·56	34·13
1902	75·58	46·71	28·87
1903	68·89	47·10	21·79
1904	79·30	52·13	27·17

The gross earnings, expenditure, and net earnings per average mile open for the past ten years, were as follow :—

Year.	Gross Earnings per average mile open.	Expenditure per average mile open.	Net Earnings per average mile open.
	£	£	£
1895	1,144	623	521
1896	1,114	613	501
1897	1,171	622	549
1898	1,138	607	531
1899	1,163	625	538
1900	1,153	645	508
1901	1,286	735	551
1902	1,259	778	481
1903	1,093	747	346
1904	1,079	709	370

In many cases the railways of the state pass through heavy and mountainous country, involving steep gradients, some of the worst of which are situated on the trunk lines. For the more expeditious and economical working of the traffic, important deviations have been and are being carried out to secure better grades and to ease the curves. In the southern system, the line at Cooma reaches an altitude of 2,659 feet above the sea level; in the western, at the Clarence station, Blue Mountains, a height of 3,658 feet is attained; while on the northern line the highest point, 4,471 feet, is reached at Ben Lomond. In no other state of the Commonwealth or New Zealand do the lines attain such an altitude. In Queensland, the maximum height is 3,008 feet; in Victoria, 2,452 feet; in South Australia, 2,024 feet; in Western Australia, 1,522 feet; and in New Zealand, 1,252

sect. Where heavy gradients prevail, the working expenditure must necessarily be heavier than in the states where the surface configuration is more level.

*Coaching and Goods Traffic.*

The following table shows the number of passengers carried on the lines of the state during the year 1881, and for the last ten years, together with the receipts from the traffic, and the average receipts per journey :—

Year.	Passengers carried.	Receipts from Coaching Traffic.	Average Receipts per journey.
	No.	£	d.
1881	6,907,312	488,675	16·97
1895	19,725,418	1,022,901	12·45
1896	21,005,048	1,043,922	11·93
1897	22,672,924	1,098,696	11·63
1898	23,233,206	1,126,257	11·63
1899	24,726,067	1,158,198	11·22
1900	26,486,873	1,227,355	11·12
1901	29,261,324	1,370,530	11·23
1902	30,885,214	1,403,744	10·91
1903	32,384,138	1,405,888	10·42
1904	33,792,689	1,442,733	10·27

It will be seen that the years 1896 to 1904 show far larger numbers of passenger journeys than preceding years, but less satisfactory results as regards average receipts per journey. This does not so much arise from curtailment of long-distance travelling as from the change of a large body of travellers from first to second class—a result due to diminished means, and doubtless to some extent to the more comfortable carriages now provided for second-class passengers. A return to prosperous times should show an increase in first-class travellers, but it frequently happens that the removal of the original impelling cause is not followed by a return to previous habits, so that the railways may not altogether recover the revenue lost by the change on the part of the travelling public.

The amount of goods tonnage for the year 1881, and from 1895 to 1904 is shown in the following table :—

Year.	Tonnage of Goods and Live Stock. tons.	Earnings. £
1881 .....	2,033,850	955,551
1895 .....	4,075,093	1,855,303
1896 .....	3,953,575	1,776,495
1897 .....	4,567,041	1,916,046
1898 .....	4,630,564	1,900,491
1899 .....	5,248,320	1,987,075
1900 .....	5,531,511	1,936,217
1901 .....	6,398,227	2,203,249
1902 .....	6,467,552	2,264,942
1903 .....	6,536,241	1,909,005
1904 .....	6,656,759	1,993,680

The subdivision of the tonnage of goods and live stock for the year ended 30th June, 1904, into a general classification is set forth in the subjoined statement, which, however, does not include 280,810 tons of coal on which only shunting and haulage charges were collected. Particulars of the tonnage are given under nine broad classes, while the table also shows the average distance goods of each class were carried, and the average earnings per ton per mile. The last figure, however, does not include the terminal charges, which would probably increase the revenue per ton per mile by about 0·20d. or from 1·03d. to 1·23d. The "miscellaneous" traffic comprises timber, bark, agricultural and vegetable seeds, in 5-ton lots; firewood, in 5-ton lots; bricks, drain-pipes, and various other goods. "A" and "B" classes consist of lime, fruit, vegetables, hides, tobacco leaf, lead and silver ore, caustic soda and potash, cement, copper ingots, fat and tallow, mining machinery, ore tailings, leather, agricultural implements in 5-ton lots; and various other goods.

Description of Traffic.	Tons carried.	Average number of miles each ton of traffic is carried.	Earnings per ton per mile.
		miles.	d.
Coal, coke, and shale .....	3,914,901	20·74	0·54
Firewood .....	226,445	26·55	0·78
Grain, flour, &c. ....	424,786	232·77	0·47
Hay, straw, and chaff .....	116,117	190·72	0·38
Miscellaneous .....	723,719	56·46	0·74
Wool .....	74,096	265·35	1·92
Live stock .....	154,525	253·14	1·47
"A" and "B" classes .....	538,606	103·49	1·13
All other goods .....	202,754	145·51	3·86
	6,375,949	61·65	1·03
Terminal charges .....	.....	.....	0·20
Total .....	6,375,949	61·65	1·23

The charge for carrying goods one mile along the lines of the state in 1872 was 3·6d. per ton, while after an interval of thirty-one years, it has

fallen to 1·23d. The decrease, however, is to some extent more apparent than real, inasmuch as it represents a more extensive development of the mineral traffic than of the carriage of general merchandise; but, when due allowance has been made on this score, it will be found that the benefit to the general producer and consumer has been very substantial, and it may safely be taken as indicating generally the lessened cost of carriage to persons forwarding goods by rail.

#### VICTORIA.

Railway operations in Victoria began with the opening of the line from Flinders-street, Melbourne, to Port Melbourne. In the early years the lines constructed were chiefly in the vicinity of the metropolis, and up to the year 1865, that is in ten years, only 274 miles were laid down; during the next decennial period a further length of 312 miles was constructed. As in the case of other states, more energy was manifested during the decade ended 1885, when no less than 1,092 miles were constructed; during the next ten years the rate of progress was maintained, and a further length of 1,444 miles was opened. The length of line open for traffic on 30th June, 1904, was 3,381 miles, upon which the sum of £41,216,703 has been expended for construction and equipment, or an average of £12,191 per mile.

The railways of the state are grouped under seven systems—the Northern, North-Eastern, Eastern, South-Eastern, North-Western, South-Western, and Suburban lines. The Northern system extends from Melbourne to Echuca; the North-Eastern stretches from Kensington to Wodonga, and is the main line connecting Melbourne with Sydney; the Eastern connects Prince's Bridge, Melbourne, with Bairnsdale; the South-Eastern runs from Lyndhurst to Port Albert; the North-Western, joining Laverton with Serviceton, is the main line connecting Melbourne with Adelaide; the South-Western runs from Breakwater to Port Fairy; and the suburban system makes provision for the requirements of the population within a distance of about 20 miles from the metropolis. Included in the seven systems are no less than ninety main, branch, and connecting lines. With the exception of the eastern and extreme north-western portions of the state, where settlement is sparse, the railway facilities provided are in advance of those of any other state, in so far as the length of the line open for traffic is concerned.

Victoria, in 1883, was the first state of the group to adopt the system of placing the management and maintenance of the railways under the control of three Commissioners. From the 1st February, 1884, to the end of 1891 the construction as well as the working of the lines was vested in this body; but on the 1st January, 1892, the duty of construction was transferred to the Board of Land and Works under the provisions of the "Railways Act, 1891." During 1896 the number

of commissioners was reduced to one ; but under the Victorian Railway Commissioners Act, 1903, the control of the lines of the state was placed in the hands of three commissioners from the 1st June, 1903.

*Revenue and Working Expenses.*

The net earnings, that is the sum available to meet interest charges during the last decennial period, are shown in the following table :—

Year.	Gross Earnings.	Working Expenses.	Net Earnings.	Proportion of Working Expenses to Gross Earnings.
	£	£	£	per cent.
1895	2,581,591	1,547,698	1,033,893	59.95
1896	2,401,392	1,551,433	849,959	64.61
1897	2,615,935	1,568,365	1,047,570	59.95
1898	2,606,896	1,649,793	959,103	63.24
1899	2,873,729	1,797,725	1,076,004	62.55
1900	3,025,162	1,902,540	1,122,622	62.89
1901	3,337,797	2,075,239	1,262,558	62.17
1902	3,367,643	2,166,118	1,201,725	64.31
1903	3,046,858	2,032,087	1,014,771	66.69
1904	3,438,141	2,022,403	1,415,738	58.82

As the table shows, both the gross and net earnings were higher in 1904 than in 1895, while the proportion of working expenses was smaller. The increase in revenue for 1904, in comparison with that earned during the previous twelve months, is chiefly attributable to the traffic resulting from the excellent harvest. In addition, the revenue from passenger traffic exceeded the average return for the preceding three years, despite the large reduction in passenger and mixed train mileage. During 1896 and subsequent years, many of the non-paying branch lines were closed, and economies effected in other directions. The high proportion of working expenses to gross earnings in 1903 was due to extensive renewals of way, repairs and renewals of stock, payment of increments to employees, extra price of coal, &c. The proportion in 1904 was the lowest for the decennial period.

Great care seems to have been taken to keep down the working expenses during the first four years of the decade shown in the following analysis of the working expenditure of Victorian railways, and a reduction

## RAILWAYS.

595

of over £200,000 per annum was made in spite of an addition of 200 miles to the length of line in operation. After 1896, concessions in regard to salary or wages were made to the staff, amounting to £35,000 in 1897, and £66,312 in the following year. In 1899 and 1900 additional concessions were made, involving an annual expenditure of £41,000. It will be observed that there is an item of £100,536 per annum for pensions and gratuities. The charges for this service for New South Wales amount to £6,708, and in none of the other railway systems is there any like expenditure.

Year ended 30th June.	Maintenance of Way, Works, and Buildings.	Locomotive Power.	Carriage and Waggon Repairs and Renewals.	Traffic Expenses.	Compensation.	Pensions and Gratuities.	General Charges.	Total.
	£	£	£	£	£	£	£	£
1896	331,196	290,536	177,082	514,131	6,806	84,509	43,486	1,547,606
1896	365,846	359,915	187,927	486,483	7,321	94,696	49,294	1,551,433
1897	381,293	359,768	193,731	497,030	4,689	83,968	47,901	1,569,365
1898	408,837	366,808	204,302	526,958	7,392	83,720	51,230	1,649,792
1899	480,792	398,807	234,615	546,754	3,611	81,284	51,862	1,797,725
1900	498,459	432,860	247,129	564,908	6,865	95,239	57,068	1,902,540
1901	518,488	620,527	272,818	609,000	7,945	90,443	56,018	2,075,239
1902	501,988	578,921	278,543	640,443	31,145	93,744	48,385	2,166,119
1903	522,253	521,090	258,842	582,163	10,729	98,507	42,498	2,082,087
1904	545,013	455,544	287,438	577,799	3,216	100,536	47,807	2,022,408

## PER TRAIN MILE.

	d.	d.	d.	d.	d.	d.	d.	d.
1896	8.31	9.81	4.43	12.90	.17	2.11	1.09	38.82
1896	9.77	9.61	5.02	12.99	.19	2.53	1.32	41.43
1897	9.92	9.26	5.08	12.93	.12	2.18	1.25	40.79
1898	10.62	9.52	5.32	13.69	.20	2.17	1.33	42.85
1899	11.38	9.36	5.80	13.51	.09	2.01	1.28	44.42
1900	11.84	10.23	5.87	13.41	.16	2.26	1.35	45.17
1901	11.26	11.29	5.92	13.21	.17	1.96	1.21	46.01
1902	10.68	12.27	5.92	13.62	.66	1.99	.92	46.06
1903	12.33	12.16	5.92	13.53	.25	2.13	.99	47.41
1904	14.27	11.98	7.53	16.11	.21	2.63	1.24	52.92

## PER MILE OPEN.

	£	£	£	£	£	£	£	£
1896	107.4	126.6	57.4	166.8	2.2	27.5	14.1	592.0
1896	117.2	115.3	60.2	155.9	2.4	30.3	15.8	497.1
1897	122.0	115.1	61.9	159.0	1.5	26.9	15.3	501.7
1898	130.9	117.2	65.6	168.7	2.5	26.3	16.4	523.1
1899	154.0	127.7	75.2	175.1	1.2	26.0	16.6	575.8
1900	156.5	135.9	77.6	177.3	2.1	29.9	17.9	597.2
1901	160.6	161.3	84.5	188.6	2.2	28.0	17.4	642.6
1902	153.8	176.7	85.3	196.2	9.5	23.7	13.3	663.5
1903	158.4	156.2	76.2	174.6	3.2	23.0	12.7	600.3
1904	161.7	125.1	85.3	171.4	2.4	29.3	14.2	599.9

*Interest returned on Capital.*

Continuing the basis adopted in the case of New South Wales of taking into consideration the absolute interest paid on the loans of the state and comparing this with the net earnings, the following table

furnishes a review of the past ten years, and shows the average loss for each year of the period :—

Year.	Interest returned on Capital.	Actual Rate of Interest payable on Outstanding Loans.	Average Loss.
	per cent.	per cent.	per cent.
1895	2·73	3·96	1·23
1896	2·24	3·98	1·74
1897	2·74	3·96	1·22
1898	2·49	3·93	1·44
1899	2·75	3·83	1·08
1900	2·83	3·89	1·06
1901	3·14	3·76	0·62
1902	2·96	3·72	0·76
1903	2·47	3·86	1·39
1904	3·43	3·78	0·35

The earnings of the Victorian lines are largely reduced by the necessity for working lines upon which there is an annual loss of £294,697. The fluctuations in net profits are due to the opening of new lines in sparsely-settled districts and the effect of the drought upon the traffic. From 1900 onwards there is a gradual improvement noticeable, except as regards 1903, the special circumstances in connection with which have already been referred to.

*Earnings and Expenses per Mile.*

While the present returns bear no comparison with those of 1872, when the net earnings per train mile were 73·29d. and per mile open £1,342, they are considerably in excess of those of any other year of the decennial period. The gross earnings, expenditure, and net earnings per train mile for the past ten years are set forth in the following table :—

Year.	Gross Earnings per train mile.	Expenditure per train mile.	Net Earnings per train mile.
	d.	d.	d.
1895	64·76	38·82	25·94
1896	64·11	41·43	22·68
1897	68·03	40·79	27·24
1898	67·77	42·85	24·92
1899	71·00	44·42	26·58
1900	71·83	45·17	26·66
1901	72·39	45·01	27·38
1902	71·63	46·06	25·57
1903	71·09	47·41	23·68
1904	89·95	52·92	37·03



The gross earnings, expenditure, and net earnings per average mile open for the past ten years were as follow :—

Year.	Gross Earnings per average mile open.	Expenditure per average mile open.	Net Earnings per average mile open.
	£	£	£
1895	837	502	335
1896	769	497	272
1897	837	501	336
1898	835	528	307
1899	920	576	344
1900	949	597	352
1901	1,034	642	392
1902	1,031	663	368
1903	913	609	304
1904	1,020	600	420

The tables indicate that while the gross earnings gradually improved up to 1902, the peculiar conditions of 1903 resulted in a considerable reduction ; a substantial improvement is, however, observable in the return for the year just closed. It is evident that the strict economy exercised during the year ended 30th June, 1904, has borne good fruit. The revenue has improved, while the working expenses are lower. Under the present management the railways should, with fair seasons, not only pay working expenses, but also interest on the capital cost of the lines and equipment.

#### *Coaching and Goods Traffic.*

The following table shows the number of passengers carried on the lines of the state during the year 1881, and for each of the last ten years, with the receipts from coaching traffic and the average receipts per journey :—

Year.	Passengers carried.	Receipts from Coaching Traffic.	Average Receipts per journey.
	No.	£	d.
1881	18,964,214	770,617	9·75
1895	40,210,733	1,259,609	7·51
1896	40,993,798	1,264,219	7·40
1897	42,263,638	1,328,687	7·55
1898	43,090,749	1,325,062	7·38
1899	45,805,043	1,372,000	7·19
1900	49,332,899	1,468,910	7·15
1901	54,704,062	1,625,903	7·13
1902	57,465,077	1,648,381	6·89
1903	54,798,073	1,592,088	6·96
1904	54,282,008	1,645,163	7·27

The number of passengers carried on the railways of Victoria reached its maximum in 1890, when no less than 58,951,796 persons made use of the lines. The reaction following on the banking crisis of 1893 unfavourably affected the traffic, and in 1895 the number of passengers fell to 40,210,733; a gradual improvement, however, has since been manifest in the returns. Victoria occupies the leading position among the states as regards the number of passengers carried, the latest figures being as follow:—New South Wales, 33,792,689; Victoria, 54,282,003; Queensland, 4,144,314; South Australia, including the Northern Territory, 9,751,065; Western Australia, 10,225,976; Tasmania, 814,483; and New Zealand, 8,306,383. The superiority of the Victorian figures results from the large number of passengers carried on the suburban railways, the Melbourne system effectively serving the population within a distance of 20 miles from the centre, and carrying upwards of 88 per cent. of the total passengers. The magnitude of the suburban traffic is evidenced by the fact that the average receipts per journey during the last year are shown to be 7·27d., as against 10·27d. in New South Wales; 28·68d. in Queensland; 9·12d. in South Australia, including Northern Territory; 10·85d. in Western Australia; 31·06d. in Tasmania; and 18·84d. in New Zealand.

The amount of goods and live stock tonnage in 1881, and for each of the ten years from 1895 to 1904, with the earnings therefrom, is shown in the following table:—

Year.	Tonnage of Goods and Live Stock.	Earnings.
	Tons.	£
1881 .....	1,366,603	894,592
1895 .....	2,435,857	1,321,962
1896 .....	2,163,722	1,137,173
1897 .....	2,383,445	1,287,248
1898 .....	2,408,665	1,283,834
1899 .....	2,779,748	1,501,729
1900 .....	2,998,303	1,555,252
1901 .....	3,381,860	1,711,894
1902 .....	3,433,627	1,719,462
1903 .....	3,093,997	1,454,770
1904 .....	3,439,203	1,792,978

The table indicates a gradual increase in the tonnage carried and earnings therefrom during the seven years preceding 1903. The considerable falling off in 1903 was due, as already pointed out, to the total failure of the harvest; but, in consequence of the favourable season in 1904, the tonnage and earnings are the highest for the decennial period. Particulars of the subdivision of the tonnage of goods and live stock into a general classification are not available, and no information is furnished that will admit of a comparison being made in order to determine how far the cost of carriage per mile has been reduced during the period under review.

## QUEENSLAND.

The progress of railway construction in Queensland for the first ten years after the opening of the Ipswich to Grandchester line was somewhat slow, only 268 miles having been constructed. In the decade ending in 1885, more energy was displayed, and a further length of 1,167½ miles was constructed, while during the quinquennial periods ending in 1890 and 1895, extensions of 712 and 250 miles were opened. The length of line open on 30th June, 1904, was 2,928, miles, and the amount expended thereon for construction and equipment was £20,887,585, or at the rate of £7,134 per mile. During the year ended 30th June, 1904, the length of line open for traffic was increased by the opening of the extensions from Nerang to Tweed Heads, Goomeri to Wondai, Esk to Toogoolawah, Redbank-Bundamba Loop, Gladstone to Rockhampton, Hughenden to Richmond, and Mareeba to Atherton.

The railways of the state may be grouped into three divisions, comprising six systems. The southern division extends from Brisbane to Wallangarra in a southerly direction, to Cunnamulla in a westerly direction, and to Rockhampton northerly along the coast, and has fifteen branch lines connected with it. The central division extends from Archer Park to Longreach, and has five branch lines connected with it. The northern division comprises the line from Mackay to Eton, Mirani and Pinnacle; the line from Townsville to Winton, with a branch to Ravenswood, and another to Richmond; the line from Cairns to Mareeba, with a branch to Atherton; and the line from Normanton to Croydon.

For many years the construction, maintenance, and control of the railways were carried out by a branch of the Public Works Office, and subsequently by a separate Ministerial Department with a Secretary responsible to Parliament and administering the details of the office in a manner similar to any other Crown Minister. The "Railways Act of 1888," however, while leaving the Minister in charge of the Department, vested the construction, management, and control of all Government railways in three Commissioners, of whom one was to be Chief Commissioner. The number was subsequently reduced to two, and later a single commissioner was appointed holding the authority formerly vested in the three. In undertaking railway construction the state is guided by other considerations than those which would direct the action of private investors, and is content, for a time at least, to recoup the expenditure in an indirect form. The disastrous result of the continued drought has operated against successful management during recent years, and in consequence of the fact that the rate of interest returned on capital expenditure during the past three years does not compare favourably with the previous years, a policy of stringent economy is to be pursued, and the rates and fares have been increased with the object of reducing the deficit.

*Revenue and Working Expenses.*

The net sum available to meet interest charges during the last decennial period is shown in the following table:—

Year.	Gross Earnings.	Working Expenses.	Net Earnings.	Proportion of Working Expenses to Gross Earnings.
	£	£	£	per cent
1895	1,025,512	581,973	443,539	56·75
1896	1,085,494	644,362	441,132	59·36
1897	1,179,273	684,146	495,127	59·01
1898	1,215,811	686,066	529,745	56·43
1899	1,373,475	784,811	588,664	57·14
1900	1,464,399	948,691	515,708	64·78
1901	1,316,936	1,057,981	258,955	80·34
1902	1,382,179	992,751	389,428	71·82
1903	1,234,230	863,382	370,848	69·95
1904	1,305,552	811,951	493,601	62·19

As the table shows there have been considerable fluctuations in the proportion of working expenses to gross earnings. The net earnings for the year ended 30th June, 1900, were 35·22 per cent. of the total earnings, as against 36·33 per cent. when the railways were placed under their present control. The return for 1900 was considerably lower than those of the preceding two years, and was due to the fact that the railways were compelled to carry very large numbers of starving stock and large quantities of fodder at unremunerative rates. There were also heavy disbursements to replace and increase the stock of locomotives, and to carry out works which, though improving the equipment of the railways and ensuring safe running, have not been of a reproductive character, while during the year substantial increases in pay were conceded to all classes of railway employees. For the year ended 30th June, 1901, the revenue from passenger traffic showed a substantial increase; the decrease in earnings shown in the preceding table was entirely due to the loss of live stock by drought and consequent stoppage of station improvements, and to the necessity of carrying starving stock and fodder at merely nominal rates. The net earnings for the year were thus reduced to 19·66 per cent. of the total earnings. A slight improvement was manifested in the year ended 30th June, 1902, the percentage gained being 28·18 of the total earnings, the increase in rates and fares being responsible for the advance. Working expenses were curtailed by a reduction in the train mileage, and by the exercise of stringent economy in administration, and with the return of favourable seasons it was hoped that more satisfactory results would be secured. The adversity of the season during the year ended the 30th June, 1903, however, was responsible for a heavy decline. Less wool and live stock were carried, while the

traffic in produce from the agricultural districts decreased by as much as 43 per cent. The returns for 1904, show an increase in the passenger traffic, and also in all classes of goods traffic, save that of minerals other than coal; while with the exception of general charges, which have been slightly increased, the working expenses under each heading show a reduction over those of the previous year.

An analysis of the working expenses of the Queensland railways for the ten years, 1895-1904, is given below. Taking the first year with the last it will be seen that there has been a substantial increase in the total cost, as well as in the rate per train mile and per mile of line open. In 1899 the expenditure per train mile had been reduced to 32·35d., as compared with 40·82d. in 1893 and 42·05d. in 1902. There can be no doubt that the expenditure for 1899 had been reduced below the point of safety and some services had been starved, and this necessitated in the following years an abnormal expenditure on improvements of the locomotive, carriage and waggon stock, and in bringing the equipment generally up to a better standard to ensure the safe working of the lines. In 1901 there was a considerable outlay on relaying and other heavy works; similar expenditure, or, at least, expenditure on so large a scale, will not, of course, be needed for some little time.

Year ended 30th June.	Maintenance of Way, Works, and Buildings.	Locomotive Power.	Rolling Stock Repairs and Renewals.	Traffic Expenses.	General Charges.	Total.
	£	£	£	£	£	£
1895	223,772	114,544	60,726	144,483	28,448	581,973
1896	248,468	142,127	65,182	161,656	26,929	644,362
1897	271,602	145,503	77,028	164,097	25,916	684,146
1898	261,706	145,045	79,900	172,503	26,912	686,066
1899	289,005	172,695	97,800	196,680	28,631	784,811
1900	335,777	204,532	154,478	221,640	32,266	948,691
1901	401,013	226,000	164,967	229,902	36,099	1,057,981
1902	355,793	206,096	183,650	226,745	20,467	992,751
1903	292,952	189,278	154,397	207,303	19,452	863,382
1904	277,913	168,540	149,219	196,806	19,473	811,951

## PER TRAIN MILE.

	d.	d.	d.	d.	d.	d.
1895	14·32	7·02	3·72	8·85	1·74	35·65
1896	12·57	7·19	3·30	8·18	1·36	32·60
1897	13·20	7·07	3·74	7·97	1·26	33·24
1898	12·54	6·95	3·83	8·27	1·29	32·88
1899	11·91	7·12	4·03	8·11	1·18	32·35
1900	12·54	7·64	5·77	8·28	1·20	35·43
1901	16·63	9·37	6·84	9·53	1·50	43·87
1902	15·07	8·73	7·78	9·60	0·87	42·05
1903	14·21	9·18	7·49	10·06	0·94	41·88
1904	14·35	8·71	7·71	10·16	1·01	41·94

Year ended 30th June.	Maintenance of Way, Works, and Buildings.	Locomotive Power.	Rolling Stock Repairs and Renewals.	Traffic Expenses.	General Charges.	Total.
PER MILE OPEN.						
	£	£	£	£	£	£
1895	98·3	48·2	25·5	60·7	11·9	244·6
1896	104·3	59·7	27·3	67·8	11·3	270·4
1897	111·9	60·0	31·7	67·6	10·7	281·9
1898	101·2	56·1	30·9	66·7	10·4	265·3
1899	106·5	63·6	36·1	72·5	10·6	289·3
1900	120·1	73·2	55·2	79·3	11·5	339·3
1901	143·1	80·7	58·9	82·1	12·9	377·7
1902	127·0	73·6	65·6	81·0	7·3	354·5
1903	105·5	68·1	55·6	74·6	7·0	310·8
1904	98·3	59·6	52·8	69·6	6·9	287·2

*Interest returned on Capital.*

The financial results of the working of the lines are exhibited in the following table which covers a period of ten years :—

Year.	Interest returned on Capital.	Actual Rate of Interest payable on Outstanding Loans.	Average Loss.
	per cent.	per cent.	per cent.
1895	2·68	4·16	1·48
1896	2·63	4·09	1·46
1897	2·87	4·04	1·17
1898	2·92	4·04	1·12
1899	3·15	4·00	0·85
1900	2·67	4·02	1·35
1901	1·31	3·98	2·67
1902	1·93	3·94	2·01
1903	1·48	3·92	2·44
1904	2·36	3·92	1·56

A fair proportion of the railway construction of recent years has been in country of a purely pastoral character, and it is manifest that a sufficient traffic to prove remunerative cannot be looked for immediately from localities possessed of only a scattered and limited population; but it is confidently expected that these lines will ultimately pay interest on cost of construction. Unfortunately, Queensland, in common with the other provinces, is burdened with lines of railway not warranted by existing or prospective traffic, and these will always be a handicap to successful management.

*Earnings and Expenses per Mile.*

While the results now secured cannot be compared with those of 1880, when the net earnings per train mile were a little over 43d., and per mile open £222, a satisfactory state of affairs is disclosed by a review of the figures for earnings shown in the subjoined tables. It will be seen that the net earnings per train mile, as well as the net return for each mile of line open, have, except in the four years preceding that just closed, been fairly well sustained. The fall in the years 1900, to 1903, as compared with the previous three years, is due to the fact that the continuance of the drought and the consequent loss in sheep and cattle have operated against the revenue from the carriage of wool and live stock, while the increased traffic which was obtained consisted largely of the removal of starving stock from and the carriage of fodder to drought-stricken districts, a class of traffic which had to be undertaken at unremunerative rates. The gross earnings, expenditure, and net earnings per train mile for the past ten years are shown in the following table:—

Year.	Gross Earnings per train mile.	Expenditure per train mile.	Net Earnings per train mile.
	d.	d.	d.
1895	62·82	35·65	27·17
1896	54·91	32·60	22·31
1897	57·30	33·24	24·06
1898	58·27	32·88	25·39
1899	56·02	32·35	24·27
1900	54·69	35·43	19·26
1901	54·61	43·87	10·74
1902	58·54	42·05	16·49
1903	59·87	41·88	17·99
1904	67·43	41·94	25·49

The gross earnings, expenditure, and net earnings per average mile open for the past ten years were as follow:—

Year.	Gross Earnings per average mile open.	Expenditure per average mile open.	Net Earnings per average mile open.
	£	£	£
1895	431	244	187
1896	455	270	185
1897	486	281	205
1898	470	265	205
1899	506	289	217
1900	523	339	184
1901	470	377	93
1902	493	354	139
1903	444	311	133
1904	462	287	175

*Coaching and Goods Traffic.*

The number of passengers carried on the lines of the state during the year 1881, and for the last ten years, together with the receipts from the traffic, and the average receipts per journey, are set forth in the following table :—

Year.	Passengers carried.	Receipts from Coaching traffic.	Average Receipts per Journey.
	No.	£	d.
1881	247,284	113,490	110·14
1895	2,054,416	308,025	35·98
1896	2,274,219	324,790	34·27
1897	2,633,556	359,811	32·79
1898	2,742,108	391,270	34·24
1899	3,716,425	447,123	28·87
1900	4,395,841	505,536	27·60
1901	4,760,559	536,462	27·06
1902	4,636,174	513,257	26·59
1903	4,048,161	467,594	27·72
1904	4,144,314	495,375	28·68

It will be seen that the years 1899 to 1904 show a far larger number of passenger journeys than preceding years; this was chiefly due to an extraordinary expansion in the suburban traffic. The falling off in 1903 as compared with the three preceding years occurred almost wholly on the lines of the Southern Division. During the period the average receipts per journey show a decline, which may be expected to continue as the suburban traffic expands, so that in a few years the receipts per person carried will approximate closely to the average for the rest of Australia, viz., one shilling per journey.

The amount of goods tonnage for a similar period is shown in the following table :—

Year.	Tonnage of Goods.	Earnings.
1881.....	161,008	£235,100
1895.....	900,591	717,487
1896.....	1,026,899	760,704
1897.....	1,243,603	819,462
1898.....	1,323,782	824,541
1899.....	1,684,858	926,352
1900.....	1,688,635	958,863
1901.....	1,530,440	780,474
1902.....	1,725,520	868,922
1903.....	1,566,960	766,696
1904.....	1,572,226	810,177

In the foregoing statement the tonnage of live stock is not included, the information not being available, but the earnings shown include the revenue derived from this class of traffic. The general traffic is divided into seven classes, particulars of which, for the year ended 30th June,



1904, together with the receipts for each class, are shown in the sub-joined table. No information is available as to the average number of miles each ton of traffic is carried, or the earnings per ton per mile.

Description of Traffic.	Tons carried.	Receipts from traffic.
General merchandise .....	240,794	... £362,065
Agricultural produce .....	290,390	... 111,917
Wool .....	18,579	... 63,005
Coal.....	448,460	... 69,575
Minerals other than coal ..	163,058	... 21,168
Timber .....	412,945	... 91,135
Live stock .....	.....	... 91,312
Total .....	1,572,226	... £810,177

#### *Guaranteed Railways.*

Up to the 30th June, 1904, four railways, having a total length of 37 miles 40 chains, were constructed under "The Railways Guarantee Act of 1895." In accordance with this Act the local authority, representing the ratepayers of a district, agrees to pay up to one-half of the deficiency in working expenses with interest at the rate of 4 per cent. on the capital cost during the first fourteen years after opening, the sum to be raised by means of a rate not exceeding 3d. in the £ of value of ratable lands. Should the operations of any year provide a surplus, half of this is retained by the Government and the other half paid to the local authority for distribution among the ratepayers in return for the payments made on account of the deficiency in previous years. When the line has been payable for three years, the Government may cancel the agreement. The results of the working of three out of the four railways do not afford much encouragement to apply the provisions of the Act to other lines which may be projected in the future. The Pialba branch, on which the expenditure to 30th June, 1904, was £46,352, showed, without taking into consideration the interest on capital cost, a net revenue for the year 1899 of £715; in 1900, £966; in 1901, £994; in 1902, £1,139; while in 1903, there was a loss of £219; and in 1904, of £255. Leaving out of consideration the interest on a capital cost of £11,457, the Allora branch shows a net revenue of £262 in 1899; £120 in 1900; and £105 in 1901; in 1902, there was a loss of £182; in 1903, a loss of £187; while in the year just closed there was a net revenue, after paying working expenses, of £431. A capital expenditure of £48,210 has been incurred in connection with the Enoggera branch, and leaving out of consideration the interest charge thereon, there was a net revenue of £159 in 1899, and £67 in 1900, while the loss in 1901 was £440; in 1902, £235; in 1903, £737; and in 1904, of £675. The Mount Morgan branch, which up to the 30th June, 1904, had involved a capital expenditure of £84,612, has given satisfactory results. The net revenue, leaving out of consideration the interest on capital cost, was £7,127 in 1899; £9,084 in 1900; £6,297 in 1901; £4,872 in 1902; £4,147 in 1903; and £6,671 in 1904.

## SOUTH AUSTRALIA.

While the beginning of railway construction in South Australia dates as far back as 1854, very little progress was made in the subsequent twenty years, and in 1874 the total length of line in operation was only 234 miles; in 1880 this had increased to 627 miles; in 1890 to 1,610 miles; and in 1895 to 1,722 miles. The length of line in operation on the 30th June, 1904, was 1,736½ miles, and the amount expended thereon for construction and equipment, £13,517,727, or at the rate of £7,785 per mile.

The railways of South Australia proper are divided for the purposes of management into five systems. The Midland system, constructed on the 5ft. 3in. gauge, has a length of 236½ miles, and extends from Adelaide to Terowie in a northerly direction, and to Morgan, on the Murray River, in a north-easterly direction. The Northern system has a total length of 1,008½ miles, 1,003 of which are 3 ft. 6 in. gauge, and 5½ miles 5 ft. 3 in. gauge. This system includes that portion of the transcontinental line which extends to Oodnadatta, a distance of 550 miles from Adelaide; the line to Cockburn, which provides for the requirements of the Broken Hill district of New South Wales; and branches to Port Augusta, Port Pirie, Wallaroo, and Port Wakefield. The Southern system comprises a length of 265½ miles on a gauge of 5 ft. 3 in., and includes the main line connecting Adelaide with Melbourne, and branches—Wolseley to Naracoorte and from Naracoorte to Kingston, Mount Gambier, and Beechport. The line from Port Broughton to Barunga has a length of 10 miles.

During 1887 the control of the railways was entrusted to three commissioners; in 1895, however, the number was reduced to one, who is responsible to Parliament.

*Revenue and Working Expenses.*

The net sum available to meet interest charges is set forth in the following table:—

Year.	Gross Earnings.	Working Expenses.	Net Earnings.	Proportion of Working Expenses to Gross Earnings.
	£	£	£	£
1895	960,155	568,973	391,182	59.28
1896	986,500	583,022	403,478	59.10
1897	1,025,035	614,254	410,781	59.92
1898	984,228	603,474	380,754	61.31
1899	1,058,397	617,380	441,017	58.33
1900	1,166,987	657,841	509,146	56.37
1901	1,236,616	729,039	507,577	58.96
1902	1,085,175	689,517	395,658	63.54
1903	1,076,612	624,511	452,101	58.01
1904	1,160,639	675,395	485,244	58.19

The foregoing table shows that the gross earnings in 1901 were the largest during the decade, while the proportion of working expenses to gross earnings was lowest in 1900, the net earnings in the latter year

being the highest for the period. The failure of the harvest and the succession of adverse seasons which South Australia laboured under during part of the decennial period are the causes of the falling off in the revenue for several years. No other railway system in Australia depends so much upon the carriage of agricultural produce for its traffic, and years of shrinkage in the railway revenue are coincident with years of harvest failure. The increase in working expenses during the years 1899 and 1900 was due to the renewal of rolling stock, the relaying of portion of the permanent way, and other outlay expended from the improved revenue. The further increase during 1901 is explained by the rise in the price of coal and materials; by the increased train mileage; and by the fact that opportunity was taken of a fairly good year's revenue to debit working expenses with an unusual outlay under the head of "replacements." The operations of the year ended 30th June, 1902, show a considerable reduction in the gross earnings, which is attributable to the shrinkage in the Barrier traffic caused by the fall in the price of lead reducing the output of the mines. Moreover, consequent on the decrease in mining profits, the department was compelled to carry ore and concentrates at much lower rates, so that there was a diminished receipt from every ton of a smaller volume of traffic, and an increase in the proportion of working expenses to gross earnings. While the gross earnings for the year ended 30th June, 1903, exhibit a slight shortage in comparison with those of the previous year, a large reduction is manifest in the working expenses. This was secured by restricting expenditure in every branch, and the postponement of repairs and renewals, which it would have been the truest economy to effect. The transactions for the year ended 30th June, 1904, show increased receipts under each head except wool and livestock, the slight falling off in these items being accounted for by the recent unfavourable season. The percentage of working expenses was slightly higher than that of the preceding year, and was due to causes referred to later. The results secured may be looked upon as fairly satisfactory, when it is considered that the management is burdened with some very unproductive lines, notably that from Hergott Springs to Oodnadatta, which barely pays working expenses, and entails an annual payment of about £44,000 in interest.

The working expenditure of the South Australian lines, an analysis of which is given below, does not show very much variation from year to year. The average reached its lowest point in the year 1900 with 37·78d. per train mile; since then there has been a rise of about 2d. per train mile, which the railway managers attribute to the increased price of coal and materials, to larger expenditure on repairs and rolling stock, and to increases in the wages of the employees. The large increase in expenditure during the year ended 30th June, 1904, on maintenance of way, works and buildings, and locomotive power, was due to a large amount expended in repairing damage done by floods in the north, the necessary relaying of parts of the permanent way, an

exceptional outlay in improving the condition of engines, and the purchase of locomotive boilers.

Year ended 30th June.	Maintenance of Way, Works, and Buildings.	Locomotive Power.	Rolling Stock Repairs and Renewals.	Traffic Expenses.	Compensation.	General Charges.	Total.
	£	£	£	£	£	£	£
1895	138,983	156,326	100,901	147,173	73	16,517	568,973
1896	137,865	161,623	122,965	146,127	162	14,290	563,022
1897	159,798	177,205	117,676	144,935	713	14,027	614,254
1898	152,091	173,825	107,731	150,033	826	13,968	603,474
1899	160,514	183,570	111,738	146,862	646	13,901	617,230
1900	163,851	194,134	124,280	160,641	687	14,228	657,841
1901	185,292	218,430	144,137	164,589	1,562	15,029	729,069
1902	166,691	211,115	132,467	162,926	1,894	15,224	690,517
1903	139,297	195,319	121,896	151,733	1,663	14,566	624,511
1904	164,066	199,821	143,666	151,697	1,571	14,574	675,396

## PER TRAIN MILE.

	d.	d.	d.	d.	d.	d.	d.
1895	9.83	11.05	7.77	10.41	0.01	1.17	40.24
1896	9.58	11.24	8.55	10.16	0.01	0.99	40.53
1897	10.44	11.57	7.67	9.47	0.05	0.92	40.12
1898	9.82	11.56	6.96	9.69	0.06	0.80	38.96
1899	9.88	11.30	6.88	9.05	0.04	0.85	38.00
1900	9.41	11.15	7.13	9.23	0.04	0.82	37.78
1901	10.12	11.93	7.88	8.99	0.09	0.82	39.83
1902	9.53	12.03	7.58	9.30	0.08	0.87	39.44
1903	8.87	12.43	7.76	9.66	0.10	0.93	39.75
1904	10.53	12.82	9.22	9.74	0.10	0.94	43.26

## PER MILE OPEN.

	£	£	£	£	£	£	£
1895	80.7	90.8	63.8	85.5	.....	9.6	330.4
1896	80.1	93.8	71.4	84.9	.....	8.3	338.5
1897	92.8	102.9	68.2	84.1	0.4	8.1	356.5
1898	88.2	103.8	62.5	87.0	0.5	8.1	350.1
1899	93.1	106.5	64.9	85.3	0.4	8.0	352.2
1900	94.7	112.2	71.3	92.8	0.4	8.2	380.1
1901	106.7	125.8	83.0	94.8	0.9	8.7	419.9
1902	96.0	121.6	76.3	93.6	0.8	8.8	397.1
1903	80.2	112.5	70.2	87.4	1.0	8.4	359.7
1904	94.5	115.1	82.7	87.4	0.9	8.4	399.0

*Interest returned on Capital.*

The following table exhibits the financial results of the working of the lines during the last ten years :—

Year.	Interest returned on Capital.	Actual rate of Interest payable on Outstanding Loans.	Average Loan.
	per cent.	per cent.	per cent.
1895	3.12	4.22	1.10
1896	3.21	4.12	0.91
1897	3.26	4.05	0.79
1898	2.98	4.03	1.05
1899	3.42	3.95	0.53
1900	3.91	3.69	0.02*
1901	3.86	3.57	0.01
1902	2.98	3.81	0.83
1903	3.08	3.74	0.66
1904	3.59	3.69	0.10

\* Represents profit.

The interest returned on capital during 1900 was the highest secured since 1892, when the railways returned 4·78 per cent. on capital expenditure, and exceeded by a slight amount the interest rate on the debt of the province. South Australia possesses one advantage not shared by any other province, namely, a large and steady long-distance traffic from a neighbouring state. The Broken Hill traffic is a very important factor in the railway revenue, as the greater portion of the line connecting the mines with the seaports runs through South Australian territory. The extent of this traffic will be found mentioned on page 611.

*Earnings and Expenses per Mile.*

The net earnings now secured are very much below those of 1891 when the return per train mile was 38·64d., and per mile open £370; a gradual improvement is, however, noticeable up to 1900, the fall in 1901 and 1902 being due to the reasons already adverted to on a previous page. The figures for 1903 again show an upward tendency, and those for 1904 show a substantial improvement, being the highest for the decennial period in respect of the net earnings per train mile. The gross earnings, expenditure, and net earnings per train mile for the past ten years are shown in the following table:—

Year.	Gross Earnings per train mile.	Expenditure per train mile.	Net Earnings per train mile.
	d.	d.	d.
1895	67·90	40·24	27·66
1896	68·57	40·53	28·04
1897	66·95	40·12	26·83
1898	63·57	38·98	24·59
1899	65·14	38·00	27·14
1900	67·02	37·78	29·24
1901	67·56	39·83	27·73
1902	62·06	39·44	22·62
1903	68·53	39·75	28·78
1904	74·49	43·35	31·14

The gross earnings, expenditure, and net earnings per average mile open for the past ten years are set forth in the following table:—

Year.	Gross Earnings per average mile open.	Expenditure per average mile open.	Net Earnings per average mile open.
	£	£	£
1895	558	330	228
1896	573	338	235
1897	595	356	239
1898	571	350	221
1899	614	358	256
1900	674	380	294
1901	712	419	293
1902	625	397	228
1903	620	360	260
1904	668	389	279

The results for the year 1900 may be viewed as satisfactory, taking into consideration the fact that the number of train miles run during that year was higher than in any previous year during the period. It will be seen that there was a substantial fall in the net earnings per train mile for the year ended 30th June, 1902, due to the reasons already referred to. The present earnings per train mile are above the average of the Commonwealth as a whole.

*Coaching and Goods Traffic.*

The following table shows the number of passengers carried on the lines of the state during the year 1881, and for each of the last ten years, together with the receipts from the traffic, and the average receipts per journey:—

Year.	Passengers carried.	Receipts from Coaching Traffic.	Average Receipts per Journey.
	No.	£	d.
1881	3,032,714	151,867	12-01
1895	5,224,854	263,448	12-09
1896	5,435,956	288,594	12-73
1897	5,789,297	297,026	12-31
1898	6,050,189	291,411	11-56
1899	6,171,081	297,207	11-56
1900	7,416,506	337,723	10-93
1901	8,863,632	359,172	9-74
1902	9,643,058	369,677	9-34
1903	9,061,488	342,037	9-05
1904	9,747,412	367,607	9-05

The table indicates an improvement in the number of passengers carried; the falling off during 1903 in comparison with 1902 being due to the less prosperous season; the average receipts per journey have, however, gradually declined.

The amount of goods tonnage for the same period is shown in the following table:—

Year.	Tonnage of Goods and Live Stock.	Earnings.
	No.	£
1881 .....	646,625	222,184
1895 .....	1,000,408	666,600
1896 .....	1,056,963	670,961
1897 .....	1,146,293	700,629
1898 .....	1,189,095	664,348
1899 .....	1,403,727	731,156
1900 .....	1,485,976	798,231
1901 .....	1,828,444	843,019
1902 .....	1,392,257	681,045
1903 .....	1,349,617	703,522
1904 .....	1,515,621	761,298

Fluctuation in the tonnage of goods carried is presented by the figures in the foregoing table, and the considerable decrease manifested in the

years 1902 and 1903, in comparison with 1901, is due to the continuous fall in the metal market not only reducing the output, but leading to a general slackness of business on the Barrier, while, in addition, ore and concentrates were carried at lower rates. The volume of traffic secured by South Australia from the Barrier District of New South Wales amounted to 532,331 tons out of the total of 1,515,621 tons, and the receipts from all traffic passing through Cockburn to £362,663 out of a revenue of £1,160,639.

The following table shows a classification of the goods carried during 1904, and the amount received for carriage. It would have been interesting to exhibit also the charge for haulage of each description of goods during the last ten years, but no information is available which will enable such particulars to be compiled. There has been a general reduction in freight charges, and the average charge per ton per mile for all goods has fallen from 1·05d. in 1897 to 1·02d. in 1904:—

Description of Traffic.	Tons Carried.	Receipts from Traffic. £
Minerals .....	676,399	250,469
Grain .....	200,025	59,596
Wool .....	14,331	18,129
Goods other than above .....	591,695	361,093
Live stock .....	33,171	72,011

#### NORTHERN TERRITORY.

Railway construction in the Northern Territory has been confined to the line from Palmerston to Pine Creek, 145½ miles in length, opened on the 1st October, 1889, and the returns for the eight years preceding that just closed show that the traffic did not even pay working expenses.

#### *Revenue and Working Expenses.*

The gross earnings, expenditure, and net earnings, with the proportion of working expenses to gross earnings of the line are set forth in the following table, which covers a period of ten years:—

Year.	Gross Earnings.	Working Expenses.	Net Earnings.	Proportion of Working Expenses to Gross Earnings.
	£	£	£	per cent.
1895	14,722	11,477	3,245	77·96
1896	15,105	15,289	(—) 184	101·22
1897	17,908	18,968	(—) 1,058	105·91
1898	14,124	20,268	(—) 6,144	143·50
1899	14,758	17,375	(—) 2,617	117·73
1900	14,799	24,340	(—) 9,541	164·47
1901	13,845	25,280	(—) 11,435	182·59
1902	12,522	34,649	(—) 22,127	276·70
1903	11,298	12,812	(—) 1,514	113·40
1904	17,006	13,219	3,787	77·73

(—) Denotes loss

While the transactions of the year just closed show a substantial improvement in respect of the Palmerston and Pine Creek line, the experience of the previous eight years offers no encouragement to any further extension of railways in the Northern Territory. The actual results of working have not been quite so unfavourable as would appear from the foregoing table, as each of the two years 1900 and 1901 was charged with the payment of an instalment of £10,000, and 1902 with the final instalment of £21,931, towards the reconstruction of the jetty which was destroyed by a hurricane in 1896.

The expenditure on working for 1904 may be divided as follows :—

	£
Maintenance of Permanent Way Buildings, &c.....	7,037
Locomotive Power.....	2,295
Rolling Stock Repairs and Renewals .....	1,225
Traffic Expenses.....	2,300
Compensation.....	2
General Charges.....	360
<b>Total.....</b>	<b>13,219</b>

These figures are equivalent to 100·57d. per train mile, and £90·91 per mile of line open for traffic.

#### *Interest returned on Capital.*

The following table shows the average loss for each year during the last ten years, after the interest on cost of construction has been deducted from the net earnings :—

Year.	Interest returned on Capital.	Actual Rate of Interest payable on Outstanding Loans.	Average Loss.
	per cent.	per cent.	per cent.
1895	0·28	4·22	3·94
1896	(—) 0·02	4·12	4·14
1897	(—) 0·09	4·05	4·14
1898	(—) 0·53	4·03	4·56
1899	(—) 0·22	3·95	4·17
1900	(—) 0·32	4·04	4·36
1901	(—) 0·98	4·05	5·03
1902	(—) 1·99	4·37	6·36
1903	(—) 0·13	4·37	4·50
1904	0·32	5·30	4·98

(—) Denotes loss.

From the outset there was very little prospect that the traffic on this line would meet the interest on the cost of construction and equipment; and although for the first five years there was a margin after paying working expenses, the results for the eight years ended 30th June, 1903, show that even working expenses have not been met. The deficiency is in part due to the heavy expenditure necessitated by the ravages of the teredo in the sub-structure of the jetty at Palmerston, and the large



outlay to repair damages caused by the cyclone which struck Port Darwin in the early part of 1897. Fluctuations in the volume of traffic are also partly responsible for the deficiency.

*Earnings and Expenses per Mile.*

The gross earnings, expenditure, and net earnings per train mile for a period of ten years are shown in the following table :—

Year.	Gross Earnings per Train Mile.	Expenditure per Train Mile.	Net Earnings per Train Mile.
	d.	d.	d.
1895	115·10	89·73	25·37
1896	114·28	115·67	(—) 1·39
1897	137·28	145·38	(—) 8·10
1898	112·97	162·12	(—) 49·15
1899	115·53	136·02	(—) 20·49
1900	114·53	188·37	(—) 73·84
1901	109·75	200·39	(—) 90·64
1902	99·26	274·65	(—) 175·39
1903	89·13	101·07	(—) 11·94
1904	129·38	100·57	28·81

(—) Denotes loss.

The gross earnings, expenditure, and net earnings per average mile open for the last decennial period were as follow :—

Year.	Gross Earnings per average mile open.	Expenditure per average mile open.	Net Earnings per average mile open.
	£	£	£
1895	101	79	22
1896	104	105	(—) 1
1897	123	130	(—) 7
1898	97	139	(—) 42
1899	102	119	(—) 17
1900	102	167	(—) 65
1901	95	174	(—) 79
1902	86	238	(—) 152
1903	78	88	(—) 10
1904	117	91	26

(—) Denotes loss.

The gross earnings show little variation from year to year, but the expenditure was increased through the series of accidents at the terminal port, to which reference has already been made.

*Coaching and Goods Traffic.*

The following table shows the number of passengers carried on the Palmerston to Pine Creek Line since its opening, together with

the receipts from the traffic and the average receipts per journey:—

Year.	Passengers carried.	Receipts from Coaching Traffic.	Average Receipts per journey.
	No.	£	d.
1890 (nine months) .....	4,567	4,330	227·54
1891 .....	4,515	4,693	249·45
1892 .....	4,541	4,159	219·80
1893 .....	6,169	4,007	155·89
1894 .....	4,076	3,820	224·91
1895 .....	2,950	3,755	305·48
1896 .....	2,901	3,772	312·04
1897 .....	3,080	4,055	315·97
1898 .....	3,126	3,556	273·01
1899 .....	3,191	3,173	238·64
1900 .....	3,374	3,556	260·48
1901 .....	4,097	3,415	200·05
1902 .....	3,755	3,032	193·80
1903 .....	3,631	2,913	192·53
1904 .....	3,653	2,803	184·15

The table shows an increase in the number of passengers carried during 1893; but the promise of the year was not sustained, and the traffic fell away by more than one-half during 1895, 1896, and 1897, although the earnings did not decline in anything like the same proportion. Since the year last mentioned there has been a steady, though small, increase in the number of passengers; but without a corresponding addition to the revenue. The receipts per journey indicate that a large proportion of the traffic is of a long-distance character.

The amount of goods tonnage for a similar period is shown in the following table:—

Year.	Tonnage of Goods and Live Stock. Tons.	Earnings. £
1890 (nine months)* .....	2,114	7,499
1891 .....	2,426	9,035
1892 .....	2,633	9,267
1893 .....	2,328	9,470
1894 .....	2,524	10,260
1895 .....	2,063	8,643
1896 .....	2,493	9,149
1897 .....	3,150	11,222
1898 .....	2,678	8,570
1899 .....	3,187	10,091
1900 .....	3,009	9,626
1901 .....	2,981	8,892
1902 .....	2,436	7,996
1903 .....	2,455	7,000
1904 .....	6,209	11,568

The average receipts per ton per mile during the year 1904 were 5·23d., as against 8·43d. in 1896.

## WESTERN AUSTRALIA.

The first railway constructed in Western Australia was that from Geraldton to Northampton, a length of 34 miles 17 chains, opened for traffic on the 26th July, 1879. Between that date and the close of 1885, a further length of 91 miles 55 chains was constructed. To the end of 1890, only 200½ miles were constructed, and on the 30th June, 1895, there were 573 miles open for traffic. Railway construction received a considerable impetus subsequent to 1895, and on the 30th June, 1904, there were 1,541 miles open for traffic, at a cost of £8,955,929 for construction and equipment, or at the rate of £5,812 per mile.

The state railways of Western Australia are comprised in five systems. The Eastern system has a length of 179½ miles, and includes the line from Fremantle to Northam, with branches to Owen's Anchorage and Woodman's Point, Belmont, Upper Darling Range, Newcastle, Greenhills, and Beverley and Mahogany Creek deviation; the Eastern Gold Fields system extends eastward from Northam, and includes the Kanowna, Goomalling, Leonora, and Boulder branches and Brown Hill loop line, the total length being 525½ miles; the South-western system comprises the line from East Perth to Bunbury, with branches to Collie, Collie Boulder, Bridgetown, Busselton, and Donnybrook, and Canning and Bunbury Racecourses, and has a length of 240 miles; the Northern system includes the line from Geraldton to Cue and Nannine, with branches to Walkaway, Mullewa, and Northampton, the total length being 353 miles; and the Great Southern system, from Beverley to Albany, is 243 miles in length.

The control of the state railways was formerly vested in the Commissioner for Railways as member of the Government, the active management being undertaken by an officer with the title of General Manager, but on the 1st July, 1902, the administration was placed in the hands of an independent Commissioner.

*Revenue and Working Expenses.*

The net sum available to meet interest charges during the last ten years is shown in the following table:—

Year.	Gross Earnings.	Working Expenses.	Net Earnings.	Proportion of Working Expenses to Gross Earnings.
	£	£	£	per cent.
1895 .....	296,000	182,046	113,954	61·50
1896 .....	529,616	263,704	265,912	49·79
1897 .....	915,483	577,655	337,828	63·09
1898 .....	1,019,677	786,318	233,359	77·11
1899 .....	1,004,620	712,329	292,291	70·81
1900 .....	1,259,512	861,470	398,042	68·40
1901 .....	1,363,704	1,044,920	308,784	77·19
1902 .....	1,521,429	1,256,370	265,059	82·68
1903 .....	1,553,485	1,247,873	305,612	80·33
1904 .....	1,588,084	1,179,624	408,460	74·28

From the foregoing statement it will be seen that the gross earnings have increased from £296,000 in 1895 to £1,588,084 in 1904. The rush to the gold-fields of Western Australia has brought an enormous amount of traffic to the railways of that state, and the lines stand in a position which it is impossible for those of any other province to attain, except under similar circumstances. The proportion of working expenses to gross earnings during the ten years has increased from 61·50 per cent. to 74·28 per cent., the intervening years showing considerable irregularity. The rates for the carriage of merchandise are so low that the revenue derived from the traffic is hardly sufficient to pay for working it, and with a view to economy during 1899 the train service was considerably curtailed, and trains previously confined to passenger traffic were converted into mixed trains, conveying both passengers and goods, the result being a substantial reduction in working expenses proportionately to the gross earnings.

The relation of working expenses to gross earnings for 1904 showed a percentage of 74·28, as compared with 80·33, 82·58, and 77·19 in the preceding three years. The comparatively large increase during the period is attributable to several causes. There was a substantial addition to the tonnage of coal, timber, and goods hauled at low rates, but no profit was returned therefrom, the receipts only about equalling the working expenses in connection therewith. A heavy expenditure was incurred on locomotive repairs, and among other contributing causes were the rise in price of coal and stores, and increased rates of wages.

Western Australian lines show much greater variation from year to year than the lines of any other state. During the ten years 1895-1904, the lowest expenditure was in 1896 with 41·05d. per train mile, which rose to 66·89d. in 1902, but dropped to 61·62d. in 1904. The conditions, however, in the earlier years of the decade, when only 550 miles of line were open for traffic, and the train miles run amounted only to 997,540, were entirely different from those of 1904 with 1,541 miles open for traffic and an aggregate train mileage of 4,594,234. In 1899 there was a reduction in the total working expenses, brought about mainly by the curtailment of the mileage; this was accomplished by reducing the number of passenger trains and adopting a system of mixed trains. In the year 1900 there was a large increase in the number of locomotives, and in the repairs to carriages, waggon, &c. This increase, so far as can be seen, was attributable, partly to the natural development of the traffic, but chiefly to the inadequate workshop accommodation and to the fact that the water supply for railways was both inferior and expensive. The year 1901 showed a great advance in the cost of the railways, the expenditure per train mile rising from 49·04d. to 60·78d., every branch participating in the increase. It was in this year that the fifty-four hours per week system was introduced, involving the employment of an increased wages staff, and in addition thereto there was a general increase in the rates of wages. The conditions of working at Fremantle locomotive shops entailed a large outlay, while there was an increased

expenditure on locomotives due to the compulsory use of bad water, and the overwork of rolling stock owing to a shortage of hauling power and waggons. During the year named the railways were undoubtedly worked at a very great disadvantage.

The increased expenditure per train mile in 1901 was continued during 1902, when it rose from 60·78d. to 66·89d., in consequence of the large outlay in all branches of the service. There was a specially heavy expenditure in the locomotive branch, amounting to £173,297. In 1904, however, the average per train mile fell to 61·62d.

Year.	Maintenance of Way, Works, and Buildings.	Locomotive Power.	Rolling Stock Repairs and Renewals.	Traffic Expenses.	Compensation.	General Charges.	Total.
	£	£	£	£	£	£	£
1895	36,202	86,453	Included in Locomotive Power.	50,725	.....	8,666	182,046
1896	56,036	101,892		94,388	.....	11,588	263,704
1897	97,184	221,884		225,615	11,651	21,321	577,655
1898	176,741	315,066		266,167	9,803	18,541	796,318
1899	165,277	297,500		227,225	3,568	18,759	712,329
1900	183,096	406,565	Locomotive Power.	252,750	4,455	14,604	861,470
1901	221,451	497,188		296,045	6,926	23,310	1,044,920
1902	246,931	670,485		306,408	7,246	25,300	1,256,370
1903	265,548	354,406		312,364	4,808	22,345	1,247,873
1904	264,430	336,708	288,402	306,998	3,940	22,601	1,179,624

## PER TRAIN MILE.

	d.	d.	d.	d.	d.	d.	d.
1895	8·71	20·80	Included in Locomotive Power.	12·21	.....	2·08	43·80
1896	8·72	15·83		14·69	.....	1·81	41·05
1897	9·19	20·99		21·34	1·10	2·02	54·64
1898	11·74	20·92		17·68	0·65	1·23	52·22
1899	12·18	21·92		16·74	0·26	1·38	52·48
1900	10·42	23·15	Locomotive Power.	14·39	0·25	0·83	49·04
1901	12·88	28·92		17·22	0·40	1·36	60·78
1902	13·15	35·70		16·31	0·38	1·35	66·89
1903	13·82	18·46		16·26	0·25	1·16	64·95
1904	13·82	17·59	15·00	16·04	0·21	1·17	61·62

## PER MILE OPEN.

	£	£	£	£	£	£	£
1895	65·8	157·2	Included in Locomotive Power.	92·2	.....	15·8	331·0
1896	96·6	175·3		162·7	.....	20·0	454·6
1897	117·1	267·3		271·8	14·0	25·7	695·9
1898	181·5	323·5		273·3	10·0	19·0	807·3
1899	130·1	234·3		178·9	2·8	14·8	560·9
1900	126·1	300·0	Locomotive Power.	186·5	3·3	10·8	635·7
1901	163·4	366·9		218·5	5·1	17·2	771·1
1902	182·1	494·5		225·9	5·3	18·7	926·5
1903	185·2	247·2		217·7	3·4	15·6	870·2
1904	172·3	219·3	201·1	200·0	2·5	14·7	768·4

*Interest returned on Capital.*

The following is a statement of the average interest earned by the railways on the money invested in them, and affords a comparison with the interest paid on the public debt of the state :—

Year.	Interest returned on Capital.	Actual Rate of Interest payable on Outstanding Loans.	Average gain.
	per cent.	per cent.	per cent.
1895 .....	5·45	4·57	0·88
1896 .....	11·48	3·84	7·64
1897 .....	9·05	3·61	5·44
1898 .....	4·62	3·59	1·03
1899 .....	4·55	3·54	1·01
1900 .....	5·81	3·52	2·29
1901 .....	4·35	3·52	0·83
1902 .....	3·54	3·47	0·07
1903 .....	3·75	3·48	0·27
1904 .....	4·58	3·49	1·07

The railways of Western Australia have not only met working expenses during the past ten years, but have left a margin after making provision for the payment of interest on capital expenditure. In the construction of these railways, few engineering difficulties were met with, and the lines, which are of a light character, were constructed at a cheaper rate than those of any other state. This fact, together with the enormous increase in coaching and goods traffic, due to the development of the gold-fields, has been instrumental in securing such a favourable return.

*Earnings and Expenses per Mile.*

The gross earnings, expenditure, and net earnings per train mile for the last ten years are shown in the following table :—

Year.	Gross Earnings per train mile.	Expenditure per train mile.	Net Earnings per train mile.
	d.	d.	d.
1895 .....	71·22	43·80	27·42
1896 .....	82·44	41·05	41·39
1897 .....	86·59	54·64	31·95
1898 .....	67·72	52·22	15·50
1899 .....	74·01	52·48	21·53
1900 .....	71·70	49·04	22·66
1901 .....	78·74	60·78	17·96
1902 .....	81·00	66·89	14·11
1903 .....	80·85	64·95	15·90
1904 .....	82·96	61·62	21·34

The gross earnings, expenditure, and net earnings per average mile open for the past ten years were as follow :—

Year.	Gross Earnings per average mile open.	Expenditure per average mile open.	Net Earnings per average mile open.
	£	£	£
1895 .....	538	331	207
1896 .....	913	454	459
1897 .....	1,103	696	407
1898 .....	1,047	807	240
1899 .....	791	561	230
1900 .....	930	636	294
1901 .....	999	771	228
1902 .....	1,122	927	195
1903 .....	1,083	870	213
1904 .....	1,034	768	266

While the gross earnings per train mile have increased from 71·22d. in 1895 to 82·96d. in 1904, the net earnings show a considerable decrease during the period, having fallen from 27·42d. in the former year to 21·34d. in the latter. The causes that have led up to this have already been indicated. The volume of coaching and goods traffic carried during 1898 was larger than in previous years, but the net earnings per average mile open show a marked reduction. The increased traffic, of course, necessitated extra expenditure; and being accompanied by a reduction in rates, had the temporary effect of reducing the net earnings. It is estimated that the adoption of the new rates, as compared with the old, involved a loss during 1898 of at least £232,000 in the working of the Northam, Southern Cross, Coolgardie, and Kalgoorlie railways, but the wisdom of the railway policy of the country was justified by the results of the following two years. The abnormal rise in the expenditure for 1901 has already been explained.

#### *Coaching and Goods Traffic.*

The following table shows the number of passengers carried on the lines of the state during the year 1887, the earliest for which particulars

are available, and for the last ten years, together with the receipts from the traffic, and the average receipts per journey :—

Year.	Passengers carried.	Receipts from Coaching Traffic.	Average Receipts per Journey.
	No.	£	d.
1887 .....	173,656	19,032	26·29
1895 .....	1,022,248	122,051	28·65
1896 .....	1,679,816	188,765	26·97
1897 .....	3,607,486	410,750	27·33
1898 .....	5,669,444	458,402	19·41
1899 .....	5,872,200	364,687	14·90
1900 .....	6,225,068	402,500	15·52
1901 .....	6,823,453	407,319	14·33
1902 .....	8,158,299	430,093	12·65
1903 .....	9,106,396	437,232	11·52
1904 .....	10,225,976	462,455	10·85

The statement shows a large increase in the number of passengers carried each year ; the gradual reduction in the average receipts per journey indicates the expansion of the suburban and local traffic.

The amount of goods tonnage for a similar period is shown in the following table :—

Year.	Tonnage of Goods.	Earnings.
1887 .....	52,151	£20,380
1895 .....	255,839	173,949
1896 .....	435,855	340,850
1897 .....	858,748	494,733
1898 .....	1,203,911	561,275
1899 .....	1,132,246	639,933
1900 .....	1,384,040	857,012
1901 .....	1,719,720	946,385
1902 .....	2,040,092	970,684
1903 .....	1,968,331	983,877
1904 .....	2,291,764	1,026,734

It will be seen that the increase in the goods traffic has been considerable since 1897, while the tonnage in 1902 was nearly two and a half times that of 1897. Owing to reduction in the charges for carriage, the earnings have not shown so considerable an expansion.

#### TASMANIA.

The progress of railway construction in Tasmania has been somewhat slow, for owing to the fact that the island is small and possesses numerous harbours, the railways have had to face severe competition with sea-borne traffic. As stated earlier in the chapter, the line from Launceston to Deloraine, 45 miles in length, was opened on 10th February, 1871, and though an agitation long existed for the construction of a railway between the principal centres, Hobart and Launceston, it was not till



the 1st November, 1876, that it was opened for traffic. No further extension was carried out until 1884, when an increase of 48 miles was made, and up to 1890 the total mileage opened was only 398, of which 48, opened in 1884, were constructed by a private company. The length of state railways opened to 31st December, 1903, was 461½ miles, at a cost of £3,883,729 for construction and equipment, or at the rate of £8,411 per mile.

The lines of state railway in operation in Tasmania are the Western, from Launceston to Burnie, with branch to Chudleigh; the Main line from Hobart to Launceston, with branches from Launceston to Scottsdale, Parattah to Oatlands, Conara Junction to St. Mary's, Bridgewater to Glenora, and Brighton Junction to Apsley; the Sorell line, from Bellerive to Sorell; and the West Coast line, from Regatta Point to Zeehan.

The control of the railways is vested in the Department of Lands and Works, the active management being undertaken by an officer with the title of General Manager.

*Revenue and Working Expenses.*

The net sum available to meet interest charges in connection with the railways of the state for each of the years during the last decennial period was as follows:—

Year.	Gross Earnings.	Working Expenses.	Net Earnings.	Proportion of Working Expenses to Gross Earnings.
	£	£	£	£
1894 .....	144,488	122,850	21,638	85·02
1895 .....	149,642	120,351	29,291	80·42
1896 .....	162,932	122,171	40,761	74·98
1897 .....	166,834	128,544	38,290	77·04
1898 .....	178,180	141,179	37,001	79·23
1899 .....	193,158	152,798	40,360	79·10
1900 .....	202,959	160,487	42,472	79·07
1901 .....	205,791	173,400	32,391	84·26
1902 .....	233,210	173,292	59,918	74·31
1903 .....	247,683	166,355	81,328	67·16

The cost of working the Tasmanian railways is comparatively high, and, as in New Zealand, the lines have to face severe competition with sea-borne traffic, while there are no large inland centres that could support railways. There is a marked decrease year by year in the Australian traffic, *via* Launceston, which is attributed to the great improvement in the direct steamer service between Melbourne and Hobart. The figures show a gradual increase in gross earnings over the period, the substantial gain in the last year being due to increased traffic consequent on the favourable harvest and the higher passenger and goods rates.

The following analysis of the working expenses of Tasmanian railways for the ten years 1894–1903 does not call for special comment. There has, of late years, been a slight upward tendency in the cost of train mileage, partly due to the increased price of coal. In the years 1895, 1896 and 1897 it is evident that necessary expenditure on rolling stock was not carried out, thus throwing the burthen of repairs on to later years—this was especially the case in regard to locomotive repairs. In 1901 there were extensive renewals of locomotive boilers, but a portion of the expenditure in connection therewith might have been saved by earlier attention :—

Year ended 31st December.	Maintenance of Way, Works, and Buildings.	Locomotive Power, Carriage and Waggon Repairs and Renewals.	Traffic Expenses.	General Charges.	Total.
	£	£	£	£	£
1894.....	44,762	42,483	29,507	6,098	122,850
1895.....	46,548	38,381	29,424	5,998	120,351
1896.....	46,813	36,326	30,909	6,123	122,171
1897.....	48,561	40,683	32,989	6,311	128,544
1898.....	54,927	45,180	33,765	7,307	141,179
1899.....	56,238	51,662	37,370	7,528	152,798
1900.....	58,862	53,865	39,300	8,460	160,487
1901.....	59,897	63,580	41,138	8,785	173,400
1902.....	58,612	63,791	42,416	8,473	173,292
1903.....	51,957	62,376	42,820	9,202	166,355

## PER TRAIN MILE.

	d.	d.	d.	d.	d.
1894.....	14.2	13.5	9.3	1.9	38.9
1895.....	15.4	12.6	9.7	2.0	39.7
1896.....	15.2	12.4	10.0	2.0	39.6
1897.....	15.2	12.8	10.3	2.0	40.3
1898.....	17.3	14.2	10.7	2.3	44.5
1899.....	16.7	15.4	11.1	2.2	45.4
1900.....	17.3	15.8	11.6	2.5	47.2
1901.....	16.1	17.0	11.0	2.3	46.4
1902.....	15.6	16.9	11.2	2.3	46.0
1903.....	13.4	16.0	11.0	2.4	42.8

## PER MILE OPEN.

	£	£	£	£	£
1894.....	104.8	99.4	68.0	14.3	287.5
1895.....	109.0	89.8	68.8	14.0	281.6
1896.....	109.6	89.7	72.3	14.3	285.9
1897.....	112.4	94.1	76.3	14.5	297.3
1898.....	123.3	101.5	75.8	16.4	317.0
1899.....	126.3	116.0	83.9	16.9	343.1
1900.....	132.1	120.9	88.2	19.0	360.2
1901.....	130.3	138.4	89.5	19.1	377.3
1902.....	125.2	136.3	90.6	18.1	370.2
1903.....	110.8	133.0	91.3	19.6	354.7

*Interest returned on Capital.*

The following table shows the average loss on the working of the Tasmanian railways for each year during the last ten years :—

Year.	Interest returned on Capital.	Actual rate of Interest payable on Outstanding Loans.	Average Loss.
	per cent.	per cent.	per cent.
1894	0·61	3·96	3·35
1895	0·83	3·88	3·05
1896	1·16	3·87	2·71
1897	1·09	3·85	2·76
1898	1·03	3·82	2·79
1899	1·12	3·81	2·69
1900	1·16	3·78	2·62
1901	0·85	3·76	2·91
1902	1·56	3·76	2·20
1903	2·09	3·76	1·67

The foregoing table shows that there was a slight improvement in the condition of the railway revenue during the five years preceding 1901. During 1901 the interest returned on capital expenditure fell to nearly that of the year 1895. Among the causes leading to this was the reduction in passenger fares, in the case of single fares by 45 per cent., and return fares by 27½ per cent. These large reductions did not result in the fulfilment of anticipations, and on the 1st December, 1901, a revised scale was adopted, which is still 20 per cent. below that in force in 1900. The competition of the Emu Bay Company and the low prices ruling for lead and silver have brought about a decrease in revenue on the Government West Coast line. Working expenses have absorbed 84·26 per cent. of total revenue, and the large increase over the previous five years is due to increased mileage, more extensive renewals of locomotive boilers paid for out of working expenses, and the increased price of coal. The competition already referred to, together with the heavy initial cost of the railways themselves, especially of the main line connecting Hobart with Launceston, for which the price paid by the Government on its resumption was at the rate of £9,069 per mile, as against an average of £8,304 per mile for the lines of the state generally, render it extremely difficult, even with the most careful management, to effect any considerable diminution in the average loss. Even in the case of the Western line from Launceston to Burnie, which passes through the finest agricultural land in the state, the return, after paying working expenses for the year ended 31st December, 1903, was only 3·49 per cent. on the cost of construction and equipment. The results for all lines in 1902 were fairly satisfactory, while in 1903, both

gross and net earnings were higher than in any previous year shown in the table. It is not expected that these excellent returns will be secured during the present year, as the goods traffic is prejudicially affected by the difficulty experienced in securing a market for agricultural produce.

*Earnings and Expenses per Mile.*

The following tables indicate the gross earnings, expenditure, and net earnings per train mile and per average mile of line open. The considerable falling off in net earnings during 1901, in comparison with the previous five years, is due to the reduction of fares and the shrinkage in revenue from goods traffic already referred to.

Year.	Gross Earnings per train mile.	Expenditure per train mile.	Net Earnings. per train mile.
	d.	d.	d.
1894	45·83	38·96	6·87
1895	49·36	39·69	9·67
1896	52·85	39·63	13·22
1897	52·34	40·33	12·01
1898	56·17	44·50	11·67
1899	57·50	45·49	12·01
1900	59·70	47·20	12·50
1901	55·14	46·46	8·68
1902	61·99	46·06	15·93
1903	63·79	42·84	20·95

The earnings and expenditure per average mile open were as shown in the following statement:—

Year.	Gross Earnings per average mile open.	Expenditure per average mile open.	Net Earnings per average mile open.
	£	£	£
1894	328	287	51
1895	350	281	69
1896	381	286	95
1897	386	297	89
1898	400	317	83
1899	434	343	91
1900	456	360	96
1901	448	377	71
1902	496	370	126
1903	528	354	174

In comparison with the other states the proportion of expenses to gross earnings in Tasmania is extremely high, and while for the five years ended 1900 an improvement was shown, the increase in 1901 and 1902 indicates that it is not possible under present conditions to reduce expenditure, the material advantage secured during 1904 being due to exceptionally favourable circumstances.

*Coaching and Goods Traffic.*

Particulars in regard to the number of passengers carried on the state lines of Tasmania during the year 1881, and for the last ten years, together with receipts from the traffic and the average receipts per journey, are set forth in the following table:—

Year.	Passengers carried.	Receipts from Coaching Traffic.	Average Receipts per Journey.
	No.	£	d.
1881	102,495	10,396	24·34
1894	514,461	58,070	27·09
1895	526,814	57,947	26·39
1896	542,825	59,771	26·43
1897	603,530	62,447	24·88
1898	617,643	68,317	26·54
1899	640,587	73,147	27·40
1900	683,015	76,184	26·77
1901	777,445	78,328	24·18
1902	761,345	99,115	31·25
1903	814,483	105,389	31·06

During the year 1892 there was a comparatively large number of passengers carried. This was due to the resumption of the main line connecting Hobart with Launceston, the returns for the years in question being swollen by the traffic over the increased length of line. The traffic, however, was not sustained, for in the subsequent year a large diminution in the number of persons making use of the lines was recorded. There has since been a revival, and there are good grounds for supposing that this improvement will be continued. The average receipts per journey do not vary to any considerable extent, the amount of suburban traffic properly so-called being very small. The fall in 1901 is largely due to the considerable reduction in fares already alluded to. A reaction, however, set in during 1902, and the average receipts per journey for that year are the highest during the decennial period, and the improvement was fairly well sustained during 1903.

The amount of goods tonnage for a similar period is shown in the following table :—

Year.	Tonnage of Goods and Live Stock.	Earnings. £
1881 .....	21,043	8,332
1894 .....	174,457	73,639
1895 .....	204,480	78,797
1896 .....	229,707	85,780
1897 .....	229,620	86,941
1898 .....	235,096	93,620
1899 .....	312,446	107,661
1900 .....	308,453	111,904
1901 .....	314,628	108,698
1902 .....	407,505	134,096
1903 .....	418,701	121,129

No information is available showing the subdivision of the tonnage of goods and live stock into a general classification. The average distance each ton of goods was carried was 34·86 miles, and the average receipts per ton per mile 2·10d.

#### NEW ZEALAND.

The continuance of the native war in New Zealand militated against the rapid extension of the railways, and at the close of the war in 1870 there were only 46 miles in operation. In 1875 the length of line opened for traffic had increased to 542 miles; in 1885, to 1,613 miles; in 1890, to 1,842 miles; and in 1895 to 2,014 miles. The length of line opened to 31st March, 1904, was 2,328 miles, at a cost of £20,692,911 for construction and equipment, or at the rate of £8,888 per mile.

The railway system of the colony is divided into ten sections. The Kawakawa and Whangarei sections, in the extreme north of the North Island, are short lines to coal-fields, and the Kaihu section was built for the purpose of tapping large timber areas inland. The Auckland section forms the northern portion of the North Island main trunk railway, which, when complete, will terminate at Wellington, on the shores of Cook's Strait. The Wellington-Napier-New Plymouth section comprises the group of lines which serve the southern portion of North Island. In the northern portion of Middle Island, the Westland, Westport, Nelson, and Picton sections form only the first link in the chain of through communication. On the East Coast of Middle Island, the actual working portion of the main trunk line is to be found. The present terminus is at Culverden, from whence extension will be made northward. This is known as the Hurunui-Bluff section, and includes the service to Christchurch, Dunedin, Invercargill, and the Bluff.

During the year ended March, 1901, the whole of the Midland railways were formally taken possession of by the Government and incorporated with the Westland section of the Government railways. They had previously been worked by the Government as a trust. The total length of these lines was about 83 miles.

The management of the railways of New Zealand was placed in the hands of three Commissioners in 1887, but early in 1895 the Government resumed charge of the lines, the active control being vested in an officer with the title of General Manager, who is responsible to the Minister for Railways.

*Revenue and Working Expenses.*

The net sum available to meet interest charges during each year of the last decennial period is set forth in the following table:—

Year.	Gross Earnings.	Working Expenses.	Net Earnings.	Proportion of Working Expenses to Gross Earnings.
	£	£	£	£
1895	1,150,851	732,161	418,690	63·62
1896	1,183,041	751,368	431,673	63·51
1897	1,286,158	789,054	497,104	61·35
1898	1,376,008	857,191	518,817	62·30
1899	1,469,665	929,738	539,927	63·26
1900	1,623,891	1,052,358	571,533	64·80
1901	1,727,236	1,127,848	599,388	65·30
1902	1,874,586	1,252,237	622,349	66·80
1903	1,974,038	1,343,415	630,623	68·05
1904	2,180,641	1,438,724	741,917	65·98

The foregoing table shows that the serious fluctuations which at times characterise the returns of the states on the mainland of Australia are absent from those of New Zealand, the configuration of the islands and their higher latitude rendering them to a very great extent immune from the periodical droughts to which the Australian states are so subject. The proportion of working expenses to gross earnings does not vary to any considerable extent, and the rise during the past five years is attributed to the payment of an increased rate of wages to employees, replacing old engines with new, extensive repairs due to the increased age of the stock, and the relaying of a portion of the permanent way with heavier rails. The traffic has, in many places, practically outgrown the carrying capacity of the lines, which were originally intended as the pioneers of settlement, and were not built to cope with a business such as exists in many parts of the colony. The management urges the employment of the heaviest type of locomotive as a matter of the utmost importance in the interests of economy, together with the running of trains at frequent intervals and higher speeds. During the year just closed the number of locomotives was increased by five, while twenty-one are under construction. There are considerable portions of main line still laid with light rails, and until such time as these can be replaced with rails of a heavier type, and the bridges strengthened to carry the heavier class of engine, it is impossible to obtain completely satisfactory results in working.

The analysis of the working expenses of the New Zealand railways for the ten years, 1895-1904, which is here presented, shows that there

has been a regular increase since 1895, in which year the expenditure amounted to £732,161, equal to 54·54d. per train mile compared with 60·48d. per train mile in 1904.

In 1902 the Minister for Railways drew attention to the increasing age of the lines, the necessity for employing heavier rolling stock, and the accelerated speed which render the efficient maintenance of the track an imperative necessity; if the Minister's ideas are fully carried out an increased expenditure may be looked for. The advance in the cost of working from £372 to £624 per mile of line open is of no significance, such expenditure being due merely to the continued growth of the traffic.

Year ended 31st March.	Maintenance of Way, Works, and Buildings.	Locomotive Power.	Rolling Stock Repairs and Renewals.	Traffic Expenses.	General Charges.	Total.
	£	£	£	£	£	£
1895	272,718	144,653	82,054	201,641	31,095	732,161
1896	282,593	150,037	90,324	207,253	21,161	751,368
1897	301,981	130,689	125,679	213,914	16,791	789,054
1898	327,987	143,458	131,175	232,646	21,925	857,191
1899	357,189	154,752	150,460	244,932	22,405	929,738
1900	394,619	176,925	195,172	262,552	23,090	1,062,358
1901	426,405	210,681	174,234	296,159	20,369	1,127,849
1902	436,847	254,451	196,243	333,211	31,485	1,252,237
1903	460,398	279,932	204,619	360,061	38,405	1,343,415
1904	490,819	306,785	219,371	374,347	47,402	1,438,724

## PER TRAIN MILE.

	d.	d.	d.	d.	d.	d.
1895	20·32	10·77	6·11	15·02	2·32	54·54
1896	20·51	10·89	6·55	15·04	1·54	54·55
1897	21·26	9·20	8·85	15·06	1·18	55·55
1898	21·47	9·39	8·58	15·23	1·44	56·11
1899	21·60	9·36	9·10	14·81	1·35	56·22
1900	22·61	10·14	11·18	15·05	1·33	60·31
1901	22·15	10·94	9·05	15·38	1·06	58·58
1902	20·69	12·05	9·30	15·79	1·49	59·32
1903	20·30	12·34	9·02	15·88	1·69	59·23
1904	20·72	12·95	9·26	15·80	1·75	60·48

## PER MILE OPEN.

	£	£	£	£	£	£
1895	138·57	73·50	41·70	102·45	15·90	372·02
1896	141·45	75·09	45·21	103·74	10·59	376·08
1897	149·77	64·82	62·33	106·09	8·33	391·34
1898	160·53	70·21	64·20	113·86	10·73	419·53
1899	172·92	74·92	72·84	118·56	10·85	450·09
1900	187·99	84·29	92·98	125·08	11·00	501·34
1901	196·14	96·91	80·15	136·23	9·37	513·80
1902	196·17	114·26	88·12	149·63	14·14	562·32
1903	203·55	123·75	90·46	159·17	16·97	593·90
1904	212·94	133·09	95·17	162·41	20·56	624·17



*Interest Returned on Capital.*

The basis employed in the case of the states comprised within the Commonwealth for ascertaining the net interest payable on the railway debts cannot be adopted for New Zealand, the necessary data not being available. The nominal loss is, therefore, shown in the following statement, the actual loss being somewhat higher :—

Year.	Interest Returned on Capital.	Average rate of Interest payable on Outstanding Loans.	Average Loss.
	per cent.	per cent.	per cent.
1895	2·73	4·00	1·27
1896	2·80	3·94	1·14
1897	3·19	3·92	0·73
1898	3·24	3·89	0·65
1899	3·29	3·81	0·52
1900	3·42	3·79	0·37
1901	3·48	3·78	0·30
1902	3·43	3·76	0·33
1903	3·31	3·71	0·40
1904	3·58	3·83	0·25

The foregoing table indicates that the railways are approaching the stage of being self-supporting, the interest returned on capital cost showing an upward tendency during the period.

*Earnings and Expenses per Mile.*

The gross earnings, expenditure, and net earnings per train mile for the past ten years are shown in the following table :—

Year.	Gross Earnings per train mile.	Expenditure per train mile.	Net Earnings per train mile.
	d.	d.	d.
1895	85·75	54·54	31·21
1896	85·75	54·53	31·22
1897	90·50	55·55	34·95
1898	90·00	56·11	33·89
1899	89·00	56·22	32·78
1900	93·00	60·31	32·69
1901	89·75	58·58	31·17
1902	88·80	59·32	29·48
1903	87·02	59·23	27·79
1904	91·75	60·48	31·27

The gross earnings per train mile have varied very little during the ten years, the lowest point touched being 85½d., and the highest, 93d., while the expenditure has varied even less. The expenditure during 1904 was higher than in any other year during the decennial period. The gross earnings per train mile for the past four years were less than

those of 1900, and the net earnings show a slight but gradual reduction during the past seven years. The results, however, compare very favourably with the other states, and are only exceeded by those of New South Wales, with the exception of the year just closed, when New Zealand showed a slightly higher net return.

The gross earnings, expenditure, and net earnings per average mile open for the past ten years are as follow :—

Year.	Gross Earnings per average mile open.	Expenditure per average mile open.	Net Earnings per average mile open.
	£	£	£
1895	585	372	213
1896	592	376	216
1897	638	391	247
1898	673	419	254
1899	712	450	262
1900	774	501	273
1901	794	519	275
1902	842	562	280
1903	873	594	279
1904	943	622	321

The foregoing table indicates that the gross earnings have increased from £585 per average mile open to £943, and the net earnings from £213 to £321, the return for 1904 being the highest secured during the decennial period—evidence of the fact that the extensions in recent years have been judicious, and that the volume of traffic has been maintained.

#### *Coaching and Goods Traffic.*

The following table shows the number of passengers carried on the lines of the colony during the year ended 31st March, 1882, and for the last ten years, together with the receipts from the traffic, and the average receipts per journey :—

Year.	Passengers carried.	Receipts from Coaching traffic.	Average Receipts per Journey.
	No.	£	d.
1882	2,911,477	329,492	27·16
1895	3,905,578	360,243	22·14
1896	4,162,426	359,822	20·74
1897	4,439,387	378,684	20·47
1898	4,672,264	399,262	20·51
1899	4,953,553	438,367	21·23
1900	5,468,284	474,793	20·83
1901	6,243,593	503,051	19·34
1902	7,356,136	575,697	18·78
1903	7,575,390	576,529	18·26
1904	8,306,383	652,080	18·84

It will be observed that there was a falling off during the decennial period in the average receipts per journey. The continued increase in the number of passengers carried is, however, very marked, the advance for the closing year of the period being nearly 731,000, while the receipts from the traffic rose by £75,551. Taking the returns for the year ended 31st March, 1884, as a basis, it has been found that those for 1904 show an increase of only 40 per cent. in the number of passengers who travelled first-class, while the increase in those who travelled second-class was not less than 124 per cent. While the marked prosperity of the past five years has induced more passengers to travel first-class, it is none the less evident that the tendency is towards one class of carriage, as already exists in the case of tramways.

The amount of goods tonnage for a similar period is shown in the following table :—

Year.	Tonnage of Goods exclusive of Live Stock.	Earnings. £
1882.....	1,437,714	491,057
1895.....	2,048,391	683,726
1896.....	2,087,798	698,115
1897.....	2,368,927	774,163
1898.....	2,518,367	837,590
1899.....	2,624,059	882,077
1900.....	3,127,874	985,723
1901.....	3,339,687	1,051,695
1902.....	3,529,177	1,110,575
1903.....	3,730,394	1,189,101
1904.....	3,918,261	1,293,169

The large increase in the tonnage of goods carried during 1900 over preceding years was caused by the bountiful harvest in the Middle Island, which was carried at freight rates averaging 20 per cent. below those ruling in the previous year. The further increase of 211,813 tons for 1901 was contributed to by all descriptions of goods, with the exception of wool, the grain traffic alone being 84 per cent. higher than in 1899. The returns for 1902 show an advance of 189,490 tons over the traffic in 1901. During the years 1902, 1903 and 1904 increases occur under all the various headings, the largest being in grain and timber, the traffic in each class, with the exception of wool, being the largest on record.

The subdivision of the tonnage of goods and live stock for the year ended 31st March, 1904, is shown in the following table. Particulars of the goods traffic are set forth in seven classes, but the average distance

for which goods of each class were carried cannot be given, and there are no data available showing the average earnings per ton per mile.

Description of Traffic.	Tons carried.	Number carried.
Lime and Chaff .....	132,562	.....
Wool.....	101,316	.....
Firewood .....	106,066	.....
Timber.....	509,712	.....
Grain .....	820,453	.....
Merchandise .....	658,144	.....
Minerals .....	1,744,323	.....
Cattle .....	.....	107,435
Sheep .....	.....	3,756,378
Pigs .....	.....	70,268

#### GOVERNMENT RAILWAYS SUPERANNUATION FUND.

On the 1st January 1903 "The Government Railways Superannuation Act, 1902" came into operation. Participation in the scheme was entirely optional as regards employees in the railway service at the time of the passing of the Act, and such persons were given a period of six months from the 1st January, 1903, within which to determine whether they would be contributors. In the case of persons appointed on or after the date on which the Act came into force, a condition of employment was that they were to become contributors to the fund. Notwithstanding that it was optional on the part of those officers on the permanent staff prior to the 1st January, 1903, when the time expired only 66 eligible members of the whole railway staff of the colony had failed to join the fund. The object of the Act is to enable contributors to make provision against want in old age or compulsory retirement in consequence of infirmity or disablement by injury or sickness, and to relieve the department from the payment of compassionate and other allowances. The balance sheet of the fund shows that contributions from members amounted for the year to £39,788, fines £255, and interest £774, which, with the balance of £7,057 brought forward from the previous year makes the total receipts to the 31st March, 1904, £47,874. The superannuation allowances paid during the year amounted to £6,434, representing grants to 184 members of the railway service who have either voluntarily resigned or been retired as medically unfit. Allowances amounting to £577 were paid in respect of twenty two widows and thirty nine children, dependents of deceased members of the railway service who were not entitled to allowances at the time of their death. A sum of £244, representing contributions of members of the service who voluntarily retired or whose services were otherwise dispensed with during the year, was refunded to the members concerned. Fines remitted and refunded to members amounted to £2, and travelling expenses of the Board, and commission paid to the Public Trusts Office totalled £259, leaving a balance to the credit of the fund on the 31st March, 1904, of £40,358.

## TRAMWAYS.

In all the Australasian states tramways are in operation, but it is chiefly in Sydney and Melbourne, the inhabitants of which numbered at the latest date 511,030 and 501,460 respectively, that the density of settlement has necessitated the general adoption of this mode of transit.

In New South Wales the three systems of electric, cable, and steam traction are in vogue. Within the metropolitan area, however, the electric is being substituted for steam power. The length of line under electric traction on the 30th June, 1904, was 67 miles 76 chains, comprising 11 miles 68 chains at North Sydney; 4 miles 18 chains, Ocean-street, Woollahra, to South Head; 3 miles 36 chains, George-street-Harris-street tramway; 4 miles 11 chains, Glebe Junction to Newtown, Marrickville, and Dulwich Hill; 2 miles 73 chains, Forest Lodge Junction to Leichhardt; 2 miles 57½ chains, Newtown to St. Peters and Cook's River; 1 mile 63 chains, Railway to Bridge-street; 5 miles 55 chains, Waverley and Bondi; 2 miles 28 chains, Railway to Glebe and Forest Lodge; 3 miles 41 chains, Forest Lodge to Balmain; 1 mile 26 chains, Redfern to Moore Park; 3 miles 20 chains, Pitt and Castlereagh streets to Fort Macquarie; 55 chains, George-street to Miller's Point; 5 miles 33 chains, Randwick and Coogee; 1 mile 18 chains, Waverley to Randwick; 69 chains, Crown-street to Cleveland-street; 2 miles 12 chains, Drummoyne; 6 miles 66 chains, Railway Station junction to Botany; 1 mile 45 chains, Zetland; 1 mile 34 chains, Mitchell-road; and 48 chains, Bridge and Phillip streets to Circular Quay. The only line worked by cable traction is that from King-street, Sydney, to Ocean-street, in the suburb of Woollahra, a distance of 2 miles 32 chains. On the remaining lines steam motors are still used, with the exception of that at Manly where horse traction is employed. The length of Government tram lines open to 30th June, 1904, was 125½ miles, which had cost for construction and equipment £3,471,759. The receipts for the year were £802,985, and the working expenses £673,625, leaving a profit of £129,360, or 3·73 per cent. on the invested capital. The number of passengers carried during 1904 was 137,843,513.

In Victoria the cable system is in operation in the metropolitan area, the lines having been constructed by a municipal trust at a cost of £1,705,794. The tramways are leased to a company, and the receipts for the year ended 30th June, 1904, were £473,726. The number of passengers carried during the year was 50,002,416. The miles of track operated on were 43½ cable and 4½ horse lines, or 48 miles of double track. Besides the lines of the Tramway Trust, there are additional suburban systems worked by limited liability companies, as follows:—Horse, 8½ miles; electric, 4 miles; and cable, 2½ miles.

In Queensland there is a system of electric trams controlled by a private company. The only information available shows that the capital of the company is £750,000 fully paid up, and that there are

also debentures to the amount of £400,000. Particulars as to receipts and disbursements are not available, but the report presented to the shareholders in London during May, 1902, showed a net profit of £42,815 for the period from 20th November, 1900, to 31st December, 1901. The length of the tramways is 25 miles, or 43 miles of single line. The company owned seventy-nine electric cars, and during the year 1901, 16,183,801 passengers were carried.

In South Australia there are no Government tramways, but horse trams are run in the principal streets of Adelaide by private companies. No particulars have been collected respecting the length of the lines, nor of the returns therefrom. A proposal is under consideration for the substitution of electric traction on these lines.

The Western Australian Government owns a line of horse tramway on a 2-foot gauge between Roeburne and Cossack, a length of  $8\frac{1}{2}$  miles, constructed at a cost of £24,022. For the year ended 30th June, 1904, the gross earnings were £2,192, and the working expenses £1,869, leaving a profit on working expenses of £323.

In Tasmania there is an electric tramway from Hobart railway station, about 9 miles in length, owned by a private company. The cost of construction and equipment was £95,015; and the company possesses 20 cars. For the year ended 31st December, 1903, the receipts amounted to £18,327, and the working expenses, to £12,519. The passengers carried during the twelve months ended 31st December, 1902, numbered 1,848,104. There is also a steam system at Zeehan, 2 miles in length, constructed at a cost of £5,388. No information is available as to the receipts, but the working expenses for the year ended 31st December, 1901, were £1,848. The number of passengers carried during the twelve months ended 31st December, 1902, was 7,302.

There are also tramways in existence in New Zealand under municipal and private management, but no particulars in regard to them are at present available.

## COMMONWEALTH FINANCE.

THE financial obligations of the Commonwealth began with the appointment of the Executive and the proclamation of the Constitution on the 1st January, 1901, at which date also the administration of the Customs passed over to the federal control. Besides the Customs and Excise, the Commonwealth has authority to take over from the states the administration of the following services, viz., posts, telegraphs, and telephones; naval and military defence; lighthouses, lightships, beacons and buoys; astronomical and meteorological observations; quarantine; census and statistics; bankruptcy and insolvency; patents and copyrights; naturalisation and aliens; divorce and matrimonial causes; and immigration and emigration.

In accordance with this power, the Postal Service was transferred to the Commonwealth on the 1st March, 1901, and on the same date the Defence Administration was taken over. The control of the Patents offices became vested in the Commonwealth from the 1st June, 1904. None of the other departments has yet been completely transferred.

The expenditure of the Commonwealth is divisible into new expenditure—that is to say, on services called into being after the proclamation of the Federal Union, and other expenditure, or expenditure on services previously existing. The new expenditure is charged to the states proportionately to their population, and the cost of transferred services over and above the revenue derived therefrom being ascertained, the total of the two amounts is deducted from the net revenue from Customs and Excise, and the balance handed back to the states.

Under the provisions of section 87 of the Constitution Act, the Treasurer of the Commonwealth is entitled to retain one-fourth of the net proceeds of Customs and Excise services for the purposes of defraying the expenses of the Commonwealth, the remaining three-fourths, and as much more as the Treasurer does not require, being handed back to the states. It is, therefore, very essential, in considering the question of Federal and State Finance, to remember that, so far as concerns three-parts of the net revenue derived from customs and excise, such revenue, though appearing in the receipts of the Commonwealth, is not within the disposal of Parliament, but must be returned to the states. A large amount, in a normal year estimated at from seven to seven and a half millions, appears first as a federal receipt and a federal expenditure, and again as received by the states. Therefore, in calculating the total sums raised by the Australian Governments, the amount returned to the states by the Federal Treasurer should be deducted from the total

receipts. It is necessary, however, that the whole transactions of the Federal Treasurer should be shown both as to revenue and expenditure; for, unless this is done, a proper understanding of federal and state accounts cannot be obtained.

The financial year of the Commonwealth ends on the 30th June. Since the 1st January, 1901, there have been four financial periods, the first being the six months, January to June, 1901, and the others embracing the three following years ending 30th June, 1902 to 1904. The first of these periods was quite abnormal: the transferred departments were not administered by the Commonwealth for the whole period, while in addition there were some exceptional expenses by reason of the federal elections, and the cost of establishing the Commonwealth itself; on the other hand, the federal departments were not organised, and cost less than in an ordinary year.

#### OPERATIONS FOR HALF-YEAR ENDED 30TH JUNE, 1901.

For the half-year ended 30th June, 1901, the following were the income and expenditure of the Treasurer:—

Income.		Expenditure.	
	£		£
Customs and Excise .....	4,150,589	New services of Commonwealth .....	131,255
Posts and Telegraphs .....	740,665	Customs and Excise collection .....	121,443
Other .....	4,502	Posts and Telegraphs .....	809,840
		Military and Naval .....	233,515
		Balance carried to following year .....	5,974
		Returned to States .....	3,593,729
	<u>£4,895,756</u>		<u>£4,895,756</u>

During this period the state tariffs existing at the establishment of the Commonwealth remained in force, the uniform customs tariff with the abolition of inter-state duties not coming into operation until some time later. The collections in each state were:—

State.	Half-year ended 30th June, 1901.				
	Taxation.		Posts and Telegraphs.	Other.	Total.
	Customs.	Excise.			
	£	£	£	£	£
New South Wales .....	820,012	198,996	276,936	1,019	1,296,963
Victoria .....	1,123,106	232,993	177,931	2,780	1,536,810
Queensland .....	643,059	67,771	95,586	301	806,717
South Australia .....	330,695	21,258	90,702	395	443,050
Western Australia .....	475,456	15,915	67,736	1	559,106
Tasmania .....	209,865	11,463	31,774	6	253,108
Total .....	<u>3,602,193</u>	<u>548,396</u>	<u>740,665</u>	<u>4,502</u>	<u>4,895,756</u>



The expenditure on account of new services distributed on a capita-  
tion basis, and the other expenditure chargeable to the states were as  
follows:—

State.	Expenditure during half-year ended 30th June, 1901.					Balance carried for- ward to fol- lowing year.	Total.
	New Expendi- ture.	Customs and Excise Collections.	Posts and Telegraphs.	Naval and Military.	Total.		
	£	£	£	£	£	£	£
New South Wales	47,806	29,005	262,086	70,743	409,639	Cr. 4,300	413,939
Victoria .....	41,056	32,645	208,177	77,143	360,026	Dr. 956	359,070
Queensland .....	17,031	27,944	129,368	49,666	224,029	Dr. 594	223,435
South Australia .....	13,088	11,666	71,080	18,606	111,379	Dr. 567	110,812
Western Australia .....	6,038	15,338	84,191	8,610	114,177	Cr. 4,070	113,247
Tasmania .....	6,436	4,865	54,018	11,743	77,062	Dr. 279	76,773
Total .....	131,255	121,443	809,840	233,515	1,296,053	Cr. 5,974	1,302,027

The difference between these figures and the amounts set out in the  
preceding table represents the payments which the states were entitled  
to receive under the provisions of section 87 of the Constitution Act,  
and the sums handed back to each were as shown below.

	£
New South Wales .....	833,273
Victoria .....	1,177,740
Queensland .....	583,282
South Australia .....	332,239
Western Australia .....	440,860
Tasmania .....	176,335

Total..... £3,593,729

The financial operations of the Commonwealth for its first half-year  
call for no special comment,—the payments made and the sources of  
income were in continuation of those of the states; no new sources of  
revenue were entered on by the Commonwealth, while the amount of  
new expenditure was comparatively small.

#### OPERATIONS FOR YEAR ENDED 30TH JUNE, 1902.

An entirely new set of conditions came into operation on the 9th  
October, 1901, when the schedule of uniform customs duties was  
promulgated. Under the new conditions the inter-state duties ceased,  
except, as will be hereafter explained, in the case of Western Australia.  
The federal customs and excise duties were in force for thirty-eight  
weeks and the state duties for fourteen weeks, while the Post Office and  
Defence Services were administered by the Commonwealth for the

whole year. The following is a statement of the transactions of the Federal Treasurer for the year :—

Income.		Expenditure.	
	£		£
Balance brought forward from 30th June, 1901 ...	5,974	New Services of Commonwealth .....	275,862
Customs and Excise .....	8,692,750	Customs and Excise collection .....	260,322
Posts and Telegraphs .....	2,372,861	Posts and Telegraphs .....	2,461,916
Customs collected on behalf of Western Australia ...	201,569	Military and Naval .....	934,646
Other revenue .....	29,805	Returned to States .....	7,368,137
		Balance carried forward to 1902-3 .....	2,076
Total .....	£11,302,959	Total .....	£11,302,959

The amount of revenue collected within each state was as shown in the following table. The Customs and Excise collections of Western Australia include £1,134,045 revenue from the Commonwealth tariff, and £201,569 from inter-state duties.

State.	Balance brought forward from previous year.	Collections during year ended 30th June, 1902.				
		Taxation.		Posts and Telegraphs.	Other Revenue.	Total.
		Customs.	Excise.			
	£	£	£	£	£	£
New South Wales...	Cr. 4,300	2,324,000	488,732	873,312	8,223	3,698,567
Victoria .....	Dr. 956	1,978,245	400,279	591,470	8,506	2,975,544
Queensland .....	Dr. 594	1,135,562	162,100	312,905	934	1,610,907
South Australia .....	Dr. 567	625,637	73,010	277,811	1,639	977,530
Western Australia...	Cr. 4,070	1,273,125	62,489	225,752	172	1,565,608
Tasmania .....	Dr. 279	335,401	37,739	91,611	10,331	474,803
Total .....	Cr. 5,974	7,669,970	1,224,349	2,372,861	29,805	11,302,959

The distribution of the expenditure between the states was as shown in the following table, the new expenditure as it is called being distributed amongst the states according to population, the other expenditure according to the states on behalf of which it was incurred :—

State.	Expenditure during year ended 30th June, 1902.					Balance carried forward to following year.	Total.
	New Expenditure.	Customs and Excise Collections.	Posts and Telegraphs.	Naval and Military.	Total.		
	£	£	£	£	£	£	£
New South Wales .....	99,252	63,450	840,685	309,147	1,312,534	Cr. 128	1,312,662
Victoria .....	87,194	63,812	588,888	316,876	1,056,770	Dr. 2300	1,054,570
Queensland .....	36,464	64,225	419,965	185,958	706,612	Dr. 478	706,134
South Australia .....	26,320	26,517	246,752	58,670	358,259	Cr. 3408	361,667
Western Australia .....	14,061	81,991	258,570	34,967	389,589	Cr. 912	390,501
Tasmania .....	12,571	10,327	107,066	29,023	158,987	Cr. 251	159,238
Total .....	275,862	260,322	2,461,916	934,646	3,932,746	Cr. 2076	3,934,822

The difference between the collections and disbursements by the Commonwealth on behalf of the states was returned to the latter, and the following sums represent the amount in each case:—

	£
New South Wales .....	2,385,904
Victoria .....	1,920,974
Queensland .....	904,775
South Australia .....	615,863
Western Australia.....	1,225,076
Tasmania .....	315,540
<b>Total.....</b>	<b>7,368,137</b>

#### OPERATIONS FOR YEAR ENDED 30TH JUNE, 1903.

The following statement indicates the transactions of the Federal Treasurer for the year ended 30th June, 1903:—

Income.	£	Expenditure.	£
Balance brought forward from 30th June, 1902...	2,076	New services of Commonwealth .....	315,564
Customs and Excise .....	9,451,588	Customs and Excise collection.....	272,622
Posts and Telegraphs .....	2,404,731	Posts and Telegraphs.....	2,563,617
Customs collected on behalf of Western Australia...	233,467	Military and Naval.....	746,526
Other revenue .....	16,152	Other expenditure .....	3,043
		Returned to States.....	8,200,457
		Balance carried forward to following year .....	6,185
<b>Total.....</b>	<b>£12,108,014</b>	<b>Total.....</b>	<b>£12,108,014</b>

The revenue collected within each state is set forth in the subjoined table. The Customs and Excise collections of Western Australia include £1,162,535 revenue from the Commonwealth tariff, and £233,467 from inter-state duties.

State.	Collections during year ended 30th June, 1903.					Total.
	Balance brought forward from previous year.	Taxation.		Posts and Telegraphs.	Other Revenue.	
		Customs.	Excise.			
	£	£	£	£	£	£
New South Wales	Cr. 128	2,861,710	617,032	906,798	5,479	4,391,147
Victoria .....	Dr. 2,200	2,096,318	402,696	622,701	5,406	3,124,921
Queensland .....	Dr. 478	1,042,188	218,746	300,737	2,119	1,563,312
South Australia...	Cr. 3,403	583,446	106,310	255,214	1,737	950,110
Western Australia	Cr. 942	1,317,770	78,232	225,244	717	1,622,905
Tasmania.....	Cr. 281	312,016	48,591	94,037	694	455,619
Total.....	Cr. 2,076	8,213,448	1,471,607	2,404,731	16,152	12,108,014

The distribution of the expenditure between the states was as shown in the following table, the new expenditure being distributed amongst the states according to population, the other or transferred expenditure to the states on behalf of which it was incurred :—

State.	Expenditure during year ended 30th June, 1903.						Balance carried forward to following year.	Total.
	New Expenditure.	Customs and Excise Collections.	Posts and Telegraphs.	Naval and Military.	Other.	Total.		
	£	£	£	£	£	£	£	£
New South Wales..	114,181	70,438	890,203	268,146	10	1,842,928	Dr. 4,914	1,338,014
Victoria .....	98,172	64,770	597,008	258,852	23	1,018,830	Cr. 641	1,019,471
Queensland .....	41,519	66,198	437,267	107,672	5	652,651	Cr. 5,416	658,077
South Australia .....	29,795	25,832	254,756	54,009	3,000	367,392	Cr. 3,789	371,181
Western Australia .....	17,524	34,740	280,304	32,471	..	365,039	Cr. 2,134	367,173
Tasmania .....	14,423	10,644	104,079	25,376	..	154,522	Dr. 881	153,641
Total .....	315,564	272,622	2,563,617	746,526	3,043	3,901,372	Cr. 6,186	3,907,557

The difference between the collections and disbursements by the Commonwealth on behalf of the states was returned to the latter, and the following sums represent the amount in each case :—

	£
New South Wales .....	3,053,133
Victoria .....	2,105,450
Queensland .....	905,235
South Australia .....	578,929
Western Australia .....	1,255,732
Tasmania .....	301,978
Total .....	8,200,457

#### OPERATIONS FOR YEAR ENDED 30TH JUNE, 1904.

The following statement shows the transactions of the Commonwealth Treasurer for the year ended 30th June, 1904 :—

Income.	£	Expenditure.	£
Balance brought forward from 30th June, 1903...	6,185	New services of Commonwealth .....	459,472
Customs and Excise .....	8,909,329	Customs and Excise collections .....	264,598
Posts and Telegraphs .....	2,510,264	Posts and Telegraphs .....	2,692,457
Customs collected on behalf of Western Australia ..	196,429	Military and Naval .....	836,005
Other revenue .....	15,034	Other expenditure .....	30
		Returned to States .....	7,382,460
		Balance carried forward to following year .....	2,219
Total ... ..	£11,637,241	Total .....	£11,637,241

The revenue collected within each state is set forth in the following table. The Customs and Excise collections of Western Australia include

£1,062,296 revenue from the Commonwealth Tariff and £196,429 from interstate duties.

State.	Balance brought forward from previous year.	To adjust the Expenditure made in 1901-2 and 1902-3 for new rifles.	Revenue collected within the years ended 30th June, 1904.				Total.
			Taxation.		Posts and Telegraphs.	Other Revenue.	
			Customs.	Excise.			
New South Wales.....	Dr. £ 4,914	Cr. £ 10,093	£ 2,604,049	£ 625,737	£ 941,529	£ 5,075	£ 4,181,569
Victoria .....	Cr. 641	Dr. 1,832	2,040,123	403,377	650,583	4,723	3,007,620
Queensland.....	Cr. 5,416	Cr. 2,127	897,786	233,975	324,009	2,975	1,466,288
South Australia.....	Cr. 3,789	Dr. 6,816	593,946	106,907	258,471	1,024	956,280
Western Australia ..	Cr. 2,134	Dr. 5,166	1,151,665	107,140	230,910	823	1,437,431
Tasmania .....	Dr. 881	Cr. 1,594	290,313	51,876	104,762	409	448,073
Total.....	Cr. 6,185	.....	7,577,746	1,528,012	2,510,264	15,034	11,637,241

The distribution of the expenditure between the states was, as shown in the following table, the new expenditure being distributed amongst the states according to population, the other or transferred expenditure to the states on behalf of which it was incurred :—

State.	Expenditure during the year ended 30th June, 1904.						Balance carried forward to following year.	Total.
	New Expenditure.	Customs and Excise Collections.	Posts and Telegraphs.	Naval and Military.	Other.	Interstate adjustment of duties on ships' stores. Period, 8th October, 1901, to 30th June, 1903.		
New South Wales ..	£ 167,007	£ 63,188	£ 960,172	£ 298,760	£ ..	Dr. £ 10,101	Cr. £ 2,925	£ 1,498,162
Victoria .....	£ 141,438	£ 66,736	£ 631,330	£ 258,494	£ 30	Cr. £ 3,639	Cr. £ 377	£ 1,094,816
Queensland.....	£ 60,818	£ 57,187	£ 434,103	£ 104,506	£ ..	Dr. £ 464	Dr. £ 1,145	£ 655,433
South Australia .....	£ 48,154	£ 25,091	£ 259,703	£ 76,611	£ ..	Cr. £ 3,526	Dr. £ 1,432	£ 399,511
Western Australia ..	£ 26,554	£ 36,494	£ 805,906	£ 56,520	£ ..	Cr. £ 3,285	Cr. £ 998	£ 422,187
Tasmania .....	£ 21,001	£ 9,902	£ 111,193	£ 42,115	£ ..	Dr. £ 185	Cr. £ 486	£ 184,682
Total.....	£ 450,472	£ 264,598	£ 2,692,457	£ 836,906	£ 30	.....	Cr. £ 2,219	£ 4,254,781

The difference between the collections and disbursements by the Commonwealth on behalf of the states was returned to the latter, the amounts in each case, being as follows :—

New South Wales .....	£2,683,417
Victoria .....	2,002,804
Queensland.....	810,855
South Australia .....	556,949
Western Australia .....	1,065,244
Tasmania .....	263,191
Total .....	£7,382,460

## PROBABLE REVENUE AND EXPENDITURE, 1904-5.

Sufficient time has elapsed since the settlement of the tariff to admit of the consumption of goods introduced into the Commonwealth in anticipation of the imposition of new or increased duties, and the passage of the Postal Act having brought about a uniform administration of postal and telegraph matters, the Federal Treasurer is in a position to forecast the probable revenue and expenditure for the year ending 30th June, 1905, with a reasonable assurance that the forecast will be realised. The following table indicates the revenue estimated to be received during the year :—

State.	Customs and Excise.	Posts and Telegraphs.	Other Revenue.	Total.
	£	£	£	£
New South Wales.....	3,160,000	935,000	6,900	4,101,900
Victoria .....	2,490,000	660,000	7,300	3,157,300
Queensland.....	1,115,000	324,000	3,300	1,442,300
South Australia.....	685,000	273,000	9,000	967,000
Western Australia .....	1,190,000	258,000	1,700	1,449,700
Tasmania .....	340,000	110,000	1,800	451,800
Total .....	£ 8,980,000	2,560,000	30,000	11,570,000

The expenditure that will probably be incurred during the same period is as follows :—

State.	New Expendi- ture.	Customs and Excise Collection.	Posts and Telegraphs.	Naval and Military.	Mis- cellaneous.	Total.
	£	£	£	£	£	£
New South Wales .....	301,639	74,022	896,883	250,543	...	1,523,687
Victoria .....	250,816	66,579	624,032	245,350	36	1,186,813
Queensland .....	108,247	52,014	422,890	118,512	...	701,663
South Australia .....	76,647	26,197	249,577	62,738	...	415,159
Western Australia .....	50,411	35,292	284,163	44,573	...	414,439
Tasmania .....	37,293	9,974	112,815	31,390	...	191,472
Total .....	£ 825,053	264,678	2,590,360	753,106	36	4,433,233

The probable return to the states, after adding or deducting the balance brought forward from 1903-4, will, therefore, be—

New South Wales.....	£2,581,138
Victoria .....	1,970,864
Queensland .....	739,492
South Australia .....	550,419
Western Australia .....	1,036,259
Tasmania .....	260,814
Total .....	£7,138,986

The proportions of estimated revenue and expenditure borne by each state, are shown in the following table :—

State.	Estimated Revenue, 1904-5.		Estimated Expenditure, 1904-5.	
	Amount.	Proportion to Total.	Amount.	Proportion to Total.
	£	per cent.	£	per cent.
New South Wales.....	4,101,900	35·45	1,523,687	34·37
Victoria .....	3,157,300	27·29	1,186,813	26·77
Queensland.....	1,442,300	12·47	701,663	15·83
South Australia.....	987,000	8·36	415,159	9·36
Western Australia .....	1,449,700	12·53	414,439	9·35
Tasmania .....	451,800	3·90	191,472	4·32
Total .....	11,570,000	100·00	4,433,233	100·00

The proportions of population in each state to the total Commonwealth population, are—New South Wales, 36·56 per cent. ; Victoria, 30·40 ; Queensland, 13·12 ; South Australia, 9·29 ; Western Australia, 6·11 ; and Tasmania, 4·52. It will be seen that Western Australia alone has a revenue in excess of the proportion indicated by its population.

The financial working of the Commonwealth for the three complete years of its operations and the Treasurer's estimate for 1904-5 are outlined by the following tables :—

## REVENUE.

Year ended 30th June.	From Customs and Excise.	From Posts and Telegraphs.	From other Sources.	Total.
	£	£	£	£
1902 .....	8,894,319	2,372,861	29,805	11,296,985
1903 .....	9,685,055	2,404,731	16,152	12,105,938
1904 .....	9,105,758	2,510,264	15,034	11,631,056
1905 (estimate) ...	8,980,000	2,560,000	30,000	11,570,000

## EXPENDITURE.

Year ended 30th June.	On Transferred Services.	New Services of Commonwealth.	Return to States.	Total.
	£	£	£	£
1902 .....	3,656,884	275,862	7,368,137	11,300,883
1903 .....	3,585,808	315,564	8,200,457	12,101,829
1904 .....	3,793,090	459,472	7,382,460	11,635,022
1905 (estimate) ...	3,608,180	825,053	7,138,986	11,572,219

The difference between the total revenue and expenditure represents small sums to be carried forward into next year's transactions.

The chief matter that calls for remark in these statements is the large increase in the expenditure on new services of the Commonwealth. The expenditure proposed for 1905 is £825,053, an increase of £365,581 over that of the previous year, and £509,469 over that of 1903. This increase is chiefly due to the determination of Parliament that public works should be constructed out of revenue, and the

proposed expenditure for 1905 includes the sum of £404,240 for various public works, the corresponding figures for previous years being

1901-2 .....	£1,971
1902-3 .....	6,622
1903-4 .....	20,859

In addition to the amounts set out above against each of the years specified there was in 1901-2 a sum of £94,564, in 1902-3, £157,816, and in 1903-4, £304,150 representing expenditure incurred in connection with new works and buildings, such amounts being debited to the respective States in which the money was expended.

#### CUSTOMS AND EXCISE.

The customs and excise collections during the year ended 30th June, 1901, were under divided control. From the 1st July, 1900, to the 31st December of that year, the collections were made by the state Governments, and for the latter half of the financial year, the administration was carried out by the Commonwealth Government. During the whole period the tariffs existing in the various states at the time of their union remained in force, and afforded no indication of the revenue likely to be received under a uniform tariff. Nor did the collections for the year ended 30th June, 1902, settle satisfactorily this important question. In the first place three months of the twelve were under state tariffs and inter-state duties, and secondly, in some of the states it is believed that there were large importations in anticipation of the federal tariff affecting goods then free or subject to low duties. During the passage of the tariff through Parliament, material alterations were made in the rates proposed, and on that account also the revenue received gives no exact indication of the possibilities of the tariff as a revenue-producing instrument.

The following table shows the customs and excise collections for the years ended 30th June, 1902, 1903, and 1904, with the amounts collected in each state, and the average per inhabitant:—

State.	Year ended 30th June, 1902.		Year ended 30th June, 1903.		Year ended 30th June, 1904.	
	Amount Collected.	Average per Inhabitant.	Amount Collected.	Average per Inhabitant.	Amount Collected.	Average per Inhabitant.
	£	£ s. d.	£	£ s. d.	£	£ s. d.
New South Wales..	2,812,732	2 0 11	3,478,742	2 9 8	3,229,796	2 5 3
Victoria.....	2,376,524	1 19 4	2,499,014	2 1 6	2,443,505	2 0 5
Queensland .....	1,297,662	2 11 4	1,261,066	2 9 6	1,131,761	2 3 11
South Australia ...	698,647	1 18 4	689,727	1 17 9	699,792	1 17 11
Western Australia	1,134,045	5 16 5	1,162,530	5 8 1	1,062,236	4 13 7
Tasmania .....	372,146	2 2 10	369,607	2 0 9	342,189	1 18 2
Total .....	£ 8,692,750	2 5 6	9,451,686	2 8 10	8,909,329	2 5 5

In addition to the amount set down in the foregoing table as collected in Western Australia during the year ended 30th June, 1902, a sum of



£301,569 was received by the Customs Department on interstate goods taxable under the special Western Australian tariff. For the year ended 30th June, 1903, the amount received on inter-state goods and on foreign goods taxed at a higher rate under that tariff than under the Federal tariff was £233,467. The amount received under the special Western Australian tariff for the year ended 30th June, 1904, was £196,429. Under the provisions of the 95th section of the Commonwealth of Australia Constitution Act, Western Australia is empowered for the first five years after the imposition of a uniform tariff to impose duties on goods passing into that state and not originally imported from beyond the limits of the Commonwealth. The duty so imposed on any goods, however, is not to exceed, during the first of such years, that chargeable under the law of Western Australia in force at the imposition of uniform duties, and shall not exceed during the second, third, fourth, and fifth of such years respectively, four-fifths, three-fifths, two-fifths, and one-fifth of such latter duty. This special tariff therefore ceases on the 9th October, 1906. If the collections for the year ended 30th June, 1902, had been included, the total revenue for the Commonwealth would have been £8,894,319, and for Western Australia £1,335,614, equal in the former case to £2 6s. 6d. per inhabitant, and in the latter to £6 17s. 1d. Taking into consideration these collections for the year ended 30th June, 1903, the total revenue for the Commonwealth would have been £9,685,153, and for Western Australia £1,395,997, or in the former case equal to £2 10s., and in the latter £6 9s. 9d. per inhabitant. The addition of the collections under the special Western Australian tariff to those under the Commonwealth tariff would give a total revenue for the Commonwealth, from this source of taxation, of £9,105,758, and for Western Australia £1,258,725; in the former case equal to £2 6s. 5d., and in the latter £5 10s. 11d. per inhabitant.

In his financial statement made in October, 1904, the Federal Treasurer estimated the revenue that may be expected from duties of customs and excise during the financial year ending 30th June, 1905, at £8,840,000. Excluding the receipts from the special Western Australian tariff, calculated to yield £140,000, the estimated collections in each state are as follows:—

State.	Estimated Net Revenue from Customs and Excise for year ending 30th June, 1905.
	£
New South Wales .....	3,160,000
Victoria .....	2,490,000
Queensland .....	1,115,000
South Australia .....	685,000
Western Australia .....	1,050,000
Tasmania .....	340,000
Total .....	£ 8,840,000

Grouping the receipts according to the divisions of the tariff, the estimated return under each head will be—

Estimated Revenue, 1904-5.

Customs—	£	Customs—	£
Stimulants .....	2,080,000	Paper and stationery...	106,000
Narcotics .....	980,800	Vehicles .....	78,000
Sugar .....	268,700	Musical instruments ...	47,500
Agricultural products		Miscellaneous receipts,	
and groceries .....	737,400	including licenses ...	125,500
Apparel and textiles ...	1,274,500		
Metals and machinery	473,500	Total Customs.....	7,031,000
Oils, paints, and var-		Excise .....	1,759,000
nishes .....	127,000		
Earthenware, &c. ....	146,500	Total collections...	8,790,000
Drugs and chemicals ...	58,500	Transfer of Sugar	
Wood, wicker, and cane	201,600	Duty from Trust	
Jewellery and fancy		Fund .....	50,000
goods.....	169,500		
Leather and rubber ...	156,000		£8,840,000

The item £50,000, "Transfer of Sugar Duty from Trust Fund," appearing in the foregoing table requires explanation. The sum is not an amount to be received during 1904-5, but is now for the first time brought to account. When the Federal tariff was imposed a difference of opinion arose between the Colonial Sugar Refining Company and the Customs Department as to whether certain sugar was liable to duty or not. The amount in question in Victoria was £11,000, and as the sugar was not all withdrawn from bond at one time it was decided that the excise collections should be paid to a trust account pending a determination of the matter. This course was followed, and a sum of £60,962 was accumulated, an amount greater than what was in dispute. The Treasurer now proposes to pay to the state the sum in hand in excess of £11,000, and in order to do this the amount to be handed back will be paid first to the revenue fund and then transferred to the state to which it belongs. The item of £50,000 appearing as estimated revenue for 1904-5 is, therefore, a purely formal entry.

The foregoing estimated revenue is equal to £2 4s. 5d. per inhabitant, the rates for each state being :—

	£	s.	d.
New South Wales.....	2	3	5
Victoria .....	2	1	2
Queensland .....	2	2	9
South Australia .....	1	17	0
Western Australia .....	4	6	5
Tasmania .....	1	17	9
Commonwealth .....	£2	4	5

If the yield from its special tariff had been included the rate for Western Australia would be £4 17s. 11d., and for the Commonwealth, £2 5s. 1d. Western Australia stands far above any of the other states in regard to revenue per inhabitant, and in total revenue it exceeds Tasmania and South Australia, and approximates Queensland. This position it owes to the consuming power of its population, which consists very largely of adult males receiving higher wages than those paid in any other state.

The proportion in which the various states have contributed, and may be expected to contribute to the Commonwealth tariff, is a question of much interest, as under the book-keeping provisions of the Constitution the return to be made to each state depends upon its contribution to the revenue. The following is a statement of the proportions of customs and excise collected in each state for the nine months of the financial year 1902 during which the uniform tariff was in operation, the proportions for the years ended June, 1903, and June, 1904, and the proportions estimated by the Treasurer for the year ending June, 1905; in order to throw further light on the question, the proportion of population in each state to the total population of the Commonwealth is also given.

State.	Proportion of—				
	Population, 31st Dec., 1904.	Customs and Excise Revenue raised, 9 months ended 30th June, 1902.	Customs and Excise Revenue raised for year ended 30th June, 1903.	Customs and Excise Revenue raised for year ended 30th June, 1904.	Customs and Excise Revenue estimated for year ending 30 June, 1905.
	per cent.	per cent.	per cent.	per cent.	per cent.
New South Wales	36.56	35.31	36.81	36.25	35.75
Victoria .....	30.40	25.05	26.44	27.43	28.17
Queensland .....	13.12	14.62	13.33	12.70	12.61
South Australia ...	9.29	7.67	7.30	7.86	7.75
Western Australia	6.11	13.18	12.30	11.92	11.88
Tasmania .....	4.52	4.17	3.82	3.84	3.84

The chief element in determining the amount of revenue to be raised by the Commonwealth was the necessities of the various states, and so long as these necessities exist, a sum approximating to what is now obtained will need to be raised. It can hardly be supposed, however, that Australia will long continue to raise as large a revenue as £2 4s. 5d. per inhabitant from a customs tariff containing so large a free list, embracing as it does imports amounting to £10,380,000 out of a total import of general merchandise of £36,244,000.

Although indirectly connected with the question of the Commonwealth tariff, the returns obtained in past years from customs and excise

by the states under their local tariffs are worth recording. It will be found from a consideration of the subsequent tables that the rate per inhabitant has varied greatly, not only as regards the different states but for the same state in different years. This variation arises from diverse causes. First, the influence of good or bad seasons on the producing power of the people is directly felt in the customs collections. Certain states, notably Queensland and Western Australia, and until recently New South Wales, grow insufficient agricultural produce for their own requirements, and in times past a good season—since it enabled those states to depend to a greater extent on their own resources—meant a decrease in the revenue from the importation of agricultural produce. Similar effects have also been felt in regard to revenue derived from live stock and other forms of produce. In addition, it must be remembered that for many years the states have been systematic borrowers from the London market, while they have been the recipients of much money sent for investment by private persons. As loans of all descriptions reach the borrowing country in the form of goods, and a considerable proportion of the importations is the subject of taxation, years of lavish borrowing are naturally years of large revenue collections, and coincident with the cessation of a flow of foreign capital there is a decrease in customs revenue. Furthermore, there have been extensive alterations in the tariffs affecting the revenue during the years which the following table covers. In New South Wales, in 1891 and 1895, and in Western Australia, in 1893 and 1896, radical tariff changes were made, and in other years minor alterations took place in nearly all the other states. To these latter changes is chiefly attributable any sharp rise or fall in the rate of revenue per inhabitant. Speaking generally the customs revenue per inhabitant has tended to decline, especially when the tariffs are high, unless adjusted from time to time to meet the decline, for, apart from the specific causes mentioned above, other effective, if less obtrusive, influences are at work. Year by year the industries of the states are being developed, and the local producer is acquiring a firm hold on the domestic markets. Except in drought years little revenue will be received from duties on agricultural produce, as such produce will not be imported from abroad, and many descriptions of manufactured goods have likewise ceased to be introduced, the locally-made article being produced in sufficient quantities to meet the demand. There can be no reasonable doubt that this tendency will be still more marked in the future; and it is, therefore, not surprising that Australasian Treasurers have of late years found it necessary to look to other sources than the customs for the revenue necessary to carry on the business of the country, and under the Commonwealth, with complete interstate freetrade and growing manufactures, this necessity will be greatly accentuated.

The amount of import and excise duties collected in the various states during each of the last fourteen years is set forth in the following

table—drawbacks and refunds being deducted from the gross collections of those states for which such information can be obtained :—

State.	1891.	1892.	1893.	1894.	1895.	1896.	1897.
	£	£	£	£	£	£	£
New South Wales .....	2,417,673	2,865,112	2,328,274	2,265,058	2,240,596	1,637,078	1,530,116
Victoria .....	2,609,551	2,318,218	1,887,474	2,045,853	2,021,564	2,060,880	2,025,896
Queensland .....	1,241,447	1,155,695	1,099,450	1,146,260	1,296,883	1,320,247	1,244,566
South Australia .....	647,263	611,723	546,006	539,863	551,103	613,190	612,323
Western Australia .....	233,777	271,376	254,095	409,886	614,457	988,829	1,062,026
Tasmania .....	392,457	326,034	303,682	290,661	322,755	347,925	370,312
Commonwealth... £	7,443,168	7,568,163	6,418,961	6,706,676	7,045,858	6,967,668	6,895,278

State.	1898.	1899.	1900.	1901 (Half-year).	1901-2.	1902-3.	1903-4.
	£	£	£	£	£	£	£
New South Wales .....	1,551,827	1,650,333	1,778,903	1,019,003	2,812,732	3,478,742	3,239,796
Victoria .....	2,217,541	2,224,811	2,320,555	1,356,099	2,876,524	2,499,014	2,443,506
Queensland .....	1,418,941	1,568,744	1,565,838	710,830	1,297,662	1,261,066	1,181,761
South Australia .....	618,430	641,181	639,005	351,953	698,647	699,727	699,792
Western Australia .....	906,831	859,915	976,411	491,371	1,335,614	1,395,967	1,258,725
Tasmania .....	426,799	447,036	490,921	221,323	373,140	360,607	342,189
Commonwealth... £	7,140,299	7,892,020	7,770,723	4,150,580	8,894,319	9,685,153	9,105,768

The revenue from import and excise duties per head of population probably offers more food for reflection than the figures in the table just given. New South Wales raised the smallest revenue compared with population of any of the states until 1891, a circumstance due to the comparatively low rate of the tariff; in 1892 its collections were about the average for Australasia; but at the beginning of 1896 a new tariff came into force which was designed to make the ports of the state free to all imports except narcotics and stimulants, and, although this intention was not fully carried out, yet the revenue per head of population was, until the introduction of the Commonwealth tariff, very considerably less than in any of the other states. The variations in the rates from year to year are interesting as illustrating the force of the remarks made a few pages back in introducing the subject of customs duties.

State.	1891.	1892.	1893.	1894.	1895.	1896.	1897.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
New South Wales .....	2 2 4	2 8 8	1 13 8	1 16 11	1 15 10	1 5 9	1 3 7
Victoria .....	2 3 10	1 19 10	1 12 2	1 14 8	1 14 2	1 14 8	1 14 4
Queensland .....	3 2 7	2 17 2	2 13 2	2 14 2	2 19 7	2 19 8	2 14 8
South Australia .....	2 0 3	1 17 2	1 12 3	1 11 3	1 11 7	1 14 11	1 14 10
Western Australia .....	4 13 6	4 17 0	4 2 2	5 11 5	6 14 1	8 5 4	7 1 8
Tasmania .....	2 13 1	2 4 7	2 0 5	1 19 7	2 2 0	2 4 3	2 5 10
Commonwealth... £	2 6 5	2 6 1	1 13 5	1 19 5	2 0 8	1 19 6	1 13 1

State.	1898.	1899.	1900.	1901 (Half-year).	1901-2.	1902-3.	1903-4.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
New South Wales..	1 3 8	1 4 9	1 6 8	0 14 11	2 0 11	2 9 8	2 5 3
Victoria .....	1 17 6	1 17 6	1 18 11	1 2 8	1 19 4	2 1 6	2 0 5
Queensland .....	3 0 11	3 5 10	3 3 10	1 8 6	2 11 4	2 9 6	2 3 11
South Australia ..	1 15 0	1 15 11	1 15 6	0 19 6	1 18 4	1 17 9	1 17 11
Western Australia	5 9 11	5 1 5	5 11 2	2 14 7	6 17 1	6 9 10	5 10 11
Tasmania .....	2 11 5	2 12 6	2 16 9	1 5 7	2 2 10	2 0 9	1 18 2
Commonwealth £	1 19 2	2 0 0	2 1 6	1 2 0	2 6 5	2 10 0	2 6 5

The proportion of the cost of collection of customs and excise duties to the total amount received is less under the Commonwealth than under the separate control of the states. The experience of the five years immediately preceding federation shows that an average of 3·34 per cent. was expended, as against an average of 2·96 per cent. for the three-and-a-half years since the control of the customs and excise was vested in the Commonwealth Government. The average percentages for each state for the five years previous to federation were as follows:—New South Wales, 3·26; Victoria, 3·07; Queensland, 3·91; South Australia, 4·31; Western Australia, 3·28; and Tasmania, 1·96. For the period subsequent to the consummation of federation, the percentages are, New South Wales, 2·28; Victoria, 2·71; Queensland, 4·97; South Australia, 3·74; Western Australia, 2·67; and Tasmania, 2·84. The proportion of cost to total amount collected has been reduced under Commonwealth control in the states of New South Wales, Victoria, South Australia and Western Australia, and increased in Queensland and Tasmania.

#### POSTS AND TELEGRAPHS.

The administration of the Post and Telegraph services was undertaken by the Commonwealth on the 1st March, 1901; the departments consequently were under state direction for a period of eight months in the year ended 30th June, 1901. In discussing the question of the revenue derived from these services, it must be borne in mind that the taking over of the administration by the Commonwealth made no immediate change in the management, which was conducted as if the six states were separate systems. On the coming into operation of the Commonwealth Postal Act on 1st November, 1902, a uniform system was introduced, but the finances of the postal service before that date

remained unaffected. In the following table is set out the revenue derived during each of the last four financial years :—

State.	Year ended 30th June, 1901.	Year ended 30th June, 1902.	Year ended 30th June, 1903.	Year ended 30th June, 1904.
	£	£	£	£
New South Wales .....	833,942	873,312	906,798	941,529
Victoria .....	588,366	591,470	622,501	650,583
Queensland .....	309,170	312,905	300,724	324,009
South Australia .....	274,012	277,811	255,480	258,471
Western Australia .....	210,127	225,752	225,099	230,910
Tasmania .....	104,325	91,611	94,048	104,762
Total .....	£ 2,319,942	2,372,861	2,404,650	2,510,264

The expenditure during the same periods is shown in the subjoined table :—

State.	Year ended 30th June, 1901.	Year ended 30th June, 1902.	Year ended 30th June, 1903.	Year ended 30th June, 1904.
	£	£	£	£
New South Wales .....	789,290	840,685	890,618	952,044
Victoria .....	514,964	588,888	596,810	632,965
Queensland .....	376,186	419,965	437,266	434,778
South Australia .....	223,318	246,752	254,808	260,186
Western Australia .....	255,513	258,570	280,171	306,204
Tasmania .....	106,830	107,056	104,116	111,428
Total .....	£ 2,266,101	2,461,916	2,563,789	2,697,605

The operations of the past year show an apparent deficiency of £187,341 in the working of the Post and Telegraph Department. The financial position of the postal service, however, cannot be correctly stated unless the interest on the capital cost of the land, buildings, plant and appliances existing at the time of transfer to the Commonwealth, be taken into account. This cost has been variously estimated at from £7,312,000 to £7,514,000, and if an interest payment of £3.61 per annum be charged to the postal service, the transactions would show a net loss of nearly £455,000. The revenue and expenditure of the Post and Telegraph Department for the year ending 30th June 1905, is estimated by the Treasurer to be, approximately, as follows :—

State.	Revenue.	Expenditure.
New South Wales .....	£935,000	£896,863
Victoria .....	660,000	624,032
Queensland .....	324,000	422,890
South Australia .....	273,000	249,577
Western Australia .....	258,000	284,163
Tasmania .....	110,000	112,815
Total .....	£2,560,000	£2,590,360

These figures indicate a probable loss of £30,360 on the operations of the year, not including a proposed expenditure of £224,207, for works and buildings proposed to be constructed during the year, the expense of which is charged against the new services of the Commonwealth. From all the states an increased revenue is expected. A considerable falling off in the receipts from South Australia occurred during the two years ended June, 1903; this was due to the fact that alterations, by way of reduction in the terminal and other charges in connection with the Eastern Extension Cable Company's business, were not compensated for by new business. Losses in connection with the Pacific cable also increased the expenditure of the Department.

#### EFFECT OF FEDERATION ON STATE FINANCE.

The question of the effect which the operations of the Commonwealth may have upon the finances of the states is of great moment, and one which will not lessen in importance with the passage of time. That the finances of the states are in a disturbed state is evident from the fact that increased taxation and drastic retrenchment are being carried out, or are contemplated, in several of the states, while some show large deficits on the year's transactions. This financial disturbance has not, however, in all cases any connection with the management by the Commonwealth of the customs, excise, post office, and other transferred services.

The following statement gives the excess of revenue over expenditure from transferred services for the three years immediately preceding federation and for the last financial year, as well as the sums returned to the various states during the last-named period.

State.	Excess of Revenue over Expenditure on transferred services. Average 1898-1900 (three years).	Excess of Revenue over Expenditure on transferred services, 1903-4.	New Expenses of Commonwealth.	Sums returned to States, 1903-4.
	£	£	£	£
New South Wales.....	1,380,488	2,842,376	167,007	2,683,417
Victoria .....	2,073,799	2,128,808	141,438	2,002,804
Queensland.....	1,274,972	856,002	60,318	810,855
South Australia.....	616,191	593,985	43,154	556,969
Western Australia.....	837,225	1,069,834	26,554	1,065,244
Tasmania.....	403,650	282,234	21,061	263,191

It is clear from the proceedings of the Federal Convention, which prepared the draft of the existing Constitution of the Commonwealth, that it was universally conceded that each state joining the federation would be called upon to bear the new expenses of the Commonwealth



in addition to any expenditure then existing ; so that to determine the influence of federation upon the finances of the various states, a comparison might very well be restricted to the figures contained in the second and third columns of the preceding table. Without insisting, however, upon this point, if the sums returned to the states during the last financial year be compared with the average excess of revenue over expenditure on transferred services during the three years immediately preceding federation, the following results are obtained :—

State.	Return during the financial year ending 30th June, 1904, compared with excess of Revenue over Expenditure in the years preceding federation.	
	Excess.	Deficiency.
	£	£
New South Wales .....	1,302,929	.....
Victoria .....	.....	70,995
Queensland .....	.....	464,017
South Australia .....	.....	59,242
Western Australia.....	228,019	.....
Tasmania .....	.....	140,459

In two cases, those of New South Wales and Western Australia, the return now received is considerably greater than the average of the period immediately preceding federation ; the effect of federation on the finances of these states has, therefore, been beneficial. As regards Victoria, the deficiency on the revenue now received is less than the new expenses of federation chargeable to that State ; in South Australia the excess is very little greater than these new expenses, and it may, therefore, be considered that the disturbing effect of federation upon the finances of these states has been no greater than could reasonably have been expected. The cases of Queensland and of Tasmania are in another category, the disturbance to the finances of each state being very considerable. The cause of this disturbance is not very far to seek. Prior to the establishment of the Commonwealth, the State of Tasmania levied duties equivalent to 24·2 per cent. ad valorem on 91 per cent. of its total imports ; this is equivalent to 22 per cent. ad valorem on all goods other than narcotics and stimulants, which were subject to specially high duties. The free list of the Commonwealth extends to about 30 per cent. of the merchandise imported, and the average range of duties, excluding narcotics and stimulants, is 19·1 per cent. ad valorem, or, reckoning on all merchandise imported, excluding, of course, narcotics and stimulants, 13·4 per cent., that is to say, about three-fifths the rate imposed by Tasmania before federation. To this must be added the fact that Tasmania levied duties on intercolonial produce at the same rates as on foreign produce, and from such duties obtained a revenue of £76,829.

In Queensland, the rate of duty on all imports, other than narcotics and stimulants, averaged, before the establishment of federation, about 14 per cent., as compared with 13·4 per cent. levied by the Commonwealth. The loss of revenue due to a change in the rate of customs duties on oversea imports has not, therefore, been of much consequence, as the present condition of Queensland revenue has been brought about by a decline in general imports resultant on a falling off in the purchasing power of the people of the state and the cessation of Government borrowing,—matters entirely unconnected with federation. There has, of course, been a considerable loss of revenue by the abolition of duties on interstate produce; these duties, prior to federation, yielded a revenue of about £144,000 a year, which was a considerable sacrifice out of a total of a million and a quarter.

Section 87 of the Constitution of the Commonwealth provides that during a period of ten years after the establishment of the Commonwealth, and thereafter until the Parliament otherwise provides, of the net revenue of the Commonwealth from duties of customs and of excise, not more than one-fourth shall be applied annually by the Commonwealth towards its expenditure.

The meaning of the term "net revenue" has not yet been authoritatively decided, but it is a probable opinion that the term represents the total receipts less the cost of collection and the amount of drawbacks and refund of revenue. It is interesting to see how this limitation of expenditure has operated. The following statement shows the net revenue of the Commonwealth from customs and excise, and the amount returned to the various states for each of the last three years, and also the Treasurer's estimate for the financial year ending June, 1905.

Year.	Net collections, Customs and Excise.	Amount returned to States.	Proportion of total returned.
	£	£	per cent.
1901-2 .....	8,894,319	7,368,137	82·84½
1902-3 .....	9,685,064	8,200,457	84·67
1903-4 .....	9,108,813	7,382,460	81·05
1904-5 ..	8,980,000	7,138,986	79·50

It will be observed that in no year has the proportion which the Commonwealth is entitled to retain from the net revenue of customs and excise been closely approached. In the year ending June, 1905, however, owing to the appropriation of the sum of £404,240 out of revenue for the construction of public works, a very much nearer approach will be made by the Commonwealth to the limits of expenditure assigned to it by the Constitution. The Treasurer estimates that his net receipts from customs and excise will be £8,840,000, and the return to the different states £6,998,986, which represents a total of

79·2 per cent. of net receipts, so that the sum retained by the Commonwealth will be 20·8 per cent., but even in this instance the amount handed over by the Treasurer to the states will represent £602,494 in excess of the three-fourths which must be paid under Section 87 of the Constitution Act. The minimum prescribed by the Constitution to be paid back to the states has been interpreted as applying to the states as a whole, and not to the individual members of the Commonwealth; any other interpretation would probably have thrown the finances of the Commonwealth into confusion, as it would have been impossible, in any year, to have given back to Queensland 75 per cent. of the net revenue from customs and excise, and at the same time have met the obligations of that state on account of transferred services. Nevertheless, it is interesting to note what proportion of the net revenue raised in each state has been returned to it, and how much was paid by the Federal Treasury for the general purposes of the Commonwealth. This information the following table affords. The revenue of Western Australia from duties on interstate produce has been left out of consideration, as such is not Commonwealth revenue properly so-called, being a temporary expedient terminating in October, 1906.

State.	1901-2.			1902-3.		
	Net Revenue, Customs and Excise.	Revenue returned to States.	Percentage returned.	Net Revenue, Customs and Excise.	Revenue returned to States.	Percentage returned.
	£	£	%	£	£	%
New South Wales ...	2,812,731	2,385,904	84·86	3,478,747	3,053,133	87·76
Victoria .....	2,378,524	1,920,974	80·83	2,499,014	2,105,450	84·25
Queensland .....	1,297,663	904,775	69·72	1,260,934	905,235	71·79
South Australia .....	698,647	615,868	88·15	689,760	578,929	83·93
Western Australia ...	1,134,045	1,023,507	90·25	1,162,535	1,022,265	87·93
Tasmania .....	373,140	315,540	84·56	360,607	301,978	83·74
Commonwealth...	8,692,750	7,166,568	82·44	9,451,597	7,966,990	84·29

State.	1903-4.			1904-5 (Estimate).		
	Net Revenue, Customs and Excise.	Revenue returned to States.	Percentage returned.	Net Revenue, Customs and Excise.	Revenue returned to States.	Percentage returned.
	£	£	%	£	£	%
New South Wales ...	3,221,121	2,683,417	83·30	3,160,000	2,581,138	81·68
Victoria .....	2,447,152	2,002,804	81·84	2,490,000	1,970,864	79·15
Queensland .....	1,132,894	810,855	71·57	1,115,000	739,492	66·32
South Australia .....	703,618	556,949	79·15	685,000	550,419	80·35
Western Australia ...	1,065,592	868,815	81·53	1,050,000	896,259	85·26
Tasmania .....	342,007	263,191	76·95	340,000	260,814	76·71
Commonwealth...	8,912,384	7,186,031	80·63	8,840,000	6,998,986	79·17

As pointed out in the chapter dealing with "State Finance," the Treasurers of the states are seeking, by means of retrenchment and increased taxation, to balance their accounts. It is well, perhaps, that this resolution has been taken, for a little consideration will show that it is idle, so far as concerns some of the states, to expect a return from the Commonwealth equal to satisfying their needs on the basis of this present expenditure. The following would need to be the amount of customs and excise duties to be levied by the Commonwealth to enable each state to receive back sufficient to balance its finances as on the 30th June, 1904. In order to illustrate the measure of responsibility to be attached to the states, a column has been added showing the customs and excise revenue that would have sufficed had their requirements been not greater than in 1899:—

State.	Customs and Excise revenue required, so that the return to each State would be sufficient to balance its expenditure.	
	On the basis of 1899.	On the basis of 1904.
	£	£
New South Wales .....	5,031,000	9,106,000
Victoria .....	8,311,000	7,456,000
Queensland .....	11,418,000	9,007,000
South Australia .....	9,537,000	10,680,000
Western Australia .....	7,457,000	9,982,000
Tasmania .....	10,203,000	9,474,000

It will thus be seen that whereas a tariff from which £7,456,000 is obtainable would, at the present time (1904), satisfy the requirements of the Victorian Treasurer, it would take one yielding £10,680,000 to satisfy South Australia, the other states occupying positions at various intervals between these extremes. The most remarkable feature of the table is the position of New South Wales. Five years ago there was much talk about the surplus revenue of that state being needed to make up the requirements of the so-called necessitous states. At the present time the revenue necessities of the mother state place a demand on the Commonwealth above that of some of the other states, and very little short of the requirements of the state standing most in need of revenue.

It will have been observed from a previous table in this chapter, and in the part of this volume dealing with State Finance, that the requirements of the state Treasurers vary greatly from year to year; it would be hopeless, therefore, for the Commonwealth Treasurer to endeavour to adjust his revenue to the needs of any state; still more hopeless would it be for him to attempt to mould his revenue to suit the variations in the requirements of six states. Hence the obvious policy of fixing a reasonable sum to be raised through the Customs

House, and allowing the states to adjust their incomes and expenditures to the revenue thus provided.

The question of taking over the whole or part of the state debts by the Commonwealth has been much discussed from time to time, and is a matter of considerable importance. The debts of the states consist of their obligations in regard to debentures, inscribed stock, and treasury bills, as well as the debts on a loan or consolidated revenue account. Confining attention solely to the part of the obligations of the states for which debentures, stock, or treasury bills have been issued, the following is a statement of the gross amount of the public debt of each state, the interest charge thereon, and the balance of Commonwealth revenue which the Treasurer estimates he will return to the states during the year 1905. It will be seen that in the cases of Victoria and Western Australia alone are the returns sufficient to cover the interest payments. In regard to New South Wales the excess of state charges over the balance of revenue returnable to the state amounts to £260,230. In Queensland the excess is £807,978, in South Australia £518,906, and in Tasmania £80,813.

State.	Public Debt— Debentures, Inscribed and Funded Stock, and Treasury Bills.	Interest charge on Public Debt.	Balance of Commonwealth Revenue estimated to be returned to the States Governments.
	£	£	£
New South Wales .....	80,033,581	2,841,368	2,581,128
Victoria .....	51,819,962	1,885,983	1,970,864
Queensland .....	41,781,287	1,547,470	739,492
South Australia .....	28,593,645	1,069,325	550,419
Western Australia .....	16,090,288	547,160	1,036,259
Tasmania .....	9,318,400	341,627	260,814
Total .....	227,637,163	8,232,933	7,138,986

The foregoing figures give the total debts of the states represented by debentures, stock or treasury bills as on the 1st July, 1904, but the question arises as to the limitation placed upon the Commonwealth by Section 105 of the Constitution. This section reads as follows:—

“The Parliament may take over from the states their public debts as existing at the establishment of the Commonwealth, or a proportion thereof, according to the respective numbers of their people as shown by the latest statistics of the Commonwealth, and may convert, renew, or consolidate such debts, or any part thereof; and the states shall indemnify the Commonwealth in respect of the debts taken over, and thereafter the interest payable in respect of the debts shall be deducted and retained from the portions of the surplus revenue of the Commonwealth payable to the several states, or if such surplus is insufficient, or if there is

no surplus, then the deficiency or the whole amount shall be paid by the several states.

If it be accepted that this section limits the transfer of such debts only as existed on the 1st January, 1901, the following is a statement of the amounts of the outstanding loans, debentures, stock, and treasury bills, with the annual interest payable in respect thereof :—

State.	Amount.	Interest payable.
	£	£
New South Wales.....	66,366,541	2,402,898
Victoria .....	49,374,885	1,888,980
Queensland.....	35,898,414	1,343,243
South Australia .....	26,131,780	989,578
Western Australia.....	12,641,510	398,607
Tasmania ... ..	8,511,005	317,359
Commonwealth .....	198,924,135	7,340,665

The question is, however, complicated by the fact that since the establishment of the Commonwealth, all the states except Queensland have paid off loans then existing, and the point may arise as to whether the amount of the debts which the Commonwealth may take over is not thus further limited. The following is a statement of the loans redeemed from the 1st January, 1901, to the 1st July, 1904, together with the interest payable in respect thereof :—

State.	Amount.	Interest.
	£	£
New South Wales .....	3,496,837	145,509
Victoria .....	9,823,002	414,510
Queensland .....	nil.	nil
South Australia .....	232,300	13,938
Western Australia.....	1,598,000	62,725
Tasmania.....	614,535	22,480
Commonwealth .....	15,754,674	659,162

Few of the redemptions indicated above were absolute, that is to say, effected out of revenue or from sinking funds. For the most part, the loans redeemed were repaid from the proceeds of new loans, and the total amount of the debt was not appreciably reduced; nevertheless, technically speaking, certain debts existing on the 1st January, 1901, no longer exist, their place being taken by new loans to the extent just indicated.

If it be accepted that the Parliament of the Commonwealth can take over only the debts of the states existing at the establishment of the

Commonwealth and now extant, the following is a statement of the public debts of the states under this category together with the interest payable thereon :—

State.	Amount.	Interest.
	£	£
New South Wales .....	62,879,704	2,257,389
Victoria ... ..	39,551,883	1,474,470
Queensland .....	35,898,414	1,343,243
South Australia .....	25,899,480	975,640
Western Australia.....	11,043,510	335,882
Tasmania.....	7,896,470	294,879
Commonwealth .....	183,169,461	6,681,503

During the next five years loans to the extent of £18,179,645 will fall due, and in the ensuing 5 years £24,879,364 and so on in large amounts within no very distant period. An early settlement of the question of transfer of debts is therefore, not only of great, but of pressing importance.

## STATE FINANCE.

THE functions of government are much alike throughout Australasia, and it is only to be expected, therefore, that similar items of expenditure should be found in the budgets of the various states. The chief point of difference is the extent to which local requirements are provided for out of general revenue. In most of the states provision for local improvements is a matter of which the state has long since divested itself; but in New South Wales and Western Australia the central government still charges itself with the construction of works of a purely local character, especially in the rural districts; hence the appearance, in the statements of public expenditure of those states, of items of large amount which find no parallel in the other states. Also, when comparison is made with outside countries, other points of difference are found. In Australasia, as in other young communities, it has been necessary for the state to initiate works and services which in older countries have come within the province of the local authorities or have been left to be undertaken by private enterprise. Even at the present day it is deemed advisable that the Government should retain the control of services, such as the railways, which in the United Kingdom and some other countries are not regarded as forming part of the functions of the state, and it is on account of the administration of these services that the budgets of the Australasian states reach such comparatively high figures.

The revenues of the Australasian states have been subject to considerable fluctuations, due not so much to changes in the incidence of the revenue, as to variation in the amount of the imports, for it was upon taxation of imports that the states have most largely depended for revenue. The years of highest revenue ought, under normal conditions, to be coincident with the years of greatest prosperity; but some of the states have been able to efface the effect of unfavourable seasons by lavish borrowing, and the inflow of loans, as represented by taxable goods, has, at times, more than counterbalanced the shrinkage in the imports, due to failure in the wool or wheat crops, for which these imports are payment. This effect of the borrowing policy of the various states upon their revenue was not so great in the last decade as in the previous one, but that it was considerable may be gathered from the fact that in the ten years 1895-1904 the various state Governments contrived to borrow and spend over £52,000,000, obtained in London. The unsteadiness of the railway revenue, due to variations in the seasons, is another cause of disturbance to Australian finance, and one which will not be obviated



until the resources of the states are so developed that wool and wheat will no longer play the important part they do at present in the railway trade of the country. In 1895 large reductions were made in the New South Wales tariff; these account for a reduction in the revenue of the state during that and the three following years, while to other influences must be added the financial crisis of 1893, which had a numbing effect upon trade throughout the states comprised in the Commonwealth. It will be observed from the table that Western Australia and New Zealand are in a different position to the more important mainland states. The financial position of Western Australia is exceptional, being due to the opening up of the goldfields, and the influx of a large amount of capital, and, as the tariff was of a wide range, the importation necessarily involved a large customs revenue, while the trade expansion increased the earnings of the railways. The configuration of the colony of New Zealand renders it to a very great extent immune from the droughts that so much affect the mainland of Australia, and the financial crisis of 1893 had only a comparatively slight influence on its trade; the progress of trade in that colony was, therefore, fairly regular during the years when the finances of the mainland states were most disturbed.

The establishment of the Commonwealth on the 1st January, 1901, necessitated the transfer of the Customs Department to the Federal Government; and, by proclamation, the Postal, Telegraph, and Defence Departments were taken over on the 1st March of the same year. The receipts of the six states are inclusive of the surplus returned by the Commonwealth, but the expenditure excludes all Federal transactions. The finances of the Commonwealth are dealt with on page 635.

The revenue for each state during the past ten years is shown in the following table. For New South Wales and New Zealand the figures shown for the year 1895, are those for the twelve months ended on the 31st December of the previous year; while for the remainder of the period the fiscal year ended on the 30th June in the former state, and on the 31st March in New Zealand. The amounts given for Tasmania are for the year ended 31st December prior to the years shown, while for the remaining states the financial year ends on the 30th June:—

Year.	New South Wales.	Victoria.	Queensland.	South Australia, including Northern Territory.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
	£	£	£	£	£	£	£	£	£
1895	9,350,051	6,712,152	3,413,172	3,497,648	1,125,941	690,795	23,705,750	4,447,899	28,243,658
1896	9,091,908	6,458,032	3,041,583	2,585,320	1,353,095	761,971	24,397,523	4,556,015	28,953,544
1897	9,199,253	6,630,217	3,613,160	2,698,759	2,342,751	797,976	25,092,108	4,798,708	30,490,814
1898	9,304,884	6,898,340	3,768,152	2,633,727	2,754,747	845,019	26,304,769	5,079,280	31,228,999
1899	9,573,415	7,378,842	4,174,086	2,731,308	2,478,811	908,223	27,244,565	5,258,223	32,502,813
1900	9,973,786	7,450,676	4,588,307	2,858,529	2,375,866	948,970	28,936,814	5,099,618	34,034,982
1901	10,612,422	7,722,397	4,096,390	2,886,554	2,904,121	1,064,980	29,537,064	5,906,916	35,245,980
1902	11,007,356	7,006,578	3,535,062	2,477,432	3,849,450	823,163	28,201,841	6,152,889	34,354,680
1903	11,296,069	6,968,051	3,526,465	2,531,543	3,630,238	734,668	28,037,023	6,447,435	35,174,464
1904	11,243,328	7,313,591	3,695,440	2,508,101	3,550,016	857,668	29,133,144	7,130,116	36,268,260

The revenue per inhabitant for each state during the past ten years was as follows :—

Year.	New South Wales.	Victoria.	Queensland.	South Australia, including Northern Territory.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
1895	7 12 5	5 14 5	7 19 4	7 1 11	13 14 5	4 9 5	6 19 0	6 11 0	6 17 8
1896	7 4 1	5 10 1	8 5 1	7 5 0	18 7 2	4 15 10	6 19 7	6 11 0	6 12 3
1897	7 2 5	5 13 10	8 0 6	7 10 6	20 12 2	4 17 8	7 4 3	6 15 1	7 2 9
1898	7 2 11	5 18 7	8 8 8	7 5 11	17 0 3	5 0 1	7 4 6	7 0 1	7 3 9
1899	7 4 8	6 7 2	8 17 1	7 9 7	14 14 10	5 4 2	7 8 4	7 2 2	7 7 4
1900	7 8 5	6 8 1	9 10 3	7 13 11	16 16 3	5 5 0	7 14 1	7 11 4	7 13 7
1901	7 15 6	6 9 0	8 4 5	7 19 10	16 9 1	6 2 3	7 15 5	7 13 4	7 15 1
1902	7 19 7	5 15 11	6 18 6	6 15 10	17 4 2	4 15 2	7 7 2	7 16 3	7 8 7
1903	8 0 9	5 15 7	6 17 0	6 18 5	16 17 6	4 3 8	7 7 9	7 19 7	7 9 10
1904	7 17 2	6 1 0	6 18 1	6 19 6	15 12 7	4 16 1	7 8 1	8 12 7	7 12 4

The following statements show that the expenditure of the six Commonwealth states has increased from £23,786,695 in 1895, to £29,127,665 for the year 1903-4, while the amount per inhabitant has increased from £7 1s. 3d. to £7 8s. 0d. The expenditure of Australasia has increased, during the same period, from £28,053,407 to £35,561,946, while the amount per inhabitant has increased from £6 18s. 11d. to £7 9s. 4d. The expenditure for each state during the past ten years is set forth in the following table :—

Year.	New South Wales.	Victoria.	Queensland.	South Australia, including Northern Territory.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
	£	£	£	£	£	£	£	£	£
1895	9,329,358	6,760,439	3,808,434	2,661,934	936,729	789,806	23,786,695	4,268,712	28,053,407
1896	9,068,991	6,540,182	3,567,947	2,640,688	1,323,863	743,946	25,020,517	4,370,481	29,390,998
1897	9,316,620	6,568,932	3,604,264	2,779,110	2,339,453	750,244	25,858,622	4,509,981	30,368,604
1898	9,299,411	6,928,850	3,747,423	2,760,959	3,256,912	785,026	26,763,599	4,602,372	31,370,971
1899	9,562,789	7,001,663	4,024,170	2,777,614	2,589,858	830,168	26,735,712	4,858,511	31,594,223
1900	10,086,186	7,280,689	4,540,418	2,998,619	2,615,675	871,454	28,331,041	5,140,128	33,471,169
1901	10,729,741	7,683,079	4,624,479	3,007,034	2,061,331	923,731	30,019,395	5,479,708	35,499,098
1902	11,020,105	7,407,781	3,967,001	2,823,578	3,151,427	870,442	29,240,334	5,914,915	35,155,249
1903	11,467,225	6,774,084	3,717,806	2,641,789	3,521,768	850,694	28,973,861	6,214,019	35,187,880
1904	11,319,887	6,914,993	3,607,364	2,707,253	3,608,312	879,356	29,127,665	6,434,281	35,561,946

The expenditure per inhabitant in each state for the last ten years is as follows:—

Year.	New South Wales.	Victoria.	Queensland.	South Australia, including Northern Territory.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
1905	£ s. d. 7 12 1	£ s. d. 6 15 8	£ s. d. 7 14 5	£ s. d. 7 11 8	£ s. d. 11 8 3	£ s. d. 5 1 4	£ s. d. 7 1 3	£ s. d. 6 5 8	£ s. d. 6 18 11
1906	7 13 8	5 11 5	8 1 9	7 8 1	18 0 4	4 14 2	7 5 9	6 5 8	7 2 9
1907	7 5 9	5 16 10	8 0 1	7 15 0	20 11 8	4 11 10	7 7 11	6 7 0	7 4 9
1908	7 2 10	5 17 2	8 2 9	7 12 5	20 2 8	4 13 0	7 7 10	6 6 11	7 4 3
1909	7 4 6	5 18 4	8 10 8	7 12 2	15 2 1	4 15 2	7 5 10	6 11 4	7 2 8
1910	7 10 1	6 3 1	9 8 8	7 18 5	15 5 10	4 17 0	7 12 5	6 16 6	7 9 8
1911	7 17 8	6 8 4	9 5 8	8 6 5	16 18 9	5 7 0	7 19 1	7 2 3	7 16 8
1912	7 19 9	6 2 7	7 15 5	7 14 10	16 8 5	5 0 8	7 12 7	7 10 2	7 12 0
1913	8 3 2	5 12 4	7 4 5	7 4 5	16 7 5	4 16 10	7 9 8	7 13 10	7 10 1
1914	7 18 2	5 14 5	6 18 7	7 7 0	16 5 7	4 18 7	7 8 0	7 15 9	7 9 4

Below will be found a statement showing the total revenue and expenditure of each state for the financial year 1903-4, with the amounts per head of population. It must be pointed out that from the revenue and expenditure of New South Wales, Victoria, South Australia, Tasmania, and New Zealand, as given in the table, refunds are excluded; while for Queensland and Western Australia there is nothing in the published statements to show whether the amounts are gross or net:—

State.	Year ended—	Total.		Per head of population.	
		Revenue.	Expenditure.	Revenue.	Expenditure.
		£	£	£ s. d.	£ s. d.
New South Wales.....	30 June, 1904..	11,948,828	11,319,887	7 17 2	7 18 2
Victoria.....	30 June, 1904..	7,313,591	6,914,993	6 1 0	5 14 5
Queensland.....	30 June, 1904..	3,595,440	3,607,884	8 18 1	6 18 7
South Australia*.....	30 June, 1904..	2,568,101	2,707,253	6 19 6	7 7 0
Western Australia.....	30 June, 1904..	3,550,016	3,698,312	15 12 7	16 5 7
Tasmania.....	31 Dec., 1903..	857,668	879,356	4 16 1	4 18 7
Commonwealth.....	.....	29,133,144	29,127,665	7 8 1	7 8 0
New Zealand.....	31 Mar., 1904..	7,130,116	6,434,281	8 12 7	7 15 9
Australasia.....	.....	36,263,200	35,561,946	7 12 4	7 9 1

\* Including Northern Territory.

As will be seen from the table, the revenue of the states included in the Commonwealth for the financial year 1903-4 was £29,133,144, or £7 8s. 1d. per head of population, and the expenditure £29,127,665, or £7 8s. 0d. per head, showing a total surplus on the twelve months' transactions of £5,479. The revenue of the

whole of Australasia was £36,263,260, or £7 12s. 4d. per head of population, and the expenditure £35,561,946, or £7 9s. 4d. per head, showing a surplus of £701,314. The only states which had a surplus were Victoria, Western Australia and New Zealand.

#### SOURCES OF REVENUE.

The revenue of the states is mainly derived from taxation and public services. During the year 1903-4 the customs and excise duties, and postal and telegraph revenue of the states forming the Commonwealth were collected by the Federal Government, and the balance, after deducting expenses of the transferred and new services, was returned to the states. These balances amounted to £7,424,126, and other forms of taxation, £3,074,946; while the railways and tramways returned a revenue of £11,999,976, making altogether a sum of £22,499,048 derived from these sources, or 77·23 per cent. of the total receipts. For New Zealand, customs and excise duties yielded £2,698,046 and other taxation, £951,555; railways returned £2,167,992, and posts and telegraphs, £580,771; the receipts from the sources mentioned being £6,398,364, or 89·74 per cent. of the total. It will thus be seen that for the whole of Australasia the collections under the headings mentioned amounted to £28,897,412, or 79·69 per cent. of the gross revenue. A division of the revenue of each state is appended:—

State.	Taxation.		Railways and Tramways	Posts and Telegraphs.	Public Lands.	Surplus Commonwealth Revenue returned to State.	All Other Sources.	Total Revenue.
	Import and Excise Duties.	Other.						
	£	£	£	£	£	£	£	£
New South Wales	....	1,100,193	4,263,744	....	1,800,570	2,683,417	1,340,404	11,248,328
Victoria	....	760,929	3,400,243	....	384,708	2,002,804	764,907	7,313,591
Queensland	....	475,184	1,296,961	....	637,080	810,855	375,360	3,595,440
South Australia	....	358,434	1,178,306	....	181,008	556,949	297,714	2,508,101
Western Australia	....	235,114	1,612,008	....	206,854	1,005,244	481,196	3,550,016
Tasmania	....	150,092	248,024	....	72,585	304,857	82,110	857,595
Commonwealth	....	3,074,946	11,999,976	....	3,342,406	7,424,126	3,291,691	29,133,144
New Zealand	2,698,046	951,555	2,167,992	580,771	247,842	....	483,910	7,130,116
Australasia	2,698,046	4,026,501	14,167,968	580,771	3,590,247	7,424,126	3,775,601	36,263,260

Below will be found a statement of the revenue in 1903-4 on the basis of population. The average for the states of the Commonwealth was £7 8s. 1d., and for the whole of Australasia £7 12s. 4d. per head, the amounts ranging from £4 16s. 1d. in Tasmania to £15 12s. 7d. in Western Australia. The high revenue in the latter state is attributable partly to the influx of foreign capital for the development of the gold-fields, but chiefly to the large consumption of dutiable goods and the railway revenue yielded by the gold-fields. While overseas goods entering the state are

subject to the Federal tariff, importations from the other states are dutiable under the Special Western Australian Tariff, and as a consequence a large importation of capital necessarily means a large customs revenue and increased traffic and earnings for the railways:—

State.	Taxation.		Railways and Tramways.	Posts and Telegraphs.	Public Lands.	Surplus Commonwealth Revenue returned to State.	All Other Sources.	Total Revenue.
	Import and Excise Duties.	Other.						
	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
New South Wales ..	....	0 15 4	2 19 7	....	1 6 0	1 17 6	0 18 9	7 17 2
Victoria .....	....	0 12 7	2 16 8	....	0 6 4	1 13 2	0 12 8	6 1 0
Queensland .....	....	0 13 8	2 9 10	....	1 4 6	1 11 1	0 14 5	6 18 1
South Australia ..	....	0 19 8	8 4 0	....	0 9 10	1 10 8	0 16 2	6 19 6
Western Australia ..	....	1 0 8	7 2 0	....	0 18 2	4 13 9	1 18 0	15 12 7
Tasmania .....	....	0 16 10	1 7 9	....	0 8 2	1 14 2	0 9 2	4 16 1
Commonwealth ..	....	0 15 7	3 1 0	....	0 17 0	1 17 9	0 16 9	7 8 1
New Zealand .....	8 5 3	1 8 8	2 12 5	0 14 1	0 5 11	....	0 11 8	8 12 7
Australasia .....	0 11 4	0 16 11	2 19 6	0 2 5	0 15 1	1 11 2	0 15 11	7 12 4

Dividing the revenue derived from taxation into that payable (a) directly and (b) indirectly by the people, the former including land and income taxes, stamp duties, &c., and the latter customs and excise, license fees, &c., the appended figures are obtained. The figures for the Commonwealth states include the collections of the Federal Government within each state as shown on page 639. As already stated, the Customs and Excise Duties were collected by the Commonwealth Government during the year ended 30th June, 1904, and from the 9th October, 1901, were not determined by the state, but by the Parliament of the Commonwealth.

State.	Total Taxation, 1903-4.			Per head of population.		
	Direct.	Indirect.	Total.	Direct.	Indirect.	Total.
	£	£	£	£ s. d.	£ s. d.	£ s. d.
New South Wales .....	978,056	3,355,255	4,333,311	0 13 8	2 7 0	3 0 8
Victoria .....	744,568	2,458,676	3,203,239	0 12 4	2 0 8	2 13 0
Queensland .....	420,930	1,186,134	1,607,064	0 16 2	2 5 7	3 1 9
South Australia .....	383,664	718,304	1,062,068	0 18 1	1 19 0	2 17 1
Western Australia .....	202,598	1,290,100	1,492,698	0 17 10	5 13 8	6 11 6
Tasmania .....	125,258	857,930	983,188	0 15 2	1 19 9	2 14 11
Commonwealth .....	2,815,064	9,365,619	12,180,683	0 14 4	2 7 7	3 1 11
New Zealand .....	961,556	2,696,046	3,657,602	1 3 1	3 5 5	4 8 6
Australasia .....	3,706,619	12,063,636	15,890,254	0 15 10	2 10 8	3 6 6

Comparing these figures with the returns for the year 1881, which are given below, it will be found that the general tendency has been to

increase both forms of taxation: this is contrary to the general experience, which is that the expenses of government as compared with population, should diminish as population increases.

State.	Total Taxation, 1831.			Per Inhabitant.		
	Direct.	Indirect.	Total.	Direct.	Indirect.	Total.
	£	£	£	£ s. d.	£ s. d.	£ s. d.
New South Wales .....	192,508	1,578,845	1,770,848	0 5 0	2 1 3	2 6 3
Victoria .....	347,782	1,638,345	1,985,137	0 8 1	1 18 0	2 6 1
Queensland .....	49,811	608,448	657,754	0 4 7	2 16 7	3 1 2
South Australia .....	14,322	509,617	584,139	0 1 0	3 2 7	3 3 8
Western Australia .....	1,206	114,919	116,125	0 0 10	3 17 10	3 18 8
Tasmania .....	66,748	283,398	350,146	0 11 5	2 8 6	2 19 11
Commonwealth .....	672,072	4,790,067	5,462,139	0 5 11	2 1 11	2 7 10
New Zealand .....	406,302	1,480,507	1,886,309	0 16 6	3 0 1	3 16 7
Australasia .....	1,077,874	6,270,574	7,348,448	0 7 10	2 5 8	2 13 6

With regard to the proportion of revenue raised at the present time by direct taxation, the states differ considerably. Thus, no less than 15·76 per cent. of the revenue of Tasmania in 1903-4 was derived from that source; while in New Zealand the proportion was 13·34 per cent.; in Queensland, 11·71 per cent.; in Victoria, 10·18 per cent.; in Western Australia, 5·71 per cent.; in South Australia, 12·99 per cent.; and in New South Wales, only 8·69 per cent. The comparison, however, is chiefly interesting as showing the large territorial revenue that New South Wales is fortunate enough to possess.

In all the states probate duties are levied, and except in Western Australia and Queensland, land and income taxes. In Queensland, with few exemptions, all incomes are taxed as well as the dividends of joint-stock companies, and in Western Australia a dividend and companies tax was introduced at the close of the financial year 1898-9. In the edition of this work for 1895-6 the changes in the probate and succession duties, and in the land and income taxes, were traced; the description given below deals only with the duties as they stand at the present time.

#### PROBATE AND SUCCESSION DUTIES.

*New South Wales.*—In this state a duty of 1 per cent. was payable to the end of the year 1899 on the value of the real and personal estate of a testator or intestate, and on settlements of property taking effect after death, provided the value of the property was less than £5,000: 2 per cent. was payable on estates of the value of £5,000 and under £12,500; 3 per cent. upon £12,500 and under £25,000; 4 per cent. upon £25,000 and under £50,000; and 5 per cent. upon £50,000 and upwards. Estates not exceeding £200 in gross value were exempt from duty. On the 22nd December, 1899, an amending Act was assented

to, under which the following duties on the estates of deceased persons are now payable :—

Exceeding—	Not exceeding—	Rate.	Exceeding—	Not exceeding—	Rate.
£	£	per cent.	£	£	per cent.
.....	1,000	Nil.	34,000	36,000	6½
1,000	5,000	2	36,000	38,000	6½
5,000	6,000	3	38,000	40,000	6½
6,000	7,000	3½	40,000	44,000	7
7,000	8,000	3½	44,000	48,000	7½
8,000	9,000	3½	48,000	52,000	7½
9,000	10,000	3½	52,000	56,000	7½
10,000	12,000	4	56,000	60,000	7½
12,000	14,000	4½	60,000	64,000	8
14,000	16,000	4½	64,000	68,000	8½
16,000	18,000	4½	68,000	72,000	8½
18,000	20,000	4½	72,000	76,000	8½
20,000	22,000	5	76,000	80,000	8½
22,000	24,000	5½	80,000	84,000	9
24,000	26,000	5½	84,000	88,000	9½
26,000	28,000	5½	88,000	92,000	9½
28,000	30,000	5½	92,000	96,000	9½
30,000	32,000	6	96,000	100,000	9½
32,000	34,000	6½	100,000	.....	10

Only one-half of these rates is payable on the net amount received by the widow, children, and grand-children of the testator or intestate, provided the total value of the estate is not more than £30,000 after all debts have been paid.

*Victoria.*—The succession duties in force in Victoria are the same as those levied in New South Wales under the 1899 Act, with the exception that on estates exceeding £1,000, but not exceeding £5,000, an exemption of £1,000 is allowed in Victoria. The conditions as to half-rates payable by widows, children, and grand-children, on amounts received by them, are the same as in New South Wales.

*Queensland.*—A succession duty of 2 per cent. is levied in Queensland on property acquired by a person on the death of its former owner when the value of the property is £200 and under £1,000; 3 per cent. is chargeable upon property valued at £1,000 and under £2,500; 4 per cent. upon £2,500 and under £5,000; 6 per cent. upon £5,000 and under £10,000; 8 per cent. upon £10,000 and under £20,000; and 10 per cent. upon £20,000 and upwards. No duty is levied on estates under the net value of £200. When the successor is the wife or husband or lineal issue of the predecessor, one-half of these rates only is charged; and when the successor is a stranger in

blood to the predecessor double rates are charged. The following small probate duties are also payable on the net value of the property :—

Value.	Probates.	Letters of Administration.
Under £50 .....	Nil .....	Nil.
£50 and not exceeding £100.....	10s. ....	£1
Over £100 and not exceeding £200.....	£1 .....	£2
„ £200 „ „ £500.....	£2 .....	£4
„ £500 .....	£5 .....	£10

Succession duty is chargeable on all property held within the state, although the testator or intestate may have been domiciled elsewhere; but power is taken to compound the duty and to accept one sum in respect of all successions, present and future, where the deceased has been domiciled in the United Kingdom or a British possession, and it has been found difficult to assess the value of the succession. Also, where the British Government or the Government of a British possession exempts from duty property held in Queensland by a person domiciled in the United Kingdom or the British possession referred to, no duty is chargeable by the Queensland Government on property held in the United Kingdom or such British possession by a person domiciled in the state.

*South Australia.*—Succession duties are imposed on real and personal property derived from the estate of a deceased person; on settlements of property to take effect after the death of the settlor; and on property made over by deed of gift during the lifetime of the donor, and not made before and in consideration of marriage, or in favour of a *bona-fide* purchaser or encumbrancer for valuable consideration. The duty is levied on the net present value, and is fixed at 10 per cent. when the legatee or beneficiary is a stranger in blood to the person from whom the property is received. When the person taking the property is the widow, widower, descendant, or ancestor, it is subject to a duty of  $1\frac{1}{2}$  per cent. if the value is £500 and under £700; if £700 and under £1,000, 2 per cent.; £1,000 and under £2,000, 3 per cent.; £2,000 and under £3,000,  $3\frac{1}{2}$  per cent.; £3,000 and under £5,000, 4 per cent.; £5,000 and under £7,000,  $4\frac{1}{2}$  per cent.; £7,000 and under £10,000, 5 per cent.; £10,000 and under £15,000,  $5\frac{1}{2}$  per cent.; £15,000 and under £20,000, 6 per cent.; £20,000 and under £30,000,  $6\frac{1}{2}$  per cent.; £30,000 and under £40,000, 7 per cent.; £40,000 and under £60,000,  $7\frac{1}{2}$  per cent.; £60,000 and under £80,000, 8 per cent.; £80,000 and under £100,000,  $8\frac{1}{2}$  per cent.; £100,000 and under £150,000, 9 per cent.; £150,000 and under £200,000,  $9\frac{1}{2}$  per cent.; and £200,000 and upwards, 10 per cent.; one-half of these rates only to be charged when the person taking the property is the child (under 21 years of age) or the widow of the deceased, and the net present value of the whole estate is under £2,000. When the property is taken by a brother or sister, or a descendant of a brother or sister or a person in any other



degree of collateral consanguinity to the deceased person, settlor, or donor, a duty of 1 per cent. is charged if the net present value is under £200 ; if £200 and under £300,  $1\frac{1}{2}$  per cent. ; £300 and under £400, 2 per cent. ; £400 and under £700, 3 per cent. ; £700 and under £1,000,  $3\frac{1}{2}$  per cent. ; £1,000 and under £2,000, 4 per cent. ; £2,000 and under £3,000, 5 per cent. ; £3,000 and under £5,000, 6 per cent. ; £5,000 and under £10,000, 7 per cent. ; £10,000 and under £15,000, 8 per cent. ; £15,000 and under £20,000, 9 per cent. ; and £20,000 and upwards, 10 per cent.

*Western Australia.*—Probate duty is payable on the estates of deceased persons, and upon settlements of property to take effect after the death of the donor, with the exception of ante-nuptial settlements, on all post-nuptial settlements made in pursuance of an agreement entered into before marriage, all settlements, on or for the wife, or her issue, or the issue of the settlor, of property which has accrued to the settlor after the marriage in right of his wife ; and upon all settlements made in favour of a purchaser or encumbrancer in good faith and for valuable consideration. The duty is imposed on the net value of the estate after all debts have been paid. The lowest sum subject to taxation is £1,500, and this sum is likewise exempted when the net value of the estate is less than £2,500, but when this value is exceeded no exemption is made. The rates of duty are as follow :—

£1,500 and under £2,500 (on excess of £1,500)	1 per cent.
£2,500       "     £5,000	2   "
£5,000       "     £10,000	3   "
£10,000     "     £20,000	4   "
£20,000     "     £30,000	5   "
£30,000     "     £40,000	6   "
£40,000     "     £60,000	7   "
£60,000     "     £80,000	8   "
£80,000     "     £100,000	9   "
Over £100,000	10   "

with half these rates when the beneficiaries comprise the parent, issue, husband, wife, or issue of husband or wife of the deceased.

*Tasmania.*—In this state duties are imposed on probates of wills and letters of administration. The duty is levied on the net value of the personal estate of the testator or intestate. When the amount is under £200 no duty is payable ; when it is £200 and not more than £500 the duty is 2 per cent. ; and when it is £500 and upwards the duty is 6 per cent. Life policies are exempt from taxation up to £1,000, and the duty on bequests to widows and children is one-half the rates indicated.

*New Zealand.*—The following duties are imposed in New Zealand on the final balance of the real and personal property left by a testator or intestate ; on settlements of property taking effect after the death of the settlor ; and on property made over by deed of gift taking effect during the lifetime of the donor, and not being property granted before

and in consideration of marriage, or in favour of a *bona-fide* purchaser or encumbrancer in return for valuable consideration:—

Not exceeding £100 .....	Nil.
£100 and not exceeding £1,000—	
On first £100 .....	Nil.
On remainder .....	2½ per cent.
Over £1,000 and not exceeding £5,000 .....	3½ „
Over £5,000 and up to £20,000 .....	7 „
On £20,000 and upwards .....	10 „

with 3 per cent. additional in the case of strangers in blood, except adopted children. It is provided that no duty shall be payable on property passing absolutely into the possession of the widow of the deceased, or of the widower of the deceased; and that only half-rates shall be payable on property acquired by the children, step-children, and grand-children of the testator or intestate. It is further provided that in the case of property in which a life estate or interest is acquired by the widow on the death of her husband, or by the widower on the death of his wife, payment of duty shall be made in ordinary course if the property possesses a capital value which would give an annual return of not less than £500 if invested at 6 per cent., and when the property is of lower value the widow or widower shall obtain a refund not exceeding 50 per cent. of the duty.

#### LAND AND INCOME TAXATION IN NEW SOUTH WALES.

In New South Wales, land tax is levied on the unimproved value; the present rate being 1d. in the £. An exemption of £240 is allowed, and if the unimproved value is in excess of this sum a deduction equal to the exemption is made, but when a person or company holds several blocks of land only one sum of £240 may be deducted from the aggregate unimproved value. Also, when a block of land is mortgaged, the mortgagor is allowed to deduct from the amount of his tax a sum which is equal to the income tax chargeable to the mortgagee on the interest derived from the mortgage of the whole property, including improvements. The exemptions from taxation comprise Crown lands not subject to right of purchase, or held under special or conditional lease, or as homestead selections; other lands vested in His Majesty or his representatives; lands vested in the Railway Commissioners; lands belonging to or vested in local authorities; public roads, reserves, parks, cemeteries, and commons; lands occupied as public pounds, or used exclusively for or in connection with public hospitals, benevolent institutions, and other public charities; churches and chapels, the University and its affiliated colleges, the Sydney Grammar School, and mechanics' institutes and schools of arts; and lands dedicated to and vested in trustees and used for zoological, agricultural, pastoral, or horticultural show purposes, or for other public or scientific purposes. Should the tax remain unpaid for a period of two years after it becomes due the

Commissioners may, after giving another year's notice, let the land for a period not exceeding three years, or, with the permission of a Judge of the Supreme Court, sell so much of it as may be necessary for the payment of the tax, with fines, costs, and expenses added.

A tax is also imposed upon so much of every income as may be in excess of £200, except in so far as it is derived from the ownership or use or cultivation of land upon which land tax is payable; the present rate being 6d. in the £. The exemptions include the revenues of local authorities; the income of life assurance societies and of other societies and companies not carrying on business for purposes of profit or gain, and not being income derived from mortgages; the dividends and profits of the Savings Bank of New South Wales and the Post Office Savings Bank; the funds and income of registered friendly societies and trade unions; the income and revenues of all ecclesiastical, charitable, and educational institutions of a public character; and income accruing to foreign investors from Government stock. The regulations provide that in the case of every company its income shall be taken as the income of the company in New South Wales and from investments within the state. Public companies are not allowed the exemption of £200.

The receipts from the land and income taxes since their imposition were as follows. The amounts are exclusive of refunds rendered necessary through correction of errors by the taxpayer or adjustments by the Department, but include refunds brought about through the income of the year of assessment falling short of the amount of income of the preceding year on which the assessment was made, a provision which has been repealed by the "Land and Income Tax Amendment Act, 1904."

Year.	Land Tax.	Income Tax.
	£	£
1896 .....	.....	27,658
1897 .....	139,079	295,537
1898 .....	364,131	166,395
1899 .....	253,901	178,032
1900 .....	236,227	183,460
1901 .....	288,369	215,893
1902 .....	301,981	203,625
1903 .....	314,104	214,686
1904 .....	322,246	211,831

The irregularities noticeable in the first three years are due to the difficulties inseparable from the introduction of a system of direct taxation; the returns for 1899 and subsequent years are under normal conditions.

The value of land assessed for taxation purposes is £129,178,000; while £16,440,000 represents the value of land falling below the minimum taxable value (£240), or untaxable in consequence of mortgage deductions. As an exemption of £240 is allowed for each person, the taxable amount is further reduced by £9,840,000; exemptions in respect of mortgages described in the text still further

reduce the taxable balance by £16,800,000, and balances due on land conditionally purchased from the state by £9,298,000, so that the actual taxable value is £76,800,000.

The number of persons owning land in New South Wales is about 178,000, but the deductions allowed by law reduced the actual number of taxpayers to 41,000.

The incomes liable to taxation do not vary greatly either in regard to their number or amount, and during the last five years were as follows:—

Year.	Number of Incomes.	Net Income.
		£
1899 .....	19,775	11,123,343
1900 .....	20,051	12,140,569
1901 .....	19,991	12,065,842
1902 .....	20,299	12,127,129
1903 .....	22,234	13,415,760

The difference between the gross and the net income represents the deductions allowed to taxpayers on account of cost of earning their incomes, and certain allowances for life assurance on premium payments up to £50 per annum. A distribution of the incomes subject to taxation according to amounts taxable is given below, the figures representing the average of four years. It should be remembered that these represent only a proportion of the incomes derived from New South Wales, as incomes derived from land, or the use or occupancy of land, are not taxable. The amounts given are the net earnings:—

Categories.	Average of four years.		Percentage in each category.	
	Number of Incomes.	Amount of Incomes.	Of number of Incomes.	Of amount of Incomes.
		£	%	%
£200 and under £250 ...	5,798	1,292,273	28·94	10·89
250   "   300 ...	3,899	1,052,000	19·47	8·87
300   "   400 ...	3,951	1,344,751	19·73	11·33
400   "   500 ...	1,836	812,063	9·17	6·84
500   "   700 ...	1,802	1,044,465	9·00	8·80
700   "   1,000 ...	1,114	913,504	5·56	7·70
1,000   "   1,200 ...	353	390,491	1·79	3·29
1,200   "   2,000 ...	666	1,005,414	3·32	8·48
2,000   "   5,000 ...	434	1,262,306	2·16	10·84
5,000   "   10,000 ...	103	701,682	0·51	5·92
10,000   "   20,000 ...	44	595,209	0·22	5·02
20,000 and upwards .....	26	1,450,044	0·13	12·22
Total .....	20,029	11,864,222	100·00	100·00

## LAND AND INCOME TAXATION IN VICTORIA.

The Land Tax Act in force in Victoria was passed with the object of breaking up large holdings. For this purpose it was declared that all "landed estates" should be subject to taxation; that a "landed estate" should consist of one or more blocks of land not more than 5 miles apart which possessed an aggregate area of upwards of 640 acres and a capital value of more than £2,500; that the value in excess of £2,500 should be taxed at the rate of  $1\frac{1}{2}$  per cent. per annum, but that only one exemption should be allowed to a person or company owning more than one "landed estate"; and that the assessment of the capital value of the "landed estate" should be based upon the average number of sheep which it was estimated to be able to maintain, £4 per acre being fixed as the value of land which could carry 2 sheep or more to that area; £3 per acre if it could carry only  $1\frac{1}{2}$  sheep; £2 per acre if it could carry only 1 sheep, and £1 if it could not maintain an average of a single sheep to the acre.

The rate of income tax payable in the state varies according to the source whence the income is derived and the taxable amount of such income. On incomes derived from personal exertion 3d. in the £ is payable up to £300; on every £ in excess of £300 up to £800, 4d.; on every £ in excess of £800 up to £1,300, 5d.; on every £ in excess of £1,300 up to £1,800, 6d.; and on every £ in excess of £1,800, 7d.; double these rates being payable on incomes the produce of property within the state. All incomes, except those of companies, of and under £150 escape taxation. In the case of a company liable to pay tax, with the exception of those referred to later on, the income chargeable is the profits earned in or derived from Victoria by such company during the year immediately preceding that of assessment. The taxable amount of the income of a company which carries on in Victoria the business of life assurance, is assessed at a sum equal to £30 per cent. of the premiums received by the company during the year immediately preceding that of assessment in respect of insurances or assurances effected in Victoria, and such sum is chargeable with tax as income the produce of property. In respect of companies carrying on fire, fidelity, guarantee, marine assurance or insurance business, the premiums derived from any such business are not included in the premiums received by any such company within the meaning of the previous sentence. The rate of income chargeable in respect of life assurance companies is 12d. in the £ of the taxable amount of income. The income of a taxpayer, from any trade carried on in Victoria, to the extent of £4 per cent. of the surplus of assets employed or used in such trade over and above the liabilities thereof during the year immediately preceding that of assessment, is chargeable with tax as income from property, and beyond such extent with tax as income from personal exertion, the determination of such surplus being left with the Commissioner. Land and buildings used by the owner for residential

purposes are regarded as returning an income of 4 per cent. on the capital value. It is provided that shipowners whose principal place of business is outside the state shall pay £5 for every £100 received for the carriage of Victorian passengers, goods, and mails. In the case of sales of property, where the principal is not a resident of Victoria, the taxable amount of his income derived from such sale or disposal of property is assessed at 5 per cent. of the total amount for which the property was sold or otherwise disposed of, unless it should be proved to the satisfaction of the Commissioner that the amount received was less than 5 per cent., when a corresponding reduction will be made. The exemptions include the income of the state, local authorities, savings banks, University of Melbourne and affiliated colleges, Working Men's College, schools of mines, technical schools, religious bodies, registered friendly societies, building societies, and trade unions; of societies and public bodies not carrying on business for purposes of gain to shareholders or members of insurance companies (other than life) taking out an annual license under the Stamps Act; and of mining companies; also such dividends derived from mining companies as may not be in excess of calls paid up during the year; and income derived by foreign investors from the stock of Government or local bodies.

The land tax of Victoria affects an area of 6,797,028 acres of the nominal value of £9,972,340, the municipal valuation being estimated to be about £22,000,000. Private land having an area of about 16,000,000 acres and land values to the extent of about £100,000,000 therefore escape taxation. The classification of land for taxation purposes has been given in a preceding paragraph, and the following table gives the number of taxpayers of each class, with the area, assessed capital value, and other particulars of taxable land.

Classification of land.	No. of Proprietors.	Area.	Capital Value.	Net taxable value allowing deduction of £2,500 for each proprietor.	Tax payable.
		acres.	£	£	£
I. (2 sheep per acre).....	80	232,383	925,632	725,632	7,070
II. (1½ sheep per acre) .....	158	503,225	1,504,613	1,109,613	13,870
III. (1 sheep per acre).....	274	1,480,675	2,961,350	2,276,350	28,454
IV. (less than 1 sheep per acre)	360	4,580,745	4,580,745	3,680,745	46,010
Total .....	872	6,797,028	9,972,340	7,792,340	95,404

The number of payers of income tax in Victoria during 1904, on incomes earned in 1903, was 43,003, comprising 42,379 individuals and 624 companies. Of these 34,572 were from personal exertion only: 4,620 from property only; and 3,811 combined both classes of income. The total income of taxpayers, who paid tax, was £18,138,606, being

£14,425,963 from personal exertion, and £3,712,643 from property. The income on which the tax was assessed after the deduction of the exemption amounted to £14,084,876, and was distributed as follows: In the case of individuals, from personal exertion, £9,678,185, and from property £2,571,454; and in the case of companies £1,379,478 from personal exertion, and £455,759 from property. Taking into consideration 3,811 assessments, which combine income from both personal exertion and property, the taxpayers aggregate 46,814, of whom, 38,383 derived their income from personal exertion, with net incomes valued at £11,057,663, while 8,431 obtained their income from property with a net return of £3,027,213. The following is a statement of the taxpayers and their incomes after deducting the exemption of £100, according to the latest assessment, the tax payable being that for the year 1904:—

Incomes.	Total Taxpayers.		Taxable Incomes.		
	Personal Exertion.	Property.	From Personal Exertion.	From Property.	Total.
	No.	No.	£	£	£
£200 and under .....	26,718	5,305	2,728,563	459,243	3,187,806
£201 to £1,200 .....	10,548	2,710	4,490,768	1,248,006	5,738,774
£1,201 to £2,000 .....	565	216	863,142	329,088	1,192,230
£2,001 and upwards .....	552	200	2,975,190	993,876	3,969,066
<b>Total .....</b>	<b>38,383</b>	<b>8,431</b>	<b>11,057,663</b>	<b>3,027,213</b>	<b>14,084,876</b>

The annual assessments, and the revenue obtained from all sources since the imposition of the income tax, were as follows:—

Year.	Tax Assessed.		Revenue.
	Personal Exertion.	Property.	
	£	£	£
1896 .....	79,928	92,793	169,946
1897 .....	85,977	85,133	168,320
1898 .....	89,140	90,373	178,619
1899 .....	89,444	83,976	172,721
1900 .....	123,457	93,787	215,867
1901 .....	125,824	95,091	218,792
1902 .....	123,609	91,494	214,492
1903 .....	206,227	188,535	385,208

The revenue in arrears is the difference between the total of the second and third columns and the last column.

## INCOME AND DIVIDEND TAXES IN QUEENSLAND.

The Income Tax Act became law in November, 1902, and provided for the imposition from the 1st January, 1902, of a tax on the income of all persons, except males under the age of 21 years and all females whose incomes did not respectively amount to £150.

The Act was limited in its operation to the 31st December, 1904, but was continued in its operation, and amended by the Income Tax Amendment of 1904. Under the Amending Act, where the total income does not in the aggregate exceed £100 it is exempt from taxation, except in the case of companies or absentees. If the taxable income does not in the aggregate exceed £300, and is derived partly from personal exertion and partly from property, the exemption of £100 is to be deducted from the income from personal exertion. The rates levied on income derived from personal exertion are as follows:—Where the total income exceeds £100 but does not exceed £125, a fixed sum of 10s. If the total income exceeds £125 but does not exceed £150, a fixed sum of £1. For incomes over £150 but not over £300, the tax is 6d in every £ in excess of £100. For incomes over £300 but not over £500, the rate is 6d in the £ without exemption. On incomes over £500 but not exceeding £1000, the tax is 6d. in the £ on the first £500, and 7d on each £ over £500, without exemption. For incomes over £1000 but not exceeding £1500, the tax is 7d. in the £ on the first £1000, and 8d in each £ over £1000, without exemption. On incomes over £1500, the rate is 8d in the £, without exemption. On incomes derived from the produce of property the rates are:—On the taxable income over £100 but not exceeding £120, a fixed sum of £1; on incomes over £120 but not exceeding £300, 1s in the £ over £100; on incomes over £300, 1s in the £, without exemption. Incomes of all companies and absentees pay 1s in the £. Companies having their head office or chief place of business in Queensland are assessed at not less than the amount of the dividends declared during the year of assessment, and where any of the profits remain undistributed to shareholders only 6d in the £ is paid on such undistributed profits. In the case of mining companies carrying on business in Queensland, the first or subsequent dividend declared or paid by the companies is to be taken to be applied in the first place in repayment of the cost actually incurred prior to the declaration of such dividend in respect of labour or material employed in developing the mine and in repayment of three-fourths of the cost of machinery erected for raising ore and other materials from the mine, and is to be deducted from the income of the company.

The Dividend Tax which was collected up to the 1st December, 1904, has now become merged in the ordinary Income Tax.

The incomes, revenues, and funds not liable to taxation are: Governor's salary and incidental expenses; revenues of local bodies; incomes of



**Mutual Assurance Companies**; incomes of societies and institutions not carrying on business for profit or gain; funds of friendly societies and trade-unions; incomes of religious, charitable, and educational institutions; income from dividends which have paid dividend duty; income derived by absentees from debentures, stock, or treasury bills; sums expended on the maintenance of infirm, aged, and indigent relatives up to the amount of £26; premiums on life assurance up to £50; payments for superannuation or into friendly societies up to £50; calls or contributions to companies in liquidation.

The number of taxpayers was 77,240, of whom 16,726 were assessed at over £1; 20,022 at the fixed sum of £1; and 40,492 at 10s. each. The number of taxpayers subject to the tax by way of property was 1,013, with a total income of £414,239, and from personal exertion; 16,037 with an aggregate income of £5,624,756. The total incomes over £150 subject to taxation were £6,038,995, and, allowing for 324 appearing under both heads, the number of individual taxpayers was 16,726. The following table shows the grades of assessments, number of taxpayers, and amount of income in relation to those above £150:—

Assessment.	From Property.		From Personal Exertion.	
	Number of Taxpayers.	Amount of Income.	Number of Taxpayers.	Amount of Income.
		£		£
Over £150 up to £210. . . .	316	56,772	8,149	1,383,284
„ £210 „ £310.....	262	65,538	3,848	959,754
„ £310 „ £510.....	241	91,306	2,275	855,803
„ £510 „ £910... ..	120	82,582	1,007	665,475
„ £910 „ £2,110... ..	60	74,924	552	670,064
„ £2,110 ..... ..	14	43,117	206	1,090,376
	1,013	414,239	16,037	5,624,756

An additional tax, called the “Totalisator Tax,” is imposed at the rate of 5 per cent. on all moneys received by conductors of authorised totalisators in connection with horse races.

#### LAND AND INCOME TAXATION IN SOUTH AUSTRALIA.

In South Australia the land tax is calculated on the unimproved value, the rate being  $\frac{1}{4}$ d. in the £, with an additional tax of  $\frac{1}{4}$ d. on every £ in excess of £5,000. The amount of tax payable by an absentee, who is defined as a person who has been absent from or resident out of the state for twelve months, is increased by 20 per cent. The exemptions to the land tax comprise Crown lands which are not subject to

any agreement for sale or right of purchase, park lands, public roads, public cemeteries, and other public reserves, and land used solely for religious or charitable purposes, or used by any institute under the provisions of the Institute Act of 1874. It is provided that an assessment shall be made every three years, and that the distribution of the tax shall be made according to the proprietary interest held in the land. It is further provided that if the payment of the tax has been in arrear for a period of two years the Commissioner may, after giving another year's notice of his intention, let the land from year to year, and after deducting from the rents the amount of tax, with costs and expenses, hold the balance for the benefit of the owner; or he may even go so far as to petition the Supreme Court for permission to sell so much of the land as may be necessary for the payment of the tax and costs and expenses.

The income tax varies according to the source whence the income is derived. On incomes derived from personal exertion the rate imposed is 4½d. in the £ up to and including £800, and 7d. for every £ in excess of that sum. On incomes the produce of property the rate imposed is 9d. in the £ up to and including £800, and 13½d. for every £ in excess of that amount. The sum exempted from taxation is £150, but where the net income of a taxpayer from all sources exceeds £400 he is not entitled to any exemption. No exemption is allowed if the taxpayer has been absent from South Australia for twelve consecutive months prior to November, 1904. The exemptions from taxation comprise the incomes of municipal corporations and district councils; of companies, public bodies, and societies not carrying on business for purposes of gain to be divided amongst shareholders or members; and of friendly societies. Land and buildings occupied by the owner for residential purposes are taken as returning an income of 5 per cent. on the capital value, and the income of a company is declared to be the produce of property for taxation purposes. In the case of income derived from shipping, the taxable amount is £5 per cent. of the gross receipts for the carriage of passengers, mails, or goods out of any port in South Australia, whether to some other port in South Australia or beyond the state. Income tax may be charged on casual shipping, the assessment being made by the Commissioner. In the case of companies carrying on the business of life assurance the taxable amount is such portion of the profits and surplus as would be actuarially distributable to or amongst the holders of in South Australia of the company's policies. In the case of companies other than banking, fire insurance, life assurance, and those engaged in carrying by sea, the taxable amount of income is a sum which shall bear to the company's whole net income wherever arising the proportion which the assets in South Australia bear to the whole assets of the company.

The net receipts from land tax during the past ten years are shown below. The total number of holders of land within the state is approximately 61,712, and the aggregate unimproved value of the land is

£41,348,241, while the unimproved value of the land subject to taxation is £28,598,241.

Year ended 30th June.	Land Tax.	Year ended 30th June.	Land Tax.
	£		£
1894	74,501	1900	78,404
1895	86,306	1901	79,908
1896	75,295	1902	76,350
1897	78,389	1903	105,024
1898	81,508	1904	77,369
1899	77,622		

The payers of income tax during 1903 numbered 11,952, comprising 13,120 assessments, viz., 9,923 on personal exertion, 2,695 on property, 121 firms, 185 companies, and 196 trustees. The taxable incomes from personal exertion amount to £2,220,002, and from property, £1,188,136. The incomes for the five years, 1899 to 1903, were :—

Year.	Number of Taxable Incomes.	Amount of Assessment.
		£
1899	12,761	3,050,396
1900	8,528	3,384,928
1901	9,632	3,162,423
1902	15,226	3,791,848
1903	11,952	3,247,818

These sums do not represent the total income, being exclusive of the exemptions allowed by law to incomes under £150. For the year 1903 the total incomes subject to taxation were :—

11,952 incomes, exclusive of exemption.....	£3,247,818
Exemption of £150 on 9,569 incomes.....	1,453,200
	£4,701,018

The receipts from income tax during the last ten years are shown in the following table :—

Year.	Income Tax Received.	Year.	Income Tax Received.
	£		£
1894	70,853	1899	84,184
1895	55,969	1900	92,281
1896	86,570	1901	85,746
1897	86,476	1902	81,293
1898	82,396	1903	129,327

#### DIVIDEND AND COMPANIES TAX IN WESTERN AUSTRALIA.

Of all the states, Western Australia was the last to introduce the system of direct taxation ; but, the field of taxation was restricted to the income and dividends of companies. The Act authorising this taxation is known as the Companies Duty Act of 1899. The main

object aimed at by Parliament in sanctioning this partial taxation of incomes was to secure to the state some portion of the golden harvest of the mining fields. The Act was regarded as legislation of an experimental character, and as a consequence was limited in its operation to the period of three years ended 31st December, 1902. It is apparent that the fears of the opponents of this method of taxation—that it would scare away capital from the state—have not been realised, for in December, 1902, the Dividend Duties Act was passed into law. Under Section 6 of that Act a tax of 1s. in the £ is imposed on the dividends of all companies, other than insurance or assurance companies, carrying on business in Western Australia and not elsewhere. In the case of any company, other than an insurance or assurance company, carrying on business in Western Australia and elsewhere, a similar tax is imposed, under Section 7 of the Act, on profits made by such company in Western Australia. Section 8 provides that any company carrying on, in Western Australia, any insurance or assurance business, not being a life assurance company which is exempt from the operation of the Act, shall be taxed to the amount of 20s. per £100 of gross premiums paid in Western Australia, but the taxable amount shall exclude any portion of such premiums actually paid away by way of reinsurance effected in Western Australia with any other company.

The net receipts from the tax on companies during the four years ended 30th June, 1903, were as follows:—

Year.	Amount of Tax received. £
1900.....	55,015
1901.....	67,998
1902.....	85,990
1903.....	127,607

The receipts under the Dividend Duties Act for the year ended 30th June, 1904, are as follows:—

Class of Business.	Section 6.	Section 7.	Section 8.	Total.
	£	£	£	£
Mining .....	82,699	22,795	...	105,494
Mercantile Firms.....	724	1,553	...	2,277
Shipping.....	77	1,438	...	1,515
Financial Institutions	1,079	5,295	...	6,374
Insurance .....	...	...	2,229	2,229
Miscellaneous .....	4,982	2,200	...	7,182
Total .....	89,561	33,281	2,229	125,071

#### LAND AND INCOME TAXATION IN TASMANIA.

The land tax payable in Tasmania is at the rate of  $\frac{1}{4}$ d. in the £ where the assessed value is under £5,000;  $\frac{3}{4}$ d. in the £ where the assessed value is £5,000 and under £15,000;  $\frac{1}{2}$ d. in the £ where the value is £15,000 and under £40,000;  $\frac{1}{4}$ d. in the £ where the value is £40,000 and under £80,000; and 1d. in the £ where the value is

£80,000 and over, with a deduction of  $\frac{1}{2}$ d. in the £ on account of mortgages. The exemptions comprise land the property of a municipal corporation or other local authority, or of a registered friendly society; the site of a State school under the Education Department; of a public library or museum; of the Tasmanian Museum; of a hospital or benevolent asylum or other building used solely for charitable or religious purposes, or land vested in trust for public purposes; public roads; cemeteries which are not owned by joint-stock or public companies; and public reserves, gardens, and recreation grounds. Crown lands held on lease are also exempted from taxation, but if they have been purchased on credit the occupier is required to pay tax, provided one-half of the price has been paid or has become due. The owner of the land is looked to directly for the amount of the tax, unless he resides out of the state or cannot be found, in which case the occupier becomes responsible, but is allowed to deduct the sum from the amount of his rent. The Commissioner has power to let the land if the tax remains unpaid six months after it has become due, or, with the approval of a Judge of the Supreme Court, to sell it if the tax has remained unpaid for two years; and it is provided that the balance of the proceeds, after the amount of the tax, with costs and expenses, has been deducted, shall be handed over to the owner of the rented property or the original owner of the property which has been sold. As the value of the land rated is declared by law to be the sum which the fee-simple would sell for, the tax is not purely a land tax, but a tax on real estate.

The income tax in force in the state provides for the imposition of 1s. in the £ on all income of any company, on the income of any person at the rate of 6d. in the £ of the taxable amount thereof derived from business and 1s. in the £ on that derived from property, and on every dividend not included in either of the foregoing at the rate of 1s. in the £ on such dividend. The chief exemptions are the revenues of municipal corporations and other local authorities, incomes of companies, societies, or public bodies or trusts not carrying on business with a view to a distribution of profits amongst their shareholders or members, the funds and incomes of registered friendly societies and trade unions, income accruing to foreign investors in Tasmanian Government stock, rents from land subject to land tax, income derived from dividends which have already been taxed, income of the Governor of Tasmania, income from all sources that is less than £100 per annum, and incomes of persons who have not been resident in the state for six months. Where any person's income is assessed at £100 or over and is less than £400 a deduction by way of exemption is allowed as follows:—£100 and under £110, a deduction of £80; £110 and under £120, £70; £120 and under £150, £60; £150 and under £200, £50; £200 and under £250, £40; £250 and under £300, £30; £300 and under £350, £20; £350 and under £400, £10. Where the income is derived partly from business and partly from property the deduction is made upon that from

business, and if such income is insufficient to allow the full benefit of the deduction, the balance of the deduction is made from the income from property. No deductions are allowed in respect of the income of a company or on income receivable by a person as a prize in any lottery authorised by law in Tasmania. The taxable amount of the income of companies having their head office in Tasmania is the sum represented by the dividends declared or becoming due to the shareholders. In the case of companies whose head office is outside Tasmania, the income during the year preceding that of assessment is adopted, but in no case is it to be deemed less than £1,000, and the assessment is to be calculated as follows:—In the case of banking companies to be so much of the total dividend declared by the company during the year ended 31st December preceding that of assessment as is proportionate to the average amount of the average quarterly assets and liabilities of the company in Tasmania during the same year compared with the total assets and liabilities of the company for a like period as disclosed by the balance sheet. In the case of fire, accident, fidelity, guarantee or marine assurance or insurance companies, the taxable amount is a sum equal to £50 per cent. of the net premiums received by the company in Tasmania. The taxable amount of life assurance companies is £20 per cent. of the premiums received in Tasmania. In the case of shipping companies the taxable amount is £5 per cent. of the receipts for the carriage of livestock, goods, mails and passengers shipped in Tasmania and carried to any port in or beyond the state. Mercantile and other companies liable to taxation are taxed on £5 per cent. of the turnover of business in Tasmania.

On the 1st November, 1904, assent was given to an Act to levy a tax upon persons in proportion to their means or ability entitled "The Taxation Act, 1904." Under this form of taxation a man's income is determined according to the annual assessment of the house in which he lives, provision being made for the taxation of lodgers according to the amount they pay for board and lodging. The amount upon which tax is to be paid by occupiers or sub-occupiers of property who occupy for purposes of residence or partly for purposes of residence and partly for business, and who practise a profession other than that of schoolmaster, is as follows:—"Where the assessed annual value or aggregate assessed annual value of the property or properties is under £30 the taxable amount is to be five times thereof; £30 and under £40, six times thereof; £40 and under £60, seven times thereof; £60 and under £80, eight times thereof; £80 and under £100, nine times thereof; and £100 and over, ten times thereof. Where the taxable amount is £60 or over an exemption of the first £30 is allowed, and a further reduction of £10 for each child under the age of 17 years residing with and dependent upon the taxpayer where the taxable amount is under £100. Where the taxable amount is under £60, the amount of the tax to be paid is 2s. 6d.; £60 and under £100, 1d. in the £; £100 and under £115, 2d. in the £; £115 and under £150,

3d. in the £; £150 and under £400, 4d. in the £; £400 and over, 4d. in the £ for the first £400, and 6d. in the £ for the amount in excess thereof. Where the taxable amount is £400 or over the exemption is to be made from the first £400, on which the tax is payable at the rate of 4d. in the £. Occupiers or sub-occupiers of property who occupy partly for purposes of residence and partly for those of business, and who do not practise a profession other than that of school-master are assessed in the following amounts:—For the first £50 of the assessed annual or aggregate annual value of the property or the fractional part two and a half times thereof; for the second £50 or fractional part, one and a half times thereof; and for the remainder three-fourths thereof. Where a person carries on any agricultural, pastoral, or horticultural pursuit, the land upon which such pursuit is carried on or upon which he resides is deemed to be property occupied partly for purposes of residence and partly for business. Where the taxable amount is £50 or over an exemption of £30 is allowed. Where the taxable amount is under £50, the amount of the tax to be paid is 2s. 6d.; £50 and under £100, 2d. in the £; £100 and under £153, 3d. in the £; £153 and under £185, 4d. in the £; £185 and under £238, 4½d. in the £; £238 and under £2,375, 5d. in the £; £2,375 and over, 6d. in the £.

The amount upon which tax is to be paid by lodgers is calculated upon and ascertained from the assessed annual value of their board and lodging as follows:—Where the assessed annual value of the board and lodging is under £36 in the case of a female lodger it is exempt; under £36 in the case of a male lodger, twice the amount thereof; £36 and under £65 in the case of either sex, twice the amount thereof; £65 and under £78 in the case of either sex, two and half times thereof; £78 and under £104 in the case of either sex, three times the amount thereof; and £104 and over in the case of either sex, four times the amount thereof. Where the taxable amount is under £60, the amount of the tax to be paid is 2s. 6d.; £60 and under £100, 1d. in the £; £100 and under £115, 2d. in the £; £115 and under £150, 3d. in the £; £150 and under £400, 4d. in the £; £400 and over, 4d. in the £ on the first £400, and 6d. in the £ for any amount in excess thereof. Where a tax-payer proves to the satisfaction of the Commissioner that his income is exclusively derived from property, being "income from property" within the meaning of the "Income Tax Act, 1902," he may be declared exempt.

The land tax of Tasmania is levied on a capital value of £21,831,937, and yields over £46,000 a year. The imposition of a graduated tax, under the provisions of "The Land Tax Amendment Act, 1902, together with the increase resulting from improved capital values, has considerably swelled the receipts from land tax for 1903. In connection with the graduated tax there were during 1903, 551 owners of £5,000 and under £15,000, possessing property of the capital value of £4,502,056; 142, of £15,000 and under £40,000, with a

capital value of £3,206,571; 22, of £40,000 and under £80,000, with a capital value of £1,136,732; and 13, of £80,000 and over, with a capital value of £1,585,430. The estates subject to taxation in 1903 numbered 46,655. The following is the result of seven years' working:—

Year.	Estates subject to Tax.	Capital Value of Land.	Amount of Tax.
	No.	£	£
1896	24,806	19,376,539	37,609
1897	34,980	19,213,591	37,226
1898	34,987	19,261,841	37,577
1899	42,739	20,020,051	38,866
1900	43,132	20,026,162	38,915
1901	44,417	20,258,393	39,337
1902	45,188	20,464,094	39,337
1903	46,655	21,831,937	46,548

The demand for payment of income tax, for 1903, was not issued until the 31st December of that year, consequently the only collections made were those relating to companies, particulars of which are furnished below. The returns for the last five years were—

Year.	Companies.	No.	Taxable Dividends.	Tax Paid.
			£	£
1899	Mining .....	16	365,437	18,272
	Other .....	23	45,732	2,286
	Total .....	39	411,169	20,558
1900	Mining .....	13	505,123	25,256
	Other .....	27	47,963	2,399
	Total .....	40	553,106	27,655
1901	Mining .....	9	302,823	15,141
	Other .....	25	47,964	2,397
	Total .....	34	350,787	17,538
1902	Mining .....	12	164,906	9,245
	Other .....	26	52,937	2,647
	Total .....	38	227,843	11,892
1903	Mining .....	11	195,164	9,758
	Head office, or chief place of business in Tasmania, including licensees of lotteries.....	31	460,961	23,048
	Head office, or chief place of business not in Tasmania .....	48	94,563	4,728
	Total .....	90	750,688	37,534



## LAND AND INCOME TAXATION IN NEW ZEALAND.

In New Zealand the Land and Income Tax Assessment Act imposes a tax upon incomes and an ordinary tax upon land and mortgages, the amount of which it is provided shall be fixed annually by a Rating Act; and also an additional graduated tax upon the unimproved value of land, the rates of which are fixed by the Assessment Act. The rate of the ordinary tax upon land and mortgages at present stands at 1d. in the £ of capital value, but on native land occupied by Europeans the rate is  $\frac{1}{2}$ d. in the pound. It is provided that the owner of any land shall pay the tax on the actual value of his land, and also on the value of any mortgages which he may hold over other land, less the value of improvements, and of any mortgage which may be owing on his land. If the net value does not then exceed £1,500, an exemption of £500 is allowed, but for every £2 by which the net value exceeds the sum of £1,500 the exemption of £500 is reduced by £1, so that when the value reaches the sum of £2,500 there is no exemption at all. In cases where the income from any land or mortgages, plus income from all other sources, is less than £200 per annum, and the owner is incapacitated by age or infirmity from supplementing such income, a further exemption may be allowed by the Commissioner upon his being satisfied that the payment of the tax would entail hardship on such owner. All mortgages are assessed at their full nominal value, except where it is satisfactorily shown that owing to depreciation of the security or other cause such value has been diminished. In the case of mixed mortgages, that is, mortgages which are secured on both real and personal property, the amount of the mortgage chargeable with land tax is taken to be the assessed value of the land included in the security, the interest derived from the balance of mortgage being liable to income tax.

The graduated land tax is imposed on all land possessing an unimproved value of £5,000 and upwards, an important difference between the two taxes being that the mortgagee escapes the graduated tax, and no deduction is allowed to the mortgagor in consideration of any sum which may be advanced on the property. It is provided that on an unimproved value of £5,000 and under £7,000,  $\frac{1}{4}$ d. per £ shall be payable; on £7,000 and under £9,000,  $\frac{1}{2}$ d.; on £9,000 and under £11,000,  $\frac{3}{4}$ d.; £11,000 and under £13,000, 1d.; £13,000 and under £15,000,  $1\frac{1}{4}$ d.; £15,000 and under £17,500,  $1\frac{1}{2}$ d.; £17,500 and under £20,000,  $1\frac{3}{4}$ d.; £20,000 and under £22,500, 1d.; £22,500 and under £25,000,  $1\frac{1}{2}$ d.; £25,000 and under £27,500,  $1\frac{3}{4}$ d.; £27,500 and under £30,000,  $1\frac{1}{2}$ d.; £30,000 and under £35,000,  $1\frac{3}{4}$ d.; £35,000 and under £40,000,  $1\frac{1}{2}$ d.; £40,000 and under £45,000,  $1\frac{3}{4}$ d.; £45,000 and under £50,000,  $1\frac{1}{2}$ d.; £50,000 and under £55,000, 1d.; £55,000 and under £60,000,  $1\frac{1}{4}$ d.; £60,000 and under £65,000,  $1\frac{1}{2}$ d.; £65,000 and under £70,000,  $1\frac{1}{4}$ d.; £70,000 and under £75,000,  $1\frac{1}{2}$ d.; £75,000 and under £80,000,  $1\frac{1}{4}$ d.; £80,000 and under £85,000,  $1\frac{1}{2}$ d.; £85,000 and under £90,000,  $1\frac{1}{4}$ d.; £90,000 and under £95,000

1½d. ; £95,000 and under £100,000, 1¾d. ; £100,000 and under £105,000, 1½d. ; £105,000 and under £110,000, 1½d. ; £110,000 and under £115,000, 1½d. ; £115,000 and under £120,000, 1½d. ; £120,000 and under £125,000, 1½d. ; £125,000 and under £130,000, 1½d. ; £130,000 and under £135,000, 2d. ; £135,000 and under £140,000, 2½d. ; £140,000 and under £145,000, 2½d. ; £145,000 and under £150,000, 2½d. ; £150,000 and under £155,000, 2½d. ; £155,000 and under £160,000, 2½d. ; £160,000 and under £165,000, 2½d. ; £165,000 and under £170,000, 2½d. ; £170,000 and under £175,000, 2½d. ; £175,000 and under £180,000, 2½d. ; £180,000 and under £185,000, 2½d. ; £185,000 and under £190,000, 2½d. ; £190,000 and under £195,000, 2½d. ; £195,000 and under £200,000, 2½d. ; £200,000 and under £205,000, 2½d. ; £205,000 and under £210,000, 2½d. ; and £210,000 and over, 3d. in the £ ; and it is further provided that an absentee, who is declared to be a person who has been absent from or resident out of the colony for a period of not less than one year next preceding the date of the passing of the annual taxing act, shall pay a graduated tax of 50 per cent. additional to the schedule rates.

It is provided that returns of land and mortgages shall be made biennially. Purchasers of Crown lands on credit are liable to taxation, and the owner of a leasehold interest in land is liable to taxation in respect of the value of such interest. The exemptions comprise Crown lands ; lands vested in the Railway Commissioners and in local governing bodies ; land used solely in connection with a place of worship or a place of residence for the clergy of any religious body, or in connection with public schools established under the Education Act of 1877, or with any other school not carried on exclusively for gain or profit, but the maximum area of land exempted for the purposes of any school carried on for profit is 15 acres ; the site of a university or college, or school incorporated by any Act or Ordinance, or the site of a public library, atheneum, mechanics' institute, or school of mines ; a public cemetery or burial-ground ; the ground or place of meeting of any agricultural society, provided it be the property of such society ; the place of meeting of a friendly society or Masonic lodge, or of a registered building society ; land used for the purposes of public charitable institutions constituted under the Hospitals and Charitable Institutions Act, and of other charitable institutions not carried on for gain or profit ; public gardens, domains, or recreation or other public reserves not occupied by a tenant, and all public roads and streets ; land owned and occupied by Maoris, and not leased to or occupied by any person other than the Maori owner ; and any public railway, including the land occupied and used as permanent way and for yards, stations, and sheds, and all buildings used for the purposes of railway traffic only. Further exemptions comprise all land owned and mortgages held by any friendly society within the meaning of the Act ; all land owned and mortgages held by any savings bank constituted under the Savings Bank Act of 1858 ; all land owned and mortgages held by the Commissioners of Sinking Funds

under the Public Debts Sinking Funds Act of 1868, or by the trustees of any local authority whose revenues are exempt from taxation; and all mortgages held by or on behalf of any charitable institution.

Still another exemption is provided for, namely, all land owned and mortgages held by or on behalf of any religious body, the proceeds of which land and mortgages are devoted to the support of aged or infirm ministers, or of widows or orphan children of ministers. It is also declared that native land occupied by any other person than the Maori owner shall be subject to one-half of the ordinary land tax in respect of the Maori landowner's interest therein, while being exempt from the graduated tax, and that all mortgages held by or in trust for Maoris shall be liable to the payment of ordinary land tax. Mortgages held by banking companies are reached by the income tax; and land owned and mortgages held by any registered building society are exempted from taxation, the profits derived by members being subject to income tax. In the event of land being undervalued, the Commissioner may give notice to the owner, within twelve months of the signing of the assessment roll, that he must increase the value of the land to the sum placed upon it by the taxation authorities. If the owner is not willing to increase the value to the sum notified by the Commissioner, he may appeal to the Resident Magistrate to assess the value; but should he neither adopt this course nor consent to the Commissioner's valuation within thirty days, the Commissioner may recommend that the Government shall purchase the land at the returned value plus 10 per cent. On the other hand, if the owner is not satisfied with the value at which the land has been assessed, whether by the Board of Review or not, he may call upon the Commissioner to reduce the valuation to a certain sum or to purchase the land at this price.

The income tax is payable upon income derived from employment and from business, including investments other than those in mortgages of land, upon which ordinary land tax is levied. An exemption of £300 is allowed to every person domiciled in the colony, this concession being withheld from absentees; but no exemption is allowed to a public company. The rate of tax is 6d. in the £ on the first taxable £1,000, and 1s. on every additional £, except in the case of public companies which pay 1s. per £ on the whole sum. The income of public companies is declared to be the amount of dividends earned, sums carried to reserve fund, and any other profits made or income derived by such companies. To this provision exception is made in the case of banking companies, insurance companies, shipping companies, and loan, building, and investment companies. It is provided that every banking company shall be assessed for income tax at the rate of 7s. 6d. per £100 of the average of the total liabilities and assets for the four quarters of the preceding year. The shareholders of loan, building, and investment companies are personally taxed upon the amount of income derived from such societies. The regulations declare that a person or company engaged in business as the owner or charterer of shipping shall be

assessed upon the income derived from such business carried on in New Zealand and with places beyond the colony; and that when the head office of a person or company engaged in such business is outside the colony the agent shall be liable to the payment of income tax of 5 per cent. of the receipts from the carriage of passengers, goods, and live stock shipped at New Zealand ports. It is also provided by these regulations that the income of every insurance company shall be taken as the income derived from business carried on in the colony, and from investments within the colony other than those in land and in mortgages of land. The exemptions to the income tax comprise the revenues of any county council, borough council, town board, road board, harbour board, public university, public school, education board, school commissioners, licensing committee, and every other local authority receiving revenue of any kind for the purposes of or in relation to local self-government; the income of friendly societies and building societies, and of all public bodies and societies not carrying on business for purposes of gain to be divided amongst the shareholders or members; and income derived by the owner or occupier from any land on which land tax is payable, and from mortgages of such land. The income of any savings bank constituted under the Savings Bank Act of 1858, and the income of any public charitable institution, are also exempted. Also, when a person occupies for purposes of business or employment land on which he pays land tax, he is allowed to deduct from his income a sum equal to 5 per cent. on the amount on which he is liable to pay land tax. It is imperative that a person who does not reside permanently in the colony, and who offers or exposes goods for sale or disposition by sample or otherwise, shall take out an annual license, the fee for which is fixed by regulation at £50.

There are about 115,713 landowners in New Zealand, and of these 20,865 pay tax, the remainder being exempted from one cause or another. The land tax yielded £335,122 for the year ended 31st March, 1904, of which £232,906 came from ordinary land tax and £102,216 from graduated tax, the latter amount including £3,536, imposed upon persons who have been absent from the colony for not less than one year prior to the passing of the yearly taxing act. The total value of land subject to taxation is £35,550,809 out of a total unimproved value of £70,524,604. The following is a statement of the tax levied during the past six years:—

Year ended 31st March.	Ordinary Land Tax.	Graduated Land Tax.	Total Amount of Land Tax.
	£	£	£
1898	196,000	73,000	269,000
1899	215,000	83,000	298,000
1900	214,000	80,000	294,000
1901	222,000	72,000	294,000
1902	234,000	79,000	313,000
1903	217,000	79,000	296,000
1904	232,906	102,216	335,122

The income tax returns have shown great expansion during the last four years ; indeed, the yield shows substantial increases in almost every year since the first imposition of the tax. The revenue obtained during each of the last ten years was as follows:—

Year ended 31st March.	Income Tax Paid.	Year ended 31st March.	Income Tax Paid.
	£.		£
1895	89,891	1900	128,721
1896	92,778	1901	173,609
1897	105,504	1902	179,397
1898	115,210	1903	200,684
1899	115,480	1904	221,369

The number of taxpayers for 1904 was 8,258, including 489 absentees and 605 companies. The total incomes assessed for taxation cannot be stated, but the taxable amount was reduced to £5,767,984 by exemptions. The incomes of companies are assessed at £2,600,020, and of absentees £181,712.

The cost of collection in each of the states imposing either land or income taxes, or both combined, varies considerably. The complex character of the Acts under which the impost is levied necessitates a larger expenditure in some states than in others. In New South Wales, where the machinery for the administration of the land tax is of an elaborate character, taking land and income taxes together, the cost is largely in excess of that of any other state, showing, for the period since the inception of the taxes in 1895-6, an expenditure of 8.52 per cent. of the net receipts. In Victoria, for the ten years ended 30th June, 1904, it was only 3.22 per cent. ; In South Australia, for the same period, 5.75 per cent. ; in Tasmania, for the same period, 4.55 per cent. ; and in New Zealand, for the same period, 3.88 per cent. Queensland has had only two years' experience, and the proportion of cost to net receipts was 5.11 per cent. Covering a period of ten years, the proportion of cost to net receipts, for the whole of Australasia, was 5.26 per cent.

## REVENUE FROM DIRECT TAXATION.

The following table shows the amount of revenue received from the various sources of direct taxation during the year 1903-4 :—

State.	Stamp Duties.		Land Tax.	Income Tax.	Dividend Tax.	Total.
	Probate.	Other.				
	£	£	£	£	£	£
New South Wales .....	225,115	237,455	322,246	193,240	.....	978,056
Victoria .....	308,531	18,440	106,445	311,147	.....	744,563
Queensland .....	96,454	90,535	.....	144,488	*89,453	420,930
South Australia .....	72,926	61,899	77,370	121,469	.....	333,664
Western Australia .....	21,769	55,768	.....	.....	†125,071	202,598
Tasmania .....	4,750	42,093	50,881	337,529	.....	135,253
Commonwealth .....	729,535	506,190	556,942	807,873	214,524	2,815,064
New Zealand .....	142,917	252,275	334,991	221,369	‡3	951,555
Australasia .....	872,452	758,465	891,933	1,029,242	214,527	3,766,619

\* Includes £11,598 from Totalisator Tax. † From Companies' Tax. ‡ Property-tax.  
‡ Includes Dividend Tax.

## LAND REVENUE.

The practice of treating as ordinary revenue money derived from the sale and occupation of Crown lands obtains in all the states, and the money so raised forms in several states a large item of income. The propriety of so doing is open to grave doubt, but the argument used in its justification is that the sums so obtained have enabled the Government either to construct works, which both enhance the value of the remaining public lands and facilitate settlement, or to endow municipalities, and thus enable them to carry out local works. The revenue from land sales is declining year by year, both absolutely and as compared with population. In New South Wales and South Australia the falling-off has been most noticeable; in the former state the revenue from this source is now some £1,367,000 less than was the case in 1881, while in South Australia the revenue from land sales is only £51,000.

Adopting the division of land revenue into receipts from sales and receipts from occupation, the following table shows the income for 1881 :—

State.	Total Land Revenue, 1881.			Land Revenue per head.		
	From Auction and other classes of sales.	Occupation, &c., of Crown lands.	Total.	From Auction and other classes of sales.	Occupation, &c., of Crown lands.	Total.
	£	£	£	£ s. d.	£ s. d.	£ s. d.
New South Wales .....	2,483,338	337,651	2,820,989	3 4 11	0 8 10	3 13 9
Victoria .....	701,276	135,194	836,470	0 16 4	0 3 2	0 19 6
Queensland .....	435,664	186,893	622,557	2 0 6	0 17 5	2 17 11
South Australia .....	651,914	97,042	748,956	2 8 9	0 7 3	2 16 0
Western Australia .....	5,750	34,695	40,445	0 3 11	1 3 6	1 7 5
Tasmania .....	37,269	39,487	76,756	0 6 5	0 6 9	0 13 2
Commonwealth .....	4,315,211	830,962	5,146,173	1 17 10	0 7 3	2 5 1
New Zealand .....	376,461	174,479	550,940	0 15 4	0 7 1	1 2 5
Australasia .....	4,691,672	1,005,441	5,697,113	1 14 2	0 7 4	2 1 6

Compared with 1881, the land revenue for 1903-4 shows a large decline, amounting to £1,803,768 for the states included in the Commonwealth, and to £2,106,866 for the whole of Australasia. The falling-off is found entirely in the amount of revenue from sales, that derived from rents having largely increased in all the states except Victoria and Tasmania. However, general remarks applicable to all the states can scarcely be made. New South Wales obtained £2,483,338 from land sales in 1881, out of a total of £4,691,672 for all the states, or more than one-half; while from occupation its revenue was £337,651 out of £1,005,441, or little more than one-third. In 1903-4 the revenue of the state from sales amounted to £1,116,061—still a large amount, but £1,367,277 short of the receipts of 1881. In regard to occupation, a different condition of things is disclosed. The receipts in New South Wales during 1903-4 totalled £744,509, or an increase of £406,858 as compared with 1881, and amounting to 49·11 per cent. of the total of the states comprising the

Commonwealth, or to 43·59 per cent. of the total for Australasia. The following are the figures for 1903-4 :—

State.	Total Land Revenue, 1903-4.			Land Revenue per head.		
	From Auction and other classes of sales.	Occupation, &c., of Crown lands.	Total.	From Auction and other classes of sales.	Occupation, &c., of Crown lands.	Total.
	£	£	£	£ s. d.	£ s. d.	£ s. d.
New South Wales . . . . .	1,116,061	744,509	1,860,570	0 15 7	0 10 5	1 6 0
Victoria . . . . .	278,554	106,154	384,708	0 4 7	0 1 9	0 6 4
Queensland . . . . .	314,298	322,782	637,080	0 12 1	0 12 5	1 4 6
South Australia . . . . .	51,079	130,529	181,608	0 2 9	0 7 1	0 9 10
Western Australia . . . . .	25,077	180,777	205,854	0 2 2	0 16 0	0 18 2
Tasmania . . . . .	41,231	31,354	72,585	0 4 8	0 3 6	0 8 2
Commonwealth . . . . .	1,826,300	1,516,105	3,342,405	0 9 4	0 7 8	0 17 0
New Zealand . . . . .	56,072	191,770	247,842	0 1 4	0 4 7	0 5 11
Australasia . . . . .	1,882,372	1,707,875	3,590,247	0 7 10	0 7 3	0 15 1

In all the states, New South Wales and Victoria excepted, a general sinking fund is established to assist in the redemption of public loans on maturity, and in New South Wales and Victoria special sinking funds have been inaugurated in connection with portions of the local funded stocks. The desirableness of establishing a general sinking fund is on all sides admitted, and a portion of the proceeds of land sales could with advantage be set apart from the general revenue and devoted to this purpose. Victoria deals with a portion of the proceeds from the sale of Crown lands apart from the general revenue, and at the close of the financial year 1890-1 a sum of £578,740 derived from that source had been placed to the credit of the Railway Construction Account; while since that year various sums amounting to £678,532 have been appropriated on account of the "Land Sales by Auction Fund" for expenditure on public works, and a total of £381,349 has been received from sales, &c., leaving a debit balance of £297,183 on the 30th June, 1904.

#### HEADS OF EXPENDITURE.

The amount disbursed by the Government of New South Wales is far larger than that expended by any other state of the group; in the last financial year it exceeded the expenditure of Victoria by £4,404,894, was nearly twice as great as that of New Zealand, and was nearly one million and a half more than the united expenditure of Queensland, South Australia, and Western Australia. This is chiefly owing to the absence of a complete system of local government in New South Wales, and the system of centralisation already referred to. The following is a



statement of the expenditure of each state during the financial year 1903-4 :—

State.	Railways and Tramways.	Posts and Telegraphs.	Public Instruction.	Interest and charges on Public Debt.	All other Services.	Total Expenditure.
	£	£	£	£	£	£
New South Wales .....	2,921,026	.....	906,975	2,114,760	4,378,126	11,319,887
Victoria .....	1,894,553	.....	657,565	2,169,060	2,203,825	6,914,993
Queensland .....	810,251	.....	214,809	1,547,321	985,883	3,607,864
South Australia .....	693,600	.....	154,320	1,120,731	738,702	2,707,253
Western Australia .....	1,223,235	.....	134,337	714,634	1,621,106	3,693,312
Tasmania .....	166,851	.....	70,973	840,095	302,837	1,379,856
Commonwealth .....	7,714,016	.....	2,236,569	8,906,601	10,180,479	29,127,665
New Zealand .....	1,461,954	524,500	583,860	1,967,963	1,911,004	6,434,281
Australasia .....	9,165,970	524,500	2,820,429	10,964,564	12,091,483	35,561,946

It will be seen from the foregoing figures that for the states of the Commonwealth 26·5 per cent. of the whole expenditure is for working the railways—a service not undertaken by the Government in the United Kingdom and the United States. Public instruction accounts for 7·7 per cent., and interest on the public debt, 30·9 per cent. For the whole of Australasia the corresponding percentages are:—Railways, 25·8; public instruction, 7·9; and interest on the public debt, 30·9 per cent.

Adopting the classification of expenditure used in the preceding table, the amounts per inhabitant of each province are given below. It may be here mentioned that in New South Wales, and to some extent in South Australia and Western Australia, the tramways are the property of the state, and are under the same management as the railways, with which they are included in the various statements in this sub-chapter relating to revenue and expenditure:—

State.	Railways and Tramways.	Posts and Telegraphs.	Public Instruction.	Interest and charges on Public Debt.	All other Services.	Total Expenditure.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
New South Wales..	2 0 10	.....	0 12 8	2 3 6	3 1 2	7 18 2
Victoria .....	1 11 4	.....	0 10 11	1 15 9	1 16 5	5 14 5
Queensland .....	1 11 1	.....	0 12 1	2 9 6	1 15 11	6 18 7
South Australia...	1 17 8	.....	0 8 5	3 0 10	2 0 1	7 7 0
Western Australia..	5 8 1	.....	0 11 10	3 2 11	7 2 9	16 5 7
Tasmania .....	0 18 8	.....	0 7 10	1 18 2	1 13 11	4 18 7
Commonwealth	1 19 2	.....	0 11 4	2 5 9	2 11 9	7 8 0
New Zealand .....	1 15 2	0 12 8	0 14 3	2 7 5	2 6 3	7 15 9
Australasia .....	1 18 6	0 2 2	0 11 10	2 6 0	2 10 10	7 9 4

The most remarkable feature in the general expenditure of the Australasian states is the largeness of the amount required to pay interest and charges on the public debt, both in regard to the rate per head and the proportion of total revenue thus hypothecated. The proportion for the states of the Commonwealth is 30·89 per cent. of the total expenditure, or £2 5s. 9d. per head of population, and for the whole of Australasia 30·80 per cent., or £2 6s. 0d. per head. The actual expenditure for each state during 1903-4 was as shown below. The amounts given are actual payments made during the financial year, and do not represent the interest liabilities of that period, the amounts of which will be found on page 703 :—

State.	Interest and Charges on Public Debt.		
	Total.	Per head of Population.	Proportion of Total Expenditure.
	£	£ s. d.	per cent.
New South Wales .....	3,114,760	2 3 6	27·51
Victoria .....	2,159,050	1 15 9	31·22
Queensland .....	1,547,331	2 19 6	42·88
South Australia .....	1,120,731	3 0 10	41·40
Western Australia .....	714,634	3 2 11	19·32
Tasmania .....	340,095	1 18 2	38·68
Commonwealth .....	8,996,601	2 5 9	30·89
New Zealand .....	1,957,963	2 7 5	30·43
Australasia .....	10,954,564	2 6 0	30·80

A casual glance at the figures quoted will lend colour to the suggestion sometimes hazarded that the states are too rapidly mortgaging their resources, and that the expense of the public debt will prove a greater burthen than can easily be borne. However true this may be so far as any individual state is concerned, it is certainly erroneous as regards the whole of Australasia. Out of the sum of £8,996,601 required to pay interest and charges on the public debt by the states of the Commonwealth during 1903-4, £4,285,960 was directly recouped by the net revenue from public railways. Water supply and sewerage yielded a sum of £629,354, the net revenue from harbour and river improvements was £184,905, and the interest on advances to settlers, local bodies, and on the purchase of lands for settlement yielded a further sum of £140,584, making a total of £5,240,803. Including New Zealand, the sum required to pay interest and charges on the public debt was £10,954,564, but of this £6,294,087 was directly recouped, viz., £5,001,998 by the net revenue from railways, £629,354 by water supply and sewerage, together with £662,735, representing the net revenue from harbour and river improvements, interest on

advances to settlers and local bodies, and on the purchase of land for settlement. Besides this, there is a large indirect revenue obtained by each of the states from the opening-up of its public lands, and from the construction of breakwaters, wharves, bridges, and other works of public utility. But even these advantages might have been bought at too high a price if production had not correspondingly advanced. Fortunately such has been the case, as will be seen from the chapters in this volume which deal with the leading items of Australasian production.

#### ADJUSTED REVENUE AND EXPENDITURE.

The form in which the public accounts of the states are presented has led to a great deal of misconception regarding the actual requirements of the various Governments for public purposes. Nor has it been possible to do other than follow that form in the foregoing pages, as otherwise the figures quoted would differ from the various Treasury statements, and add another element of confusion; nevertheless, it would be well before closing the remarks on this branch of public finance to make a separation of the items of revenue and expenditure according to the principles which should govern the presentation of the public accounts. This is effected by treating the services which are generally regarded as outside the functions of the central Government, viz., railways and tramways, water supply and sewerage, harbours, rivers, and navigation, advances to settlers, loans to local bodies, and the purchase of land for settlement, as matters apart from the general receipts and expenditure, and only crediting the state with the surplus from, or debiting it with the cost of these services, after deducting working expenses and making allowance for the estimated interest on the invested capital. Posts and telegraphs have not been excluded in the case of New Zealand, but the exclusion has been made from the returns of the six states of the Commonwealth as the administration is now with the Federal Government. The adjusted revenue for the year 1903-4 will be found below :—

State.	Revenue, excluding Services.	Net Revenue from Services.	Total adjusted Revenue.	Per head of Population.
	£	£	£	£ s. d.
New South Wales.....	6,120,640	.....	6,120,640	4 5 6
Victoria .....	3,639,225	.....	3,639,225	3 0 2
Queensland .....	2,197,261	.....	2,197,261	4 4 5
South Australia.....	1,203,858	.....	1,203,858	3 5 5
Western Australia.....	1,859,149	43,480	1,902,629	8 7 6
Tasmania .....	599,089	.....	599,089	3 7 2
Commonwealth .....	15,619,222	43,480	15,662,702	3 19 7
New Zealand .....	4,030,736	.....	4,030,736	4 17 7
Australasia .....	19,649,958	43,480	19,693,438	4 2 9

It will be seen that Western Australia was the only state that obtained a revenue from its services during 1903-4, after working expenses and interest on capital had been allowed for, a result brought about chiefly by the decrease in the revenue of most of the states, due to the after effects of the prolonged drought. The next table shows the adjusted expenditure :—

State.	Expenditure, excluding Services.	Net Expenditure on Services.	Total adjusted Expenditure.	Per head of Population.
	£	£	£	£ s. d.
New South Wales .....	5,483,655	708,544	6,192,199	4 6 6
Victoria .....	3,214,776	25,851	3,240,627	2 13 7
Queensland .....	1,706,725	502,960	2,209,685	4 4 11
South Australia .....	1,192,578	150,432	1,343,010	3 12 11
Western Australia .....	2,050,925	.....	2,050,925	9 0 7
Tasmania .....	534,538	88,239	620,777	3 9 7
Commonwealth .....	14,183,197	1,474,026	15,657,223	3 19
New Zealand .....	3,262,260	72,641	3,334,901	4 0 9
Australasia .....	17,445,457	1,546,667	18,992,124	3 19 9

The figures just given show that the actual cost of government is materially less in the states than would appear from the returns of ordinary revenue and expenditure.

#### POSITION OF REVENUE ACCOUNTS.

The following table has been compiled with the view of showing the position of the Revenue Account of each state at the close of the last financial year. It will be seen that five of the states have large overdrafts, partly cash and partly in the form of Treasury bills, and that to establish the necessary equilibrium between income and outgo a restricted expenditure by future administrations will be absolutely necessary. For Tasmania the figures refer to the end of the year 1903 ; for New Zealand, to the 31st March, 1904 ; and for the other five states, to the 30th June, 1904. The figures given in the last column of the table represent the total debit balances at these dates. It is very necessary

that this fact should be borne in mind, as it often happens that the official returns of the states show only the cash overdraft, the amount represented by outstanding Treasury bills being omitted from consideration :—

State.	Cr. Balance.	Dr. Balance.		
		Overdraft represented by Treasury Bills.	Cash Overdraft.	Total Dr. Balance.
	£	£	£	£
New South Wales.....	.....	1,977,626	524,064	2,501,690
Victoria .....	.....	75,000	2,156,119	2,231,119
Queensland.....	.....	1,130,000	35,705	1,165,705
South Australia.....	.....	1,088,950	364,189	1,453,139
Western Australia .....	83,364	.....	.....	.....
Tasmania.....	.....	107,380	234,545	341,875
Commonwealth .....	83,364	4,378,906	3,314,622	7,693,528
New Zealand .....	837,966	.....	.....	.....
Australasia.....	921,350	4,378,906	3,314,622	7,693,528

It will be seen that for the state of New South Wales the table shows an overdraft of £1,977,626 which has been liquidated by Treasury bills, and a cash overdraft on 30th June, 1904, of £524,064, inclusive of £484,356 brought forward from the previous year. In reference to the South Australian cash overdraft of £364,189, it should be pointed out only £32,230 represents the debit balance for South Australia proper, while the overdraft liquidated by Treasury bills belongs both to South Australia proper and the Northern Territory. During the year ended 30th June, 1903, the Government issued Treasury bills liquidating the cash overdraft on the 30th June, 1902, for the state proper.

The condition of the revenue accounts of New South Wales, Victoria, and New Zealand needs further explanation. In New South Wales land was resumed in 1889 for the purpose of facilitating certain improvements in connection with a street facing the General Post-office, Sydney, and it was determined that the sum paid for resumption should not be treated as a matter of ordinary expenditure, but be held in suspense pending the sale of the land resumed, or so much of it as was not needed for the formation of the Post-office street. Another resumption of land by the Government of New South Wales was authorised by the Centenary Celebration Act of 1887, which provided for the acquisition of a large area of land, close to Sydney, for the formation of a public park to

commemorate the centenary of the state. Of the area so acquired, 640 acres were to be set aside for the park, and the remainder was to be sold, and the proceeds placed against the expenditure. So far no sales have been effected, and in 1894 the payments on account of the formation of the park were transferred from the Consolidated Revenue Fund Account to a special Suspense Account. On the 30th June, 1901, the debit balance of the Centennial Park Account was £228,417, and of the General Post-office New Street Resumption Account, £376,762, neither of which amounts is included in the above table. Legislation has been passed, and Treasury bills have been issued covering the liability under the Suspense Accounts referred to, and the replacing of £150,000 to the credit of the sinking fund for Railway Loan, 53 Vic. No. 24, which was applied to the redemption of the balance of Railway Loan, 31 Vic. No. 11. The authority was for the issue of Treasury bills to the amount of £755,179, which will cover all deficiencies to 30th June, 1902, with the exception of the debit balance of the Consolidated Revenue Fund. Provision was made that on the 31st December, 1902, and on the same day in each year thereafter, until all the payments provided for have been made, the sum of £100,000 was to be paid from the Consolidated Revenue Fund to the credit of the respective accounts mentioned. Such annual sums are in the first place to be paid to the credit of a special Trust Account. In addition to the annual sum of £100,000, the net proceeds of the sales of the unsold portions of the land resumed under the General Post Office (Approaches Improvement) Act of 1889, and the net proceeds of the sale of the unsold portions of the land referred to in the Centenary Celebration Act of 1887 (Centennial Park), are to be paid to the credit of the account. The moneys at credit of such account are to be applied to the purpose of redeeming the bills issued under the Treasury Bills Deficiency Acts of 1901 and 1902, and when all such bills have been redeemed the account is to be closed. The appropriation of £100,000 is, however, to continue to redeem bills issued under the Deficiency Act of 1889, and on the redemption of these bills, the same annual appropriation is to be applied to redeem bills issued under the Deficiency Act of 1895. When this has been effected the appropriation is to lapse. The annual appropriation of £150,000 under the Deficiency Act of 1889 continues, so that the total annual appropriation for the liquidation of the unfunded debt for revenue purposes will be £250,000.

In Victoria certain public works to the amount of £678,624 were undertaken on the understanding that the cost should be defrayed from the proceeds of the sale of certain lands specifically set apart for the purpose. These works have been constructed, but the sales have fallen short to the extent of £297,183, and this sum has been placed to a Suspense Account, which is likewise excluded from the debit balance given above. In the credit balance of New Zealand, shown on page 697, allowance has been made for the transactions of several Suspense Accounts, viz., the State Forests Account, the Local Bodies Account,

the Deposits Account, and the State Coal Mines Account ; but in order to place the revenue and expenditure of that colony on the same footing as those of the other provinces, the operations on the accounts referred to have not been taken into consideration in the table on page 661. The credit balance of the Consolidated Revenue Fund proper amounted to £649,741.

The practice of issuing Treasury bills for the purpose of liquidating an overdraft, which is illustrated by the above table, obtains in all the states. The bills have been sometimes compared to the exchequer bills issued by the British Treasury. There is, however, only a slight resemblance between the two. The British exchequer bills bear interest at a rate which is fixed from year to year, and at the end of every twelve months the holder has the option of retaining them or presenting them at the Treasury for payment. They are, therefore, readily saleable, and are used with great freedom in commercial transactions, for, as will be seen, they combine the two advantages of ready money and money bearing interest. The Treasury bills of these states, on the other hand, are only payable at the Treasury on the expiry of the period for which they are issued, and they carry interest at a fixed rate during the whole term of currency ; consequently they are not used to any extent in commerce. The nearest approach to the British system is that prevailing in New Zealand, where Treasury bills to the amount of £700,000 are outstanding at the close of the financial year, but are redeemed early in the following year. With the exception of these New Zealand bills, Treasury bills are regarded as unfunded or floating debt, and until wiped off form part of the public debt.

#### TRUST FUNDS.

It may be pointed out here that all the Governments in Australasia hold sums in trust, either directly or indirectly. In some instances these sums are considerable, and are found extremely useful in adjusting the finances, forming a strong reserve which a Government is able to use in tiding over temporary difficulties. It is, however, very questionable whether the existence of a large balance, out of which a necessitous Treasurer can make advances to an overdrawn Revenue or Loans Account, is desirable. In past years it has led to much extravagance that a Treasurer forced to rely on the legitimate revenue of the country would have been compelled to avoid. Several states have seen this, and in Victoria, New Zealand, and South Australia, public trustees have been appointed to control Trust Funds in the hands of the Government ; but in the other states these funds are directly subject to the Treasury. The following are the balances of the Trust Funds at the close of the financial year, exclusive of the Funds now dealt with by the Federal Government. The figures for New South Wales, Victoria, Queensland, South Australia, and Western Australia, are for the year ended 30th June, 1904 ; for

Tasmania, for the year ended 31st December, 1903; and for New Zealand, for the year ended 31st March, 1904:—

State.	Invested.	Uninvested.	Total.
	£	£	£
New South Wales.....	6,807,829	3,883,331	10,191,160
Victoria .....	3,728,986	5,023,413	8,752,399
Queensland .....	3,210,973	402,808	3,613,781
South Australia .....		372,508	372,503
Western Australia .....	3,076,549	773,360	3,849,849
Tasmania .....	601,012	53,479	654,491
Commonwealth .....	16,925,349	10,508,834	27,434,183
New Zealand .....	9,213,887	154,435	9,368,322
Australasia .....	26,139,236	10,663,269	36,802,505

The New Zealand figures include £1,660,716 in the hands of the Public Trustees.

#### GROWTH OF PUBLIC DEBT.

The practice of raising money for state purposes by means of public loans was begun in 1842, when New South Wales issued debentures redeemable in two years and bearing interest at the rate of 8 per cent. per annum. The sum raised—£45,900—was devoted to immigration purposes. This, as well as the succeeding loans, nine in number, raised prior to 1855, was obtained locally; in the year named, however, New South Wales placed on the London market the first instalment of a 5 per cent. loan for £683,300, which was the first external loan raised, and may be rightly said to mark the commencement of the present Australasian indebtedness.

So far as most of the states are concerned, their public debts date from about the time of their assuming the control of their own affairs; but Western Australia, which obtained responsible Government in 1890, incurred liabilities in London as far back as 1872. In the case of that state, however, the granting of Parliamentary government was unduly delayed. The following table is interesting as showing the liabilities of each of the provinces at the date of its taking charge of its own affairs:—

State.	Date of obtaining Responsible Government.	Amount of Debt Liability at that date.
		£
New South Wales .....	1855	1,366,770
Victoria .....	1855	490,000
Queensland .....	1859	Nil.
South Australia .....	1856	294,900
Western Australia.....	1890	1,367,444
Tasmania.....	1855	Nil.
New Zealand .....	1856	Nil.



No feature of Australasian finance is so astonishing as the growth of the public indebtedness, and this fact has formed the gravamen of the many indictments which have been urged against the states during recent years. The debts have undoubtedly grown at a much more rapid pace than the population; but as the states were in an entirely undeveloped state when public borrowing first came into favour, the more rapid growth of their indebtedness as compared with the population was in a sense the corollary of the position taken up by the various Governments—that the state should reserve to itself the construction of railways and similar undertakings which in other countries are prosecuted by private enterprise. Even with this explanation, however, the figures in the following statement are sufficiently striking:—

State.	1861.	1871.	1881.	1891.	1901-2.	1903-4.
	£	£	£	£	£	£
New South Wales .....	4,017,630	10,614,330	16,924,019	52,950,733	71,592,485	80,083,581
Victoria .....	6,345,060	11,994,800	22,422,502	43,638,897	50,938,967	51,819,962
Queensland .....	70,000	4,047,860	13,245,150	29,457,134	39,338,427	41,781,237
South Australia .....	866,500	2,167,700	11,196,800	20,347,125	27,272,545	28,593,645
Western Australia .....	1,750	Nil.	511,000	1,618,594	14,942,310	16,090,288
Tasmania .....	Nil.	1,815,200	2,003,000	7,110,390	9,095,735	9,318,400
Commonwealth .....	11,300,940	30,139,880	66,306,471	156,117,773	213,175,459	227,687,163
New Zealand .....	600,761	8,900,991	29,659,111	33,844,914	52,968,447	57,522,215
Australasia .....	11,901,701	39,040,871	96,965,582	199,962,687	266,141,906	285,159,878

The Queensland figures are inclusive of £1,082,060 for Savings Bank Inscribed Stock.

The amounts for the year 1903-4 represent both funded and unfunded debt. In round figures the increase for the states of the Commonwealth from 1861 to 1871 was 19 millions; from 1871 to 1881, 36 millions; from 1881 to 1891, 89 millions; and from 1891 to 1903-4, 72 millions; or for the whole of Australasia, from 1861 to 1871, 27 millions; from 1871 to 1881, 57 millions; from 1881 to 1891, 98 millions; and from 1891 to 1903-4, 91 millions. It must be pointed out that the figures in the last column show the public indebtedness as represented by outstanding debentures or stock; but the real sum is less by the amount of sinking funds in the case of all the states viz, New South Wales, £369,621; Victoria, £271,687; Queensland, £8,159; South Australia, £114,476; Western Australia, £864,752; Tasmania, £180,257; and New Zealand, £2,457,887. In New South Wales, sinking funds have been established in connection with some of the recent loans for the purpose of extinguishing portions of the expenditure on works of an unproductive character, the total amount accrued to 30th June, 1904, being £294,621. There are also annual payments on account of one of the railway loans and the Treasury bills in aid of revenue, but the instalments in the latter case are deducted annually, and the net indebtedness is shown in the statement of the

public debt, while for the redemption of the railway loan an amount of £75,000 was in hand at the same date, the sum of £525,000 having been applied during the year just closed in liquidation of debentures that had matured.

The figures showing the total amount of the debt of each state would be incomplete without corresponding information respecting the debt per head of population. In 1861 the public debt of the states included in the Commonwealth stood at £9 13s. 8d. per inhabitant; in 1871, at £17 13s. 11d.; in 1881, at £28 10s. 9d.; in 1891, at £47 14s. 1d.; in 1901-2 it was £55 3s. 10d.; in 1902-3 it was £57 1s. 5d, while in 1903-4 it was £57 8s. 8d. The corresponding figures for Australasia were: in 1861, £9 8s.; in 1871, £19 16s. 4d.; in 1881, £34 0s. 2d.; in 1891, £49 18s. 4d.; in 1901-2, £57 4s. 8d.; in 1902-3, £59 1s. 3d., and in 1903-4, £59 7s. 6d. For each state the figures are as follows:—

State.	1861.	1871.	1881.	1891.	1901-2.	1902-4.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
New South Wales .....	11 4 5	20 10 0	21 14 8	45 10 8	51 6 0	55 7 2
Victoria .....	11 14 3	16 0 11	25 9 7	37 14 4	42 4 2	42 19 4
Queensland .....	2 0 9	82 6 11	58 7 2	73 12 5	76 8 6	79 11 5
South Australia .....	6 16 8	11 13 7	39 2 1	62 9 11	75 2 10	77 9 1
Western Australia .....	0 2 3	NIL	17 0 6	30 5 8	71 14 6	67 12 1
Tasmania .....	NIL	12 18 5	16 16 10	46 11 10	52 4 1	51 18 4
Commonwealth .....	9 13 8	17 13 11	28 10 9	47 14 1	55 3 10	57 8 3
New Zealand .....	6 1 4	33 6 9	59 4 2	61 5 3	67 4 11	65 11 3
Australasia .....	9 8 0	19 16 4	34 0 2	49 18 4	57 4 8	59 7 6

Of the £227,637,163 which constituted the debt of the states of the Commonwealth in 1903-4, £210,539,607 represented funded debt raised either as debentures or as funded or inscribed stock, and £17,097,556 unfunded or floating debt. For the whole of Australasia, the total debt of £283,159,378 was divided into £268,061,822 of funded debt and £17,097,556 of unfunded debt. The particulars for each state will be found below:—

State.	Date.	Debenture Bonds.	Inscribed and Funded Stock.	Treasury Bills.		Total.
				For Works.	In aid of Revenue.	
New South Wales..	30 June, 1904	£ 7,366,150	£ 62,560,505	£ 18,129,300	£ 1,977,638	£ 80,033,593
Victoria .....	30 June, 1904	12,599,236	35,730,867	5,408,900	75,000	51,813,992
Queensland .....	30 June, 1904	13,930,980	26,070,807	.....	1,130,000	41,731,787
South Australia .....	30 June, 1904	9,210,200	17,113,945	1,180,550	1,068,960	28,573,655
Western Australia..	30 June, 1904	436,350	15,663,988	.....	.....	16,099,338
Tasmania .....	31 Dec., 1903	3,046,020	6,164,450	.....	107,330	9,318,800
Commonwealth..	.....	46,639,595	163,900,012	12,718,650	4,378,906	227,637,163
New Zealand .....	31 Mar., 1904	12,219,373	45,302,842	.....	.....	57,522,215
Australasia .....	.....	58,858,968	209,202,854	12,718,650	4,378,906	285,159,373

\* £3,550 overdue.

† £4,000 overdue.

The relative burthen of the public debt of the various states is not to be determined only by comparing the gross amounts with the population, for the rate of interest payable must also be taken into consideration. Thus the general average interest payable by Western Australia is 3·40 per cent., while South Australia pays 3·74 per cent., so that a debt of £100 in the former is not more burthensome than £90 18s. 2d. in the latter state. A more exact basis of comparison is obtained by taking the interest liability, which is shown below. The interest given is on the supposition that the debt is outstanding for the whole of the year following the day on which the amounts are made up. The whole debt, funded and unfunded, has been included :—

State.	Average rate of Interest.			Amount of Interest	
	Funded Debt.	Unfunded Debt.	Total.	Amount on Outstanding Liabilities.	Per Inhabitant.
	per cent.	per cent.	per cent.	£	£ s. d.
New South Wales.....	3·53	3·70	3·55	2,841,368	1 19 4
Victoria .....	3·63	3·79	3·64	1,885,983	1 11 3
Queensland .....	3·70	4·00	3·70	1,547,470	2 18 11
South Australia .....	3·75	3·59	3·74	1,069,325	2 17 11
Western Australia.....	3·40	.....	3·40	547,160	2 6 0
Tasmania ... ..	3·67	3·50	3·68	341,627	1 18 1
Commonwealth.....	3·60	3·66	3·61	8,232,933	2 1 7
New Zealand .....	3·83	.....	3·83	2,203,420	2 12 6
Australasia .. ..	3·66	3·66	3·66	10,436,353	2 3 6

In 1884 the nominal rate of interest on New South Wales loans floated in London was reduced to  $3\frac{1}{2}$  per cent., at which rate stock to the amount of £29,326,200 and Treasury bills for £2,000,000 had been sold to June, 1903. This example was not followed by any of the other states until 1888, when Queensland successfully floated a loan of £2,520,000 at the reduced rate; and in 1889 Victoria, South Australia, Tasmania, and New Zealand, in the order named, were successful in issuing stock at a similar nominal rate. Through the pressure of the financial crisis, the nominal rate for those states which issued in 1893 was increased to 4 per cent. Early in the following year, however, South Australia and Tasmania again placed loans on the market at the lower rate. New Zealand, in May, 1895, was the first colony to issue a 3 per cent. loan—an example which was followed by New South Wales in October of the same year, and by all the states since that date. Tasmania, however, did not place a 3 per cent. loan in London till 1901, but local inscribed stocks had been previously sold at the rate mentioned. Hereunder will

be found the amount of the total debt under each rate of interest. For Tasmania the figures refer to the 31st December, 1903; for New Zealand, to the 31st March, 1904; and for all the other states to the 30th June, 1904:—

Rate of Interest.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
FUNDED DEBT.									
% cent.	£	£	£	£	£	£	£	£	£
NIL.	3,550	1,000	....	....	....	....	4,550	....	4,550
6	2,800	....	....	431,400	....	....	433,700	55,200	488,900
5	60,700	....	....	265,000	17,600	100	343,400	501,500	844,900
4½	....	....	....	....	60,100	....	60,100	52,900	122,000
4	20,441,658	22,383,795	21,384,800	16,302,400	3,968,768	4,045,320	88,986,741	35,500,652	124,588,393
3½	1,500,000	....	....	....	....	....	1,500,000	349,000	1,849,000
3¼	30,576,375	15,013,294	13,777,604	3,363,000	4,694,820	4,200,335	71,625,428	10,772,480	82,397,918
3½	....	....	....	....	....	30,700	30,700	....	30,700
3	17,342,072	10,468,073	5,489,233	5,962,345	7,350,000	934,115	47,545,968	10,191,473	57,737,461
Total	69,926,655	48,336,162	40,651,287	26,324,145	16,090,288	9,211,070	210,530,607	57,522,215	268,061,822
UNFUNDED DEBT. (Treasury Bills for Works and Deficiencies in Revenue.)									
NIL.	4,000	....	....	....	....	....	4,000	....	4,000
4	5,831,800	2,183,800	1,130,000	417,400	....	....	9,563,000	....	9,563,000
3½	325,000	....	....	....	....	....	325,000	....	325,000
3¼	2,000,000	1,075,000	....	1,352,100	....	107,330	5,684,430	....	5,684,430
3½	....	225,000	....	....	....	....	225,000	....	225,000
3	1,946,126	....	....	....	....	....	1,946,126	....	1,946,126
Total	10,103,926	3,483,800	1,130,000	2,369,500	....	107,330	17,097,556	....	17,097,556
Total Debt	80,033,581	51,819,962	41,781,287	28,593,645	16,090,288	9,318,400	227,627,163	57,522,215	285,159,378

The Treasury Bills of New Zealand do not rightly form part of the public debt, and such of these as were outstanding have therefore been excluded from the foregoing statement.

#### REDEMPTION OF LOANS.

Loans are either redeemed or renewed. In the former case, the amount of the obligations of the state to its public creditors is reduced; in the latter case, the liability remains the same or is only slightly

altered. Repayments, however, are chiefly effected under the head of renewals, the amount of loans redeemed from revenue—by sinking fund, annual drawings, or directly from the general account—being small. The principle of extinguishing public debt by the operation of sinking funds or by annual drawings does not extend to the whole of the public debt of Australasia, and the loans affected do not amount to a large sum. In the case of sinking funds, the money is held until the date of redemption; but exactly the opposite course is followed where annual drawings are provided, for in such cases the Government retire a certain amount of their debentures yearly, and thus effect a gradual extinction of the loan. As already explained, all the states have sinking funds in operation, the amounts to the credit of which will be found on page 701. The system of annual drawings has been adopted to a very limited extent only by New Zealand, New South Wales, and Western Australia; the only loan so issued by New South Wales has, however, been redeemed.

With the exception of one or two small amounts of perpetual or interminable stock, all the Australasian loans are redeemable at prescribed dates; hence the Governments frequently find themselves at the mercy of an adverse market when they are compelled to raise a loan to pay off stock falling due. Within the last few years, however, practical steps have been taken by Victoria, Queensland, South Australia, Western Australia, and Tasmania to avoid this disability, the Governments of those states, in their late issues, having reserved to themselves the option of redeeming at a minimum or a maximum date, or any intervening period, on giving the necessary six or twelve months' notice. Canada was the first of the British possessions to introduce this principle.

#### DATES OF MATURITY.

Australasian loans have been issued for fixed periods, and the amount maturing in each year is given in the following statement. No combined action is taken to regulate the raising of loans, each state acting according to the exigencies of its Government, regardless of the financial condition of its neighbours. The placing of a loan on the London market, especially if it be for a large amount, generally results in an all round fall in the prices of Australasian stocks, and subsequent issues of other states are placed at a disadvantage if the market is approached before it has recovered its tone; in fact, the states have in this respect all the evils of disintegration and all the liabilities of federation, without any of the advantages which federation would give. The evil effects of this lack of consultation between the Australian Treasurers will be seen from the table on the opposite page. In ten years only of the next fifty years is there no loan to be renewed or to be paid off, and the amounts to be met range as high as £37,859,677. Happily, the amounts to be redeemed during the next decade are moderate, and the fact of heavy obligations requiring to be met in any remote year may prove of advantage, as it will simplify negotiations when the time is

ripe for the conversion of Australasian loans into one consolidated stock. Only one colony—New Zealand—is at present systematically working with this end in view, but so far it has treated the question from a provincial standpoint only. The principle of adopting a minimum and a maximum date for repayment has been so recently introduced that, in the table now given, no attempt has been made to show specially the amounts to which it is applicable, the period of redemption in each case being assumed to be the more remote date.

Due Dates.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
FUNDED DEBT.									
Overdue..	£ 2,550	£ 1,000	£ .....	£ .....	£ .....	£ .....	£ 4,550	£ .....	£ 4,550
1904	58,000	.....	.....	.....	.....	24,840	82,840	1,748,960	1,831,799
1905	903,800	.....	.....	72,500	17,600	179,988	1,178,888	1,960,700	3,124,286
1906	224,900	.....	.....	87,500	.....	236,511	498,911	2,124,766	2,623,677
1907	378,218	4,000,000	.....	1,037,500	.....	177,629	5,591,346	1,866,800	7,458,146
1908	2,865,500	2,000,000	.....	1,961,100	.....	449,367	7,285,967	1,113,088	8,399,655
1909	384,000	.....	.....	3,122,700	.....	122,835	3,629,535	1,455,150	5,064,685
1910	2,863,700	.....	.....	60,300	1,522,105	67,701	4,520,806	499,276	5,920,682
1911	.....	2,107,000	.....	68,300	.....	1,024,681	3,199,961	843	3,200,304
1912	9,366,227	63,000	.....	85,000	.....	2,125	9,516,352	53,476	9,569,828
1913	.....	4,746,795	1,406,500	46,300	.....	547,650	6,807,245	496,300	7,303,545
1914	.....	.....	.....	26,000	.....	800,000	825,000	331,800	1,196,800
1915	.....	.....	11,728,800	35,000	35,715	.....	11,799,515	5,000	11,802,515
1916	.....	.....	.....	9,486,045	.....	100	9,486,145	12,700	9,498,845
1917	.....	3,120,492	.....	3,546,200	.....	.....	6,666,692	.....	6,666,692
1918	12,823,200	.....	.....	1,474,400	.....	100	14,300,700	.....	14,300,700
1919	415,050	4,000,000	.....	28,000	.....	.....	4,441,050	.....	4,441,050
1920	.....	6,000,000	.....	336,300	.....	300,000	6,536,300	.....	6,636,300
1921	.....	6,000,000	.....	.....	.....	270,164	6,270,164	500,000	6,770,164
1922	.....	.....	.....	.....	.....	8,252	8,252	.....	8,252
1923	.....	7,331,500	.....	.....	.....	.....	7,936,325	.....	7,936,325
1924	16,668,065	.....	12,978,834	1,661,300	354,590	.....	31,677,789	299,800	31,977,589
1925	222,256	.....	.....	.....	.....	5,060	227,306	.....	227,306
1926	.....	.....	.....	.....	.....	67,600	67,600	.....	67,600
1927	.....	.....	.....	.....	2,500,000	.....	2,500,000	.....	2,500,000
1928	.....	8,509,375	.....	200,000	.....	.....	8,709,375	29,150,302	27,859,677
1929	.....	.....	.....	.....	.....	.....	3,704,800	.....	3,704,800
1931	.....	.....	3,704,800	.....	.....	.....	1,876,000	.....	1,876,000
1933	9,686,300	457,000	.....	.....	1,876,000	.....	10,143,300	.....	10,143,300
1934	.....	.....	.....	.....	983,563	.....	983,563	.....	983,563
1935	12,500,000	.....	.....	.....	6,880,000	.....	19,380,000	.....	19,380,000
1936	.....	.....	.....	332,900	1,100,000	.....	1,432,900	.....	1,432,900
1939	.....	.....	.....	2,719,800	.....	.....	2,719,800	.....	2,719,800
1940	.....	.....	.....	.....	.....	4,906,500	4,906,500	6,161,167	11,067,667
1945	.....	2,750,000	.....	.....	.....	.....	2,750,000	9,572,997	12,322,997
1947	.....	4,498,693	.....	.....	.....	.....	4,498,693	.....	4,498,693
1950	.....	946,600	.....	.....	.....	.....	946,600	.....	946,600
1951	.....	1,000,000	.....	.....	.....	.....	1,000,000	.....	1,000,000
Inter-min-able..	532,890	.....	.....	.....	.....	.....	532,890	.....	532,890
Annual Draw-ings...	.....	.....	.....	.....	198,400	.....	198,400	180,500	378,900
Unde-fined	.....	.....	1,582,060	.....	.....	.....	1,582,060	.....	1,582,060
Total	62,926,655	48,336,162	40,661,287	26,324,145	16,090,288	9,211,070	210,539,607	57,522,215	368,061,822

Due Dates.	New South Wales.	Victoria.	Queens-land.	South Aus-tralia.	Western Aus-tralia.	Tas-mania.	Common-wealth.	New-Zealand.	Austral-asia.
UNFUNDED DEBT. ( <i>Treasury Bills for Works and Deficiencies in Revenue.</i> )									
	£	£	£	£	£	£	£	£	£
Over-due..	4,000	....	....	....	....	....	4,000	....	4,000
1904	....	....	....	361,500	....	....	361,500	....	361,500
1905	2,000,000	50,000	....	700,725	....	106,210	2,916,985	....	2,916,985
1906	1,000,000	2,233,900	....	333,325	....	1,120	3,568,245	....	3,568,245
1907	4,900,000	1,050,000	....	295,575	....	....	6,245,575	....	6,245,575
1908	225,300	25,000	....	257,050	....	....	507,350	....	507,350
1909	....	25,000	....	261,325	....	....	296,325	....	296,325
1910	555,179	25,000	....	....	....	....	580,179	....	580,179
1911	....	25,000	....	....	....	....	25,000	....	25,000
1912	....	25,000	530,000	....	....	....	555,000	....	555,000
1913	....	25,000	600,000	....	....	....	625,000	....	625,000
Annual Draw-ings.	1,422,447	....	....	....	....	....	1,422,447	....	1,422,447
Total	10,106,926	3,483,800	1,130,000	2,260,500	....	107,330	17,097,556	....	17,097,556
Total Debt	30,083,581	51,819,962	41,781,237	23,593,645	16,090,288	9,318,400	227,637,163	57,522,215	286,159,378

## EXPENSES OF NEGOTIATION.

From 1855, when the first New South Wales loan was placed on the London market, until the present time, the Australasian states have obtained from the same source a large proportion of the money which they have borrowed.

The following table shows the amounts raised locally, and in London, but small sums raised in states other than those incurring the debt have been included with the London flotations :—

State.	Raised Locally.			Raised in London.			Total Debt.	Percentage of Loans raised Locally to Total Debt.
	Deben-tures, Inscribed and Funded Stock.	Treasury Bills for Public Works and in aid of Revenue.	Total.	Deben-tures, Inscribed and Funded Stock.	Treasury Bills for Public Works and in aid of Revenue.	Total.		
	£	£	£	£	£	£	£	£
New South Wales ..	11,281,306	5,102,926	16,384,231	58,645,350	5,004,000	63,649,350	80,083,581	20.43
Victoria .....	5,719,787	1,300,000	7,019,787	42,616,375	2,183,800	44,800,175	51,819,962	13.55
Queensland .....	5,241,940	1,130,000	6,371,940	35,409,347	....	35,409,347	41,731,287	15.25
South Australia .....	3,434,195	2,069,500	5,503,695	22,889,950	200,000	23,089,950	28,593,645	19.24
Western Australia .....	2,524,735	....	2,524,735	13,565,553	....	13,565,553	16,090,288	15.60
Tasmania .....	1,390,820	107,330	1,498,150	7,830,250	....	7,830,250	9,318,400	15.97
Commonwealth .....	29,532,782	9,709,750	39,242,538	180,956,825	7,387,900	188,344,625	227,637,163	17.26
New Zealand .....	9,473,373	....	9,473,373	48,048,942	....	48,048,942	57,522,215	16.47
Australasia .....	39,056,155	9,709,750	48,765,911	229,005,667	7,387,900	236,393,467	286,159,378	17.10

The dependence on the English market was originally due to lack of local capital ; but even in late years, when such capital has been fairly abundant, the Governments have still turned to London, and, strange to say, have offered the London investor a higher rate than that at which they have been able to place the small loans raised locally.

The charges incidental to the floating of an inscribed stock loan in England are heavy. The chief expense is the stamp duty of 12s. 6d. per cent. imposed by the British Government on inscribed stock, the other charges being for services rendered. New South Wales, Queensland, and New Zealand issue their stock through the Bank of England; the London and Westminster Bank acts for Victoria and Western Australia; South Australia issues its loans through its Agent-General in London; in the case of Tasmania also the Agent-General is the channel through whom the loans are placed, but he has the assistance of the London and Westminster Bank.

The cost of negotiation by the Bank of England is  $\frac{1}{2}$  per cent. commission; and by the London and Westminster Bank,  $\frac{1}{4}$  per cent. Brokerage costs  $\frac{1}{4}$  per cent. In addition to these charges and the stamp duty referred to above, there has usually to be added 4d. or 5d. per £100 for incidental expenses. The charges annually made by the Bank of England for the inscription and management of stock and the payment of the half-yearly dividends were formerly £600 per million for the first ten millions, £550 for the next five, and £500 per million for all subsequent amounts. In 1895, however, these rates were reduced by £100 per million to the three states employing the Bank; while from May, 1899, all amounts raised through the agency of the Bank of England, on behalf of New South Wales, are charged £200 per million. The charges of the London and Westminster Bank were £500 per million for the first ten millions, £450 for a second like sum, and £400 per million for any subsequent amount to the end of 1897, when the Victorian Government arranged with the Bank to reduce its rates for inscription of stock to £250 per million, without regard to the total amount inscribed.

On the old form of debenture the stamp duty imposed is 2s. 6d. per cent., or £1,250 per million. The expenditure per £100 debentures or inscribed stock floated in London of those states for which information is obtainable is given in the subjoined table. The debenture loans shown are some of the last issued. It will be seen that the cost of floating inscribed stock loans is much greater than that under the debenture system, but the extra outlay is inappreciable when compared with the advantages gained :—

State.	Year of Negotiation.	Principal.		Expenses per £100 Debenture and Stock.	Class of Stock.
		Rate of Interest.	Amount.		
			£	£ s. d.	
	1883	4	2,000,000	0 11 5	Debentures.
	1889	3½	3,500,000	1 7 10	Inscribed.
	1891	3½	4,500,000	1 7 9	do.
	1893	4	2,500,000	1 8 0	do.
New South Wales.....	1894	3½	832,000	1 9 5	do.
	1895	3	4,000,000	1 7 10	do.
	1898	3	1,500,000	1 8 5	do.
	1901	3	4,000,000	*2 12 8	do.
	1902	3	3,000,000	*2 12 11	do.

\* Including underwriting commission.



State.	Year of Negotiation.	Principal.		Expenses per £100 Debenture and Stock.	Class of Stock
		Rate of Interest.	Amount.		
Victoria .....	1880	4½	£ 2,000,000	£ s. d. 0 17 9½	Debentures.
	1891	3½	3,000,000	1 2 9	Inscribed.
	1892	3½	2,000,000	1 3 0	do.
	1893	4	2,107,000	1 3 0	do.
	1899	3	1,600,000	1 2 11	do.
	1901	3	3,000,000	2 8 0	do.
	1903	3½	2,964,720	2 6 10	do.
Queensland .....	1881	4	1,069,500	0 15 9	Debentures
	1890	3½	2,264,734	1 8 0	Inscribed.
	1891	3½	2,500,000	1 8 2	do.
	1893	3½	1,182,400	2 18 8	do.
	1895	3½	1,250,000	1 11 7	do.
	1896	3	1,500,000	1 9 4	do.
	1900	3	1,400,000	2 15 0	do.
	1901	3	1,374,213	2 15 0	do.
	1903	3½	750,090	3 2 6	do.
	1883	4	1,438,500	0 9 0	Debentures.
South Australia.....	1889	3½	1,317,800	0 19 1	Inscribed.
	1892	3½	932,300	1 1 2	do.
	1893	3½	125,000	.....	do.
	1894	3½	475,600	.....	do.
	1894	3½	200,000	.....	do.
	1896	3	839,500	1 2 5	do.
	1897	3	500,000	1 0 11	do.
	1899	3	1,500,000	2 4 5	do.
	1900	3	1,000,000	2 7 7	do.
	1891	4	250,000	1 3 6	do.
Western Australia ...	1892	4	400,000	1 3 7	do.
	1894	4	540,000	1 5 6	do.
	1895	3½	750,000	1 3 7	do.
	1896	3	750,000	1 3 8	do.
	1897	3	1,000,000	1 3 7	do.
	1898	3	1,000,000	1 3 11	do.
	1898	3	1,000,000	1 3 11	do.
	1900	3	1,000,000	2 9 0	do.
	1900	3½	880,000	2 12 3	do.
	1886	4	1,000,000	0 18 0	Debentures.
Tasmania .....	1889	3½	1,000,000	1 3 6	Inscribed.
	1893	3½	600,000	1 3 5	do.
	1894	4	1,000,000	1 3 8	do.
	1895	3½	750,000	1 4 5	do.
	1901	3	450,000	.. ..	do.
New Zealand.....	1895	3	1,500,000	2 2 8	do.
	1899	3	1,000,000	1 13 0	do.
	1901	3	1,500,000	2 16 0	do.
	1903	3	1,250,000	2 14 5	do.

The loan of £3,000,000 raised by Victoria in 1901 was for the purpose of redeeming a similar amount floated in 1876 and falling due on 1st July, 1901, and that raised by the same state in 1903 was partly for the purpose of redeeming £5,000,000 debentures maturing on 1st January, 1904.

Against several loans the expenses have not been stated, as the information has not been published by the state interested. The high rate of expenses on the 1893 Queensland loan is accounted for partly by the fact that the amount was underwritten at the rate of 1 per cent. The latest loans issued by all the states and New Zealand have also been burdened with a charge for underwriting.

#### QUOTATIONS OF STOCK.

In another chapter the growth of Australasian indebtedness on private account has been traced over a period of about thirty-two years, and it has been shown that during that time nearly the whole of the advances made to the various state governments, and one hundred and eighteen millions of private advances, have been obtained in Great Britain. This condition of dependence on external capital for the development of the country has on more than one occasion proved a great danger to Australasia, but never to the same extent as during the crisis of 1892-93. The withdrawal of confidence on the part of the British investor at that time caused widespread confusion in almost every department of industry, with intense financial unrest, from which some of the states have not yet recovered, although, as will be seen from the appended table, Australasian stocks are now quoted at satisfactory prices.

The quotations for Colonial stocks in the London markets at the close of June, 1892, 1893, 1894, and 1904 are given below, the price in every instance being "cum dividend." With one exception—India—the quotations are for loans raised on the security of the local revenues of the country borrowing; in the case of India there is an Imperial guarantee. This advantage has also been extended to some Canadian, Mauritius, and New Zealand loans, but these are not quoted in the following list. In passing, it may be mentioned that the guarantee of the British Government is certainly to the advantage of the dependencies to which it has been extended, as in addition to the absolute security afforded, it carries the right of trustees in the United Kingdom to invest trust funds in the stock—a privilege which was not extended to Australasian securities till September, 1901:—

Country.	Class of Stock.	Selling Price, "cum dividend."			
		June, 1892.	June, 1893.	June, 1894.	June, 1904.
<b>Australasia—</b>					
New South Wales .....	3½ per cent. Inscribed	96½	93	98½	98
Victoria .....	3½ do do ...	97	88½	97½	97
Queensland .....	4 do do ...	103½	99	104	104
South Australia .....	4 do do ...	106	103	106½	102
Western Australia .....	4 do do ...	103½	104	108	103
Tasmania .....	4 do do ...	103	98½	103	102
New Zealand .....	4 do do ...	104½	104½	108½	107
Canada .....	3 do do ...	94½	96	97	99
Cape Colony .....	4 do do ...	106	108	112	103
Natal .....	4 do do ...	103	108	109	109
India .....	3 do Stocks	97½	98½	99½	96½

In order to make the comparison between different stocks quite fair, other things than bare quotations on a given date—chiefly the accrued interest and the unexpired currency of the scrip—have to be considered. A uniform date for the payment of interest on loans has not been adopted, so that the amount of interest accrued at the above-quoted dates varies with each loan; while the date on which the loan is repayable is a factor not to be neglected in estimating the price of a stock. The return obtained by investors from the inscribed stock of each colony on the basis of previous quotations, allowing for interest accrued and redemption at par on maturity, is given below:—

Country.	Nominal rate of Interest.	Selling Price, "ex dividend."	Cur- rency.	Effective annual Rate of Interest per £100 sterling.	
				If no allowance is made for redemption at par on maturity.	Rate if Stock is held till date of maturity.
	per cent.	£	Years.	£ s. d.	£ s. d.

## June, 1892.

Australasia—					
New South Wales.....	3½	96.19	32	3 13 5	3 14 2½
Victoria .....	3½	95.45	31	3 13 11½	3 15 0
Queensland.....	4	101.72	32	3 19 5	3 19 1½
South Australia.....	4	105.22	44	3 16 9½	3 16 4
Western Australia.....	4	101.72	42	3 19 5	3 19 3
Tasmania .....	4	101.22	16	3 19 10	3 19 0
New Zealand .....	4	104.05	37	3 17 8	3 17 1½
Canada .....	3	93.17	46	3 4 10½	3 5 7½
Cape Colony .....	4	105.89	31	3 16 3½	3 15 1½
Natal .....	4	102.55	34	3 18 9½	3 18 4½
India .....	3	96.69	56	3 2 6½	3 2 9

## June, 1893.

Australasia—					
New South Wales.....	3½	92.33	31	3 16 5½	3 18 2½
Victoria .....	3½	86.97	30	4 1 2½	4 4 3½
Queensland.....	4	97.25	31	4 3 1	4 3 7½
South Australia.....	4	102.23	43	3 19 0½	3 18 10
Western Australia.....	4	102.25	41	3 19 0½	3 18 9½
Tasmania .....	4	96.75	15	4 3 6	4 6 0½
New Zealand .....	4	104.06	36	3 17 8	3 17 1
Canada .....	3	94.68	45	3 3 10	3 4 5½
Cape Colony .....	4	107.90	30	3 14 10½	3 13 2½
Natal .....	4	107.56	33	3 15 1½	3 13 9½
India .....	3	97.92	55	3 1 8½	3 1 0½

Country.	Nominal rate of Interest.	Selling Price, "ex dividend."	Cur- rency.	Effective annual Rate of Interest per £100 sterling.	
				If no allowance is made for redemption at par on maturity.	Rate if Stock is held till date of maturity.
	Per cent.	£	Years.	£ s. d.	£ s. d.

## June, 1894.

<b>Australasia—</b>					
New South Wales.....	3½	98-21	30	3 11 10½	3 12 4
Victoria .....	3½	95-92	29	3 13 7½	3 14 8
Queensland.....	4	102-25	30	3 19 0½	3 18 6½
South Australia.....	4	105-74	42	3 16 5	3 15 10½
Western Australia .....	4	106-25	40	3 16 0½	3 15 4½
Tasmania .....	4	101-25	14	3 19 9½	3 18 9
New Zealand .....	4	108-45	35	3 14 6	3 13 2½
Canada .....	3	95-68	44	3 3 2½	3 3 8
Cape Colony .....	4	111-91	29	3 12 2½	3 9 5
Natal .....	4	108-57	32	3 14 5	3 12 9½
India .....	3	98-68	54	3 1 3	3 1 4½

## June, 1904.

<b>Australasia—</b>					
New South Wales.....	3½	97-32	20	3 12 6½	3 13 11½
Victoria .....	3½	95-45	22	3 14 0	3 16 0
Queensland.....	4	102-22	20	3 19 0½	3 18 0
South Australia .....	4	101-22	32	3 19 9½	3 19 7
Western Australia.....	4	102-22	27	3 19 0½	3 18 5½
Tasmania .....	4	100-22	4	4 0 7½	3 19 7½
New Zealand .....	4	106-55	25	3 15 10	3 13 9½
Canada .....	3	97-67	34	3 1 10½	3 2 4½
Cape Colony .....	4	102-89	19	3 18 6½	3 17 0½
Natal .....	4	108-55	22	3 14 5	3 11 0½
India .....	3	95-67	44	3 3 5	3 3 11½

The figures given in the last column of the table show the relative positions of the various stocks quoted. As will be seen, the credit of each division of Australasia was somewhat better in 1894 than

in 1892, notwithstanding the financial panic which occurred between those dates. In 1893 there was naturally a heavy fall, as compared with the preceding year, in all Australasian securities except those of New Zealand and Western Australia. Victorian stock showed the largest fall—which was only to be expected in view of the fact that the panic originated in that state. The quotation for New Zealand stock at the middle of 1893 was the same as that of the preceding year, which seemed to point to the conclusion that the London market did not consider the interests of New Zealand to be bound up with those of the states on the mainland. In 1895 a great improvement took place in the prices of stock of all the states, and the rise has since been well maintained. To illustrate the fluctuations in the prices of colonial securities, the rates obtained during 1892, 1893, 1894, and 1904 are given below in a simpler form than in the preceding table. It is probable that the price of Victorian securities would have been higher were it not for the large sum that matured at the opening of the year.

Country.	1892.	1893.	1894.	1904.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.
<b>Australasia—</b>				
New South Wales .....	3 14 2½	3 18 2½	3 12 4	3 13 11½
Victoria .....	3 16 0	4 4 3½	3 14 8	3 16 0
Queensland .....	3 19 1½	4 3 7½	3 18 6½	3 18 0
South Australia .....	3 16 4	3 18 10	3 15 10½	3 19 7
Western Australia .....	3 19 3	3 18 9½	3 15 4½	3 18 5½
Tasmania .....	3 19 0	4 6 0½	3 18 9	3 19 7½
New Zealand .....	3 17 1½	3 17 1	3 13 2½	3 13 9½
Canada .....	3 5 7½	3 4 5½	3 3 8	3 2 4½
Cape Colony .....	3 15 1½	3 13 2½	3 9 5	3 17 0½
Natal .....	3 18 4½	3 13 9½	3 12 9½	3 11 0½
India .....	3 2 9	3 1 0½	3 1 4½	3 3 11½

So far, only the return yielded to the investor has been considered. The following table shows the average prices obtained by the Australasian Governments for some of their last issues, and the quotations for

the same stocks in June, 1904, the latter prices being, of course, "ex dividend":—

State.	Date of Negotiation.	Rate per cent.	Amount of Issue.	Net average price realised.	Quotation, ex-dividend, June, 1904.
			£	£	£
New South Wales.....	1895	3	4,000,000	95·14	86·42
Do .....	1898	3	1,500,000	98·65	86·42
Do .....	1901	3	4,000,000	91·12	86·42
Do .....	1902	3	3,000,000	90·90	86·42
Victoria .....	1893	4	2,107,000	96·00	99·23
Do .....	1899	3	1,600,000	93·21	87·50
Do .....	1901	3	3,000,000	89·86	87·50
Queensland .....	1897	3	1,500,000	95·61	86·00
Do .....	1900	3	1,400,000	91·28	86·00
Do .....	1900	3	1,374,213	91·50	86·00
South Australia.....	1896	3	839,500	95·34	85·67
Do .....	1897	3	500,000	96·05	85·67
Do .....	1899	3	1,500,000	92·67	85·67
Do .....	1900	3	1,000,000	90·81	85·67
Western Australia .....	1897	3	1,000,000	93·45	85·66
Do .....	1898	3	1,000,000	94·76	85·66
Do .....	1898	3	1,000,000	91·96	85·66
Do .....	1900	3	1,000,000	89·66	85·66
Do .....	1900	3½	880,000	97·39	95·61
Tasmania .....	1895	3½	750,000	98·30	99·00
Do .....	1895	3	450,000	.....	•
New Zealand.....	1896	3	1,500,000	93·73	88·42
Do .....	1899	3	1,000,000	96·55	88·42
Do .....	1901	3	1,000,000	.....	88·42
Do .....	1903	3	1,250,000	.....	88·42

\* No quotation.

#### CHARACTER OF STOCK ISSUED.

By far the larger part of Australasian loans is inscribed, and the outstanding issues under the debenture system are being converted into inscribed stock as quickly as circumstances permit. New Zealand was the first colony to introduce inscription in 1877, in which year was passed the Consolidated Stock Act, a measure made necessary by the abolition of the Provincial Councils. Under this Act the liabilities of the various provinces were merged into the general debt of the colony; and under the same Act and its amendment of 1884 the Government has worked systematically to consolidate the debt by conversion and inscription, so that in March, 1903, the whole of the public liabilities were inscribed, with the exception of £10,601,997 represented by debentures. The Consolidated Stock Act of New Zealand was assented to in December, 1877; and in August of that year the Imperial Parliament passed the Colonial Stock Act, which provided for the inscription and transfer of Colonial stock raised in the United Kingdom. Certain

steps were required to be taken before a colony could take advantage of the provisions of the Imperial Act. As already mentioned, New Zealand passed the necessary legislation at the end of 1877; but nothing was done by the other states until 1882, when Victoria and South Australia passed Inscribed Stock Acts; New South Wales and Queensland passed similar legislation in the following year, Western Australia in 1884, and Tasmania in 1889. It will thus be seen that a gradual change in the mode of floating loans for public purposes has been going on since 1877, and the time cannot be far distant when the whole debt of each state will be represented by one class of stock. In 1879, or two years after passing the Consolidated Stock Act, New Zealand placed on the market a 5 per cent. loan of £5,000,000 at  $97\frac{1}{2}$  in the form of debentures, the subscribers having the option up to March, 1881, of exchanging for 4 per cent. inscribed stock, at the rate of £120 of stock for each £100 of debentures. The loan was successfully floated, and within the stated period £4,476,000 of the £5,000,000 debentures were exchanged for £5,371,200 inscribed stock at 4 per cent. The other states issued inscribed stock loans shortly after passing the respective Acts.

The Imperial Colonial Stock Act, 1877, as previously mentioned, provides for the inscription and transfer of stock raised in the United Kingdom and for stamp duty to be levied thereon. It also defines the position of the British Government as regards Colonial indebtedness, and provides that every document connected with stock transactions shall have printed upon it a distinct intimation that no liability, direct or indirect, is incurred by the British Government in respect of such stock, unless the loan is under Imperial guarantee.

Under the provisions of the Colonial Stock Act, 1900, trustees are empowered to invest in Australasian securities after certain conditions have been complied with, and these conditions were proclaimed in the *London Gazette* of 6th September, 1901.

The difference between registered and inscribed stock is practically small. Transactions under the former head are confined to a few old funded stock loans. Debentures and inscribed stock form the principal classes of securities, and, as previously pointed out, the debenture form is rapidly giving way to inscription. Debenture coupons are, like ordinary scrip, negotiable by bearer, and are liable to the risk of forgery. By inscription the possibilities of fraud in transfer are minimised, as the stock is inscribed in the books of the bank, and transferable therein by the stock-holders personally or by their attorneys, without the issue of certificates of stock. In the case of registered stock, certificates are issued transferable by deed.

The practice of issuing Treasury bills, either in anticipation of or to make good deficiencies in revenue, obtains in each state, and, as previously explained, is an old-established custom; but Treasury bills have been made to serve another purpose, and money has been raised by their sale to meet certain obligations for public works. This is an innovation which could not well be avoided in the disturbed markets of the last few years.

The bills are in reality ordinary loans with short currencies, and carry generally a higher rate of interest than issues of the funded debt. The unsatisfactory state of Australasian finance does not allow of the absolute redemption of these bills; consequently they will either have to be renewed or converted into stock, an operation which will entail an additional expenditure to the charges of first negotiation. The New Zealand Treasury bills are issued direct by the Treasury at par, and the expenses of negotiation are small. The bills are usually redeemed during the year of issue, and for this reason they have not been included with or considered as part of the public debt of New Zealand, though in the case of the other states Treasury bills have been so included.

#### CONVERSION AND CONSOLIDATION OF LOANS.

Conversion and consolidation as applied to loans are not interchangeable terms, but represent two distinct transactions in so far related that without conversion consolidation would be impracticable. All the states are systematically converting their old loans into inscribed stock, and by so doing they are taking a step towards consolidation. Since the Consolidated Stock Act was passed in 1877, New Zealand has been engaged in converting its old loans into inscribed stock, and consolidating the whole debt by adopting three uniform interest rates of 4, 3½, and 3 per cent., and fixing the dates of maturity at 1929, 1940, and 1945 respectively. The transactions in conversion and consolidation in New Zealand from 1877 to the 31st March, 1903, were as stated below. In addition to the transactions shown, old debentures to the amount of £6,225,500 were converted into short-dated debentures under the 1884 Consolidated Stock Act, pending subsequent conversion into inscribed stock; of these short-dated debentures, £4,257,700 have since been converted into 4 per cent. stock, and are included in the £19,724,400 shown below. The amount of these debentures outstanding on 31st March, 1903, was £1,967,800 :—

Amount of Old Debentures Converted or Redeemed.	Additional Capital added to Principal by Conversion or Consolidation.	New Stock Issued.		
		Nominal Rate of Interest.	Amount.	Date of Maturity.
£	£		£	
19,724,400	1,600,902	4 per cent.	21,325,302	1929
5,720,550	440,617	3½ „	6,161,167	1940
3,919,332	68,665	3 „	3,987,997	1945

The loading of the principal by conversion appears heavy; but New Zealand was saddled with a number of small loans, much after the type of municipal borrowings, which it was most desirable should be consolidated without delay, and some sacrifice was made to accomplish this; besides, the compensation obtained in a lower rate of interest must be set against the increased capital. The annual saving in interest on the



amount converted to the 31st March, 1903, is stated as £203,658, viz., £102,114 on the 4 per cent., £59,262 on the 3½ per cent., and £42,282 on the 3 per cent. stock. All conversions into short-dated debentures took place at par, the saving in interest thereby amounting to £7,990 annually, in addition to the £203,658 shown above. The subject of the New Zealand conversion is a large one, and inquirers should consult the publications of the Government of that colony, which give details that would hardly be in place in a volume such as this.

In Victoria the 4 per cent. stock floated in Melbourne to the amount of £2,089,613 was converted during 1898-9 into 3 per cent. stock, with the exception of £120,062 subsequently redeemed. The saving in interest by the conversion is £19,696.

#### LATE ISSUES OF LOANS AND TREASURY BILLS.

As late as the year 1890 the states could borrow in London on very favourable terms, but in the year named the conditions were no longer satisfactory. This change had for its immediate cause a condition of things not of Australasia's own creation, the Baring failure and the Argentine crisis being primarily responsible for the stoppage of Australasian credit; but there is no reasonable ground for supposing that if the Baring failure had not taken place the London markets would have been much longer open to the Australasian states. The Treasurers of the various provinces were entirely unprepared for this revulsion in credit. They were committed to engagements for the construction of public works which they could not terminate; contracts had been entered into for large sums on the assumption that funds would be available; besides this, no preparations had been made to meet debentures falling due in a short time. The sudden stoppage of credit greatly embarrassed the Governments, and most of the states had recourse to Treasury bills to enable them to adjust their finances to the altered circumstances. The amounts received from the sale of these bills were devoted to meeting loans maturing, and providing funds for public works already contracted for. Pressing necessities and the improved condition of the London market encouraged several of the states during 1893 and 1894 to place ordinary loan issues, which were successfully negotiated; and the proceeds of these loans relieved the liabilities on matured Treasury bills and current obligations. In 1895 the credit of the Australasian states was fully re-established in London.

*New South Wales.*—In 1892 and 1893 the Treasury had authority to issue £3,000,000 of 4 per cent. funded stock at a minimum price of par. Up to the 30th June, 1904, £2,549,850 had been disposed of, leaving stock to the amount of £450,650 yet to be raised, the cost of the issue being practically nil.

The Loan Acts 58 Vic. No. 14, 59 Vic. No. 6, 60 Vic. No. 32, 61 Vic. No. 43, 62 Vic. No. 36, 63 Vic. No. 42, and 64 Vic. No. 60, passed

in 1894, 1895, 1896, 1897, 1898, 1899, and 1900 respectively, provided for the establishment of other local stocks. The stocks under the first-mentioned Act are known as New South Wales 1924 Stock and Funded Stock, the latter running *pari passu* with the stock floated under 56 Vic. No. 1, the amounts outstanding on 30th June, 1904, being £198,065 and £863,947 respectively; the stocks under the 1895 Act are known as New South Wales 1925 Stock and Funded Stock, the latter also being subject to the same conditions as that floated under 56 Vic. No. 1 (Funded Stock Act of 1892). The amounts outstanding on the 30th June, 1904, were £222,255 and £1,332,945 respectively. The stocks under the 1896 Act are known as New South Wales 1927 Stock and Funded Stock, and are subject to conditions similar to those imposed in respect of the issues under the 1894 and 1895 Acts. Up to the 30th June, 1904, sales of funded stock had been effected to the extent of £1,809,810. The rate of interest on the stock is 3 per cent., and the date of maturity, 1912. The stocks under the 1897 Act are known as New South Wales 1928 Stock and Funded Stock, and are issued under the same conditions as those already referred to. The amount of funded stock sold to 30th June, 1904, was £1,250,175, the rate being 3½ per cent., and the date of maturity, 1912. The only expense attached to the issues was a small amount for brokerage. The stocks under the 1898 Act are known as New South Wales 1929 Stock and Funded Stock, and are issued under similar conditions to those already adverted to. The amount of funded stock sold to 30th June, 1904, was £1,500,000, the rate being 3½ per cent., and the date of maturity 1912. No expense was attached to the issue. Provision has been made for sinking funds to liquidate certain portions of the loans expended on works of an unproductive character. With regard to the loan authorised under the Loan Act 1899, it must be mentioned that no sales have yet taken place under that Act, but the annual instalment for the sinking fund has been appropriated each year. Under the Loan Act of 1900, 64 Vic. No. 60, sales to the amount of £376,218 were made locally during the year ended 30th June, 1904.

The Loan Act of 1899 gave authority for the local issue of £500,000 inscribed stock at 3 per cent., maturing in 1919, for the purpose of making advances to settlers. Under the Advances to Settlers (Amendment) Act, No. 106 of 1902, the issue was increased to £1,000,000. Of this stock, £415,050 were issued to the 30th June, 1904. As in the case of the 4 per cent. funded stock, the only expense in connection with the later local issues of funded and inscribed stock was a small amount of brokerage.

In October, 1893, an inscribed stock loan of £2,500,000 was floated in London, the rate of interest being 4 per cent., and the currency forty years. The minimum price was fixed at 98½, and the average price realised was £100 11s. 10½d. The rate paid by the Government, allowing for redemption at par on maturity, was £4 3s. 0½d.; while the return to investors was £4 1s. 8½d.

During 1894 several small 5 per cent. loans matured, amounting in the aggregate to £832,000. In September of that year a 3½ per cent. covering loan was successfully issued, the average price realised on the gross proceeds being £101 15s., which is reduced to £99 13s. 6d. if allowance be made for accrued interest and charges. The rate paid by the Government is £3 10s. 11d. per cent., and the interest yielded to investors, £3 9s. 4½d. The loan was subscribed over five-fold, the amount tendered being £4,268,000.

In October, 1895, an inscribed stock loan for £4,000,000 was floated, the rate of interest being 3 per cent., and the currency forty years. The minimum price was fixed at 94, and the gross proceeds averaged £96 18s. 3d. The next flotation on the London market took place in January, 1898, when a loan of £1,500,000, bearing interest at 3 per cent., with a minimum of 99, was successfully floated, the gross proceeds being £1,506,269. The actual rate paid by the Government was £3 1s. 6d., and the yield to investors, allowing for redemption at par, was £3 0s. 4½d.

In September, 1901, stock to the amount of £4,000,000 was authorised to be raised for the purpose of resuming wharfs and other premises and services generally. The loan was negotiated at 94, the nominal rate being 3 per cent., and the due date 1935. The actual cost to the Government was £3 9s. per cent., while the yield to investors was £3 5s. 10d. In May, 1902, a 3 per cent. loan of £3,000,000 was placed in London at a fixed price of 94½, the total applications being £35,420,000. The gross proceeds amounted to £2,835,000, and the net proceeds available for expenditure, after allowing for accrued interest, underwriting, and other expenses, were £2,727,191, or £90 18s. 1½d. per £100. The actual rate per cent. payable by the Government, allowing for redemption at par on maturity, is £3 8s. 7d. per £100, and the yield to investors £3 6s. 1½d.

In 1895 authority was given to issue Treasury bills to the amount of £1,174,700 to cover the accumulated deficiencies in revenue on the 30th June of that year. The rate of interest allowed is 3 per cent., and a sum of £150,000 is set aside annually for the repayment of the debt, together with the Treasury bills issued under the Act of 1889.

In 1899 the London market was practically closed to the state government, chiefly on account of the South African war; and, as money was urgently required to complete existing contracts, and to provide for urgent works, authority was obtained under Act 63 Vic. No. 46 for the issue of short-dated Treasury bills to the amount of £4,000,000. The first instalment, viz., £1,000,000 at 4 per cent. was negotiated in London, the net proceeds realising £99 12s. per £100—the cost to the Government being £4 9s. 11½d., and the yield to investors £4 6s. 0½d. The second instalment, amounting to £500,000, was placed locally at 3½ per cent., the net average price realised being 100·14 per £100. The actual cost to the Government was £3 10s. 7½d., and

the yield to investors £3 9s. 6d. During 1900-1 three instalments of £500,000 each at  $3\frac{1}{2}$  per cent. were sold at the Treasury in Sydney. The net averages per £100 were 99-92, 99-71, and 99-37 respectively, and the corresponding amounts paid by the Government were £3 10s. 11 $\frac{1}{2}$ d., £3 11s. 9 $\frac{1}{2}$ d., and £3 13s. 3 $\frac{1}{2}$ d., the yield to investors being £3 10s. 3 $\frac{1}{2}$ d., £3 11s. 4 $\frac{1}{2}$ d., and £3 12s. 9d. respectively. The balance, viz., £1,000,000, was floated in London at 4 per cent., the net price per £100 being 98-63—the cost to Government, £4 8s. 1d., and the actual yield to investors, £4 6s. 1d. During 1901 Treasury bills to the amount of £755,179 were issued to cover deficiencies in revenue to the 30th June, 1902, exclusive of the debit balance of the Consolidated Revenue Fund. The rate allowed is 3 per cent., and the bills are repayable by annual instalments of £100,000. During the year ended 30th June, 1903, Treasury bills for public works were issued in London, under the authority of 2. Edw. VII No. 94 for £1,000,000, £600,000 and £200,000, carrying interest at the rate of 4 per cent., redeemable in 1907. After allowing for charges of negotiation, the net amount raised in each case was £996,250, £597,750, and £197,750, or a net price per £100 in respect of the first two of 99-63, and in the last 98-88. Under the same authority Treasury bills were issued locally to the amount of £175,000 with interest at the rate of 4 per cent., £75,000 being redeemable in 1907, and £100,000 in 1909; no expense was attached to these issues. During the year ended 30th June, 1904, Treasury bills were issued for public works in London under the authority of 2. Edw. VII No. 94 for £200,000, £1,000,000, £250,000, and £250,000, carrying interest at the rate of 4 per cent., redeemable in 1907. After allowing for charges of negotiation, the net amount raised in each case was £197,625, £986,250, £244,607, and £244,063. Treasury bills to the amount of £500,000 were also floated in London under the authority of 64 Vic. No. 10, in connection with the Darling Harbour resumptions, at 4 per cent., redeemable in 1907, the net amount raised being £486,875. Treasury bills for public works were raised locally under the authority of 2 Edw. VII No. 94, and 2 Edw. VII No. 14 for £325,000 and £125,300 respectively, the former carrying interest at the rate of  $3\frac{1}{2}$  per cent. and the latter 4 per cent.; the net amounts realised were £325,000 and £124,450. In addition, under the provisions of 64 Vic. No. 10 in connection with the Darling Harbour resumptions, amounts of £260,000, £203,000, and £37,000 were raised locally, with interest at the rate of 4 per cent., redeemable in 1907, the net amounts realised being £260,000, £202,690, and £37,000.

*Victoria.*—An inscribed stock loan of £2,107,000 was floated in London in October, 1893, the rate of interest being 4 per cent., and the date of maturity between 1911 and 1936, at the option of the Government on due notice being given. A 3 per cent. inscribed stock loan of £1,600,000 was floated in London in February, 1899—the minimum price fixed being £95. The gross proceeds amounted to

£1,522,835, and the net proceeds to £1,491,355, or to £93 4s. 2d. per £100. The date of maturity is from 1929 to 1949. Four per cent. debentures were also disposed of locally from March, 1893, to June 1903, to the amount of £746,795, and 3 per cent. debentures, amounting to £1,063,000, had been sold in Melbourne to the same date.

During 1896 an Act was passed providing for the conversion of the 4 per cent. stocks on the Melbourne register into a 3 per cent. stock. The amount of 4 per cent. stock sold from January, 1895, to June, 1903, was £249,130, holders of which have availed themselves of the privilege of conversion. The amount of new 3 per cent. stock sold under the Conversion Act to 30th June, 1903, was £2,290,482.

In December, 1898, and December, 1901, Acts were passed providing for the issue of local inscribed stock at 3 per cent. to the amount of £500,000, and on the 30th June, 1904, the total sales amounted to £311,135. Another Act for the same purpose became law in November, 1899, the amount authorised being £500,000 at 3 per cent., of which £268,184 had been sold to 30th June, 1904.

An issue of 4 per cent. Treasury bills in aid of revenue to the amount of £1,250,000 was authorised in 1893; in 1898, however, the amount was reduced to £350,000. The amount sold to 30th June, 1903, was £250,000, of which £150,000 has been redeemed.

In September, 1896, authority was given for the issue of Treasury Bills to the amount of £375,000 for public works and services. The amount sold to the 30th June, 1903, was £375,000, bearing interest at  $3\frac{1}{2}$  per cent., and repayable in annual instalments of £25,000 each. The total amount of Treasury bills outstanding under this Act on the 30th June, 1903, was £250,000.

A further issue of £1,000,000 Treasury bills was authorised in December, 1898, and, to the 30th June, 1903, bills to the amount of £500,000 were sold locally at  $3\frac{1}{2}$  per cent. interest, and to the amount of £500,000 at 4 per cent. interest in London. These bills were converted into stock in January, 1903, carrying interest at the rate of 3 per cent. The total amount of Treasury bills outstanding on 30th June, 1903, was £1,050,000.

On the 22nd March, 1901, a loan of £3,000,000 at 3 per cent. was floated in London for conversion purposes, the price being fixed at 93 $\frac{1}{2}$ . The expenses were increased by a charge of  $1\frac{1}{2}$  per cent. for underwriting, and, consequently, the net proceeds realised only £89 17s. 3d. per £100. Debentures to the amount of £500,000 at 3 per cent. were disposed of locally on the 21st August, 1900, realising £96 10s. 5d. per £100, and a further instalment of £500,000, sold on 4th June, 1901, realised £96 8s. 1d. per £100. Local 3 per cent. inscribed stock, amounting to £86,833, was also taken up during 1900-1, at par or a slight premium.

To meet £5,000,000 debentures at  $4\frac{1}{2}$  per cent., falling due on 1st January, 1904, arrangements were made in London during October,

1903, for their conversion. The present holders of the maturing debentures were offered the following options, viz.:—(1) £108 of  $3\frac{1}{2}$  per cent. inscribed stock, due 1929-49, at the Government's option, acceptors to retain the interest coupons on the  $4\frac{1}{2}$  per cent. debentures due on 1st January, 1904, and equal to  $2\frac{1}{2}$  per cent., while the new  $3\frac{1}{2}$  per cents. will carry interest as from 1st October, 1903; (2) for every £100 of  $4\frac{1}{2}$  per cent. debentures, £100 in Treasury bills, bearing interest at 4 per cent. and maturing on 1st July, 1906, acceptors to be paid 25s. per cent. in cash, and have the option, up to 31st December, 1905, of converting into  $3\frac{1}{2}$  per cent. inscribed stock, due 1929-49, at par, six months' interest to be paid on the Treasury bills on 1st July, 1904. The balance was offered to the public, with the option of taking  $3\frac{1}{2}$  per cent. stock at £92 12s. 6d., or 4 per cent. Treasury bonds at £98 15s. The total amount of inscribed stock sold to the 30th June, 1904, was £2,964,720, and the amount of Treasury bonds issued was £2,254,800. The net proceeds amounted to £2,650,419 and £2,185,832 respectively, and the actual rates realised per £100 were £3 18s.  $3\frac{1}{2}$ d. on the stock, and £4 2s. 6d. on the Treasury bonds. The total amount of the loan, if all bonds are converted into stock on or before the 31st December, 1905, will be £5,309,712, and the saving in interest will be approximately 15s. per cent.

*Queensland*, in January, 1893, placed a  $3\frac{1}{2}$  per cent. loan of £1,182,400 on the London market, the average price obtained being £88 14s.  $0\frac{1}{2}$ d. The charges were heavier than usual, as the loan was underwritten at the rate of 1 per cent.

In June, 1895, another  $3\frac{1}{2}$  per cent. loan for £1,250,000, with a currency of fifty years, was placed on the market. The gross price obtained was £101 12s. 7d., and deducting accrued interest the Government received about £100 0s. 2d. In addition, stock to the amount of £750,000 was sold locally, the net proceeds being £743,750, or £99 3s. 4d. per £100.

In June, 1897, a 3 per cent. loan for £1,500,000, repayable in 1947, was floated in London, the average price realised being £97 1s. 5d. Local sales of 3 per cent. stock were also negotiated during the year, the total issued being £124,480, which was sold at the average price obtained in London.

In July, 1898, an amount of £100,000 at 3 per cent. was sold locally at £97 1s. 5d. per £100, and in December, 1899, further sales to the extent of £750,000, also at 3 per cent., took place at an average of 97. In July, 1900, loans amounting to £150,000 at 3 per cent., and £1,400,000 at the same rate, were floated in Brisbane and London respectively, the average prices realised being £97 for the former issue, and £94 0s. 2d. for the latter. The expenses of the London issue were largely increased owing to an underwriting commission of  $1\frac{1}{2}$  per cent. In 1900, further sales to the amount of £2,374,213 took place, £1,000,000 of which bearing interest at  $3\frac{1}{2}$  per cent.

was sold locally, and the balance, which carries 3 per cent., in London. The former realised £99 7s. 7½d. (net) per £100, and the latter, £88 12s. 4d. per £100.

In July, 1903, a 3½ per cent. loan for £750,000, maturing in 1945, was floated in London. The gross price obtained was £96, and after deducting the expenses of issue the net proceeds amounted to £697,500, the actual interest payable being therefore £3 15s. 3d. per cent.

Another class of stock was authorised in 1895, viz., Government Savings Bank Stock. The object of the establishment of this class of security was to enable depositors of over £200 to earn interest on such excess. On the 30th June, 1904, the amount outstanding was £1,074,070, of which £983,380 is bearing interest at 3½ per cent., and £90,690 at 3 per cent.

During 1893 three issues of Treasury bills were placed locally, viz., £222,500 in January, £5,000 in April, and £11,000 in December. The rate of interest was 4 per cent., and the bills have been redeemed. In January, 1894, bills to the amount of £1,000 were also disposed of locally, the rate being the same as for the previous issues, and the date of redemption, 1903. Bills to the amount of £286,000, which were issued during 1897–8, under the 1893 Act, have been purchased with the proceeds of the Savings Bank Stock. Under the Treasury Bills Act of 1901, authority was given for the issue of bills to the amount of £530,000 to cover deficiencies in revenue. The rate of interest was fixed at 4 per cent., and the due date is 1912. The total amount realised, less expenses, was £535,119, or £100 19s. 5d. per £100.

Under the Treasury Bills Act of 1902, authority was given for the issue of bills to the amount of £600,000 to cover deficiencies in revenue. The rate of interest was determined at 4 per cent., and the due date is 1913. The total amount realised, less expenses, was £603,826, or £100 12s. 9d. per £100.

The Treasury bills outstanding on the 30th June, 1904, amounted to £1,130,000, £530,000 of which mature on the 1st January, 1912, and the balance on 1st January, 1913.

*South Australia.*—In 1893 a small loan of £125,000, being portion of the 1890 loan of £1,532,900, was floated in London. The rate of interest is 3½ per cent., and the loan is redeemable in 1939. An instalment of the £1,013,279 loan of 1892 was placed in Adelaide in February, 1894. The amount of the issue was £200,000, the price realised per £100 being £92. The rate of interest is 3½ per cent. In June, 1895, a further issue of £311,000 was floated in Adelaide. In February, 1896, a loan of £839,500 was issued in London, bearing interest at 3 per cent., and redeemable in 1926. The net proceeds, after allowing for charges and accrued interest, amounted to £800,406, or £95 6s. 10d. per cent. In May, 1897, the first of a number of loans under the

"Consolidated Stock Act" was floated in London, amounting to £500,000. Further issues took place in Adelaide for £295,835 and £606,800; in London and Adelaide, for £1,500,000; and in Adelaide, for £249,075. Of the last issue, £36,000 was sold at par, on condition of being placed on the London register, while the balance realised £98 17s. 3d. per cent. The first issue of £500,000 was sold for £94 7s. 4d.; the £295,835 for £99 18s. 8d.; the £606,800, for £98 3s. 9d.; and the £1,500,000, for £94 17s. 10½d. per cent. The total issues under the "Consolidated Stock Act" to the 30th June, 1903, amounted to £5,094,245. All these loans bear interest at the rate of 3 per cent., and mature in 1916. On the 4th April, 1900, an issue of £1,000,000 at 3 per cent. was floated in London, being part of the loan authorised under the "Public Purposes Loan Act of 1898," the minimum price being fixed at 94½. The net proceeds, after allowing for charges, amounted to £92 3s. 1½d. per £100. During 1899-1900, stock to the amount of £518,970 was disposed of in Adelaide, the net price realised being £95 7s. 11d., while in 1900-1, further local sales, amounting to £384,325, were effected at an average price of £94 7s. 6½d. These issues bear the same rate, and are redeemable on the same date, as the former consolidated stock loans. During 1901-2, a small parcel of £64,240 was sold locally at £95 6s. 10d., and in 1902-3 £3,600 at about £92.

In June, 1892, Treasury bills were issued to the amount of £349,225 with interest at the rate of £4 11s. 3d. per cent., and payable in five years; and in March and July, 1893, further issues of £250,000 each were made bearing the same rate; the bills have all been redeemed.

In order to liquidate the debt due by the Northern Territory to South Australia proper, authority was obtained in 1901 to issue Treasury bills to the amount of £849,500 at 3½ per cent. The whole of the bills were floated at par, and, with the exception of £200,000 sold in London, were negotiated locally.

During the year ended 30th June, 1903, it became necessary to issue Treasury bills to liquidate the deficit of the previous year, and to provide funds for carrying on works in progress without appealing to the London money market, which was not in a favourable condition. An issue of Treasury bills, in aid of revenue, to the amount of £238,950 was made, the expenses in connection with which totalled £607. The bills were for periods extending from two to seven years, carrying interest at the rate of 3½ per cent. Other bills, to aid the loan fund, were issued to the extent of £367,775, the total expense attached to which was £2,568. The bills have a currency of from two to five years, and carry interest at the rate of 3½ per cent.

During the year ended 30th June, 1904, Treasury bills to the amount of £812,775 were issued, of which £66,125 carries interest at



the rate of  $3\frac{1}{2}$  per cent. and the balance 4 per cent. The bills have a currency ranging from three to five years.

*Western Australia.*—In June, 1894, a loan of £540,000, at 4 per cent., was floated in London at a minimum of 102, the average price realised being £103 6s. 1d. In May, 1895, the state floated a  $3\frac{1}{2}$  per cent. loan of £750,000, having a forty years' currency, but redeemable from 1915 on twelve months' notice being given. The minimum price was fixed at 99, and the average obtained was £103 1s. 5d., or, deducting accrued interest, £101 9s. 2d.

In May, 1896, Western Australia, following the example of New Zealand and New South Wales, placed on the market a 3 per cent. loan for £750,000, having a currency until 1935, but redeemable from 1915 on twelve months' notice being given. A sinking fund is to be established in connection with this loan, commencing three years after flotation, the contribution being 1 per cent. per annum. The gross price obtained was £100 16s. 8d., and the accrued interest amounted to about 7s. 6d., so that the Government obtained £100 9s. 2d. This is the cheapest loan yet floated by any of the Australasian states.

In May, 1897, an issue of £1,000,000 was floated in London, the minimum price being fixed at 95, and the rate of interest 3 per cent. The loan is redeemable in 1935, and the net proceeds per £100, after allowing for charges and accrued interest, amounted to £93 8s. 11d.

In January, 1898, an issue of £1,000,000 was placed in London, being the first instalment under the Coolgardie Gold-fields Water Supply Loan Act, the minimum price being fixed at £95, and the rate of interest 3 per cent. For this, applications to the amount of £2,891,250 were received. The loan matures in 1927, and the net proceeds were £94 15s. 3d. per £100.

In July, 1898, a further issue of £1,000,000 was floated in London, being the second instalment under the Loans Act of 1896, the minimum price being fixed at £94, and the rate of interest 3 per cent. At the public tendering only £550,000 were offered, which brought an average price of £94 3s. 4d. The balance was sold afterwards at the minimum, which brought the average down to £94 1s. 10d. per cent. The loan is redeemable in 1935, and the net proceeds per £100 amounted to £91 19s. 4d.

In March, 1900, another issue of £1,000,000 was floated in London, the minimum price being fixed at £93 $\frac{1}{2}$ , and the rate of interest 3 per cent. The amount offered was £1,570,000, and the average price obtained was £93 12s. 9 $\frac{1}{2}$ d. per cent., while the net proceeds per £100, after deducting accrued interest and expenses, came to £89 13s. 2d. In November, 1900, loans to the amount of £880,000 were negotiated, the rate of interest being raised to  $3\frac{1}{2}$  per cent. The net proceeds per £100 were £96 8s. 3d. and the rate paid by the Government, allowing for

redemption at par at the latest date of maturity (1935) was £3 13s. 8d., while the corresponding yield to original investors was £3 11s.

During the year ended 30th June, 1904, loans aggregating £468,290 were floated locally, but no particulars in connection with them are yet available.

The Government has authority to issue Treasury bills, but there were no bills outstanding on the 30th June, 1904.

*Tasmania*, in March, 1893, issued a 3½ per cent. loan of £800,000, which was part of the £2,100,000 authorised in December, 1892. The loan was only a partial success, £600,000 being taken up and the balance withdrawn. The average price realised per £100 was £92 2s. 2d. In 1894 a loan of £1,000,000 was negotiated in London, the rate of interest being 4 per cent., and the date of maturity between 1920 and 1940, at the option of the Government on 12 months' notice being given. The average amount realised per £100 was £101 4s. 3d. In February, 1895, a 3½ per cent. loan of £750,000 was floated, redeemable in 1940, or from 1920 on 12 months' notice being given. The price realised was £98 6s. 1d. In 1901, stock to the amount of £450,000 was sold in London, being the first 3 per cent. loan placed there. The amount realised averaged 92 per £100, but no other particulars are available.

In 1895 authority was given for the issue of £250,000 "local inscribed stock" to cover deficiencies in revenue, and in 1896 and 1897 further sums of £250,000 in each year, and a sum of £100,000 in 1898, were authorised. Prior to the passing of the Appropriation Act of 1899 the whole of the local inscribed stock hitherto raised in the state was placed in the Treasury books to an account for stock raised temporarily in aid of Consolidated Revenue; but as the amount raised was far in excess of revenue requirements, and was largely being used to meet expenditure on loans and public works accounts, which had not otherwise been provided for, a transfer of the whole of the local inscribed stock then issued, and maturing subsequently to the year 1900, was effected by that enactment, and was marked as an addition to the funded debt of the state. The amount so treated was £510,747, leaving a sum outstanding on the 31st December, 1899, of £91,727, which has been duly paid off.

Local inscribed stock for general purposes was sold during 1900 to the amount of £270,258, the rate of interest being 3 per cent., while during 1901, £136,000 was sold at 3 per cent., £25,000 at 3½ per cent., and £252,000 at 3½ per cent. During 1902, local inscribed stock to the amount of £302,719 was sold, and in 1903 similar stock to the amount of £150,100, but no particulars in connection therewith are available.

During 1894, Treasury bills to the amount of £96,900 were negotiated in the state, viz., £40,500 at 4 per cent. and £56,400 at 4½ per cent., the bills having a currency until 1899 and 1900 respectively. The total amount of Treasury bills floated was £215,000, and they have

all been redeemed. During the year ended 31st December, 1903, Treasury bills in aid of revenue amounting to £107,330 were issued locally.

*New Zealand.*—Under the amending Consolidation Act of 1884, short-dated debentures are issued pending the sale of inscribed stock under the Act of 1877. In May, 1895, New Zealand placed a loan for £1,500,000 on the market. With the exception of some New South Wales Treasury bills, this was the first 3 per cent. loan floated by any of the Australasian colonies. The loan has a currency of fifty years, and the minimum price was fixed at 90. The average gross price obtained was £94 8s. 9d., so that, after deducting accrued interest, the Government obtained £93 14s. 6d.

In February, 1899, a further issue of £1,000,000 was placed in London, the minimum price being fixed at £96, and the rate of interest 3 per cent. For this stock applications to the amount of £3,027,500 were received. The loan is redeemable in 1945, and the average price secured was £96 11s. per cent. This was the last flotation in London till November, 1901, when a loan of £1,500,000 was floated at 3 per cent. The price of issue was £94 per £100, and the loan was underwritten at a fee of £1 per cent. The amount subscribed by the public was £665,000, and that taken by the underwriters £835,000. The cost of raising the loan was £41,996. 'Debentures and stocks have been sold locally, £500,000 being disposed of in 1900-1, bearing interest at 4 per cent., and £250,000 in 1901-2 at the same rate of interest. Authority was given to raise £1,750,000 under "The Aid to Public Works and Land Settlement Act of 1902," and £1,000,000 of the loan so authorised, together with £250,000 authorised by "The Government Advances to Settlers Extension Act, 1901," was placed upon the London market in February, 1903, the loan carrying 3 per cent. interest. The price of issue was £94 10s. per £100. Inclusive of £50,000 New Zealand 3 per cent. stock the net amount realised was £1,148,719. During the year ended 31st March, 1903, under the authority of "The Aid to Public Works and Land Settlement Act, 1902," an amount of £750,000, and a sum of £338,700 under "The Land for Settlements Consolidation Act, 1900," were raised locally; these amounts carry interest at the rate of 4 per cent. Under "The Aid to Public Works and Land Settlement Act, 1903," an amount of £500,000 was raised locally or in Australia. The loan carries interest at the rate of 4 per cent., with an alternative currency of five or twenty years at the option of the Government.

The amount of Treasury bills outstanding on the 31st March, 1903, was £700,000; the issue during the ensuing twelve months amounted to £1,100,000, while bills representing £1,100,000 were paid off, leaving the amount outstanding on the 31st March, 1904, at £700,000. As, however, allowance is made for these at the end of the financial year when carrying forward the balance of the Revenue Account, the liability is practically wiped out.

The particulars of the latest issues of the Funded Debts negotiated in London for which information is available are as follow :—

State.	Year of Issue.	Year of Maturity.	Nominal—		Net Proceeds, less charges and accrued interest.		Effective annual interest per £100 sterling, paid by Government.	
			Interest.	Amount of Loan.	Total.	Per cent.	Nominal interest on net Proceeds.	Rate paid, allowing for redemption at par on maturity.
			per cent.	£	£	£	£ s. d.	£ s. d.
New South Wales.....	1893	1933	4	2,500,000	2,440,549	97.02	4 2 3½	4 3 0½
" .....	1894	1918	2½	882,000	829,551	99.70	3 10 10	3 19 11
" .....	1895	1935	3	4,000,000	3,804,573	95.14	3 3 6½	3 4 2½
" .....	1898	1935	3	1,500,000	1,479,746	98.66	3 1 3½	3 1 0
" .....	1891	1895	3	4,000,000	3,644,918	91.12	3 6 4	3 9 0
" .....	1902	1935	3	3,000,000	2,727,191	90.91	3 6 6	3 8 7
Victoria.....	1892	1921-26	2½	2,000,000	1,870,696	90.53	3 18 0	3 19 2½
" .....	1898	1911-26	4	2,107,000	1,989,733	94.91	4 5 1½	4 6 0
" .....	1899	1925-49	3	1,600,000	1,491,355	93.21	3 4 4	3 5 7
" .....	1901	1925-49	3	3,000,000	2,606,976	89.86	3 7 3½	3 8 3
" .....	1908	.....	2½	2,944,780	2,650,419	89.40	.....	.....
Queensland .....	1893	1930	2½	1,182,400	1,014,162	85.77	4 2 4	4 4 4½
" .....	1895	1945	2½	1,250,000	1,230,274	98.42	3 11 9	3 11 10½
" .....	1896	1947	3	1,500,000	1,484,122	96.61	3 3 2½	3 3 7½
" .....	1900	1950	3	1,400,000	1,277,590	91.26	3 6 3	3 7 0
" .....	1901	1947	3	1,374,213	1,217,780	88.61	3 8 2½	3 9 4½
" .....	1903	.....	2½	750,000	607,500	83.00	.....	.....
South Australia .....	1890-4	1930	2½	1,582,900	1,417,457	92.47	3 16 4½	3 17 0
" .....	1892-4	1930	2½	513,200	497,062	96.88	3 12 11	3 13 2½
" .....	1896	1925	3	889,500	800,406	90.84	3 3 5	3 4 8½
" .....	1897	1916	3	500,000	480,246	96.06	3 2 11½	3 5 4½
" .....	1899	1916	3	1,590,000	1,380,084	92.67	3 5 2½	3 10 2½
" .....	1900	1916	3	1,000,000	908,125	90.81	3 6 6½	3 14 1
Western Australia.....	1892	1911-31	4	400,000	393,211	98.30	4 2 2½	4 2 4½
" .....	1894	1911-31	4	540,000	544,984	100.92	4 0 0½	4 0 0
" .....	1895	1915-35	2½	750,000	709,384	101.46	3 9 7	3 9 5
" .....	1896	1915-35	3	750,000	744,542	99.27	3 0 10½	3 1 0
" .....	1897	1915-35	3	1,000,000	934,465	93.45	4 4 8½	3 5 0½
" .....	1898	1927	3	1,000,000	947,610	94.76	3 3 4	3 5 3
" .....	1898	1915-35	3	1,000,000	919,648	91.96	3 5 8	3 7 3
" .....	1890	1915-35	3	1,000,000	886,683	88.66	3 7 5	3 9 6
" .....	1900	1920-35	3½	880,000	848,422	96.41	3 12 7	3 11 0
Tasmania .....	1893	1920-40	4	1,000,000	994,912	99.49	4 1 2½	4 1 3
" .....	1895	1920-40	2½	760,000	737,308	96.33	3 11 10	3 12 0
" .....	1901	.....	3	450,000	.....	.....	.....	.....
New Zealand .....	1895	1945	3	1,500,000	1,394,117	92.94	3 5 0½	3 5 2½
" .....	1899	1945	3	1,000,000	933,375	93.34	3 4 9	3 5 6
" .....	1901	1945	3	1,500,000	1,398,008	91.20	.....	.....
" .....	1903	.....	3	1,250,000	1,148,719	91.89	.....	.....

\* Approximate.

The Treasury bills outstanding on the 30th June, 1904, were issued to cover deficiencies in revenue, with the exception of £8,129,300 in New South Wales, of which a sum of £4,000 is overdue, £3,408,800 in Victoria, and £1,180,550 in South Australia. The expenses incurred in these issues were practically nil—except for the flotations by New South Wales in London, the usual charges being made for brokerage, commission, and stamp duty—as the bills were sold at par, or a very small discount, and in some cases even at a premium. Particulars of the cost of Treasury bills negotiated prior to 1896 will be found in previous editions of this work.

#### EXPENDITURE FROM LOANS.

In the foregoing pages the chief points dwelt upon have been the amount of the public indebtedness and the credit enjoyed by each state as tested by the selling price of its loans. Before closing this chapter it would be well to consider for what purpose the debts were incurred. The services upon which the proceeds of the public loans were expended are various, but the bulk of the expenditure may be placed to the account of the construction of railways, water supply and sewerage, and electric telegraphs. In the early stages of Australasian borrowing the expenditure was moderate, loans being difficult to raise and interest high; but latterly, as the conditions under which loans could be contracted became favourable, especially since 1881, few of the states have set any bounds to their requirements. It was a repetition of the old experience—the opportunity engendered the desire, and the open purses of the investors tempted the states to undue borrowing and lavish expenditure. What is termed a “vigorous public works policy” was the order of the day, and works were pressed forward which under other circumstances would either not have been undertaken, or have been held back until the growth of population warranted their construction. The plethora of money has been harmful in many ways, the most apparent being the construction of not a few branch railways, in outlying and sparsely-settled districts, which do not pay even their working expenses. But when every allowance is made for unwise or improvident expenditure, it will be found that by far the larger portion of the proceeds of loans has been well expended. In some instances it will be years, taking a most hopeful view of the situation, before many of the revenue-producing works will yield a sum sufficient to pay working expenses and interest; nevertheless, a practical consideration of the conditions which surround Australasian settlement will demonstrate that in some instances the construction of these works was justifiable, for apart from the consideration that they will ultimately be self-supporting, they have already materially assisted in developing the country's resources, and have largely enhanced the value of the public estate. Whether their cost in all cases should have been charged against the loans account is a

different matter, seeing that the rents obtained from public lands, and proceeds of sales, invariably go into the ordinary revenue of the states.

The following statement gives, under a convenient classification, the loan expenditure of each state during 1903-4 :—

Service.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.
	£	£	£	£	£
Railways and Tramways .....	805,530	229,444	388,255	132,376	443,319
Telegraphs and Telephones .....			16,465		
Water Supply and Sewerage .....	316,760	113,592	7,327	150,671	130,442
Harbours, Rivers, and Navigation .....	879,213	3,766	10,073	50,387	84,165
Roads and Bridges .....	47,812			78	
Public Works and Buildings .....	164,063	62,531	58,768	81,058	53,343
Defence .....			9,408	1,157	
Immigration .....			7,654		Cr. 540
Advances to Settlers .....	80,600				
Land for Settlement .....		3,666			
Loans to Local Bodies .....			105,865		
Total .....	2,293,973	417,569	603,905	415,727	710,629

Service.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
	£	£	£	£
Railways and Tramways .....	37,450	2,036,364	828,704	2,865,088
Telegraphs and Telephones .....		16,465	47,227	63,692
Water Supply and Sewerage .....		723,592	16,278	739,870
Harbours, Rivers, and Navigation .....	31,614	1,069,218	10,863	1,070,691
Roads and Bridges .....	89,037	56,927	357,595	474,522
Public Works and Buildings .....	30,472	449,980	552,604	982,934
Defence .....		10,565	38,724	49,289
Immigration .....		7,114		7,114
Advances to Settlers .....		80,600	230,350	300,950
Land for Settlement .....		3,666	632,135	635,801
Loans to Local Bodies .....	28,550	134,415	221,405	355,820
Total .....	167,123	4,608,856	2,326,975	7,544,831

The expenditure of the Commonwealth states during 1903-4 from funds derived from the proceeds of loans was £4,608,856. Of this amount, the sum of £4,037,855 was spent on services, the net revenue from which, during the financial year ended 30th June, 1904, amounted to £5,240,803, and the remainder was chiefly devoted to works such as the construction of roads and bridges, and the erection of schools and public buildings, less obviously a proper charge against loan votes. The loan expenditure of the six Commonwealth states and New Zealand during 1903-4 was £7,544,831, of which amount £5,967,590 was spent on works from which a net return of £6,294,087 was received during the year ended 30th June, 1904.

In most of the states the expenditure from loans was greatly reduced during the years 1893 to 1896. In some cases this was to be attributed to a settled policy of retrenchment; but in others, the

difficulty of raising a loan in London affords a more probable explanation. The expenditure, however, since 1897-8, shows a tendency to increase, the figures for the last financial year being largely in excess of the previous five years in the states of New South Wales, Tasmania, and New Zealand. The expenditure was chiefly on account of revenue-producing works; and in the case of New Zealand and Queensland large advances from loans were also made to local bodies. The expenditure of each state during the last five years is given in the following table:—

State.	1899-1900.	1900-1.	1901-2.	1902-3.	1903-4.
	£	£	£	£	£
New South Wales .....	2,400,943	2,788,120	4,938,212	4,708,815	2,293,973
Victoria .....	1,005,889	932,265	884,275	729,403	417,599
Queensland .....	1,182,868	1,212,020	1,161,689	1,022,405	603,805
South Australia .....	602,650	422,343	566,080	465,554	415,727
Western Australia .....	878,329	1,495,292	1,545,823	1,665,901	710,629
Tasmania .....	176,257	283,537	341,994	238,631	167,123
Commonwealth	6,248,736	7,133,577	9,438,073	8,830,709	4,608,856
New Zealand .....	2,071,604	2,126,141	3,297,100	2,441,865	2,935,975
Australasia .....	8,318,340	9,259,718	12,735,173	11,272,574	7,544,831

The total expenditure of the proceeds of loans from the commencement of borrowing to the end of the financial year 1903-4 for the six Commonwealth states was £220,121,461, and for the whole of Australasia £277,196,111. Of these sums, £190,661,378, or over eighty-six per cent., was spent by the Commonwealth states, and £221,528,110, or seventy-nine per cent., by the six states of Australia and New Zealand in the construction of railways, water supply and sewerage works, electric telegraphs, the improvement of harbours and rivers, advances to settlers, purchase of estates for the purpose of settlement, and advances to local bodies from which a net revenue of £5,240,000 was received during the last financial year in the case of the Commonwealth states, and in that of the whole of Australasia a net return of £6,294,000. The balance was expended on services which, though non-productive, were claimed by their proposers as being necessary in the interests of national development. The expenditure on defence and the payments made to meet deficiency in revenue are the exceptions to the rule which has governed the expenditure of the proceeds of loan issues. The expenditure to cover deficiency in revenue has not been large, and is looked upon as but a temporary charge on the loan funds, while the expenditure on defence has been extremely small in all the states except New South Wales and New

Zealand. The following table shows the total loan expenditure of each state up to the close of the last financial year :—

Service.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.
	£	£	£	£	£
Railways and Tramways .....	47,903,758	33,317,317	23,518,746	13,725,204	9,064,027
Telegraphs and Telephones .....	1,294,337	8,366	1,064,975	991,312	239,398
Water Supply and Sewerage .....	11,245,479	3,303,315	1,259,008	5,064,126	2,373,232
Harbours, Rivers, and Navigation .....	10,195,735	617,824	2,607,558	1,422,139	2,057,798
Roads and Bridges .....	1,654,411	106,259	900,221	1,464,736	162,638
Public Works and Buildings .....	4,864,435	3,190,708	3,170,162	3,478,514	1,066,623
Defence .....	1,421,976	149,324	386,506	293,840	...
Immigration .....	194,430	...	2,951,617	...	23,695
Advances to Settlers .....	508,435	...	...	...	...
Land for Settlement .....	...	209,341	...	235,708	300,000
Loans to Local Bodies .....	...	...	2,098,150	...	...
Total .....	79,283,537	51,402,354	37,956,940	26,676,079	15,304,485

Service.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
	£	£	£	£
Railways and Tramways .....	4,085,243	136,000,855	30,080,453	136,091,306
Telegraphs and Telephones .....	142,410	3,771,758	1,063,693	4,325,461
Water Supply and Sewerage .....	...	29,245,167	742,170	29,987,337
Harbours, Rivers, and Navigation .....	472,453	17,373,597	1,002,216	18,375,723
Roads and Bridges .....	2,214,738	6,482,946	6,635,843	13,113,791
Public Works and Buildings .....	1,397,540	17,188,178	16,651,512	33,839,690
Defence .....	128,139	2,379,825	777,563	3,182,398
Immigration .....	235,080	3,400,132	2,148,000	5,567,132
Advances to Settlers .....	...	568,435	3,543,749	4,062,184
Land for Settlement .....	...	745,049	2,631,148	3,376,197
Loans to Local Bodies .....	318,457	2,416,607	1,803,303	4,219,910
Total .....	8,994,066	220,121,461	57,074,650	277,196,111

In the New Zealand returns, old provincial debts contracted prior to 1876, amounting to £11,535,469, have been included under the head "Public works and buildings," as there is no available record of the services upon which the loans of the old Provincial Governments were expended, except for the construction of railways. There is, however, no doubt that a very large proportion of this expenditure was incurred for war purposes, the cost of suppressing the Maori risings between 1860 and 1870 being charged to loan votes. The figures given for New South Wales, South Australia, Western Australia, and Tasmania under the head of "Railways" include loan expenditure on state tramways, but, except in the case of the first-mentioned state, the amount thus expended is unimportant, as this service in the other states is generally in the hands of municipal authorities or private companies. The Governments of New South Wales and New Zealand have borrowed money for the purpose of making advances to settlers for the improvement of their holdings, such advances being interest bearing and repayable by instalments. The sums advanced by the respective Governments named were—New South Wales, £508,435, to the 30th June, 1904, and New Zealand, £3,543,759, to 31st March, 1904.



In the case of New South Wales a sum of £724,733 was spent on immigration before the inauguration of the General Loan Account, but it is not included in the above table. The total expenditure on immigration in the states comprising the Commonwealth was, therefore, £4,133,865, and for Australasia, £6,281,865.

The subjoined table shows the expenditure per inhabitant on the basis of the figures given in the table on page 732 :—

Service.	New South Wales.			Victoria.			Queensland.			South Australia.			Western Australia.			Tasmania.			Commonwealth.			New Zealand.			Australasia.		
	£	s.	d.	£	s.	d.	£	s.	d.	£	s.	d.	£	s.	d.	£	s.	d.	£	s.	d.	£	s.	d.	£	s.	d.
Railways and Tramways.	33	9	8	31	13	10	45	3	5	37	5	5	50	15	11	22	17	10	34	14	3	34	6	3	32	18	2
Telegraphs and Telephones.	0	18	1	0	0	2	2	0	11	2	13	10	1	3	8	0	16	0	0	19	2	1	5	6	1	0	8
Water Supply and Sewerage.	7	17	1	7	5	7	2	8	4	13	15	0	12	13	0	....	7	8	8	0	17	11	6	5	11		
Harbours, Rivers, and Navigation.	7	2	5	0	10	3	5	0	2	3	17	3	9	1	2	2	12	11	4	8	4	1	4	3	3	17	2
Roads and Bridges.	1	3	1	0	1	9	1	14	7	3	10	6	0	12	7	12	8	2	1	12	11	8	0	7	2	15	1
Public Works and Buildings.	3	8	0	2	12	9	6	1	10	9	8	11	4	15	8	7	16	7	4	7	4	20	8	1	7	2	2
Defence.	0	19	10	0	2	6	0	14	10	0	16	0	....	....	....	0	14	4	0	12	11	0	18	8	0	18	3
Immigration.	0	2	9	....	....	5	13	5	....	....	0	2	6	1	6	4	0	17	4	2	12	0	1	3	4		
Advances to Settlers.	0	7	1	....	....	....	....	....	....	....	....	....	....	....	....	....	0	2	7	4	5	9	0	17	0		
Land for Settlement.	....	....	0	3	5	....	....	0	12	10	1	6	5	....	....	....	0	3	10	3	3	8	0	14	2		
Loans to Local Bodies.	....	....	....	....	4	0	7	....	....	....	....	....	....	1	15	8	0	12	4	2	3	8	0	17	9		
Total.....	55	7	7	42	10	3	72	18	1	72	8	9	69	11	11	50	7	10	55	19	8	30	1	4	58	4	3

A perusal of the previous pages indicates that while the public debt of the states of the Commonwealth, on the 30th June, 1904, aggregated £227,637,163, there has been an expenditure of £220,121,461 on public services; and that in New Zealand the total debt stood at £57,522,215 and the loan expenditure £57,040,650. An attempt has been made in the previous pages to classify this expenditure under such specific headings as would admit of the amount being ascertained on which there is a margin left after the payment of working expenses to meet interest on capital cost. In the subjoined table the receipts, expenditure, and the amount available to meet the interest on capital expenditure in connection with the services are set forth, and it will be observed that so far as the Commonwealth states are concerned, the net revenue shows a return of 2·30 per cent. on the public debt of the states, and for the whole of Australasia, 2·21 per cent. In the consideration of these figures, the fact must not be overlooked that the transactions of the past twelve months can by no means be considered normal, inasmuch as the greater part of Australia, and certainly that portion involving the most vital interests, has not altogether recovered from the effects of a severe drought, and as a consequence not only were the avenues

of revenue restricted, but the working expenditure necessary to obtain the results secured unduly increased. There may have been other items of receipts that might be included but have been overlooked; the sum of such items in any case would, however, be very small.

Service.	New South Wales.			Victoria.		
	Receipts.	Expenditure.	Amount available to meet interest on capital cost.	Receipts.	Expenditure.	Amount available to meet interest on capital cost.
	£	£	£	£	£	£
Railways and Tramways .....	4,263,744	2,921,026	1,342,718	3,400,243	1,894,553	1,505,690
Water Supply and Sewerage .....	444,148	141,550	302,598	190,401	28,163	162,238
Harbours, Rivers, and Navigation .....	407,763	282,765	124,998	77,673	32,205	45,468
Advances to Settlers .....	12,158	4,456	7,702			
Loans to Local Bodies .....						
Land for Settlement .....				6,049		6,049
Total .....	5,127,813	3,349,797	1,778,016	3,674,366	1,954,921	1,719,445

Service.	Queensland.			South Australia.		
	Receipts.	Expenditure.	Amount available to meet interest on capital cost.	Receipts.	Expenditure.	Amount available to meet interest on capital cost.
	£	£	£	£	£	£
Railways and Tramways .....	1,296,961	810,251	486,710	1,173,396	663,800	484,796
Water Supply and Sewerage .....				144,839	44,942	99,897
Harbours, Rivers, and Navigation .....				25,788	11,349	14,439
Advances to Settlers .....						
Loans to Local Bodies .....	101,218		101,218			
Land for Settlement .....				15,220	100	15,000
Total .....	1,398,179	810,251	587,928	1,364,243	749,951	614,232

Service	Western Australia.			Tasmania.		
	Receipts.	Expenditure.	Amount available to meet interest on capital cost.	Receipts.	Expenditure.	Amount available to meet interest on capital cost.
	£	£	£	£	£	£
Railways and Tramways .....	1,612,008	1,228,235	384,373	243,024	106,351	81,673
Water Supply and Sewerage .....	78,250	13,738	64,512			
Harbours, Rivers, and Navigation .....						
Advances to Settlers .....						
Loans to Local Bodies .....				10,555		10,555
Land for Settlement .....						
Total .....	1,690,258	1,241,973	448,884	253,579	106,351	92,228

Service.	Commonwealth.			New Zealand.		
	Receipts.	Expenditure.	Amount available to meet interest on capital cost.	Receipts.	Expenditure.	Amount available to meet interest on capital cost.
	£	£	£	£	£	£
Railways and Tramways .....	11,900,976	7,714,016	4,235,960	2,167,902	1,451,954	716,038
Water Supply and Sewerage .....	857,647	228,298	629,354	.....	.....	.....
Harbours, Rivers, and Navigation .....	511,224	328,319	184,905	.....	.....	.....
Advances to Settlers .....	12,158	4,456	7,702	132,712	8,032	124,680
Loans to Local Bodies .....	111,773	.....	111,773	67,498	.....	67,498
Land for Settlement .....	21,269	160	21,109	150,407	4,789	145,668
<b>Total .....</b>	<b>13,514,047</b>	<b>8,273,244</b>	<b>5,240,903</b>	<b>2,518,609</b>	<b>1,465,325</b>	<b>1,053,234</b>

Service.	Australasia.		
	Receipts.	Expenditure.	Amount available to meet interest on capital cost.
	£	£	£
Railways and Tramways .....	14,167,968	9,165,970	5,001,998
Water Supply and Sewerage .....	857,647	228,298	629,354
Harbours, Rivers, and Navigation .....	511,224	328,319	184,905
Advances to Settlers .....	144,870	18,088	126,782
Loans to Local Bodies .....	178,271	.....	178,271
Land for Settlement .....	171,676	4,809	166,777
<b>Total .....</b>	<b>16,082,656</b>	<b>9,783,509</b>	<b>6,294,087</b>

## EXPENDITURE BY THE GOVERNMENT AND LOCAL BODIES.

The question of Local Government is dealt with in another chapter. It is well, however, to give here a statement of the total amount which has passed through the hands of the general and local governments. The sum can in no sense, however, be taken as the cost of governing the various states; as will appear from page 696, this may be taken as £15,657,223 for the six Commonwealth states, and £18,992,124 for the whole of Australasia.

The total sum expended by the general and local governments of the Commonwealth states during the year 1903-4 was £37,944,705, or £9 12s. 10d. per head, and for Australasia £49,689,520, or £10 8s. 7d. per head. Of these large sums, £29,127,665, or £7 8s. per inhabitant, was spent by the general governments of the six Commonwealth states from their revenues, and £4,608,856, or £1 3s. 5d. per inhabitant, from loans; the local expenditure—exclusive, of course, of a sum equal to the

Government endowment—was £4,208,184, or £1 1s. 5d. per inhabitant. For the six Commonwealth states and New Zealand the expenditure by the general government from revenue was £35,561,946 or £7 9s. 4d. per inhabitant, and from loans £7,544,831, or £1 11s. 8d. per inhabitant; while the local expenditure, exclusive of government endowment, amounted to £6,582,743, or £1 7s. 7d. per inhabitant.

The following table shows the general, loan, and local expenditure for each state :—

State.	General Government.		Local Government.	Total.
	From Revenue.	From Loans.		
	£	£	£	£
New South Wales.....	11,319,887	2,293,973	927,560	14,541,420
Victoria .....	6,914,993	417,599	2,187,897	9,520,489
Queensland.....	3,607,864	603,805	452,202	4,663,871
South Australia.....	2,707,253	415,727	244,893	3,367,873
Western Australia.....	3,698,312	710,629	201,837	4,610,778
Tasmania.....	879,356	167,123	193,795	1,240,274
Commonwealth .....	29,127,665	4,608,856	4,208,184	37,944,705
New Zealand .....	6,434,281	2,935,975	2,374,559	11,744,815
Australasia .....	35,561,946	7,544,831	6,582,743	49,689,520

The expenditure per inhabitant, under the same classification, will be found below. The distribution of the expenditure for New South Wales, between general and local government, is to some extent misleading, as 38 per cent. of the population lives outside the boundaries of the municipalities :—

State.	General Government.		Local Government.	Total.
	From Revenue.	From Loans.		
	£ s. d.	£ s. d.	£ s. d.	£ s. d.
New South Wales..	7 18 2	1 12 1	0 12 11	10 3 2
Victoria .....	5 14 5	0 6 11	1 16 2	7 17 6
Queensland .....	6 18 7	1 3 2	0 17 4	8 19 1
South Australia ...	7 7 0	1 2 7	0 13 4	9 2 11
Western Australia..	16 5 7	3 2 7	0 17 9	20 5 11
Tasmania .....	4 18 7	0 18 8	1 1 7	6 18 10
Commonwealth	7 8 0	1 3 5	1 1 5	9 12 10
New Zealand .....	7 15 9	3 11 1	2 17 0	14 3 10
Australasia ...	7 9 4	1 11 8	1 7 7	10 8 7

## POSTS AND TELEGRAPHS.

THE first Australasian post-office was established by Governor Macquarie in the year 1810, Mr. Isaac Nichols being appointed Postmaster. The office was in High-street (now known as George-street), Sydney, at the residence of Mr. Nichols, who was, "in consideration of the trouble and expense attendant upon this duty," allowed to charge on delivery to the addressee 8d. for every English or foreign letter of whatever weight, and for every parcel weighing not more than 20 lb., 1s. 6d., and exceeding that weight, 3s. The charge on colonial letters was 4d., irrespective of weight; and soldiers' letters, or those addressed to their wives, were charged 1d. Very little improvement in regard to postal matters took place for some years.

In 1825 an Act was passed by Sir Thomas Brisbane, with the advice of the Council, "to regulate the postage of letters in New South Wales," giving power for the establishment of post-offices, and to fix the rates of postage. It was not, however, until 1828 that the provisions of the Act were put into full force. The rates of postage appear to have depended upon the distance and the difficulty of transmission. The lowest single inland rate was 3d., and the highest 12d., the postage on a letter increasing according to its weight, which was fixed for a single letter at  $\frac{1}{4}$ -ounce. Letters between New South Wales and Van Diemen's Land were charged 3d. each (ship rate), and newspapers 1d. Other ship letters were charged 4d. single rate, and 6d. for any weight in excess. The privilege of franking was allowed to the Governor and a number of the chief public officials, and letters to and from convicts passed free under certain regulations.

In 1831 a twopenny post was established in Sydney; and in 1835, under Sir Richard Bourke, the Act of 1825 was repealed and another Act was passed, fixing the charge on a single letter at 4d. for 15 miles, 5d. for 20 miles, 6d. for 30 miles, and so on up to 1s. for 300 miles. In 1837 a post-office was established in Melbourne, and a fortnightly mail was established between that city and Sydney. Stamps were introduced in the same year in the shape of stamped covers or envelopes, which are believed to have been the first postage-stamps ever issued. By 1838 there were 40 post-offices in the state of New South Wales, which at that time, of course, included the territory now known as Victoria and Queensland; and in the Sydney office about 15 persons were employed. The revenue of the Department for the year was

£8,390, and the expenditure £10,347 ; while payments were made by the New South Wales Government to the post office at Kororaraka, in New Zealand, which was not created a separate colony until 1841. In 1847 an overland mail between Sydney and Adelaide was established. Stamps in their present form were issued in 1849, and the postage rates were fixed at 1d. per  $\frac{1}{2}$  oz. for town and 2d. for country letters, at which they remain in most of the states to-day.

Regular steam mail communication with Great Britain was first established in 1852. Until that time the Australian colonies had to depend upon the irregular arrival and despatch of sailing vessels for the carriage of mails ; but in the year mentioned the steamships *Australia*, *Chusan*, and *Great Britain* were despatched from England, making the voyage in 60 days, and causing a strong desire in the minds of the colonists for a more frequent and steady system of steam communication with the Old World. The outbreak of the Crimean War in 1854 hindered for a while the accomplishment of this object ; but in 1856 a line of steamers was again laid on, and the service was carried on by the Peninsular and Oriental Company and the Royal Mail Company for some years, but without giving so much satisfaction to the public as might have been expected.

As far back as 1854 a proposal was made for the establishment of a line of mail packets *via* Panama, and negotiations on the subject were carried on for several years between the British Government and the Governments of New South Wales and New Zealand. The result was that in 1866 the service was started, and continued in operation until the end of 1868, when it was terminated through the failure of the company by which it had been carried out. In the following year New South Wales, in conjunction with New Zealand, inaugurated a mail service *via* San Francisco, which, with a few interruptions and under various conditions, has been continued up to the present time.

The establishment of a mail route *via* America had the effect of stimulating the steamship-owners who were engaged in the service *via* Suez, and from that time there was a marked improvement in the steamers employed, as well as in the punctuality and speed with which the mails were delivered. The Peninsular and Oriental Company have carried mails for the colonies almost from the inception of the ocean steam service, with very few interruptions. Towards the end of 1878 the Orient Company commenced carrying mails between Australia and the United Kingdom, and have continued to do so ever since. In the year 1883 the fine steamers of the Messageries Maritimes of France entered the service, followed in 1887 by the North German Lloyd's, so that there are now sometimes two or even three mails received and despatched every week, and a voyage to Europe, which was formerly a formidable undertaking, involving great loss of time and much discomfort, is regarded as a mere pleasure trip to fill up a holiday.

In the year 1893 another mail service was established, by a line of steamers running from Sydney to Vancouver Island, in British Columbia.

There is also a line of steamers running between Brisbane and London, but the states other than Queensland make little use of these vessels.

Under the provisions of the 51st clause of the Commonwealth of Australia Constitution Act, the control of the Post and Telegraph services became vested in the Commonwealth, and by proclamation these services were taken over on the 1st March, 1901. The systems of administration, and the rates levied in force in each state at the date of union were however continued until the Commonwealth Postal Act was brought into operation on the 1st November, 1902, thus securing uniformity in all the states.

#### GROWTH OF POSTAL BUSINESS.

The growth of postal business in each of the states during the forty-three years from 1861 to 1903 is shown below. It will be seen that the number of letters for all Australasia in 1861 was less than the present total for any individual state, with the exception of Tasmania. The true total for Australasia is, of course, not to be found by adding the figures of the several states together, as interstate letters are counted both in the state from which they are despatched and in that in which they are received for delivery. A second total is therefore given from which this excess has been excluded:—

State.	Post Offices.		Letters and Post-cards.		Newspapers.		Packets.	
	1861.	1903.	1861.	1903.	1861.	1903.	1861.	1903.
New South Wales....	340	2,228	4,369,463	92,238,211	3,384,245	37,900,340	105,338	16,305,421
Victoria .....	309	1,646	6,109,929	105,922,527	4,277,179	37,706,769	....	14,068,300
Queensland .....	24	1,325	515,211	24,244,089	427,489	18,510,626	8,555	8,441,438
South Australia .....	160	705	1,540,472	24,407,908	1,069,424	8,274,442	....	2,749,042
Western Australia ..	..	218	198,817	15,786,777	137,476	9,171,203	....	4,483,618
Tasmania .....	100	373	835,373	9,911,692	895,656	7,201,733	....	2,980,620
Commonwealth ..	..	6,501	13,564,265	272,511,204	10,211,469	118,765,613	....	48,968,443
Commonwealth (excluding Inter-State excess) ..	..	..	12,844,300	253,799,472	9,608,000	99,580,261	....	44,314,366
New Zealand ..	..	1,844	1,236,768	68,140,920	1,428,351	19,696,434	....	19,895,363
Australasia .....	..	8,245	14,801,038	335,652,124	11,639,820	133,462,047	....	68,898,806
Australasia (excluding intercolonial excess) ..	..	..	14,061,000	315,541,674	10,941,400	118,035,458	....	63,907,387

A corresponding table to that already given, showing the number of letters, newspapers, and packets per head of population, is appended :—

State.	Letters and Post-cards.		Newspapers.		Packets.	
	1861.	1903.	1861.	1903.	1861.	1903.
New South Wales .....	12	65	10	27	1	12
Victoria .....	11	87	8	31	.....	11
Queensland .....	17	47	14	26	1	16
South Australia .....	13	66	9	23	.....	7
Western Australia .....	12	72	9	42	.....	20
Tasmania .....	9	66	10	40	.....	17
Commonwealth.....	11	70	8	29	.....	13
New Zealand .....	14	77	16	24	.....	24
Australasia* .....	11	67	9	29	.....	13

\* Interstate excess excluded.

Western Australia takes the lead in the transmission of newspapers, Victoria in letters and postcards, and New Zealand in packets. A comparison of the average number of letters and postcards per head of population in Australasia with similar figures for the principal countries of the world is afforded by the table given below. It will be seen that on a population basis the correspondence of Australasia exceeds that of any of the countries named, with the exception of the United Kingdom and the Argentine Republic :—

Country.	Letters and Post-cards per head.	Country.	Letters and Post-cards per head.
United Kingdom.....	72	France .....	30
Australasia .....	67	Norway .....	28
Argentine Republic ..	70	Hungary.....	18
Switzerland.....	58	Japan .....	16
Germany.....	57	Italy ... ..	12
Sweden.....	58	Portugal.....	14
Austria .....	44	Spain.....	8
Denmark .....	43	Roumania.....	6
Canada.....	45	Chili .....	5
Belgium .....	38	Greece .....	3
Netherlands .....	34	Russia .....	5



## RATES OF POSTAGE.

The inland letter postage is 1d. per  $\frac{1}{2}$  oz. on town and 2d. on country letters in all the states of the Commonwealth of Australia, except Victoria and South Australia. In Victoria the rate is 1d. per  $\frac{1}{2}$  oz., and in South Australia 2d. per  $\frac{1}{2}$  oz. on all letters posted for delivery within the state. In Victoria the minimum charge was altered in 1890 from 2d. per oz. to 1d. per  $\frac{1}{2}$  oz.; but the loss at that time was too great, and in 1892 the rate was again raised to 2d. per oz.; in 1901 it was once more reduced to 1d. per  $\frac{1}{2}$  oz. In New South Wales the city and suburban rate of 1d. per  $\frac{1}{2}$  oz., which is in force in the Metropolitan Suburban District, is also in operation within a 12-mile radius of Newcastle, and a 13-mile radius of fifty-four of the other principal country towns; also between Broken Hill and its suburbs, Harden and Murrumburrah, Narrabri and Narrabri West, and Wyalong and Wyalong West. The inter-state and intercolonial rate is uniformly 2d. per  $\frac{1}{2}$  oz. in Australasia. On the 1st January, 1901, New Zealand adopted a universal penny postage, and the loss attendant thereon for the year may be set down at about £34,000. By arrangement with the Commonwealth, New Zealand letters come to Australia for 1d., but letters to New Zealand are charged 2d. When this matter was settled it was further arranged that New Zealand should reduce its terminal rate on cable messages exchanged with Australia from 1d. to  $\frac{1}{2}$ d. per word; but, on the other hand, the Commonwealth made a liberal concession by reducing its terminal rate from 1d. per word per state to a uniform 1d. for the whole of Australia.

The diverse rates imposed on the carriage of newspapers in the various states of the Commonwealth, prior to the union, continued after the control became vested in the Federal Government, and up to the 1st November, 1902, when a uniform rate was imposed under the Post and Telegraph Rates Act, 1902. On all newspapers posted for delivery within the Commonwealth by registered newspaper proprietors, or by newsvendors, or returned by an agent or newsvendor to the publishing office, without condition as to the number contained in each addressed wrapper, a charge of 1d. per 20 oz. on the aggregate weight is imposed, and on all other newspapers posted within the Commonwealth for delivery therein,  $\frac{1}{2}$ d. per 10 oz. or fraction thereof for each newspaper is levied. In New Zealand a charge of  $\frac{1}{2}$ d. each is levied upon all newspapers, town and inland. The intercolonial postage is 1d. each to all the states except Queensland, to which province the charge is 1d. each if not exceeding 4 oz., and  $\frac{1}{2}$ d. additional for every succeeding 2 oz.

## REGISTERED LETTERS.

The number of registered letters and packets passing through the post-offices of the Australasian states has largely increased of late

years. In New South Wales the number of such letters in 1903 was 928,521. This number was exceeded during 1901, when the number registered was 1,213,277. Even in 1892, when the total was largely made up of correspondence relating to so-called "consultations," or lottery sweeps connected with horse-racing, which were established in Sydney, and to support which large sums of money were sent to that city from all parts of Australasia, as well as from other countries, the registrations only numbered 1,075,241. Probably not less than 600,000 of the total for New South Wales in 1892 were in connection with these lotteries. The Government of that state dealt with the evil in an amending Postal Bill in 1893, and this illicit branch of the postal traffic was removed to Queensland, where the number of registered letters at once greatly increased, and numbered 541,148 in 1895. But in 1896 the Parliament of Queensland passed an Act making these lotteries illegal, and the evil was transferred to Hobart. The registrations in the northern state in 1903 numbered 256,475. In South Australia 205,821 registered letters were dealt with during the year. In Western Australia 232,167 registered letters and packets were passed through the head office. In Tasmania 317,831 registered letters passed through the post; while in New Zealand the registered articles dealt with numbered 632,299. In Victoria the registered letters dealt with during the year numbered 876,968.

#### PARCELS POSTS.

Excepting Western Australia, where there was no inland service, there were inland, intercolonial, and international parcels posts in operation in 1903; but statistics of the services on a uniform basis are not obtainable. During the year 834,329 parcels, weighing 2,696,392 lb., with a declared value of £398,214, passed through the post-office of New South Wales, the postage collected amounting to £52,052; in Victoria 710,858 parcels, weighing 2,400,000 lb., with a declared value of £1,250,000, yielding a revenue of £34,804, were dealt with; in Queensland the number of parcels which passed through the post-office was 314,651, weighing 1,341,868 lb., and the revenue derived from the service amounted to £18,499; in South Australia 71,975 parcels, weighing 190,081 lb., were forwarded, and the revenue received was £4,089; in Western Australia 40,546 parcels, weighing 33,190 lbs., the declared value of which was £86,563, and which yielded a revenue of £1,588 were dealt with; in Tasmania 59,387 parcels, weighing 102,654 lb., with a declared value of £131,315, passed through the post, and yielded a revenue of £6,433; and in New Zealand the parcels dealt with numbered 327,629, weighing 1,161,584 lb., of which 59,655, weighing 226,969 lb., and valued at £151,236, were received from places outside the colony, and 17,577, weighing 41,707 lb., and valued at £20,844, were despatched from the colony.

## MONEY ORDERS AND POSTAL NOTES.

In all the states there are money order and postal note systems in operation; and in all the states, except Victoria, Queensland, and South Australia, post-office savings banks. In Queensland there is a Government Savings Bank, but it is not placed under the administration of the Postmaster-General. The Victorian Post Office Savings Bank was amalgamated with the Commissioners' Savings Bank in September, 1897. Particulars of the working of these services will be found in the chapter dealing with "Accumulation."

## POSTAL FACILITIES.

The following table shows the number of inhabitants and the area in square miles to each post-office for the year 1903. It will be seen that the most sparsely populated states have the greatest number of post-offices in comparison with their population, but in order to judge of the relative extension of postal facilities the area of country to each office must also be taken into account:—

State.	Number of Inhabitants to each Post Office.	Number of Square Miles of Territory to each Office.
New South Wales .....	642	139
Victoria .....	734	53
Queensland .....	393	504
South Australia .....	521	1,280
Western Australia .....	1,042	4,476
Tasmania .....	475	69
<hr/>		
Commonwealth .....	603	457
New Zealand .....	451	57
<hr/>		
Australasia .....	571	369

## OCEAN MAIL SERVICES.

The Federal Ocean Mail Service, which is carried on by the Orient Pacific and Peninsular and Oriental Steam Navigation Companies, is subsidised by the United Kingdom and all the Australian states. New contracts were entered into on the 1st February, 1898, for a period of seven years. The total amount of the subsidy is £170,000, of which £98,000 is payable by the Imperial authorities and £72,000 by the states in proportion

to their population. The sea transit rates collected from other countries and colonies making use of the service are credited to the Imperial and Colonial Governments in proportion to the amount of their contribution towards the subsidy. The following table shows the amount of the subsidy, with exchange, payable by each of the states during 1903, on the basis of the population at the end of the preceding year. In addition to the subsidy, there are other charges in connection with the service, such as transit rates in France and Italy and in Australia. After adding these, and deducting the postages collected in the states, and the proportion of sea transit rates payable by other countries using the service, the net cost charged to New South Wales in 1903 was £3,491, and to Tasmania £3,174, while South Australia obtained a profit of £2,119, Western Australia of £12,121, and Victoria of £456. No information is available regarding the position of the State of Queensland. New Zealand, although not a contracting party, yet avails itself of the Federal Service for the carriage of mail matter, and its net loss during the year amounted to £2,965 :—

Subsidy, 1903. Net Cost, 1903.			
United Kingdom .....	£98,000	.....	
Australasia—			
New South Wales.....	£26,040	.....	£3,491
Victoria .....	22,555	.....	.....
Queensland.....	9,592	.....	.....
South Australia.....	6,805	.....	.....
Western Australia .....	3,969	.....	.....
Tasmania .....	3,312	.....	3,174
	<hr/>	£72,273	<hr/>
Total .....	£170,273	.....	

The mail service has been performed with great regularity and expedition. The average time occupied by the outward and homeward services in 1903 was as follows :—

	Orient Pacific.	P. and O.
London to Sydney .....	33 $\frac{1}{8}$ days.	32 $\frac{1}{8}$ days.
Sydney to London .....	33 $\frac{1}{8}$ „	32 $\frac{1}{8}$ „

On several occasions the mails from London have been delivered in Sydney in 32 days.

The failure on the part of the Commonwealth Government to obtain suitable offers for the carriage of Australian mails to England will necessitate the introduction of the poundage system on the termination of the present contract.

In addition to the Federal Ocean Mail Service *via* Suez, New South Wales and New Zealand until November, 1890, subsidised the Union

Steamship Company, in conjunction with the Pacific Steamship Company, for a four-weekly service, *via* San Francisco, to the amount of £37,000, of which New South Wales paid £25,750, and New Zealand £11,250. Under the new contract which was entered into, the amount of the subsidy was largely reduced, the contribution being based on the weight of mail matter carried, and New South Wales made an annual payment of £4,000 to the New Zealand Government, subject to appropriation by Parliament. Various extensions of the contract have been made, and at present the New Zealand Government is working under an agreement with the J. D. Spreckels Company (the Oceanic Steamship Company of San Francisco) which expires on the 10th November, 1906. During the year 1903 the net cost of the service to New Zealand was £14,796. New South Wales incurred an expense of £602 during 1903 in connection with this service, and the share of Victoria amounted to £291. The average time occupied in carrying the mails by the San Francisco route during the same year was as follows:—

London to Sydney .....	34 $\frac{1}{2}$ days.
Sydney to London .....	34 $\frac{1}{2}$ ..

During 1893 a calendar monthly service between Sydney and Vancouver was established by the Canadian-Australian Royal Mail Line, the state of New South Wales granting an annual subsidy of £10,000, and the Canadian Dominion one of £25,000. This action was taken more in the interests of trade between the great British colonies in Australasia and America than in those of the postal service. The Government of New Zealand guaranteed a minimum payment of £7,500 annually to this line in consideration of Wellington being made a port of call. But on the expiry of the contract on the 31st March, 1899, a fresh agreement, to hold for four years, was made by the Shipping Company with the Governments of New South Wales and Queensland, by which Brisbane was substituted for Wellington as a port of call, on condition that Queensland paid a subsidy of £7,500. New Zealand, therefore, does not now subscribe to the Vancouver service, though negotiations are pending for the service to embrace that colony. The contract having expired on the 31st April, 1903 a fresh one was entered into for a period of two years. The subsidy paid is £60,000, and is allotted as follows:—Canada, £34,091; New South Wales, £13,636; Queensland, £10,227; and Fiji, £2,046. Sydney is the initial and terminal port, but a call is made at Brisbane and Fiji, and it is provided that the round trip shall not exceed twenty-one days. During 1903 the net cost of the Vancouver service to New South Wales was £8,757; to Victoria £65; and to Queensland £8,179. The average time occupied by the mails in transit from Sydney to London was 38 $\frac{1}{2}$  days.

The Queensland line of steamers, sailing from Brisbane, *via* Torres Straits, carries mails for the Queensland Government, payment being

made according to weight. This route is from four to ten days longer than those previously mentioned. Queensland, under a former contract, paid the company an annual subsidy of £55,000. This arrangement ceased in January, 1890, and under a new contract the state agreed to pay the company an annual subsidy of £19,800 for a four-weekly, or £32,500 for a fortnightly service. The latter service was commenced on 1st July, 1890, the monthly service having lasted nearly six months; but in November, 1891, the contractors, on account of the heavy losses under the fortnightly system, were allowed to revert to the four-weekly service, the subsidy being reduced to the smaller amount mentioned above, viz., £19,800. When the contract expired, an agreement was arrived at for the institution of a subsidised service for purely commercial purposes. This arrangement lasted but a short time, when the subsidy was abandoned by the shipping company, who preferred to run their steamers without restriction. Payment is now only made in accordance with the weight of the mails carried. The amount of mail matter despatched from the other states by the Torres Straits route is very small.

Besides those mentioned, the other steamship companies trading with the Australasian states carry mails, notably the Messageries Maritimes Company and the North German Lloyd's, sailing from Sydney; and the Shaw, Savill, and Albion Company, and the New Zealand Shipping Company, sailing from Lyttelton, *via* Magellan Straits. The companies are paid by the states in proportion to the weight of mail matter carried, but the Messageries Maritimes Company and the North German Lloyd's are in receipt of large subsidies from the French and German Governments respectively.

The postage to the United Kingdom was reduced in January, 1891, from 6d. per  $\frac{1}{2}$  ounce *via* Italy, and 4d. *via* the long sea route, to the uniform rate of 2 $\frac{1}{2}$ d. In 1891 the states were represented at the Congress of the Universal Postal Union held in Vienna, and on the 4th July a convention was signed on their behalf, by which they joined the Union from the 1st October of that year. From that date the rate of postage to all British colonies and possessions and foreign countries included in the Union was reduced to 2 $\frac{1}{2}$ d.

A common scale of postage on newspapers to the United Kingdom and foreign countries has been adopted by the Australasian states, the rate being 1d. for the first 4 ounces, and  $\frac{1}{2}$ d. for every additional 2 ounces.

#### TELEGRAPHS.

The electric telegraph was introduced into these states almost at the time of the earliest railway construction. The first telegraph messages were sent in New South Wales in 1851. In Victoria the telegraph line from Melbourne to Williamstown was opened in 1854. The first line in South Australia, from Adelaide to Port Adelaide,

was opened in 1856; and the first Tasmanian line was completed in 1857. In New Zealand the first telegraph office was opened in 1862; and the line from Brisbane to Rockhampton, the first in Queensland, was opened in 1864. Telegraphic communication was established between Sydney, Melbourne, and Adelaide in 1858. The first telegraph in Western Australia was opened in 1869, and communication between that state and all the others of the group was completed in 1877.

All the states show very rapid progress in regard to telegraphic matters during the period from 1871 to 1881. In the case of Queensland this increase was largely due to the construction of the line to the Gulf of Carpentaria; and in the case of South Australia, resulted from the construction of the lines to Port Darwin, and to Eucla on the boundary of Western Australia. The following table shows the length of telegraphic lines in each state at the last five census periods, and at the end of 1903, so far as the returns are available:—

State.	1861.	1871.	1881.	1891.	1901.	1903.
New South Wales .....	1,616	*4,674	8,515	11,697	14,272	14,395
Victoria .....	.....	*2,295	3,350	6,840	6,467	6,596
Queensland .....	169	2,525	6,280	9,996	10,246	10,180
South Australia .....	597	1,183	4,946	5,640	5,763	6,038
Western Australia .....	.....	*550	1,585	2,921	6,173	6,079
Tasmania .....	.....	*291	928	1,380	1,852	1,852
Commonwealth .....	.....	11,518	23,604	38,474	44,773	45,140
New Zealand .....	.....	2,015	3,824	5,349	7,469	7,779
Australasia .....	.....	13,533	29,428	43,823	52,242	52,919

\* In 1873

The next table gives similar particulars, but the figures represent miles of wire instead of miles of line :—

State.	1861.	1871.	1881.	1891.	1901.	1903.
New South Wales.....	1,981	5,579	14,278	24,780	46,133	62,356
Victoria .....		3,472	6,626	13,989	13,490	15,883
Queensland .....	169	2,614	8,585	17,646	20,537	20,759
South Australia .....	915	1,718	7,228	12,707	17,853	14,846
Western Australia .....		*750	1,593	3,546	9,104	9,369
Tasmania .....		291	1,157	2,822	3,356	3,256
Commonwealth .....		14,424	39,467	75,490	110,463	126,569
New Zealand.....		3,287	9,658	13,235	21,705	22,920
Australasia .....		17,711	49,120	88,725	132,168	149,489

\* In 1873. † Including telephone wires.

The number of telegrams passing along the wires of each state and the revenue received by the Telegraph Departments during the year 1903 were as appended. In the total for Australasia a correction has been made for interstate telegrams recorded in both the despatching and the receiving state :—

State.	Number of Telegrams.	Revenue received.
New South Wales .....	3,638,591	£154,839
Victoria .....	2,820,338	106,839
Queensland .....	1,500,551	83,206
South Australia .....	1,606,598	74,840
Western Australia .....	1,587,734	68,137
Tasmania .....	449,347	17,289
Commonwealth .....	11,603,159	505,210
Do (Interstate excess excluded)†.	9,621,162	.....
New Zealand .....	5,139,383	166,536
Australasia .....	16,742,542	671,746
Do (Intercolonial excess ex- cluded).	14,673,452	.....

In the whole of Australasia there were on the 31st December, 1903, 4,282 telegraph stations, of which 987 were in New South Wales, 878 in Victoria, 481 in Queensland, 290 in South Australia, 172 in Western Australia, 321 in Tasmania, and 1,153 in New Zealand.



In no other country in the world has the development of telegraphic communication been so rapid as in Australasia, and in none has it been taken advantage of by the public to anything like the same extent. Taking Australasia as a whole, there are only four countries that possess a greater extent of telegraph lines, and only seven in which a larger number of messages is actually sent. In no other countries, however, except the United Kingdom, and Belgium, do the number of messages bear anything approaching the same ratio to the population. The following table illustrates these remarks :—

Country.	Length of Telegraph Lines.	Messages.	Messages per head of popu- lation.
	miles.	No.	No.
United Kingdom .....	49,450	92,471,000	2·18
France .....	90,590	47,280,070	1·21
Belgium .....	4,047	14,252,100	2·13
Netherlands* .....	4,010	5,728,222	1·07
Germany .....	83,258	45,216,963	0·80
Denmark .....	3,780	2,409,365	0·98
Sweden .....	10,077	2,813,830	0·54
Norway .....	9,978	2,278,639	1·02
Austria-Hungary .....	39,326	31,554,715	0·69
Switzerland .....	5,556	4,010,943	1·21
Italy .....	28,472	11,682,366	0·35
Spain .....	20,170	4,627,713	0·25
Portugal .....	5,301	4,054,240	0·75
Russia .....	106,417	101,639,542	0·98
Roumania .....	4,350	2,318,683	0·39
United States† .....	196,517	69,790,888	0·92
Canada .....	35,697	5,318,850	0·99
Cape Colony .....	7,634	4,439,459	1·77
Argentine Republic .....	29,397	7,000,000	1·39
Japan .....	16,128	18,073,407	0·40
Commonwealth of Australia .....	45,140	9,621,162	2·45
Australasia .....	52,919	14,673,432	3·10

\* Government lines only. † Western Union Company only.

From the above table it appears that in Australasia during the year over three messages were sent over the telegraph for each inhabitant. In the United Kingdom the number was nearly two and one-fifth for each inhabitant; and in the United States of America about one message to every inhabitant. The return for the United States, however, includes only the lines of the Western Union Company, which owns the principal part of the telegraph system of that country. The other countries shown in the table sent messages ranging from two and one-eighth per inhabitant in the case of Belgium, to about one-fourth per inhabitant in the case of Spain.

## TELEGRAPH RATES.

The rates for the transmission of telegrams within the Commonwealth were determined by the Post and Telegraph Rates Acts, 1902, and came into force on the 1st November, 1902. For ordinary telegrams, not exceeding sixteen words, including the address and signature, the charges are 6d. in town and suburban districts within prescribed limits or within 15 miles from the sending station, 9d. to other places within the state, and 1s. for inter-state, that is, from any one state to any other, and for each additional word, an extra charge of 1d. in each case is made. On telegrams from and to Tasmania, the cable charges of  $\frac{1}{2}$ d. per word are added to those already specified, and double rates are imposed for the transmission of telegrams on Sunday, Christmas Day, and Good Friday, and between the hours of 8 p.m. and 9 a.m., and for urgent telegrams. In New Zealand a charge of 6d. for the first twelve words, including address and signature, and 1d. for each additional word on all inland telegrams is made. Urgent messages are transmitted upon payment of double the ordinary rates.

## CABLE SERVICES.

Australasia is in telegraphic communication with Europe and the rest of the world by means of five cables, three of which are connected with the various Asiatic continental lines, one by America, and one by Durban and along the West Coast of Africa. The first of the three cables by Asia, which were all laid by the Eastern Extension Telegraph Company, Limited, was opened in October, 1872, joining Port Darwin to Banjoewangie, in Java, whence communication is provided with Europe by way of Batavia, Singapore, Madras, and Bombay. In 1879 a duplicate cable was laid down, the states of New South Wales, Victoria, South Australia, Western Australia, and Tasmania agreeing to pay the company a subsidy of £32,400 per annum for a period of 20 years, the amount to be apportioned between the states on the basis of population. At Port Darwin the cables connect with an overland wire, which extends to Adelaide, a distance of 1,971 miles, the construction of which involved an expenditure by the South Australian Government of about half a million sterling. The total length of line between Adelaide and London is 12,570 miles, of which 9,146 miles are submarine cable, and 3,424 miles overland wire. The third cable was laid in 1888 from Broome, in Roebuck Bay, Western Australia, to Banjoewangie. The length of line by this route from Perth to London is 12,296 miles, 10,811 being cable and 1,485 land wire. The eastern states are connected with Broome by a line running from Adelaide, *via* Port Augusta, Eucla, and Albany, to Perth.

The cable joining Tasmania to the continent of Australia was laid in 1869, the length being about 170 miles. It starts from the township of Flinders, near Cape Schanck, in Victoria, and terminates at Low Head, at the mouth of the Tamar, in Tasmania. This line is subsidised to the

extent of £4,200 yearly by the states of New South Wales, Victoria, South Australia, Western Australia, and Tasmania, the contributions being based on the population figures.

New Zealand was joined to the continent by a cable laid in 1876 the length being about 1,191 miles. The line has its Australian terminus within sight of the spot where Captain Cook landed on the shores of Botany Bay, and within a stone's throw of the monument of La Perouse. The New Zealand terminus of the cable is at Wakapuaka, near Nelson, on the Middle or South Island, whence another cable, 109 miles in length, is laid to Wanganui, in the North Island, with an alternate line from White's Bay across Cook Strait to Wellington. For the first ten years after its opening, the New Zealand cable was subsidised by the Governments of New South Wales and New Zealand, their annual contributions being £2,500 and £7,500 respectively. Under agreement, dating from the 1st January, 1893, the Company which laid the cable was guaranteed £26,258 per annum in return for the reduction of the cable rates from 8s. 6d. for the first ten words and 10d. for every additional word to 2s. and 3d. respectively, the Company to bear one-fourth of any loss. On the 1st May, 1885, an amended agreement came into operation under which the guarantee was reduced to £20,000, and the Company ceased to share in any loss. This agreement expired on the 30th April, 1900, and the Company in proposing a renewal claimed that the guarantee should be increased to £26,000. This was absolutely declined by New Zealand, and the Company then determined on a uniform word rate of 3d., and abolished the minimum charge of 2s. for the first ten words. This was agreed to, pending the laying of the Pacific Cable.

As a direct result of the completion of the Pacific cable of which the sections, Queensland-Norfolk Island and Norfolk Island-New Zealand, were opened for business on the 23rd April, 1902, the charges for New Zealand-Australian telegrams, except to and from Tasmania, were reduced to one uniform rate of 4½d. per word, and to Tasmania to 5½d.; the additional 1d. to Tasmania is to cover the transmission over the Australia-Tasmania cable. In addition to the reduction of the rates for telegrams to and from Australia, the opening of the Pacific cable has benefited senders of cable telegrams to places beyond Australia, by bringing about a general reduction of the rates in New Zealand to the more favourable rates obtaining in New South Wales and some of the other Commonwealth states. The rates on ordinary telegrams from New Zealand to Europe were reduced from 1st June, 1902, from 5s. 2d. to 3s. 4d. per word.

A cable connecting New Caledonia with Queensland at Bundaberg was opened in October, 1893. It was constructed by a French company, and is guaranteed by the French Government to the extent of £8,000, and by the states of New South Wales and Queensland to the amount of £2,000 each annually for a period of thirty years, in return

for which the Governments of these states are entitled to use the cable for the transmission of official messages up to the amount of the guarantee.

During the year 1890 the states opened negotiations with the Eastern Extension Telegraph Company for a reduction in the cable rates to Europe, which at that time were 9s. 4d. per word for ordinary messages and 2s. 8d. per word for press messages sent from New South Wales; and at a conference of the postal and telegraphic authorities a proposal to reduce the tariff to 4s. per word for ordinary messages and 1s. 10d. per word for press messages was agreed to, the states contributing to the subsidy undertaking to make good half the loss which the company would sustain by this reduction in the schedule of charges, and New South Wales, Victoria, Western Australia, Tasmania, and New Zealand at the same time agreeing to pay to South Australia a proportion of the loss to the revenue of that state which the lower charges would cause in the working of the overland wires. The amended tariff came into force in May, 1891, and the amount to be guaranteed to the company for the portion of the year during which the contract was in existence was £158,491. The sum earned by the company for the same period was £120,141, so that the deficiency on the eight months' business was £38,350, one-half of which was made good by the contributing states according to population. But this sum, combined with the amount of the subsidy, was more than the states were prepared to bear, and on the 1st January, 1893, the rates were fixed at 4s. 11d. per word from Sydney to London for ordinary messages, and 1s. 10d. for press messages. Even at these charges there was a loss to be borne, the total amount payable to the cable company being £21,778 in 1893 (as compared with £27,520 in 1892), and £6,191 in 1894; and to the South Australian Government £7,675 in 1893 (as compared with £10,415 in 1892), £822 in 1894, and £1,125 in 1895. Since the years mentioned the amounts guaranteed—£227,000 to the cable company, and £37,552 to the South Australian Government—have been met by the revenue, and the states have therefore not been called upon to contribute. Queensland later joined the other states in the guarantee.

The agreement between the Australian Governments and the Company expired on the 30th April, 1900. In July, 1899, the Company offered to lay a cable to Australia, *via* the Cape of Good Hope, to reduce the tariff per word from 4s. 11d. to 4s. at once, and later to 2s. 6d. under a sliding scale, if the states would agree to certain conditions. South Australia, Western Australia, and Tasmania accepted the terms offered and now enjoy the reduced rates. The other states refused, but notified the Company that they also would accept if certain alterations were made in the agreement, the alterations being intended to safeguard the Pacific cable, to which these states were definitely committed. On the 16th January, 1901, New South Wales entered into the agreement.

The following table shows the amount paid by each state towards cable subsidies and guarantees during the year 1903. From the 1st May, 1901, the whole of the subsidy in connection with the Tasmanian cable has been paid by Tasmania.

State.	Victoria- Tasmania Subsidy.	Queensland- New Caledonia Guarantee.	Total.
	£ s. d.	£ s. d.	£ s. d.
New South Wales .....		1,970 0 0	1,970 0 0
Victoria .....			
Queensland .....		1,970 0 0	1,970 0 0
South Australia .....			
Western Australia .....			
Tasmania .....	5,200 16 9		5,200 16 9
Total .....	5,200 16 9	3,940 0 0	9,140 16 9

The desirableness of constructing a Pacific cable, which shall touch only British territory on its way from Australia to America, was acknowledged by the Governments of most of the Australasian colonies as well as by those of the United Kingdom and Canada, and an informal Conference was held in London in July, 1898, of representatives of Great Britain, Canada, New South Wales, Victoria, Queensland, South Australia, and New Zealand, when it was suggested that Great Britain should pay one-third of the cost of laying such a cable, Canada two-ninths, and the Australian colonies the remaining four-ninths. This proposal was eventually adopted, and in July, 1899, a meeting was held in London by the representatives of the countries interested, and it was agreed that the cable should be laid and that the capital necessary to construct and manage it should be raised and controlled by a Board designated the Pacific Cable Board, comprising Sir Spencer Walpole, as president, representing the United Kingdom; Lord Strathcona, Canada; and the Australian Agents-General their respective states. A contract was entered into with the Telegraph Construction and Maintenance Company of Greenwich, and the Australian shore end of the cable was laid at Southport, Queensland, on the 13th March, 1902, and the cable was completed to Vancouver, and opened for traffic on the 3rd November, 1902. The cable comprises four sections, with a branch to New Zealand from Norfolk Island, the length of the sections being: Brisbane to Norfolk Island, 834 nautical miles; Norfolk Island to Fiji, 961 miles; Fiji to Fanning Island, 2,093 miles; and Fanning Island to Vancouver, 3,240 miles, the branch from Norfolk Island to New Zealand measuring 537 miles.

From the report of the Pacific Cable Board for the year ended 31st March, 1904, it appears that a sum of £1,992,967 has been expended upon the cable. The gross revenue from messages for the year was £81,832

from which has to be deducted £2,008, being the sum paid to the Atlantic and Canadian Pacific Telegraph Companies for supplying the date and the time of filing all messages to and from the United Kingdom and the Continent, leaving the net message reserve at £79,824. The actual expenditure of the Board for the year amounted to £54,284. After making provision for interest the actual deficit on the year's transactions amounted to £89,810.

The direct Cape cable, from Durban to Fremantle, which provides an alternative all-British route to that of the Pacific, was completed on the 19th October, 1901.

#### TELEPHONES.

In connection with the telegraph departments of the various states, telephone exchanges have been established in the capitals and other important centres of population. In order to popularise the use of the instrument, the charges in some of the states have within the last few years been reduced, and the result is seen in a satisfactory extension of this means of communication. Information regarding telephones in the different states during 1903, so far as can be ascertained, will be found in the following table:—

State.	Exchanges.	Telephones.	Length of Telephone Wires.	Revenue.
	No.	No.	miles.	£
New South Wales	57	16,155	.....*	105,002
Victoria .....	20	7,610	22,995	86,600
Queensland.....	15	3,749	5,613	27,321
South Australia...	10	1,974	4,572	23,209
Western Australia	13	3,332	5,431	30,324
Tasmania.....	16	1,236	1,300	8,910
Commonwealth	131	34,056	.....	281,366
New Zealand .....	81	12,105	9,834	71,028
Australasia .....	212	46,161	.....	352,394

\* Not ascertained.

In the Australasian states the rates for telephones at places of business range from £5 to £10 for the maximum length of wire—generally one mile, the colonies with a half-mile radius being New Zealand and Queensland—and the charge is higher in the city than in

the country. In New South Wales and Victoria the city and suburban rates are £9 per annum, and the country rates £8 in the former state, and £7 in the latter. In South Australia the city rate is higher, being £10 within one mile radius of the telephone exchange, and for each additional half-mile up to three miles an extra £1, and for every additional quarter of a mile above three miles one extra £1. Queensland, for a radius of half-a-mile, has a uniform rate of £6, which is also the charge made in Tasmania, for a one-mile radius, in Hobart, Launceston, and Zeehan, while for the suburbs and country districts the rate is a matter of arrangement. In New Zealand a distinction is drawn between exchanges continuously open and those not continuously open, the charges being respectively £7 and £5; while in Western Australia, for commercial subscribers within one mile radius of the telephone exchange the rate is £7, and for every additional half mile, £1 per annum. The charges for telephones at private residences are, of course, less than for places of business. In New South Wales, Victoria, and New Zealand, the rate is uniformly £5; and in Queensland, £6. In South Australia the charge is £5 within one mile radius of the exchange, and for each additional half mile up to 3 miles, an extra £1, and for every additional quarter of a mile above 3 miles, an extra £1; in Tasmania, it is £4 10s. in Hobart, Launceston, and Zeehan, and a matter of arrangement in the suburbs and country; while in Western Australia the charge is £5 within one mile radius of the exchange, and for every additional half mile £1 per annum.

## POSTAL AND TELEGRAPHIC FINANCES.

The following table shows the revenue and expenditure of the Postal and Telegraph Departments of the states during 1903:—

State.	Revenue.				Expenditure.
	Posts.	Telegraphs.	Telephones.	Total.	
	£	£	£	£	£
New South Wales .....	652,761	154,839	105,002	912,602	884,963
Victoria .....	448,486	106,839	86,600	641,925	582,520
Queensland .....	191,931	83,266	27,321	302,518	425,568
South Australia .....	166,400	74,840	23,209	264,449	240,987
Western Australia .....	122,862	68,137	30,324	221,323	277,021
Tasmania .....	75,412	17,289	8,910	101,611	100,232
Commonwealth ....	1,657,852	505,210	281,366	2,444,428	2,511,291
New Zealand .....	343,207	166,536	71,028	580,771	526,747
Australasia .....	2,001,059	671,746	352,394	3,025,199	3,038,036

In the expenditure shown in the table, interest on the outlay on post-office buildings and telegraph lines and maintenance of buildings is not taken into account. If allowance be made for these, so far as is possible from the very imperfect returns concerning the expenditure on post-offices in each state, the total expenditure and the deficiency in revenue would be as follow :—

State.	Departmental Expenditure.	Interest and Maintenance of Works and Buildings.	Total charge.	Deficiency in Revenue.
	£ .	£	£	£
New South Wales .....	884,963	120,076	1,005,039	92,437
Victoria .....	582,520	96,960	679,480	37,555
Queensland .....	425,563	68,036	493,604	191,066
South Australia .....	240,937	59,009	300,896	36,447
Western Australia .....	277,021	27,058	304,079	82,756
Tasmania .....	100,232	8,956	109,188	7,577
Commonwealth .....	2,511,291	330,995	2,892,286	447,858
New Zealand .....	526,747	78,535	606,282	24,511
Australasia .....	3,038,038	459,530	3,497,568	472,369

With the progress of settlement and the increase of population, the expenditure on the postal and telegraphic services naturally expands year by year, and it is apparent that in order to keep pace with the growing needs of the community the department must be administered on ordinary business principles. Hitherto the application of such principles has not been obvious, and perhaps it has not been possible; but now that the affairs of the six states are centred under one control, much of past extravagant expenditure will be avoided, and there is every prospect of the service becoming self-supporting—that is, returning a revenue sufficient not only to meet current expenditure, but provide a surplus to cover maintenance of works and buildings, together with interest on capital cost.



## LOCAL GOVERNMENT:

### MUNICIPAL INSTITUTIONS:

ONLY of recent years has the question of Local Government received the attention which its importance demands, the states of the Commonwealth that have adopted general systems being Victoria, Queensland, South Australia, and Tasmania. New Zealand, however, has also for a number of years been divided into districts with local governing powers. It will be noted, from the information given in the following pages, that the Acts controlling Local Government vary considerably, especially as regards the election of representatives and presiding officers, method of valuation, and rating powers; but the particulars available in regard to each state are not sufficiently exhaustive to admit of making any effective comparison between the systems of the different provinces:

The first portion of this chapter is devoted to an account of the local bodies operating under the various Municipal Acts, while the particulars relating to Boards and Trusts, for the establishment and control of which special Acts have in most cases been passed, will be found in the second part.

#### NEW SOUTH WALES:

The first Act providing for the establishment of a Local Council in this state was passed in 1842, when the City of Sydney was incorporated. In 1867, the Municipalities Act became law, but as that Act left it optional for any district to become constituted as a municipality, only a small proportion of the area of the state is incorporated.

Under the provisions of the original Acts, the aldermen were elected by the ratepayers (except in the City of Sydney, where both owners and occupiers voted), and the mayors were chosen by the aldermen. By legislation enacted in 1900 the franchise was extended to tenants and lodgers in the city of Sydney.

During 1900 the Sydney Corporation Amending Act became law. Under its provisions the city is divided into twelve wards, each returning two aldermen, instead of into eight wards, each represented by three aldermen, as heretofore. The mayor is still elected by the aldermen, as the proposal to provide for his election by the citizens was not carried. Other important amendments are those providing (1) for the abolition of auditors elected by citizens, with the substitution of Government inspectors to audit the accounts; and (2) for the resumption of land for the opening or enlarging of streets or public places. The rating powers have not been altered, the general rate remaining

at not more than 2s. in the £ of the annual value, but lighting and other special rates may also be imposed, if necessary.

The Municipalities Act of 1867 provided that the general rate should not exceed 1s. in the £ of the annual value, but that special rates could be levied, so long as the general and special rates together did not come to more than 2s. in the £. A further charge, limited to 6d. in the £, could be made for street-watering, and an additional rate for water supply, where necessary, the amount not to exceed 1s. in the £.

The condition of Local Government in New South Wales is admittedly unsatisfactory, and various proposals have been made for the amendment of the law, but none of a general character has been passed by Parliament. Recently the Government has laid before the Legislative Assembly a comprehensive scheme for extending Local Government to the eastern and central divisions of the state, and ultimately to the whole area of New South Wales. The scheme proposes to divide the unincorporated area into shires, each shire to have an area of not less than 1,000 square miles; a municipality is to be limited in area to 200 square miles or under, with a population of not less than 1,500. The Bill proposes that the powers that may be exercised by municipalities shall be defined by law, and these powers are very wide, and are to be acquired in instalments as the development of municipal life proceeds. Each local body is invested at its creation with certain elementary duties and responsibilities, and propositions to extend these must be approved of by the electors of the area before the extended powers can be granted. The most important departure in the principles of municipal taxation proposed by the Bill is the authority to be conferred on all local bodies to levy their rates on the unimproved capital value of the land instead of on the annual value of improved property. The essential object of the measure is the establishment of home rule in local affairs throughout the state, and with this end in view as much as possible is left to local bodies, the Bill simply providing for the creation of municipal life. Further development is provided for by the powers which are conferred upon the local bodies to legislate by ordinances.

The total area incorporated at the close of the municipal year 1903 was only 2,829 square miles, so that it will be seen that a large area still remains under the control of the central government in New South Wales. For this some justification is claimed on account of the largeness of the territory and the sparseness of the population residing in the unincorporated areas; but this is hardly tenable, seeing that both these conditions exist to a greater degree in Queensland, where the whole territory is under local government. The total area still unincorporated in New South Wales amounts to 307,871 square miles.

The total capital value of all property in municipalities is returned as £134,218,300, and the annual value as £8,351,420; so that the annual return from property is about 6·22 per cent.

Taking the municipalities as a whole, the following particulars in regard to the number of municipalities, the area incorporated, and the annual and capital values of property assessed for municipal purposes, will not be without interest. The figures relate to all municipalities, and cover a period of twelve years :—

Year.	No. of Municipalities.	Area Incorporated.	Annual Value.	Capital Value.
		acres.	£	£
1892	168	1,637,046	8,697,503	144,277,400
1893	171	1,660,675	8,929,475	150,938,000
1894	175	1,683,990	8,460,674	151,226,000
1895	182	1,754,941	7,895,645	136,202,100
1896	183	1,767,079	7,603,735	127,499,700
1897	183	1,767,749	7,430,120	122,787,000
1898	184	1,768,500	7,379,350	120,625,600
1899	184	1,768,500	7,412,100	121,213,800
1900	189	1,807,522	7,905,760	124,546,200
1901	191	1,802,532	8,109,200	127,996,900
1902	191	1,802,532	8,080,160	130,019,800
1903	192	1,810,912	8,351,420	134,218,300

The annual and capital values of Sydney and suburbs since 1892 are shown below :—

Year.	Sydney and Suburbs.		Year.	Sydney and Suburbs.	
	Annual Value.	Capital Value.		Annual Value.	Capital Value.
	£	£		£	£
1892	6,013,687	106,891,100	1898	4,965,400	86,927,600
1893	6,067,882	110,061,000	1899	4,995,200	87,464,000
1894	5,686,197	108,951,000	1900	5,069,630	88,116,600
1895	5,352,920	96,692,200	1901	5,188,700	90,060,600
1896	5,141,990	91,427,100	1902	5,455,270	93,413,300
1897	5,022,910	88,464,400	1903	5,669,670	96,171,600

A reference to these figures will show the depreciation which has taken place in the value of real estate since 1892, but it is satisfactory

to note that a steady increase is shown from 1898; while the annual value for 1903 exceeds that of any previous year since 1894, and the capital value is higher than in any year since 1895.

In view of the fact that it is proposed in the new Bill to levy rates on the unimproved values of land, the following statement will be of some value :—

Division.	Estimated Unimproved Value.
City of Sydney .....	£20,207,800
Suburban Municipalities.....	19,583,600
Total Metropolitan.....	£39,791,400
Country Municipalities .....	14,753,200
Grand Total .....	£54,544,600

The values of five of the principal towns are given in the subjoined table, and for the purposes of comparison, the corresponding figures for 1892 are shown. With regard to Broken Hill, it should be remembered that the mines were not fully developed in 1892, and although the capital value in 1899 had increased by about £364,000, the values in the years 1894 and 1895 were stated to be £2,952,000, and £2,862,000 respectively, but for 1897 the figures declined to £1,232,600, which was practically the value in 1899. The annual and capital values shown for 1903 exclude the assessments on the output of the silver mines, as the mining companies were successful in the appeals against the rating of their products :—

Town.	1892.		1903.	
	Annual Value.	Capital Value.	Annual Value.	Capital Value.
Bathurst .....	£ 70,363	£ 905,000	£ 55,205	£ 943,000
Broken Hill .....	244,776	1,410,000	221,710	1,438,000
Goulburn.....	88,222	1,330,000	61,755	944,900
Newcastle and suburbs ...	496,200	6,784,000	407,170	6,413,200
Parramatta .....	83,440	1,692,000	63,435	1,368,700

The revenues of municipalities are derived chiefly from rates, but under the Act of 1867 the Government allows an endowment for the first fifteen years following incorporation, the scale being £ for £ of general rates received during the first five years, 10s. per £ during the next five years, and 5s. per £ for the remaining period. The Government also contributes grants in aid of roads and other works, and occasionally a special endowment is given. Rates are levied on nine-tenths of the annual value of improved property, and on 5 per

cent. of the capital value of unimproved land, except in the City of Sydney, where the maximum percentage on unimproved is 6 per cent. The following table shows the receipts during the year ended February, 1903, the Government endowments and grants being specified. The total shown is exclusive of refunds and cross entries, but it includes proceeds of loans :—

Total receipts—	£
Government.....	50,721
Rates .....	580,291
Proceeds of Loans .....	197,949
Other Revenue .....	200,746
Total.....	1,029,707
Receipts per inhabitant in incorporated area—	£ s. d.
Government.....	0 1 2
Rates .....	0 12 10
Proceeds of Loans .....	0 4 5
Other Revenue .....	0 4 5
Total .....	1 2 10

The burthen of rates is, therefore, 1s. 4½d. per £ of annual improved value, and about 2½d. per £ of estimated unimproved capital value.

The total expenditure, exclusive of refunds, &c., for the same period amounted to £978,281, distributed as follows :—

	£
Public works, services, and improvements.....	545,636
Interest on loans and overdrafts .....	134,232
Repayments of loans .....	151,471
Salaries and office expenses .....	80,619
Payments to sinking funds.....	15,315
Other expenditure .....	51,008
	£978,281

The proportion of the expenditure incurred for salaries and office expenses was slightly over 8 per cent., and for interest on loans and overdrafts it was 13·72 per cent., while the average rate of interest payable on the liabilities was 4·46 per cent.

The amount of loans and secured overdrafts outstanding on the 2nd February, 1903, was £2,931,511, of which £1,301,580 was due to investors in London, principally by the city of Sydney, while of the balance, £21,762 was floated in Victoria, and £1,608,169 in New South Wales. The unsecured overdrafts amounted to £79,927, so that the total liability on which interest was payable was £3,011,438. The interest charged ranged from 3½ to 8 per cent. for the secured loans, and from 4 to 8½ per cent. on the unsecured overdrafts. Against the total liability, sinking funds have been established, the total amount at the credit of such funds being £323,894.

## VICTORIA.

In Victoria a comprehensive system of local government has been in force for many years. In 1842 the Act of the Legislative Council of New South Wales, which incorporated Sydney, also constituted Melbourne a municipality, and in 1874 an Act was passed by the Victorian Government under which the general system was inaugurated. The whole of the local government Acts passed up to the year 1890 were consolidated in that year, and in December, 1903, a further consolidation took place, the last Act also amending the law in some particulars. Under the present system the state is divided into cities, towns, boroughs, and shires, the total area under local control being 87,302 square miles, only 582 square miles remaining unincorporated.

The councillors are elected by the ratepayers, and the mayors of cities, towns, and boroughs, or presidents of shire councils, are elected by the councillors. A general rate of not more than 2s. 6d. or less than 6d. in the £ of the annual value may be imposed, but extra rates may be levied, provided that general and extra rates together do not exceed 2s. 6d. in the £. A further rate, called a "separate" rate, may also be charged for works in particular parts of any district, the amount varying according to the requirements of the areas assessed.

The number of municipalities with the annual and capital values of property assessed for local purposes for the eleven years ending with 1904, were as follows :—

Year.	No. of Municipalities.	Annual Value.	Capital Value.
		£	£
1894	203	12,779,600	208,444,800
1895	207	11,676,079	191,538,051
1896	208	10,641,200	181,221,430
1897	208	10,393,000	182,894,800
1898	208	10,345,535	184,364,474
1899	208	10,152,500	181,783,006
1900	208	10,283,500	183,180,010
1901	208	10,537,497	187,409,864
1902	208	10,885,067	198,945,803
1903	208	11,188,932	203,902,919
1904	208	11,437,830	209,143,730

The total capital value of property assessed for municipal purposes in 1904 was £209,143,730, while the annual value was £11,437,830, the figures for Melbourne and suburbs being £81,872,463 and £4,489,181 respectively. The values for the metropolitan district since 1894 are given below, and it will be noticed how great has been the decrease during the period under review, though both the annual and capital

values for 1904 show a marked improvement, and are higher than in any year since 1895 :—

Year.	Melbourne and Suburbs.		Year.	Melbourne and Suburbs.	
	Annual Value.	Capital Value.		Annual Value.	Capital Value.
	£	£		£	£
1894	5,847,079	97,900,240	1900	4,042,497	73,523,845
1895	4,984,596	83,377,584	1901	4,144,816	74,564,733
1896	4,299,515	74,986,355	1902	4,365,297	80,033,929
1897	4,168,182	74,819,140	1903	4,441,649	81,014,350
1898	3,968,888	73,515,367	1904	4,489,181	81,872,463
1899	3,973,357	73,798,015			

If the figures relating to the capital value of Melbourne shown in the present edition be compared with those of previous issues, it will be seen that the value of property has increased by more than 16 millions from 1902 to 1903. There has, however, been no sudden rise in value, such as would appear from the figures; what has happened is that the basis of valuation was changed in the year 1903 by the local authorities from ten times the annual value to twenty times the annual value. There is no reason to doubt the correctness of the view that property in Melbourne is worth 20 years purchase, but there has been no sudden change in valuation, consequently it has been necessary to correct the figures of previous years, and this has been done in the two foregoing tables.

The annual and capital values for the five principal provincial municipalities for 1894 and 1904 will be found in the following statement, the annual return from property having been estimated at 7 per cent. :—

City, Town, or Borough.	1894.		1904.	
	Annual Value.	Capital Value.	Annual Value.	Capital Value.
	£	£	£	£
Ballarat .....	171,047	2,443,529	166,582	2,379,743
Ballarat, East.....	81,745	1,024,900	82,807	1,182,957
Bendigo .....	177,290	2,532,714	200,661	2,866,586
Geelong .....	87,027	1,243,243	91,988	1,314,114
Geelong, West .....	28,998	414,257	27,653	393,743

The revenue of the local governing bodies is chiefly derived from taxation, under the headings of general and special rates (which are levied on the net annual value), licenses, dog fees, market and weighbridge dues, &c. The total amount collected from all sources during the year 1903 was £1,360,647, of which £99,294 was contributed by the Government, either as endowment, special grant, or loan, while the amount of rates received was £772,519, and £174,441 was received from licenses, fees, &c., the total local taxation thus being

£946,960. The balance, £814,393, includes sanitary fees amounting to £44,718, £58,081 received as rents of municipal property, £80,900 as loans, £21,577 for contributions to works, and £109,117 from other sources. The receipts per inhabitant in incorporated areas amounted to £1 4s. 7d. The amount received as rates shown above represents a tax of 1s. 4d. in the £ of annual value, and 1½d. per £ of the estimated unimproved capital value.

The total expenditure for the year 1903 was £1,330,273, of which £811,518 were spent on public works, &c., while the amount paid for interest was £193,638. The payments to sinking funds were £31,411, and the repayments of loans from revenue, £18,735, the other items in the balance being—salaries, £135,730, representing 10·2 per cent. of the total; payments to Fire Brigades, £16,530; expenses of loans, £2,809; charitable institutions, £12,431; and other expenditure, £107,471. The proportion paid as interest on loans and overdrafts was about 14·5 per cent. of the total, while the average interest paid on loans and overdrafts amounted to about £4 9s. 8d. per cent.

The municipal loans outstanding were £4,212,051, of which £275,974 were borrowed through the Government, and the bank overdrafts amounted to £107,090, giving a total interest-bearing liability of £4,319,141. The total liabilities were £4,527,229, other items being—amount due on contracts, £67,335; temporary advances from Government, £13,310; overdue interest on loans, £17,616; and other, £109,827. The assets totalled £3,932,062, and consisted of—municipal property, £2,736,802; sinking funds, £656,314; unexpended loan funds, £223,624; outstanding rates, £130,193; bank balances and cash in hand, £80,417; contributions due for streets, &c., £21,634; and miscellaneous, £83,078.

#### QUEENSLAND.

The beginning of local government in Queensland was the proclamation constituting Brisbane a municipality, the date of which was the 6th September, 1859, or about three months prior to the separation of the state from New South Wales. A general system of government by local authorities was inaugurated in 1878, when the state was divided into boroughs, shires, and divisions, and in 1902 the Local Authorities Act was passed, which consolidated and amended all measures relating to local government. This Act also provides that the local areas shall be called cities, towns, and shires, and the members are called aldermen in cities and towns, and councillors in the shires. The only cities declared under the Act are Brisbane, Rockhampton, and Townsville, but any other town may be constituted a city by proclamation of the Governor in Council, and South Brisbane was so proclaimed during 1903.

The aldermen and councillors are elected by ratepayers in each area, while mayors of cities and towns and chairmen of shires are chosen by the representatives.



Under the provisions of the Act of 1878, the rates were levied on the annual value, and the maximum general rate was 1s. in the £ for boroughs, shires, and divisions, but the minimum was 6d. per £ for boroughs and shires, and 4d. per £ in divisions. Special rates could also be imposed for sewerage, drainage, lighting, street-watering, sanitary works, loans, or particular works. By an amending Act passed in December, 1890, the rates thenceforward were to be charged on the unimproved capital value of the land; and this system has been continued in the 1902 Act. The maximum general rate now allowed is 3d. in the £ for all areas, while the minimum is  $\frac{1}{2}$ d. The special and separate rates may still be charged, and if waterworks have been established a further rate may be imposed for that service. The total amount of all special rates (exclusive of water rates, separate rates, loan, cleaning, and tramway rates, if any) shall not exceed 3d. in the £.

The total area controlled by local bodies is 668,252 square miles, leaving only 245 square miles unincorporated. The total capital value was estimated at the end of 1903 to be £43,150,000. This represents the value of land without improvements; if improvements had been considered, the capital value would have been approximately £72,334,000, and the annual value £4,593,000.

The unimproved capital value declined steadily from 1894 to 1896, but from 1897 it improved gradually, and in 1901 it was even greater than in 1893. The 1902 and 1903 figures show a small falling-off, which was only to be expected owing to the bad seasons. The following statement shows the total unimproved values from 1894 to 1903:—

Year.	Assessed Value of Unimproved Property.	Year.	Assessed Value of Unimproved Property.
	£		£
1894.....	41,772,975	1899 .....	42,195,693
1895.....	40,821,733	1900 .....	42,722,000
1896.....	40,810,384	1901 .....	43,807,000
1897.....	41,009,739	1902 .....	43,203,000
1898.....	41,486,971	1903 .....	43,150,000

The capital values of Brisbane and some of the other large cities and towns are given below for 1893 and 1903:—

Municipality.	1893.	1903.
	Unimproved Capital Value.	Unimproved Capital Value.
	£	£
Brisbane .....	7,508,789	6,538,755
South Brisbane .....	1,429,673	1,439,040
Other Brisbane Suburbs .....	3,804,721	3,509,752
Rockhampton .....	1,326,328	920,626
North Rockhampton .....	189,760	130,792
Townsville .....	944,060	963,583
Toowoomba .....	708,030	646,919

North Rockhampton has been included, as it is a suburb of Rockhampton.

The receipts for the year 1903 amounted to £477,256, the chief sources being—Government endowments, grants, and loans, £60,013 and rates, £340,102 (levied, as already stated, on the unimproved capital value), leaving £77,141 derived from other sources. The amount collected for rates represents 1s. 5½d. per £ of the improved annual value and 1½d. per £ of the unimproved capital value. The expenditure for the same period was £512,215, the amount spent on public works being £316,532, while repayments of loans and interest amounted to £49,333, salaries and office expenses to £56,981, or slightly more than 11 per cent. of total, and all other disbursements £89,369.

The outstanding loans, including overdue instalments payable to the Government, amounted to £939,054, the whole of which, with the exception of part of the loans of the city of Brisbane (£343,000), and part of the indebtedness of South Brisbane (£105,000), is due to the Government, as no local body, except the two mentioned, is allowed to borrow from outside sources. The amount of other liabilities was £220,452, making a total of £1,159,506 owing by local bodies.

The total assets on the same date were given as £1,542,547, the only item specified being outstanding rates, which amounted to £134,406.

#### SOUTH AUSTRALIA.

Adelaide, the capital of South Australia, was proclaimed a municipality as far back as 1840, and was thus the first local body established in Australasia.

The state was divided into district councils in 1876, and corporations were established in 1880, but the original Acts and subsequent amendments were consolidated in 1887 and 1890 respectively, and the various districts are now operating under the last-mentioned statutes.

In district councils the councillors are elected by the ratepayers, and the chairman is chosen by the councillors. In the corporations, however, the mayors and councillors are elected by the citizens, who may be owners or occupiers of property. The rates are assessed on the annual value, and in district councils must not be more than 1s. 6d. nor less than 3d. per £. Special rates may also be levied, provided that the general and special rates do not exceed 2s. 6d. in the £, and separate rates for works in particular areas may also be imposed if necessary. In corporations the general rate is limited to 1s. per £ and lighting and park rates are also charged, the maximum being 4d. and 3d. per £ respectively. Other rates may be declared for street-watering, loans, &c., provided that the total amount of general and special rates does not exceed 2s. in the £.

The total area incorporated at the close of the last municipal year was 42,493 square miles, leaving 337,577 square miles still under the control of the central government. The unincorporated territory consists chiefly of the unsettled portion of the state, as the populous centres have all been brought under municipal government. The figures in this chapter relating to South Australia are in all cases exclusive of the Northern Territory.

The annual and capital values of all the incorporated districts for the ten years ending with 1903 are as shown in the following table:—

Year.	Annual Value.	Capital Value.
	£	£
1894 .....	2,552,820	41,325,000
1895 .....	2,494,326	40,512,000
1896 .....	2,463,564	40,076,000
1897 .....	2,485,995	40,472,000
1898 .....	2,518,688	41,047,000
1899 .....	2,553,415	41,668,000
1900 .....	2,576,729	42,080,000
1901 .....	2,590,357	42,341,000
1902 .....	2,629,027	42,975,600
1903 .....	2,661,238	43,495,900

The capital value of the incorporated districts in 1903 as shown above was estimated at £43,495,900, and the annual value at £2,661,238. Adelaide and its suburbs are the largest corporations, and the following were the values of the most important centres for 1903, compared with those for 1894:—

Corporation.	1894.	1903.
	Annual Value.	Annual Value.
	£	£
Adelaide .....	393,522	443,638
Port Adelaide (including Semaphore) .....	126,471	153,735
Unley .....	88,535	124,860
Kensington and Norwood .....	71,262	76,397
Hindmarsh .....	47,627	58,619
St. Peters .....	44,484	54,112
Glenelg .....	37,654	37,632
Thebarton .....	23,857	33,066
Brighton .....	11,209	10,949

The total receipts for 1903 were £344,397, the amount contributed by the Government as subsidy and grants being £92,568, while the rates collected were £149,909, leaving £101,920 from other sources. The rates collected, which are levied on the annual, value equal 1s. 1½d. in the £ of the annual value, and 1d. per £ of unimproved capital value. The expenditure reached £337,461, the amount spent on works being £179,368, while salaries and office expenses absorbed £28,445, or 8·43 per cent., and miscellaneous services, £129,648.

The corporation loans outstanding at the close of 1903 amounted to only £119,202, of which the city of Adelaide was liable for £67,900. The particulars relating to the loans of district councils are not available. The interest payable on the specified loans ranges from 3 to 6 per cent., the average being 4.55 per cent.

#### WESTERN AUSTRALIA.

The great resources of this state have only been made manifest during recent years, and the limited population, compared with the vast area of the province, has prevented any great extension of local government.

The first Municipalities Act was passed in 1871, but only a few districts were incorporated under it. In 1900 the existing Act, which consolidated the previous Acts, became law, and a considerable increase in the area locally controlled has resulted from its provisions. The local bodies are termed Municipalities, Road Boards, and Health Boards; the latter may be established within or outside municipal boundaries.

The Municipal Act provides for the election of both councillors and mayors by the ratepayers. With regard to Road Boards, which are administered under the Roads Act of 1902, the members are elected by the ratepayers, and the chairmen by the members. In 1904 another local government measure, called the Water Boards Act, was passed, under which Boards may be appointed for the control of water works, and rates may be levied for the purpose, the maximum being fixed at 2s. per £ of ratable value.

The general rate imposed in municipalities must not exceed 1s. 6d. in the £ of annual value, and a special rate may be levied under the Health Act. In the Road Board districts the general rate is limited to 1s. 6d. in the £ of annual value. Rates, which must not exceed 6d. in the £ of annual value, are also struck for repayment of loans.

The total area of municipalities is only about 108 square miles. The remainder of the state comprises 975,812 square miles, a large proportion of which is still under the central government. The Road Board districts occupy a considerable area, but as the general government exercises a certain amount of control over the expenditure, these districts cannot be said to be endowed with full local government.

The capital value for the year 1902 was estimated at £8,906,000, and the annual value at £1,068,700. The particulars for 1891 are not available, but it may be said generally that since 1895, the earliest year for which figures are obtainable, there has been a considerable increase both in the annual and capital values. The following table shows the annual values of some of the most important towns for 1896 and 1902. These values, as shown by the official figures in some of the earlier years, range from 10 to 13 per cent. of the capital values, but as this return from property in old settled districts like Perth and Albany seems improbable, and

as the assessments are on the annual value, the capital values cannot be said to have been properly ascertained, and, therefore, are not given :—

Municipality.	Annual Value.	
	1896.	1902.
	£	£
Perth .....	105,409	297,132
Perth, North .....	• 24,320	20,332
Albany .....	74,140	24,732
Fremantle .....	11,810	129,396
„ North .....	• 38,732	19,206
„ East .....	22,355	22,067
Coolgardie .....	• 46,157	46,157
Kalgoorlie .....	108,497	108,497
Boulder .....	• 71,183	71,183

• Not incorporated.

The total receipts for 1902 amounted to £289,922, included in which is the sum of £81,436 given by the Central Government as subsidy and special allowances. The general and special rates received were £94,894, while the remainder, £113,592, comprises £37,123 collections from rents, £8,755 from license fees, &c., £51,433 proceeds of loans, and £16,281 from all other sources. The disbursements in the same year came to £283,272, of which the large proportion of £188,645, or 66·6 per cent. was spent on works and improvements. The other important items are:—Salaries and office expenses, £18,111, or 6·39 per cent.; repayments of loans, £3,218; grants to local fire brigades and Health Boards, £7,909; and interest on loans and overdrafts, £18,573; leaving £46,817 expended on other services, including £12,149 for payments to sinking funds.

The amount shown for rates represents a tax of 1s. 9½d. per £ of annual value, and 4½d. per £ of estimated unimproved capital value.

The total liabilities at the close of the year were approximately £442,750, the principal item being outstanding loans, which amounted to £413,050. The unsecured overdrafts (including unpaid cheques) amounted to £4,827, the balance, £24,873, being due for amounts owing on contracts, outstanding accounts, &c. Against the loan indebtedness, however, must be placed the accumulated sinking fund, which amounts to £62,239.

The assets on the same date were estimated at £427,017. The largest proportion of this amount is accounted for by the value of landed property, plant, and furniture, which was stated to be £294,800. The outstanding rates amounted to £13,346; while other important items were:—Bank and cash balances, and fixed deposits, £49,556, and sinking fund, £62,239, leaving £7,076 for other assets.

The information given above is incomplete, as some of the municipalities failed to furnish the necessary financial returns required by the Government.

## TASMANIA.

In this state, the city of Hobart was incorporated by a special Act in 1852, and in 1858 the Rural Municipalities Act was passed which provided for the establishment of corporations throughout the state, and although various amendments have been made from time to time, the vital principles have not been affected to any extent. The whole area of the state is not under the provisions of these Acts as, there are other bodies, notably Town Boards and Road Trusts, which are authorised to control outlying districts.

In the urban municipalities—Hobart and Launceston—the aldermen are elected by the ratepayers, and the mayors by the aldermen. The ratepayers in the rural districts also elect their representatives, who are termed councillors, and the latter have the privilege of choosing their presiding officer, who is called warden.

The general rate in each class of corporation is limited to 1s. 6d. in the £ of the annual value, while special rates may be levied in rural districts, provided that the general and special rates together do not exceed 1s. 6d. in the £. Road rates may also be imposed under the Roads Act in addition to municipal rates.

The area of municipal districts may be set down as 10,771 square miles, leaving 15,444 square miles under the control of the other local bodies, or of the central government. The total capital value at the close of 1902 was estimated at £26,843,900, and the annual value at £1,457,800. These figures may be somewhat over-stated, as the same property may be rated by more than one of the local authorities. The values of the two principal municipalities will be found below, and a reference to the corresponding particulars for 1893 will show that although the figures for 1903 are lower than in the former year, Tasmania was not so much affected by the depreciation of property, as the mainland States of the Commonwealth:—

Municipality.	1893.		1902.	
	Annual Value.	Capital Value.	Annual Value.	Capital Value.
	£	£	£	£
Hobart.....	185,396	3,707,920	175,194	3,503,880
Launceston.....	143,775	2,875,500	130,207	2,604,140

The total receipts of Municipalities, Town Boards, and Road Trusts for 1902 were £170,275, the proportion contributed by the central government being only £17,306. The bulk of the collections consisted of rates (which are levied on the annual value), the amount of which was £89,685; and the remainder, £63,284, was accounted for by fees, licenses, proceeds of loans, &c. The total expenditure for the same year amounted

to £160,864, but no details relating to this sum are available. The collections for rates are equal to 1s. 2½d. in the £ of annual value, and 1½d. per £ of the estimated unimproved value.

The total loans outstanding at the close of 1902 for the local bodies under review amounted to £597,323, of which a sum of £87,937 is due to the Government, but in the majority of cases sinking funds have been established for the extinction of the debts, the total amount accumulated at the end of 1902 being £62,225.

#### NEW ZEALAND.

In New Zealand an Act was passed in 1852 which divided the colony into six provinces, the local administration being vested in provincial councils. This system continued till 1876, when the provincial system was abolished, and the whole colony, except the area within the forty-one boroughs then existing, was subdivided into counties, each county having full control of its local affairs. The Acts controlling the boroughs and counties were consolidated in 1900 and 1886 respectively, and these are the statutes under which the local bodies are now operating, the total number of boroughs being increased to 101.

The provisions for election differ in the boroughs and counties. In the former bodies both the councillors and mayors are elected by "burgesses," but in counties, the councillors are elected by the "county electors," and the chairmen by the councillors. The rating powers are also different. In boroughs, the rates are in most cases levied on the annual value, and the general rate is limited to 2s. per £ of the annual value, or six farthings of the unimproved capital value if the latter system is adopted. Separate rates for works may also be levied which are limited to 1s. in the £ of annual value or three farthings per £ of unimproved capital value, while provision is also made for water rates, lighting rates, sanitation rates, and library rates, if necessary. In counties, and in a few of the boroughs (the latter having taken advantage of the "Rating on Unimproved Value Act of 1896"), the rates are charged on the capital value, and the general rate must not exceed three farthings in the £ in counties or boroughs where road boards or town districts exist, and six farthings in other local areas. Separate rates may also be levied, provided the general and special rates do not exceed three farthings and six farthings in the £ respectively. Extra rates may be charged for special works, for interest and sinking funds on loans, and, where necessary, for water supply and drainage.

In addition to the boroughs and counties, road districts and town districts have been proclaimed, and the area locally governed may be set down at 104,471 square miles, or the total area of the colony, exclusive of Cook Island and other Pacific dependencies.

The capital value for 1903 was estimated at £168,849,000, and the annual value at £7,868,000. The remarks with regard to the overstatement of the values in Tasmania may also be applied to New Zealand, as the boundaries of the various districts in some cases may overlap.

The distribution of the population of New Zealand differs from that of the Commonwealth. In the Australian States, especially those in the eastern portion of the continent, the great majority of the people are centred in the metropolitan areas, and consequently the capital and annual values are proportionately great in the chief cities. In New Zealand, however, there are four large centres of population, and the values of the assessed properties are shown below. The figures for 1894 are also given, and it will be noticed that the values have largely improved, as New Zealand, like Tasmania, did not experience the great depreciation which took place in some of the other states after the Bank reconstructions in 1893 :—

Borough	1894.		1903.	
	Annual Value.	Capital Value.	Annual Value.	Capital Value.
	£	£	£	£
Wellington .....	339,443	6,465,581	574,124	10,935,068
Auckland .....	299,514	5,884,361	358,864	7,049,904
Dunedin .....	245,205	4,973,732	268,965	5,452,589
Christchurch .....	194,434	3,567,596	247,049	4,534,565

The total receipts for 1903 amounted to £2,076,762, the Government contributions being £483,068, inclusive of loans. The collections from rates (which are levied chiefly on capital values) were £759,498, and from other sources £834,196, represented chiefly by fees for licences and rents. The expenditure for the same period was £2,111,910, the amount spent on works being £1,280,194; on hospitals and charitable aid, £85,745; on management, £143,228 or 6·78 per cent. of the total; and on other services, £602,743. The payments for interest, contributions to sinking funds, and repayments of loans, are not shown separately in the total expenditure, and the amounts disbursed under these heads are, therefore, not available. The rates collected represent 2s. 2½d. per £ of annual value, and 1½d. per £ of estimated unimproved value.

The total loans outstanding at the close of 1902-3 for the bodies referred to amounted to £4,946,467, and the sinking fund was £406,035, the net indebtedness, therefore, being £4,540,432. The annual charge for interest and sinking fund is approximately £269,557, the rates of interest ranging from 3½ to 7 per cent.

#### COMPARISON OF CITIES.

Estimated by the annual value of its ratable property, Sydney is, and has been for many years, the second city of the British Empire; next comes Glasgow, and then Melbourne, as Manchester, exclusive of Salford, is valued at £3,532,300. None of the other Australasian cities ranks high on the list, but the extreme value of property in relation to



population in the Australasian population centres as compared with the principal British cities, will be seen from the following table :—

Cities and Towns.	Population.	Annual Value.	
		Total.	Per Inhabitant.
<b>Australasia—</b>		£	£ s. d.
Sydney .....	514,750	5,669,670	11 0 4
Newcastle and suburbs .....	58,620	407,170	6 18 11
Melbourne .....	483,684	4,498,181	9 5 8
Ballarat and Ballarat East .....	45,788	249,389	5 9 0
Brisbane .....	124,463	1,167,135	9 7 7
Adelaide .....	168,066	1,201,996	7 3 0
Perth .....	42,474	378,266	8 18 1
Hobart .....	34,809	175,194	5 0 8
Wellington .....	53,573	646,649	12 1 5
<b>United Kingdom—</b>			
London (County) .....	4,613,812	40,590,786	8 15 11
Glasgow .....	782,110	5,395,000	6 18 0
Manchester (including Salford) .....	770,352	4,528,584	5 17 7
Liverpool .....	716,810	4,305,767	6 0 2
Edinburgh .....	316,479	2,924,173	9 4 10
Birmingham .....	522,204	2,789,314	5 6 10
Leeds .....	443,559	1,857,065	4 3 9
Bristol .....	338,895	1,615,923	4 15 4
Sheffield .....	418,765	1,610,931	3 16 11
Bradford .....	279,767	1,484,631	5 6 2
Newcastle-on-Tyne .....	215,328	1,390,799	6 9 2
Belfast .....	849,180	1,204,490	3 9 0
Nottingham .....	239,753	1,154,078	4 16 3
Cardiff .....	172,598	1,075,000	6 4 7
Hull .....	240,739	1,044,028	4 6 9
Dublin .....	291,190	871,119	2 19 10

The populations of the Australasian cities and towns given in the table are the estimates at the dates of the annual valuations of the incorporated districts and not the present populations.

#### BOARDS AND TRUSTS IN NEW SOUTH WALES.

In addition to the municipalities, there are bodies known as Boards or Trusts whose function it is to construct and supervise certain works which have been established for the benefit of districts generally comprising one or more of the ordinary municipalities. These bodies are usually composed of members representing respectively the central Government, the municipalities affected, and other persons directly interested in the particular undertakings; and as a rule they raise the funds necessary for carrying out the works they control, by means of rates on the assessed value of the properties benefited, as is the case with municipalities.

In New South Wales there are the Metropolitan Board of Water Supply and Sewerage, having charge of the water supply, which it

assumed in 1888, and of the sewerage system, which it has controlled since 1889, and the Hunter River District Board of Water Supply and Sewerage, formed in 1892. The Wollongong Harbour Trust, which was instituted in 1889, was the only one of the kind in the state up to the year 1900—the works connected with shipping, and the improvements to navigation, at Sydney, Newcastle, and other ports, having always been carried out at the expense and under the supervision of the central Government. The Wollongong Trust, however, failed, and its powers have been assumed by the Government. During the year 1900, an Act was passed for the establishment of a Harbour Trust for the port of Sydney, and in the same year the Wharfs Resumption Act became law, which enabled the Government to acquire certain wharf properties in Darling Harbour; these wharfs, and others, originally the property of the Government, are now controlled by the Harbour Trust. The total receipts for the financial year ended 30th June, 1903, amounted to £257,961, and the expenditure, exclusive of interest on capital, to £86,185, leaving £171,776 to meet charges for interest and sinking fund. The capital debt of the Trust has not yet been determined, but the total loan expenditure on resumptions and harbour improvements, &c., to the 30th June, 1903, amounted to £3,206,107. There is also a Metropolitan Fire Brigades Board, on which the municipalities within the metropolitan area are represented, and towards the annual expenses of which they contribute one-third. The fire insurance companies and the state Government are also represented, and contribute equally with the municipalities in maintaining the Fire Brigades Board. Thirty-eight country boards have also been established under the Fire Brigades Act of 1884, four of which are, however, within the area administered by the Metropolitan Board, and contribute to its funds.

The Country Towns Water Supply and Sewerage Act of New South Wales was passed in 1880. Under the provisions of this measure municipalities outside the area under the control of the Metropolitan and Hunter District Water Supply and Sewerage Boards were entitled to construct, or to have constructed for them by the Government, works for water supply and sewerage, provided the construction of the same were approved by the Governor-in-Council and the municipalities agreed to pay back the original cost of the works with interest at the rate of 4 per cent. per annum. The Government were to pay the certified cost of the works, and the municipalities were to repay the Government by instalments extending over a period of sixty years. Under the operations of this Act twenty-seven water-supply works have been carried out by the Government (exclusive of Richmond, now administered by the Metropolitan Board of Water Supply and Sewerage), and three by municipal councils, while works in fifty other places were in course of construction on the 30th June, 1903, including additions to twenty-three existing works. The amount advanced by the Government to local bodies under the Act to the end of 1892 was £370,549, and instalments to the amount of £25,866

were then overdue. It was found that the liability of some of the municipal councils was too heavy for their resources, and in 1894 an amending Act was passed distributing the payments over 100 years and reducing the interest to 3½ per cent. On the 30th June, 1903, the total amount expended by Government, inclusive of interest, stood at £745,789, viz.: £572,333 for works completed under Government control; £27,344 for works carried out under the supervision of municipal councils; and £146,112 for works still in course of construction. Of the total amount of £599,677 due on account of completed works to the 31st December, 1902, £19,266 had been repaid, and £81,162 had been remitted by Government, leaving the debt at £499,249, which is repayable by annual instalments of £18,055. The net debt on the 30th June, 1903, was not altered, and of the total amount owing (£499,249) a sum of £100,676 had been repaid to the same date, leaving a balance of £398,573 still due to the Government.

#### BOARDS AND TRUSTS IN VICTORIA.

In Victoria the port of Melbourne is under the control of a Harbour Trust, which was established as far back as 1877. A Tramway Trust, representing twelve of the metropolitan municipalities, viz.:—Melbourne, Prahran, Richmond, Fitzroy, Collingwood, South Melbourne, Hawthorn, Kew, St. Kilda, North Melbourne, Brunswick, and Port Melbourne, was formed under the provisions of an Act passed in 1883. This body was entrusted with power to construct tramways through the streets of the municipalities interested, the requisite funds being raised by loans on the security of the tramways and the revenues of the municipal bodies connected with the undertaking. The trustees had the option either of working the tramways themselves or of leasing them to a private company. They adopted the latter alternative, and the tramways are being worked on a thirty-two years' lease, commencing from 1884. In 1891 the Melbourne and Metropolitan Board of Works was established for the purpose of constructing and supervising all works connected with water supply, sewerage, and drainage in Melbourne and suburbs. The Government is not directly represented on this Board, which differs from the Metropolitan Board of Water Supply in Sydney, of which three members are nominated by the state. The reason for this difference is that in New South Wales the Government constructs the works and is responsible for the debt incurred in doing so, while in Victoria the Board carries out the work of construction in addition to the maintenance and management to which the operations of the Sydney Board are confined. Throughout Victoria there are Water Works Trusts and Irrigation and Water Supply Trusts. During 1902–3 there were seventy-three Water Works Trusts and thirty-two Irrigation and Water Supply Trusts. The Government authorised an advance of £1,240,934 for the former service, and for the latter £1,452,400, and the amounts outstanding in June, 1903, were £764,774 and £421,887 respectively, the large sum of £724,778 having been

written off the debt of the Irrigation Trusts. As in New South Wales, the municipal bodies are represented on the Fire Brigade Boards, and bear a proportionate share of the expenses.

The Government of Victoria, prior to the establishment of the Trusts for Water Works, Irrigation, and Water Supply, advanced money from the Public Loans Account to local bodies requiring assistance to construct these works. The amount advanced for the development of the services to June, 1903, including arrears of interest capitalised, was £424,643, which has to be repaid into a sinking fund, or by annual instalments. The amount outstanding on the date mentioned was only £155,136, owing to large sums having been written off during the last two years. The figures just given are exclusive of the advances to the city of Ballarat for the water-supply works, as these are now under a special commission. The outstanding debt of the Ballarat Water Commission on the 30th June, 1903, was £323,197. Under a special Act the Government have power to advance funds to shires for the construction of tramways, and £60,811 had been so advanced up to June, 1903. The Government, under two different Acts, can also make advances to shires for the purchase of rabbit-proof fencing. The amount so advanced to June, 1903, was £192,370, of which £14,517 was outstanding on that date.

#### BOARDS AND TRUSTS IN OTHER STATES.

In Queensland the water supply service forms part of the local government system; the works are proposed by the municipal bodies, but the Government constructs and supervises them, and when completed hands them over to the local authorities with their attendant liabilities. The latter form a debt to the state which is repaid in instalments. The total cost of construction to 31st December, 1903, was £1,264,877, and the amount due to the Government on the same date was £810,600. There are also Bridge Boards in connection with the Victoria Bridge (Brisbane) and the Lamington Bridge (Maryborough), and four Harbour Boards, viz., at Bundaberg, Rockhampton, Townsville, and Mackay. Tramways have also been constructed by nine Councils; the total amount due to the Government at the end of 1903 being £340,324.

In South Australia there are no Boards or Trusts of any importance beyond the municipal bodies already mentioned; extensive municipal powers exist, however, for raising loans for the construction of local works, and each corporation and District Council is constituted a Board of Health.

In Western Australia there are Road Boards, Local Boards of Health, and a Metropolitan Water Works Board.

In Tasmania seven Marine Boards, forming part of the local government system, have been established in different parts of the state, and there are fifteen Water Trusts in connection with municipal bodies.

In New Zealand there are, in addition to the ordinary forms of municipal government, River and Harbour Boards, which are established throughout the colony. The number of these at the end of 1903 was respectively thirty-two and twenty-eight. There are City and Suburban Drainage Boards at Christchurch and Dunedin, and sixteen other Land Drainage Boards in country towns, and Water Supply Boards at Waimakariri—Ashley and Manukau.

Complete information relating to the Boards and Trusts in each state is not readily obtainable; the following table, however, which has been compiled from the latest available returns, gives important details in connection with some of these bodies:—

Board or Trust.	Receipts.			Expenditure including Interest.	Out-standing Loans.
	Government.	Other.	Total.		
<b>New South Wales—</b>	£	£	£	£	£
Metropolitan Board of Water Supply and Sewerage .....	...	368,495	368,495	397,714	7,891,072
* Hunter District Water Supply and Sewerage .....	...	31,102	31,102	32,217	500,784
Sydney Harbour Trust .....	...	257,961	257,961	186,185	...
<b>Victoria—</b>					
Melbourne Harbour Trust .....	...	177,233	177,233	150,174	2,000,000
Melbourne and Metropolitan Board of Works .....	...	362,450	362,450	398,879	8,172,337
Melbourne Tramways Trust .....	...	473,726	473,726	371,028	1,650,000
Fire Brigade Boards .....	16,334	38,021	54,355	53,171	130,000
Water Works Trusts .....	...	...	...	...	764,774
Irrigation and Water Supply Trusts .....	...	...	...	...	421,887
Ballarat Water Commission .....	...	...	...	...	323,197
<b>Queensland—</b>					
Water Works, Brisbane .....	...	63,765	63,765	64,739	440,620
" " Country Towns .....	12,161	67,744	79,905	70,093	369,980
<b>Western Australia—</b>					
Road Boards .....	67,750	17,108	84,858	83,136	...
Boards of Health in Municipalities..	1,663	29,035	30,698	30,776	...
" " outside Municipalities .....	1,894	7,639	9,533	8,597	...
Metropolitan Water Works Board.	14,600	29,987	44,587	44,552	387,452
<b>Tasmania—</b>					
Marine Boards (including, Light-houses) .....	44,534	44,095	88,629	87,059	188,639
Water Trusts .....	6,300	7,204	13,504	14,012	38,200
Road Trusts .....	7,150	22,794	29,944	27,579	1,200
Town Boards .....	6,645	18,862	25,507	25,015	49,300
<b>New Zealand—</b>					
River Boards .....	6,965	16,442	23,407	29,556	38,470
Harbour Boards .....	1,293	718,654	719,947	675,002	4,256,481
Drainage Boards .....	1,621	41,744	43,365	48,151	220,580
Water Supply Boards .....	...	2,904	2,904	2,887	21,200

\* Water supply only.

† Exclusive of Interest on Capital Debt.

The Melbourne Tramways Trust shows an expenditure on working and interest of £371,028; to this should be added £42,314 placed to reserve, £48,000 paid in dividends, and £12,384 carried forward in excess of the amount brought over from the previous year. A sinking fund has been established for the purpose of liquidating outstanding loans, but information relating thereto is not available.

The amounts shown in the foregoing table under Road Trusts and Town Boards in Tasmania are included in the figures given on page 770. The outstanding loans for Tasmania are gross, sinking funds amounting to £27,035, £1,426, £523, and £3,751 respectively being established in connection with the debts of Marine Boards, Water Trusts, Road Trusts, and Town Boards. In New Zealand, also, sinking funds amounting to £6,861, £422,753, £41,459, and £1,412, exist in connection with the liabilities of River, Harbour, Drainage, and Water Supply Boards respectively.

The outstanding loans of the Boards and Trusts of New South Wales constitute part of the public debt. This is true also with regard to the amounts for Victoria, except the loans of the Tramway Trust and the Melbourne Harbour Trust, the Fire Brigades Boards, and part of the loans of the Melbourne and Metropolitan Board of Works, which are not guaranteed. The liabilities shown for Queensland and Western Australia, and a small portion of the Tasmanian indebtedness, also form part of the public debt of those states; but the amounts given for New Zealand are not included in the debt of the Central Government. In the foregoing table the advances made by the Governments to the borrowing bodies are included.

#### TOTAL REVENUE OF LOCAL BODIES.

The total revenue of all local bodies was as follows, the receipts from the various Governments being distinguished from the ordinary receipts:—

State.	Receipts from Government.	Other Receipts.	Total.
	£	£	£
New South Wales .....	50,721	1,636,544	1,687,265
Victoria .....	115,628	2,312,783	2,428,411
Queensland .....	72,174	548,752	620,926
South Australia .....	92,568	251,823	344,397
Western Australia .....	167,343	292,255	459,598
Tasmania .....	68,140	204,268	272,408
Commonwealth .....	566,574	5,246,431	5,813,005
New Zealand .....	492,947	2,373,435	2,866,385
Australasia .....	1,059,521	7,619,869	8,679,390

## INDEBTEDNESS OF LOCAL BODIES.

The following table shows the total indebtedness of local bodies in each of the states including the liabilities to the Government. It must also be explained that the liabilities of Road Trusts and Town Boards in Tasmania, and Town Boards and Road Boards in New Zealand, have been included with municipalities :—

State.	Outstanding Loans.		
	Municipalities.	Boards, Trusts, &c.	Total for local purposes.
	£	£	£
New South Wales .....	2,931,511	8,391,856	11,323,367
Victoria .....	4,212,051	13,462,195	17,674,246
Queensland .....	939,054	810,600	1,749,654
South Australia .....	119,202	.....	119,202
Western Australia .....	413,050	387,452	800,502
Tasmania .....	597,323	226,839	824,162
Commonwealth .....	9,212,191	23,278,942	32,491,133
New Zealand .....	4,946,467	4,536,731	9,483,198
Australasia ... ..	14,158,658	27,815,673	41,974,331

For the amounts that have just been given the local bodies are responsible directly to their creditors in part, and the general governments hold themselves directly liable for the balance. In the following table is given a division of the indebtedness of local bodies into the sum due to the state and that due to the public. It may be mentioned that the amount owing to the state is included with the general debt of the state; and in order to estimate the total state and municipal indebtedness the figures in the second column only have to be added to the figures given in the chapter dealing with State Finance.

State.	Amount of Corporation Indebtedness included in the Public Debt.	Loans of Local Bodies floated in open market.	Total Indebtedness.
	£	£	£
New South Wales .....	8,391,856	2,931,511	11,323,367
Victoria .....	3,868,169	13,806,077	17,674,246
Queensland .....	1,301,654	448,000	1,749,654
South Australia .....	.....	119,202	119,202
Western Australia .....	387,452	413,050	800,502
Tasmania .....	287,076	537,086	824,162
Commonwealth .....	14,236,207	18,254,926	32,491,133
New Zealand .....	1,266,002	8,217,196	9,483,198
Australasia .....	15,502,209	26,472,122	41,974,331

## STATE AND MUNICIPAL RATES AND LAND VALUES.

The extent of the charges on land levied by the various corporations and other local bodies as rates will have been gathered from the foregoing pages ; in addition thereto a land tax is levied by the General Government in all the states except Queensland and Western Australia, and the income tax imposed by Victoria, Queensland, South Australia, and Tasmania, includes income derived from land and its use ; in New South Wales and New Zealand, however, incomes derived from the use and occupancy of land are untaxed. The following table shows the collections for rates and the other taxes mentioned, and also the capital values of property and of land and improvements, with the amount per £ on the value of unimproved land and land and improvements which the rates would equal. The figures for Tasmania are exclusive of the income tax on property, particulars of which are not available, as the tax was levied after the close of 1903 :—

State.	Amount of Rates and Land and Property taxes collected.	Capital Value.		Amount per £ of—	
		Unimproved Land.	Land and Improvements	Unimproved Land.	Land and Improvements.
	£	£	£	d.	d.
New South Wales .....	1,293,992	136,417,000	264,492,000	2·28	1·17
Victoria .....	1,363,883	126,078,000	234,057,000	2·60	1·40
Queensland .....	485,561	41,400,000	72,040,000	2·81	1·62
South Australia .....	389,601	35,957,000	59,176,000	2·60	1·58
Western Australia .....	146,472	11,995,000	19,272,000	2·93	1·82
Tasmania .....	154,070	21,832,000	34,907,000	1·69	1·06
Commonwealth .....	3,833,579	373,679,000	683,944,000	2·46	1·35
New Zealand .....	1,142,778	87,576,000	152,826,000	3·13	1·79
Australasia .....	4,976,357	461,255,000	836,770,000	2·59	1·43

The amount of rates collected in Western Australia is only approximate, as the returns are incomplete.



## ACCUMULATION.

### BANKING.

THE laws relating to banks and banking at present in force are susceptible of great improvement, and in 1893 the failure of many monetary institutions which posed as banks directed attention to the urgent necessity for entirely revising the conditions under which deposits might be taken from the general public, but so far no new legislation has been enacted. All institutions transacting the business of banking are required by law to furnish, in a specified form, quarterly statements of their assets and liabilities, and from these statements and the periodic balance-sheets the tables in this chapter have been compiled. The returns furnished by the banks, though in compliance with the laws of the states, are by no means satisfactory, being quite unsuited to the modern methods of transacting banking business, and they cannot be accepted without question as indicating the stability or instability of the institutions by which they are issued. As a rule, nothing can be elicited beyond what is shown in the half-yearly or yearly balance-sheets. No uniformity is observed as regards the dates of closing the accounts, and the modes of presentation are equally diverse. Important items which should be specifically stated are included with others of minor import, and, in some cases, current accounts are blended with other accounts instead of being separately shown. The value of the information vouchsafed to the public is illustrated by the fact that it was impossible to obtain from the publications of several institutions suspending payment in 1893 the amount of their liabilities either to the public or the state, and these particulars were never disclosed.

### CAPITAL RESOURCES OF BANKS.

According to the latest information published, the paid-up capital of the twenty-two banks operating in Australasia is £18,490,015, of which £5,818,629, inclusive of £2,500,000 guaranteed to the Bank of New Zealand by the Government of that colony, has a preferential claim on the profits of the companies. Below will be found a statement of the ordinary and preferential capital of each bank at the date shown, with the amount of the reserve fund of the institution. In the case of several companies which were reconstructed, there are reserves which

are held in suspense pending realisation of assets, and of these no account has been taken in the table :—

Bank.	Date of Balance-sheet.	Capital paid up.			Reserve Fund.
		Ordinary.	Preferential.	Total.	
		£	£	£	£
Australian Joint Stock Bank (Ld.) .....	30 June, 1904	154,529	....	154,529	....
Bank of Adelaide .....	28 Mar., 1904	400,000	....	400,000	225,000
Bank of Australasia .....	11 April, 1904	1,600,000	....	1,600,000	1,160,000
Bank of New South Wales .....	30 Sept., 1904	2,000,000	....	2,000,000	1,370,000
Bank of New Zealand .....	31 Mar., 1904	431,713	2,500,000	2,931,713	73,987
Bank of North Queensland (Ld.) .....	30 June, 1904	100,000	....	100,000	18,000
Bank of Victoria (Ld.) .....	30 June, 1904	1,061,250	416,760	1,478,010	150,000
City Bank of Sydney .....	30 June, 1904	400,000	....	400,000	3,500
Colonial Bank of Australasia (Ld.) .....	30 Sept., 1904	134,663	304,044	438,707	65,000
Commercial Bank of Australia (Ld.) .....	30 June, 1904	95,274	2,117,230	2,212,504	198,521
Commercial Banking Co. of Sydney (Ld.) ..	30 June, 1904	1,000,000	....	1,000,000	1,065,000
Commercial Bank of Tasmania (Ld.) .....	31 Aug., 1904	141,493	....	141,493	125,000
English, Scottish, and Australian Bank (Ld.)	30 June, 1904	539,438	....	539,438	184,174
London Bank of Australia (Ld.) .....	31 Dec., 1903	375,713	171,980	547,693	*192,367
National Bank of Australasia (Ld.) .....	30 Sept., 1904	1,192,440	305,780	1,498,220	105,000
National Bank of New Zealand (Ld.) .....	31 Mar., 1904	250,000	....	250,000	210,000
National Bank of Tasmania (Ld.) .....	31 May, 1904	152,040	....	152,040	27,500
Queensland National Bank (Ld.) .....	30 June, 1904	413,192	....	413,192	45,000
Royal Bank of Australia (Ld.) .....	30 Sept., 1904	150,000	....	150,000	35,000
Royal Bank of Queensland (Ld.) .....	30 June, 1904	454,641	2,825	457,466	63,000
Union Bank of Australia (Ld.) .....	29 Feb., 1904	1,500,000	....	1,500,000	1,025,000
Western Australian Bank .....	26 Sept., 1904	125,000	....	125,000	300,000

\* Includes Capital Reserve Account.

During the half-year ended 30th June, 1904, a reduction in the capital of the Australian Joint Stock Bank, Limited, took place, resulting in the writing off of £6 10s. per share in respect of 154,348 shares, portion of the shares which have been issued and are now outstanding; £5 per share on 936 shares, the remainder of the shares which have been issued and are now outstanding; and £5 5s. per share on 506 shares which were issued, but have been forfeited, and are not now outstanding; while the nominal value of all unissued shares in the company's capital was reduced from £10 per share to £3 10s. per share.

The preceding table shows the position of the capital account at date of balancing; but a number of the banks had made calls on their

shareholders which will increase their paid-up capital. The amount of these calls and the total working capital that will be available when they are met are appended :—

Bank.	Capital paid and being called up.		
	Paid up.	Being called.	Total Working Capital.
	£	£	£
Australian Joint Stock Bank (Limited) .....	154,529	3,298	157,827
Bank of Adelaide .....	400,000	.....	400,000
Bank of Australasia .....	1,000,000	.....	1,000,000
Bank of New South Wales ..	2,000,000	.....	2,000,000
Bank of New Zealand .....	2,931,713	3,367	2,935,080
Bank of North Queensland (Limited) .....	100,000	.....	100,000
Bank of Victoria (Limited) .....	1,478,010	.....	1,478,010
City Bank of Sydney .....	400,000	.....	400,000
Colonial Bank of Australasia (Limited) .....	488,707	573	489,280
Commercial Bank of Australia (Limited) .....	2,212,564	.....	2,212,564
Commercial Banking Company of Sydney (Limited) ..	1,000,000	.....	1,000,000
Commercial Bank of Tasmania (Limited) .....	141,493	.....	141,493
English, Scottish, and Australian Bank (Limited) ....	539,438	.....	539,438
London Bank of Australia (Limited) .....	*547,643	750	548,393
National Bank of Australasia (Limited) .....	1,498,220	.....	1,498,220
National Bank of New Zealand (Limited) .....	250,000	.....	250,000
National Bank of Tasmania (Limited) .....	152,040	.....	152,040
Queensland National Bank (Limited) .....	413,192	2,056	415,248
Royal Bank of Australia (Limited) .....	150,000	.....	150,000
Royal Bank of Queensland (Limited) .....	457,466	.....	457,466
Union Bank of Australia (Limited) .....	1,500,000	.....	1,500,000
Western Australian Bank .....	125,000	.....	125,000

\* Includes £3,190 prepaid on account of Reserve Liability.

The paid-up capital of the banking companies now operating in Australasia has increased from £14,724,587 to £18,490,015, or by £3,765,428 since 1893, the year of the great banking crisis. In 1893, however, there were in existence two banks, with a combined capital of £900,000, which are now defunct; and it should also be mentioned that capital to the amount of £9,324,803 has been written off during the last eleven years, including £1,000,000 guaranteed stock repaid to the New Zealand Government in July, 1904, and £1,010,598 of the capital of the Australian Joint Stock Bank, Limited.

#### LIABILITIES AND ASSETS OF BANKS.

The liabilities of the banks enumerated, at the dates which have been previously given, totalled £141,537,509, against which amount assets aggregating £167,415,341 were shown. The following table

gives the liabilities of each institution to the public, notes in circulation and deposits being distinguished from other liabilities. In some cases small items which should be classed with "other liabilities" are included with deposits, as they cannot be distinguished in the balance-sheets; and in the case of the Commercial Bank of Australia (Limited), the accounts of the assets trust have been excluded:—

Bank.	Notes in Circulation.	Deposits.	Other Liabilities to Public.	Total Liabilities to Public.
	£	£	£	£
Australian Joint Stock Bank (Limited) .....	59,085	5,392,717	183,000	5,634,802
Bank of Adelaide .....	136,710	2,218,374	205,882	2,560,966
Bank of Australasia .....	520,008	15,106,272	2,320,275	17,956,555
Bank of New South Wales .....	937,790	21,093,160	2,330,711	25,361,661
Bank of New Zealand .....	858,135	10,356,929	1,443,879	12,657,943
Bank of North Queensland (Limited) .....	.....	303,525	25,333	328,858
Bank of Victoria (Limited) .....	104,914	4,427,561	833,180	5,365,655
City Bank of Sydney .....	67,459	1,082,103	1,120	1,150,701
Colonial Bank of Australasia (Limited) .....	107,072	2,380,740	243,674	2,731,486
Commercial Bank of Australia (Limited) .....	157,548	3,190,968	486,498	3,834,714
Commercial Banking Company of Sydney (Ltd.) .....	390,227	11,291,140	544,536	12,225,903
Commercial Bank of Tasmania (Limited) .....	59,759	1,433,098	19,326	1,512,083
English, Scottish, and Australian Bank (Ltd.) .....	31,918	5,139,082	246,796	5,517,796
London Bank of Australia (Limited) .....	150,088	3,940,638	577,518	4,668,244
National Bank of Australasia (Limited) .....	240,497	5,934,040	462,814	6,637,351
National Bank of New Zealand (Limited) .....	273,515	3,043,440	368,505	3,685,465
National Bank of Tasmania (Limited) .....	54,672	459,923	20,765	535,364
Queensland National Bank (Limited) .....	.....	6,529,756	414,061	6,944,417
Royal Bank of Australia (Limited) .....	8,611	740,425	217,968	966,904
Royal Bank of Queensland (Limited) .....	.....	839,038	5,444	844,482
Union Bank of Australia (Limited) .....	464,766	15,990,011	2,130,145	18,584,922
Western Australian Bank .....	101,972	1,064,961	113,746	1,280,679

The assets of each bank are shown below:—

Bank.	Coin and Bullion.	Advances.	Other Assets.	Total Assets.
	£	£	£	£
Australian Joint Stock Bank (Limited) .....	806,751	4,236,804	749,344	5,792,799
Bank of Adelaide .....	439,969	1,551,884	1,238,140	3,229,993
Bank of Australasia .....	3,204,342	14,785,908	2,789,186	20,779,436
Bank of New South Wales .....	4,568,762	18,909,250	5,322,078	28,800,090
Bank of New Zealand .....	1,967,320	6,903,197	6,963,529	15,834,046
Bank of North Queensland (Limited) .....	48,210	312,829	87,188	448,227
Bank of Victoria (Limited) .....	822,763	4,839,620	1,876,010	7,038,393
City Bank of Sydney .....	253,134	1,117,399	192,821	1,563,354
Colonial Bank of Australasia (Limited) .....	411,678	2,196,596	644,140	3,252,414
Commercial Bank of Australia (Limited) .....	916,941	3,644,031	1,731,344	6,292,316
Commercial Banking Company of Sydney (Ltd.) .....	2,726,076	9,134,983	2,490,664	14,351,723
Commercial Bank of Tasmania (Limited) .....	137,693	1,312,967	269,175	1,720,835
English, Scottish, and Australian Bank (Ltd.) .....	908,656	4,123,539	1,203,251	6,235,446
London Bank of Australia (Limited) .....	759,655	3,809,816	1,176,496	5,745,967
National Bank of Australasia (Limited) .....	1,296,373	5,224,625	1,755,454	8,276,452
National Bank of New Zealand (Limited) .....	726,943	3,178,721	265,607	4,171,271
National Bank of Tasmania (Limited) .....	93,019	577,674	53,719	724,412
Queensland National Bank (Limited) .....	641,428	5,546,742	1,317,439	7,405,609
Royal Bank of Australia (Limited) .....	164,637	644,518	362,642	1,161,797
Royal Bank of Queensland (Limited) .....	223,117	968,257	164,686	1,356,060
Union Bank of Australia (Limited) .....	2,682,365	13,171,511	5,167,351	21,021,227
Western Australian Bank .....	836,838	1,266,729	242,238	2,345,805

The difference between the assets and liabilities shown in these tables amounts to £25,877,832, and practically corresponds with the paid up capital and reserves (£24,946,890) shown on a previous page, the difference in the two amounts representing for the most part undivided profits. It will be noted that both the assets and liabilities represent the total of the various banks wherever situated, and not merely the Australasian assets and liabilities which are shown in a succeeding paragraph. The business of the banks outside Australasia appears to be represented by liabilities amounting to £24,852,487, and by assets £32,910,868.

#### METALLIC RESERVES OF BANKS.

The following table shows the metallic reserves held by the banks as against their total Australasian liabilities, and also against their liabilities at call, viz., deposits at call and note circulation. The table, however, cannot be taken as complete, as some banks receiving deposits in England and elsewhere do not include such liabilities in their returns:—

State.	Coin and Bullion.	Total Liabilities.	Liabilities at Call.	Proportion of Coin and Bullion—	
				To Total Liabili- ties.	To Lia- bilities at Call.
	£	£	£	per cent.	per cent.
New South Wales .....	6,966,107	34,768,363	14,310,304	20·64	48·68
Victoria .....	6,226,964	32,267,119	11,765,074	19·29	52·92
Queensland .....	1,818,807	12,693,759	3,931,603	14·33	46·26
South Australia .....	1,452,760	6,826,298	2,823,805	21·28	51·45
Western Australia .....	2,143,049	5,186,192	3,650,946	41·32	58·70
Tasmania .....	751,792	3,751,345	1,619,919	20·04	46·41
Commonwealth .....	19,358,469	95,493,076	38,101,651	20·27	50·81
New Zealand .....	3,867,826	21,191,946	11,101,447	18·25	34·84
Australasia .....	23,226,295	116,685,022	49,203,098	19·91	47·20

It will be seen that Queensland, apparently, holds the weakest position in the proportion of cash reserves to total liabilities, and New Zealand in proportion to liabilities at call. This, however, means very little, seeing that in some of the states many banks profess to hold gold largely in excess of their wishes or requirements.

The explanation of the excess of liabilities over assets in some of the foregoing instances lies in the fact that several of the banks find it more convenient to keep their reserves at headquarters, rather than distributed amongst all their branches, but in some instances it is not possible to use to advantage deposits at the place where they are obtained. The Bank of New Zealand shows an excess of liabilities

amounting to £2,340,146, but an inspection of its balance sheet shows large holdings in London, viz., money at call, bills receivable, debentures, &c. To discuss the position of the bank would be entirely foreign to the purpose of this work, but it may be mentioned that the Government of New Zealand is largely interested in it, and the bank for all practical purposes, may be regarded as a state guaranteed institution.

Taking the Australian Commonwealth as a whole the following is a statement of the excess of assets over liabilities of all the banks of issue for the December quarters of the years named (1890-1903), with like information regarding New Zealand.

Year.	Commonwealth.	New Zealand.	Total.
	£	£	£
1890 .....	48,439,607	4,378,661	52,818,268
1891 .....	50,863,656	2,994,060	53,857,716
1892 .....	50,141,666	2,934,633	53,076,499
1893 .....	49,284,805	2,765,901	52,050,706
1894 .....	45,657,841	2,815,630	48,473,471
1895 .....	38,755,820	3,668,154	42,423,974
1896 .....	37,901,614	1,379,768	39,281,382
1897 .....	33,411,114	1,896,523	35,307,637
1898 .....	29,900,443	1,714,346	31,614,789
1899 .....	22,506,850	1,355,575	23,862,424
1900 .....	22,220,669	349,953	22,570,622
1901 .....	21,893,036	932,239	22,825,275
1902 .....	20,542,489	143,646	20,686,135
1903 .....	22,138,179	218,394	22,356,573

For the Commonwealth and New Zealand, the excess of assets over liabilities amounts to £22,356,573, while according to the balance-sheets of the banks at the date nearest the 31st December, 1903, the working capital and reserves were :—

Capital .....	£18,490,015
Reserves .....	6,810,913
Total .....	£25,300,928

The capital and reserves thus exceeded the assets in the Commonwealth and New Zealand by £2,944,355, the difference being accounted for by the holdings of the various banks in London, the headquarters of several of the largest institutions doing business in Australia. The table just given is important in that it illustrates effectively the process of the withdrawal of capital from Australia and New Zealand, which has been silently going on since 1891. Taking the figures of the table as they stand, without considering additions and cancellations of capital, there has been a decrease in the money employed in Australia by the banks of issue during thirteen years to the extent of £30,461,695. Within the same period, capital to the extent of £7,071,874 has been written off, and £1,300,000, the capital of three defunct banks, has also been lost; on the other hand, capital (including

preferential capital) to the amount of £9,964,961 has been called up. It may therefore be stated that approximately £1,593,087, new capital, has been obtained by the banks; so that the actual withdrawal of money has been greater by this amount than shown above, and, in reality, the total withdrawals may be put down at £32,054,782. The greater part of the money withdrawn consisted of British deposits, which the banks were accustomed to accept very freely in the period before the bank crisis of 1893. The extent of the deposits made with the branches of the banks in Great Britain may be gauged from the fact the twelve banks from which returns were obtained held British interest-bearing deposits to the amount of £26,406,000, while the nine smaller banks from which returns were not obtained are estimated to have had British deposits to the amount of £3,684,000; so that the total of such deposits in use in Australia could not have been far short of £30,000,000. It is impossible, by reason of the scant information given in the quarterly banking statements and the balance-sheets, to speak definitely as to the amount of British deposits now in the hands of Australian banks; but a consideration of the foregoing figures would show that such amount must be very small, while it is also clear that several of the banks are now using a portion of their Australian deposits in their London business.

The detailed statements of the movement in each state afford interesting reading. In New South Wales, the assets of the banks touched their highest point in 1891 and 1892, and in the latter year the capital employed by them in excess of their local liabilities was £16,146,513; this excess included the paid-up capital and reserves of the banks, as well as the British and other deposits used in the state. From the sum just named, the excess of assets fell in 1901 to £8,359,727; the gradual decline of assets and liabilities is shown in the following table:—

Year.	Assets.	Liabilities.	Excess of Assets.
	£	£	£
1890	52,436,977	37,248,937	15,188,040
1891	53,596,259	37,589,764	16,006,495
1892	53,317,892	37,171,379	16,146,513
1893	48,794,036	34,102,172	14,691,864
1894	47,261,405	31,649,255	15,612,150
1895	45,622,329	32,037,052	13,585,277
1896	44,527,828	31,254,776	13,273,052
1897	43,980,722	31,026,623	12,954,199
1898	42,638,224	31,311,293	11,326,931
1899	42,194,661	33,055,059	9,139,602
1900	43,036,427	33,969,731	9,066,696
1901	43,437,559	35,077,832	8,359,727
1902	43,630,491	34,930,428	8,700,063
1903	43,165,576	34,250,541	8,915,035

There was some writing down of capital after the bank crisis, but the difference between the highest and lowest years (1892 and 1901) shown in the foregoing table, viz., £7,786,786, represents for the most part the withdrawal of British and other deposits obtained outside of New South Wales. In the year 1901 the total deposits obtained by the banks in respect of their New South Wales business was probably a little over £40,000,000, so that the British and other external deposits then held but subsequently withdrawn represented not far short of twenty per cent. of the total. With the year 1901 the withdrawals of banking capital ceased and each subsequent year shows a slight recovery. The total capital withdrawn covered a period of nine years, the average withdrawal therefore was at the rate of about £800,000 a year, a sum, taken in connection with the period over which it continued, sufficiently large to cause considerable dislocation of business.

In the case of Victoria, the withdrawal of money from the banks was also spread over a period of nine years, coming to an end in the year 1902, but the average annual withdrawals were on a much larger scale than in New South Wales. Melbourne was undoubtedly the financial centre of the Australian States at the time of the crisis, and it was but natural that the general disturbance of banking business which took place subsequent to 1893 should be felt more acutely there than elsewhere, especially as Melbourne was also the chief seat of speculative enterprise for all Australia. In 1891 the banking assets in Victoria were set down at the huge figure of £63,720,546, and this has now been reduced to £39,291,125, a fall of £24,429,421. In the year 1891 the excess of assets over liabilities, which represents the capital of the banks employed in their business and deposits obtained outside the State of Victoria, amounted to £21,476,329. This was increased in 1893, the year of the bank failures, to £23,004,892, or £1,376,000 in excess of the previous year, an increase due largely to the fact that several of the reconstructed banks were able to treat a portion of their deposits as capital.

From 1893 to 1902 there was a continued decline in the amount of the excess of assets over liabilities, until in the year last named it stood at £7,570,163, that is to say as compared with 1893, a fall of £15,434,729, which gives a yearly average of £1,715,000 for the nine years. The cause of the decline was chiefly the withdrawal of British deposits—which do not appear in the bank returns as a liability—and also a writing down of assets and cancellation of capital called up.

This decline has now ceased, but while it persisted it placed a severe strain on the business of the state; it is however a very happy circumstance that the great producing interests of the country were not affected. Indeed, during the nine years in which the withdrawals took place the agricultural and dairying industries showed signs of great vitality, proving that very little of the money which was obtained outside of Victoria for use by the banks, was employed in these industries. The following is a statement of the assets and liabilities



# ACCUMULATION.

789

and excess of assets over liabilities during each year from 1890 to 1903 :—

Year.	Assets.	Liabilities.	Excess of Assets.
	£	£	£
1890 .....	60,937,955	42,224,084	18,713,871
1891 .....	63,720,546	42,244,217	21,476,329
1892 .....	63,169,942	41,541,161	21,628,781
1893 .....	56,644,511	33,639,619	23,004,892
1894 .....	55,277,824	34,727,373	20,550,451
1895 .....	49,518,627	33,127,299	16,391,328
1896 .....	49,130,925	32,681,831	16,449,094
1897 .....	45,560,432	31,650,631	13,909,801
1898 .....	42,032,701	29,412,293	12,620,408
1899 .....	40,522,115	31,274,374	9,247,741
1900 .....	41,755,923	31,895,571	9,860,357
1901 .....	41,460,634	31,856,497	9,604,137
1902 .....	39,795,793	32,225,630	7,570,163
1903 .....	39,291,125	31,553,334	7,737,791

The banking capital employed in Queensland has always been very large, and, compared with population, larger than in any of the other states. A considerable proportion of the capital employed, however, was not obtained within the state itself, and on the occurrence of the bank crisis there were very large withdrawals. The assets and liabilities from 1890 onwards are as set out in the following table, from which it will be seen that the banking capital and resources obtained by the banks outside the state, represented in the table by excess of assets, amounted in 1891 to £9,821,409, while in 1900 it fell to £2,066,883, a reduction of nearly four-fifths.

Year.	Assets.	Liabilities.	Excess of Assets.
	£	£	£
1890 .....	20,906,932	11,133,750	9,773,182
1891 .....	20,658,180	10,836,771	9,821,409
1892 .....	20,552,087	11,193,201	9,358,886
1893 .....	19,739,959	11,079,630	8,660,329
1894 .....	18,540,514	11,037,294	7,503,220
1895 .....	18,917,403	11,423,946	7,493,457
1896 .....	18,850,945	11,346,303	7,504,642
1897 .....	16,842,439	12,370,467	4,471,972
1898 .....	16,068,673	12,691,398	3,367,275
1899 .....	16,207,695	13,419,674	2,788,021
1900 .....	16,257,443	14,190,560	2,066,883
1901 .....	16,741,379	13,983,898	2,757,481
1902 .....	16,812,451	13,602,176	3,210,275
1903 .....	16,922,239	12,826,338	4,095,895

Since 1900 the outflow through the banks has ceased, and the amount of capital provided out of their own resources or from external deposits has increased to £4,095,895. In New South Wales and Victoria, particularly the latter, the withdrawal of external deposits from the banks was accompanied by a decline in the amount of the internal deposits; with Queensland it was otherwise, for the amount of the latter has shown improvement during almost every year, an improvement not materially interrupted even by the bank crisis of 1893.

The figures showing the assets and liabilities of the South Australian banks are given below for 1890 and subsequent years. In the year 1890 there was an excess of assets to the amount of £3,729,917, which rapidly declined, so that in 1895 the excess was £165,069 only, and in the following year there was an excess of liabilities to the extent of £42,847. The extraordinary character of these figures will not be diminished if they be read in connection with those of still earlier years, such as in 1886, when the excess of assets over liabilities was £6,000,000.

Year.	Assets.	Liabilities.	Excess of Assets.
	£	£	£
1890 .....	11,469,843	7,759,926	3,729,917
1891 .....	10,806,548	8,303,606	2,502,942
1892 .....	9,691,620	7,960,037	1,731,583
1893 .....	8,971,060	7,596,687	1,374,373
1894 .....	8,019,346	7,204,456	814,890
1895 .....	7,436,051	7,270,982	165,069
1896 .....	7,754,673	7,797,520	*42,847
1897 .....	7,473,670	6,919,882	553,788
1898 .....	6,809,603	5,821,303	988,300
1899 .....	6,752,772	6,283,735	469,037
1900 .....	6,549,292	6,215,700	333,592
1901 .....	6,616,505	6,350,734	265,771
1902 .....	6,481,038	6,334,008	147,030
1903 .....	6,547,447	6,046,063	501,384

\* Denotes excess of Liabilities.

South Australia was not so directly affected by the bank failures of 1893 as were the three eastern states, nevertheless, there were large withdrawals during the four years following the crisis, as the preceding table shows. The condition of the banks, as evidenced by their returns, is not an absolute indication of the condition of business within the state, as Adelaide is an important financial centre with a large external business embracing the Northern Territory, the western districts of New South Wales, and south-west Queensland; while, latterly, considerable interests have been acquired in Western Australia. The bank returns, however, make it plain that South Australian business has been shorn of much of its speculative character, and that there is, and has been for the past eight years, little outside capital employed by the banks in the state.

The returns of Western Australia show the vitalising effect of the gold discoveries on the trade of the state. In 1890 the total assets of the banks within the state amounted to £1,801,976, but increased to £5,754,475 in six years, and to £6,417,950 at the close of 1903.

Year.	Assets.	Liabilities.	Excess of Assets.
	£	£	£
1890 .....	1,801,976	1,016,833	785,143
1891 .....	2,113,469	1,291,568	821,921
1892 .....	2,625,989	1,525,783	1,100,206
1893 .....	2,780,787	1,420,606	1,360,181
1894 .....	2,956,082	1,805,936	1,150,146
1895 .....	3,948,449	2,877,056	1,071,393
1896 .....	5,754,475	5,063,273	671,202
1897 .....	5,978,798	4,588,830	1,389,968
1898 .....	5,420,479	4,037,252	1,383,227
1899 .....	4,986,034	4,196,983	789,051
1900 .....	5,742,012	4,836,886	905,126
1901 .....	5,944,769	4,929,042	1,015,727
1902 .....	6,439,561	5,300,576	1,138,985
1903 .....	6,417,950	5,325,819	1,092,131

Tasmania is the only state which shows excess of liabilities over assets, a condition which has prevailed for the last four years. The state is within a day's journey of Melbourne, and the banks, whose headquarters are in that city, find it more convenient to keep their general reserve there than on the island; nevertheless, there must be some lack of opportunity for investment, seeing that the Tasmanian deposits are considerably in excess of local assets. The two local banks show assets £2,520,151, liabilities £2,070,586, deposits included in the liabilities £1,939,382; while the two English banks return assets as £1,032,130, liabilities £1,685,752, and deposits included in the liabilities £1,643,574. The following is a statement of the Tasmanian banking position from 1890 onwards:—

Year.	Assets.	Liabilities.	Excess of Assets.
	£	£	£
1890 .....	4,711,549	4,412,094	299,454
1891 .....	4,428,251	4,192,791	235,460
1892 .....	3,974,259	3,798,562	175,697
1893 .....	3,580,406	3,396,240	183,166
1894 .....	3,365,336	3,338,362	26,974
1895 .....	3,358,894	3,309,598	49,296
1896 .....	3,246,904	3,200,433	46,471
1897 .....	3,234,320	3,102,943	131,386
1898 .....	3,327,101	3,112,799	214,302
1899 .....	3,341,030	3,287,623	73,407
1900 .....	3,388,112	3,400,097	*11,985
1901 .....	3,264,592	3,374,399	*109,807
1902 .....	3,527,695	3,751,722	*224,027
1903 .....	3,552,281	3,756,338	*204,057

\* Denotes excess of Liabilities.

The peculiarity of the New Zealand position has already been alluded to. For the December quarter, 1903, the statements show an excess of assets equal to £218,394, notwithstanding that the two local banks have capital and reserves to the extent of £2,950,260, while the other banks also have a large amount of capital employed in the colony. The anomalous condition of affairs arises from the position of the Bank of New Zealand as a state guaranteed institution. This bank had in December, 1903, liabilities in New Zealand to the extent of £10,242,866, including a Government deposit of £1,481,636, and assets of £8,111,398, showing a deficiency of £2,131,468. The balance-sheet of the March quarter, 1904, shows that the bank had in London money at call £2,475,285, bills receivable £1,003,287, and other securities accounting for the short holdings in New Zealand. The following is a statement of assets and liabilities, with the excess of assets in each year from 1890 onwards:—

Year.	Assets.	Liabilities.	Excess of Assets.
	£	£	£
1890 .....	17,735,259	13,856,598	4,378,661
1891 ..	16,814,518	13,820,458	2,994,060
1892 .....	17,558,168	14,623,335	2,934,833
1893 .....	19,255,534	15,489,633	2,765,901
1894 .....	17,746,421	14,930,791	2,815,630
1895 .....	18,159,781	14,491,627	3,668,154
1896 .....	16,900,199	15,520,431	1,379,768
1897 .....	17,276,771	15,380,248	1,896,523
1898 .....	17,013,404	15,299,058	1,714,346
1899 .....	17,190,433	15,834,858	1,355,575
1900 .....	17,314,535	16,964,582	349,953
1901 .....	18,422,274	17,490,035	932,239
1902 .....	19,162,178	19,018,532	143,646
1903 .....	20,590,387	20,861,993	218,394

## RESULTS OF WORKING OF BANKS.

The results of working of each bank for the latest period for which information is available are given below. With the exception of the Bank of Adelaide, the Bank of New Zealand, the English, Scottish, and Australian Bank, the London Bank of Australasia, and the National Bank of New Zealand, for which the figures refer to twelve months' operations, the amounts given cover a period of six months. The dates of the balance-sheets are as shown on page 782 :—

Bank.	Class of Shares.	Amount brought forward.	Net Profit less Rebate on Bills current.	Dividend paid.		Amount transferred to Reserve Fund, Contingency Accounts, Reduction of Premises Account, &c.	Amount carried forward.
				Rate per cent. per annum.	Amount.		
Australian Joint Stock Bank (Ltd.)..	Ordinary ..	£ Nil	£ 2,459	..	Nil	£ Nil	£ 2,459
Bank of Adelaide .....	" ..	17,740	31,337	8	16,000	15,000	18,077
Bank of Australasia .....	" ..	16,952	150,934	12	96,000	55,000	16,886
Bank of New South Wales .....	" ..	18,024	120,435	10	100,000	20,000	18,459
Bank of New Zealand .....	{ Preferential ..	.....	200,303	{ 5	21,281	{ 50,000	129,022
Bank of North Queensland (Limited)	Ordinary ..	117	2,251	24	1,312	1,000	56
Bank of Victoria (Limited) .....	{ Preferential ..	10,173	34,555	{ 5	10,419	.....	15,737
City Bank of Sydney .....	Ordinary ..	1,108	9,045	4	8,000	1,000	1,153
Colonial Bank of Australasia (Ltd.)..	{ Preferential ..	2,764	18,237	{ 5	7,001	5,000	5,083
Commercial Bank of Australia (Ltd.)	Ordinary ..	31,792	67,618	3	31,759	62,893	14,758
Commercial Banking Co. of Sydney (Limited) .....	Ordinary ..	20,265	65,555	10	50,000	15,000	20,820
Commercial Bank of Tasmania (Ltd.)	" ..	3,044	12,635	10	7,428	5,000	3,251
English, Scottish, and Australian Bank (Limited) .....	" ..	10,221	58,847	4	33,840	23,193	12,035
London Bank of Australia (Limited)	{ Preferential ..	10,024	22,056	{ 5	9,456	.....	14,317
National Bank of Australasia (Ltd.)..	Ordinary ..	10,831	36,950	34	20,868	10,000	9,263
National Bank of New Zealand (Ltd.)	Ordinary ..	7,761	60,642	12	30,000	30,000	8,403
National Bank of Tasmania (Limited)	" ..	4,261	5,347	6	4,790	.....	4,718
Queensland National Bank (Limited)	" ..	.....	21,822	.....	3,000	18,822	.....
Royal Bank of Australia (Limited) ..	" ..	2,470	7,333	6	4,500	.....	5,303
Royal Bank of Queensland (Limited)	{ Preferential ..	880	9,181	{ 34	8,421	1,000	640
Union Bank of Australia (Limited) ..	Ordinary ..	25,066	115,239	10	75,000	39,000	26,305
Western Australian Bank .....	" ..	13,380	24,846	174	10,938	.....	27,288

The total net profit for the Bank of New Zealand was £292,803, and the interest on guaranteed stock amounted to £80,000, leaving £212,803 for distribution. Of this sum £12,500 was written off the various estate and property accounts; £50,000 was paid to the Assets Realisation Board and £21,281 for dividend on ordinary shares at 5 per cent. : leaving a balance of £129,022 which must be paid to the Assets Realisation Board in accordance with the Act of 1895 which governs the operations of the bank. The dividend paid by the Queensland

National Bank represents a repayment to the Government of that state in terms of the scheme of arrangement, and the amount transferred to reserve fund, etc., includes £6,000 paid to private depositors' repayment fund. The total net profit was £21,822, of which £9,822 was allotted to the contingency account. The net profit shown for the London Bank of Australia, and the English, Scottish, and Australian Bank (Limited), is exclusive of the interest on Transferable Fixed Deposits, Debenture Stocks, &c. ; while the earnings of the Commercial Bank of Australia (Limited), exclude £8,500 transferred to the Special Assets Trust Reserve Account, and £28,871 to the Special Assets Trust Company. The net profit shown for the Union Bank of Australia (Limited) is inclusive of £10,000 for reduction of premises, and £4,000 in aid of the guarantee and provident funds. The dividend tax payable by the two Tasmanian banks, the Royal Bank of Queensland, and the Bank of North Queensland, has been included in the amount of dividend shown in the table. The amount shown as carried to reserve by the Bank of Australasia includes £25,000, for reduction of cost of premises. In the case of the English, Scottish, and Australian Bank (Limited), the amount of dividend shown includes a further payment of £12,262, being an extra  $1\frac{1}{2}$  per cent. interest to the holders of Deferred Inscribed Deposit Stock, and the amount shown as carried to reserve includes £7,193 for the purchase and cancellation of Deferred Inscribed Deposit Stock, in accordance with the articles of association, and £1,000 contribution to Officers' Guarantee and Provident Fund.

#### BANKING BUSINESS OF EACH STATE.

Of the twenty-two banks operating in Australasia during 1904 thirteen had offices in New South Wales, eleven in Victoria, eleven in Queensland, seven in South Australia, six in Western Australia, four in Tasmania, and five in New Zealand. There were only two banks doing business in all the seven states; one transacted business in six states; one in five states; two in four; two in three; four in two; and ten banks did not extend their business beyond the limits of one state or colony. The majority of the institutions, however, had offices in London.

The liabilities and assets of the twenty-two banks of issue operating in the different states and New Zealand during the June quarter of 1904 are shown in the following tables. The total liabilities of the banks are given as £116,685,022, and the assets as £134,504,473, showing a surplus of assets of £17,819,451. If the returns gave all the facts in relation to the operations of the banks, this surplus should represent the capital or funds provided out of their own resources; but as the capital and reserve funds amount to £25,268,456, it is evident that there is a balance of £7,449,005 not used in the Australasian business. It should be noted that in the following table under the heading of deposits bearing interest has been included perpetual inscribed stock of the English, Scottish, and Australian Bank (Limited), to the amount of

# ACCUMULATION.

795

£2,049,594, viz., £692,634 in New South Wales, £939,761 in Victoria, £321,235 in South Australia, and £95,964 in Queensland :—

State.	Notes in circulation not bearing Interest.	Bills in circulation not bearing Interest.	Deposits.		Balances due to other Banks, &c.	Total Liabilities.
			Not bearing Interest.	Bearing Interest.		
	£	£	£	£	£	£
New South Wales.....	1,844,822	208,782	12,965,482	20,178,225	71,102	34,708,368
Victoria .....	891,646	125,588	10,878,428	20,315,543	60,914	32,267,119
Queensland .....		88,624	3,931,603	8,609,215	64,417	12,603,760
South Australia .....	389,560	34,339	2,434,255	3,941,012	27,142	6,826,296
Western Australia.....	354,715	43,294	3,296,231	1,429,927	62,025	5,186,192
Tasmania .....	152,585	20,790	1,467,384	2,105,797	4,830	3,761,346
Commonwealth .....	3,133,268	521,267	34,968,383	56,579,719	290,439	95,468,076
New Zealand .....	1,519,784	50,758	9,581,663	9,998,118	41,623	21,191,946
Australasia.....	4,653,052	572,025	44,550,046	66,577,837	332,062	116,065,022

The preceding table shows that over 95 per cent. of the Australasian liabilities of the banks consisted of deposits, viz., £111,127,883 out of £116,685,022. The returns of the banks in each state, distinguish between deposits at call and deposits bearing interest, and the total deposits at call are as stated in the table, viz., £44,550,046, or 40 per cent. of all deposits.

The assets for the same period are shown below. Certain assets of small amount, consisting chiefly of Government and other securities, have been included under all debts due to the banks. The value of landed property in Victoria is exclusive of the interest of the Commercial Bank of Australia (Limited), in the Special Assets Trust Company (Limited). Also, under the heading of "Notes and Bills of other banks," &c., are included Queensland Treasury Notes to the amount of £652,752 :—

State.	Coin.	Bullion.	Landed Property.	Notes and Bills discounted, and all other Debts due to the Banks.	Notes and Bills of other Banks, and Balances due from other Banks.	Total Assets.
	£	£	£	£	£	£
New South Wales.....	6,753,342	212,765	1,812,419	33,273,258	554,197	42,605,976
Victoria .....	5,775,832	450,122	1,965,555	29,426,062	502,196	38,119,757
Queensland .....	1,590,636	228,171	785,002	13,285,384	814,197	16,693,990
South Australia .....	1,437,507	15,253	425,714	4,401,991	112,968	6,393,273
Western Australia.....	1,001,662	541,887	197,697	3,955,108	79,982	6,575,335
Tasmania .....	751,792	....	108,924	2,710,083	63,429	3,634,228
Commonwealth .....	17,910,771	1,447,698	5,245,311	87,052,471	2,126,809	113,783,000
New Zealand .....	3,712,352	155,474	410,278	16,349,880	94,424	20,721,413
Australasia.....	21,023,123	1,608,172	5,655,584	108,401,361	2,221,243	134,504,473

The liabilities referred to in the table on the preceding page are those to the public, the paid up capital and reserves not being considered. If the assets be compared with the liabilities of the banks in the various states, in three instances, namely, South Australia, Tasmania, and New Zealand, it will be found that there is an excess of liabilities over assets, showing that, taken as a whole, the banks do not employ any of their own capital in those states. It not infrequently happens that the liabilities of an individual bank in one or more of the states in which it trades exceed the assets, but only in the states mentioned do the total liabilities of the banks exceed the assets. As the question is of considerable economic interest the banks having an excess of liabilities in any particular state are enumerated in the list now given.

NEW SOUTH WALES.		
	Assets.	Liabilities.
	£	£
Queensland National Bank, Limited .....	186,347	288,639
Bank of North Queensland, Limited.....	54,953	85,413
VICTORIA.		
Bank of Australasia .....	5,669,889	5,347,804
SOUTH AUSTRALIA.		
Bank of Australasia .....	493,111	793,157
Union Bank of Australia, Limited.....	1,170,806	1,405,799
English, Scottish, and Australian Bank, Limited.....	612,888	736,313
Bank of Adelaide .....	1,567,759	1,734,512
TASMANIA.		
Bank of Australasia .....	535,783	923,741
Union Bank of Australia, Limited.....	499,252	730,402
NEW ZEALAND.		
Bank of New Zealand .....	8,138,694	10,478,840
Union Bank of Australia, Limited.....	2,846,745	2,899,511
National Bank of New Zealand, Limited ...	3,067,086	3,088,021

#### EXPENSES OF BANKING.

The balance-sheets of banks, as presented to the shareholders, do not usually contain details likely to satisfy the inquirer curious to discover the amount of gross profits as compared with the net amount divisible amongst shareholders. Allowing the same proportion of expenses for the banks not disclosing this information as for those concerning which particulars are available, the following results are obtained for the last working year dealt with in the preceding pages :—

Total trading assets.....	£160,823,392
Capital and reserves .....	25,300,226
Gross earnings, less reserve for bad and doubtful debts .....	6,800,281
Gross expenditure, including interest.....	4,965,816
Net earnings.....	1,834,465



Compared with the total assets, the net earnings represent 1·12 per cent.; and compared with the banks' own resources, i.e., capital and reserved profits, 7·46 per cent. The gross expenditure above set down may be divided into expenses of management, £2,255,588, and interest, £2,730,228; these together amount to 72·68 per cent. of the gross earnings, the management expenses being 32·88 per cent., and the interest 39·80 per cent. It would appear, therefore, that for every £1 of net earnings, the sum of £1 4s. 1d. is spent in management expenses, and £1 9s. 2d. in interest. The cost of working banking institutions in Australia is undoubtedly very large; but this class of business is everywhere expensive, and an analysis of the balance-sheets of some thirty British banks shows that the expenses of management amount to about 16s. 1d. for every £1 of net earnings.

## EARNINGS COMPARED WITH RESOURCES.

Compared with their resources, the net earnings of Australasian banks are far less than those of English banks, as will appear from the following statement, which gives the rate per cent. per annum of earnings compared with total resources, including, of course, deposits and issue, as well as shareholders' capital and reserves:—

	£	s.	d.
Bank of England .....	1	5	9
English Provincial Banks.....	1	8	2
Irish Banks .....	1	8	8
London Banks.....	1	4	8
Scotch Banks .....	1	4	7
Banks trading in Australasia .....	1	4	7

The net earning power of Australian banks has much improved during recent years, and is now larger than at any time since the crisis. The year 1892 showed net earnings equal to £1 0s. 4d. per cent. of the banks' resources; this is, however, as will be seen from the statement below, a reduction on the earnings of previous years. From that year there was a steady falling off, until in 1897 the net earnings were only 8s. 5d. per cent., which was perhaps as poor a showing as could be found in the history of Australian banking. After 1897 there was a gradual recovery, and the year closing with June, 1903, showed an improvement even on 1892. The net earnings per cent. during the past sixteen years, were:—

	£	s.	d.		£	s.	d.
1889.....	1	8	10	1897.....	0	8	5
1890.....	1	7	10	1898.....	0	10	10
1891.....	1	6	4	1899.....	0	13	10
1892.....	1	0	4	1900.....	0	16	1
1893.....	0	17	7	1901.....	1	0	1
1894.....	0	12	10	1902.....	1	1	7
1895.....	0	9	0	1903.....	1	3	7
1896.....	0	8	8	1904.....	1	4	7

The expense of banking in Australasia is largely due to the number of branches open throughout the country ; thus in Australasia there are 1,673 banks and branches, or one to every 2,870 persons, while in England the proportion is one bank to 7,900 persons (exclusive of private banks), in Scotland one to every 4,100, and in Ireland one to every 7,200.

#### BANK CLEARING HOUSES AND EXCHANGES.

In the year 1868 a Clearing-house was established in Melbourne in the interests of the nine principal banks doing business in that city. These banks agreed to deposit in gold certain sums proportionate to the capital employed, and at the present time the amount of this deposit is £650,000. To each bank there were originally issued parchment certificates, each representing the sum of £1,000, the number of certificates issued to a bank being proportionate to the amount of its original deposit. An inspector was appointed to supervise the business of the clearing house, and every bank is required to hold certificates to an amount corresponding to the share which it should have in the total sum held by the clearing house. There are six or more clearances daily, and at the close of the day the balances for or against each bank are made out by the inspector, and once a week settlements are made, and, in effecting these settlements, certificates or coin are used indifferently, but any bank holding certificates above the proportion required by the constitution of the clearing house may demand gold if it chooses to do so ; and any bank holding less than its proportion is called upon by the inspector to make up its quota by the payment of gold.

The total transactions of the Melbourne Clearing House for each of the last ten years were :—

	Total Amount Cleared.	Weekly Average.
	£	£
1894 .....	125,589,000	2,415,000
1895 .....	130,789,000	2,515,000
1896 .....	141,736,000	2,725,000
1897 .....	143,843,000	2,766,000
1898 .....	142,675,000	2,744,000
1899 .....	158,914,000	3,056,000
1900 .....	159,949,000	3,076,000
1901 .....	170,426,000	3,277,000
1902 .....	170,025,000	3,270,000
1903 .....	166,693,000	3,206,000

The year 1894 showed the lowest figures recorded since the establishment of the Clearing-house in 1868, and the figures will appear especially small if they be compared with those of some of the preceding years. Thus, in 1888, the total clearances amounted to £239,991,000, that is at an average of £5,576,750 per week, an enormous figure for a population of little more than a million, and indicating over-speculation and inflation. The returns enable the amount of notes, cheques, and bills sent in for exchange to be stated, as well as the payments in

vouchers and coin to complete the clearances. During the year 1903 there were sent to the Clearing-house for exchange or settlement :—

Notes .....	£ 10,322,000
Cheques, Bills, &c. ....	156,371,000
Total .....	£166,693,000

The exchange of this large sum was effected by the transfer of documents to the amount of £145,188,000, leaving a balance of £21,505,000 to be made good by payments in cash. The actual amount of coin used was £4,164,000, payment of £17,341,000 being in certificates.

The proportion of coin used was 2·5 per cent. ; of clearing-house certificates 10·4 per cent. ; and the proportion of exchanges effected by the transfer of cheques, bills, and other documents was 87·1 per cent. The use of so much gold coin is due to the circumstance that the uncoined gold received by the Melbourne Mint for coinage comes almost entirely from the banks, and is paid for by cheque ; the amount of this cheque sometimes forms a very considerable proportion of the money in the pool, and for this reason it would be impossible to maintain the deposit intact if the gold certificates were not supplemented by actual transfers of gold from bank to bank.

The value of the bank notes brought to the Clearing-house for exchange for other notes or cash was £10,322,250.

The whole note circulation in Victoria during 1903 was £930,000, so that on an average each note was cleared eleven times. The Melbourne house is a clearing-house in the full sense of the term, as practically the whole exchange business of the banks connected with it is transacted therein. In this respect it differs from a somewhat similar institution which has been established in Sydney. The clearances of the latter do not include bank notes, nor cheques, bills, &c., drawn on any other than metropolitan branches of the institutions connected with it. The Sydney Banks' Exchange Settlement Office was established on the 18th January, 1894, and, as just explained, is not a clearing-house in the accepted term, as the exchanges are still effected daily at the banks by clerks of each institution ; but the results of the daily operations are notified to the secretary of the Banks' Exchange Settlement, who establishes the daily credit of each bank with the "pool." The "pool" is placed in the hands of three trustees, and consists of £700,000 in gold, which is deposited in the vaults of three of the banks, and cannot be circulated or disturbed. The contributions to the "pool" are according to the volume of the operations of each bank. The secretary notifies each bank daily of the amount of its credit with the "pool," and no bank is permitted to allow its balance to continue below 25 per cent. of the fixed contribution. In the event of its credit reaching this margin, the bank is required to make up its deficiency with gold ; this payment, however, is not made to the

"pool," but to such other banks as may happen to have at their credit with the "pool" a larger sum than is required by the agreement. This arrangement enables the £700,000 comprising the "pool" to remain intact.

The volume of the exchanges from the establishment of the "pool" to the end of 1903 is shown in the following table:—

Period.	Amount of Exchanges.	Period.	Amount of Exchanges.
	£		£
1894 (part) .....	101,242,905	1899.....	146,188,144
1895.....	108,500,860	1900.....	144,060,314
1896.....	117,718,862	1901.....	167,676,707
1897.....	121,645,873	1902.....	178,637,708
1898.....	196,978,018	1903.....	180,961,406

The year 1894 shown in the above table represents the transactions of 49½ weeks; the other figures are for the whole year.

In Brisbane, the Queensland National Bank is the settling bank for all institutions transacting bank business in that state. In none of the other states has it been found necessary to establish a clearing-house, nor has one yet been established in any of the New Zealand cities.

#### INVESTMENT COMPANIES.

In addition to the Banks of Issue, there are numerous Savings Banks, and Land, Building, Investment, Trading, and Commercial Companies receiving money on deposit and transacting much of the business usually undertaken only by banks of issue. The land, building, and other trading companies were presumed to be in a flourishing condition even as late as the year 1890. Their dividends to shareholders were very large, and the rates allowed on deposits were considerably in excess of those current in the banks of issue. As might be expected, the high interest offered was too tempting a bait to be resisted by a section of the investing public, and large sums were placed in these institutions with the utmost confidence that they would be available when required. This confidence, unfortunately, proved to be, in many instances, unmerited. The shrinkage of land values, and the depreciation of real estate generally, put an end to all unsound institutions working on speculative lines, as well as to some other companies that were conducted on reasonable principles. The difficulties into which the deposit companies fell may for the most part be attributed to their practice of borrowing money for short periods, and locking it up for long terms. Besides this, however, many so-called building societies indulged in speculative land purchases, and having retailed the land at enhanced prices, with payments over extended periods, proceeded to divide the presumed profits among the shareholders, with a result that might easily have been foreseen, for in many cases the purchasers, after paying a few instalments towards the price, left the allotments on the hands of the companies, whose anticipated profits were therefore purely visionary, and whose dividends were really never earned, but, in many

instances, were merely taken from the deposits. Complete returns of these societies are not available, but the amounts held on deposit in some of the states will be found on page 806.

#### SAVINGS BANKS.

The Savings Banks are on a very different footing, being to a greater or less extent under state control and otherwise safeguarded, so that they enjoy public confidence. The institutions classed as Savings Banks may be divided into two kinds—those worked in conjunction with the Post Office, and, consequently, directly administered by the state; and those under trustees or commissioners, who are generally nominated by the government. The declared objects of these banks are to encourage thrift in the working classes, and to provide a safe investment for the funds of charitable institutions, friendly societies, and such like. The institutions, however, have become so popular that all classes of the community are represented amongst their depositors, and the banking crisis of 1893 had the effect of largely increasing their business.

In New South Wales there are both state and trustee institutions for the receipt of savings, the Post Office Savings Bank having been established in 1871, and the Savings Bank of New South Wales as far back as 1832. In both institutions sums of one shilling and any multiple of that amount may be deposited; but, with the exception of the funds of charitable institutions and friendly societies, deposits exceeding £300 do not bear interest on such excess. From the 1st January, 1904, the Post Office Savings Bank allowed interest at the rate of 3 per cent. on all sums deposited, not exceeding a total of £300, to the credit of any one account, Friendly and Charitable Societies being allowed interest on all deposits made. During the year ended 31st December, 1903, the Savings Bank of New South Wales allowed 3 per cent. interest on accounts closed during the year, and  $3\frac{1}{2}$  per cent. for those remaining open at the end of the year. It is proposed to increase the interest to depositors to  $3\frac{1}{2}$  per cent. during 1904, and by the Amendment Act assented to on 5th December, 1903, the limit of deposits by individuals was raised from £200 to £300. A measure providing for the amalgamation of the two institutions is now before Parliament, but up to the present the Bill has not been passed.

In Victoria both Commissioners' and Post Office Savings Banks, established in 1842 and 1865 respectively, were in operation until the 30th September, 1897, when they were amalgamated under the Savings Bank Amendment Act of 1896, the Commissioners assuming the control of the new institution. Amounts of one shilling and any multiple thereof are received. The Act referred to further provided for advances to farmers and others, and this portion of the Act was brought into operation without delay. From the 1st July, 1903, interest is allowed

at the rate of 3 per cent. on sums not exceeding £100, and  $2\frac{1}{2}$  per cent. from £100 to £250, the latter being the maximum amount carrying interest.

In Queensland, a Government Savings Bank, not administered in connection with the Post Office, is in operation, the system dating from 1865. The interest allowed during 1895 was  $3\frac{1}{2}$  per cent. on all deposits below £200; but from July, 1896, the rate was reduced to 3 per cent., which is the rate now being paid. In December, 1895, authority was obtained for the issue of Savings Bank Stock at 3 per cent. to enable depositors of upwards of £200 to obtain interest on such excess, as it was found that large sums were entrusted to the Government which could not earn interest under the old constitution of the Bank.

In South Australia there is, properly speaking, no Government Savings Bank; but an institution administered by trustees was established in 1848. The rate of interest paid by the trustees has been the subject of many changes. Starting at 3 per cent., it fell as low as 1 per cent. in 1853; rose to 6 per cent. in 1858; and declined to 4 per cent. in 1873. Between the year last mentioned and 1892, interest fluctuated between  $5\frac{1}{2}$  and  $4\frac{1}{2}$  per cent.; and in 1893 it was reduced to 4 per cent., at which it remained during the years 1894 and 1895, while in 1896 and 1897 it was still further reduced to  $3\frac{1}{2}$  per cent. and 3 per cent. respectively—the latter rate being allowed in 1901–2. During 1904, interest at the rate of  $3\frac{1}{2}$  per cent. was allowed on accounts open on the 30th June, and at the rate of 3 per cent. on accounts closed during the year, the maximum amount bearing interest being £250.

In Western Australia, Post Office banks have been in operation since 1864. One shilling and upwards may be received, provided not more than £150 is deposited in any one year, while the maximum amount of deposits must not exceed £600. Interest is allowed at the rate of 3 per cent. provided the amount at credit is not less than £1, and not more than £300.

In Tasmania, Post Office and trustee banks are working side by side. Sums of one shilling and upwards may be deposited, the interest allowed being 3 per cent. both in the Post Office banks and in the trustee institutions, with the exception of the Hobart Savings Bank, which has decided to increase the rate of interest to  $3\frac{1}{2}$  per cent. Interest is not allowed on amounts over £150.

In New Zealand, Post Office and trustee institutions are also established. The former commenced operations in February, 1867; but some of the other class of banks are of much older standing, the Auckland Savings Bank, for instance, having been established as far back as 1847. Deposits of one shilling and upwards are received. Interest was formerly allowed in both classes of institutions at the rate of  $4\frac{1}{2}$  per cent. up to £200, and 4 per cent. from £200 to £500; but in July, 1893, the rates allowed in the Government Savings Bank were reduced to 4 per cent. and  $3\frac{1}{2}$  per cent. respectively, the maximum

amount bearing interest remaining at £500. These rates remained in force until the 1st January, 1896, when the interest was reduced to  $3\frac{1}{2}$  per cent. and 3 per cent. respectively; while from the 1st November, 1897, a further reduction was made, the rates ruling from that date being 3 per cent. up to £200, and  $2\frac{1}{2}$  per cent. from £200 to £500, no interest being allowed on sums in excess of £500. The trustee Savings Banks in 1895 allowed 4 per cent., but reduced this rate to  $3\frac{1}{2}$  per cent. from the beginning of 1896. In 1897 the interest was increased to 4 per cent. on amounts under £100; but in 1900 it was again reduced to  $3\frac{1}{2}$  per cent., which is the rate now allowed. A feature of the New Zealand Post Office Savings Bank is that deposits of one shilling may be made by means of postage stamps affixed to cards specially issued for the purpose. This plan was adopted to encourage thrift among children. It was recognised to be a difficult matter for a child to save its pence until they accumulated to a shilling; but under the present system, whenever a child receives a penny it may purchase a postage stamp and affix it to the card in its possession.

The returns of the Savings Banks show an enormous development since the year 1861. At that period the number of depositors in Australasia (excluding Tasmania, for which there are no returns) was 29,062, with the sum of £1,367,396 to their credit, or an average of £47 to each depositor. In 1871 the number of depositors had risen to 115,074, with deposits amounting to £3,675,772; but the average amount credited to each depositor was only £31 18s. 10d. In the year 1881 there were 311,124 depositors, with a total of £9,442,979, averaging £30 7s. for each account. In 1891 the number of depositors had increased to 741,627, and the amount of deposits to £18,943,541, the average being £25 10s. 1d. In 1901-2 the number of depositors had risen to 1,252,219, with deposits amounting to £40,126,061, giving an average sum of £32 0s. 11d. to each account. In 1902-3 the number of depositors had increased to 1,299,681, with deposits amounting to £41,736,977, or an average sum of £32 2s. 3d. to each account. In 1903-4 the number of depositors had increased to 1,352,853, with deposits amounting to £42,613,014, or an average sum of £31 9s. 10d. It will thus be seen that there has been a decline in the amount per depositor from the period first mentioned; but this is no sign of retrogression, for the large increase in the number of depositors, which must be taken into consideration, evidences the fact that the less affluent classes of the community are more largely represented in the books of the banks than was formerly the case. In point of fact, the proportion of depositors to the entire population has increased throughout the period dealt with. Thus, in 1861 the number of persons who had accounts in the Savings Banks represented only 2.31 per cent. of the entire population of Australasia; but in 1871 the percentage had risen to 5.98; in 1881, to 11.33; in 1891, to 19.47; in 1900-1, to 25.52 per cent.; in 1902-3 the proportion was 27.69 per cent.; while in 1903-4 it was 28.41 per cent. Dealing with the individual states, the Queensland

## ACCUMULATION.

depositors have the largest amount at their credit, averaging £46 14s. 9d. per head; New South Wales depositors come next with £37 3s. 9d.; Western Australia depositors occupy the third position with £36 7s. 1d.; while those of Victoria have the smallest sum, their average being only £24 9s. 0d. The subjoined table shows the progress of accumulation in the Savings Banks of each of the states and of New Zealand since 1871 :—

Year.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
NUMBER OF DEPOSITORS.									
1871	24,379	45,819	6,760	14,270	1,662	8,500	100,769	14,275	115,074
1881	72,384	101,880	20,168	37,742	3,310	14,738	250,070	61,054	311,134
1891	158,426	300,781	46,259	78,796	3,564	26,916	614,741	126,886	741,627
1900-1	282,643	393,086	81,096	111,637	36,339	42,509	960,079	228,888	1,178,992
1902-3	323,212	418,511	80,043	120,349	48,015	47,626	1,037,759	261,922	1,399,631
1903-4	331,956	432,567	80,069	123,455	56,623	47,904	1,072,369	279,984	1,352,938
AMOUNT OF DEPOSITS.									
1871	£ 945,915	£ 1,117,761	£ 407,134	£ 517,000	£ 16,568	£ 217,413	£ 3,220,806	£ 454,908	£ 5,675,772
1881	2,098,703	2,569,438	944,251	1,288,460	23,344	836,278	7,893,464	1,549,515	9,442,979
1891	5,342,135	5,715,687	1,680,753	2,217,419	46,181	554,417	15,536,592	3,406,949	18,943,541
1900-1	10,901,882	9,662,007	3,896,170	3,782,575	1,613,359	1,006,098	30,866,591	6,665,344	37,534,885
1902-3	12,425,464	10,341,757	3,772,686	4,172,720	1,941,331	1,206,242	33,860,100	7,876,877	41,736,977
1903-4	12,344,623	10,582,808	3,741,967	4,202,637	2,068,619	1,249,401	34,180,056	8,432,969	42,613,014
AVERAGE AMOUNT PER DEPOSITOR.									
1871	£ s. d. 38 16 0	£ s. d. 24 7 11	£ s. d. 60 2 11	£ s. d. 36 4 7	£ s. d. 14 13 6	£ s. d. 25 11 7	£ s. d. 31 19 0	£ s. d. 31 17 5	£ s. d. 31 18 10
1881	37 5 8	25 4 7	46 16 5	34 2 9	7 5 0	35 1 6	31 11 4	35 7 7	30 7 0
1891	33 14 5	19 0 1	35 18 0	23 2 10	12 19 2	20 13 0	25 5 6	36 17 0	35 10 1
1900-2	38 11 4	24 11 8	44 1 8	33 18 3	41 2 9	23 14 8	32 9 10	30 2 5	31 16 9
1902-3	38 8 10	24 14 8	47 2 8	34 13 3	40 8 25	6 25 6	32 12 7	30 1 6	32 2 3
1903-4	37 3 9	24 9 0	46 14 9	34 0 10	36 7 1	26 1 8	31 17 2	30 2 4	31 9 10

The following table shows the average amount per head of population, and the average number of depositors per 100 of population, in each of the states for the year 1903-4 :—

State.	Average amount per head of population.	Depositors per 100 of population.
	£ s. d.	
New South Wales .....	8 12 5	23
Victoria .....	8 15 5	36
Queensland .....	7 3 9	15
South Australia .....	11 8 3	34
Western Australia .....	9 1 3	23
Tasmania .....	7 0 0	21
Commonwealth.....	8 13 8	27
New Zealand .....	10 4 1	34
Australasia .....	8 19 0	28

It will be observed that Victoria had the largest number of depositors per 100 of population; while the largest amount per head of population was reached in South Australia.



The following table shows the number of depositors in the savings banks of the principal countries of the world, the total amount standing at their credit, and the average amount per depositor. The figures are compiled from the latest available returns :—

Country.	Depositors.	Amount of Deposits in Savings Bank.	Average Amount per Depositor.
	No.	£	£ s. d.
United Kingdom .....	10,803,555	197,110,169	18 4 10
Sweden .....	1,865,596	30,101,881	16 2 8
Norway .....	718,823	18,812,997	26 3 5
Holland .....	1,260,603	14,427,083	11 8 10
Austria-Hungary .....	5,393,002	178,896,632	33 2 5
Belgium .....	1,862,829	29,151,761	15 12 11
Italy .....	6,766,775	103,507,753	15 5 11
France .....	11,237,510	176,641,811	15 14 4
Denmark .....	1,203,120	36,996,197	30 15 0
Russia .....	4,857,000	97,124,736	22 5 10
United States .....	6,666,672	565,880,101	84 17 8
* Canada .....	911,762	12,024,318	56 5 8
Australasia .....	1,352,853	42,613,014	31 9 10

\* Exclusive of £4,189,483 in special Savings Banks—number of depositors not available.

The figures for the United States are given on the authority of the official *Statistical Abstract*, and are, to all appearances, correct.

#### TOTAL DEPOSITS IN BANKS.

If to the amounts deposited in the savings banks of the states be added the deposits in banks of issue, it will be seen that the total sum on deposit in banking institutions is equal to £32 for each inhabitant of Australasia. The largest amount on deposit as compared with population is found in Victoria, with £34 12s. 8d., or £2 12s. 8d. above the average of all the states. The particulars for each state will be found below :—

State.	Deposits in Banks of Issue (Averages for the second quarter of 1904.)	Deposits in Savings Banks.	Total Deposits.	Amount of Deposits per head of Population.
	£	£	£	£ s. d.
New South Wales .....	33,143,707	12,344,623	45,488,330	31 9 3
Victoria .....	31,188,971	10,582,808	41,771,779	34 12 8
Queensland .....	12,540,818	3,741,967	16,282,785	31 0 2
South Australia .....	6,376,267	4,202,637	10,577,904	28 13 3
Western Australia .....	4,726,158	2,058,619	6,784,777	28 10 2
Tasmania .....	3,573,181	1,249,401	4,822,582	27 2 0
Commonwealth .....	91,548,102	34,180,055	125,728,157	31 14 8
New Zealand .....	19,579,781	8,432,959	28,012,740	83 5 3
Australasia .....	111,127,883	42,613,014	153,740,897	32 0 0

As already mentioned, large sums are also deposited with various building and investment societies, but the returns with reference to these are incomplete. The latest available figures show that the amounts so invested were:—In New South Wales, £1,142,344; in Victoria, £735,017; in Tasmania, £118,466; and in New Zealand, £360,129.

In the following table are given the deposits in banks, including savings banks, and, where available, building societies, &c., at five decennial periods, as well as for the year 1903-4:—

State.	1861.	1871.	1881.	1891.	1900-1.	1903-4.
	£	£	£	£	£	£
New South Wales .....	5,645,108	7,969,801	23,006,720	42,988,550	44,954,947	66,630,674
Victoria .....	7,575,408	12,476,677	23,721,348	50,183,551	42,006,957	42,506,795
Queensland .....	334,503	1,647,830	5,633,097	12,154,657	17,090,650	16,282,785
South Australia .....	875,320	2,088,719	6,231,004	9,992,338	10,652,971	10,577,904
Western Australia .....	*2,487	*15,583	*23,344	1,365,906	6,030,578	6,784,777
Tasmania .....	†729,085	875,512	2,969,390	4,220,292	4,327,371	4,941,668
Common-wealth { Total .....	15,161,909	25,044,122	61,584,968	120,906,294	124,462,763	127,723,964
wealth { Per head .....	£13	£15	£27	£26	£23	£21
New Zealand .....	905,675	3,789,639	10,612,253	17,497,436	23,306,260	24,572,569
Austral-Asia { Total .....	16,067,584	28,833,761	72,203,796	138,402,730	147,769,048	156,096,533
asia { Per head .....	£13	£15	£26	£26	£23	£22

\* Savings Banks only.

† Banks of Issue only.

From this table it will be seen that the increase of deposits in all classes of banks between 1861 and 1881 was exactly 100 per cent., allowing for the growth of population; while between 1871 and 1891 the deposits per head of population increased by 140 per cent. Compared with the figures for Great Britain, the amount of deposits per head of population in Australasia far exceeds that in the older country. In 1861, indeed, the sum per head in Great Britain was higher than in Australasia, amounting to £15 as against £13 in the colonies, and in 1874 the British average stood at £25 per head; but ten years later, in 1884, it had sunk to £23, and in 1890 to £16; while in 1901 the rate per head had increased to over £24. In the colonies there was no falling-off at any period until 1893—the total deposits per head in 1888 far exceeding the highest level ever reached in Great Britain. In 1893, however, there was a decline of about ten millions in the sum total of Australasian deposits; that is to say, the commercial depression which prevailed more or less throughout Australasia during that year caused the amount mentioned to be withdrawn from the savings of the people and to be employed in meeting current expenses and in the maintenance of credit. During 1894 and 1895 there was a further falling-off in Victoria and Tasmania; but the other states showed larger deposits in 1895 than in 1893—the Queensland, Western Australia, and New Zealand deposits being even larger than in 1891. In 1903-4 the savings in all the states were greater than in 1895, the net increase in the eight and a half years being nearly twenty-six millions, while, compared with 1891, there was an increase of about seventeen and a half millions. It will thus be seen that the states have entirely recovered from the effects of the financial crisis of 1893.

In some of the states the *Credit Foncier* system has been established in connection with the Savings Banks, and particulars relating to the operations of the system will be found in the chapter dealing with Agriculture.

## CURRENCY.

There is no universal currency in Australia except the British sovereign, the silver and bronze current being more properly tokens than coins. The bank notes issued by the banks of issue are not legal tender in any state, and do not circulate beyond the state in which they are issued. The question of note circulation is discussed further on, but it may be here mentioned that the total note currency of the Commonwealth comprises £3,133,268 bank notes issued in the various states in the proportions shown on page 795, and £652,752 Treasury notes of Queensland, in all £3,786,020, equal to 19s. 1d. per inhabitant. The coin in circulation is a doubtful quantity; if the ratio found for New South Wales, viz., gold, £1 8s. 7d., silver, 5s. 7d., and bronze, 6d., obtains throughout the Commonwealth—the total coin circulation of Australia is gold, £5,477,800, silver, £1,070,000, and bronze, £95,800. These sums, with the note circulation, bring the total currency to £10,429,620, or £2 12s. 8d. per inhabitant. The coin and bullion held in reserve by the banks amount to £19,358,469, so that the total currency of the Commonwealth, both active and reserved, amounts to £29,788,089. Gold coins are legal tender to any amount, silver for an amount not exceeding forty shillings, and bronze for one shilling. The standard weight and fineness of each coin are given below. The least current weight of a sovereign is 122·5 Imperial grains, and of a half-sovereign, 61·125 grains :—

Denomination of Coin.		Standard Weight.	Standard Fineness.
		Imperial grains.	
		Troy.	
Gold .....	{ Sovereign .....	123·27447	{ Eleven-twelfths fine gold, one-twelfth alloy, or decimal fineness ·91666
	{ Half-sovereign .....	61·63723	
	{ Crown .....	436·36363	
Silver.....	{ Double Florin.....	349·09090	{ Thirty-seven-fortieths fine silver, three-fortieths alloy, or decimal fineness ·925.
	{ Half-crown .....	218·18181	
	{ Florin .....	174·54545	
	{ Shilling .....	87·27272	
	{ Sixpence .....	43·63636	
Bronze ...	{ Threepence .....	21·81818	{ Mixed metal :—Copper, 95 parts ; tin, 4 parts ; and zinc, 1 part.
	{ Penny .....	Avoirdupois. 145·83333	
	{ Halfpenny .....	87·50000	
	{ Farthing .....	43·75000	

The only coins struck at the Sydney, Melbourne, and Perth Mints are of gold, though silver and bronze of English coinage are also issued at Sydney and Melbourne. The amounts of silver and bronze issued during 1903 were, at the Sydney Mint, silver, £16,000, and bronze, £3,720; and

at the Melbourne Mint, £11,435 and £1,100 respectively. No silver or bronze coin had been issued at the Perth Mint up to the end of 1903. The Sydney Branch of the Royal Mint was opened on the 14th May, 1855, the Melbourne Branch on the 12th June, 1872, and a third branch was established at Perth on the 20th June, 1899. The amount of gold received for coinage up to the end of 1903, at the Sydney Mint, was 28,669,425 oz., valued at £105,767,019; the amount received at the Melbourne Mint to the same date was 26,860,024 oz., valued at £106,055,368; while at the Perth Branch the amount received was 4,335,710 oz., the value being £15,390,430.

The following table shows the quantity of gold received into the three Mints to the end of 1903, the metal received from outside sources being distinguished from that locally produced :—

Where produced.	Gold received for Coinage.		
	Sydney Mint.	Melbourne Mint.	Perth Mint.
	oz.	oz.	oz.
New South Wales .....	9,929,463	126,316	.....
Victoria .....	1,443,182	19,483,215	19
Queensland .....	13,506,996	13,060	.....
South Australia .....	86,308	646,311	41
Western Australia .....	13,428	2,727,352	4,335,211
Tasmania .....	100,365	997,756	.....
New Zealand .....	3,278,480	2,639,047	.....
Other Countries .....	50,116	215,816	418
Old Coin, etc. ....	261,087	11,151	21
Total .....	28,669,425	26,860,024	4,335,710

The total value of gold raised in Australasia to the end of 1903 was £494,092,292, of which amount 46 per cent. passed through the Sydney, Melbourne, and Perth Mints.

The following table shows the amount of gold coin and bullion issued by each Mint to the end of 1903 :—

Mint.	Sovereigns.	Half-sovereigns.	Bullion.	Total Value of Coin and Bullion issued.
	£	£	£	£
Sydney .....	99,307,500	3,025,000	3,445,657	105,778,157
Melbourne .....	97,779,120	547,362	7,716,024	106,042,506
Perth .....	14,430,319	59,683	896,797	15,386,804
Total .....	211,516,939	3,632,050	12,058,478	227,207,467

The quantity of gold received into the Sydney Mint in 1903 was 861,514 oz., valued at £3,076,616, of which only 163,675 oz., or about 19 per cent., represented the produce of New South Wales. Queensland contributed 572,979 oz., or about 66 per cent. of the whole, while of the remainder, 118,038 oz. came from New Zealand, and 6,025 oz. from Tasmania. The amount of gold received into the Melbourne Mint for the same year was 1,097,501 oz., of which 812,823 oz., or 74 per cent., was the produce of Victoria, while 51,306 oz. came from Western Australia, notwithstanding the fact that the Perth Mint was opened on the 30th June, 1899; and 166,513 oz. were the produce of New Zealand. With the exception of 270 oz. the whole of the gold coined at the Perth Mint was the produce of Western Australia.

The gold coins issued from the Sydney Mint in 1903 consisted of 2,806,000 sovereigns and 231,000 half-sovereigns, while the Melbourne Mint issued 3,521,780 sovereigns, and the Perth Mint, 4,674,783 sovereigns during the year.

The value of the gold coinage issued from Sydney, Melbourne, Perth, and London Mints during the year 1903 was as follows:—

	£
Sydney.....	2,921,500
Melbourne .....	3,521,780
Perth .....	4,674,783
London .....	10,149,655

Besides gold coin, the Sydney Mint during 1903 issued gold bullion to the value of £159,626; the Melbourne Mint to the value of £792,594; and the Perth Mint to the value of £489,552.

The great bulk of the gold coined in Australia is exported, the total sent away in 1903 amounting to £11,591,274. This export was distributed as follows:—

	£
United Kingdom.....	843,648
Cape Colony .....	1,500,000
Ceylon .....	3,397,203
Hong Kong .....	279,923
India .....	3,511,000
Natal .....	100,000
New Zealand .....	338,000
United States .....	1,500,000
Other Countries .....	121,500

The annual report of the Deputy-Master of the Royal Mint for 1903 shows the value of silver coin issued to and withdrawn from, and the value of bronze coin issued to each of the Commonwealth states and

New Zealand during the thirty-two years, 1872–1903, to have been as follows :—

State.	Silver Coin.			* Bronze Coin issued.
	Issued.	Withdrawn.	Net Issue.	
	£	£	£	£
New South Wales.....	1,044,700	212,285	832,435	55,850
Victoria .....	1,051,350	300,065	751,285	46,535
Queensland .....	270,345	4,750	265,595	3,650
South Australia.....	294,300	2,176	292,124	14,065
Western Australia .....	111,950	4,860	107,090	4,915
Tasmania.....	50,400	23,443	26,957	1,320
Commonwealth .....	2,823,045	547,559	2,275,486	126,335
New Zealand .....	357,135	.....	357,135	20,745
Australasia .....	3,180,180	547,559	2,632,621	147,080

\* From 1874.

These figures show a net annual average circulation of silver of £82,269 and of bronze of £4,596, but no allowance is made in the figures for coin brought to the states or taken away by passengers.

Complete information regarding worn coin is not available for the Melbourne Mint; the following figures, therefore, refer to Sydney only. From 1873, when the Mint first received worn silver coin, until 1903, the amount of silver withdrawn from circulation was of the nominal value of £218,859. The actual weight after melting was 701,668 oz., and the corresponding weight of new coinage would be 795,847 oz. The loss while the coins were in circulation was therefore 94,179 oz., the average loss being 11·8 per cent. From 1876 to 1903 gold coin of the nominal value of £826,918 was received at the Sydney Mint for recoinage.

As has already been pointed out, standard silver consists of ·925 pure metal and ·075 alloy. A pound troy of standard silver is coined into sixty-six shillings; that is to say, 11·1 ounces of fine metal produce coin to the value of £3 6s. The average price of silver during 1903 was 2s. 0½d. per ounce, which for 11·1 ounces gives the sum of £1 2s. 10½d.; so that, after making due allowance for Mint expenses and loss entailed by abrasion of the coinage, it is evident that the British Government derives a fairly large profit from the silver coin issued to Australasia. This explains why the Governments of New South Wales and Victoria have approached the Imperial authorities for permission to coin silver to the value required for circulation in the states. With the present limited population of Australasia, however, it is doubtful whether the profits would do more than pay for the outlay necessary in connection with the minting.

## PAPER CURRENCY.

Paper or bank-notes have long formed part of the currency of Australia, and until the discovery of gold and the establishment of the local mints, paper was the principal means of effecting exchanges. As will be seen by a subsequent table, the note circulation compared with population was formerly much greater than it is at the present time. Several causes have tended to bring about the reduction which these figures indicate. Amongst the principal causes may be mentioned first the spread of banking facilities, accompanied by an increased use of cheques for the settlement of accounts, which have had the effect of decreasing the amount of currency (coin and notes) required to be kept in circulation; and secondly, the taxing of the note issue which has had the effect of so reducing the profit to the banks, arising from their circulation, that the issue of notes is not made a feature of banking business in the large cities, although the possession of the right to issue notes is valuable in the country districts, as the necessity of maintaining gold reserves in branch banks is thereby obviated. There is also another cause operating against an increase in the circulation. In some of the states, the notes are issued by the banks again and again, so that they become eventually torn and dirty, and their use becomes repugnant to many people. This, of course, is not a complaint of recent origin; probably the bank-note is cleaner at the present time than was formerly the rule, but the ordinary condition of an Australian note compares very unfavourably with that of a Bank of England note, or of any other bank-note, which is frequently renewed.

The banks acquire their right to issue notes either under the authority of a Royal Charter, or a Special Act of Parliament, but in some states the power to issue notes is assumed by the banks, these institutions having no greater legal rights in the matter of note issue than any other company or citizen of the Commonwealth. There is a limitation of issue in most instances where the privilege is conferred by law, but the range allowed is so great, that few banks would be able, even if they were desirous, to utilise their power of note issue to its full extent. For the privilege of issuing notes, the state charge what is called a composition at the rate of 2 per cent per annum, and from this source the following revenues were received in 1903-4 :—

	£		£
New South Wales ...	28,743	Western Australia ...	7,852
Victoria ...	18,434	Tasmania ...	3,262
South Australia ...	8,055	New Zealand ...	29,005

The law does not require any special reserve to be maintained against bank-notes, but the issue is many times covered by the reserves; thus in June, 1904, the total note issue for banks, excluding the Queensland Treasury notes, amounted to £4,653,052, while the gold reserve and till money at the same period was £23,226,295. The lowest value for which notes are issued is £1, and the bulk of the issue is of this denomination.

In Queensland, the right to issue notes was taken away from the banks by Statute, and the State Government substituted in lieu of the bank-note, a Treasury note, which is issued under the following conditions:—

The State Treasurer issues to the banks, desirous of this form of currency, Treasury notes to an amount within the limit sanctioned by law. The amount of Treasury notes supplied to any bank is deemed to be a debt due to the Crown, and their face value, less the weekly average amount of notes on hand is regarded as a fixed deposit, standing in the name of the Treasurer, and bearing interest at the rate of 4 per cent. per annum. Such deposit may be withdrawn by the Treasurer, so far as 25 per cent. thereof is concerned, on demand, and the balance in equal proportions, at the expiration of 3, 6, and 9 months from the date of first demand; on the other hand, any bank may, on the same conditions, repay its deposits, and cancel its debt to the Treasury. It is provided that the amount of notes issued to any bank shall not exceed its most recently ascertained average circulation at the time of the passing of the Treasury Notes Act, but 50 per cent. additional is allowed to the bank for stock. Under the authority of this act, the Queensland Government has issued to the banks trading in their state, Treasury notes to the value of £700,000. This is considerably less than the amount of circulation which the banks maintained prior to the crisis of 1893, which was responsible for the passing of the Treasury Notes Act.

Including Queensland, the following is a statement of the average issue of bank-notes in each state at various intervals from 1880 onwards:—

Year.	New South Wales.	Victoria.	*Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.
	£	£	£	£	£	£	£
1880	1,260,772	1,236,046	338,684	506,887	†.....	122,442	£3,464,831
1885	1,793,686	1,474,089	661,163	522,556	†.....	153,622	£4,605,121
1890	1,557,805	1,543,340	633,897	480,425	58,939	161,680	4,486,086
1891	1,673,425	1,408,320	636,846	459,082	90,521	149,075	4,417,269
1892	1,439,871	1,210,565	575,435	400,156	101,433	110,680	3,838,140
1893	1,804,531	1,121,675	458,236	350,771	80,611	96,238	3,912,062
1894	1,235,989	1,067,846	410,635	349,359	177,785	87,950	3,329,564
1895	1,223,864	960,300	428,945	402,596	232,569	95,968	3,304,262
1896	1,237,971	979,460	528,802	399,787	460,328	105,909	3,712,317
1897	1,227,964	956,665	513,750	380,803	379,216	106,007	3,565,005
1898	1,278,940	904,303	509,585	347,201	321,026	121,432	3,482,487
1899	1,340,557	951,794	398,591	397,616	364,243	148,319	3,601,120
1900	1,447,600	963,447	495,328	391,689	376,772	144,948	3,819,784
1901	1,499,936	947,597	658,462	394,602	411,206	152,831	4,064,636
1902	1,454,416	940,082	654,264	361,372	408,548	161,418	3,960,097
1903	1,378,643	913,590	620,060	380,115	397,963	154,595	3,944,866

\* Includes Treasury notes from 1893. † No information available. ‡ Exclusive of Western Australia.



Allowing about £45,000 for Western Australia, it will be seen that while the note circulation in 1885 was £4,650,000, in 1903 it was £3,844,866, or some £800,000 less, notwithstanding an increase of population of 75·85 per cent. The circulation per head, which is largest in Western Australia and least in Victoria, is affected greatly by the development of business, and by local and other considerations. In states where the number of wage-earners, especially of adult males, is large in proportion to the population, there is a tendency for increased circulation; under opposite conditions the reverse is the case. It is, however, impossible to generalise safely upon this question, which involves a consideration of the habits of the people, the gain which banks consider they may obtain from their note circulation, and the popular belief in the notes themselves.

The figures in the foregoing table should be read in connection with those now given, showing the circulation per inhabitant at different periods. Taking the Commonwealth as a whole, the note circulation is now only 57 per cent. of what it was in 1885. From 1885 onwards there was a gradual decline in the proportion of notes required per inhabitant, until in 1892 and 1893 the circulation was £1 3s. 5d., compared with £1 14s. 11d. in 1885; in 1893 the bank crisis occurred, and the following year saw a reduction of about four shillings per inhabitant, and at about that level (19s. 6d.) the circulation has since remained.

Year.	New South Wales.	Victoria.	* Queens-land.	South Australia.	Western Australia.	Tasmania.	Common-wealth.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
1880	1 14 7	1 9 1	1 10 6	1 18 6	† .....	1 1 7	† 1 11 10.
1885	1 18 8	1 10 10	2 1 10	1 14 1	† .....	1 4 0	† 1 14 11
1890	1 8 3	1 7 7	1 15 2	1 10 6	1 6 2	1 2 6	1 8 10
1895	0 19 7	0 16 3	0 18 11	1 3 4	3 2 8	0 12 5	0 19 6
1900	1 1 4	0 16 2	0 19 7	1 2 0	2 2 7	0 16 9	1 0 4
1903	0 19 4	0 15 1	1 4 2	1 0 9	1 16 0	0 17 5	0 19 8.

\* Includes Treasury notes from 1893. † No information available. ‡ Exclusive of Western Australia.

The question as to the amount of notes which could be issued and maintained in circulation, where the tax on notes would admit of sufficient margin of profit to make it worth while for the banks to encourage the issue of notes, has been considerably debated, but it may be safely asserted that under conditions such as have been alluded to, the Australian note circulation would certainly be equal per inhabitant to that of New Zealand, and if the notes were guaranteed by the Commonwealth and made legal tender, their probable issue might be set down at £6,750,000.

The circulation of New Zealand during the past four years has ranged between £1 15s. and £1 16s. per inhabitant, having been as low as £1 5s. 4d., in 1895. The note issue of the colony is an excellent

measure of its progress, which may be said to have been continuous for the past ten years. The bank crisis of 1893 did not affect New Zealand, and the low circulation about that year was due to other and local causes. As the progress of the note circulation of the colony presents some very interesting features the figures are given for each year from 1880 onwards :—

Year.	Total Note Circulation.	Per Inhabitant.
	£	£ s. d.
1880	918,297	1 18 9
1885	968,481	1 14 2
1890	837,230	1 8 7
1891	946,046	1 10 0
1892	955,623	1 9 9
1893	940,418	1 8 5
1894	893,715	1 7 0
1895	861,717	1 5 4
1896	971,046	1 8 0
1897	1,015,040	1 8 9
1898	1,074,143	1 9 9
1899	1,195,562	1 12 5
1900	1,317,706	1 15 2
1901	1,354,206	1 15 6
1902	1,399,044	1 16 0
1903	1,466,279	1 15 9

#### LIFE ASSURANCE.

All the states save New South Wales have special laws regulating the business of life assurance. Except in the case of Queensland, the Life Assurance Acts require yearly statements to be made showing the total business of companies in operation, and also certain particulars regarding the transactions within their own state, and the Western Australian Act also enforces particulars of the business in each of the other states. In New South Wales no special law has been passed, and companies doing this class of business are either registered under the Companies or Friendly Societies Act, or incorporated by special Act. In the other states the Acts regulating the business of life assurance deal chiefly with deposits to be made by companies commencing business, and with returns of business transacted. In no province are the full returns officially published; nevertheless, interesting and valuable reports are prepared and circulated by several of the companies, and all information reasonably to be desired is given in their pages. Other companies pursue a different course, and disclose very few particulars of their business. However, from such sources as are available, the information contained in the following pages has been compiled.

Of the twenty-two companies doing ordinary and industrial business in the states, eight have their head-offices in New South Wales, six in

Victoria, one in South Australia, two in New Zealand, one in the United Kingdom, three in the United States, and one in Canada. Some of the British companies have agencies in the states, principally for the collection of renewal premiums on policies effected in the United Kingdom, but as particulars of the business in the states are not available, these companies have also been excluded. The Mutual Assurance Society of Victoria was amalgamated with the National Mutual Life Association at the beginning of 1897, and consequently the figures in the tables show the transactions of the new company.

The results of the latest published actuarial investigations of the various societies are appended :—

Institution.	Year of Foundation.	Basis of Valuation.	Date of last Valuation.	Net or Present Liability.	Total Assets.
		per cent.		£	£
Australian Mutual Provident Society .....	1849	3½ & 3 (a)	31 Dec., 1903	19,008,640	20,140,925
Mutual Life Association of Australasia .....	1889	4 (q)	31 „ 1899	1,234,900	1,372,331
City Mutual Life Assurance Society (Ltd.) ..	1879	4 (t)	31 „ 1903	247,876	254,751
*Citizens' Life Assurance Company (Ltd.) ..	1896	3 (a)	31 „ 1903	729,940	778,584
Standard Life Association (Ltd.) .....	1899	5.. (q)	5 .....	5 .....	26,150
Australian Metropolitan Life Assurance Company (Ltd.) .....	1896	3½ (q)	31 Aug., 1902	*5,826	**38,584
Australian Alliance Assurance Company .....	1862	3½ (t)	31 Dec., 1903	230,567	†235,966
National Mutual Life Association of Australasia (Ltd.) .....	1869	3½ (t)	30 Sept., 1901	3,063,319	3,399,231
Australian Widows' Fund Life Assurance Society (Ltd.) .....	1871	3½ (q)	31 Oct., 1901	1,418,509	1,527,566
Colonial Mutual Life Assurance Society (Ltd.)	1874	3½, 4 (q)	31 Dec., 1899	2,071,579	2,391,882
Australasian Temperance and General Mutual Life Assurance Society (Ltd.) .....	1876	3½ (q)	30 Sept., 1900	*233,142	**260,751
People's Prudential Assurance Company (Ltd.)	1896	3½ (q)	31 Aug., 1904	**6,288	††12,611
Phoenix Mutual Provident Society (Ltd.) ....	1902				
Victoria Life and General Insurance Company	1858	3 (d)	30 June, 1900	123,951	364,018
Adelaide Life Assurance and Guarantee Company .....	1866	4 (q)	30 June, 1892	18,322	22,124
New Zealand Government Life Insurance Department .....	1870	3½ (t)	31 Dec., 1902	3,214,409	3,474,184
†Provident Life Assurance Company .....	1889	4 (q)	30 June, 1899	7,211	13,375
Liverpool, London, and Globe Insurance Company .....	1836	3 (q)	31 Dec., 1898	4,891,268	†† 10,376,924
Independent Order of Foresters .....	1877	4 (q)	31 „ 1897	7,159,342	
Equitable Life Assurance Society of the United States .....	1859	3, 3½, 4 (a)	31 „ 1903	63,238,225	78,341,950
New York Life Insurance Company .....	1845	3, 4 (a)	31 „ 1903	62,789,909	72,469,996
Mutual Life Insurance Company of New York	1843	3, 4 (a)	31 „ 1903	69,834,411	82,881,230

(a) Annual. (t) Triennial. (q) Quinquennial. (d) Decennial.

\* Ordinary branch only. † Industrial and Medical Benefit business only. ‡ Exclusive of

Fire, Marine, and Guarantee branches. § The first investigation will be made in June, 1904.

|| Information not available. \*\* Includes Industrial branch.

†† Includes Industrial and Medical Benefit branches. ‡‡ Includes Fire branch.

The net or present liability represents the present value of the sums assured in respect of whole life and endowment assurance, reversionary bonuses, endowments, and annuities in force at date of valuation, less the present value of the future pure premiums thereon.

Of the twenty-two companies, twelve are mutual, and the remainder are what is termed in insurance parlance "mixed"—that is, proprietary

companies dividing profits with the policy-holders. Six of the institutions also transact industrial business, while one company also undertakes fire, marine, and guarantee risks, and another does guarantee as well as life business. Most of the offices have representatives in all the states. Three institutions have extended their operations to London, and two also to South Africa. The New Zealand Government institution does not transact any business outside that colony.

The following table gives the policies in force and the sums assured in each society at the latest date available. The item "Sums assured" represents the sums payable, exclusive of reversionary bonuses, at death, or on attaining a certain age, or at death before that age:—

Institution.	Policies in force, exclusive of Annuities.	Assurances.			Annual Premium Income.
		Sums Assured, exclusive of Bonuses.	Bonus Additions.	Total.	
	No.	£	£	£	£
Australian Mutual Provident Society .....	182,810	52,394,839	10,458,563	62,753,392	1,715,067
Mutual Life Association of Australasia .....	23,609	6,053,835	365,309	6,419,044	313,672
City Mutual Life Assurance Society (Ltd.) ..	10,977	1,890,537	46,535	1,937,072	64,424
Citizens' Life Assurance Company (Ltd.)....	36,592	4,997,746	183,941	5,181,687	296,296
Standard Life Association (Ltd.) .....	1,916	196,667	¶	196,667	5,399
Australian Metropolitan Life Assurance Company (Ltd.) .....	1,015	92,242	855	93,097	4,271
Australian Alliance Assurance Company .....	993	352,224	32,265	384,589	10,655
National Mutual Life Association of Australasia (Ltd.) .....	57,295	13,472,150	973,080	14,445,230	442,991
Australian Widows' Fund Life Assurance Society (Ltd.) .....	24,082	5,020,521	277,670	5,298,191	184,781
Colonial Mutual Life Assurance Society (Ltd.)	35,395	10,705,748	267,660	10,973,408	340,232
Australasian Temperance and General Mutual Life Assurance Society (Ltd.) .....	12,356	1,635,774	¶	1,635,774	89,894
People's Prudential Assurance Company (Ltd.)	572	* 35,424	....	35,424	1,120
Phoenix Mutual Provident Society (Ltd.) ....	445	12,427	....	12,427	1,412
New Zealand Government Life Insurance Department .....	42,806	10,069,262	1,051,645	11,111,807	305,479
†Provident Life Assurance Company .....	....	....	....	....	....
‡Liverpool, London, and Globe Insurance Company .....	904	273,558	¶	273,558	9,981
‡Independent Order of Foresters .....	2,671	406,100	....	406,100	7,610
‡Equitable Life Assurance Society of the United States .....	15,091	*5,227,496	....	5,227,496	262,839
‡Mutual Life Insurance Company of New York	4,989	2,178,376	¶	2,178,376	83,405
‡New York Life Insurance Company .....	7,083	2,710,564	¶	2,710,564	117,949

\* Includes bonus additions.

† This Company transacts industrial business only.

‡ Australasian business only.

¶ Not available.

# ACCUMULATION.

817

The following table shows the assurances in force at the close of each of the last three years :—

Institution.	Amount Assured, excluding Bonuses and Annuities.		
	1901.	1902.	1903.
	£	£	£
Australian Mutual Provident Society .....	49,308,585	50,763,589	52,324,329
Mutual Life Association of Australasia .....	5,501,585	5,816,259	6,053,335
City Mutual Life Assurance Society (Ltd.) .....	1,385,716	1,389,508	1,390,537
†Citizens' Life Assurance Company (Ltd.) .....	4,173,655	4,608,190	4,997,746
‡Standard Life Association (Ltd.) .....	156,817	159,327	198,067
‡Australian Metropolitan Life Assurance Company (Ltd.) .....	75,458	77,907	92,242
Australian Alliance Assurance Company .....	309,271	371,341	352,234
National Mutual Life Association of Australasia (Ltd.) .....	11,338,347	11,338,347	13,472,150
Australian Widows' Fund Life Assurance Society (Ltd.) .....	5,025,229	5,025,229	5,020,521
Colonial Mutual Life Assurance Society (Ltd.) .....	10,420,684	10,420,684	10,706,748
‡Australasian Temperance and General Mutual Life Assurance Society (Ltd.) .....	1,407,379	1,512,740	1,635,774
People's Prudential Assurance Company (Ltd.) .....	*	12,400	.....
Phoenix Mutual Provident Society (Ltd.) .....	*	*	12,427
New Zealand Government Life Insurance Department .....	9,742,102	9,896,572	10,060,292
‡Provident and Life Assurance Company .....	*	.....	.....
Liverpool, London, and Globe Insurance Company .....	*	373,558	373,558
Independent Order of Foresters .....	*	344,800	406,100
‡Equitable Life Assurance Society of the United States .....	4,729,161	5,305,491	5,327,495
‡Mutual Life Insurance Company of New York .....	1,800,500	2,017,141	2,173,376
‡New York Life Insurance Company .....	2,380,404	2,472,484	2,710,564

\* Information not available. † Australasian business only, but inclusive of bonus additions except for the Mutual Life of New York and the New York Life Company in 1901, 1902, and 1903, for which the information relating to bonuses is not available. ‡ Ordinary branch only. § June, 1902.

‡ This Company transacts Industrial business only.

The receipts of the societies are chiefly represented by the collections from premiums on policies and the interest arising from investments of the accumulated funds; while payments on account of claims, surrenders, cash bonuses, and expenses of management chiefly comprise the disbursements. The receipts and disbursements during 1903 of each society having its head office in Australasia were as follow :—

Institution.	Receipts.	Expenditure.	Excess Receipts (Addition to Funds).
	£	£	£
Australian Mutual Provident Society .....	2,598,809	1,703,499	895,310
Mutual Life Association of Australasia .....	322,329	192,069	129,060
City Mutual Life Assurance Society (Ltd.) .....	66,869	50,553	16,316
*Citizens' Life Assurance Company (Ltd.) .....	217,061	69,238	147,823
‡Standard Life Association (Ltd.) .....	44,140	40,438	3,652
‡Australian Metropolitan Life Assurance Company (Ltd.) .....	17,240	16,290	990
Australian Alliance Assurance Company .....	19,732	31,943	†12,161
National Mutual Life Association of Australasia (Ltd.) .....	630,071	416,106	213,965
Australian Widows' Fund Life Assurance Society (Ltd.) .....	251,785	189,313	61,972
Colonial Mutual Life Assurance Society (Ltd.) .....	433,825	330,369	107,966
*Australasian Temperance and General Mutual Life Assurance Society (Ltd.) .....	73,983	47,849	26,134
Victoria Life and General Insurance Company .....	11,976	31,201	†19,225
People's Prudential Assurance Company (Ltd.) .....	12,685	11,191	1,494
Phoenix Mutual Provident Society (Ltd.) .....	1,609	1,843	†239
Adelaide Life Assurance and Guarantee Company .....	2,045	3,369	†1,324
New Zealand Government Life Insurance Department .....	463,360	394,135	129,244
‡Provident and Life Assurance Company .....	13,473	12,010	1,463
Total .....	£ 5,196,032	£ 3,453,532	1,702,530

\* Ordinary branch only.

† Decrease.

‡ Includes Industrial Branch.

The aggregate receipts and disbursements of the seventeen Australasian institutions during 1903 were as follow :—

Receipts.		Expenditure.	
	£		£
Premiums—		Claims .....	1,991,872
New .....	378,421	Surrenders .....	548,254
Renewals .....	3,185,744	Annuities .....	74,222
Consideration for Annuities .....	89,796	Cash Bonuses and Dividends .....	96,787
Interest .....	1,521,589	Expenses .....	724,634
Other Receipts (Rents, etc.) .....	10,512	Amount written off to Depreciation, Reserves, etc. ....	45,778
Total .....	£ 5,186,062	Total .....	£ 3,485,532

The basis of the valuation of the various companies operating in Australia and New Zealand has been shown on a previous page. It will be seen that the assumed rate of interest is either  $3\frac{1}{2}$  or 4 per cent., while the actual rate earned on the average amount of funds for last year was 4·82 per cent., so that there is still a good margin above valuation rates. The question of the earnings of investments is one of great concern both to insurers and insured, and the following table covering the last sixteen years, will show the downward tendency of interest during that period :—

Year.	Average rate of interest realised on mean funds.
	Per cent.
1888 .....	5·91
1889 .....	5·85
1890 .....	5·81
1891 .....	5·86
1892 .....	5·80
1893 .....	5·66
1894 .....	5·44
1895 .....	5·35
1896 .....	5·15
1897 .....	4·77
1898 .....	4·73
1899 .....	4·58
1900 .....	4·47
1901 .....	4·46
1902 .....	4·45
1903 .....	4·82

ASSETS AND LIABILITIES OF ASSURANCE COMPANIES.

The societies publish annually a statement of assets and liabilities, with the object of showing the distribution of the accumulated funds and the amount placed to commercial reserve. The return is, however, in no way connected with the valuation balance-sheet prepared at the date of the actuarial investigation. The assets and liabilities for each institution, for the financial year of 1903, were as shown in the subjoined table :—

Institution.	Assets.			Liabilities.		
	Loans on Mortgages and Policies.	Government and Municipal Securities, Freehold Property, Cash on Deposit, etc., etc.	Total.	Insurance Endowment and Annuity Funds.	Paid-up Capital, Reserve Funds, etc., etc.	Total.
	£	£	£	£	£	£
Australian Mutual Provident Society .....	13,541,207	6,509,658	20,140,925	19,670,303	470,622	20,140,925
Mutual Life Association of Australasia .....	1,054,500	728,173	1,782,673	1,768,599	14,074	1,782,673
City Mutual Life Assurance Society (Ltd.) .....	132,172	122,579	254,751	254,718	33	254,751
*Citizens' Life Assurance Company (Ltd.) .....	381,421	397,168	778,584	774,578	4,006	778,584
†Standard Life Association (Ltd.) .....	1,009	29,921	30,990	16,180	14,810	30,990
‡Australian Metropolitan Life Assurance Company (Ltd.) .....	1,894	87,089	38,913	15,764	23,149	38,913
†Australian Alliance Assurance Company .....	237,226	231,134	468,360	225,127	243,233	468,360
National Mutual Life Association of Australasia (Ltd.) .....	2,463,369	1,356,543	3,819,882	3,674,436	145,446	3,819,882
Australian Widows' Fund Life Assurance Society (Ltd.) .....	1,193,168	462,401	1,655,809	1,639,726	16,143	1,655,809
Colonial Mutual Life Assurance Society (Ltd.) .....	1,404,274	1,418,388	2,822,662	2,735,082	87,580	2,822,662
‡Australasian Temperance and General Mutual Life Assurance Society (Ltd.) .....	154,307	213,789	368,046	359,646	8,400	368,046
Victoria Life and General Insurance Company .....	121,378	164,016	295,394	209,000	86,394	295,394
People's Prudential Assurance Company (Ltd.) .....	6,887	4,270	11,157	6,325	4,832	11,157
Phoenix Mutual Provident Society (Ltd.) .....	.....	765	765	469	296	765
‡Adelaide Life Assurance and Guarantee Company .....	3,881	22,094	25,975	9,550	16,425	25,975
New Zealand Government Life Insurance Department .....	2,504,764	1,105,535	3,610,299	3,512,061	98,238	3,610,299
Provident and Life Assurance Company .....	.....	29,159	29,159	7,725	21,434	29,159
Total .....	£ 23,211,777	12,922,627	36,134,404	34,879,284	1,256,120	36,134,404

\* Ordinary branch only. † Inclusive of Fire, Marine, and Guarantee Branches, which cannot be separated. ‡ Inclusive of the Industrial Branch. ¶ Inclusive of Guarantee Branch.

Loans on mortgages and policies represent about two-thirds of the total assets, and in former years the investment of funds was almost exclusively confined to these securities; but lately the operations in Government stocks, municipal loans, and other securities and shares have greatly increased. The remaining items require no special comment, except loans on personal security, combined with life assurance. Investments of this character are unusual in Australasia, and are decreasing each year, the amount invested aggregating only £44,639. In some of the states the companies are obliged by law to deposit certain sums with the Treasury as a guarantee of good faith, and the amount so lodged is included either under the head of Government securities or of deposits.

#### EXPENSES OF MANAGEMENT OF ASSURANCE COMPANIES.

The ratio of expenses of management to premium income and gross receipts must necessarily vary according to the age of the society and the proportion of new business transacted. The figures are given for what they are worth. That a more exact comparison cannot be made is the fault of certain companies which fail to make a complete disclosure of their affairs, and do not distribute their expenses of management so that the cost of new business may be distinguished from that of old business; the reports of other companies are unequalled in any part of the world:—

Institution.	Expenses of Management.		
	Amount.	Proportion to—	
		Premium Income.	Gross Receipts.
	£	per cent.	per cent.
Australian Mutual Provident Society .....	234,640	13.58	9.08
Mutual Life Association of Australasia .....	58,267	23.48	18.08
City Mutual Life Assurance Society (Ltd.) .....	14,142	28.08	21.15
*Officers' Life Assurance Company (Ltd.) .....	29,786	15.86	13.71
†Standard Life Association (Ltd.) .....	26,562	61.28	60.18
‡Australian Metropolitan Life Assurance Company (Ltd.) .....	18,298	88.44	77.08
§Australian Alliance Assurance Company .....	2,508	24.03	12.73
National Mutual Life Association of Australasia (Ltd.) .....	111,404	24.81	17.09
Australian Widows' Fund Life Assurance Society (Ltd.) .....	46,738	26.91	18.44
Colonial Mutual Life Assurance Society (Ltd.) .....	86,963	26.44	19.61
*Australasian Temperance and General Mutual Life Assurance Society (Ltd.) .....	19,586	32.22	26.47
Victoria Life and General Insurance Company .....	1,425	41.90	11.90
People's Prudential Assurance Company (Ltd.) .....	6,456	52.43	50.09
Phoenix Mutual Provident Society (Ltd.) .....	877	63.23	60.72
†Adelaide Life Assurance and Guarantee Company .....	.....	.....	.....
New Zealand Government Life Insurance Department .....	64,410	20.71	13.90
Provident and Life Assurance Company .....	7,232	56.85	58.90

\* Ordinary Branch only.

† Included in expenses of Guarantee Branch, not shown separately.

‡ Includes Industrial Branch.

§ Life branch only.



## ASSURANCE IN VARIOUS COUNTRIES.

The average amount assured per policy for each state, and for the United Kingdom, Canada, and the United States, is given in the following table. The figures in certain instances are probably somewhat overstated, as all the companies do not show complete returns of the business in each state; but the results may be taken as a fair estimate for each province. The Australasian business of the American institutions excluded from the previous returns, has been included for the purpose of establishing the Australian averages, but the industrial business has been excluded in each case, and the Canadian figures are also exclusive of the assessment companies' business:—

Country.	Average Sum assured per Policy.	Average Premium per £100 of Assurance.
	£	£ . d.
Australasia .....	256	3 7 7
New South Wales .....	285	3 5 1
Victoria .....	237	3 7 5
Queensland .....	280	3 2 8
South Australia .....	232	3 8 10
Western Australia .....	304	3 3 4
Tasmania .....	261	3 7 5
New Zealand.....	257	3 4 4
United Kingdom .....	313	.....
United States... ..	430	.....
Canada .....	325	.....

The average amount of assurance per head of population was, in Australasia, £25; in Canada, £19; in the United Kingdom, £16; and in the United States £22; while the average number of policies per thousand of population was, in Australasia, 97; in Canada, 59; in the United Kingdom, 51; and in the United States, 52.

The average policy is scarcely a fair measure of thrift. In these states mutual assurance is the rule, and members of the various societies have acquired large bonus additions. The average existing policy, including reversionary bonus, of the Australasian companies, on the 31st December, 1903, was £285, as compared with the £256 shown in the comparative table.

It would seem that the practice of assuring life is much more prevalent in Australasia than in any of the other countries instanced; and although the average sum assured by each policy is less, the number of policies is so much greater, as compared with the population, that the amount assured per inhabitant is considerably higher.

## INDUSTRIAL ASSURANCE.

In addition to the ordinary life transactions mentioned in the foregoing tables, a large industrial business has grown up during the past few years. The policies in this class are usually for small amounts, and the premiums are, in most cases, payable weekly or monthly. The assurances may be effected on the lives of infants and adults, and the introduction of this class of business has proved of great benefit to the industrial population.

As already mentioned there are four of the Australasian companies previously dealt with which combine industrial with ordinary business, while two limit their operations to industrial and medical benefit transactions. The balance-sheets of these companies, however, do not show sufficient information to admit of making a satisfactory comparison of the business transacted, as, in some cases, the two branches are not treated separately. At the close of 1903, the business in force of the six companies showing transactions in the industrial branch, was as follows:—

Company.	Date.	No. of Policies.	Sum Assured.	Annual Premiums.
			£	£
Citizens' Life Assurance Company, Ltd.	Dec., 1903 .....	195,402	4,097,564	179,505
Australasian Temperance and General Mutual Life Assurance Society, Ltd.	Sept., 1903 ...	62,073	1,151,571	71,331
Standard Life Association, Ltd. ...	*Dec., 1902 ...	21,698	395,123	29,101
Australian Metropolitan Life Assurance Company, Ltd.	August, 1903...	10,319	481,580	15,411
People's Prudential Assurance Company, Ltd.	August, 1904...	6,315	105,797	6,019
Provident and Life Assurance Company.	June, 1903.....	12,315	375,419	16,067
Total .....	.....	308,322	6,607,054	317,434

\* Latest Available.

It will thus be seen that the average amount per policy for these companies was about £21 8s. 0d., while the average premium per policy amounted to £1 0s. 7d. per annum, or about 4½d. per week.

The receipts and disbursements of the companies publishing the information are given below, the dates to which the figures relate being also shown :—

Company.	Date.	Receipts.			Disbursements.			
		Premiums.	Other.	Total.	Claims, Surrenders, and Cash Dividends.	Expenses of Management, Commission on New Business, &c.	Other.	Total.
Citizens' Life Assurance Company, Ltd.	Dec., 1903..	£ 177,715	£ 14,776	£ 192,491	£ 55,543	£ 101,289	£ 571	£ 157,408
Australasian Temperance and General Mutual Life Assurance Society, Ltd.	Sep., 1903..	67,891	1,856	69,547	8,925	46,230	..	55,156
People's Prudential Assurance Company, Ltd.	† Aug., 1903..	12,313	871	12,684	1,225	9,966	..	11,191
Provident and Life Assurance Company	June, 1903..	13,048	425	13,473	3,988	7,222	800	12,010
Total .....	.....	270,767	17,428	288,195	69,681	104,707	1,371	235,759

\* Includes payments to medical practitioners and chemists.

† Not separated in 1904.

The figures quoted show that about 94 per cent. of the total receipts consists of premiums, the other sources of revenue being interest, rent, fines, &c. With regard to the disbursements it will be noticed that a large amount was paid for expenses of management, commission, etc., the proportions under this head being :—

	Percentage of Total Income.	Percentage of Premium Income.
Citizens' Life Assurance Co., Ltd.....	52·6	57·0
Australasian Temperance and General Mutual Life Assurance Society, Ltd.....	66·5	63·3
People's Prudential Assurance Co., Ltd. ....	78·6	80·9
Provident and Life Assurance Co. ....	53·6	55·3

The expenses of all societies transacting this class of business are invariably high, as a large staff of collectors and agents have to be employed, who are required to call at the homes of the assured for payments, but it may be said generally that the above ratios compare not unfavourably with those of old-established societies in the United Kingdom and the United States of America.

A distinctive feature of the liabilities of five of the companies (the Australasian Temperance and General is purely mutual) is the amount of share capital employed, and the profits generally provide for the payment of dividends to shareholders, the policy-holders, as a rule, not being entitled to participate. A complete table of assets and liabilities

cannot be given, but the paid-up capital at the latest available date was as follows :—

	£
Citizens' Life Assurance Company, Ltd.....	20,000
Standard Life Association, Ltd.....	12,500
Australian Metropolitan Life Assurance Co., Ltd. ....	9,227
People's Prudential Assurance Company, Ltd. ....	4,721
Provident and Life Assurance Co. ....	19,000

#### FRIENDLY SOCIETIES.

The services which friendly societies directly render to the state in enabling the labouring classes to combine for the making of due provision to meet unforeseen demands in the case of sickness or death, are clearly recognised by the Governments of the various states, and all such societies which are registered according to law are granted certain privileges in consideration of the important part which they play in the social welfare of the community, in relieving the public purse of claims which would otherwise have to be preferred against it, and in maintaining the independence of their members and obviating the necessity of those members accepting aid which would have a tendency to pauperise them. The Acts regulating the operations of friendly societies in the states are all based on English legislation; and, generally speaking, the following privileges, which are granted to members of such societies in the state of New South Wales, may be taken as typical of those enjoyed in Australasia :—

1. A registered Society can legally hold land and other kinds of property in the names of trustees, such property passing from one trustee to another by the mere fact of appointment; and can carry on all legal proceedings in the trustees' names.
2. The Society has a remedy on summary conviction whenever any person—
  - (a) Obtains possession of its property by false representation or imposition;
  - (b) Having possession of any of its property, withholds or misapplies it;
  - (c) Wilfully applies any part of such property to purposes other than those expressed or directed by the rules and authorised by the Act.
3. If an officer of the Society dies or becomes bankrupt or insolvent, or if an execution is issued against him whilst he has money or property of the Society in his possession by virtue of his office, the trustees of the Society are entitled to claim such money or property in preference to any other creditors.
4. The documents of the Society are free from stamp duty.

5. The Society can admit members under twenty-one and take from them binding receipts, which would otherwise be of no effect.
6. If it invests money on mortgage, such mortgages can be discharged by a mere endorsed receipt without reconveyance.
7. Its officers are legally bound to render account and give up all money or property in their possession on demand or notice, and may be compelled to do so.
8. Disputes can be legally settled according to the Society's own rules.
9. Members of registered Friendly Societies have the privilege of legally insuring money, on the deaths of their wives and children, for their funeral expenses, without having an insurable interest in their lives.
10. Members of registered Societies may dispose at death of sums payable by the Society by written nomination without a will; and this nomination may be made by youths of sixteen who cannot make a will till they are twenty-one.
11. Where there is no will and no nomination, the trustees may distribute sums without letters of administration being taken out (a person doing so in any other case would make himself liable for the debts of the deceased).

The Acts contain provisions inserted with the object of securing the solvency of the societies. In most of the states these provisions have been operative; but in others the position of some of the orders is not so satisfactory as it should be.

In the following table will be found the number of societies, the number of lodges or branches of these societies, the aggregate number of members, the total amount of their funds, and the average amount per member in each of the states. The figures are for the latest available periods, the dates being set forth below :—

State.	Date.	Societies.	Lodges or Branches.	Members.	Total Funds.	Average Amount of Funds per member.
		No.	No.	No.	£	£ s. d.
New South Wales .....	31 Dec., 1902	64	969	96,671	802,602	8 6 1
Victoria .....	31 Dec., 1902	28	1,146	102,364	1,364,290	13 6 7
Queensland .....	31 Dec., 1903	17	280	31,913	314,711	9 17 4
South Australia .....	31 Dec., 1900	16	474	43,043	535,198	12 8 8
Western Australia .....	31 Dec., 1902	*15	169	†11,746	59,209	5 0 10
Tasmania .....	31 Dec., 1901	18	159	14,716	114,305	7 15 4
Commonwealth .....		153	3,317	300,453	3,190,322	10 12 4
New Zealand .....	31 Dec., 1902	12	462	42,408	846,314	19 9 11
Australasia .....		170	3,779	342,861	4,036,636	11 14 9

\* Exclusive of 11 specially authorised societies.

† Exclusive of honorary members.

It will be seen from the foregoing table that, taking the average amount of funds per member as the basis of comparison, New Zealand occupies first position with the sum of £19 9s. 11d. ; Victoria comes next with £13 6s. 7d. ; South Australia takes third place with £12 8s. 8d. ; Queensland comes next with £9 17s. 4d. ; and then follow New South Wales and Tasmania in the order named, with £8 6s. 1d. and £7 15s. 4d. respectively; Western Australia having the smallest amount, viz., £5 0s. 10d., to the credit of each individual member.

### MONEY ORDERS.

The business transacted in the various Postal Departments under the system of money orders has grown to very large dimensions. This increase is due mainly to the greater facilities now afforded for the transmission of money by this method, though it is also to some extent attributable to the more general appreciation of the system by the working classes. The following is a statement of the business transacted during 1903 :—

State.	Orders issued.		Orders paid.	
	Number.	Amount.	Number.	Amount.
		£		£
New South Wales.....	541,392	1,772,186	553,283	1,835,295
Victoria .....	215,694	721,017	318,766	1,121,807
Queensland .....	137,048	501,375	115,927	431,091
South Australia .....	71,933	251,655	82,930	310,058
Western Australia .....	197,407	839,073	100,155	451,774
Tasmania .....	97,187	260,705	73,379	191,949
Commonwealth.....	1,260,661	4,346,011	1,244,440	4,341,974
New Zealand.....	396,312	1,416,225	304,106	1,224,843
Australasia.....	1,656,973	5,762,236	1,548,546	5,566,817

The average amount of each money order issued was £3 9s. 6d., and the business done by New South Wales greatly exceeded that of any other state. The average value of money orders issued in the United Kingdom during 1903 was £3 2s. 6d.

## POSTAL NOTES.

Besides the money orders mentioned above, a system of postal notes is in force in all the states. The notes are issued for fixed amounts, varying from 1s. to 20s. The number and value of notes issued and paid during 1903 in each of the states were as follows :—

State.	Notes issued.		Notes paid.	
	Number.	Amount.	Number.	Amount.
		£		£
New South Wales.....	1,571,612	581,604	1,566,508	580,774
Victoria .....	1,475,853	558,976	1,552,775	591,805
Queensland .....	346,375	130,651	298,688	113,434
South Australia .....	320,740	113,076	322,341	118,003
Western Australia ...	186,263	90,939	186,238	90,078
Tasmania .....	121,653	41,930	54,894	22,989
Commonwealth...	4,022,496	1,517,176	3,981,444	1,517,063
New Zealand.....	707,044	220,070	704,031	219,312
Australasia.....	4,729,540	1,737,246	4,685,475	1,736,395

These figures show that, for the transmission of small amounts, postal notes are rapidly superseding money orders. While in 1903 the number of money orders issued was less than half that of postal notes, the value of the latter was only slightly over one-fourth of the value of money orders, the average value of postal notes being 7s. 4d. as compared with £3 9s. 6d. for money orders.

The number of postal notes issued does not by any means represent the number of transactions involving the use of these notes, as an order for a sum in postal notes cannot always be satisfied except by issuing two or more notes, whereas a money order can be issued for any sum.

The progress of money order and postal note business may be traced from the following statement of the value of orders and notes issued since 1890, when the West Australian business was first ascertained :—

Year.	Value of Money Orders.		Value of Postal Notes.	
	Commonwealth.	New Zealand.	Commonwealth.	New Zealand.
	£	£	£	£
1890	2,807,936	602,077	212,913	69,722
1891	3,245,583	651,990	250,408	79,326
1892	3,399,141	694,847	307,034	87,857
1893	3,291,369	750,929	407,181	101,002
1894	2,944,620	776,783	628,503	112,306
1895	3,038,399	812,605	797,456	123,369
1896	3,675,665	902,160	872,646	129,012
1897	3,911,740	970,831	969,326	134,378
1898	3,899,354	1,029,241	1,076,299	139,957
1899	3,805,285	1,118,908	1,147,589	147,696
1900	4,000,700	1,214,853	1,228,354	154,434
1901	4,192,646	1,286,508	1,287,402	173,317
1902	4,280,620	1,277,069	1,327,853	191,906
1903	4,346,011	1,416,225	1,517,176	220,070

#### BANKRUPTCIES.

The bankruptcy laws of the different states are even more dissimilar than the laws on most other questions of importance; they have also been fluctuating, and the subject of many experiments and amendments. This renders any work of comparison difficult and unsatisfactory. Returns are available for all the states for the year 1903, and are given below. In connection with the table it may be pointed out that the figures are exclusive of 59 liquidations in Queensland, with liabilities stated at £54,654, and assets at £43,232; and also of 196 private arrangements under the Insolvency Act in South Australia, for which the assets and liabilities are not stated. The Victorian figures include



195 Deeds of Arrangement under the Act of 1897, the liabilities of which were £227,604, and the assets £177,205:—

State.	Number of Sequestrations.	As shown in Bankrupts' Schedules.		
		Liabilities.	Assets.	Deficiency.
		£	£	£
New South Wales...	463	230,429	123,037	107,392
Victoria .....	699	412,561	249,062	163,499
Queensland .....	874	70,916	14,817	56,099
South Australia.....	24	15,221	14,633	588
Western Australia..	79	34,952	10,631	24,321
Tasmania .....	77	16,259	5,812	10,947
Commonwealth	1,718	760,336	417,522	362,816
New Zealand .....	204	96,866	46,767	50,099
Australasia .....	1,920	877,204	464,289	412,915

Little, if any, reliance can be placed upon the statements made by bankrupts as to the position of their affairs, the assets being invariably exaggerated. Taking the figures given above for what they are worth, it would appear that the average amount of liabilities per bankrupt was £457, and of assets, £242, showing a deficiency of £215. In the following table the average figures for the ten years ended 31st December, 1903, are given; the assets, however, have been omitted, since the statements, so far as some of the states are concerned, are palpably worthless. The Victorian figures include the "Deeds of Arrangement" for the years 1898 to 1903, while the South Australian returns are exclusive of private arrangements, which averaged 194 per annum. The Queensland figures are exclusive of liquidations.

State.	Number of Sequestrations.	Liabilities, as shown in Bankrupts' Schedules. £
New South Wales .....	788	662,289
Victoria .....	700	1,553,044
Queensland .....	365	103,133
South Australia .....	49	76,922
Western Australia .....	74	105,506
Tasmania .....	88	32,512
Commonwealth .....	2,064	2,533,358
New Zealand ....	367	185,292
Australasia .....	2,431	2,718,650

## SOCIAL CONDITION.

THE high rates of wages which have generally prevailed in Australasia and the cheapness of food have permitted the enjoyment of a great degree of comfort, if not of luxury, by a class which elsewhere knows little of the one and nothing of the other; and even in times of trade depression and reduced wages it may safely be said that the position of the wage-earner in Australia is equal to that occupied by his compeers in any other part of the world. Although a high standard of living is not conducive to thrift, saving has gone on with marked rapidity, notwithstanding the industrial disturbances resulting from the great strikes and the bank crisis of 1893. Some idea of the rate and extent of this accumulation of wealth may be obtained from the tables showing the growth of deposits with banks. The banking returns, however, afford in themselves but an incomplete view of the picture; it should also be regarded from the standpoint of the expenditure of the people. Both of these subjects are dealt with in their proper places in this volume, and these evidences of the social condition of the people need not, therefore, be further considered here.

### NEWSPAPERS AND LETTERS.

Few things show more plainly the social superiority of a civilized people than a heavy correspondence and a large distribution of newspapers. In these respects all the provinces of Australasia have for many years been remarkable. In proportion to population it is doubtful whether any country in the world can boast of a larger number or a better class of newspapers than they publish. Great advances were made in this respect between 1871 and 1891, but the rate of progress, both in number and in excellence of production, has been even more rapid since the year last named. There are no means of correctly estimating the number of newspapers actually printed and distributed in the states, because the Post-office carries but a small proportion of the circulation. For purposes of comparison with other countries, however, it may be stated that during the year 1903 no less than 116,136,000 newspapers passed through the Post-offices of the various states, giving the large proportion of 25 per head of population. In the same year the number of letters and post-cards carried was 313,329,000, being over 66 for every person in Australasia. An examination of the statistics of other countries shows that these states stand third among the countries of the world in the transmission of

correspondence, being only exceeded by the United Kingdom and the United States of America per head of population. The following table shows the increase which has taken place in the quantity of postal matter carried, together with the proportion of letters and newspapers carried per head of population at the last six census periods and in 1903 :—

Year.	Letters and Post Cards.	Newspapers.	Letters per head.	Newspapers per head.
1851.....	2,163,000	2,150,000	4·7	4·7
1861.....	14,061,000	10,941,400	11·3	8·8
1871.....	30,435,300	17,252,700	15·7	8·9
1881.....	80,791,700	43,802,000	29·1	15·8
1891.....	183,694,900	95,879,760	47·9	25·0
1901.....	273,582,000	121,000,000	59·7	26·4
1903.....	313,329,000	116,136,000	66·1	24·5

There are 1,187 newspapers published in Australasia ; 315 in New South Wales, of which 107 are published in Sydney and suburbs ; 405 in Victoria, of which 181 are published in Melbourne and suburbs ; 132 in Queensland ; 61 in South Australia ; 49 in Western Australia ; 27 in Tasmania ; and 198 in New Zealand.

#### PARKS, MUSEUMS, AND ART GALLERIES.

All the Australasian capitals are liberally supplied with parks and recreation-grounds. In Sydney and suburbs there are parks, squares, and public gardens comprising an area of 4,598 acres, including 745 acres which form the Centennial Park. Then there is the picturesque National Park, of 36,810 acres, situated about 16 miles from the centre of the metropolis ; and, in addition to this, an area of 35,300 acres, in the valley of the Hawkesbury, and distant about 12 miles from the railway terminus on the northern shore of Sydney Harbour, has been reserved for public recreation under the name of Ku-ring-gai Chase. Thus Sydney has two extensive and picturesque domains for the enjoyment of the people at almost equal distances north and south from the city, and both accessible by railway. An area of 248 acres has also been set apart as a public park at Kurnell, Captain Cook's landing place on the south shore of Botany Bay. Melbourne has about 5,400 acres of recreation-grounds, of which about 1,750 acres are within the city boundaries, 2,850 acres in the suburban municipalities, and 800 acres outside those municipalities. Adelaide is surrounded by a broad belt of park lands, and also contains a number of squares within the city boundaries, covering altogether an area of 2,300 acres. Brisbane, Hobart, Perth, and the chief cities of New Zealand are also well provided for in this respect, and in all the provincial towns large areas have been dedicated as public parks. There are fine Botanic Gardens in

Sydney, Melbourne, Brisbane, Adelaide, Perth, and Hobart, which are included in the areas above referred to. Each of these gardens has a special attraction of its own. They are all well kept, and reflect great credit upon the communities to which they belong.

The various capitals of the states, and also some of the prominent inland towns, are provided with museums for the purposes of instruction as well as recreation; and in Sydney, Melbourne, Brisbane, Adelaide, Perth, and Hobart there are art galleries containing excellent collections of paintings and statuary. All these institutions are open to the public free of charge.

#### PUBLIC CHARITIES.

One of the most satisfactory features of the social condition of the Australian communities is the wide distribution of wealth, and the consequently small proportion of people who are brought within the reach of want. In the United Kingdom, the richest country of Europe, only nine out of every hundred of the population possess property of the value of £100, while in Australasia the number is about fifteen, and the violent contrast between the rich and the poor which blots the civilisation of the old world is not observable in these young states. It is, unfortunately, only too plain that a certain amount of poverty does exist; but there is a complete absence of an hereditary pauper class, and no one is born into the hopeless conditions which characterise the lives of so many millions in Europe, and from which there is absolutely no possibility of escape. No poor-rate is levied in Australasia, the assistance granted by the state to able-bodied men who find themselves out of employment in times of depression, taking the form of payment, in money or in rations, for work done by them.

The chief efforts of the authorities, as regards charity, are directed towards the rescue of the young from criminal companionship and temptation to crime, the support of the aged and infirm, the care of the imbecile or insane, and the subsidising of private institutions for the cure of the sick and injured and the amelioration of want. Even where the state grants aid for philanthropic purposes, the management of the institutions supervising the expenditure is in private hands, and in addition to state-aided institutions there are numerous charities wholly maintained by private subscriptions, whose efforts for the relief of those whom penury, sickness, or misfortune has afflicted are beyond all praise.

The rescue of the young from crime is attempted in two ways—first, by means of Orphanages and Industrial Schools, where children who have been abandoned by their natural guardians, or who are likely, from the poverty or incapacity of their parents, to be so neglected as to render them liable to lapse into crime, are taken care of, educated, and afterwards apprenticed to some useful calling; and second, by sequestering in Reformatories children who have already committed

crime, or whose parents or guardians find themselves unable to control them; but the accommodation in the latter class is very limited, and might well be extended.

Although more than a century has elapsed since settlement commenced in Australasia, its resources are by no means developed, and very many men are at work far away from the home comforts of everyday life, and from home attendance in case of sickness or injury. Owing to the peculiar nature of the occupations in which a great part of the adult male population is employed, accidents are very common, the annual death-rate being about 7 per 10,000 living, and the majority of the cases treated, especially in the districts outside the metropolitan area are injuries arising out of accidents to men following hazardous pursuits. Hospitals are therefore absolutely essential under the conditions of life in the rural districts of the states, and they are accordingly found in every important country town. Below will be found the number of hospitals in each state, with the number of indoor patients treated during the year mentioned, and the total expenditure for the same year. Unfortunately, the South Australian returns are defective, as will be seen by the note appended to the table:—

State.	Year.	Hospitals.	Indoor patients treated.	Expenditure.
		No.	No.	£
New South Wales ...	1903	128	45,346	211,115
Victoria .....	1902-3	53	27,104	166,543
Queensland.....	1903	73	19,510	122,451
South Australia ....	1902	8	3,375*	19,065*
Western Australia...	1902-3	28	6,408	54,938
Tasmania .....	1902	14	3,966	25,645
Commonwealth	.....	304	105,718	599,757
New Zealand .....	1902-3	45	14,659	138,027
Australasia ...	.....	349	120,377	737,784

\* Adelaide Hospital only.

All the states possess institutions for the care of the insane, which are under Government control. The treatment meted out to the inmates is that dictated by the greatest humanity, and the hospitals are fitted with all the conveniences and appliances which modern science points out as most calculated to mitigate or remove the affliction from which these unfortunate people suffer. The following table shows the number of insane patients under treatment, the total expenditure on hospitals for the insane during the year, and the average expenditure per inmate under treatment. The figures refer to the year 1903, for all the states,

with the exception of Tasmania, for which the information is for the year 1902. The question of insanity is treated farther on in this chapter:—

State.	Insane Patients under treatment.	Total Expenditure.	Average Expenditure per Inmate under treatment.
	No.	£	£ s. d.
New South Wales .....	5,958	151,310	25 7 11
Victoria .....	5,299	133,708	25 4 8
Queensland .....	2,254	46,438	20 12 0
South Australia .....	1,199	26,967	22 9 10
Western Australia .....	520	16,376	31 9 10
Tasmania .....	506	15,557	30 14 11
Commonwealth .....	15,738	390,356	24 16 1
New Zealand .....	3,317	64,688	19 10 0
Australasia .....	19,053	455,044	23 17 8

The amounts expended on Destitute Asylums and Benevolent Societies cannot be separated from other items of expenditure in some of the states. As far as they can be ascertained they are given in the following table, together with the number of adult inmates of the various asylums for the year 1902:—

State.	Inmates. No.	Expenditure. £
New South Wales .....	4,530	125,736
Victoria .....	3,114	105,263
Queensland .....	2,666	42,274
South Australia .....	686	20,450
Western Australia .....	487	11,432
Tasmania .....	932	6,176
Commonwealth .....	12,415	311,331
New Zealand .....	2,162	49,737
Australasia .....	14,577	361,068

In addition to the above, a liberal amount of out-door relief is given in all the Australasian provinces, and destitute children are taken care of, either by being supported in the Government institutions or by being boarded out to persons deemed able to take care of them properly.

The expenditure by the Governments of the six states of the Commonwealth on hospitals, benevolent asylums, orphanages, and poor relief generally, amounted in 1903 to £1,382,790, the total for New Zealand for the same year being £233,179. This sum does not include payments to old-age pensioners, but as want of means is a necessary qualification for a pension, it is very doubtful whether this service does not come under the general description of poor relief. Including payments for old-age pensions, the total expenditure of the various states reaches £2,131,702, and of New Zealand £442,335, the distribution among the states being as follows. The figures refer to expenditure

from revenue only, the outlay from loans being separately shown in a subsequent table :—

State.	Hospitals, Asylums, and Poor Relief.	Old-Age Pensions.	Total.
	£	£	£
New South Wales.....	503,900	532,940	1,036,840
Victoria .....	330,484	215,972	546,456
Queensland .....	231,657	.....	231,657
South Australia.....	121,302	.....	121,302
Western Australia.....	147,188	.....	147,188
Tasmania.....	48,250	.....	48,250
Commonwealth .....	1,382,790	748,912	2,131,702
New Zealand .....	233,179	209,156	442,335
Australasia .....	1,615,969	958,068	2,574,037

Comparing these amounts with the population of the various states the following results are obtained :—

State.	Expenditure per head in 1903.		
	Hospitals, Asylums, and Poor Relief.	Old-Age Pensions.	Total.
	£ s. d.	£ s. d.	£ s. d.
New South Wales.....	0 7 0	0 7 6	0 14 6
Victoria .....	0 5 5	0 3 7	0 9 0
Queensland .....	0 9 0	.....	0 9 0
South Australia.....	0 6 8	.....	0 6 8
Western Australia .....	0 13 4	.....	0 13 4
Tasmania.....	0 5 5	.....	0 5 5
Commonwealth .....	0 7 1	0 3 10	0 10 11
New Zealand .....	0 5 8	0 5 1	0 10 9
Australasia .....	0 6 10	0 4 1	0 10 11

It will be seen that the expenditure was proportionately highest in New South Wales, with 14s. 6d. per inhabitant, followed by Western Australia, with 13s. 4d., and Victoria and Queensland with 9s., whilst Tasmania showed the lowest average, with 5s. 5d. per inhabitant. For the Commonwealth and for Australasia the average was 10s. 10d. per head.

In addition to the amounts shown in the preceding table there is a fairly considerable expenditure from loans in some of the states on

hospitals and charitable institutions. The total loan expenditure under this heading is given below :—

State.	Expenditure from Loans on Hospitals and Charities.
	£
New South Wales .....	74,407
Victoria .....	66,838
Queensland .....	13,239
Tasmania .....	4,609
Commonwealth .....	159,093
New Zealand .....	11,051
Australasia .....	170,144

Including expenditure from revenue and from loans the total outlay by the Commonwealth for the year 1903, on all forms of charitable relief, amounted to £2,291,000, or at the rate of 11s. 8d. per head of population, and for Australasia, £2,744,000, equal to 11s. 7d. per inhabitant.

It was anticipated by the introducers of the old age pension system that there would be a reduction in the expenditure on poor relief, especially on asylums. The expectation was without reasonable foundation, as the classes of people affected by the two systems of relief are essentially distinct, and little or no reduction in the expenditure on poor relief can be traced to the establishment of the pension system. The following is a statement of the expenditure in 1896 ; the total for 1903 has been given on a previous page. It will be seen that on the whole there has been a large increase in expenditure during the period, the rate per inhabitant—excluding old-age pensions—being 6s. 10d. in 1903, as compared with 6s. per head in 1896.

State.	Expenditure in 1896 on Hospitals, Asylums, and Poor Relief.	
	Total.	Per Inhabitant.
	£	£ s. d.
New South Wales .....	410,800	0 6 6
Victoria .....	266,300	0 4 6
Queensland .....	153,900	0 7 2
South Australia .....	94,600	0 5 4
Western Australia .....	110,100	0 18 5
Tasmania .....	42,100	0 5 4
Commonwealth .....	1,082,800	0 6 2
New Zealand .....	179,400	0 5 1
Australasia .....	1,262,200	0 6 0

As far as can be judged from the imperfect returns, adding together the amount received from the Government and the amount of private



subscriptions, the expenditure in the whole of the Australasian states in connection with all forms of relief and in aid of hospitals and other charitable institutions excluding old age pensions is certainly not less than £1,823,000 per annum. This sum, though not excessive in proportion to the population, may yet appear large in view of the general wealth of the states, which should preclude the necessity of so many seeking assistance; and there is the risk that the charitable institutions may encourage the growth of the pauper element, for while free quarters and free food are so accessible, those who are disinclined to work are tempted to live at the public expense. It should be stated, however, that of the total number of persons who seek hospital relief, less than one-half are natives of the states, the remainder being mostly natives of the United Kingdom, with a few who were born in a European country or in China. This, however, cannot be taken as evidence of the superiority of the Australian born. The inmates of the institutions referred to are in almost all cases aged persons, and probably not more than half the number of aged persons are Australian born.

#### OLD-AGE PENSIONS.

The question of granting pensions to aged persons has been of late years much discussed throughout Australia and New Zealand, and at the present time the old age pension system is in operation in New South Wales, Victoria, and New Zealand. The last-named province was the first to legislate in regard to the matter, and pensions were payable from 1st April, 1898.

Every person in New Zealand, of the full age of sixty-five years, or upwards, is eligible for a pension, provided he has resided continuously in the colony for twenty-five years, certain concessions in regard to residence being made in favour of seamen and others. To be entitled to a pension, a person must not possess an income in excess of £52 a year, nor property exceeding £270 in value. There are also other qualifications, principally affecting good citizenship. The full pension is £18 a year, payable in monthly instalments. For each £1 of income above £34 a year, and for each £15 of property above £50, £1 per annum is deducted from the amount of the pension. In March, 1903, there were 32,800 persons in New Zealand whose ages exceeded sixty-five years, and of these 12,481 had already been granted pensions. The average pension paid was £16 19s., and the sum payable in respect of all pensions, excluding management, was £211,594. On the 31st March, 1904, the number of pensions was 11,926 (729 Maoris), and the amount payable thereon £200,915. The proportion of the population who claim old-age pensions varies according to the locality. This variation is due partly to the differences in the proportion of the persons above the pension age, and partly to the fact that in districts where mining is the chief industry, few persons are able to earn their living after they reach sixty-five years. The proportion of pensioners to the population over-sixty-five years of age is about 35 per cent., and the proportion of

pensioners to those qualified, both by age and residence, is about 45 per cent.

The old-age pension scheme sanctioned by the Parliament of New South Wales specifies a pension of £26 a year, diminished by £1 for every £1 of income above £26 a year, and by £1 for every £15 of property that the pensioner possesses. Where a husband and wife are each entitled to a pension, the amount is fixed at £19 10s. a year each, unless they are living apart under a decree of the Court or a deed of separation, when the full sum of £26 will be allowed. Persons under 65 years of age but over 60 years are entitled to pensions if they are incapacitated by sickness or injury from earning their livelihood, but debility due merely to age is not considered as an incapacitating sickness.

The pension system came into force on the 1st August, 1901, at which date 13,957 pensions were granted, involving a monthly payment of £28,037. The pension list gradually increased as persons entitled to claim made good their rights, and on the 1st July the number of pensioners was 22,252, the monthly pension bill being £44,362. This was the highest point attained, and from that date onward there has been a gradual decline, both in the number of pensioners and the amount payable. On the 1st August, 1902, at the close of the first twelve months of the system the number of pensioners was 22,182, the monthly pension bill being £44,318. In August, 1903, the number of pensioners was 20,905, the monthly payments being £41,695. In August, 1904, the number was 20,438, and the monthly payments £40,617. This is the lowest point reached since the pension system has been in full operation. On the 1st December following the number of pensioners was approximately 20,900, and the monthly payments £41,460. The average annual pension is now about £23 16s., and it has varied very little since the pension system came into force. From the highest point, July, 1902, to the 1st of December, 1904, there was a decline of 1,352 pensions, and a further decline is expected to take place. This is due to the direct control which the Central Board of Old Age Pensions is now able to exercise over the District Boards, as very few persons not entitled to a pension either by age, residence, or character remain long on the pension list.

The figures just given represent the actual pensions paid by the bank; the number of persons who hold rights during any month is always in excess of the numbers just given. As will be seen below, the pensions that become payable in any month are reduced by deaths, withdrawals, and cancellations, and by those pensioners who fail to draw their pensions within the time allowed by law. These, taken together, amount to a considerable number. Thus, at the 1st of December, 1904, there were 21,910 pension certificates issued and still current, while the number paid by the bank during the same period, as already stated, was 20,900, a difference of 1,010 pensions. About 320 of these would be represented by deaths and cancellations during the month, and about 700 by persons having entered public institutions

whose pensions would be temporarily suspended ; the remaining number to make up the total would be persons entitled to draw their pensions but who failed to present themselves at the bank within the time allowed by law.

During the three years and four months the pension system has been in operation—i.e., to 1st December, 1904—5,724 pensioners died, 1,174 pensions were cancelled, and 1,443 were rejected. The last-mentioned represent cases in which the boards refused to renew pensions for the second or subsequent year on account of the ineligibility of claimants or their misconduct. The death-rate represents 84·4 per 1,000 pensioners, which is only slightly in excess of the general average for persons of 65 years of age and upwards. The number of persons becoming 65 years of age in any year is about 5,000, and of these about 2,150 claim pensions, but as there is an annual death-roll of 1,840 pensioners, and about 820 pensions are cancelled or withdrawn from persons who previously enjoyed them, the pension list is yearly recruited by 2,150 persons and reduced by 2,660, showing a net reduction of 510, thus accounting for the lower pension list of 1904 compared with 1902.

The pension system of Victoria differs very materially from that in operation in New South Wales and New Zealand. The average weekly income of a claimant in Victoria during the six months immediately preceding the grant of a pension must not have amounted to 8s. per week (in New South Wales the sum allowed is £1 per week) ; he must also have made reasonable efforts to provide for himself, and this is not necessary either in New South Wales or New Zealand, where the pension is granted in consideration of old age, and a citizen may enjoy his pension on attaining the age of 65, whether he is able to work or not ; indeed, the law allows him to supplement his income to the extent of 10s. per week, in the case of New South Wales, and 13s. in that of New Zealand ; the total income enjoyed by the pensioner may, therefore, in these two states, amount to 20s. per week. In Victoria, under the original Act of 1901, the amount of pension was determined by the Commissioners appointed to adjudicate on the matter, and 8s. was the maximum allowed ; but the Commissioners had power to determine what sum less than 8s. might be reasonable and sufficient to meet the wants of the claimant. Under the Amending Act of 1903, however, the control and management of "this charitable grant," as the Premier styled it, was taken out of the hands of the Commissioners and vested in the Treasurer, the object being to secure greater uniformity of administration. The rate of pension and date of commencement of the claim is fixed by the Treasurer and specified in the pensioner's pass-book. Moreover, when a claimant, although he has attained the statutory age of 65 years, appears to be physically capable of earning or partly earning his living, a pension may be refused or fixed at a lower sum than 8s. As noted before, the total income of a pensioner in New South Wales may reach 20s., that is 10s. over and above a full pension ;

but in Victoria, the limit of a pensioner's income from all sources is 8s., although, subject to certain conditions, he was allowed, under the original Act, to earn a sum which, with his pension, would amount to 10s. in all. The power to increase the pension was, however, taken away by the Amending Act. The statutory maximum of pension is diminished by 6d. per week for every £10 of savings accumulated by the claimant, or by the value of the board and lodging which he may receive; the value of such board and lodging, however, may be taken at any sum not exceeding 5s. per week. Proceedings to obtain an old-age pension are usually in open court, but the Commissioners dealing with the claim may dispense with the personal attendance of the claimant where the latter is physically unfit, or where the claim is one that obviously should be granted. The Commissioners may not now determine the rate of pension and the manner of payment, but must forward particulars of each case to the Registrar, and no pass-book may be issued to any claimant except by authority of the Treasurer. Relatives—if the father, mother, brother, sister, or child of the claimant—are required to assist in the maintenance of the pensioner, where their means are sufficient to allow them to do so, and they may be brought before the Commissioners' Court to prove their inability to contribute to the maintenance of the pensioner to whom they are said to be related.

The granting of pensions depends on whether any money is available to pay them, for by an Act passed on the 9th December, 1903, the total sum to be paid in pensions annually is limited to £150,000 a year. The average pension works out at £17 6s. 8d. a year, or 6s. 8d. per week compared with a maximum of 8s. The following is a statement of the number of pensioners at various dates since the Act came into operation:—

June 30, 1901	...	...	...	...	...	16,275
December 6, 1901	...	...	...	...	...	16,233
June 30, 1902	...	...	...	...	...	14,570
„ „ 1903	...	...	...	...	...	12,417
„ „ 1904	...	...	...	...	...	11,609

The payments in respect of pensions were as follows; in each case the year ends on the 30th June:—

1901 (5 months)	...	...	...	...	...	£129,338
1902	...	...	...	...	...	292,432
1903	...	...	...	...	...	215,972
1904	...	...	...	...	...	205,183

It will be seen that, whereas in New South Wales and New Zealand the old-age pension is a gift by the state to citizens who have contributed by taxation, and who, as the preamble to the New South Wales Act declares, have during the prime of life helped to bear the public burthens of the state by the payment of taxes, and by opening up its resources by their labour and skill, in Victoria the pension partakes more of the nature of a charitable dole. It is easy to understand, therefore, how it is that in New South Wales there are 20,900 persons who

are in receipt of pensions, and in New Zealand 11,926, while in Victoria the number is only 11,609, although the persons of 65 years and upwards in Victoria number 67,200, compared with 49,000 in New South Wales and 33,500 in New Zealand.

The estimated number of persons of 65 years and upwards in Australia was, at the 30th June, 1904, 193,000, of whom 159,300 resided in the Commonwealth and 33,700 in New Zealand. These figures are deduced from the census returns and are probably in excess of the truth, as a large number of persons, in anticipation of the establishment of a general system of old-age pensions, described themselves as over 65 years of age, though in reality they had not reached that age. However, accepting the figures as they stand, the following are the numbers in the various states of the Commonwealth :—

New South Wales.....	51,600
Victoria .....	67,300
Queensland .....	13,400
South Australia.....	15,400
Western Australia .....	4,300
Tasmania .. .....	7,300

159,300

Proposals have been made from time to time for the Commonwealth Government to institute a system of old-age pensions applicable to persons resident in any of the states, an objection to the present state system being that residence of twenty years in the case of Victoria and of twenty-five years in the case of New South Wales is a condition precedent to the granting of a pension. There are a large number of persons who have been twenty-five years in Australia but whose time has been spent in two or more states and who, therefore, would not under any state system likely to be put into operation be entitled to a state pension. These persons would be eligible under a federal system to receive pensions in virtue of their residence in Australia.

The proportion of the 159,300 persons of 65 years and upwards now in the Commonwealth, who were born or have resided for twenty-five years in Australia, is probably about 87 per cent., and the proportion qualified to receive a pension about 39 per cent., so that if a federal pension scheme had been in operation on 30th June, 1904, there would have been 62,000 pensioners over 65 years of age. The cost of this scheme, according to the New South Wales rates, would be £1,476,000 per annum, and according to the New Zealand rates, £1,045,000. The New South Wales system, as before stated, provides for pensions to persons between the ages of 60 and 65 years, incapacitated, by reason of physical infirmity from earning their livelihood. If provision were to be made by the Commonwealth for such persons according to the New South Wales scale, the cost of the pension system would be about £1,630,000.

It is elsewhere explained that a considerable number of persons claim and obtain pensions which are subsequently forfeited by reason,

chiefly, of misconduct. It is doubtful whether the supervision the Commonwealth could exercise would be as efficient as that of a state department working through the agencies of state officers controlled by the Treasury, desirous of keeping down to as low a point as possible the pension bill of the state; but assuming that the experience of the Commonwealth would be similar to that of New South Wales, the proportion eligible to receive a pension would be little greater than 35 per cent. of those of pension age, so that the pension bill of the Commonwealth, according to the New South Wales practice, would be £1,338,000 instead of £1,476,000 shown above, or, including those under 65 years of age, £1,517,000 instead of £1,630,000. In dealing with this question of pensions, the distinction between a pension current and pension payable should be kept in mind; and this point is dwelt upon at some length in regard to New South Wales on page 838.

#### SUICIDES.

The total number of persons who committed suicide in Australasia during 1903 was 618—522 males and 96 females—corresponding to a rate of 1·18 per 10,000 living. The table below shows the number of deaths and the rates in each state, in five-year periods since 1875. It is believed that the actual number of suicides is even larger than is shown in the tables, especially during recent years; for there is a growing disposition on the part of coroners' juries to attribute to accident what is really the result of an impulse of self-destruction.

TOTAL NUMBER of Deaths.

State.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901-5.
New South Wales .....	297	368	578	713	874	453
Victoria .....	505	463	638	630	565	393
Queensland .....	141	179	292	349	400	234
South Australia .....	93	146	134	156	192	121
Western Australia .....	7	23	22	73	157	139
Tasmania .....	37	27	43	63	63	38
New Zealand .....	195	261	267	339	340	284
<b>Australasia .....</b>	<b>1,275</b>	<b>1,467</b>	<b>1,974</b>	<b>2,323</b>	<b>2,591</b>	<b>1,632</b>

DEATH RATE per 10,000 living.

New South Wales .....	·90	·87	1·12	1·19	1·33	1·06
Victoria .....	1·23	1·02	1·21	1·08	0·95	1·06
Queensland .....	1·38	1·33	1·62	1·69	1·71	1·33
South Australia .....	·77	·99	·87	·92	1·07	1·06
Western Australia .....	·50	1·46	1·05	2·25	1·99	2·26
Tasmania .....	·68	·44	·63	·85	0·79	0·51
New Zealand .....	·91	·99	·89	1·03	0·92	1·13
<b>Australasia .....</b>	<b>1·02</b>	<b>·98</b>	<b>1·12</b>	<b>1·16</b>	<b>1·18</b>	<b>1·21</b>

Speaking generally, the experience of Australasia agrees with that of other countries, namely, that the tendency to self-destruction is increasing. From the table above it is seen that the rate slowly but steadily advanced from 1886 up till the end of 1903. Tasmania has always had the lowest rate, while in New Zealand the rate is slightly above that in England, where it is 0·92 per 10,000 living. Up to 1893, the three first-named states in the table exhibited the highest rates, Queensland coming first; but since that year Western Australia has shown the largest proportional number of victims by suicide, due, no doubt, to the relatively large number of males in the state, since males are three or four times as prone to take their own lives as females.

The means of committing suicide most favoured in all the states, are poisoning, drowning, shooting, which is more common now than formerly, and hanging amongst males, and poisoning and drowning amongst females.

#### ILLEGITIMACY.

Illegitimate births are rather numerous in these states, the total number in the whole of Australasia during 1903 being 6,912, equal to 5·75 per cent. of the total births. A comparison of the results for the last two years shows that in 1903 the rates decreased in South Australia and Tasmania, while the other states showed slight increases. The following table shows the number of illegitimate births in each state and New Zealand in quinquennial periods since 1875, and the proportion per cent. of total births :—

State.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1900.	1901.	1902.	1903.
TOTAL NUMBER of Illegitimate Births.								
New South Wales..	5,401	6,949	9,394	11,875	12,622	2,712	2,497	2,413
Victoria .....	5,646	6,491	8,425	9,858	8,625	1,729	1,677	1,695
Queensland .....	1,447	1,990	3,117	3,516	4,213	848	859	857
South Australia ...	...	1,222	1,331	1,577	1,767	361	389	354
Western Australia..	...	...	...	†402	1,133	222	247	314
Tasmania .....	...	*762	911	1,136	1,322	193	311	285
New Zealand .....	2,027	2,831	3,011	3,443	4,196	937	921	994
Australasia .....	...	20,245	26,189	31,807	33,878	7,002	6,901	6,912
PROPORTION per cent. of Total Births.								
New South Wales..	4·22	4·36	4·90	6·01	6·88	7·16	6·59	6·71
Victoria .....	4·27	4·63	4·89	5·45	5·57	5·57	5·55	5·73
Queensland .....	3·85	4·06	4·44	4·83	5·92	5·93	6·04	6·79
South Australia ...	...	2·16	2·50	2·98	3·76	3·96	4·35	4·16
Western Australia..	...	...	...	†4·75	5·06	3·88	3·96	4·69
Tasmania .....	...	*4·35	3·84	4·58	5·65	3·91	6·11	5·61
New Zealand .....	2·30	2·93	3·20	3·77	4·43	4·57	4·46	4·55
Australasia .....	...	3·90	4·35	5·06	5·67	5·67	5·59	5·75

\* Four years—1882-85.

† Four years—1892-95.

It is seen that up to 1903, when it was displaced by Queensland, New South Wales has always been in the unenviable position of exhibiting the highest proportion of illegitimate births, although till 1890 it was closely followed by Victoria. Since 1890, however, the rate in New South Wales has increased very rapidly, as also in Queensland. Tasmania showed the third highest proportion in 1903 with 5.61 per cent., a considerable decrease on the figure for the previous year, which stood at 6.11. In all the states illegitimacy is on the increase; and whereas less than twenty years ago each province had a lower rate than prevailed in England, they all, with the exception of South Australia, have now a higher rate. Considered in conjunction with the declining birth-rate, these figures cast an unpleasant light on the morals of the country.

The increase, however, is more apparent than real, since the general decline in the birth-rate affects the proportion of illegitimates. A proper comparison would be obtained by relating the number of illegitimate births to the number of unmarried women of child-bearing ages during the period. If this were done it would be found that illegitimacy is not increasing in Australia.

The following table shows the proportion of illegitimate births in the United Kingdom, and in the chief countries of Europe, based on the experience of the latest five years available. In a majority of the European countries illegitimacy appears to be on the increase.

Country.	Illegitimate Births per cent.	Country.	Illegitimate Births per cent.
England and Wales...	4.04	Hungary .....	9.01
Scotland .....	6.33	France .....	8.26
Ireland .....	2.65	Belgium .....	8.51
Germany .....	9.21	Netherlands.....	2.71
Prussia .....	7.84	Sweden .....	10.80
Bavaria .....	14.00	Norway .....	7.35
Saxony .....	12.90	Italy .....	6.34
Austria .....	14.55		

#### DIVORCE.

The question of divorce is one of much interest to Australasia, as some of the states, especially New South Wales and Victoria, now



offer great facilities for the dissolution of the marriage bond. The general opinion was that such facilities were calculated to increase divorce to an extent that would prove hurtful to public morals ; and so far as the experience of New South Wales was concerned, for the first few years after the passing of the Act multiplying the grounds on which divorce could be granted, the fear did not seem to be altogether groundless ; for in 1893 the number of decrees *nisi* granted rose to 305, from 102 in 1892, and in 1901 was still as high as 252. When, however, it is remembered that advantage would be taken of the change in law to dissolve marriages the bonds of which would have been broken long before under other circumstances, it is evident that there was little ground for the fear that this somewhat alarming increase would continue, and it was, therefore, not surprising to find a decline to 245 in 1902. In Victoria, where a very similar law came into operation in 1890, the number of divorces increased considerably, immediately after the passing of the Act, although not to the alarming extent experienced in New South Wales.

In New South Wales, under the Matrimonial Causes Act of 1873, the chief grounds on which divorce was granted were adultery after marriage on the part of the wife, and adultery with cruelty on the part of the husband. Under the Act of 1892 and the Amending Act passed in 1893 petitions for divorce can be granted for the following causes, in addition to those already mentioned:—*Husband v. Wife*.—Desertion for not less than three years ; habitual drunkenness and neglect of domestic duties for a similar period ; refusing to obey an order for restitution of conjugal rights ; being imprisoned under sentence for three years or upwards ; attempt to murder or inflict grievous bodily harm, or repeated assault on the husband within a year preceding the date of the filing of the petition. *Wife v. Husband*.—Adultery, provided that at the time of the institution of the suit the husband is domiciled in the state ; desertion for not less than three years ; habitual drunkenness with cruelty or neglect to support for a similar period ; refusing to obey an order for restitution of conjugal rights ; being imprisoned for three years or upwards, or having within five years undergone various sentences amounting in all to not less than three years ; attempt to murder or assault with intent to inflict grievous bodily harm, or repeated assault within one year previously. Relief can only be sought on these grounds should the petitioner have been domiciled in the state for three years or upwards at the time of instituting the suit, and not have resorted to the state for the purpose of having the marriage dissolved. In Queensland, South Australia, Western Australia, Tasmania, and New Zealand, divorces are granted principally for adultery on the part of the wife, and adultery coupled with desertion for over two years on the part of the husband.

In the subjoined table will be found the actual number of divorces and judicial separations granted during each of the years 1896–1902. It will be seen that the rate varies considerably for the different years,

the lowest proportion being shown in 1898 and the highest in the year immediately preceding.

State.	1896.		1897.		1898.		1899.		1900.		1901.		1902.	
	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.
New South Wales .....	234	8	244	13	247	17	232	17	219	14	252	20	245	21
Victoria .....	106	2	117	..	57	..	105	2	93	..	83	..	109	..
Queensland .....	3	2	10	1	7	..	10	1	12	1	14	..	6	..
South Australia .....	6	1	3	..	7	1	11	..	7	1	6	..	2	..
Western Australia .....	1	..	4	..	3	..	3	..	16	..	12	1	8	..
Tasmania .....	3	..	5	..	4	..	4	..	4	..	11	..	3	..
New Zealand .....	36	2	33	1	32	2	46	16	85	3	108	1	91	..
Australasia .....	380	15	418	15	387	20	411	36	436	19	481	22	464	21
Totals .....	404		433		407		447		455		503		485	
Divorces and separations per 10,000 marriages ..	144.2		150.6		137.7		142.3		138.0		148.6		141.3	

The following table shows the number of decrees of dissolution of marriage and judicial separation granted in each state, in quinquennial periods since 1871, so far as it is possible to procure the information. Divorce was legalised in New South Wales in 1873, and the figures of that state for 1871-75 only cover the two years 1874 and 1875.

State.	1871-75.		1876-80.		1881-85.		1886-90.		1891-95.		1896-1902.	
	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.	Divorces.	Judicial Separations.
New South Wales .....	21	..	87	..	116	6	212	12	1087	55	1675	110
Victoria .....	33	6	41	2	74	8	124	9	441	10	700	4
Queensland .....	4	1	14	..	5	2	26	3	26	3	62	5
South Australia .....	22	3	35	2	31	10	23	2	30	2	42	3
Western Australia .....	..	..	1	1	5	..	8	..	9	..	47	1
Tasmania .....	9	..	9	..	9	..	15	2	21	2	34	..
New Zealand .....	..	..	..	..	..	..	110	5	101	14	428	25
Australasia .....	89	10	187	5	240	26	518	33	1715	86	2986	148

\* Information not available.

Taking the figures given in the foregoing table, and comparing them with the number of marriages celebrated during the same periods, the rates of divorce for the individual states, per 10,000 marriages, will be found below. It will be seen that the rate for New South Wales is

higher than that of any country of the world except the United States and Switzerland :—

State.	1871-75.	1876-80.	1881-85.	1886-90.	1891-95.	1896-1902.
New South Wales .....	†23·5	33·6	32·5	54·8	272·3	268·4
Victoria .....	16·0	16·9	24·4	31·1	119·6	125·4
Queensland .....	8·0	18·7	6·0	19·0	21·4	30·3
South Australia .....	33·5	34·6	33·1	24·3	29·9	28·9
Western Australia .....	...	20·5	44·8	53·5	38·6	41·0
Tasmania .....	27·4	22·0	18·0	35·4	50·8	41·2
New Zealand .....	*...	*...	*...	63·5	56·9	116·6

\* Information not available. † 1874 and 1875 only.

From the appended statement, which sets forth the latest divorce rates of the countries for which accurate statistics are obtainable, such rates being calculated on an experience of ten years wherever possible, it will be seen that there is a larger proportion of marriages dissolved in Australasia than in any other part of the British Empire, but that the rate for these provinces as a whole is largely exceeded by a number of foreign countries. Of countries where divorce laws are in force, no reliable statistics are available for Denmark, Hungary, Russia, and Spain. In Italy and Portugal divorce is not recognised by law :—

Country.	Divorces per 10,000 Marriages.	Country.	Divorces per 10,000 Marriages.
Canadian Dominion ...	4	Cape Colony .....	98
United Kingdom .....	11	Netherlands .....	103
Norway .....	16	Germany .....	165
Austria Proper .....	43	France .....	180
Greece .....	50	Roumania .....	204
Belgium .....	81	Switzerland .....	432
Sweden .....	87	United States .....	612

In the United States of America no general system of registration of births, deaths, and marriages is in force. For the purpose of comparison, the marriage-rate of that country has been assumed to be 6·50 per 1,000 of mean population, and on that basis the 20,660 divorces granted annually during ten years would give an average of not less than 612 per 10,000 marriages.

In the Dominion of Canada divorce was, under the Union Act, assigned to the Federal Parliament; but those provinces which had established divorce courts before the accomplishment of federation were permitted to retain the jurisdiction which they already exercised. In the remaining provinces no divorce courts have been established since

the constitution of the Dominion, and divorce can only be obtained by legislation, the matter being dealt with in each case as an ordinary private Act of Parliament, with this difference, however, that the Senate requires the production of such evidence in support of the application for relief as would be deemed sufficient in a court of law.

#### INSANITY.

The number of insane persons in Australasia, under official cognizance in the various Government hospitals for the treatment of the insane, at the end of 1902 was 15,673, equal to 3·36 per 1,000 of the population, or corresponding to one insane person in about every 300. This rate is below that prevailing in England, where one person in every 293 is officially known to be insane.

An inspection of the table given below of the insane persons, both male and female, in each state and New Zealand at the end of 1902, and the rate per 1,000 inhabitants of each sex, will disclose the fact that the rate of insanity varies greatly in the different provinces, and that the rate for males is everywhere higher than that for females.

State.	Number of Insane.			Per 1,000 of Population.		
	Males.	Females.	Total Persons.	Males.	Females.	Total Persons.
New South Wales .....	2,816	1,857	4,673	3·81	2·78	3·32
Victoria .....	2,354	2,193	4,547	3·91	3·63	3·77
Queensland .....	1,118	690	1,808	3·91	3·01	3·51
South Australia .....	566	425	991	3·05	2·36	2·71
Western Australia .....	263	102	365	2·12	1·28	1·79
Tasmania .....	243	198	441	2·64	2·33	2·49
Commonwealth .....	7,360	5,465	12,825	3·63	2·97	3·32
New Zealand .....	1,715	1,133	2,848	4·03	2·97	3·53
Australasia .....	9,075	6,598	15,673	3·71	2·97	3·36

Victoria has the highest general rate, with 3·77 per 1,000, New Zealand coming next with 3·53, closely followed by Queensland with 3·51. Next comes New South Wales with 3·32; South Australia with 2·71; Tasmania with 2·49; while Western Australia shows the lowest proportion with 1·79 per 1,000. New Zealand shows the highest rate for males with 4·03 per thousand, followed by Queensland and Victoria with 3·91; and Victoria with 3·63 per thousand has the largest proportion of females.

There is one remarkable difference between the Australasian states and Great Britain, namely, that in England the greater proportion of insanity is found amongst women, whereas in Australasia it is found amongst men.

In England the rate per 1,000 males in 1902 was 3·22, and per 1,000 females 3·59. In Australasia the greatest disproportion was in New Zealand, where the male and female rates were respectively 4·03 and 2·97 per 1,000. The smallest difference between the sexes is found in those states where the male population follow in greater proportion what may be termed the more settled pursuits. In Victoria the excess of the male over the female rate was only 0·28 and in Tasmania 0·31.

There seems to be little doubt that insanity is slowly but steadily increasing in the states, as it is in the United Kingdom and other countries. In England the rate has risen from 2·75 per 1,000 of population in 1879 to 3·41 in 1902, and in Scotland a similar rise has taken place from 2·75 per 1,000 in 1884 to 3·53 in 1902. In Ireland the rate has risen from 2·50 per 1,000 of the population in 1880 to 4·99 per 1,000 in 1902. The greater part of this increase is no doubt rightly attributed to an improvement in the administration of the Commissioners in Lunacy, by which a more accurate knowledge of the number of cases existent in the country has been gained; but the steady growth of the rate in recent years, when statistical information has been brought to a high pitch of perfection, plainly points to the fact that the advance of civilisation, with the increasing strain to which the struggle for existence is subjecting body and mind, has one of its results in the growth of insanity. In all the states of Australasia, with the sole exception of Tasmania, there is seen the same state of affairs as the insanity returns of Great Britain disclose, although the conditions of life press much more lightly on the individual here.

The experience of the various states is fairly represented in the following table, which shows the average number of insane in each state per 1,000 of population, arranged in three five-years periods:—

State.	1888-92.	1893-97.	1898-1902.
	Rate per 1,000 of Population.	Rate per 1,000 of Population.	Rate per 1,000 of Population.
New South Wales.....	2·75	2·94	3·19
Victoria .....	3·34	3·53	3·72
Queensland.....	2·77	3·17	3·43
South Australia.....	2·51	2·64	2·71
Western Australia .....	2·69	1·46	1·58
Tasmania.....	2·43	2·33	2·38
Commonwealth .....	2·92	3·07	3·23
New Zealand .....	2·88	3·12	3·45
Australasia .....	2·92	3·07	3·26

The above figures show that since 1897 the rate has increased throughout the Commonwealth and Australasia, while, with the exception of Western Australia and Tasmania, the rates for all the states show increases on those recorded for the quinquennial period ending in 1892. At present the smallest proportion of insane is shown by Western Australia, but the rate is increasing year by year, and will in all probability soon approximate that of the other states. The hospital accommodation in the state is limited, and many insane, especially males, doubtless escape notice.

It has been said that the trade depression experienced a few years ago throughout Australasia, was the cause of an increase in insanity; and at first sight it looks as if this were so, because since 1892 there has been a steady increase in the proportion of the population detained in asylums. But looking at the rates of admissions this view does not seem to be altogether borne out. Probably one effect of depressed times is to send to the asylums a number of harmless but demented persons who, under other circumstances, would be supported by their relatives. In England and Wales it is found that the increase in insanity has taken place amongst those who are termed the "pauper" class—that is, those whose relatives are not in a position to support them after they lose their reason. On the other hand, the admissions in prosperous times are kept up by insanity either directly or indirectly induced by the indulgence which commonly follows high wages and large gains.

The following table shows the average annual number of admissions and readmissions into the asylums in each state, and the rate per 1,000 of population, during each of the two quinquennial periods 1893–97 and 1898–1902:—

State.	1893–97.		1898–1902.	
	Average Number of Admissions per annum.	Rate per 1,000 of Population.	Average Number of Admissions per annum.	Rate per 1,000 of Population.
New South Wales .....	709	0.57	836	0.62
Victoria .....	699	0.59	756	0.63
Queensland .....	252	0.58	336	0.68
South Australia .....	217	0.63	217	0.60
Western Australia .....	62	0.63	115	0.64
Tasmania .....	61	0.39	75	0.43
Commonwealth .....	2,000	0.58	2,335	0.62
New Zealand .....	495	0.72	573	0.75
Australasia .....	2,495	0.60	2,908	0.77

The table shows that the rate of admissions has advanced slightly during the decade in all the states, except South Australia, where there was a small decrease.

The next table shows the total number of patients who were discharged from the asylums during the ten years 1893-1902, either on account of recovery, permanent or temporary, or on account of death, and the proportion borne by each to the total number who were under treatment during the period.

State.	Total under Treatment.	Discharged—recovered or relieved.		Died.	
		Number.	Per cent. of total under treatment.	Number.	Per cent. of total under treatment.
New South Wales.....	11,039	3,787	34.30	2,529	22.91
Victoria .....	11,228	3,243	28.88	3,334	29.69
Queensland.....	4,174	1,353	32.41	978	23.43
South Australia.....	2,990	1,159	38.76	779	26.05
Western Australia .....	984	413	41.97	169	17.17
Tasmania .....	1,035	291	28.10	278	26.85
Commonwealth .....	31,450	10,246	32.58	8,067	25.64
New Zealand .....	7,259	3,205	44.15	1,406	19.37
Australasia.....	38,709	13,451	34.75	9,473	24.47

It is seen that, of the total number under treatment, 34.75 per cent. were discharged either partially or wholly recovered, and that 24.47 per cent. died. New Zealand shows the highest proportion of recoveries, and Tasmania and Victoria the lowest, while Western Australia has the lowest death-rate, and Victoria the highest. The position of Victoria as regards results in treatment of the insane is therefore the worst in Australasia, and this unsatisfactory state of affairs has aroused anxious attention in the southern state. At present the asylums are overcrowded, while the system of classification leaves much to be desired. A serious drawback to efficient administration also lies in the fact that while the inspector and official visitors may make suggestions they have no power to give administrative effect to their recommendations. In Western Australia also the asylums are greatly overcrowded, but the congestion will be, to some extent, relieved by the new buildings opened in 1903. The passing of the Lunacy Act of 1903, which supersedes the former defective Act, will, it is believed, lead to an important change for the better in the treatment and cure of the insane in the western state. Speaking generally, it is estimated that of the persons who are discharged from the asylums in Australasia, some 28 per cent. suffer a relapse and are readmitted; and it may be said that out of every 1,000 persons who are admitted for the first time, 420 will recover, and the sufferings of the remaining 580 will only be terminated by death.

Very little information is available as to the exciting or predisposing causes of insanity in the different states, New South Wales being the

only one concerning which there is complete information. But that state may be taken as typical of the whole, as the customs and conditions of living do not vary greatly in any of them, and the statement below enables a comparison to be made with the principal assigned causes of insanity in England and Wales. The following figures represent the proportion of each assigned cause to the total known causes for a period of five years:—

Cause.	Males.		Females.	
	New South Wales.	England and Wales.	New South Wales.	England and Wales.
	per cent.	per cent.	per cent.	per cent.
Domestic trouble, Adverse circumstances,				
Mental anxiety .....	9·4	13·1	12·0	14·5
Intemperance in drink .....	14·8	19·3	4·2	7·7
Hereditary influence, ascertained; Congenital defect, ascertained .....	18·5	20·5	21·2	22·8
Pregnancy, Lactation, Parturition, and Puerperal state, Uterine and Ovarian disorders, Puberty, Change of life .....			14·3	11·7
Previous attacks .....	15·2	13·5	18·5	18·5
Accident, including Sunstroke .....	5·4	4·8	0·9	0·6
Old Age .....	8·2	5·8	6·4	6·5
Other Causes ascertained.....	28·5	23·0	22·5	17·7

Intemperance in drink is popularly supposed to be the most fruitful cause of insanity in Australasia, but as will be seen from the above table hereditary influence is the chief factor both here and in England. The figures moreover prove that insanity arising from intemperance is not nearly so common in these states as in the old country. Amongst females, the chief causes of insanity in the states are hereditary influence and pregnancy, etc. It is believed that hereditary influence and congenital defect are responsible in New South Wales for a much larger percentage of cases than the number shown in the table, and that of the unknown causes the great majority should be ascribed to hereditary influences. The small proportion of cases set down to these two causes is simply due to the difficulty of obtaining knowledge of the family history of a large number of those who enter the asylums.

#### HABITATIONS.

The latest information available concerning the habitations of the people, is that obtained at the census of 1901, when inquiry was made on the householders' schedules respecting the dwellings of the population. The information sought was in respect to whether a building was occupied, unoccupied, or in course of construction; the material of



which it was built, and the number of rooms which it contained. The tabulation was not made with the same degree of completeness in all the states; but so far as comparative figures can be given they are shown below :—

Class of Dwelling.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	New Zealand.
Inhabited .....	252,502	241,41	98,737	60,856	48,506	34,165	158,898
Uninhabited .....	14,831	11,629	1,670	5,640	2,263	2,187	10,880
Being built .....	1,488	617	*	358	201	118	866
Total .....	268,771	253,656	100,407	75,854	50,970	36,470	170,593

\* Information not ascertained.

The materials of which the dwellings in each state were constructed are shown in the following table, so far as the particulars are available. In New South Wales, South Australia, Tasmania, Western Australia, and New Zealand the information is shown for all dwellings; in Victoria and Queensland for inhabited dwellings only. Dwellings made of canvas are most numerous in Western Australia, Queensland, and New South Wales. The large numbers of men living in tents engaged in mining in Western Australia, and in mining and on railway extensions in the two last mentioned states, will sufficiently account for the totals shown in this class.

Material.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	New Zealand.
Stone .....	10,793	8,469	300	45,136	3,931	8,069	7,517
Brick .....	92,879	63,627	2,248	13,479	3,872		....
Concrete, Placé .....	1,525	1,525	33	2,664	1,164		....
Iron, metal .....	5,380	1,337	6,215	2,787	5,589	23,653	....
Wood .....	140,482	157,112	77,419	9,471	12,296		158,945
Lath and Plaster .....	4,952		....	....	....		....
Mud, bark .....		2,896	1,604	....	495	1,304	1,688
Canvas (including tents) .....	8,374	3,423	9,606	1,564	18,923	869	5,116
Others and unspecified .....	3,886	3,021	1,309	753	495	2,585	2,327
Total .....	268,771	241,410	98,787	75,854	50,970	36,470	170,593

The number of rooms is given below for all houses, whether occupied or unoccupied, in the case of New South Wales, South Australia, Tasmania

and Western Australia ; for the other states the figures refer to inhabited dwellings only :—

Dwellings, with—	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	New Zealand.
One room .....	7,915	6,841	3,606	2,902	14,435	717	8,147
Two rooms.....	16,275	11,470	5,782	5,776	7,308	3,529	10,462
Three and four rooms .....	79,366	80,076	25,108	31,180	17,278	13,028	45,490
Five and six rooms .....	98,641	84,914	31,924	24,061	7,319	8,193	22,585
Seven to ten rooms.....	43,344	43,242	16,158	11,066	2,836	4,158	36,542
Eleven to fifteen rooms.....	6,923	5,615	2,104		647	1,963	
Sixteen to twenty rooms.....	1,612	1,157	548		226		
More than twenty rooms.....	1,205	900	529		200		
Number of rooms unspecified ...	5,889	3,763	423	849	612	2,632	547
Tents, etc.....	7,096	3,423	12,555	....	....	2,245	5,116
Total ...	286,771	241,410	93,737	75,854	50,970	36,470	158,993

In the case of those states where no information is given in the table respecting tents, etc., the returns are incorporated in the first two lines of the table. From the foregoing figures it will be seen that in Australasia there are over 5 persons to every occupied house.

## EDUCATION.

IT would have been strange if communities so prosperous as the Australasian States had neglected to provide for the education of the children. This duty, so vitally affecting the welfare of the people, has been recognised as one of the most important which the state could be called upon to discharge. In every province of the group, ample provision has been made for public instruction—such provision, indeed, in some cases, extending far beyond what has been done in most of the countries of the old world. In addition to a system of primary education, in all the states there are grammar and high schools, by means of which those who have the desire may qualify for the higher studies of the University. So bountiful is the provision made by the state that in most cases the cost of education is merely nominal, and the poverty of the parents ceases to be an excuse for the ignorance of the children. It is true that in the very early days of colonisation but little attention was paid to education; but so soon as the sharp struggle for bare existence was over, attempts were made to provide means of instruction for the rising generation, and the foundations were laid of an educational system that is in the highest degree creditable to these young communities. The religious bodies were naturally the first to build schools and provide teachers; but there was always a large proportion of persons who objected to denominationalism, principally those who belonged to denominations which were not subsidised by the state; hence there arose a national or non-sectarian system, which has in the course of time almost monopolised the educational field.

In all the Australasian provinces the state system of education is secular. Compulsory clauses find a place in the Acts of the various states; but the enforcement of these is not everywhere equally strict. In Victoria, for example, compulsory attendance at school has been rigorously insisted upon, while in Queensland the principle of compulsion has been allowed to remain almost in abeyance, and in the other states it has been enforced with varying degrees of strictness. In Victoria, Queensland, New Zealand, Western Australia, and South Australia the primary education provided by the State is entirely free of charge to the parents; in New South Wales and Tasmania small fees are charged, but these are not enforced where the parents can reasonably plead poverty.

The statutory school-age in each state is as follows :—

New South Wales .....	over 6 and under 14 years.
Victoria .....	„ 6 „ 13 „
Queensland .....	„ 6 „ 12 „
South Australia .....	„ 7 „ 13 „
Western Australia .....	„ 6 „ 14 „
Tasmania .....	„ 7 „ 13 „
New Zealand.....	„ 7 „ 13 „

Exemption certificates are granted to pupils below the maximum school age, provided they can pass an examination of a prescribed standard.

In New South Wales, for many years, a dual system of education was in existence. The four State-aided denominations—the Church of England, Roman Catholic, Presbyterian, and Wesleyan bodies—had schools supported by annual votes from Parliament, administered under the control of the head of each denomination for the time being. There were also National schools, likewise supported by the State, but under the control of a Board appointed by the Government. This plan was found to be costly and wasteful in the extreme, for in many country towns there were in existence several small and inefficient competing schools where the total number of children was not more than sufficient for one well-conducted establishment. So strongly was this evil felt that changes in the law were made from time to time, until at length the denominational system was abolished altogether, and one general and comprehensive plan of public instruction adopted in its place. This reform was not accomplished without much agitation, extending over a considerable period. A league was formed with the object of securing the establishment of secular, compulsory, and free education, and in 1880, under the auspices of Sir Henry Parke, the measure establishing the present system became law. Education in the public schools is now non-sectarian, though facilities are afforded to clergymen to give religious instruction within specified school-hours to children whose parents belong to their denomination and desire that this instruction shall be given. It is compulsory, and free to all who cannot afford to pay, while a merely nominal fee is charged to those who are in a position to contribute towards the cost of the teaching of their children. For secondary education there are a number of superior and high schools entirely supported by the state, besides numerous colleges, grammar schools, and denominational schools which obtain no assistance from the Government, excepting the Sydney Grammar School, which receives a statutory endowment of £1,500. Scholarships and bursaries have been founded in connection with many of these schools. The University of Sydney, which is liberally endowed by private individuals as well as by the state, grants degrees which rank with those of Oxford and Cambridge. Educational affairs in the state are under the direction of a Minister for Public Instruction. In 1902 two Commissioners were appointed by the Government to

visit Europe and America and report upon the best educational methods pursued in those countries. Special attention was devoted by this Commission to the question of technical education.

In Victoria, under an Act passed in 1872, a system of free, compulsory, and secular primary education is in force, under a Minister of Public Instruction, who is responsible to Parliament. The compulsory clause is very strictly enforced, especially in the large towns, and education is entirely free as regards the ordinary subjects of primary instruction, while the teachers are allowed to impart instruction in additional subjects, for which a small fee is payable. The teaching of religion is strictly forbidden during school-hours, and at no time must a state teacher give religious instruction. At the close of 1901 an important Amending Bill was passed. The main provisions of this measure were designed to strengthen the compulsory clauses of the Act, and to raise the age at which children can be excused from attendance at school to 14 years. No certificates of exemption can be granted to a child below 12 years of age. A Director of Education has been appointed who will, subject, of course, to the Minister, administer all laws relating to education. Secondary education is almost entirely in the hands of private or denominational establishments. The higher education is supplied by the University, with its affiliated colleges.

The Education Department in Queensland is administered by the Secretary for Public Instruction. The Act now in force was passed in 1875, and is of a tolerably liberal character, primary education being secular and free. An Amendment Act came into operation in 1898, extending the range of subjects taught in State schools and reducing the number taught in the Provisional schools. In July, 1900, seven attendance officers were appointed, and steps taken to put in operation the provisions of the Act of 1875 regarding regular attendance at school. These officers did excellent service during the year, but, with a view to economy, they were retired in 1902, and their duties relegated to the police. The public schools are divided into two classes, termed State and Provisional schools. A State school must have an average daily attendance of not less than thirty children, and the local district must contribute one-fifth of the cost of establishing, maintaining, repairing, and making additions to the building. In 1899, Provisional schools which had previously received a subsidy not exceeding £50 for any single school, and not more than half the cost of new buildings and furniture, were placed on the same footing with regard to Government grants as the State schools. Secondary education is provided by grammar schools, which are liberally assisted by the State. The State has no University of its own, but sends a fair number of students to the Universities of Sydney and Melbourne. The system of extension lectures in connection with the University of Sydney has been extended to Queensland; and the Government has given consideration to the question of the establishment of a University in Brisbane.

The South Australian system of primary education, which was introduced in its present form in 1878, is very similar to the systems already described. Public instruction in the state is presided over by a responsible Minister, with an Inspector-General and other officials. It is compulsory, secular, and free. Until the end of 1891 a small weekly fee was payable by all parents able to do so; but at the beginning of 1892 primary instruction was made free until the scholar reached the age of 13 years or had been educated to the compulsory standard, and in 1898 the remaining fees were abolished by the Minister for Education. Children who have attained a certain standard of education are exempt from compulsory attendance. Religious instruction is not allowed except out of ordinary school-hours. There are two secondary schools in connection with the Department—the Advanced School for Girls at Adelaide, where pupils are prepared for the University Public Examinations, and the Agricultural School, where boys are prepared for entrance to the School of Mines and Agricultural College. In addition there are numerous high-class private and denominational establishments; and the University of Adelaide, though small, is efficient.

Under the Elementary Education Act of 1871, primary education in Western Australia is imparted in Government schools, which are entirely supported by the state. An Amendment Act passed in 1893 placed educational affairs in the state under the control of a responsible Minister, and afforded facilities for special religious teaching, half-an-hour per day being allotted to clergymen for the instruction of children of the same denomination. Another Amendment Act which came into force in 1894 abolished payment by results, and gave powers for the enforcement of compulsory attendance. Until 1895, private schools were also assisted from the public purse, on condition of submitting to Government inspection in secular subjects; but towards the end of that year an Act was passed abolishing the system of annual grants to denominational schools, and providing that during the year 1896 the state should hand over, as compensation for the abolition of these subsidies, the sum of £15,000, to be divided between the schools in like proportions to those which governed the distribution of the annual vote in 1895. Under the regulations of 1895, children were entitled to free education on account of inability to pay the fees, of living more than 1 mile from school, of having made 400 half-day attendances in the previous year, or of other reasons approved by the Minister, but the Education Act which came into operation in 1899 gave free education to all children of compulsory school age. There is a high school at Perth, which is subsidised by the state; and further encouragement is given to secondary instruction by the institution of scholarships which are open to competition.

In Tasmania the Treasurer holds the portfolio of Education, and has especial charge of matters relating to primary instruction. The permanent head of the department is styled Director of Education. There are public schools in every country town throughout the state,

and several in Hobart and Launceston. The principle of compulsion is in force in these two towns, the school age being from 7 to 13 years ; and special religious instruction is given by the Church of England clergy out of school-hours. Secondary education was at one time encouraged by exhibitions, but none have been granted since 1893. The University of Tasmania was established in 1890, and at first was merely an examining body, but in the beginning of the year 1893 a building was acquired and teaching provided for the purpose of enabling students to graduate in Arts, Science, and Laws. The first degree, one of B.A., was taken in 1894. The Government grants the institution an annual subsidy, the amount voted by Parliament in 1903 being £4,000.

Education at the public schools of New Zealand is free (except that at such as are also district high schools fees are charged for instruction in the higher branches) and purely secular. The attendance of all children between the ages of 6 and 13 years is compulsory, except in cases where special exemptions have been granted. There is a separate Department of Education, presided over by one of the responsible Ministers of the Crown, as in the other provinces of Australasia. The whole colony has been divided into school districts, each presided over by a local Board, and a capitation grant of £3 15s. per head is paid by the State for every child in average attendance, and, in addition, 1s. 6d. per child in support of scholarships, with other grants for school-buildings, training of teachers, etc. In districts where there are few or no Europeans, native schools are maintained for the Maori children. High schools, colleges, and grammar schools provide the means for acquiring secondary education ; and the University of New Zealand, like those of the Commonwealth states, is empowered to confer the same degrees as the Universities of Oxford and Cambridge, except as regards Divinity. It is, however, only an examining body, the undergraduates keeping their terms at the affiliated colleges—the University of Otago, the Canterbury College, the Auckland University College, and the Victoria College at Wellington.

Interest in educational matters has undoubtedly undergone a marked revival in the course of the last few years throughout the whole of Australasia. In New South Wales it has been considered that the prevailing system of state education is capable of expansion and modernisation, and a commission was appointed in 1902 to inquire into and report upon the methods employed in the chief continental countries and in America and Great Britain. This Commission presented its report in 1903, and several drastic changes in present methods were advocated. The reforms aimed at which are briefly alluded to in the succeeding paragraph cannot, of course, be introduced immediately in their entirety, but the system is being moulded gradually in accordance with them. In Victoria the system has been to a large extent remodelled ; Queensland and Western Australia have recently revised their standards ; South Australia has introduced some valuable improvements, and reform is foreshadowed in New Zealand.

As regards actual school work, Kindergarten methods are more freely employed in the early stages, while throughout greater efforts are being made to avoid the purely abstract and to correlate with the concrete. More attention is being devoted to the cultivation of the powers of observation by the introduction of courses of lessons in nature study in which the pupils are encouraged to observe and where possible handle the objects under discussion. The importance of developing the physical as well as the mental powers of the scholar is also receiving increased recognition in various directions.

#### STATE SCHOOLS.

Exclusive of the native schools established by the New Zealand Government for the instruction of the Maori children, there were 9,034 public schools in Australasia at the close of the year 1903. The number in operation in each of the states, as well as in New Zealand, will be seen on reference to the table given below. As a rule, secondary education is provided by private institutions, and the figures quoted may be taken as representing primary schools; but in New South Wales there are four high schools, which it is customary to include with the others. The secondary schools in New Zealand are excluded from the returns:—

State.	State Schools.	Teachers employed, exclusive of Sewing Mistresses.		
		Males.	Females.	Total
New South Wales .....	2,862	3,068	2,386	5,454
Victoria .....	2,094	1,969	2,615	4,584
Queensland .....	1,006	1,137	1,241	2,378
South Australia .....	715	403	908	1,311
Western Australia .....	270	271	404	675
Tasmania .....	346	249	334	603
Commonwealth.....	7,293	7,097	7,908	15,005
New Zealand .....	1,741	1,417	2,278	3,695
Australasia .....	9,034	8,514	10,186	18,700



In all the states, with the exception of Victoria, there has been a steady increase in the number of State schools during the past few years. In Victoria the reverse has been the case, for since 1891 the number in operation has decreased from 2,233 to 2,094. This is the result of a scheme of retrenchment, initiated at that time, by which there has been an amalgamation of schools in large centres of population; and in other districts schools have been closed and the pupils conveyed to other institutions at the cost of the state. The latest official returns give the number of schools converted into adjuncts as 84, while 270 others were closed and the children conveyed to central institutions in the various districts. Expenditure on conveyance for the year ended 30th June, 1903, amounted to £2,536.

The 1,006 schools in Queensland include 450 State schools, 108 special provisional schools, 445 ordinary provisional schools, and 3 schools at benevolent establishments. In compliance with a resolution of the Legislative Assembly, the provisional schools, which had previously been receiving a subsidy not exceeding £50, and not more than half the cost of new buildings and furniture, were placed on the same footing as State schools in regard to subsidy. By this step the state assumed the responsibility for four-fifths of the cost of building and equipment without limitation as to the amount. For Western Australia, the returns for years prior to 1896 included State-aided denominational schools. From these establishments the Government subsidy was withdrawn at the end of 1895, and thenceforth they are not included in the returns of the Education Department. The private schools are, however, examined by the Departmental inspectors in order to ascertain that sufficient instruction is given in arithmetic, writing, reading, spelling, and geography, while the various registers are supplied to the principals free of cost. This should be borne in mind when comparing the figures with those given for previous years, otherwise the extension of public instruction in that state would seem to be incommensurate with the growth of population. As a matter of fact, the progress has been rapid, and 19 new state schools were opened in 1903.

As shown in the previous table, the total number of teachers employed in the 9,034 state schools was 18,700—8,514 males and 10,186 females—exclusive of sewing-mistresses, of whom there were 86 in New South Wales, 423 in Victoria, 9 in South Australia, 64 in Western Australia, 88 in Tasmania, and 176 in New Zealand. New South Wales is the only state where employment is afforded to a greater number of male teachers in comparison with females; in all the other provinces there is a large preponderance of female instructors. In most of the states provision is made for the training of teachers. In New South Wales, the Fort-street Training School for male students had 32 students in training in 1903, 15 of whom held full-scholarships, 10 held half-scholarships, and 5 were non-scholarship students; while at the

Hurlstone Training School for female students there were 42 students in residence, 15 of whom held full-scholarships, 11 half, and 16 non-scholarships. At the Fort Street Training College, residence and board and lodging are not provided, but full-scholarship students receive an allowance of £72 per annum, and half-scholarship £36, while no allowance is granted to non-scholarship students. The Hurlstone College is a residential institution and, scholarship students receive free board and lodging with an allowance of £1 per month, half-scholarship students pay £15 a year and receive an allowance of 10s. per month, and non-scholarship students pay £30 per annum. The Victorian Training College, which was closed for some time in accordance with the policy of retrenchment, was re-opened in 1900. On the 30th June, 1903, there were 68 students attending the College of whom 29 were in their first year. There were 38 students in the training college in South Australia. A scheme for the more efficient training of pupil-teachers has been arranged, under which, for the first two years of their course, these young people will not be required to teach, but will receive instruction at the Pupil Teachers' School. For the third and fourth years they will engage in practical teaching, and may then be entered as students at Adelaide University for a period of two years. In addition to the 79 pupil teachers of the first and second grade who attended daily at the institution, 53 others received tuition on Saturday mornings, and 7 were taught by correspondence, while 14 boys were also in attendance who had gained exhibitions entitling them to free tuition for three years, in accordance with the Education Regulations of 1900. In 1902 a Training College was opened in Western Australia. The building is situated at Claremont, about half-way between Perth and Fremantle, and is open for both day and resident students of both sexes. There is accommodation for 60 students and the first session opened with a total of 41, of whom 30 were females. In March 1904 there were 15 male and 37 female students, or a total of 52, of whom 37 were in residence. In New Zealand, teachers are trained at normal schools in Christchurch and Dunedin and at the Napier Training School. An interesting experiment in connection with the training of teachers was the holding of a Summer School in Victoria at the close of 1901. About 600 teachers applied for permission to attend, and of these 120 were selected. Lectures on such subjects as Principles of Education, Kindergarten, etc., were given by experts, and the experiment proved so successful that the institution has now become an annual one, and the idea has been taken up with enthusiasm in some of the other states.

Within recent years it has come to be more or less clearly recognised that the pupil teacher system, as prevailing in these states, is not conducive to the acquirement of a satisfactory degree of professional ability, while the Training Colleges are hampered in their operations from the fact that they are dependent on the pupil teachers for their main supply

of students. Instead of allowing these young people to teach with varying degrees of success for a certain period and then admitting them to a Training College, it is proposed to give a course of training antecedent to appointment in the schools. It will be seen from a preceding page that this idea has received practical application in the state of South Australia. In New South Wales it is proposed to establish normal schools at various centres for the purpose of training teachers, and to enlarge the scope of the present training schools.

#### ENROLMENT AT STATE SCHOOLS.

The average enrolment of pupils at the State schools of Australasia for the year 1903 and the proportion such figures bear to the total population is given in the following table :—

State.	Average Enrolment.	Percentage of Population.
New South Wales.....	213,318	14·99
Victoria .....	207,040	17·10
Queensland .....	90,025	17·37
South Australia.....	57,145	15·56
Western Australia.....	24,532	11·14
Tasmania.....	18,506	10·42
<hr/>		
Commonwealth.....	610,656	15·59
New Zealand... ..	133,748	16·31
<hr/>		
Australasia .....	741,404	15·71

It will be seen that the largest percentage of the population enrolled at state schools was to be found in Queensland, and the lowest in Tasmania. Such a comparison, however, is of very little value, because the proportion which the children of school age bear to the total population varies considerably in the different states, being as low as 14 per cent. in Western Australia, up to 17 per cent. in Queensland and South Australia, and 19 per cent. in New South Wales. In Western Australia, which is still in its pioneer stage, there must of necessity be a much smaller percentage of dependent children than in the more widely settled states.

More important, perhaps, than the number of children enrolled is the average attendance. This, for scholars at the state schools during the year 1903, was 563,765, representing about 62 per school and 30 per

teacher, and 11·90 per cent. of the population of Australasia. The figures for the individual states will be found appended :—

State.	Scholars in average attendance.			
	Total.	Per School.	Per Teacher.	Per-centage of popula-tion.
New South Wales .....	154,382	54	28	10·85
Victoria .....	149,841	71	32	12·38
Queensland .....	69,759	69	29	13·46
South Australia .....	42,587	59	32	11·60
Western Australia .....	20,283	75	30	9·21
Tasmania .....	13,866	40	23	7·77
Commonwealth .....	450,719	62	30	11·51
New Zealand .....	113,047	65	31	13·78
Australasia .....	563,765	62	30	11·90

It will be seen from the above table that the highest percentage was shown by New Zealand with 13·78 per 100 of the population, closely followed by Queensland with 13·46 per cent. The percentage of the population of New Zealand—13·78—shown as in average attendance at the state schools, it must be remarked, is rather higher than it should be, on account of a number of Maori children attending the ordinary schools in districts where there are none established for the “natives,” while the basis on which the proportion has been calculated is the population exclusive of aborigines. The “Native” schools in New Zealand, of which the number was 101, had a teaching-staff of 176, exclusive of 12 sewing-mistresses, in 1903, with an enrolment of 3,693 and an average attendance of 3,012 scholars, and the expenditure on the schools during the year amounted to £28,719. Of the 3,693 children enrolled at these schools, 81·3 per cent. were Maoris, or between Maori and half-caste, 9 per cent. were half-castes, and 9·7 per cent. were Europeans, or between half-caste and European.

#### COST OF PRIMARY EDUCATION.

The official reports of the various states show that during the year 1903 the cost of administration and maintenance of the State schools of Australasia was £2,530,618, while the revenue from fees, rents, sales of books, etc., amounted to £125,399, leaving a net cost to the state of £2,405,219, excluding a sum of £287,458 expended on school premises. Assistance to private schools where primary or secondary education is given is not included in these figures. The expenditure for each of the states will be found below. In the case of New Zealand, the amounts given in the table represent the disbursements of the Education Boards, and not the actual capitation grant received from the Government during 1903, as the former figures more accurately represent the cost of

the state schools for the twelve months. From the total cost to the state in that colony, the receipts from the Education Reserves, £44,506, have not been deducted, as the capitation grant is now reduced by an amount equivalent to the rents derived from these reserves, so that practically they are paid into the Consolidated Revenue. The figures do not give the whole expense to the state, as most of the principal teachers enjoy residences for which no rent charge is made. In the case of New South Wales, the annual value of these residences is about £38,000 :—

State.	Expended on Administration and Maintenance.	Receipts from Fees, Rents, &c.	Net Cost to State, excluding Premises.	Expended on School Premises.
	£	£	£	£
New South Wales.....	760,589	82,906	677,683	100,955
Victoria* .....	678,698	9,321	669,377	39,369
Queensland .....	277,786	.....	277,786	2,868
South Australia .....	147,951	11,404	136,547	11,805
Western Australia.....	108,658	1,919	106,739	36,305
Tasmania .....	64,612	12,472	52,140	667
Commonwealth .....	2,038,294	118,022	1,920,272	192,467
New Zealand .....	492,324	7,377	484,947	94,991
Australasia .....	2,530,618	125,399	2,405,219	287,458

\* Year ending 30th June, 1903.

In the states of Victoria, Queensland, South Australia, Western Australia, and in the colony of New Zealand, primary education is free; in the other states a small fee is charged, but, as will be seen from the table, the revenue derived from this source is very small in Tasmania. In New South Wales the fee charged is 3d. per week for each child, the sum payable by one family being limited to one shilling; and the receipts amount to a considerable sum annually, totalling £82,906 in 1903. Free education is, of course, given to those children whose parents cannot afford to pay for them, and the number of children so treated during last year was 30,251—equal to 12·4 per cent. of the gross enrolment of distinct pupils; the average for the last five years being 12·1. In Tasmania, at the beginning of 1901, new regulations came into force, under which school fees, which had till then constituted part of teachers' incomes, are paid into the Treasury, the teachers receiving, by way of compensation, an addition to their salaries to an extent and for a period exactly defined. Free education is granted in cases of necessity, and for this purpose free public schools were established in Hobart and Launceston; but as it was considered that this system affixed a brand of pauperism to the children making use of them, they have now been abolished, and the pupils find free education at the ordinary schools. In 1899 an Education Act was

passed in Western Australia, which had for its chief object the granting of free education to all children of compulsory school age. The work of compulsion was also systematised, and the returns for 1903 show the highest percentage of attendance for any year since 1872.

Although primary instruction is free in Victoria, Queensland, South Australia, Western Australia, and New Zealand, yet Queensland is the only state where no fees were received in 1903; but, as pointed out on a previous page, the state receives contributions from local districts towards the construction of school buildings, the amount of such contributions in 1903 being £2,036. In Victoria fees are charged for instruction in extra subjects, such as book-keeping, shorthand, algebra, Euclid, French, Latin, Science, &c., but the instruction is given by visiting teachers as well as the regular staff teachers outside of statutory school hours. During last year the number of pupils paying for extra subjects was returned as 6,571; but these figures do not indicate the actual number of individuals, as some pupils take more than one subject. The fees received amounted to £2,805; but this sum has not been included in the receipts, which totalled £9,321, and were made up of fines, rents, and the amount realised by the sale of publications; and although not directly applied by the state towards the reduction of departmental expenditure, have been so treated here. In South Australia the receipts during 1903 included £4,442 from sale of books and school materials, £6,714 from rent of dedicated land, and sundry receipts amounting to £248.

It will be seen from the previous table that, excluding the expenditure on school premises, the net cost of public instruction in Australasia in 1903 was £2,405,219. This is equivalent to £4 5s. 3d. for each child in average attendance during the year; while, if the expenditure on buildings is taken into account, the amount reaches £4 15s. 6d. per child. The figures for each of the six states and for the colony of New Zealand are presented below:—

State.	Net Cost to State, per scholar in average attendance.	
	Excluding School Premises.	Including School Premises.
	£ s. d.	£ s. d.
New South Wales .....	4 7 9	5 0 10
Victoria .....	4 9 4	4 14 7
Queensland .....	3 19 8	4 0 6
South Australia .....	3 4 1	3 9 7
Western Australia .....	5 5 3	7 1 6
Tasmania .....	3 15 2	3 16 2
Commonwealth .....	4 5 2	4 13 9
New Zealand .....	4 5 9	5 2 7
Australasia .....	4 5 3	4 15 6

Expenditure on education in a large State like Western Australia, with a sparse but rapidly-expanding population, must of necessity be proportionately higher than in the older settled Eastern States. For the half-time schools, the cost per scholar in average attendance during 1903 was as high as £11 5s. 11d., while for the special schools in the North-west the expenditure was as much as £10 0s. 3d. per head of the average attendance. The figures for administration are also swollen by reason of the fact that private schools are inspected by the Departmental officers, and also receive various registers free of cost. The figures for Victoria show a considerable decrease on the average for the preceding year, the falling off being chiefly due to a smaller expenditure on buildings, the disbursements in this respect amounting to £39,369 in 1903 as compared with £81,946 in the preceding year. All the states show increases in expenditure on administration and maintenance per child in average attendance as compared with the figures for 1897-98. For New South Wales the increase amounted to 14s. 8d. per scholar; for Victoria, to 7s. 3d.; for Queensland, to 12s. 10d.; for South Australia, to 3s.; for Western Australia, to 10s. 11d.; for Tasmania, to 19s. 7d.; and for New Zealand, to 9s. 1d.

#### ENCOURAGEMENT OF SECONDARY EDUCATION.

Before passing to the consideration of private schools, reference may be made to the encouragement of secondary education by the state, apart from grants to the Universities. In New South Wales there are numerous private colleges of a high class, and there are four State High Schools—two for boys and two for girls—where higher education may be obtained at a moderate cost; as well as 129 Superior Schools, in the higher classes of which pupils are prepared for the public examinations. In 1903 the expenditure on the High Schools amounted to £6,580. A scheme of scholarships for the Sydney Grammar School, for High and Superior Schools, and for the University, is in existence. In 1903, 107 candidates were successful at these examinations. Fifty-one secured scholarships and 43 bursaries for High and Superior Schools; 3, bursaries at the Sydney Grammar School; and 10, University bursaries.

In Victoria, as previously pointed out, extra subjects are taught for a small fee at 133 of the public schools. The pupils paying for this extra instruction in 1903 numbered 6,571, and the fees received by teachers £2,805. For the encouragement of secondary education, 200 scholarships were granted from 1886 to 1890, but in 1891 the number was reduced to 100, and in 1892 to 75. Consequent on the retrenchment policy already alluded to, these scholarships were abolished in 1893, but the principals of private colleges offered a large number of exhibitions to children attending state schools. The Department,

however, decided to introduce paid scholarships similar to those withdrawn in 1893; and under the new scheme, 60 exhibitions of the annual value of £10 are awarded, the first examination for which was held in December, 1900. For the year 1902-3 the expenditure on scholarships and exhibitions amounted to £4,286.

Steps have recently been taken in Queensland to add to the curriculum of the state schools, in order that they may be brought more into line with the superior public schools of New South Wales. Secondary education, however, has long been provided for by the liberal endowment of the private grammar schools, and by a system of scholarships for these schools, which at present number ten. Each school is subsidised to the extent of £1,000 annually; and the total amount of endowments and grants by the state to these institutions to the end of 1903 was £273,035. At the annual examinations for scholarships, 186 boys and 97 girls competed, and scholarships were gained by 27 boys and 9 girls, while 6 boys and 2 girls were awarded bursaries. Three pupils of secondary schools also qualified for exhibitions to Universities. In the last quarter of 1903 there were altogether 100 state scholars in attendance at the various grammar schools, while there were in addition 14 attending other approved secondary schools. Of the 78 exhibitions granted since the year 1878, when they were first instituted, 59 have been gained by students who had previously won scholarships from state schools.

In South Australia the Advanced School for Girls was attended by 113 pupils in 1903. The fees amounted to £853, to which should be added an allowance of £506 on account of bursary holders, while the expenditure was £1,228. There are twelve bursaries for this school annually awarded to state school pupils. Six University scholarships of the value of £35 each are annually awarded to day students on the recommendation of the University Council, and 18 other scholarships of £10 each are awarded to evening students. There are also available 24 exhibitions and 24 bursaries for boys and girls, and 20 junior scholarships are offered annually to pupils attending schools under the Minister. In Western Australia there is a high school for boys at Perth, which in 1902 received Government aid to the extent of £1,000. The number of pupils on the roll, including boarders, was 96, and the average daily attendance was 93. Two state scholarships for this school, valued at £75 each and tenable for three years, are awarded annually. The Government also offers annually ten bursaries of the value of £10 to children attending the elementary schools of the state—five to boys, and five to girls. In Tasmania a system of exhibitions was at one time in force, but none have been granted since 1893. New Zealand has 25 incorporated or endowed secondary schools, with a regular teaching staff of 173, and a visiting staff of 62. At the end of 1903 there were 3,722 pupils on the rolls, and the average attendance for the year was 3,455. The receipts for 1903 amounted to £61,767, including £28,577 derived from interest on investments and rents of



reserves, and £31,204 from fees. These schools, it should be noted, are not supported directly by the state. Some have endowments of land, and others receive aid from the rents derived from the Education Reserves administered by the School Commissioners.

## PRIVATE SCHOOLS.

At the end of 1903 there were 2,582 private schools in Australasia, with a total teaching staff estimated at 8,600. The total number of pupils on the rolls was 160,698, and the average attendance, 132,294. Below will be found the figures for the individual states and for New Zealand. At the end of 1895, the Government subsidy was withdrawn from the assisted schools in Western Australia, and, thenceforward, information respecting these institutions is incorporated in the returns for private schools :—

State.	Schools.	Teachers.	Enrolment.		Average Attendance.
			Total.	Percentage of Population.	
New South Wales..	841	3,368	58,258	4·09	46,982
Victoria .....	798	2,369	45,650	3·77	36,794
Queensland .....	181	721	15,721	3·03	13,359
South Australia ...	205	654	10,269	2·79	9,330
Western Australia	92	346	6,757	3·06	5,618
Tasmania .....	177	302	8,943	4·95	6,800
Commonwealth	2,294	7,760	145,498	3·71	118,883
New Zealand .....	288	840	15,200	1·85	13,411
Australasia ...	2,582	8,600	160,698	3·39	132,294

In New South Wales during the ten years 1894–1903 the number of private schools reached its highest point in 1899, when there were

no less than 1,053 schools, with 47,560 scholars in average attendance. Since that year, however, the numbers steadily declined, until in 1903 the returns showed 841 schools, with an average attendance of 46,982. The decrease is partly attributable to the extension of the public school system. Of the private schools in the state, 350 are Roman Catholic, as compared with 70 connected with the other Churches, while 421 are undenominational; but of the scholars enrolled, 40,989, or over 70 per cent., are in attendance at Roman Catholic schools, while 4,466 attend Church of England schools; 1,447, schools belonging to other denominations; and 11,356, the undenominational schools. Since 1894 the pupils of the Roman Catholic schools have increased by 16·6 per cent., which is over 2 per cent. higher than the general rate of increase. Many of the private schools are institutions of a high class. Only one—the Sydney Grammar School—is assisted by the State, which provides a statutory endowment of £1,500 per annum. In 1903 the staff of this school consisted of 25 teachers; the total enrolment was 649; the average enrolment, 545; and the average daily attendance, 519. The receipts for the year totalled £10,914, of which £9,225 represented fees; while the expenditure was £11,108.

From returns furnished by the principals of private schools in Victoria, it appears that the total number of institutions has decreased from 867 in 1894 to 798 at the 30th June, 1903, while the gross enrolment increased from 44,038 to 45,650 during the same period. These colleges are not subsidised by the state.

Of the 181 private schools in Queensland, the principal are the ten grammar schools, which are situated at Brisbane, Ipswich, Maryborough, Rockhampton, Townsville, and Toowoomba. In each of the first four towns there are two schools—one for girls and one for boys. In 1903 the teaching staff of the grammar schools consisted of 55 permanent and 20 visiting teachers; the aggregate number of pupils on the rolls was 1,027; and the average daily attendance, 865. As previously mentioned, each of the ten schools receives an annual grant of £1,000 from the state, the Townsville school received also a loan of £2,000 during 1903. The total receipts for the year amounted to £30,371, and the expenditure, including salaries, to £30,355.

There is no special information available with respect to the private schools in South Australia. Of the 92 private schools open in Western Australia at the end of 1903, 43 were Roman Catholic institutions, with an enrolment of 4,921 pupils, or 78·6 per cent. of the total. The principal private institution is the Perth High School for Boys, which, in 1903, received Government aid to the extent of £1,000. The school is under the supervision of a Board of Governors. According to the latest returns the teaching staff numbered 5; the total number of pupils enrolled was 96, of whom 26 were boarders; and the average daily attendance was 93.

Included with the 177 private schools in Tasmania are 21 grammar schools and colleges, 8 of which are undenominational in character,

7 are connected with the Church of England, 3 with the Roman Catholic Church, 1 with the Wesleyan Church, 1 with the Presbyterian Church, and 1 with the Society of Friends. There were 112 permanent teachers at these institutions in 1903, and accommodation was provided for 3,384 students. The average attendance during the year was 2,383, of whom 996 were of the age of 15 years and upwards. As in New South Wales, the majority of the pupils at private institutions in New Zealand are enrolled at the Roman Catholic Schools. At the end of 1903 the number of schools belonging to this denomination was 139, at which 10,812 scholars were enrolled, with an average daily attendance of 9,207.

#### DIFFUSION OF EDUCATION.

It will be seen that the Governments of the various states have done much for the instruction of the children, and throughout Australia and New Zealand attendance at school of children of certain ages is compulsory. Unfortunately, in spite of the law and in spite of the educational facilities afforded by the states, large numbers of children are growing up in total ignorance, and a large number with very little instruction. It must not be supposed that the officials of the public departments controlling instruction are to blame for this lamentable state of affairs; on the contrary, they have made, and continue to make, protests against the continuance of the evil, but the rescuing of children from the neglect of parents, and the effects of their own depraved inclinations, does not seem to appeal very strongly to the legislatures of these States.

As regards New South Wales the census returns for 1901 showed that there were 17,464 children of school age, that is 6 and under 14 years, who were not receiving instruction either at school or at home. If allowance be made for those who possessed certificates showing that they had been educated up to the requirements of the Education Act, and who numbered approximately 5 percent. of the number quoted, there still remain about 16,600 children presumably growing up in blank ignorance. In addition to these a large proportion of the scholars enrolled at state schools fail to attend the requisite 70 days in each half-year. With respect to private schools the state has no means of ascertaining whether the teachers are competent to impart instruction, while nothing can be said regarding regularity of attendance at these institutions as the principals are not compelled to produce returns. Legislation to cope with the truancy evil is in contemplation by the state. At present the parents of children attending public schools are liable to prosecution if their children do not attend the number of days prescribed by the Act. Private schools are not interfered with, while there is no adequate provision made for tracing and dealing with children who are not enrolled at any school.

In Victoria, the census returns for 1901 showed that the total number of children of school age, that is 6 to 13 years, was 197,704,

and of these the number receiving instruction either at school or at home was 184,200, so that apparently there were 13,504 children growing up in ignorance. Deducting a small percentage on account of those who while not at school were yet in possession of certificates of exemption there will be left upwards of 12,000 uneducated.

In Queensland there were at the census of 1901, 75,179 children of school age, that is over 6 and under 12 years of age, and of these 71,830 were receiving instruction at school or being taught at home, so that there were 3,349 uneducated. Of these it appears that in the majority of instances the degree of education was not stated on the schedule, but there is every probability that the greater number were uninstructed. With respect to the 3,100 children who were presumably taught at home, there is of course no guarantee that the instruction received was up to standard requirements.

In South Australia the children of school age, that is 7 to 13 years, numbered 62,720 at the census of 1901. Of these the total number under instruction at school or at home was returned as 54,471, leaving 8,249 not attending school, and presumably growing up in ignorance. In Western Australia the children of school age, that is 6 and under 14 years, numbered 26,335 at the census of 1901. The total under instruction was returned as 24,333, and the remaining 2,002 were therefore uneducated.

The Tasmanian census returns for 1901 showed a total of 26,122 children of the school ages 7 to 13 years, of whom 23,676 received instruction at school or at home, the remaining 2,446 apparently being illiterate. The New Zealand census returns for 1901 record a total of 170,961 children between 5 and 15, of whom 157,803 were receiving education, leaving the apparently illiterate as 13,158.

In addition to the numbers recorded as not receiving instruction in the various states there is also to be reckoned the percentage of children who while attending school do not comply with the standard requirements respecting the yearly attendances. To what extent irregularity prevails in regard to private schools there is no means of ascertaining, the returns from the public schools, however, indicate a greater or less degree of laxity in this respect.

#### UNIVERSITY EDUCATION.

The advance of education is hardly more clearly indicated by the institution and success of Colleges and Universities than is the progress of wealth or the attainment of leisure. In Australia the earliest attempts to provide for what may be termed the luxuries of education were made in New South Wales in 1852, and in Victoria in 1855, when the Universities of Sydney and Melbourne respectively were established. No other province of Australasia was at that time sufficiently advanced in wealth and population to follow the example thus set; but New Zealand in 1870, South Australia in 1874, and

Tasmania in 1890, each founded a University. The Universities are in part supported by grants from the public funds, and in part by private endowments and the fees paid by students.

The income received by the Sydney, Melbourne, Adelaide, and Tasmanian Universities in 1903 was as follows :—

University.	Government Endowment.	Lecture Fees.	Other Sources.	Total.
	£	£	£	£
Sydney.....	15,533	13,338	18,502	45,373
Melbourne .....	13,500	9,811	6,787	30,098
Adelaide .....	6,611	9,554	4,800	20,965
Tasmania.....	4,000	449	608	5,057

The item "Other Sources" includes, in the case of New South Wales, receipts from various benefactions, the most important of these, the Challis bequest, being valued at over £268,000.

In addition to the annual endowment, the Adelaide University has received a perpetual endowment of 50,000 acres of land from the Government of South Australia. The University of New Zealand has a statutory grant of £3,000 a year from Government, and an additional income of about £2,500 from degree and examination fees. Of the affiliated colleges, Auckland University College is in receipt of a statutory grant of £4,000 a year from Government. The University of Otago derives a sum of about £5,500 annually from rents of reserves.

The number of students attending lectures in 1903 is shown below. In New Zealand the students keep their terms principally at the University of Otago, the Canterbury College, the Victoria College, and the Auckland University College.

University.	Students attending Lectures.		
	Matriculated.	Not Matriculated.	Total.
Sydney .....	724	53	777
Melbourne .....	509	119	628
Adelaide .....	343	299	642
New Zealand .....	646	216	862
Tasmania.....	51	11	62
Total .....	2,273	698	2,971

Attached to the University of Sydney there are three denominational colleges for male students, and a fourth, undenominational in character, for female students. In Melbourne there are three affiliated denominational colleges, one of which contains a hall for the accommodation of female students. In Adelaide and Hobart there are no affiliated colleges attached to the University; and in New

Zealand the University itself is an examining and not a teaching body, the students keeping their terms at three undenominational colleges at Dunedin, Christchurch, and Auckland, besides several smaller institutions which have supplied a few graduates.

The Australasian Universities are empowered to grant the same degrees as the British Universities, with the exception of degrees in Divinity. In all the Universities women have now been admitted to the corporate privileges extended to male students; and at the Sydney, Melbourne, and Adelaide Universities this includes qualifying for degrees in medicine.

The number of degrees conferred by the five Universities, including, in the case of Sydney, Melbourne, and New Zealand, those bestowed on graduates admitted *ad eundem gradum*, is as follows :—

Sydney.....	2,261
Melbourne .....	3,618
Adelaide .....	256
New Zealand .....	1,071
Tasmania .....	64

#### TECHNICAL EDUCATION.

Technical instruction is given in nearly all the capital cities of Australasia, as well as in many other parts of the country, and the question of extending the scope of the teaching in the various subjects is at present occupying the attention of the authorities in several of the states. The State expenditure on this important branch of education in five of the Commonwealth provinces and in New Zealand will be found below; information for South Australia is not available :—

	£
New South Wales .....	26,459
Victoria.....	16,430
Queensland .....	7,168
Western Australia .....	5,712
Tasmania .....	2,464
New Zealand .....	21,024

In New South Wales, during the year 1878, a sum of £2,000 was granted by Parliament towards the organisation of a Technical College, and for five years the work of the institution was carried on in connection with the Sydney School of Arts. In 1883, however, a Board was appointed by the Government to take over its management, and the Technical College thenceforth became a State institution. Towards the end of 1889 the Board was dissolved, and the institution came under

the direct control of the Minister of Public Instruction. The College, which, with the Technological Museum, is housed in a fine building at Ultimo, Sydney, is open to both male and female students. Branch technical schools have been established in the suburbs of Sydney and in many of the country districts, and technical instruction is also given in some of the public schools. In 1903 there were 477 technical classes in operation, of which 243 were held in Sydney and suburbs, and 234 in the country districts, while there were in addition 86 classes held in connection with the public schools. The enrolment at these classes was 16,561, namely, 9,556 in Sydney and suburbs, 4,200 in the country districts, and 2,805 at the public schools. The number of individual students under instruction during the year was 13,232, and the average weekly attendance 8,671. In 1896 a Technical College was opened at Newcastle, and a new College at Bathurst in June, 1898. In 1902 a Technical School was built at Lithgow, and Mechanical Engineering Shops were provided at Newcastle. During the year the expenditure by the Government on technical education amounted to £26,459, exclusive of expenditure on the Technical Museum and branches. Fees to the amount of £8,707 were received from the students.

Technical education in Victoria has extended rapidly, but while the Government of New South Wales has wholly borne the cost of this branch of instruction, that of Victoria has received great assistance from private munificence, the Hon. F. Ormond, M.L.C., having given £15,500 to assist in the establishment of a Working Men's College. In 1903 there were 18 Schools of Mines and Technical Schools receiving aid from the state. The total state expenditure during the year was £16,430, and the fees received from students amounted to £11,741. The average number of students enrolled was 3,173. In addition classes in manual training and in cookery and domestic economy are held at various centres, the net expenditure on these branches amounting in 1902-3 to £3,437. The question of more closely relating the work of the schools to the industrial conditions of the districts wherein they are situated is under consideration, and it is intended to withdraw the subsidy from those schools which fail to attract a sufficient number of students, or which do not supply a real need in local industrial requirements.

Technical education has well advanced in South Australia. The School of Design in Adelaide during 1903 had 577 students on the roll, and there were branch schools at Port Adelaide and Gawler with an enrolment of 35 and 17 students respectively. The School of Mines and Industries, founded in 1889, received Government aid in 1903 to the extent of £3,658, while the receipts from fees and sale of materials to students amounted to £3,691. Manual instruction is imparted in the public schools, and special instruction in agriculture is also given at various country centres. At the Adelaide Agricultural School 117 pupils were enrolled during the year, and there was an average attendance of 77·3.

In Queensland technical education has received some attention, and a Board of Technical Instruction was appointed in 1902, its functions being to report concerning existing colleges and advise with respect to the establishment of new institutions. The Board conducted its first examination at the close of 1903, when 960 students were examined, of whom 664 gained certificates of competency. There were 20 technical schools distributed in various centres in 1903, and the number of individual students was given as 2,600. The receipts of the various colleges amounted in 1903 to £13,385, and the expenditure to £14,280.

In Tasmania the foundations of new Technical Schools were laid in 1889 in Hobart, and there is a branch school in Launceston. The schools are under the direction of local Boards of Advice, the members of which act directly under the Minister in charge of education. The average attendance of students in 1902, including those in the two Schools of Mines, was 540. The expenditure for the year came to £2,886.

In Western Australia a Technical School was opened in Perth during 1900. The number of individual students on the roll during the last quarter of 1903 was 223, of whom 38 were females, and the average attendance for the year was 190. The expenditure amounted to £5,712. Classes for manual training and domestic economy have been established in various centres, the average daily attendance for the year being 455.

In New Zealand the Manual and Technical Instruction Acts of 1900 and 1902 provide for instruction in manual and technical subjects in accordance with specified regulations, and the recognised classes are entitled to receive capitation allowances in addition to grants in aid of buildings, furniture, and apparatus. The subjects taught in the school classes include woodwork, cottage gardening, swimming and life-saving, ambulance work, dressmaking, laundry work, and cookery. During 1903 there were 2,227 classes in operation. Of these, 1,659 were classes in handwork at the primary or secondary schools, while 568 were special, associated, or college classes, providing instruction in pure and applied art, engineering, science, plumbing, carpentry, domestic economy, and commercial subjects. The expenditure for the year was £21,034. In addition to the classes enumerated above there are several Schools of Mines in the chief mining districts, and the Government makes an annual grant of £500 towards the endowment of the chair of mining and metallurgy at the Otago University.

#### GENERAL EDUCATION.

Striking evidence of the rapid progress made by these states in regard to education is afforded by a comparison of the educational status of the people as disclosed by the five census enumerations of 1861, 1871, 1881, 1891, and 1901. In those years the numbers who could



# EDUCATION.

877

read and write, read only, and who were unable to read were as follows, children under five being considered unable to read, no matter how returned at the census :—

Degree of Education.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
1861.									
Read and write...	188,548	327,900	17,181	72,207	8,446	48,281	662,458	67,998	780,456
Read only .....	46,024	56,945	3,714	18,629	1,559	13,187	140,008	8,922	148,980
Cannot read .....	116,298	155,577	9,164	35,994	5,585	28,569	351,772	22,101	378,273
1871.									
Read and write...	296,741	478,572	74,940	115,246	18,708	55,989	1,040,141	177,419	1,317,560
Read only .....	56,391	70,999	12,080	21,123	2,614	13,945	177,152	19,240	196,392
Cannot read .....	150,849	181,967	33,084	49,257	4,036	29,444	445,627	59,734	508,361
1881.									
Read and write...	507,067	651,567	136,718	200,057	19,697	74,967	1,590,078	346,228	1,936,301
Read only .....	49,872	49,535	13,631	15,267	2,420	9,006	189,889	27,323	167,162
Cannot read .....	196,029	161,344	63,176	64,541	7,582	31,183	522,705	116,362	639,087
1891.									
Read and write...	835,570	906,767	276,881	236,514	34,254	108,188	2,394,624	484,198	2,878,822
Read only .....	43,536	52,817	14,618	9,571	2,061	6,287	106,890	24,902	138,792
Cannot read .....	244,848	196,821	102,719	74,346	13,497	87,242	671,449	117,558	789,001
1901.									
Read and write...	1,071,989	999,620	375,374	290,748	150,194	133,579	3,021,454	638,889	3,660,343
Read only .....	29,725	21,402	11,387	8,222	2,982	8,325	77,543	14,752	92,295
Cannot read .....	253,182	180,048	109,835	63,634	30,948	35,071	672,718	119,078	791,796

The figures in the preceding table refer to the total population, and the number of illiterates is therefore swollen by the inclusion of children under school-going age. If the population over 5 years of age be considered in comparison with the total population, the results for the whole of Australasia will be as follow :—

Degree of Education.	Whole Population.				
	1861.	1871.	1881.	1891.	1901.
Read and write .....	780,456	1,317,560	1,936,301	2,878,822	3,660,343
Read only .....	148,980	196,392	167,162	138,792	92,295
Cannot read .....	378,273	508,361	639,087	789,001	791,796
Total .....	1,252,699	1,922,313	2,742,550	3,801,615	4,544,434
Degree of Education.	Population over 5 years of age.				
	1861.	1871.	1881.	1891.	1901.
Read and write .....	780,389	1,180,145	1,936,111	2,878,813	3,660,343
Read only .....	143,908	190,545	161,295	128,445	92,295
Cannot read .....	168,929	585,266	245,583	263,515	279,552
Total .....	1,048,176	1,605,976	2,340,999	3,269,773	4,022,190

The following table affords a comparison of the number of each class in every 10,000 of the population for the same periods :—

Degree of Education.	Whole Population.					Population over 5 years of age.				
	1861.	1871.	1881.	1891.	1901.	1861.	1871.	1881.	1891.	1901.
Read and write ....	5,881	6,334	7,060	7,573	8,064	7,001	7,038	8,270	8,804	9,099
Read only .....	1,189	1,022	610	362	204	1,380	1,186	689	393	229
Cannot read .....	2,980	2,644	2,330	2,075	1,742	1,619	1,776	1,041	808	672
Total .....	10,000	10,000	10,000	10,000	10,000	10,000	10,000	10,000	10,000	10,000

It will be seen, therefore, that while in 1861 there were only 7,001 persons who could read and write out of every 10,000 people over 5 years of age, the number in 1901 had increased to 9,099, while those who were totally illiterate had in the same period decreased from 1,619 to 672.

Looking at the matter still more closely with reference to age, it will be seen that the improvement in education is most marked in the case of the rising generation. The following table shows the degree of education of all children between the ages of 5 and 15 years in 1861, 1871, 1881, 1891, and 1901, numerically and per 10,000:—

Degree of Education.	Total between 5 and 15 years.					Per 10,000 children.				
	1861.	1871.	1881.	1891.	1901.	1861.	1871.	1881.	1891.	1901.
Read and write	114,363	238,154	482,719	674,012	860,188	4,637	5,911	7,068	7,566	8,009
Read only ....	68,088	102,316	86,574	66,640	52,428	2,759	2,090	1,306	782	494
Cannot read ..	64,237	96,986	114,654	147,280	158,984	2,604	1,990	1,676	1,653	1,497
Total ..	246,628	437,456	683,947	890,932	1,081,600	10,000	10,000	10,000	10,000	10,000

The proportion of those able to read and write has, therefore, grown from 4,637 to 8,009 in every 10,000 children during the forty years which the table covers, while the number of those able to read only in 1901 was one-sixth of what it was in 1861, and the wholly illiterate had decreased by nearly one-half during the period.

The Marriage Register affords further proof of the advance of education, and it has the further advantage of giving annual data, while the census figures are only available for decennial periods.

The numbers of those who signed the Marriage Register by marks were as appended. Where a blank is shown the information is not available.

State.	1861.			1871.			1881.			1891.			1903.		
	Marriages.	Marks.		Marriages.	Marks.		Marriages.	Marks.		Marriages.	Marks.		Marriages.	Marks.	
		M.	F.		M.	F.		M.	F.		M.	F.		M.	F.
New South Wales.	3,222	590	989	3,953	573	768	6,234	347	525	8,457	273	248	9,759	113	101
Victoria .....	4,434	..	..	4,693	342	650	5,896	171	245	3,780	110	133	7,005	53	88
Queensland .....	820	..	..	970	..	..	1,703	84	109	2,905	89	109	2,983	50	59
South Australia .....	1,153	..	..	1,250	..	..	2,308	100	159	2,315	40	49	2,272	34	21
Western Australia .....	149	..	..	159	..	..	197	..	..	413	..	..	2,064	10	21
Tasmania .....	717	..	..	598	..	..	856	..	..	968	..	..	1,344	43	21
Commonwealth .....	10,000	..	..	11,623	..	..	17,244	..	..	23,858	..	..	25,977	303	261
New Zealand .....	878	..	..	1,864	..	..	3,279	105	190	3,805	53	64	6,748	26	42
Australasia .....	10,878	..	..	13,487	..	..	20,523	..	..	27,663	..	..	32,725	329	303

The percentages for those states for which the necessary information is available are worked out in the following table:—

Year.	Males.	Females.	Total.
1861 .....	18·50	30·69	24·60
1871 .....	10·58	16·40	13·49
1881 .....	4·14	6·61	5·38
1891 .....	2·12	2·27	2·20
1902 .....	1·03	0·98	1·01
1903 .....	1·01	0·93	0·97

The percentage in 1903 was, therefore, only about one twenty-fifth of that in 1861, and there is every reason to expect that in the course of another few years it will be still further diminished.

#### PUBLIC LIBRARIES.

In all the states public libraries have been established. The Public Libraries in Melbourne and Sydney are splendid institutions, the former comparing favourably with many of the libraries in European capitals. The following table shows the number of libraries which furnished returns, and the number of books belonging to them, for the latest year for which information is available:—

	No. of Libraries.	No. of Books.
New South Wales .....	340	520,000
Victoria .....	414	848,000
Queensland .....	163	203,680
South Australia .....	166	275,000
Western Australia .....	154	97,500
Tasmania .....	48	95,800
New Zealand .....	364	516,300
<b>Australasia .....</b>	<b>1,649</b>	<b>2,556,280</b>

## RELIGION.

THE progress of all matters relating to denominational Religion since the early years of Australasian settlement has been steady and remarkable. For the first fifteen years after the foundation of the colony of New South Wales, only a single denomination was recognised by Government or possessed either minister or organisation—the Established Church of England. In those days the whole of Australasia was ecclesiastically within the diocese of the Bishop of Calcutta, of which it formed an Archdeaconry; this continued until 1836, when the bishopric of Australia was constituted, and the Rev. William Grant Broughton, D.D. (formerly Archdeacon), was consecrated the first Bishop. In 1841 the bishopric of New Zealand was established, and in 1842 that of Tasmania. Considerable changes took place in 1847, when the dioceses of Melbourne, Adelaide (including South Australia and Western Australia), and Newcastle (including the northern portion of what is now New South Wales, and the whole of Queensland) were established, and the Bishop of Australia was styled Bishop of Sydney and Metropolitan of Australia and Tasmania. In 1857 the diocese of Perth was formed out of that of Adelaide, and in 1859 the diocese of Brisbane out of that of Newcastle; in 1863 the bishopric of Goulburn was separated from Sydney; in 1867 the bishopric of Grafton and Armidale was formed out of part of the diocese of Newcastle; in 1869 Bathurst was separated from Sydney; in 1875 Victoria was divided into the two dioceses of Melbourne and Ballarat; in 1878 the bishopric of Northern Queensland was established, with Townsville as seat of its Bishop; in 1884 the diocese of Riverina was formed out of parts of the dioceses of Bathurst and Goulburn; in 1892 parts of the bishoprics of Brisbane and Northern Queensland were formed into the new diocese of Rockhampton; in 1898 the bishopric of British New Guinea was established, and in 1900 the new diocese of Carpentaria was formed in Northern Queensland. While the six dioceses of New South Wales were united under a provincial constitution, with the Bishop of Sydney as Metropolitan, no such union existed in Victoria or Queensland, and the decision of the Lambeth Conference of 1897, granting the title of

Archbishop to Colonial Metropolitans applied, therefore, only to Sydney, whose Bishop thereby became Archbishop of Sydney.

Each state preserves its autonomy in church matters, but the Archbishop of Sydney is nominal head or Primate within the boundaries of Australia and Tasmania. In 1872 the ties between the churches in the various states under the jurisdiction of the Primacy were strengthened by the adoption of one common constitution. A general synod of representatives of each of these states meets in Sydney every five years to discuss Church affairs in general. New Zealand is excluded from this amalgamation, and possesses a Primacy of its own. As already stated, a Bishop of New Zealand was appointed in 1841. After various changes the constitution of the Church in New Zealand was finally settled in 1874, when the whole colony was divided into the six dioceses of Auckland, Waiapu (Napier), Wellington, Nelson, Christchurch, and Dunedin. After the departure of Bishop Selwyn, who has been the only Bishop of New Zealand, the Primacy was transferred to the see of Christchurch, where it remained until 1895. In that year the Bishop of Auckland was elected Primate of New Zealand. The missionary Bishop of Melanesia, whose headquarters are at Norfolk Island, is under the jurisdiction of the New Zealand primacy. At present, therefore, there are twenty-three bishops in the States, including the Bishop of Melanesia, but excluding assistant bishops. The synodical system of Church Government, by means of a legislative body, consisting of the clergy and representatives of the laity, prevails throughout Australasia, both in the individual states and as a group.

The Church of England has a larger number of adherents than any other church as well in each state as in the Commonwealth; its position is strongest in Tasmania and New South Wales, where its doctrines are professed by nearly half of the population; in Western Australia also it is a very powerful body, numbering 42 per cent. of the people of the state. The Church is proportionately weakest in South Australia with adherents numbering 30 per cent. of the total population. The adherents of the Church of England in Australia numbered 644,490 in 1871, 867,791 in 1881, 1,234,121 in 1891, and 1,497,579 in 1901, an increase of 853,089 in thirty years; in New Zealand the increase has been from 107,241 in 1871 to 314,024 in 1901, or 206,783 in thirty years.

In 1803 a grudging recognition was extended to Roman Catholics, one of whose chaplains was for some time placed on the Government establishment; but it was not until 1820 that any regular provision was made for the due representation of the clergy of this body. Until 1834 the Roman Catholics of Australia and Tasmania were under the jurisdiction of the Bishop of Mauritius (the Rev. Dr. Ullathorne being Vicar-General from 1830 to 1834), but in that year Sydney was constituted a see, and the Rev. John Bede Polding, D.D., was consecrated Bishop, with jurisdiction over the whole of the Continent and

Tasmania. In 1842 Hobart was established as a separate diocese, and Sydney became an archiepiscopal see. The diocese of Adelaide dates from 1843, that of Perth from 1845, and those of Melbourne, Maitland, Bathurst, and Wellington from 1848. During this year a diocese was established in the Northern Territory of South Australia, which since 1888 has been designated the diocese of Port Victoria and Palmerston. The bishopric of Brisbane was founded in 1859, and that of Goulburn in 1864. In 1867 the Abbey-nullius of New Norcia (Western Australia) was established. The dioceses of Armidale and Auckland date from 1869, and those of Ballarat and Sandhurst from 1874. In 1876 Melbourne became an archdiocese, and Cooktown was formed into a Vicariate-Apostolic. Other changes took place in Queensland in 1882, when the diocese of Rockhampton was founded, and in 1884, when the Vicariate-Apostolic of British New Guinea (with residence at Thursday Island) was established. In 1885 the Archbishop of Sydney was created a cardinal, and placed at the head of the Roman Catholic Church throughout Australasia. Following upon this appointment great alterations took place in the arrangement of dioceses in 1887, when the new dioceses of Lismore, Wilcannia, Sale, Port Augusta, and Christchurch, and the Vicariates-Apostolic of Kimberley and Queensland (the latter with jurisdiction over all the aborigines of the State) were established, and Adelaide, Brisbane, and Wellington became archdioceses. In 1888 Hobart was also made an archiepiscopal see; and a new see was established in 1898 at Geraldton, in Western Australia. At the present time there are six archbishops, sixteen bishops, three vicars-apostolic, and one abbot-nullius, or in all twenty-six heads of the Church with episcopal jurisdiction, irrespective of the Vicariate-Apostolic of British New Guinea and of several auxiliary and coadjutor-bishops.

The Roman Catholic Church occupies the second place in importance among the Churches of Australasia, and in each State, except South Australia, where the Methodist church is numerically stronger, and in New Zealand where its adherents are less numerous than the Presbyterians. In 1871, the Roman Catholics returned at the census of the Commonwealth States numbered 408,279, in 1881, 539,558, in 1891, 713,846, and in 1901, 855,799; this shows an increase of 447,520, in thirty years. In New Zealand the increase was from 35,608 to 109,823 in the same period, that is to say, of 74,214. Compared with the total population the Roman Catholic adherents were 23·1 per cent. in 1871 compared with 21·6 per cent. in 1901, thus showing a slight decrease.

Amongst the earliest free colonists who settled in the Hawkesbury district of New South Wales was a small party of Presbyterians, and one of the first places of worship erected in the state was put up in 1810 at Portland Head by their voluntary exertions. Services were conducted there for years before any ordained minister of the denomination reached New South Wales; indeed, it was not until 1823 that the Rev. Dr. Lang

and the Rev. Archibald Macarthur, the first Presbyterian ministers in Australasia, arrived in Sydney and Hobart respectively. The Presbyterian Churches of New South Wales, Victoria, Queensland, South Australia, Western Australia, and Tasmania, are united in a Federal Assembly which meets every year in rotation in the capital cities of the states mentioned. On the 24th July, 1901, representatives of the churches within the various states met at Sydney, when the union of the Presbyterian churches of the States of Australia was accomplished, and the first General Assembly met in pursuance of the scheme of union agreed upon by the Federal Assembly. The United Church is known as "The Presbyterian Church of Australia." New Zealand is not included in this federation, and the Presbyterian Church in that colony is divided into the Presbyterian Church of New Zealand and the Presbyterian Church of Otago and Southland. Besides the churches mentioned, there are several small bodies of Presbyterians unconnected with the larger churches, such as the Presbyterian Church of Eastern Australia in New South Wales, and the Free Church in Victoria. The church in each state, however, acts independently as regards local ecclesiastical administration, and preserves its autonomy in respect of funds and property.

The Presbyterian Church is strongest in New Zealand where its adherents number 176,503, equal to 23·4 per cent. of the population; in Victoria the Presbyterians form 16·2 per cent., and in Queensland 11·7 per cent. of the total population; in none of the other states does the proportion reach 10 per cent. Since 1871 the Presbyterian population of the Commonwealth has increased from 199,195 to 426,105, or by 226,910. In New Zealand the increase has amounted to 112,879.

The first Wesleyan minister came to New South Wales in 1815, but it was not until 1821 that a Wesleyan place of worship was erected in Sydney, and it was even later before the denomination was allowed to share in the Government provision for religion. The first Wesleyan Church in Hobart was established in 1820. From 1815 to 1855 the Wesleyan Church in the colonies was regarded as a mission of the British Wesleyan Church, and from 1855 to 1873 it was affiliated to the British Wesleyan Conference; but in the latter year it was constituted into a separate and independent Conference as the Australasian Wesleyan Methodist Church. At the conference of 1890, held in Sydney, the church districts in Queensland were formed into a separate body, and in 1898, the union of the Methodist churches took place in accordance with resolutions approved by the Wesleyan Conference and Primitive Methodist District Assembly. The union of the Methodist churches of South Australia took place in January, 1900. Western Australia formed a district of the South Australian Conference until March, 1899, when it was constituted a separate conference, its first meeting being held at Perth in March, 1900. At present the Church is divided into

six Conferences, viz., New South Wales, Victoria and ~~Tasmania~~, Queensland, South Australia, Western Australia, and New Zealand. These Conferences meet annually, while a General Conference is held at triennial periods within the boundaries of each annual Conference in the order decided upon. On the 1st January, 1902, the Wesleyan Methodist, Primitive Methodist, and United Methodist Free Churches, entered into organic union, under the name of "The Methodist Church of Australasia." The members of the various Methodist churches in Australia now number 504,139, an increase of 323,556 on the total for 1871, which was returned at 180,583. During the twenty years from 1871 to 1901, the number of adherents in New Zealand increased from 22,004 to 83,789. The denomination at present is proportionately strongest in South Australia, where it forms 25·5 per cent. of the total population, and in Victoria where the proportion amounts to 15·2 per cent. In 1871 the Methodists formed 10·5 per cent of the total population, and the percentage has steadily grown from census to census. In 1881 the proportion was 10·9 per cent., in 1891 11·4, and in 1901 it reached 13·2 per cent.

A Congregational minister arrived in Sydney as early as 1798; and in Hobart the Congregational Church was established in 1830. At present there exists a separate Congregational Union in each of the Australasian provinces. Federal meetings have been held, and a Congregational Union of Australasia has been established. The first meeting of this body was held at Wellington, New Zealand, in 1892. It is intended to hold similar gatherings from time to time in the capital cities of the various states. In 1901 the Congregationalists in Australia numbered 73,561 as against 41,595 in 1871. The membership of this body has, however, remained almost stationary since 1891, when the adherents in Australia numbered 72,738. In New Zealand there were 3,941 Congregationalists in 1871, 6,685 in 1891, and 6,844 at the census of 1901.

The Baptist Church in Australasia dates from a much later period, the establishment of the first four Baptist Churches being as follows:—Sydney, 1834; Launceston, 1839; Adelaide, 1840; and Melbourne, 1841. Churches were established in Auckland in 1852, in Brisbane in 1855, and in Perth in 1895. The adherents of this church in 1871 numbered 33,632, and in 1901 92,670, the increase in Australia for the thirty years being 59,038. In New Zealand the numbers for 1871 and 1901 were 4,732 and 16,035 respectively. The denomination is proportionately strongest in South Australia where it forms 6·2 per cent. of the total population.

The Jewish community in the Commonwealth had a membership in 1901 of 15,239 as compared with 13,805 in 1891, 8,815 in 1881, and 7,059 in 1871. In New Zealand this body numbered 1,262 in 1871, 1,536 in 1881, 1,463 in 1891, and 1,612 in 1901.



Leaving out of consideration some churches with but a small number of adherents, the Salvation Army may be said to be the youngest of the denominations in Australasia. It commenced operations in South Australia towards the close of the year 1880, and in 1882 officers were despatched from Adelaide to Victoria, New South Wales, and Tasmania, for the purpose of organising corps in those states. New Zealand was invaded in 1883, Queensland in 1886, and Western Australia in 1891. The headquarters of the Army are in Melbourne, and its head in Australasia ranks as a Commissioner. He is directly responsible to General Booth, and controls the officers commanding in each of the states, who bear the rank of colonel or brigadier. Each state is divided into districts, which are placed in the charge of superior officers; and each of these districts is subdivided into local corps under subaltern officers, assisted by secretaries, etc. These subaltern officers are responsible to the officers commanding their division, and the latter to the colonel or brigadier in charge of the Army of the whole state. In 1891 there were 33,428 members of the Salvation Army in Australia, and at the census of 1901 the total was returned at 31,100, so that there has been a falling off in membership to the extent of 2,328. For New Zealand the numbers in 1891 and 1901 were respectively 9,383 and 7,999, showing a decrease of 1,384 adherents.

In the eyes of the state all religions are equal in Australasia, and state aid to the denominations has now been abolished in all the provinces of the group. South Australia, in 1851, was the first state to withdraw such aid, after it had been in force only three years; and Queensland, in 1860, shortly after the assembling of the first Parliament, abolished the system inherited from the mother colony, and limited future payments to the clergy then actually in receipt of state aid. New South Wales passed a similar Act in 1862, and the expenditure on this account, which in that year was over £32,000, had fallen in 1903 to £3,036. The total amount paid by the state up to the 30th June, 1903, amounted to £572,236. The other states of the group subsequently abolished state aid, Victoria withdrawing its denominational grants as late as 1875. In Western Australia the system lasted until 1895, when it was abolished from that year; and, in lieu of the annual grants, two sums of £17,715 each were distributed amongst the religious bodies affected, namely, the Anglicans, Roman Catholics, Wesleyans, and Presbyterians, on the 1st October, 1895, and 1st July, 1896.

The only denominations which ever received state aid were the Church of England, Roman Catholics, Presbyterians, and Wesleyans; other denominations to which it was tendered refusing to accept it. The greater portion of the inhabitants belonged to these four persuasions, and the enormous increase of population during the last forty-five years has not in any considerable degree altered this condition of things, though in some states different bodies of Christians have represented a larger proportion of the people than in others.

The following table shows the proportions held by the principal denominations of the total population of each state at the enumerations of 1871, 1881, 1891, and 1901 :—

State.	Church of England.	Roman Catholics.	Presbyterians.	Wesleyan and other Methodists.	Congregationalists.	Baptists.	Jew, Hebrew.	All Others.
	%cent.	%cent.	%cent.	%cent.	%cent.	%cent.	%cent.	%cent.
1871 { New South Wales	45.5	29.3	9.7	7.9	1.8	0.8	0.5	4.5
Victoria .....	34.4	23.3	15.5	12.3	2.5	2.2	0.5	9.3
Queensland .....	36.5	26.5	12.8	6.0	2.2	2.4	0.2	13.4
South Australia ...	27.1	15.2	6.4	13.9	3.5	5.0	0.3	23.6
Western Australia	59.0	28.7	2.1	5.6	3.6	0.2	0.2	0.6
Tasmania .....	53.5	22.3	9.1	7.2	4.0	0.9	0.2	2.8
New Zealand .....	41.8	13.9	24.8	8.6	1.5	1.9	0.5	7.0
Australasia .....	39.1	23.1	13.6	10.5	2.4	2.0	0.4	8.9
1881 { New South Wales	45.6	27.6	9.6	8.6	1.9	1.0	0.4	5.3
Victoria .....	34.7	23.6	15.4	12.6	2.3	2.4	0.5	8.5
Queensland .....	34.6	25.5	10.6	6.7	2.2	2.6	0.2	17.6
South Australia ...	27.1	15.2	6.4	18.9	3.5	5.0	0.3	23.6
Western Australia	54.7	28.3	3.4	7.0	4.3	...	...	2.3
Tasmania .....	51.7	19.9	7.9	9.5	3.5	1.6	...	5.9
New Zealand .....	41.5	14.1	23.1	9.4	1.4	2.3	0.3	7.9
Australasia .....	39.1	22.2	13.4	10.9	2.2	2.2	0.4	9.6
1891 { New South Wales	44.8	25.5	9.7	9.8	2.1	1.2	0.5	6.4
Victoria .....	35.2	21.8	14.7	13.0	1.9	2.5	0.6	10.3
Queensland .....	36.2	23.6	11.6	7.8	2.2	2.6	0.2	15.8
South Australia ...	27.9	14.7	5.7	19.0	3.7	5.5	0.3	23.2
Western Australia	49.7	25.3	4.0	9.2	3.2	0.6	0.3	7.7
Tasmania .....	49.9	17.6	6.6	11.7	3.1	2.2	...	8.9
New Zealand .....	40.0	13.9	22.6	9.9	1.1	2.4	0.2	9.9
Australasia .....	39.1	21.1	13.0	11.4	2.1	2.3	0.4	10.6
1901 { New South Wales	46.6	26.0	9.9	10.3	1.9	1.2	0.5	3.6
Victoria .....	35.8	22.3	16.2	15.2	1.5	2.8	0.5	5.7
Queensland .....	37.5	24.5	11.7	9.5	1.7	2.6	0.2	12.3
South Australia ...	30.3	14.8	5.2	25.5	3.8	6.2	0.2	14.0
Western Australia	42.0	23.3	8.2	13.6	2.5	1.7	0.7	8.0
Tasmania .....	49.6	17.9	6.8	14.8	3.3	2.8	...	4.8
New Zealand .....	41.7	14.6	23.4	11.1	0.9	2.1	0.2	6.0
Australasia .....	40.5	21.6	13.5	13.2	1.8	2.4	0.4	6.6

From the foregoing table it will be seen that while there were fluctuations in individual states, the relative strength of the principal denominations in the whole of Australasia showed but little alteration during the thirty years from 1871 to 1901. The Church of England at the census of 1871 embraced 39.1 per cent. of the population, and at that of 1901 40.5 per cent. The Roman Catholic Church receded from 23.1 per cent. in 1871 to 22.2 per cent. in 1881, and to 21.1 per cent. in 1891 while there was a slight increase to 21.6 per cent. in

1901. The Presbyterian Church receded from 13·6 per cent. in 1871 to 13·4 per cent. in 1881 and 13·0 in 1891, rising again in 1901 to 13·5 per cent. The various Methodist bodies, which have been classed together, increased from 10·5 per cent. in 1871 to 10·9 per cent. in 1881, 11·4 per cent. in 1891, and 13·2 per cent. in 1901. Congregationalists remained almost stationary during the first three enumerations, but in 1901 the proportion receded to 1·8 per cent of the total. The percentage of Baptists at the enumeration of 1871 was 2 per cent., rising gradually to 2·4 per cent, at the census of 1901. At each of the four census periods the proportion of Jews remained the same, namely, 0·4 per cent. The column headed "All others" shows a decrease from 8·9 per cent. to 6·6 per cent. during the period. This column contains all the minor denominations, of which none are at all numerous except Lutherans in Queensland and South Australia; those whose denomination could hardly be classed as a religion; and all those who, from conscientious scruples, took advantage of the clauses of the Census Acts by which the filling in of the column "Religious Denomination" was left optional.

## THE DENOMINATIONS IN 1901.

The numbers of adherents of the various denominations in each state of the Australian Commonwealth at the census of 1901 were as follows :—

Denominations.	New South Wales.	Victoria.	Queensland.	South Australia.	West'n Australia.	Tasmania.	Australian Commonwealth.
Church of England .....	623,131	423,914	184,078	106,987	75,654	83,815	1,497,579
Roman Catholic ..	347,286	263,708	120,405	52,193	41,898	30,314	855,799
Presbyterian .....	132,617	191,459	67,442	18,367	14,707	11,523	428,106
Methodist .....	137,638	180,263	46,574	90,125	24,540	24,999	504,139
Baptist .....	16,618	88,780	12,717	21,764	8,125	4,716	92,670
Congregational .....	24,834	17,141	3,300	13,338	4,404	5,544	73,561
Lutheran .....	7,387	13,934	25,470	26,140	1,703	337	75,021
Salvation Army .....	9,685	8,829	5,612	4,030	1,690	1,454	31,100
Unitarian .....	770	788	212	621	150	88	2,629
Other Christian .....	13,636	27,429	6,896	10,612	3,626	4,770	66,968
Jew, Hebrew .....	6,447	5,907	733	796	1,259	107	15,239
Mahometan .....	1,072	467	*	449	1,191	27	3,206
Buddhist, Confucian .....	5,471	4,806	1,750	3,190	835	353	16,406
Hindoo, Brahmin .....	468	196	122	24	37	.....	846
Other Non-Christian .....	1,024	1,029	16,439	160	120	72	18,394
Free thinker, Agnostic, &c. ....	3,434	2,368	2,223	590	1,431	351	10,402
Indefinite .....	130	204	.....	.....	145	.....	479
Others .....	23,299	24,899	7,668	13,238	7,614	3,955	80,673
Total .....	1,354,946	1,201,070	496,596	393,604	134,124	172,475	3,771,715

\* Included with other Non-Christian.

The last heading, "Others," includes persons of no professed religious persuasion, those who objected to state their religious belief, and those whose religion was not ascertained. The large number of non-Christians in Queensland is accounted for by the presence in that state of numbers of Asiatics and other coloured aliens.

The numbers in New Zealand and in the whole of Australasia were as shown below :—

Denominations.	New Zealand.	Australasia.
Church of England.....	314,024	1,811,603
Roman Catholic .....	109,822	965,621
Presbyterian .....	176,503	602,608
Methodist .....	83,789	587,928
Baptist .....	16,035	108,705
Congregationalist .....	6,844	80,405
Lutheran .....	4,833	79,854
Salvation Army .....	7,999	39,099
Unitarian .....	468	3,097
Other Christian .....	18,827	85,795
Jew, Hebrew .....	1,612	16,851
Mahometan .....	41	3,247
Buddhist, Confucian .....	2,432	18,837
Hindoo, Brahmin .....	2	848
Other Non-Christian.....	1,041	19,935
Freethinker, Agnostic, &c. ....	3,495	13,857
Indefinite .....	377	856
Others .....	24,575	105,248
Total.....	772,719	4,544,434

The approximate strength of the various denominations in the Commonwealth and in Australasia at the end of 1903 was as follows :—

Denominations.	Commonwealth States.	Australasia.
Church of England.....	1,563,081	1,901,401
Roman Catholic .....	893,231	1,011,550
Presbyterian .....	444,742	634,901
Methodist .....	526,189	616,461
Baptist .....	96,723	113,999
Congregationalist .....	76,779	84,153
Lutheran .....	78,302	83,509
Salvation Army .....	32,460	41,078
Unitarian .....	2,744	3,248
Other Christian .....	69,897	90,181
Jew, Hebrew .....	15,906	17,643
Mahometan .....	3,346	3,390
Buddhist, Confucian .....	17,123	19,743
Hindoo, Brahmin .....	883	885
Other Non-Christian.....	19,720	20,842
Freethinker, Agnostic .....	10,857	14,622
Indefinite.....	500	906
Others .....	84,202	110,678
Total.....	3,936,685	4,769,190

## FOOD SUPPLY AND COST OF LIVING.

**C**ONSIDERING the comparatively high rate of wages which prevails, food of all kinds is fairly cheap in Australasia, and articles of diet which in other countries are almost within the category of luxuries are largely used even by the poorer classes. The average annual consumption per inhabitant of the principal articles of common diet, based on the experience of the last ten years, is given below :—

Article.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
<b>Grain—</b>	lb.	lb.	lb.	lb.	lb.	lb.	lb.	lb.	lb.
Wheat .....	356.1	325.5	339.8	390.0	455.5	402.7	353.0	393.4	359.6
Rice .....	9.5	7.6	17.8	9.1	17.9	5.7	10.1	8.9	9.9
Oatmeal .....	5.8	6.9	4.4	5.5	10.4	15.6	6.6	9.3	7.0
Potatoes .....	179.0	240.9	161.6	128.5	189.9	651.8	213.9	536.5	268.2
Sugar .....	109.4	97.7	125.8	101.9	107.1	97.9	106.4	98.8	105.1
Tea .....	7.4	6.7	7.1	8.2	9.7	6.2	7.3	6.5	7.1
Coffee .....	0.5	0.7	0.5	0.7	0.8	0.4	0.6	0.4	0.6
Cheese .....	3.6	3.2	4.2	2.6	6.0	2.3	3.5	5.1	3.8
Butter .....	20.9	13.9	13.8	13.0	28.7	8.8	17.0	16.3	16.9
Salt .....	40.8	14.7	61.5	17.0	19.0	19.8	30.8	36.5	31.6
<b>Meat—</b>									
Beef .....	154.5	116.1	190.4	127.0	142.1	101.5	134.5	90.0	125.8
Mutton .....	113.7	71.0	38.2	75.0	134.3	73.8	91.0	110.0	94.2
Pork and Bacon	12.0	11.8	13.5	11.4	32.5	12.2	13.5	12.5	13.3

It will be seen that the consumption of wheat in the Commonwealth is 353 lb., ranging from 325 lb. in Victoria to 455 lb. in Western Australia, the average consumption for Australasia being 360 lb. per head. There is in all the states a tendency towards reducing the consumption of bread-stuffs, the place of bread being taken by potatoes and other vegetables. In Western Australia and in Tasmania the large influx of miners some years ago materially increased the consumption of bread-stuffs, as shown by the high figures in the above table, but of late years the tendency in these, as in the other states, is towards a smaller consumption. The consumption of rice remains about the same from year to year, the average being 9.9 lb., varying from 5.7 lb. in Tasmania to 17.9 lb. in Western Australia. The consumption of rice increases greatly as an advance is made from the temperate to tropical regions. At Port Darwin rice is not only the staple food of the Chinese, but of the great bulk of the European population, the average annual consumption per head being, Chinese, 450 lb. Japanese, 200 lb. Europeans 50 lb. The use of tea is universal in Australia, but there has been a perceptible decline in the quantity used during the last fifteen years. The consumption is largest in Western Australia, with 9.7 lb. per head, while South

Australia comes next with 8·2 lb. per head. Sugar also enters largely into consumption, the average in the two principal states being 109 lb. per head in New South Wales and 98 lb. in Victoria. The figure for Queensland is based on the returns of production and export; the consumption for 1903 appears to have been only 100·5 lb. per head. Coffee is not a universal beverage in Australasia, the consumption being only one-twelfth that of tea. It is used most largely in Western Australia, where the annual demand amounts to 12·8 oz. per head; but, like tea, the consumption of this beverage is not now so great as formerly.

In some of the states the consumption of potatoes per head of population may be less than is shown in the table. It is probable that the high average consumption of 651·8 lb. in Tasmania and 536·5 lb. in New Zealand is caused by the failure of the New South Wales and other continental markets to absorb the production of potatoes in excess of local requirements in those states, with the result that a quantity has to be given to live stock and poultry. Under these circumstances, it is impossible to determine with exactitude the quantity entering into the food consumption of the population.

The consumption of meat has been ascertained with exactness for five of the states, but these may be taken as fairly representing the whole group. The average quantity of beef annually consumed in the Commonwealth amounts to 134·5 lb. per head; of mutton, to 91·0 lb.; and of pork, 13·5 lb.; in all, 239·0 lb. It would thus appear that each inhabitant requires daily nearly two-thirds of a pound of meat, and that during the year two sheep are killed for each member of the community, and one bullock to every five persons. It is obvious, therefore, that much meat must be wasted. The consumption in New Zealand cannot be accurately determined, but it is probable that about 212·5 lb. of meat is the average annual consumption per inhabitant, of which beef comprises 90·0 lb.; mutton, 110·0 lb.; and pork, 12·5 lb.

The quantity of meat used by the Australasian people, as shown by the above figures, is the most remarkable feature of their diet. The consumption per inhabitant in Germany is 64 lb., while in Australia it is nearly four times that quantity. In the United States, a meat-exporting country, the consumption is about two-thirds of that of Australasia. The following table shows the meat consumption per head for the principal countries of the world:—

Country.	Per Inhabitant.	Country.	Per Inhabitant.
	b.		lb.
Great Britain.....	109	Holland .....	57
France .....	77	Sweden .....	62
Germany .....	64	Norway.....	78
Russia .....	51	Denmark .....	64
Austria .....	61	Switzerland .....	62
Italy .....	26	United States .....	150
Spain .....	71	Canada .....	90
Belgium .....	65	Australasia .....	233

Judged by the standard of the food consumed, the lot of the population of Australasia appears to be far more tolerable than that of the people of most other countries. This will be seen most clearly from the following table, the particulars given in which, with the exception of the figures referring to Australasia, have been taken from Mulhall's *Dictionary of Statistics* :—

Country.	Lb. per Inhabitant.						Tea and Coffee — Oz.
	Grain.	Meat.	Sugar.	Butter and Cheese.	Potatoes.	Salt.	
United Kingdom	378	109	75	19	380	40	91
France .....	540	77	20	8	570	20	66
Germany .....	550	64	18	8	1,020	17	78
Russia .....	635	51	11	5	180	19	6
Austria .....	460	61	18	7	560	14	28
Italy .....	400	26	8	4	50	18	20
Spain .....	480	71	6	3	20	17	6
Portugal .....	500	49	12	3	40	17	18
Sweden .....	560	62	22	11	500	28	112
Norway .....	440	78	13	14	500	40	144
Denmark .....	560	64	22	22	410	25	140
Holland .....	560	57	35	15	820	20	240
Belgium .....	590	65	27	15	1,050	...	142
Switzerland .....	440	62	26	11	140	...	110
Roumania .....	400	82	4	9	80	...	8
Servia .....	400	84	4	9	80	...	8
United States ...	370	150	53	20	170	39	162
Canada .....	400	90	45	22	600	40	72
Australasia .....	377	233	105	21	268	32	123

Taking the articles in the foregoing list, with the exception of tea and coffee, and reducing them to a common basis of comparison, it will be found that the amount of thermo-dynamic power capable of being generated by the food consumed in Australasia is only exceeded by that eaten in Germany, Holland, and Belgium. For the purpose of comparison the figures of Dr. Edward Smith, F.R.S., in his well known work on *Foods*, have been used, and the heat developed has been reduced to the equivalent weight lifted 1 foot high. In estimating the thermo-dynamic effect of food, grain has been reduced to its equivalent in flour, and regard has been paid to the probable nature of the meat consumed. The figures for potatoes are given as they appear in the *Dictionary of Statistics*; but it is a probable supposition that but a small proportion of the quantity over 400 lb. set down for any country is required for human consumption, and the figures relating to some of the countries—notably the three just mentioned—are therefore excessive. The substances specified above are largely supplemented by other foods, both in America and in Europe, but not more so than in these states, and the figures in the

table may be taken as affording an accurate view of the comparative quantity and food value of the articles of consumption in the countries mentioned. To make such a comparison perfectly just, however, the average amount of work which each individual in the community is called upon to perform should be taken into consideration. In Australasia the proportion of women and children engaged in laborious occupations is far smaller than in Europe and America, and the hours of labour of all persons are also less, so that the amount of food-energy required is reduced in proportion. In his *Dictionary of Statistics*, under the heading of "Diet," Mulhall gives a measure of the aggregate amount of work performed by persons doing physical and mental labour, and it would appear that when burnt in the body the food of an average man should be equal to at least 3,300 foot tons of work daily; of a woman, 2,200; and of a child, 1,100 foot tons. For Australasia the average of all persons would be about 2,000 foot tons, whereas from the table just given it would appear that the amount of work to which the daily food consumed by each individual in Australasia is equivalent is not less than 4,071 foot tons.

It must be admitted, however, that the method of comparison adopted in the preceding paragraph is not entirely satisfactory, as the functions of various kinds of food have not been considered. Experiments and observations made in Europe show that a standard may be set up by which the amount of nutrients required to maintain different classes of people may be measured. Professor Voit, of Munich, has ascertained that to sustain a labouring man engaged in moderately hard muscular work there are required 118 grams of protein and quantities of carbo-hydrates and fats sufficient with the protein to yield 3,050 calories of energy. There are 454 grams in a pound avoirdupois, and the calorie is the amount of heat that would raise the temperature of 4 lb. of water 1° Fahrenheit. Applying the ascertained values of the various foods, the consumption of which has just been given, it will be found that the daily consumption per inhabitant is equivalent to 105 grams of protein and 3,195 calories, or about the quantity Professor Voit declares to be sufficient for a labouring man. If allowance be made for the fact that only 29 per cent. of the population are adult males, 24 per cent. women, and 47 per cent. children, the quantity of food consumed in Australasia would appear to be far in excess of the actual requirements of the population, and though the excess may be looked upon as so much waste, it is none the less evidence of the condition of a people whose circumstances permit them to indulge in it.

The consumption of many other articles of common use can be ascertained with some exactness, and this is given for the seventeen specified in the following list. In all cases where the commodities are wholly imported the actual quantities entering into consumption can be given; where there is a local manufacture it has been necessary in some instances



to make an estimate, but as the data for such are ample the figures given may be taken as fairly reliable.

The principal feature of the table is the high consumption of Western Australia of most of the articles comprised in the list. Amongst the most notable of these are tinned fish, 8·25 lb. per inhabitant, compared with the Commonwealth average of 4·34 lb.; preserved milk 18·47 lb., compared with 3·82 lb.; onions 28·73 lb., compared with 16·93 lb.; candles 10·49 lb., compared with 4·67 lb.; kerosene oil 7·62 gallons, compared with 3·55 gallons; and soap 18·33 lb., compared with 14·04 lb.

The annual consumption per inhabitant based on the experience of the last five years was :—

Article.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
	lb.	lb.	lb.	lb.	lb.	lb.	lb.	lb.	lb.
Cocoa and chocolate ...	0·77	0·80	0·40	1·08	0·92	0·73	0·76	0·72	0·75
Currants and raisins ..	4·04	4·67	4·02	5·29	5·47	4·67	4·45	6·84	4·85
Dates .....	1·27	0·96	0·64	0·76	1·05	0·51	1·06	1·76	1·14
Fish (preserved) .....	4·69	3·42	4·62	3·43	8·25	3·50	4·34	3·94	4·26
Honey.....	1·69	0·73	1·30	1·64	1·19	0·55	1·23	0·60	1·16
Maizena (cornflour) .....	1·69	1·58	0·82	1·09	1·36	0·57	1·45	1·23	1·42
Milk (condensed) ..	3·63	2·37	3·45	1·37	18·47	2·30	3·82	1·60	3·32
Mustard.....	0·25	0·13	0·23	0·24	0·36	0·19	0·23	0·28	0·24
Onions .....	13·35	21·70	18·03	9·50	28·73	11·66	16·93	...	...
Pepper .....	0·19	0·24	0·22	0·30	0·30	0·23	0·23	0·30	0·23
Sago .....	0·20	0·19	0·78	0·45	0·12	0·62	0·36	2·64	...
Tapioca ..	1·59	1·58	1·22	1·42	1·75	0·59	1·49	...	...
Blue (washing) .....	0·25	0·30	0·25	0·28	0·30	0·33	0·27	0·25	0·27
Candles .....	4·17	4·51	3·82	4·00	10·49	7·15	4·67	6·59	4·99
Soap .....	14·97	12·27	15·10	12·00	18·33	15·44	14·04	13·98	13·99
Starch.....	4·01	4·70	3·40	2·20	3·15	2·67	3·80	2·50	3·57
	galls.	galls.	galls.	galls.	galls.	galls.	galls.	galls.	galls.
Kerosene oil .....	3·13	3·44	3·86	3·63	7·62	7·76	3·55	3·49	3·53

The following table gives the annual consumption of tobacco in Australasia and the principal countries of the world. The use of tobacco is more prevalent in Western Australia and Queensland than in any of the other states, but not to the extent which the figures of consumption would indicate, as both Western Australia and Queensland have a larger proportion of adult males amongst their population than the other states, and the proportionate number of smokers is larger

Compared with other parts of the world, the average consumption of Australasia will not appear excessive :—

Country.	lb.	Country.	lb.
Australasia.....	2·60	Austria-Hungary.....	3·77
New South Wales.....	2·80	Italy.....	1·34
Victoria.....	2·02	Spain.....	1·70
Queensland.....	2·99	Holland.....	6·92
South Australia.....	2·02	Belgium.....	3·15
Western Australia.....	4·58	Switzerland.....	3·24
Tasmania.....	2·35	Sweden.....	1·87
New Zealand.....	2·64	Denmark.....	3·70
United Kingdom.....	1·41	Turkey.....	4·37
France.....	2·06	United States.....	4·40
Germany.....	3·00	Canada.....	2·11
Russia.....	1·23	Brazil.....	4·37

Taking Australia as a whole, the consumption of tobacco per inhabitant is slightly less than it was ten years ago ; but there has been a considerable change in the consumption in some of the states. In Queensland there has been a fall in amount consumed per inhabitant of nearly half a pound, in New South Wales one-tenth, in South Australia one-tenth, and in Victoria one-third of a pound. In Western Australia there has been an increase of nearly half a pound, in Tasmania an increase of one-seventh of a pound, and in New Zealand of two-fifths of a pound. In regard to the description of tobacco used, the chief point noticeable is the large increase in the consumption of cigarettes. In 1890 about 88·4 per cent. of the total consumption was of ordinary tobacco ; in 1903 the proportion had fallen to 84·2 per cent. ; of cigars, the consumption in 1890 was about 8·5 per cent., compared with 5·2 per cent. at present, and of cigarettes 3·1 per cent. in 1890, compared with 10·6 per cent. for the year 1903.

All the states except Tasmania manufacture tobacco, and the following figures show the consumption of the article during the year 1903 :—

State.	Consumption of—			
	Tobacco.	Cigars.	Cigarettes.	Tobacco, including Cigars and Cigarettes.
	lb.	lb.	lb.	lb.
New South Wales ...	3,365,532	180,444	440,104	3,986,080
Victoria .....	2,002,125	173,031	272,693	2,447,849
Queensland .....	1,366,307	60,876	124,138	1,551,321
South Australia .....	575,528	57,960	108,019	741,507
Western Australia ...	839,860	63,748	108,752	1,012,360
Tasmania .....	378,147	17,032	21,461	416,640
Commonwealth.....	8,527,499	553,091	1,075,167	10,155,757
New Zealand.....	1,852,423	80,027	230,279	2,162,729
Australasia .....	10,379,922	633,118	1,303,446	12,315,486

The average consumption per inhabitant for the same year was as follows :—

State.	Average consumption per inhabitant.			
	Tobacco.	Cigars.	Cigarettes.	Tobacco, including Cigars and Cigarettes.
	lb.	lb.	lb.	lb.
New South Wales ...	2·36	0·13	0·31	2·80
Victoria .....	1·66	0·14	0·22	2·02
Queensland .....	2·63	0·12	0·24	2·99
South Australia .....	1·57	0·16	0·29	2·02
Western Australia ...	3·80	0·29	0·49	4·58
Tasmania .....	2·13	0·10	0·12	2·35
Commonwealth.....	2·18	0·14	0·27	2·59
New Zealand.....	2·26	0·10	0·28	2·64
Australasia.....	2·19	0·13	0·28	2·60

The consumption of opium in Australia for other than medicinal purposes is principally by the Chinese. An investigation was recently made by Mr. Nicholas Lockyer, Collector of Customs, Sydney, who found that, as regards opium smoking, the Chinese were divided into three classes—the largest class, comprising 70 per cent. of the whole, do not use opium; about 20 per cent. consume an ounce of the narcotic per week; and 10 per cent. four ounces per week. This gives an average consumption of  $\frac{2}{3}$  of an ounce for every adult Chinese, equivalent to 1·95 lb. per annum. The total number of male adult Chinese in Australia is approximately 29,000, and a consumption of 1·95 lb. would represent a total of 56,550 lb. The average net import of opium into the Commonwealth during the last five years was 51,259 lb. which confirms the general accuracy of Mr. Lockyer's estimate. The quantity consumed in each year was as follows :—

	lb.
1889 .....	56,061
1900 .....	48,568
1901 .....	55,638
1902 .....	54,423
1903 .....	41,603

Australasia as a whole compares very favourably with most European countries in the average quantity of intoxicants consumed, as the following statement shows. The figures, which are reduced to gallons of proof spirit from data given in *Mukhall's Dictionary of Statistics*, would appear even more favourable to Australasia were the fact of the large preponderance of males over females in these states made a feature of the comparison :—

Country.	Proof gallons.	Country.	Proof gallons.
United Kingdom .....	3·57	Portugal .....	3·00
France.....	5·10	Holland.....	4·00
Germany.....	3·08	Belgium .....	4·00
Russia.....	2·02	Denmark .....	5·00
Austria .....	2·80	Scandinavia.....	4·36
Italy .....	3·40	United States .....	2·65
Spain .....	2·85	Australasia .....	2·30

The following table shows the consumption for all the states during the year 1903 :—

State.	Spirits.		Wine.		Beer, &c.		Equivalent in Alcohol (proof) per Inhabitant
	Total.	Per Inhabitant.	Total	Per Inhabitant.	Total.	Per Inhabitant.	
	galls.	galls.	galls.	galls.	galls.	galls.	galls.
New South Wales.	1,127,222	0·79	952,884	0·67	13,583,223	9·55	2·20
Victoria .....	741,535	0·61	1,503,019	1·24	14,033,907	11·61	2·42
Queensland .....	444,349	0·86	198,817	0·38	4,919,987	9·49	2·19
South Australia ...	169,292	0·46	817,382	2·22	3,063,063	8·33	2·06
Western Australia.	314,656	1·42	166,450	0·75	4,829,101	21·82	4·45
Tasmania .....	94,372	0·53	31,470	0·18	1,511,404	8·51	1·69
Commonwealth .	2,891,426	0·74	3,670,022	0·94	41,940,685	10·71	2·36
New Zealand .....	618,649	0·76	122,490	0·15	7,759,330	9·46	2·03
Australasia .....	3,511,075	0·74	3,792,512	0·80	49,700,015	10·49	2·30

The largest consumption of spirits per inhabitant is in Western Australia, Queensland being second. Wine is used most freely in South Australia and Victoria, and beer in Western Australia. The average consumption of alcohol in the Commonwealth for the year 1903 amounted to 2·36 gallons of proof spirit per inhabitant, ranging from 4·45 gallons in Western Australia to 1·69 gallons in Tasmania. There was a great diminution in the quantity of alcohol consumed in Australasia in the year immediately following the bank crisis, and in 1895 the consumption fell to 2·1 gallons, as compared with 2·94 gallons in 1891. From 1895 there was a gradual increase, and the consumption for the last eight years has ranged between 2·4 and 2·5 gallons.

During the last ten years there has been a considerable change as regards some of the states in the character of the beverages consumed, as the accompanying tables show :—

State.	Consumption of Malt Liquors in 1893.		Consumption of Malt Liquors in 1903.	
	Total.	Per Inhabitant.	Total.	Per Inhabitant.
	galls.	galls.	galls.	galls.
New South Wales.....	11,178,264	9·29	13,583,223	9·55
Victoria .....	13,197,987	11·25	14,033,907	11·61
Queensland.....	3,591,891	8·69	4,919,987	9·49
South Australia.....	3,226,479	9·51	3,063,063	8·33
Western Australia.....	584,043	9·44	4,829,101	21·82
Tasmania.....	1,130,048	7·51	1,511,404	8·51
Commonwealth .....	32,906,712	9·85	41,940,68 <sup>5</sup>	10·71
New Zealand .....	5,102,276	7·71	7,759,330	9·46
Australasia .....	38,010,988	9·50	49,700,015	10·49

The consumption per inhabitant of malt liquors both for the Commonwealth and New Zealand showed an increase during the ten years. The consumption of spirits has remained practically the same in the Commonwealth, the increase being very little, and in New Zealand there has been a slightly larger increase in the volume per inhabitant.

The following is a statement of the consumption in 1893 and 1903 respectively :—

State.	Consumption of Spirits in 1893.		Consumption of Spirits in 1903.	
	Total.	Per Inhabitant.	Total.	Per Inhabitant.
	<i>galls.</i>	<i>galls.</i>	<i>galls.</i>	<i>galls.</i>
New South Wales.....	999,984	0·83	1,127,222	0·79
Victoria .....	693,929	0·59	741,535	0·61
Queensland.....	405,316	0·98	444,349	0·86
South Australia.....	150,055	0·44	169,292	0·46
Western Australia .....	87,241	1·41	314,656	1·42
Tasmania .....	64,316	0·43	94,372	0·53
Commonwealth .....	2,400,841	0·72	2,891,426	0·74
New Zealand .. .....	461,283	0·70	619,649	0·76
Australasia .....	2,862,124	0·72	3,511,075	0·74

The consumption of wine can be determined only approximately. Wine is an article of local production not subject to excise duty, and it is quite possible that a certain quantity may be consumed without its production being noted. The following statement gives the probable consumption for the periods named :—

State.	Consumption of Wine in 1893.		Consumption of Wine in 1903.	
	Total.	Per Inhabitant.	Total.	Per Inhabitant.
	<i>galls.</i>	<i>galls.</i>	<i>galls.</i>	<i>galls.</i>
New South Wales.....	1,019,130	0·85	952,894	0·67
Victoria .....	1,394,045	1·19	1,503,019	1·24
Queensland .....	237,078	0·57	198,817	0·38
South Australia.....	341,398	1·01	317,382	2·22
Western Australia .....	68,671	1·11	166,450	0·75
Tasmania.....	13,595	0·90	31,470	0·18
Commonwealth .....	3,073,917	0·92	3,670,022	0·94
New Zealand .....	112,105	0·17	122,490	0·15
Australasia .....	3,186,022	0·80	3,792,512	0·80

Several descriptions of Australian wines have a natural strength of 30 per cent. of proof spirit, while from analyses which have been made it would appear that the strength of these wines offered for sale varies from 24 to 37 per cent. of spirit. Imported beers range from 13·88 per cent. to 15·42 per cent. in the case of English, and from 9·58 per cent. to 11·76 per cent. of proof spirit in Lager, while the local manufacture varied according to the make from 6·1 to 13·8, the average being 9·97 per cent. Four of the states manufacture spirits, and five make wine, while beer is brewed in all of them. Details of the production during 1903 will be found elsewhere in this volume.

#### EXPENDITURE ON LIVING.

In previous issues of this volume statements appeared showing the annual expenditure of the people of New South Wales and of the other states of the Commonwealth on food, clothing, house rent, and other services usually grouped together under the term "cost of living." The necessity for some such table arose from the circumstance that the states lived under separate tariffs, which in various ways influenced the prices of commodities. But with the uniform system of Customs that prevails throughout Australia, the conditions governing the cost of commodities are, so far as they are affected by the operation of tariff charges, made practically the same.

The explanation of the differences that exist in the total expenditure of the peoples of the various states will be found rather in difference of consumption than of prices, and the extent of this difference in consumption will be seen from a scrutiny of the tables relating to the annual consumption of thirty-four articles of common use given in the earlier part of this chapter.

The cost of providing food, and beverages other than intoxicants, consumed in Australia during the year 1903 may be set down at £65,499,000. This sum represents the price to the consumer, and covers all charges except that of cooking and preparing the food for the table. The expenditure on wines, spirits, and beer amounted to £14,217,000, so that the total expenditure for all food and beverages was £79,716,000, equal to £20 7s. per inhabitant, or 1s. 1·4d. daily. Excluding intoxicants, the yearly expenditure per inhabitant was £16 14s. 5d., and the average per day, 11d. Compared with the cost of food supply in other countries, this may appear considerable, but the last two years were abnormal as regards the prices of several of the staple articles of diet, while allowance must also be made for the profusion with which flesh meat is consumed and wasted in Australia.

Of the total cost of food and beverages, viz., £79,716,000, the expenditure on fresh meat is the largest item, being 25 per cent. of the whole; bread is 9·23 per cent.; milk, butter, and cheese, 15·18 per cent.; vegetables and fruits, 10·98 per cent.; sugar, 4·76 per cent.; tea,

coffee, cocoa, 2·51 per cent.; and wines, beers, and other spirituous liquors, 17·83 per cent. The following is the approximate retail cost of the chief articles that enter into daily consumption :—

	£
Bread .....	7,387,000
Fresh meat .....	19,920,000
Vegetables and fruits .....	8,752,000
Milk, butter, cheese, etc... ..	12,102,000
Other farm produce .....	2,100,000
Sugar .....	3,798,000
Tea, coffee, etc. ....	2,004,000
Other foods .....	7,710,000
Non-alcoholic beverages .....	1,758,000
<hr/>	
Total expenditure on food .....	£85,499,000
Wines, beer, and spirituous liquors .....	14,217,000
<hr/>	
Total expenditure on food and beverages...	£79,716,000

The total expenditure on food just given works out at an average of £16 14s. 5d. per inhabitant, which is considerably higher than in ordinary years, but the high prices of meat, butter, etc., are accountable for the increase. The amount is probably higher than in any other country, but the mere statement of expenditure affords but a partial view of the question, as the earnings of the people must be taken into consideration, otherwise the comparison is of little value. If this be done it will be found that few countries approach Australia in the small proportion of income absorbed in providing food for their people, for although in 1903 the ratio amounted to 44·4 per cent. of the total earnings, it must be borne in mind that the prices of foods of all kinds were abnormally high in that year; in an ordinary year the proportion would be about 37 per cent. The following table taken from Mulhall's *Dictionary of Statistics*, shows that while the actual cost of food and drink is £20 7s. in Australia, as against £14 4s. 9d. in Great Britain, the earnings required to pay for that food are not larger proportionately than in the countries which show most favourably in the table. The number of working days in the year is assumed to be 300, allowing for thirteen days' sickness and fifty-two Sundays. It should, however, be borne in mind that comparisons of this kind are more or less fanciful. The economic condition of a people is more readily and conclusively ascertained by reference to the



actual quantities of foods of various kinds entering into consumption, than by the nominal value of such foods and the proportion of the average income spent in their attainment :—

Country.	Average annual cost of food and beverage.	Ratio of cost of food to earnings.	Days' earnings equal to annual cost of food.
	£ s. d.	per cent.	days.
United Kingdom ...	14 4 9	42·2	127
France .....	12 4 5	44·0	142
Germany .....	10 18 5	40·1	148
Russia .....	5 19 7	52·0	156
Austria .....	7 17 4	50·8	182
Italy .....	6 4 10	51·2	153
Spain .....	8 9 0	51·2	154
Portugal .....	7 3 0	59·1	177
Sweden .....	9 18 11	45·2	136
Norway .....	9 15 0	47·6	143
Denmark .....	11 14 0	36·0	108
Holland .....	10 8 0	46·0	138
Belgium ..	12 3 1	43·4	130
Switzerland .....	8 11 7	45·2	135
Australia .....	20 7 0	44·4	133

The expenditure of Australia coming under the designation "cost of living" amounted in 1903 to £42 19s. 10d. per head, made up of the following items. The expenditure of New Zealand is not included.

Division of Expenditure.	Total Expenditure. £	Per Inhabitant. £ s. d.
Food and non-alcoholic beverages .....	65,499,000	16 14 5
Fermented and spirituous liquors .....	14,217,000	3 12 7
Tobacco .....	3,365,000	0 17 2
Clothing and drapery .....	17,868,000	4 11 3
Furniture .....	2,075,000	0 10 7
Rent or value of buildings used as dwellings .....	19,574,000	5 0 0
Locomotion .....	7,156,000	1 16 6
Fuel and light .....	5,416,000	1 7 8
Personal attendance, service, and lodging .....	7,032,000	1 15 11
Medical attendance, medicine, and nursing .....	4,652,000	1 3 9
Religion, charities, education (not including state expenditure) .....	3,075,000	0 15 8
Art and amusement .....	4,831,000	1 4 8
Books, newspapers, etc. ....	1,804,000	0 9 3
Postage and telegrams, not incidental to earning the incomes .....	1,066,000	0 5 7
Direct taxes not falling on trade .....	1,706,000	0 8 9
Household expenses not included elsewhere .....	5,447,000	1 7 10
Miscellaneous expenses .....	3,574,000	0 18 3
<b>Total .....</b>	<b>£168,389,000</b>	<b>42 19 1</b>

According to Mulhall, the expenditure per inhabitant in the leading countries of Europe and in America is as follows :—

Country.	Expenditure per Inhabitant.	Country.	Expenditure per Inhabitant.
	£ s. d.		£ s. d.
United Kingdom .....	29 14 9	Norway.....	19 0 0
France.....	23 19 4	Denmark .....	28 11 5
Germany.....	20 3 4	Holland .....	20 17 4
Russia.....	10 1 11	Belgium .....	25 8 2
Austria .....	14 4 9	Switzerland .....	18 0 0
Italy .....	11 11 0	United States .....	32 16 2
Spain .....	15 12 6	Canada .....	23 6 2
Portugal .....	11 5 6		
Sweden .....	20 8 4	Australia .....	42 19 10

The expenditure of Australia as compared with population is, according to this table, largely in excess of that of other countries, but as expenditure depends upon income, a table such as the above has little meaning unless regard be paid to the amount of income available for expenditure and the purchasing power of money. This latter question is too involved to be dealt with so far as European and American countries are concerned within the limits at disposal in this volume. It may, however, be mentioned that so far as the primary food requirements are concerned the purchasing power of money is greater in Australia than in any of the countries mentioned in the foregoing list: house rents, however, are higher, as well as the price of most descriptions of wearing apparel. The question of cost of living is further dealt with in another place.

#### PRICES OF COMMODITIES.

The area of Australia is so extensive, and the population, except on the sea-board, so scattered, that the determination with any exactness of the average prices of the various commodities consumed is almost a matter of impossibility. No attempt has therefore been made to ascertain the average for the whole continent, and in the following pages the prices refer to the Sydney markets alone. There is a further reason. Until the discovery of gold there were virtually only two important markets in all Australia—Sydney and Hobart—and of these Sydney was much the more considerable. Any comparisons of the prices of commodities extending back beyond 1852 must be based mainly upon the experience of Sydney, although from 1840 onwards there is sufficient information in the chapter on the Industrial Progress of Australia in this volume to enable Sydney prices to be adjusted for Melbourne, Hobart, Adelaide, and the other chief centres of population. For the earlier years the authority of contemporary newspapers has been followed where the official records are obscure or silent, but since 1836 these records have been available, and have for the most part been followed.

The accompanying table exhibits the average prices of eight commodities during each year since 1820 :—

Year.	Bread per 2-lb. loaf.	Fresh Beef per lb.	Butter per lb.	Cheese per lb.	Sugar per lb.	Tea per lb.	Pota- toes per cwt.	Maine per bushel.
	d.	d.	s. d.	s. d.	d.	s. d.	s. d.	s. d.
1820	5	5½	2 9	1 1	.....	.....	7 3	5 6
1821	6	5½	2 8	1 2	.....	.....	7 3	5 0
1822	5	5½	2 6	1 3	.....	.....	5 9	4 9
1823	3½	5½	2 2	1 2	.....	.....	6 1	2 6
1824	5	5½	3 0	1 4	.....	.....	6 10	4 10
1825	4½	6	2 2	1 5	.....	.....	8 4	5 6
1826	5½	5½	2 4	0 10	.....	.....	9 0	4 0
1827	4½	6½	2 3	1 1	.....	.....	8 0	5 0
1828	6	5	2 6	1 4	.....	.....	18 6	9 0
1829	7	6	1 10	1 1	.....	.....	12 6	7 9
1830	4½	3½	1 0	0 11	3½	2 6	8 0	3 10
1831	4	4½	1 8	0 6	3½	2 6	5 0	3 8
1832	5	5	2 3	0 7	3½	2 6	5 0	4 7
1833	4	3½	1 5	0 6	3½	2 6	10 0	2 11
1834	5	4	1 6	0 6	3½	2 6	14 0	4 4
1835	4	3½	1 10	0 5	3½	2 6	10 0	4 6
1836	5½	3	1 9	0 8½	3½	2 6	7 0	6 9
1837	3	4½	1 9	0 7½	3½	2 6	10 0	4 2
1838	5	5½	1 6	0 8½	3½	1 5	6 0	3 7
1839	11½	4½	2 6	1 1	3½	1 6	10 0	9 0
1840	7½	6½	2 0	1 0	3½	2 6	10 0	5 3
1841	4½	6½	2 6	0 10	3½	3 3	10 0	2 10
1842	5	4½	2 6	1 1½	3½	2 0	7 0	4 9
1843	3½	2½	1 9	0 9	3	2 6	5 0	2 9
1844	2½	2½	1 5	0 4½	2½	1 6	4 0	1 5
1845	2½	2½	1 6	0 6	3	1 6	4 6	2 11
1846	3½	2½	1 8	0 6	4	2 3	3 0	4 1
1847	3½	2½	1 2	0 7	4	2 4	5 10	2 1
1848	3½	2½	1 1	0 8	3½	2 0	4 4	1 8
1849	2½	2½	1 2	0 6½	3½	1 9	3 0	3 9
1850	4½	2½	1 3	0 7	3½	1 10	4 0	4 1
1851	5	2½	1 3	0 7	3½	1 4	6 0	3 7
1852	4½	3	1 3	0 7	3½	1 4	6 0	3 11
1853	6½	3½	1 5½	0 7½	3½	1 4	13 0	9 3
1854	7½	4½	2 3	0 9	5	2 6	18 6	10 0
1855	9	6	2 4	1 3	7	2 5	21 4	8 7
1856	7½	3½	1 11	1 2	5½	2 2½	10 0	3 8
1857	5	3½	2 0	1 0	7½	2 6	14 6	8 2
1858	6	4	2 0	1 0	7	2 6	15 6	6 5
1859	6	4	1 10	1 0	5	2 6	8 0	3 5

Year.	Bread per 2-lb. loaf.	Fresh Beef per lb.	Butter per lb.	Cheese per lb.	Sugar per lb.	Tea per lb.	Potatoes per cwt.	Maine per bushel.
	d.	d.	s. d.	s. d.	d.	s. d.	s. d.	s. d.
1860	6½	4	1 6	1 10	5½	2 3	7 6	2 10
1861	6½	3	1 8	0 9	5½	2 4	7 3	5 1
1862	4½	4½	2 3	0 9	4½	2 0	8 0	6 0
1863	4	4½	1 6	0 10	4½	2 0	7 0	3 10
1864	5½	4	1 6	0 8	4½	2 0	5 0	3 11
1865	7½	3	1 9	0 9	4½	2 0	8 0	3 7
1866	6½	3	1 3	1 0	4	2 6	6 0	4 1
1867	3½	2½	1 6	0 7½	4	2 0	7 0	2 5
1868	4	3½	1 3	0 9	4	2 0	9 0	2 11
1869	3½	2	1 6	0 6	4	2 0	4 0	3 8
1870	3½	3½	1 3	0 6	4	2 0	5 0	3 4
1871	3½	2½	1 3	0 7½	4	2 3	4 0	3 0
1872	3½	2½	1 0	0 9	4	1 9	5 0	2 2
1873	4	2½	1 3	0 5	4	1 9	3 6	3 1
1874	3½	4	1 7	0 6	4	1 9	4 9	4 6
1875	3	3½	1 3	0 9	4½	1 9	5 6	4 3
1876	3½	5½	1 3	0 7	4	1 9	4 9	3 1
1877	4	4½	1 6	0 6	4	2 0	4 9	3 4
1878	4	4	1 3	0 6	4	1 9	5 10	4 0
1879	3½	4	0 10½	0 6	3½	1 6	6 0	3 1
1880	3	3½	0 10	0 7	4	2 0	4 3	2 6
1881	3½	3½	0 10½	0 6½	3½	2 0	4 0	3 7
1882	4	4½	1 3	0 8	4	2 0	5 6	5 4
1883	3½	4	1 4	0 10	4	2 0	6 0	4 0
1884	3	4½	1 3	0 9	3½	1 6	6 6	5 0
1885	3	4½	1 9	1 0	3	1 9	5 6	3 11
1886	3½	4½	1 9	1 1	3½	1 9	6 3	3 9
1887	3½	4	1 4	0 10½	3½	1 9	5 0	3 11
1888	3	4	1 7	0 8½	3½	1 6	6 0	3 4
1889	3½	3	1 4	0 9	3½	1 6	9 0	3 7
1890	3½	4	1 0	0 8	3½	1 6	6 0	3 10
1891	3½	4	1 1	0 9	3½	2 0	5 0	2 11
1892	3½	4	1 3	0 8	3	1 6	5 6	3 4
1893	3½	4	1 1½	0 8	2½	1 6	6 4	4 0
1894	2½	3	1 0	0 8	2½	1 6	4 6	2 6
1895	2½	3	1 0	0 8	2½	1 6	4 3	2 9
1896	3	3	1 0	0 8	2½	1 6	5 6	2 7
1897	3	2½	1 0	0 8	2½	1 6	5 3	2 3
1898	2½	2½	1 0	0 8	2	1 6	9 0	2 9
1899	3	3½	1 0	0 8	2½	1 6	9 4	3 4
1900	3	3½	0 11	0 7½	2½	1 4	6 9	3 0
1901	3	5	1 0	0 8	2½	1 3	7 6	3 6
1902	3½	6	1 2	0 10	2½	1 3	7 6	5 10
1903	3½	5½	0 11	0 9	2½	1 3	5 10	3 4
1904	2½	5	0 10½	0 8	2½	1 3	4 0	.....

The most noteworthy feature of the history of prices in Australia—the great range of some of the commodities during the year—is not disclosed by the foregoing table. This variation is most noticeable during the early years, and amongst articles of local production, and was the result of the almost complete isolation of the country from the markets of the world. Prior to the discovery of gold, communication by letter with the outside world was at best uncertain, and as late as 1878 the regular mails were made up but once a month. The establishment of telegraphic communication, amongst other results, has had a marked effect on prices, so that except in rare instances, and for goods produced in excess of the demand, the production of Australia no longer determines the prices of goods required for the local markets. Exception must, of course, be made for perishable produce, which is still liable to a great range in price during the course of a single year, as will be shown by some examples here after given.

Potatoes have varied in price from year to year. The lowest average for a whole twelvemonth was 3s. per cwt. in 1846, and the highest was 21s. 4d. in 1855, shortly after the discovery of gold; and it may not be without interest to note that from 1853 to 1858 the price of potatoes was extraordinarily high. Commencing with the year first named, the averages were 13s., 18s. 6d., 21s. 4d., 10s. 14s. 6d., and 15s. 6d. per cwt. With regard to the variation in a single year, the following examples may be cited:—In 1820, from 4s. 6d. to 10s. per cwt.; in 1825, from 4s. to 12s.; in 1829, from 9s. to 26s.; in 1834, from 9s. to 19s.; in 1839, from 7s. to 25s.; in 1854, from 11s. to 24s.; in 1856, from 3s. to 11s.; and in 1888 from 2s. to 24s.

The price of maize has not been subject to very great fluctuation, since, being little used except for horse-feed, this grain is capable of being replaced by other products; nevertheless the prices have ranged from 1s. 5d. in 1844 to 10s. in 1854.

In the list given on pages 903 and 904 are included quotations for bread at per 2-lb. loaf. In most years the price varied somewhat regularly with that of wheat. There are, however, exceptions to this rule, chiefly in the years during which wheat brought an unusually high figure, when the price of bread was generally less than might have been expected. The lowest price at which bread has been retailed was 2½d. in 1849, and the highest was 14d. the 2-lb. loaf, which figure was paid for a short time in 1839.

In addition to the eight commodities which are given on pages 903 and 904, the following list of the average retail prices of articles largely used may not be without interest. The information begins with 1836, beyond which year it is difficult to determine the exact average

Year.	Bacon per lb.	Eggs per doz.	Rice per lb.	Oat- meal per lb.	Coffee per lb.	Salt per lb.	Beer (Col.) per gal.	Soap per lb.	Starch per lb.	Tobacco per lb. (Col.)	Tobacco per lb. (Imp.)
	s. d.	s. d.	d.	d.	s. d.	d.	s. d.	d.	s. d.	s. d.	s. d.
1836	...	2 2	9	...	...	...	...	4½	...	...	3 3
1837	...	2 6	...	...	1 6	1	1 0	...	...	...	4 0
1838	...	4 0	3	...	...	...	...	...	...	...	...
1839	...	3 0	3	...	1 6	...	...	4½	...	...	3 3
1840	0 10	2 9	2½	...	1 4	...	...	4½	...	...	3 3
1841	0 11	2 3	2½	...	1 4	...	...	4½	...	...	3 3
1842	0 10½	1 11	2	...	1 4	1	1 9	4½	...	...	3 6
1843	0 10	2 0	1½	...	0 10	0½	2 3	...	...	1 4	3 6
1844	0 5½	0 11	1½	...	0 8½	1½	1 3	3½	...	1 6	3 6
1845	0 6½	1 1	3	...	0 7½	1½	1 1	3½	...	1 6	4 6
1846	0 9½	1 3	1½	...	0 10	1½	2 0	5	...	1 9	4 6
1847	0 6½	1 1	3½	6	1 1	1½	3 4	5	1 0	1 9	4 4
1848	0 9	1 3	3½	6	1 1	1½	3 3	5	1 0	1 9	4 4
1849	0 8½	1 1	3½	5½	1 0	1½	2 8	5½	1 1	2 0	4 7
1850	0 8½	1 4	4	6	1 2	1½	2 9	5½	1 0	2 7	4 10
1851	0 9½	1 8	4	6	1 3	1½	2 6	5½	1 0	3 8	7 9
1852	1 1	1 6	4	6	1 3	1½	2 6	6	1 0	4 0	8 0
1853	1 2½	2 3	4½	6	1 3	1½	2 4½	6	1 0	4 0	7 6
1854	1 4½	2 9	5	7½	1 6	2½	3 6	8	1 6	4 0	5 6
1855	0 11½	2 8	6	9	1 8	4	4 7	8	1 6	3 0	5 0
1856	0 10	2 2	5½	7	1 7½	3	3 6	7½	1 1½	2 6½	5 3
1857	0 9½	1 11	5	7	1 8	2½	4 0	7	1 0	2 7	5 0
1858	0 7½	2 3	6	7	1 8	4½	4 3	7	1 5	2 6	5 0
1859	0 8½	1 10	4½	7	1 8	2½	4 0	6½	1 0	2 6	5 0
1860	1 0	1 3	5	6	1 6	2½	3 6	7	1 0	2 3	5 0
1861	0 10	1 6	4	6	1 6	2½	3 6	6	0 10½	2 0	5 6
1862	0 10	1 5	3	5	1 5	1½	2 0	4½	0 8	4 6	6 0
1863	0 10½	1 7	3	4	1 4	1½	1 6	4	0 7	3 0	7 6
1864	0 10	1 6	3	4	1 4	1½	2 0	4	0 8	1 6	5 6
1865	0 9½	1 6	3	4	1 4	1½	2 0	4	0 8	2 6	5 6
1866	1 0	1 6	4	4	1 4	1½	2 0	4½	0 7	2 6	5 0
1867	0 10	1 7	3½	4	1 4	1	1 6	4	0 7	1 9	4 6
1868	0 9½	1 2	4	4	1 4	1½	2 0	4	0 7	1 9	5 0
1869	0 10	1 3	3	4	1 0	1	1 4	4	0 8	1 0	3 6
1870	0 10½	1 4	3	4	1 2	1	1 4	4	0 7	1 3	3 6
1871	0 9½	1 4	2½	2½	1 0	0½	2 3	3	0 4½	1 0	3 0
1872	0 9	1 1	3	3	1 1	0½	1 4	3	0 5	1 4	3 6
1873	0 9	1 4	2½	2½	1 2	0½	2 3	3	0 5	2 0	3 6
1874	0 8½	1 6	3	3½	1 4	0½	2 0	2½	0 6	1 9	3 3

Year.	Bacon per lb.	Eggs per doz.	Rice per lb.	Oat- meal per lb.	Coffee per lb.	Salt per lb.	Beer (Col.) per gal.	Soap per lb.	Starch per lb.	Tobacco per lb. (Col.)	Tobacco per lb. (Imp.)
	s. d.	s. d.	d.	d.	s. d.	d.	s. d.	d.	s. d.	s. d.	s. d.
1875	0 9½	1 6	3	3	1 2	1½	3 0	3	0 5	2 0	3 9
1876	0 9	1 0	3	3	1 2	1	2 0	2½	0 5	1 9	3 0
1877	0 8½	1 6	3	3½	1 3	1	2 0	2½	0 5	2 0	3 9
1878	0 9	1 3	3	3	1 3	0½	2 0	2	0 5	1 6	3 9
1879	0 8	1 7	2½	2½	1 0	0½	2 0	2	0 5	1 6	3 0
1880	0 7½	1 4	3	3	1 5	0½	2 0	3	0 5½	2 0	4 0
1881	0 7½	1 0	3	3	1 5	0½	2 0	3	0 5½	2 0	4 0
1882	1 0	2 0	3½	4	1 5	1	2 0	2½	0 6	3 0	5 0
1883	1 0	1 11	3	4	1 9	1	2 0	3	0 7	3 0	6 0
1884	0 11½	1 11	2½	3	1 4	1	2 0	3	0 6	3 0	5 0
1885	0 10½	1 10	3	3	1 5	0½	2 0	3	0 6½	3 0	6 0
1886	0 10½	1 8	3½	2½	1 6	1	2 0	4	0 6½	4 0	5 6
1887	0 10	1 7	3	2½	1 6	1	2 0	3½	0 6½	4 0	5 6
1888	0 10½	1 7	3	2½	1 6	1	2 0	3½	0 6	4 0	5 6
1889	0 11	1 8	3	3½	1 6	1	2 0	3½	0 6	4 0	5 6
1890	1 0½	1 6	4	3	2 0	1	2 0	3½	0 5	4 0	6 0
1891	0 10	1 6	3	2½	2 0	1	2 0	3½	0 5	4 0	6 0
1892	0 9	1 6	3	2½	1 10	0½	2 0	3	0 4½	4 0	6 0
1893	0 11	1 6	3	2½	1 10	0½	2 0	3	0 4½	4 0	6 0
1894	0 7	1 3	3	2½	1 10	0½	2 0	3	0 4½	4 0	6 0
1895	0 7½	1 0	2½	2	1 9	0½	2 0	2	0 4	4 0	6 0
1896	0 7½	1 0	2	2	1 9	0½	2 0	2	0 4	4 0	6 0
1897	0 8	1 0	2½	2½	1 9	0½	2 0	2½	0 4	4 0	6 0
1898	0 8½	1 0	2	2½	1 9	0½	2 0	2½	0 4	4 0	6 0
1899	0 8	0 11	2	2½	1 10	1	2 0	2½	0 3½	4 0	6 0
1900	0 7½	0 11	2½	2½	1 6	0½	2 0	3	0 3½	4 0	6 0
1901	0 8½	1 3	2½	2½	1 6	0½	2 0	3	0 4	4 0	6 0
1902	0 10	1 6	2½	2½	1 6	0½	2 0	3	0 4	4 0	6 0
1903	0 10	1 6	3	2½	1 6	0½	2 0	4	0 5	4 0	6 0
1904	0 8	1 0	2½	2½	1 6	0½	2 0	4	0 5	4 0	6 0

In the quotation of prices in the foregoing tables the figures given are those charged in the retail shops. It is quite possible that produce of all kinds may have been bought at cheaper rates than those stated, but higher rates were also paid, and the figures will be found to represent the fair average rates, having regard to the class of goods consumed. It is of importance to take into consideration the quality of the produce consumed, for very considerable changes in the direction of improvement have taken place in this respect. Thus, the ordinary sugar now used, and obtainable for about 2d. per lb., is a good white sugar, whereas some years ago only a common quality of moist sugar was found on the tables of the people. A very material improvement has been effected in the quality of flour, a large proportion of the present consumption being roller-made. Salt-butter still forms the bulk

of the supply, but it is usually of recent make ; while formerly the butter was imported from Great Britain, and was several months old before reaching the dining-table. The candles now used are made of stearine, but the time is not remote when only the common tallow candle was in general use ; and so with many other articles of ordinary consumption. The retail prices are those actually paid from day to day, irrespective of the nominal wholesale rates of the commodities in the metropolitan markets.

#### PRICE-LEVELS OF ARTICLES OF COMMON USE.

A consideration of retail prices would not be complete without a statement of the price-level in different years. This can be given for foods ; but at present the data are hardly sufficient to establish an exact series of price-levels, taking into consideration all the elements of ordinary expenditure. The information in regard to foods is given below, the assumption being made that the quantities entering into consumption were the same formerly as at the present day. This assumption, however, is in some respects erroneous ; but there appear to be no other means within reach to effect a just comparison. Sugar, tea, coffee, butter, cheese, and potatoes are now more largely used than (say) prior to 1870 ; but bread, or other forms in which flour is used, and meat, are not consumed so largely. However, when full allowance is made on this score, the following table will still be found to approximate closely to the truth. The price-level is calculated on the prices ruling for beef, mutton, bread, sugar, rice, potatoes, tea, beer, and tobacco :—

Period.	Price-level of principal Articles of Consumption.	
	1821-37 prices =1,000.	1901-03 prices =1,000.
1821 to 1825 .....	1,000	1,227
1826 „ 1830 .....	1,000	1,227
1831 „ 1835 .....	802	963
1836 „ 1840 .....	930	1,141
1841 „ 1845 .....	676	829
1846 „ 1850 .....	669	821
1851 „ 1855 .....	1,038	1,273
1856 „ 1860 .....	1,153	1,414
1861 „ 1865 .....	959	1,177
1866 „ 1870 .....	753	924
1871 „ 1875 .....	709	870
1876 „ 1880 .....	759	931
1881 „ 1885 .....	756	927
1886 „ 1890 .....	730	895
1891 „ 1895 .....	670	822
1896 „ 1900 .....	646	793
1901 „ 1903 .....	815	1,000



During the past forty years prices of food stuffs have changed very slightly, such changes as there have been tending in the direction of a reduction. The average of 1896-1900 was less than in any previous period, but in 1901-3 there was a considerable increase, and prices ruled higher than in any period since 1861-65. Little practical good can be gained by comparing the prices of one period with those of another, unless regard is also paid to the earnings of labour, and as means of comparison are afforded in the chapter of this work dealing with wages, it will be unnecessary to pursue the subject further in this chapter.

#### PRICE-LEVELS OF IMPORTS AND EXPORTS.

The following tables have been compiled with the object of showing to what extent Australia has been affected by the variation in the prices of commodities imported and exported during the past forty-one years. The figures refer to New South Wales alone, but they may be accepted as also indicating in a fairly accurate degree the position in which the other states of Australasia stand in regard to this matter. The total value of the exports of each of the states is greatly affected by the prices obtained for certain leading lines of raw produce, of which wool, wheat and flour, tallow, silver and silver lead, hides, leather, tin, copper, coal, fruit, butter, sugar, meat and timber are the most important. The value of these articles represents a total of about seventeen and a half millions or ninety per cent. of the total export of domestic produce.

In the subjoined table the price-level of domestic exports is given for the forty-one years beginning with 1860. In order to ascertain the price-level, all the principal articles of domestic produce exported have been taken, the prices of 1903 have been applied to the quantities of each of the other years, and the result has been compared with the actual total of such year: the level of the year being found by dividing the actual sum obtained into the amount which would have been obtained had the prices of 1903 prevailed. The average for 1903 is assumed to be 1,000, the price-levels or index numbers of the other years being as shown in the table. In order to further facilitate comparison, the average of the five years 1870-74 has been assumed to be 1,000, and the prices of other years have been adjusted to that basis. The average of these years has been taken because the question is frequently raised as to the comparative prices of commodities before and after the demonetisation of silver by Germany in 1873. In compiling the price-level for exports, only articles of insignificant value have been omitted from consideration, and in no year does the value of articles excluded form more than 15 per cent. of the total exports, while in some years the proportion falls as low as 5 per cent., the average of all years being about 10 per cent. It is considered that this system enables a more

reliable estimate of the relative prices to be obtained than that of selecting the prices of certain articles without giving due weight to the quantities of such articles exported.

These figures show that there has been a great fall in the prices of Australian produce exported since 1860, or still greater since 1864, viz., from the index number 1,316 to 745, or over 43 per cent. Marked fluctuations, ranging to about 10 per cent., occurred between 1860 and 1866, when the index number was about the same as in the first-named year. From 1866 to 1870 there was a drop from 1,249 to 879, or about 30 per cent. A rise followed in 1871 to 1,075, or about 22 per cent., after which for four years prices continued fairly steady, until there was a further decline to 887 in 1878. In 1879 the level rose to 921 and for the next four years prices continued without much change, but from 1884 to 1885 there was a fall from 919 to 806. This was succeeded by a fairly even range until 1889, when the level stood at 785. From 1889 there was a steep decline to 532 in 1894, a fall of 32 per cent for the five years, but in 1895 and 1896 prices recovered a little, and the level rose to 573—an advance of 7·7 per cent. In 1897 there was again a slight fall from 573 to 557, equivalent to 2·8 per cent., but in 1898 the level rose to 590, and in 1899 to 736, a rise of 32 per cent. for the two years. The sharp rise in 1899 was entirely due to the improved price obtained for wool, and the fluctuation in the last four years has been mainly caused by the varying price of that commodity.

Year.	Price-level of Exports.		Year.	Price-level of Exports.	
	1908 prices = 1,000.	Average of 1870-74 prices = 1,000.		1908 prices = 1,000.	Average of 1870-74 prices = 1,000.
1860	1,674	1,247	1882	1,244	926
1861	1,672	1,244	1883	1,244	926
1862	1,761	1,310	1884	1,232	919
1863	1,599	1,191	1885	1,082	806
1864	1,769	1,316	1886	1,041	775
1865	1,619	1,203	1887	1,069	797
1866	1,676	1,249	1888	1,037	773
1867	1,550	1,154	1889	1,053	785
1868	1,551	1,155	1890	1,018	758
1869	1,414	1,053	1891	926	689
1870	1,181	879	1892	877	652
1871	1,442	1,075	1893	792	590
1872	1,316	979	1894	714	532
1873	1,395	1,037	1895	732	546
1874	1,383	1,028	1896	770	573
1875	1,377	1,027	1897	748	557
1876	1,305	972	1898	791	590
1877	1,197	891	1899	988	736
1878	1,191	887	1900	916	682
1879	1,236	921	1901	885	659
1880	1,214	903	1902	940	700
1881	1,205	897	1903	1,000	745

It will be seen that the purchasing power of money has steadily increased since 1864 and that 20s. in 1903 would purchase the same articles of domestic export which in 1864 would have cost 35s. 4d., prices having fallen 43·5 per cent. during the period of thirty-nine years. The greatest decline has taken place in the three staple exports of wool, silver, and coal, many of the minor articles having maintained or increased their price during the last fifteen years.

It must not be supposed that Australia has been a loser by the fall in the prices of its exports to the extent which the price-level shows, because the power of the exports to purchase imports must also be taken into consideration. It will, therefore, be necessary to consider also the price-level of imports. As there exist no reliable data on which price-levels for imports can be based prior to 1870, the table commences with that year :—

Year.	Price-level of Imports.		Year.	Price-level of Imports.	
	1903 prices = 1,000.	Average of 1870-74 prices = 1,000.		1903 prices = 1,000.	Average of 1870-74 prices = 1,000.
1870	1,305	966	1887	1,058	763
1871	1,311	970	1888	1,053	779
1872	1,370	1,014	1889	1,097	812
1873	1,393	1,030	1890	1,086	804
1874	1,379	1,020	1891	1,038	767
1875	1,238	962	1892	995	736
1876	1,276	944	1893	957	708
1877	1,227	908	1894	908	673
1878	1,217	900	1895	900	666
1879	1,166	862	1896	936	693
1880	1,173	868	1897	945	700
1881	1,161	859	1898	957	708
1882	1,155	855	1899	952	704
1883	1,174	869	1900	1015	752
1884	1,164	862	1901	998	738
1885	1,069	790	1902	1,026	760
1886	1,049	776	1903	1,000	740

It may be said generally that the fall in prices was somewhat in favour of the exports up to the year 1889. Since then the exports have fallen away on the average values at a much more rapid rate than the imports. A clearer view of the operation of the fall in prices will be obtained from the table which is given below, showing the price-levels of imports of merchandise for home consumption and exports of domestic

produce, for periods of five years to the end of 1899, and for the four years ended with 1903, with the relative fall per cent. :—

Period.	Imports.		Exports.	
	Average of five years, 1870-4, prices = 1,000.	Decline in prices in five years, per cent.	Average of five years, 1870-4, prices = 1,000.	Decline in prices in five years, per cent.
1870-74	1,000	.....	1,000	.....
1875-79	915	8·5	940	6·0
1880-84	863	5·9	914	2·9
1885-89	788	8·5	787	13·8
1890-94	737	6·5	646	18·0
1895-99	694	5·8	600	7·0
1900-03	748	7·8 (rise)	697	16·2 (rise)

It will be seen that, assuming the index number of the five years 1870-74 to be 1,000, the fall in the succeeding five years was 8·5 per cent. for the imports, as compared with 6 per cent. for the exports. The average value of the imports for the five years ending with 1884 was 5·9 per cent. less than in the preceding quinquennial period, whereas the difference in the value of the exports was 2·9 per cent. During the next five years the average value of the imports declined 8·5 per cent., while the fall in the value of the exports was no less than 13·8 per cent., so that the index number for 1885-89 for both imports and exports was practically the same figure. As already mentioned, the fall for the period 1890-94 was much heavier in regard to the exports than the imports, amounting to 18 as compared with 6·5 per cent.; but during the period 1895-99 the fall in the exports was not much greater than that in the imports, being 7·0 per cent. compared with 5·8 per cent. In the last four years the exports have risen by 16·2 per cent., and the imports by 7·8 per cent., so that the last two periods were the most favourable, as far as prices go, that have been experienced in Australia for many years.

The Australian states and New Zealand are chiefly affected by the fall in prices because they are debtor countries. In the chapter on "Private Finance" will be found certain calculations showing that the annual charge payable by the states and municipalities on their indebtedness to British creditors is £12,852,000, while the earnings of investments made in Australasia by private persons, or drawn by absentees, amount to £5,250,000 per annum. As the whole of the interest on Government and municipal loans has to be paid by exports, irrespective of the fall in prices, and as a large portion also of the interest payable to private investors is in the same category, the fall is a matter of very serious importance to these states. Fortunately the increase of production, as compared with the population, has been large enough in normal seasons to counteract the fall in prices.

## MINERAL RESOURCES.

**A**LMOST all the principal metals of economic value are found in Australasia, and many are common to several of the states. In dealing with the occurrence and value of mineral deposits, a classification has been made into noble and other metals, carbon minerals, salts, stones and clays, and diamonds and other gem stones.

### GOLD.

Gold, the most valuable of noble metals, is found throughout Australasia, and the important position at present occupied by these states is largely due to discoveries of this metal, the development of other industries being, in a country of varied resources, a natural sequence to the acquisition of mineral treasure. Settlement in Australia was still young when many-tongued rumour spoke of the existence of the precious metal, but it was not until the 16th February, 1823, that the Government was officially apprised of a discovery destined to be the precursor of a prosperity seldom surpassed in the history of nations. On the date mentioned Mr. Assistant-Surveyor M'Brien reported that at a spot on the Fish River, about 15 miles east of Bathurst, he had discovered gold. Mention is made in the early records of New South Wales of several other finds, but it remained for Count Strzelecki and the Rev. W. B. Clarke to demonstrate the existence of the precious metal in payable quantities, and to assert their belief in its abundance, an opinion strongly supported in England by several eminent authorities, and substantiated by Hargraves' discovery in the year 1851. The gold-fields of Lewis Ponds and Summer Hill Creek had hardly been opened up when, on the day that witnessed the severance of the Port Phillip district from the mother colony of New South Wales, Mr. J. M. Eamond discovered gold in Victoria. Shortly afterwards a rush set in for Ballarat, and the gold fever took possession of Australia. The following year (1852) saw gold found in South Australia, Tasmania, and New Zealand, though it was not until 1861 that a large population was, by the prospect of rapidly obtaining wealth, attracted to the last-mentioned colony. The rush to Canoona, in what is now Queensland, took place in 1858. The last of the states in which extensive deposits of the precious metal were found was Western Australia, but the mines there are now the richest in

Australasia, and have proved an enormous source of wealth to the state.

From the date of its first discovery, gold to the value of over 494 million pounds sterling has been obtained in Australasia. Towards this total Victoria has contributed nearly 267 millions, and for many years that state was the largest gold producer of Australasia. In the year 1898, however, for the first time, the production was surpassed by that of Western Australia, and the latter state increased its advantage each year until in 1903 the output was valued at £8,770,720, as against £3,259,483 in Victoria. The yield of gold in Victoria has been well maintained for many years, and each successive year from 1893 to 1899 showed an increase. In the last-mentioned year the production was 854,500 oz., valued at £3,418,000, but during the last four years it has been somewhat smaller, although the value has exceeded £3,000,000 annually. The yield for 1903 was 822,424 oz., equal to 767,351 oz. fine, valued at £3,259,483. The Bendigo district was again the chief centre of production, with 224,747 oz., followed by Ballarat with 174,817 oz., and Beechworth with 116,886 oz. The richest fields in the state are at Bendigo and Ballarat which, after yielding uninterruptedly for half a century, still give no evidence of depletion. The output of the former field in 1903 was 219,820 oz., and of the latter 55,800 oz. Of the total yield of the state 42,066 oz. were obtained by means of dredging and hydraulic sluicing. There were 51 dredging plants in operation during the year, comprising 15 bucket dredges, 23 pump hydraulic sluices, 10 jet elevators, and 3 rotary hydraulic plants, while 14 others were engaged in hydraulic sluicing by gravitation. The men employed in this branch of the mining industry numbered upwards of 1,100. The total number of men engaged in gold-mining on the 31st December, 1903, was 25,208, of whom 11,058 were alluvial miners, and 14,150 quartz miners. The machinery and plant in use on the same date were valued at £2,040,690.

Queensland promised at one time to overtake Victoria in the annual production of gold, but so far the southern state has maintained its position, although the production of Queensland is steadily advancing. In 1889 the output was valued at £2,586,860 but thenceforward the yield declined, and this amount was not again reached until 1898, when the value was £2,750,349. During the next two years there was again an increase, the value of the gold won in 1900 being £2,871,709, the highest yet recorded, but a considerable quantity was made up of gold obtained from old tailings, and from creeks which had served as channels for the escape of residue from the mills. In 1901 the yield was valued at £2,541,892, and in 1902 at £2,720,639, but these totals were exceeded in 1903, when the production was 921,363 oz., or 668,546 oz. fine, valued at £2,839,813.

Arranged in order of productiveness, the principal goldfields in Queensland in 1903 were Charters Towers, Gympie, and Mount Morgan, while Ravenswood and Croydon also produced a considerable quantity of the precious metal. For many years Charters Towers has been the chief

gold-producing centre, and the last two years have been amongst the most prosperous experienced on the field since its discovery in 1872. The production in 1902 amounted to 265,244 oz. fine, valued at £1,126,735, and in 1903 to 285,771 oz. fine, valued at £1,213,879. There are three great ore shoots on this field, known as The Day Dawn, Brilliant, and Victoria Reefs, and the rich developments in the Queen Cross, one of the mines engaged in working the Victoria reef, have been mainly responsible for the increased activity in the mining operations. The gold obtained from this mine alone in 1903 amounted to 78,303 oz. Over 200 men were employed and dividends amounting to £215,000 were paid. Of the mines engaged on the Day Dawn reef, the most important in point of production has hitherto been the Day Dawn Block and Wyndham, which has returned dividends amounting to £761,460, but the output is gradually becoming smaller, and in 1903 was only 17,018 oz., being considerably below that of previous years. Scarcity of water has been the chief drawback to mining operations at Charters Towers, but this difficulty was overcome by the construction of a weir across the Burdekin River, thus ensuring a constant supply. The yield from the Mount Morgan field amounted to 124,975 oz., or 116,672 oz. fine gold, valued at £495,592, or £111,122 less than in the preceding year. The Mount Morgan mine was responsible for almost the whole of the production, and yielded 120,391 oz. of gold, obtained from 238,801 tons of stone. Up to the 30th November, 1903, no less than 2,678,922 oz. of gold, valued at £10,874,553, had been obtained from this mine. The machinery employed at the Mount Morgan mine on the 31st December, 1903, was valued at £452,800, and about 1,600 hands were engaged at the mine and works. The yield of the Gympie mining district, in 1903, surpassed that of the previous year, which had hitherto ranked as the highest, and amounted to 147,622 oz. fine gold, with a value of £627,056. The chief contributing mines were the No. 2 South Great Eastern, Scottish Gympie, and South Glanmire and Monkland, which produced 52,010 oz., 39,479 oz., and 27,290 oz. of gold, and paid dividends amounting to £115,200, £53,625, and £70,500 respectively. In September, 1903, a discovery of alluvial gold in the bed of the Dee River, about 7 miles above Mount Morgan, was reported, and up to the end of the year gold to the value of £7,658 had been obtained.

There were 1777 quartz miners and 29 alluvial miners on this field at the close of 1903, the total population being estimated at 15,550 persons. The Ravenswood gold-field, which had been comparatively neglected for some years, again attracted attention owing to rich discoveries made in 1902, and during that year the production amounted to 40,969 oz. fine gold, valued at £174,034, while in 1903 the yield was 38,273 oz. fine gold, with a value of £162,572. The New Ravenswood, Limited, owns the principal mines on the field, including the Sunset, from which 19,599 oz. of gold were obtained during the year. There were 912 quartz miners and 37 alluvial miners on the

field at 31st December, 1903, in addition to 39 engaged in mining for other minerals, the total population being estimated at 4,800.

The yield of the Croydon field amounted to 31,790 oz. fine gold, valued at £135,036. The number of men engaged in gold mining at this field on the 31st December, 1903, was 425, the total population being 2,708. The machinery in use was valued at £72,400. The men engaged in gold-mining in Queensland at the end of 1903 numbered 9,229, of whom 7,278 were quartz-miners and 1,951 alluvial miners, 494 of the latter being Chinese.

In New South Wales the greatest annual production of gold occurred in 1852, soon after the first discovery of the precious metal, when the output was valued at £2,660,946. The only other year which saw a production in excess of two millions sterling was 1862, when the return reached £2,467,780. In 1874 the yield had fallen to 271,166 oz., valued at £1,041,614, and thenceforth the industry declined considerably in importance, reaching its lowest point in 1888, when only 87,541 oz., valued at £317,241, were produced. From that date onward there was a steady improvement, and in 1894 the Government took the step of furnishing large numbers of the unemployed with miners' rights and free railway passes, and sending them to the abandoned alluvial fields as fossickers. This action, with the increased attention paid to quartz-mining, nearly doubled the production, the quantity obtained during the year being set down at 324,787 oz., valued at £1,156,717, being the first time since 1874 that it had exceeded one million sterling; while in 1895 the yield reached 360,165 oz., and the value £1,315,929. During the next three years there was a falling off, but in 1899 the output reached the value of £1,623,320, the highest since 1872. From that year onwards there was a diminished production due to the scarcity of water, but with the more favourable season of 1903 there was a revival of the industry, and the yield amounted to 254,260 oz. fine, valued at £1,080,029, making the total up to the end of that year £50,924,164. The uncertainty of the water supply has always been the chief drawback to mining in New South Wales, as well as in other states of the Commonwealth, and the effects of a good or bad season can be readily seen in the gold yield of the year. Of the gold produced in 1903, 27,237 oz., valued at £104,303, were obtained by dredging, the output from this branch of the industry showing an increase of £6,412 on that of the previous year. On the 31st December, 1903, there were 41 dredging plants in commission, valued at £253,480. The chief centre of gold-dredging is in the Araluen Division, where fourteen plants were in operation, and gold to the value of £54,990 was obtained. The area held and applied for under lease for gold dredging was 9,015 acres. The principal seats of alluvial mining in the state are the Bathurst, Mudgee, Tumut and Adelong, and Braidwood districts, together with the country watered by the various feeders of the Upper Lachlan; while the principal quartz-veins are situated near Adelong, Armidale, Bathurst, Cobar, Hill End, Orange, Parkes, and



Wyalong. Cobar again maintained the position occupied in preceding years as the chief gold-producing centre, the output for 1903 being valued at £266,355. The next in importance was Wyalong, with £72,847; followed by Araluen, £58,163, and Adelong, £43,258. These totals are but small compared with those returned from several of the districts in other states, while the mines are less productive than those of Western Australia and Queensland. The principal mine in the state is that at Mount Boppy, near Cobar, which is of comparatively recent development. The lode is 5 feet and upwards in width at a depth of 300 feet, and samples taken from it averaged 79·70 dwt. to the ton. The estimated value of the machinery on the gold-fields, including dredging plant, at the end of 1903 was £953,970. The men engaged in the industry numbered 11,247, of whom 5,341 were quartz miners and 5,906 alluvial miners, the latter including 391 Chinese.

Until a comparatively recent date, Western Australia was considered to be destitute of mineral deposits of any value, but it is now known that a rich belt of mineral country extends from north to south. The first important discovery was made in 1882, when gold was found in the Kimberley district, but it was not until a few years later that this rich and extensive area was developed. In 1887 gold was found at Yilgarn, about 200 miles east of Perth, the find possessing importance as the precursor of the discovery of the immense tracts of gold-bearing country, the knowledge of the existence of which has drawn population from all parts of Australasia and brought the state into the prominent position which it occupies at the present time. General attention was first attracted to these fields by further discoveries at Southern Cross, to the east of Yilgarn; and the sensational finds at Coolgardie, which followed in 1892, resulted in a rush to Western Australia which was reminiscent of the experiences of the fifties in the older-settled portions of the continent. Thereafter, before the march of the prospector, the known gold-bearing area was rapidly extended, and in 1894 the country was divided into separate gold-fields, so extensive were the preparations for its exploitation. At the present time, there are nineteen gold-fields in the state, the most important, from the point of production, in 1903, being East Coolgardie, Mount Margaret, and North Coolgardie, in the eastern district; and Murchison, in the central district. For the past six years Western Australia has held the premier position among the Australian states in regard to gold production, and the annual output is still increasing. The production during 1902 was 2,177,441 oz., representing 1,871,037 oz. fine, with a value of £7,947,662, and ranked as the highest recorded up that year; but this return was exceeded in 1903 when the production amounted to 2,436,311 oz., or 2,064,801 oz. fine, valued at £8,770,720. Of the total yield in 1902, no less than 1,358,375 oz. were obtained from the East Coolgardie field, where some of the richest mines in the world are to be found. The dividends

returned by some of the gold-mining companies in 1903 were enormous, the total being £2,024,152. Of this amount the Great Boulder Perseverance paid £350,000, the Golden Horseshoe £270,000, the Great Boulder Proprietary £262,500, and the Great Fingall £200,000. The importance of the gold-mining industry to Western Australia may be gauged from the fact that the number of men engaged therein at the end of 1903 was 20,716, comprising 15·2 of the whole male population, while the machinery in use was valued at £4,532,737.

Although gold was discovered in New Zealand at Coromandel during the year 1852 there is no record of the production prior to 1857, when there was an export valued at £40,422. For many years the colony was a large producer of gold, and from 1865 to 1871 the value amounted to over £2,000,000 each year. The production then declined and in 1894 it was only £887,839, but this amount has been considerably increased of late years, and in 1903 the total amounted to 533,314 oz., valued at £2,037,831, the highest recorded since 1871. Up to the 31st December, 1903, gold to the value of £63,149,147 has been raised in the colony. The largest proportion of the yield in 1903 was obtained in the Auckland district; the value of the gold entered for exportation from each district being:—Auckland, £832,334; Otago, £668,852; West Coast, £501,090; Nelson, £31,710; and Marlborough, £3,845. In earlier years by far the greater portion of the yield was won in alluvial mining, but at the present time a large proportion of the production is obtained from quartz reefs which are widely distributed throughout the colony. The older methods of alluvial mining have practically passed away owing to the exhaustion of the rich, shallow grounds, and have been superseded by hydraulic sluicing, while dredging is also carried on in numerous localities. During 1903 efforts were made to test the ground on the Thames field, one of the oldest in the colony, by boring, but operations were suspended owing to the failure of the plant. The Auckland district is the principal seat of quartz mining in the colony, and the chief centre of production is at Waihi. Here are located the mines of the Waihi Gold Mining Company, which rank amongst the principal mines of the world. During 1903, 214,508 tons of stone were treated at the mills, and yielded 677,873 oz., while from the concentrates and slag tailings exported for treatment gold to the value of £83,722 was obtained, making a total of £603,167. The company employed over 1,100 hands, and paid dividends to the amount of £250,000 during the year, the total paid since the commencement of operations being upwards of £1,260,000. From Karangahake, gold valued at £182,095 was won, the mines and mills affording employment to 452 persons. The principal mines in this district are the New Zealand Crown and the Talisman Consolidated, which yielded gold to the value of £78,280 and £94,134 respectively. The principal seat of quartz mining in the Middle Island is at Reefton, where upwards of 500 persons are employed. The gold obtained in this district amounted to 55,719 oz., valued at £222,743,

of which 48,841 oz., valued at £195,469, were obtained from quartz mines; 3,937 oz., valued at £15,798 by dredging; and 2,941 oz., of a value of £11,476, from other alluvial sources. The chief mines in the district are the Progress mines, from which 57,114 tons of quartz were obtained in 1903, yielding 21,299 oz. of gold, valued at £88,738. From concentrates, &c., £19,621 worth were won. The dividends for the year amounted to £34,375.

Considerable attention is directed to the recovery of gold by dredging, and at the end of 1903 there were 201 dredges in operation. The men engaged in gold-mining at the end of 1903 numbered 10,210, of whom 6,613 were alluvial miners and 3,597 were quartz miners, 1,021 of the former being Chinese. The machinery employed in 1903 was valued at £2,082,384.

Although payable gold was found in Tasmania in 1852, it was not until the seventies that the metal was mined for on an extensive scale, the total production to the end of 1870 being less than 4,000 oz. In 1878 the value of gold produced suddenly rose to £100,000, and this total has been gradually increased, until in 1899 it was valued at £327,545, being the highest yet recorded. The production in 1902 amounted to 70,996 oz. fine, valued at £301,573; but in 1903 it decreased to 59,891 oz. fine, valued at £254,403. Beaconsfield is the principal gold-field in the state. It is situated on the west side of the river Tamar, 26 miles north-west of Launceston, and formerly produced a large quantity of alluvial gold, while there is also a rich deep lead. The Tasmania mine, on this field, is the largest gold-producer in the state, and up to 31st December, 1903, had yielded 579,694 oz. The Lefroy field has been another important centre of gold-production, but although payable gold is still obtained the yield is not nearly so large as in former years. At Mathinna a quantity of gold has also been obtained. The principal mine on this field is the New Golden Gate, the deepest in the state, its main shaft being 1,500 feet. This mine has yielded 198,818 oz. of gold, valued at about £758,378, and up to 31st December, 1903, had paid £334,400 in dividends. From the Volunteer Consolidated mine on this field some good stone has been obtained from two lodes struck at a depth of 450 feet. In the Western District a little alluvial gold is obtained, while north of the Pieman River there is a large extent of auriferous country, but owing to the dense vegetation prospecting is difficult. Attempts have been made to recover gold by the process of dredging, but the results, so far, have not been satisfactory, although the Lisle Dredging Company obtained 356 oz. by this process during the half-year ended 31st December, 1903. The men engaged in gold-mining during 1903 numbered 988.

Of all the Australian States, South Australia has produced the smallest quantity of gold, the total output from the commencement of mining operations being valued at £2,573,000. The highest production was in 1893, when it reached £153,132; but it has gradually declined, and the value has not amounted to £100,000 in any of the last six

years. In the state proper the yield is very small, amounting to but 8,650 oz. in 1903, the balance of 19,179 oz. being obtained from the Northern Territory, the total value amounting to £90,031. The North-western District, which includes Tarcoola, is the most important gold-producing area in the state. The output for 1903 was 4,629 oz. Some excitement was caused during 1902 by reports of a rich discovery at Arltunga, and visions of easily acquired wealth caused the usual rush of gold seekers. The field, however, proved most disappointing, and although a mild boom in Arltunga shares existed for a few weeks, it did not long survive the discouraging reports received from the scene of operations. Gold undoubtedly exists in considerable quantities, but capital is required for its exploitation. A report by the Government Geologist states that with good management and economic mining and treatment of the ore large and payable returns may be obtained for many years. The Government battery and cyanide plant on the field treated 1,878 tons of ore during the year, which yielded 2,019 oz. of gold, valued at £7,562. The mines in the Northern Territory are largely in the hands of Chinese, but a number of properties have been acquired by an English company, which has erected the works necessary for their development. The total number of men engaged in gold-mining in South Australia at the end of 1903 was 2,000. A considerable number of these are Chinese, physically incapable of doing a fair day's work, and dangerous from a sanitary point of view. Possessed of no means whatever, and with no proper tools adapted to the search for the precious metal, they eke out a miserable existence by mining a little alluvial gold.

The following table gives the value of gold and the proportion of the total amount raised in each state up to the end of 1903:—

State.	Production of Gold.	
	Value.	Proportion raised in each State.
	£	per cent.
New South Wales .....	50,924,164	10·31
Victoria .....	266,810,712	54·00
Queensland .....	58,312,127	11·80
South Australia .....	2,573,357	0·52
Western Australia .....	48,868,004	9·49
Tasmania .....	5,449,564	1·10
Commonwealth .....	430,938,018	87·23
New Zealand .....	63,149,147	12·78
Australasia .....	494,087,165	100·00

It will be readily understood from this and the following table how Victoria, although in area the smallest of the group with the exception

of Tasmania, achieved the foremost position amongst the Australasian States, and retained that place so long as the powerful attraction of gold continued, while the source of Western Australia's progress is also fully disclosed. The following table shows the value of the gold raised in the various states during each year for which records are available, but, for reasons which are explained in the next paragraph, discrepancies exist in the total values shown for several of the states :—

Year.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.
	£	£	£	£	£	£	£	£
1851	468,336	580,548	.....	.....	.....	.....	1,048,884	.....
1852	2,060,946	10,953,936	.....	.....	.....	.....	13,614,882	.....
1853	1,781,172	12,600,084	.....	.....	.....	.....	14,381,256	.....
1854	773,209	9,568,260	.....	.....	.....	.....	10,341,469	.....
1855	654,594	11,172,280	.....	.....	.....	.....	11,826,854	.....
1856	689,174	11,942,940	.....	.....	.....	.....	12,632,114	.....
1857	674,477	11,046,268	.....	.....	.....	.....	11,720,745	40,422
1858	1,104,175	10,132,908	.....	.....	.....	.....	11,217,083	52,464
1859	1,259,127	9,122,568	.....	730	.....	.....	10,382,725	28,427
1860	1,465,373	8,028,800	.....	.....	.....	.....	10,092,173	17,585
1861	1,806,171	7,889,812	.....	.....	.....	.....	9,675,983	751,873
1862	2,467,780	6,633,124	.....	12,442	.....	.....	9,113,346	1,591,359
1863	1,796,170	6,508,420	80,000	890	.....	.....	8,325,470	2,431,723
1864	1,304,926	6,181,748	.....	.....	.....	.....	7,486,674	1,856,837
1865	1,231,243	6,172,752	.....	.....	.....	.....	7,403,905	2,226,474
1866	1,116,404	5,913,120	79,143	.....	.....	4,382	7,113,049	2,844,517
1867	1,063,578	5,732,984	170,090	.....	.....	2,536	6,959,988	2,608,992
1868	994,666	5,536,800	429,907	2,936	.....	514	7,964,822	2,504,325
1869	974,149	5,349,184	481,352	15,593	.....	7,475	6,797,758	2,392,995
1870	931,016	4,891,192	351,412	24,217	.....	14,218	6,212,055	2,157,585
1871	1,250,485	5,421,966	504,876	6,000	.....	16,055	7,199,324	2,767,590
1872	1,044,177	5,120,984	592,993	6,363	.....	15,309	7,388,026	1,781,261
1873	1,396,875	4,964,220	555,310	298	.....	18,390	6,925,188	1,967,425
1874	1,041,614	4,623,388	561,255	4,175	.....	18,491	6,249,423	1,506,331
1875	877,694	4,383,148	596,242	7,034	.....	11,982	5,876,100	1,407,770
1876	613,190	3,855,140	660,136	9,868	.....	44,923	5,183,177	1,284,396
1877	471,448	3,238,612	838,544	.....	.....	23,289	4,571,893	1,406,060
1878	430,200	3,101,098	1,085,864	1,225	.....	100,000	4,718,377	1,240,179
1879	407,219	2,985,785	1,009,046	90	.....	230,896	4,689,988	1,148,108
1880	444,253	3,316,484	934,976	.....	.....	201,297	4,897,010	1,227,252
1881	573,582	3,485,400	948,318	112,825	.....	216,061	5,287,026	1,080,790
1882	529,522	3,594,144	787,125	80,720	.....	187,387	5,175,448	1,002,790
1883	458,530	3,240,188	744,781	87,729	.....	176,442	4,707,020	968,352
1884	396,059	3,114,472	1,077,314	93,404	.....	169,404	4,841,058	921,797
1885	378,665	2,940,672	1,088,294	83,700	.....	155,309	4,651,849	948,615
1886	366,294	2,660,784	1,193,493	95,674	1,148	117,250	4,434,053	903,569
1887	394,579	2,471,004	1,490,730	138,302	18,517	158,533	4,671,065	811,100
1888	317,241	2,500,104	1,685,750	66,160	13,273	147,154	4,729,082	891,096
1889	434,784	2,459,356	2,566,960	76,780	58,872	119,708	5,796,355	806,549
1890	460,285	2,354,244	2,137,054	106,105	86,664	87,114	5,231,466	773,486
1891	559,231	2,305,000	2,017,586	125,529	115,182	149,816	5,272,694	1,007,458
1892	575,299	2,617,824	2,154,458	139,370	226,284	174,070	5,897,360	954,744
1893	651,286	2,684,404	2,159,390	163,132	421,385	145,975	6,215,472	913,188
1894	1,156,717	2,694,720	2,378,289	162,092	787,099	225,485	7,394,402	887,839
1895	1,315,929	2,960,944	2,210,887	123,793	879,748	212,329	7,808,029	1,122,164
1896	1,073,360	3,220,348	2,241,347	112,759	1,068,808	237,574	7,954,196	1,041,438
1897	1,104,315	3,251,064	2,553,141	120,044	2,564,977	289,241	9,882,782	980,204
1898	1,201,743	3,349,028	2,750,349	95,148	3,990,698	281,485	11,066,446	1,080,691
1899	1,623,320	3,418,000	2,838,119	79,041	6,246,733	327,545	14,532,758	1,513,178
1900	1,070,020	3,229,028	2,871,709	82,186	6,007,610	316,220	13,578,275	1,489,092
1901	737,164	3,102,758	2,541,892	93,222	7,235,653	295,176	14,005,620	1,753,788
1902	684,970	3,062,028	2,720,639	95,129	7,947,692	301,573	14,812,001	1,951,433
1903	1,060,029	3,259,498	2,839,813	90,081	8,770,720	254,403	16,294,479	2,087,831

These figures do not in all cases add up to the total value of the production given elsewhere, as the information regarding earlier years is

imperfect. The total for Victoria is £297,952 less than the actual value of production, while for Queensland the amount is deficient to the extent of £3,442,948, accounted for by the fact that prior to 1878 the figures only represent the gold sent by escort. There is a deficiency of £68,611 in South Australia which cannot be traced owing to the imperfect nature of the returns available in earlier years. The figures shown for Western Australia are £427,061 less than the total value of gold produced, as prior to 1899 they only show the value of gold exported. There is also a deficiency of £2,869 in the total shown for Tasmania. The information relating to New South Wales for the years 1897 to 1901 inclusive differs from that previously published, which included gold won from other than native ores. The gross production of gold in each state during 1903 and the contents in fine gold are given below :—

State.	Weight of Gold.		Value of Gold.	
	Gross.	Fine Gold.	Total.	Proportion raised in each State.
	oz.	oz.	£	per cent.
New South Wales .....	295,778	254,260	1,080,029	5·89
Victoria .....	822,424	767,351	3,259,483	17·78
Queensland .....	921,363	668,546	2,839,813	15·49
South Australia .....	27,829	21,195	90,031	0·49
Western Australia.....	2,436,311	2,064,801	8,770,720	47·84
Tasmania .....	.....	59,891	254,403	1·39
Commonwealth .....	.....	3,836,044	16,294,479	88·88
New Zealand ..	533,314	479,749	2,037,831	11·12
Australasia .....	.....	4,315,793	18,332,310	100·00

The number of men engaged in mining for gold is shown in the following table, and it would appear that the average value of gold won by each miner is £230 6s 3d per annum. It is probable that the number of gold-miners in several of the states is largely overstated, otherwise the industry must be carried on at a great loss; and this will be the more apparent when it is remembered that a fairly large quantity of gold is obtained with other metals, the men employed in the exploitation of which are not classified as gold-miners. Moreover, many of the men employ themselves in mining for only a portion of their time, and devote the remainder to more remunerative pursuits. But when full allowance is made on this score it will be evident that, in some of the states at least, the search for gold is not a profitable occupation. The small return for South Australia is due to the large number of Chinese engaged in the

industry, many of them not possessing proper appliances for working the claims.

State.	Miners Employed.	Average production of Gold.	
		Quantity.	Value.
	No.	oz. fine.	£ s. d.
New South Wales.....	11,247	22·61	96 0 7
Victoria .....	25,208	30·44	129 6 1
Queensland .....	9,229	72·44	307 14 1
South Australia.....	2,000	10·60	45 0 4
Western Australia .....	20,716	99·67	423 7 7
Tasmania.....	988	60·62	257 9 10
Commonwealth .....	69,338	55·28	234 16 7
New Zealand .....	10,210	46·99	199 11 10
Australasia .....	79,598	54·22	230 6 3

The most extensive development of quartz-reefing is found in Victoria, some of the mines being of a great depth. At the end of 1903 there were eight mines in the Bendigo district over 3,000 feet deep, and fourteen over 2,500 feet. In the Victoria mine a depth of 3,750 feet had been reached, and in the Lazarus mine, 3,424 feet. On other fields there were six mines over 1,500 feet deep, the deepest of which were the South Star mine in the Ballarat district, where the shaft is down 2,520 feet, and the North Long Tunnel mine in the Walhalla district where a depth of 2,516 feet has been reached.

In Queensland, the West of Scotland mine, on the Gympie field, is worked at a depth of 3,156 feet, while several others exceed 2,000 feet in depth.

A notice of gold-mining would be incomplete without some reference to the remarkably large finds made at various times. Information on this point is meagre and not altogether reliable, as doubtless many nuggets were unearthed of which particulars were never published. Victoria's record is the best, and includes the following nuggets:—

	lb. oz. dwt.
"The Welcome Stranger," found 9th February, 1869.....	190 0 0
"The Welcome," found 9th June, 1858 .....	184 9 16
Nugget found at Canadian Gully, 31st January, 1853 .....	134 11 0

And others of the following weights:—98 lb. 1 oz. 17 dwt., 93 lb. 1 oz. 11 dwt., 84 lb. 3 oz. 15 dwt., 69 lb. 6 oz., 52 lb. 1 oz., 30 lb. 11 oz. 8 dwt., and 30 lb. 11 oz. 2 dwt.

New South Wales can boast of having produced some splendid specimens. In 1851 a mass of gold was found on the Turon, weighing 106 lb.; another, from Burrandong, near Orange, produced when melted at the Sydney Mint 98 lb 6 oz. 6 dwt. of pure gold; and a third, the "Brennan," was sold in Sydney in 1851 for £1,156. During 1880-82 several nuggets were discovered at Temora, weighing from 59 oz. to 1,393 oz.; and others, of 357 oz., 347 oz. (the "Jubilee"), 200 oz., 47 oz., and 32 oz. respectively, were found during the year 1887 in various parts of the state. Veins of gold of extraordinary richness have been worked in New South Wales. In January, 1873, at Beyers and Holtermann's claim, at Hill End, 1·02 cwt. of gold was obtained from 10 tons of quartz, and a mass of ore, weighing 630 lb. and estimated to contain £2,000 worth of gold, was exhibited. The Mint returns for this mine during the year 1873 were 16,279·63 oz., valued at £63,234 12s., obtained from 415 tons of stone. From Krohman's claim, at Hill End, gold to the value of £93,616 11s. 9d. was obtained during the same year. The foregoing figures, however, are insignificant when compared with the enormous yield of the Mount Morgan Mine, in Queensland, which has paid over £6,304,000 in dividends. This mine, which may be designated one of the wonders of the world, is a huge mound of ore, highly ferruginous, the peculiar formation, in the opinion of the Government Geologist of Queensland, being due to the action of thermal springs. To the end of November, 1903, 2,678,922 oz. of gold had been won from 2,110,067 tons of ore, yielding an average of 1 oz. 5 dwt. 9 gr. per ton of ore treated.

For the ten years ended 1903, the world's production of gold is estimated to have been as follows:—

Year.	Value.	Year.	Value.
	£		£
1894	37,345,000	1899	63,057,000
1895	39,191,000	1900	51,578,000
1896	41,000,000	1901	52,738,000
1897	48,088,000	1902	60,197,000
1898	58,137,000	1903	67,500,000

Of the world's production of £67,500,000 in 1903, Australasia raised 27·16 per cent.

#### SILVER.

Silver has been discovered in all the states, either alone or in the form of sulphides, antimonial and arsenical ores, chloride, bromide



iodide, and chloro-bromide of silver, and argentiferous lead ores, the largest deposits of the metal being found in the last-mentioned form. The leading silver mines are in New South Wales, the returns from the other states being comparatively insignificant. Up to the year 1882 the quantity of silver raised in New South Wales was very small, but in that and the following years extensive discoveries of the metal, associated principally with lead and copper ore, were made in various parts of the state, notably at Boorook, in the New England district, and later on at Sunny Corner, near Bathurst, and at Silvertown and Broken Hill on the Barrier Ranges in the Western district. The Sunny Corner Silver mines in 1886 paid handsome dividends, and produced £160,000 worth of silver, but since that period the yield has largely fallen off.

The fields of the Western district of New South Wales have proved to be of immense value. The yield of silver-lead ore in the Broken Hill and Silvertown districts during 1903 was valued at £1,066,114; while the machinery employed was valued at £610,000. This is much less than the value set down some years ago, the reduction being chiefly due to the removal of machinery to Port Pirie, in South Australia, where the smelting operations of the Proprietary Company are now wholly carried on. The aggregate output of silver-lead ore from the mines in the Barrier country to the end of the year named was valued at £32,011,187. This rich silver-field, which was discovered in 1883 by Charles Rasp, a boundary rider on Mount Gipps Run, extends over 2,500 square miles of country, and has developed into one of the principal mining centres of the world. It is situated beyond the river Darling, and close to the boundary between New South Wales and South Australia. In the Barrier Range district the lodes occur in Silurian metamorphic micaceous schists, intruded by granite, porphyry, and diorite, and traversed by numerous quartz reefs, some of which are gold-bearing. The Broken Hill lode is the largest as yet discovered. It varies in width from 10 feet to 200 feet, and may be traced for several miles, the country having been taken up all along the line of the lode, and subdivided into numerous leases, held by mining companies and syndicates.

The Broken Hill Proprietary Company holds the premier position. It possesses at Port Pirie, in South Australia, a complete smelting plant on the latest and most approved principles. From the commencement of mining operations in 1885 to the end of May, 1904, the company treated 7,134,526 tons of silver and silver-lead ores, producing 124,552,679 oz. of silver and 663,423 tons of lead, valued in the London market at £26,896,000. Dividends and bonuses to the amount of £7,760,000 have been paid, besides the nominal value of shares from the several "Blocks." The sum spent in the erection and construction of plant, from the opening of the property, has been about £1,308,746. The mine wages and salary sheet for the twelve months represented a sum of £573,563, including £175,261 paid to contractors. The net profit for the year was £179,782.

The quantity and value of silver and silver-lead ore exported by New South Wales to the end of 1903 is shown in the following table :—

Year.	Silver.		Silver-Lead.			Total value.
	Quantity.	Value.	Quantity.		Value.	
			Ore.	Metal.		
Up to	oz.	£	tons cwt.	tons cwt.	£	£
1882	765,397	187,429	203 12	.....	5,385	192,814
1883	77,066	16,488	105 17	..... ..	1,625	18,113
1884	93,660	19,780	4,668 1	.....	123,174	142,954
1885	794,174	159,187	2,095 16	190 8	107,626	266,813
1886	1,015,434	197,544	4,802 2	.....	294,485	492,029
1887	177,308	32,458	12,529 3	.....	541,952	574,410
1888	375,064	66,668	11,739 7	18,102 5	1,075,737	1,142,405
1889	416,895	72,001	46,965 9	34,579 17	1,899,197	1,971,198
1890	496,552	95,410	89,719 15	41,319 18	2,667,144	2,762,554
1891	729,590	134,850	92,383 11	55,396 3	3,484,739	3,619,589
1892	350,661	56,884	87,504 15	45,850 4	2,420,952	2,477,836
1893	531,972	78,131	155,859 1	58,401 3	2,953,589	3,031,720
1894	846,822	94,150	137,813 8	42,513 2	2,195,339	2,289,489
1895	550,142	81,858	190,192 19	29,657 7	1,560,813	1,642,571
1896	202,789	26,518	267,363 1	19,573 4	1,758,933	1,785,451
1897	150,005	16,711	270,913 14	18,105 7	1,681,528	1,698,239
1898	533,059	59,278	398,480 4	10,108 13	1,644,777	1,704,055
1899	692,036	76,913	424,337 5	20,289 10	1,993,744	2,070,657
1900	774,203	90,243	420,909 11	17,928 6	2,513,874	2,604,117
1901	448,501	50,484	400,156 18	16,921 5	1,803,979	1,854,463
1902	1,067,224	105,360	365,646 1	15,412 18	1,334,819	1,440,179
1903	1,099,373	113,755	330,581 7	18,483 2	1,387,648	1,501,403
Total	12,187,927	1,832,100	3,704,950 17	462,862 12	33,451,059	35,283,159

This amount was approximately made up of 160,996,160 oz. of silver, valued at £24,724,963; and of 844,387 tons of lead, valued at £10,558,196. It will be seen that the production of silver in New South Wales rapidly increased until 1891, when it exceeded in value the largest annual production of gold, even in the palmiest days of the diggings. Since that year, however, there has been a decreased output consequent upon the lower grade of the ores now being worked, while the value has been still further reduced by the serious decline in the prices of silver and lead. The price of silver has been declining steadily for some years, and in 1902 it fell below all previous records, while lead also depreciated in value, and as a consequence, all but four of the principal Barrier mines temporarily suspended the output of ore.

The serious effects of the decline may be judged from a comparison of the employment afforded by the industry during the three years ended with 1902. The number of miners engaged in silver and lead mines in 1900 was 8,196, and the average value of the metals won

amounted to £317 14s. 7d.; in 1901 the number of men employed had fallen to 6,298, and the average value won to £294 9s. 1d.; while in 1902 the men engaged numbered only 5,382, and the average value won £267 11s. 6d. The position improved in 1903, when the prices were slightly better, and the value of the output for the year showed an increase of £60,000; the men engaged numbered 6,035, and the average value per man amounted to £248 15s. 8d.

In addition to several others of a minor character, there are two large smelting works in New South Wales, one of which is situated at Cockle Creek, near Newcastle, and the other at Dapto. These works are principally engaged in treating silver ores, and have proved of great service to the mining communities in this and neighbouring states, as large supplies of ore are received for treatment from all parts of Australasia. The quantity of ore, the product of the state, treated during the year, was 55,587 tons, the metal obtained being as follows:—

Gold	...	...	...	...	22,567 oz.
Silver	...	...	...	...	1,286,185 oz.
Lead	...	...	...	...	22,087 tons.
Copper	...	...	...	...	204 tons.
Spelter	...	...	...	...	286 tons.

The number of men employed on these works at the end of 1903 was 891.

The only other state where silver has been produced to any extent is Tasmania. The industry has been steadily developed, and the production increased from £5,838 in 1888 to £293,043 in 1894. In 1903 the value was £193,246, in addition to lead valued at £75,280.

In this state, as in New South Wales, the result of the fall in silver and lead values is seen in the diminished value of production, and in this connection it must be remembered that a decline in price not only decreases the value of the output, but checks production, inasmuch as operations are restricted to dealing only with higher-grade ores. The principal silver fields are in the West Coast District, where the most important mines are the Zeehan-Montana and British Zeehan; and in the North-Western district where the Mount Magnet mine is located. The largest output of silver, however, is from the Mount Lyell mine, where the metal is found in conjunction with copper, and during the half-year ended 31st December, 1903, 364,288 oz. fine silver, valued at £39,974, were obtained from this mine. This, together with the output from the mines first mentioned, and that from the Zeehan Queen and Hercules mines, comprises nearly the whole of the production. The latter mine, situated in the Mount Read district, has abundance of silver ore mixed with copper in sight, in addition to extensive deposits of zinc.

Silver is found in various districts in Queensland, but generally associated with some other mineral, and the mines where silver predominates are but few. The chief of these is the Silver Spur mine at Texas, in the Stanthorpe district, on the border of New South Wales, from which silver and lead to the value of £9,241 were obtained during

1903. The last three years have witnessed a remarkable increase in the production of silver, despite the fall in prices. In 1900 the value of the production was only £12,712, but during 1901 it increased to £62,241, and in 1902 it reached £70,145, which is the highest value recorded since 1887, when it amounted to £80,092. The output of the preceding year was not quite maintained during 1903, but amounted to 642,125 oz., valued at £65,538. The great advance made in copper-mining during recent years is responsible for the increased silver production, as these minerals are usually found in association. This may be seen from the fact that the Herberton district, which was the chief copper-producing centre in 1903, also contributed the greater portion of the silver produced.

In New Zealand, silver is found in various localities, principally on the Te Aroha, Thames, and Coromandel fields, but the metal is generally obtained in conjunction with gold. The production of the colony during the year 1903 was 911,914 oz., valued at £91,497.

There are no silver-mines in Victoria or Western Australia, the small amount of silver produced in those states being usually found associated with gold. During 1903 the value of the silver produced in Western Australia was only £19,153, and in Victoria £2,880. The production of silver in South Australia is not large, the value in 1903 being £2,071, and it would seem that the argentiferous lead-ore fields of Broken Hill and Silverton, which are almost on the border of the two states, are exclusively confined within the boundaries of New South Wales.

Up to the end of 1903 New South Wales had produced 86·8 per cent. of the total value of silver raised in Australasia; Tasmania came second with 7·1 per cent.; and of the remaining small proportion, Queensland claimed the largest share. The total production of silver in Australasia in 1903, and up to the end of that year, was as follows:—

State.	Value of Silver produced—	
	During 1903.	To end of 1903.
	£	£
New South Wales .....	1,501,403	35,283,159
Victoria .....	2,880	864,319
Queensland .....	65,538	923,725
South Australia .....	2,071	140,441
Western Australia .....	19,153	40,225
Tasmania .....	268,626	2,872,276
Commonwealth .....	1,859,571	40,124,145
New Zealand .....	91,497	544,278
Australasia .....	1,951,068	40,668,423

The world's production of silver during the ten years ended 1903 is estimated to have been as follows :—

Year.	Ounces.	Year.	Ounces.
1894	178,668,000	1899	177,837,000
1895	182,220,000	1900	180,093,000
1896	176,707,000	1901	174,851,000
1897	182,081,000	1902	175,691,000
1898	179,252,000	1903	173,000,000

#### COPPER.

Copper is known to exist in all the states, and has been mined for extensively in South Australia, Tasmania, New South Wales, and Queensland. The fluctuations in the market value of the metal have always been a check to the progress of the industry, and at various periods in the last two years some of the lower-grade mines have been compelled to suspend operations. South Australia has produced the greatest quantity of copper, but of late years Tasmania has had by far the largest output. In Tasmania deposits were worked on a limited scale for a number of years ; but the discovery of a rich belt of copper-bearing country, extending from Mount Lyell past Mount Tyndall, Mount Read, Mount Murchison, and north of the Pieman to the Rocky and Savage Rivers, has completely changed the character of the mining industry in the state, and from a small export of copper ore valued at £1,659 in 1896, the annual production has become the largest in Australasia. The following table, which shows the annual production of copper during the last five years, will give some idea of the development of this branch of the mining industry. The output would appear to have fallen considerably in 1902, but this is due to the fact that in previous years the gold contents of the ore have been included in the values given.

	£
1899.....	762,138
1900.....	970,877
1901.....	1,010,937
1902.....	577,533
1903.....	485,640

The chief mines belong to the Mount Lyell Mining and Railway Company which also possesses reduction works at Queenstown, whence

a railway has been constructed through most difficult country to Teepookana and thence to Strahan. The company has lately amalgamated with the North Lyell Company, and the combined output of the mines during the half-year ended 31st December, 1903, amounted to 178,700 tons of ore, which proved to contain 3,706 tons of copper, 364,288 oz. fine of silver, and 10,280 oz. fine of gold, the total value thereof being £306,683.

The discovery of copper had a marked effect upon the fortunes of South Australia at a time when the young and struggling colony was surrounded by difficulties. The first important mine, the Kapunda, was opened up in 1842. It is estimated that at one time 2,000 tons were produced annually, but the mine was closed in 1879. Only tributors are now at work, but copper to the value of £1,000 was raised in 1903. The proprietors, however, intend to resume operations at an early date. In 1845 the celebrated Burra Burra mine was discovered. This mine proved to be very rich, and paid £800,000 in dividends to the original owners. For many years the average yield was from 10,000 to 13,000 tons of ore, yielding from 22 to 23 per cent. of copper. For the period of thirty years during which the mine was worked the output of ore amounted to 234,648 tons, equal to 51,622 tons of copper, valued at £4,749,224. Boring operations were conducted at the mine for the purpose of determining whether payable ore exists at greater depths than those reached by the original workings. One bore was put down to a depth of 1,004 feet, and in the opinion of the Government Geologist, the result was highly satisfactory, as it proved the continuance downwards of the copper-bearing strata sufficiently to warrant the re-opening of a portion of the mine. At present, operations are more or less exploratory in character, but 52 tons of ore were raised on the tribute system. The Wallaroo and Moonta mines, discovered in 1860 and 1861, proved to be even more valuable than the Burra Burra. The Moonta mine employed at one time upwards of 1,600 hands, and still keeps 1,138 men at work. In 1890 these mines were amalgamated, and about 1,800 miners are now employed. During 1903 the production from these mines was—Wallaroo 103,656 tons of ore yielding 3,242 tons of copper, and Moonta 61,210 tons of ore yielding 1,785 tons of copper. From the Hamley mines, where 76 men were employed, 4,631 tons of ore were obtained, which yielded 1,066 tons of copper. The total dividends paid by these mines were stated to be upwards of £1,700,000. The production of copper in South Australia during the last few years has again increased, the output in 1901 being valued at £500,077, in 1902 at £432,525, and in 1903 at £472,014.

The copper-mining industry in New South Wales has been subject to great variations. The production reached its highest point in 1883, when the value was £472,982. From that year, however, there was a general decline, and in 1894 the value was only £63,617. As in the other states, so in New South Wales, the increased prices of later years caused more attention to be directed to the

industry, and the production in 1901 had attained a value of £412,292. A heavy fall in prices occurred during that year, however, which, combined with the drought, caused a considerable falling off in production and value. The value of the output in 1902 was only £307,806, but with a more favourable season it increased to £446,286 in 1903. The chief copper mines are in the western districts, but the production is hampered by lack of a constant water supply. The principal deposits are found in the central part of the state, between the Macquarie, Bogan, and Darling Rivers. Cupriferous strata have also been located in the New England and Southern districts, as well as at Broken Hill, thus showing that the mineral is widely distributed. The largest proportion of the copper produced during 1903 was obtained in the Cobar mining district. The value of the metal raised in the Cobar division of the district amounted to £221,242. It is in this district that the Great Cobar, the largest copper mine in New South Wales, is situated. The Nymagee division of the Cobar district produced copper to the value of £41,150, and the recently developed mines at Crow's Creek and Shuttleton bid fair to increase the output materially in the near future. In the Burruga division of the Bathurst district one of the leading mines, the Lloyd Copper mine, is situated, and from this mine 1,825 tons of copper, valued at £100,375, were obtained during 1903. The lode, which averages 5 feet in width, still maintains its richness, and there are sufficient supplies in sight to last some years. The company employs about 370 men, exclusive of wood-cutters, carters, &c., and the mine and works are lighted throughout by electricity. The total number of men engaged in copper-mining during 1903 was 1,816, an increase of 117 on the numbers of the preceding year.

Copper is found in many parts of Queensland, the principal deposits being in the Herberton and Mount Perry districts. In earlier years the state occupied a prominent position as a producer of copper, but the output in recent years was very small. The year 1901, however, saw a sudden revival in this branch of the mining industry, despite a great fall in prices, and the value of the production rose to £194,227, being the highest value recorded with the exception of 1872, when it reached £196,000. This figure, however, was not maintained in 1902, the production for that year amounting to 3,784 tons, valued at £189,200, the decline being chiefly attributable to want of water. In 1903, however, the output exceeded that of any previous year, and amounted to 4,916 tons, valued at £385,122. A noteworthy feature of the revival in 1901 was the re-opening of the Mount Perry mine, which again ranks, as in former years, amongst the foremost mines in the state. The smelting returns of this mine for the year 1903 showed 1,765 tons of copper, valued at £93,103, in addition to silver valued at £7,076, and gold to the value of £5,236. The Herberton district has for many years been the chief copper-producing centre, the output in 1903 being valued at £150,510. In this district the principal mines are those of

the New Chillagoe Railway and Mining Company, which has also leased the Mount Garnet mines for a period of two years. Of the other mines in the district, the Mount Molloy shows the best results, and during the year produced 800 tons of ore averaging 35 per cent. of copper, in addition to 200 tons of a lower grade.

One of the chief obstacles to the successful development of copper and silver-mining has been the lack of facilities for transport, but with the increased advantages in this respect which are being afforded year by year, the output of copper and silver may be expected to increase materially.

In Western Australia, copper deposits have been worked for some years. Very rich lodes of the metal have been found in the Mount Malcolm, Northampton, Murchison, West Pilbarra, and Phillips River districts, but operations appear to be carried on systematically only in the first mentioned. The ore raised in this district is treated locally, while in the others it is exported for treatment, and, as the cost of carriage is heavy and the facilities for transport unfavourable, only high-grade ores can be profitably worked. The copper ore raised in the state during 1901 amounted to 10,156 tons, valued at £75,246, but in 1902 only 2,262 tons, with a value of £8,090, were produced. There was an increased output in 1903, amounting to 21,531 tons, valued at £56,541. The unfortunate fall in the price of the metal has restricted operations, but as there seems no doubt that eminently payable copper lodes, carrying a little gold, exist in the state, it is surprising that the success of the preceding three years has not further stimulated the progress of the industry. The number of men engaged in copper-mining in 1903 was 193, as against 113 in the preceding year.

Copper-mining has not attained any great proportions in Victoria, although deposits have been found in several parts of the state, particularly in the Beechworth district, where they have been traced over an area of some 50 square miles. The value of the total production is estimated at £206,895, but the output during the last few years has been very small, the value for 1903 being £500.

The copper deposits of New Zealand have been worked to a small extent only, and for a number of years have been almost entirely neglected, the output in 1903 being only 6 tons, valued at £123.

Copper is sometimes found in the Australasian mines in a virgin state, and beautiful specimens of the pure metal have been exhibited at different times, but it occurs generally in the form of oxidised copper ores, carbonates, sulphates, phosphates, and silicates of copper. The museums of South Australia, Victoria, and New South Wales contain striking samples of azurite and malachite, magnificent blocks of which have been shown from time to time at exhibitions, not only in Australasia, but also in Europe and America. Copper sulphides and arsenides are generally found in deep sinkings. The metal has also been found associated with tin in the form of stannine.



The total value of copper produced in each state during 1903 and up to the end of that year is given below :—

State.	Value of Copper produced.	
	During 1903.	To end of year 1903.
	£	£
New South Wales .....	446,286	6,611,165
Victoria .....	500	206,895
Queensland .....	285,122	2,724,014
South Australia .....	472,014	23,726,585
Western Australia .....	56,541	391,603
Tasmania .....	486,640	4,984,668
Commonwealth .....	1,746,103	38,644,930
New Zealand .....	123	18,211
Australasia .....	1,746,226	38,663,141

In June, 1872, copper realised as much as £112 per ton, whilst in December, 1886, the lowest price on record until that time was touched, and only £44 could be obtained for South Australian copper. At the end of 1887 the price had risen to £70 per ton, and in September, 1888, to £93. In March, 1889, there was a great fall in the price of the metal, and in April of that year the quotation in London was as low as £43 per ton. This was the lowest price reached until June, 1894, when it fell to £41 10s. From that date there was an upward movement, as the following quotations will show. At the close of 1896 the London price of copper stood at £52 10s. per ton; in February, 1897, £54 10s. was reached; and at the 31st December, 1898, £60 was the market value. This price was further increased during 1899, and in September of that year no less than £77 per ton was quoted. The price was well maintained during 1900, and, at the close of the year, stood at £73 per ton; but in 1901 a heavy fall occurred, and the quotations for the last week of the year were as low as £49 15s. per ton. During 1902 prices remained low, but gradually improved towards the end of the year. In the first week of January, 1903, the value was £53 12s. 6d. per ton, and at the end of that year £56 12s. 6d.

#### TIN.

Tin was known to exist in Australasia almost from the first years of colonisation, the earliest mention of the metal appearing in a report of a discovery by Surgeon Bass on the north coast of Tasmania. In the form of cassiterite (oxide of tin) it occurs in all the states, but the richest deposits have been found in Tasmania—the Mount Bischoff being the most celebrated tin-mine in Australasia. Expert authorities have also stated that Queensland and the Northern Territory of South Australia possess rich deposits of tin ore.

Tasmania has been the largest producer of tin in Australasia, and since 1880 no less than 74,637 tons of tin, valued at £6,912,336 have been exported. In 1903 the production amounted to 3,476 tons, valued at £238,883. As in New South Wales, a very large proportion of the metal hitherto produced has been from alluvial deposits. There are, however, many promising lodes in the island, and the Waratah, Blue Tier, Ben Lomond, St. Helen's, Derby, and West Coast districts all produce large quantities of the metal. In the district first mentioned is situated the Mount Bischoff mine, worked as an open quarry, which, during the six months ended 31st December, 1903, produced 636 tons of tin, and paid £27,000 in dividends, making a total of £1,912,000 dividends paid to that date. In the Blue Tier district, the Australian and Anchor mines are working on good payable stone, and from the latter mine 116 tons of tin, were obtained during the half-year ended 31st December, 1903. Of the mines in the North-Eastern District, the most important are the Briseis, at Derby, and the Pioneer, at Bradshaw's Creek. The former, produced 216 tons of tin, during the half-year ended 31st December, 1903, while the latter yielded 192 tons of stream tin, and paid dividends amounting to £10,300. Tin dredging has been carried on in some parts of the island; but, so far, only a moderate measure of success has been achieved.

In New South Wales lode tin occurs principally in the granite and stream tin under the basaltic country in the extreme northern portion of the state, at Tenterfield, Emmaville, Tingha, and in other districts of New England. The metal has also been discovered in the Barrier Ranges, at Poolamacca and Euriewie; near Bombala in the Monaro district; at Gundule, near Kempsey; at Jingellic, on the Upper Murray; at Dora Dora, on the Upper Murray; and in the Valley of the Lachlan; but in none of these districts has it been worked to any extent. The mineral was discovered by the Rev. W. B. Clarke so far back as the year 1853, but the opening of the tin-fields of New South Wales only took place in the year 1872. A large proportion of the tin obtained is recovered from alluvial deposits, and this may be assigned as the principal reason for the fluctuations in the output, as any scarcity of water diminishes the production by retarding successful washing operations.

The industry soon attained considerable importance, the value of the output in 1881 amounting to £568,795. In 1889 the total production had fallen to £207,670, and in 1893 to £126,114, while in 1898 the lowest point was reached, when the value was only £45,638. Owing to a recovery in prices there was an increase in value of production during the next two years when the totals were £90,482 and £142,724 respectively, but in 1901 there was a decline to £76,544, and in 1902 to £59,593, consequent on a fall in prices and a sustained drought. With the more favourable season of 1903 the production again advanced, and attained a value of £155,723.

Considerable success has attended the efforts to recover tin by dredging, and the yield for 1903 amounted to 244 tons, valued at

£20,100. Of this production, 190 tons, valued at £15,532, were obtained in the Tingha district, chiefly by the Cope's Creek dredges, which saved 150 tons, valued at £12,455; from Wylie Creek, in the Wilson's Downfall district, 50 tons, valued at £4,229 were obtained. The number of persons engaged in mining for tin on the 31st December, 1903 was 2,502, of whom 455 were Chinese.

In Queensland, the value of tin produced during 1873 reached £606,184, being next in importance to that of gold, but thenceforward there was a decline, the yield in 1898 falling to £36,502. Since that year, however, some attempt has been made to develop the industry in a manner more worthy of its resources, with the result that in 1903, assisted by a good season, the production reached 3,708 tons, valued at £243,149, being the highest value since 1874. The Herberton district was again the chief centre of production, the output in 1903 being valued at £181,022. The most important mines in this district are situated at Irvinebank and Stannary Hills, and from the Vulcan mine, in the former locality, 6,161 tons of black tin, valued at £205,560, have been obtained since October, 1890. The output of the mine for 1903 was 693 tons, valued at £24,560. From the Stannary Hills mines, 209 tons, valued at £15,848, were obtained during the five months ending December, 1903. In 1901 a rich discovery of tin was made at Smith's Creek, near the Mount Garnet railway, and shafts sunk to a depth of 300 feet have proved the lode to be continuous; the output up to the end of the year 1903 was 540 tons of concentrates, valued at £38,013. The number of persons engaged in tin-mining on the 31st December, 1903, was 1,598.

In Western Australia, tin has been found to exist in large quantities, but the ore is of inferior quality, and, until recent years the industry languished owing to the superior attractions of the goldfields, the average annual production for the three years ending with 1898 being only £3,960. The advance in price gave a stimulus to the industry in the following year, and the output increased considerably, being valued at £25,270. In 1900 the yield amounted to £56,702, but declined during the next year to £40,000, while in 1902 only 620 tons, valued at £39,783, were produced. The production in 1903 was 817 tons, valued at £55,890; the Greenbushes district contributed 525 tons, valued at £34,362, and the Pilbarra field, in the Marble Bar district, 292 tons, valued at £21,528. The full development of the industry in both districts is retarded by the inadequacy of the water supply.

The yield of tin in Victoria is small, no discoveries of any importance having been recorded prior to 1890, but towards the end of that year extensive deposits were reported to exist in the Gippsland district at Omco and Tarwin. In 1903 the production was only 33 tons, valued at £2 165 and was obtained in connection with gold-dredging.

In South Australia very little tin is produced. Durin 1903 the production was 171 tons of ore, valued at £10,772, obtained in the

Northern Territory of the State. There is no record of any production of tin in New Zealand.

The tin-mining industry has been subject to frequent fluctuations, especially of late years. The value of the metal in the European market was £159 per ton in 1872, £52 in 1878, £114 in 1880 and 1882, and £72 in 1884. A gradual recovery then took place, until in 1888 the price reached £121. During the ten years from 1888 to 1898 tin was subject to an almost continuous fall in price, realising in 1898 only one-half of that obtained a decade before. The metal, however, made a great advance in price during 1900, London quotations in December being £125 10s. per ton, as compared with £82 in 1898, and £63 in 1897, and although this value was not maintained during 1901, the prices current at the end of the year averaged £109 10s. per ton. Since 1901 there has been a further improvement, and for the first week of 1903 the quotations were £123 10s. per ton, while at the close of the year they had risen to £129 10s. per ton.

The value of the production of tin in Australasia during 1903, and up to the end of that year, was as given below :—

State.	Value of Tin produced.	
	During 1903.	To end of year 1903.
	£	£
New South Wales .....	155,723	6,817,122
Victoria .....	2,165	718,163
Queensland .....	243,149	5,053,186
South Australia .....	10,772	49,530
Western Australia .....	55,890	293,872
Tasmania .....	238,883	7,758,167
Australasia .....	706,582	20,690,040

The number of persons engaged in tin-mining in 1903 was as follows :—In New South Wales, 2,502 ; Tasmania, 1,258 ; Queensland, 1,598 ; Western Australia, 294 ; South Australia, 50.

#### IRON.

Iron is distributed throughout the Commonwealth, and extensive deposits are known to exist in New South Wales, Queensland, South Australia, Western Australia, and Tasmania. In evidence before the Royal Commission on the Bonus for Manufactures Bill, it was stated that the deposits in New South Wales were estimated by the Government

Geologist to contain 59,317,000 tons of ore. The chief deposits are at Carcoar, where they are estimated to contain 3,100,000 tons, and at Cadia, where the quantity is set down at 39,000,000 tons. The ores in the former locality contain rather a high percentage of phosphorus, while at Cadia the product is impregnated with sulphur and copper.

In Queensland the principal deposits occur in the Northumberland and other islands between Rockhampton and Bowen, at Mount Lucy in the Herberton district, at the Iron Mountain in the Kangaroo Hills, and at Mount Leviathan in the Cloncurry district.

In South Australia large deposits of iron ore are found, the most important being those at the Iron Knob and Iron Monarch mines, situated about 40 miles west of Port Augusta. The ore contents of the Iron Monarch were estimated to be 20,000,000 tons.

The deposits in Western Australia are widely distributed, the most important being those in the watershed of the Murchison River, but owing to their geographical position they are practically valueless.

In Tasmania the chief deposits are on the Blythe River, near Burnie, where they are situated within easy distance of shipping facilities. During 1901 the deposit was tested by tunnelling and found to maintain its size and quality, and it is estimated to contain 17,000,000 tons of ore. Considerable attention has been given to the question of establishing ironworks in New South Wales capable of supplying the requirements of Australia, and in 1901 the idea assumed a definite shape. Two schemes were advocated—one to smelt ore at Lithgow from the Carcoar and Cadia deposits, and the other to bring ore from the Blythe River, Tasmania, and smelt it in Sydney or elsewhere on the seaboard. Had the Bonus for Manufactures Bill, introduced into the Federal Parliament, been passed in the same form as submitted, there is no reason to doubt that one of these schemes would have been adopted and the industry established immediately by private enterprise. The amendments made in the Bill, however, provide only for a bonus to works established by a State of the Commonwealth, and in view of the importance of the question, the Federal Government appointed a Royal Commission to inquire into the whole matter. The Commission held meetings in various towns of the Commonwealth, and collected a great deal of valuable evidence regarding the iron deposits in the various states, and the possibility of their successful treatment. In submitting their report the members were unanimously agreed that all the materials necessary for the manufacture of iron from its ores were to be found in Australia, in large quantity and of good quality, but they were evenly divided in opinion as to the desirableness of paying bonuses to private individuals, and it was only by the casting vote of the Chairman that the report was in favour thereof. As to the desirableness of establishing the iron industry there can be no doubt, as each year Australia pays away huge sums for its requirements in this direction. The imports in 1903 were valued at £1,429,996, and in previous years even this amount has been greatly exceeded. The following

table shows the value of the imports of iron and steel for the last five years, and their approximate weights:—

Year.	Bar and Rod Iron, Girders, Plate, and Sheets.		Galvanised, Plate, and Sheet Iron.		Pig and Scrap Iron.	
	Quantity.	Value.	Quantity.	Value.	Quantity.	Value.
	cwt.	£	cwt.	£	cwt.	£
1899	1,855,895	834,211	916,700	780,279	723,920	127,872
1900	2,223,731	1,176,655	983,399	966,201	985,265	230,245
1901	2,081,423	967,323	905,709	741,795	732,512	140,572
1902	.....	744,007	1,104,701	948,059	766,725	131,015
1903	1,211,437	483,448	836,570	786,413	989,988	160,135

In addition to the above, the imports of iron in its manufactured forms, including nails, pipes, tanks, wire, &c., amounted to about £1,780,000 in 1903, so that the total imports for the year reached over £3,210,000. The re-exports were valued at only £84,000; it follows, therefore, that the iron retained for local use was worth some £3,126,000, and as the tendency of the consumption is to increase with production, the quantity of iron required for home use would certainly become greater if works were established locally. The experience of the United States may be cited in this respect. In 1895 the production of ore was 15,958,000 tons, in 1898 it had increased to 19,434,000 tons, and in 1901 to 28,887,000 tons. The consumption for the same years was 16,480,000, 19,589,000, and 29,789,000 tons respectively, having increased from 0·24 tons per head in 1895 to 0·38 tons in 1901.

The production of iron-ore amounts to between 85 and 90 million tons annually, and probably three-fourths of this is produced by the United States, Germany, the United Kingdom, and Spain.

In 1901 the output of iron-ore and the production of pig-iron in various countries was as follows:—

	Output of Iron Ore. tons.	Production of Pig-iron. tons.
United States .....	23,887,000	15,878,000
United Kingdom.....	16,570,000	7,929,000
Germany .....	16,304,000	7,741,000
Spain .....	7,780,000	.....
France .....	4,714,000	2,351,000
Austria-Hungary .....	3,463,000	1,458,000
Sweden .....	2,750,000	520,000
Belgium.....	223,000	752,000
Russia .....	.....	2,776,000

At present the only works in the Commonwealth for the manufacture of iron from the ore are situated at Eskbank, near Lithgow, in New South Wales, where red siliceous ores, averaging 22 per cent., and brown hematite, yielding 50 per cent., metallic iron, have been successfully treated. Abundance of coal and limestone are found in the

neighbourhood. Even at these works the manufacture of pig-iron, for which the establishment was originally built, has been abandoned for some years, and the work now carried on consists in the re-rolling of old rails, and the manufacture of iron bars, rods, and nails, and of ordinary castings. The quantity manufactured from scrap during 1903 was 6086 tons, valued at £85,790. During the past four years considerable quantities of iron ore have been raised from the deposits situated in the Marulan, Picton, and Carcoar districts and despatched to the smelting-works at Dapto and Cockle Creek, where they have been used as flux, the gold contents of the ore helping to defray the extra cost of railway carriage. The total raised in 1903 was 22,120 tons, valued at £15,834, and up to the end of that year 63,478 tons, valued at £49,422, had been raised. A considerable quantity of iron oxide is also raised each year and used for flux, while there is also an export, usually of small dimensions, but amounting in 1903 to 1,193 tons, valued at £1,181.

In Tasmania, notwithstanding the huge deposit of iron ore at the Blythe River, the production has not been great, and in 1903 only 9,320 tons, valued at £3,300, were raised, the greater portion of which was shipped to New South Wales for fluxing purposes.

In Queensland 9,808 tons of ore, valued at £3,852, were raised, chiefly in the Herberton district, for use as a flux in smelting, and in South Australia 33,359 tons were obtained from the deposits at Iron Knob and used in the Broken Hill Proprietary Company's reduction works at Port Pirie.

In Western Australia the only iron raised is for smelting purposes, the production in 1903 being 220 tons, valued at £88.

In New Zealand 17 tons of hematite, valued at £116, were raised in 1903, but there was no production in 1903.

Goethite, limonite, and hematite are found in New South Wales, at the junction of the Hawkesbury sandstone formation and the Wianamatta shale near Nattai, and are enhanced in value by their proximity to coal-beds. Near Lithgow extensive deposits of limonite or clay-band ore are interbedded with coal. Siderite or spathic iron (carbonate of iron) and vivianite (phosphate of iron) are found in New Zealand. The latter also occurs in New South Wales, intermingled with copper and tin ores.

The Government of South Australia has offered a bonus of £2,000 for the first 500 tons of pig-iron produced in that state.

#### ANTIMONY.

Antimony is widely diffused throughout Australasia, and is sometimes found associated with gold. The low price of the metal during late years has discouraged operations in this branch of the mining industry, and the output in all the states has fallen away considerably. In New South Wales, deposits of antimony occur in various places, chiefly in the Armidale, Bathurst, and Rylstone districts; and at

Bowraville on the North Coast. The production, however, is confined to the Hillgrove mines, and in 1903 was valued at only £135, the total production to the end of the year being £194,910.

In Victoria the production up to the end of 1898 was valued at £177,174, and there was no further output until 1903, when the value was £50, while in Queensland the production ceased in 1899, when the value raised was only £200. In New Zealand also, the production of antimony has practically ceased, although during 1901 there was an export of 3 tons, valued at £101. Good lodes of stibnite (sulphide of antimony) have been found near Roebourne, in Western Australia; but no attempt has yet been made to work them.

The following table shows the value of antimony produced in Australasia up to the end of 1903 :—

State.	Value.
New South Wales .....	£194,910
Victoria ....	177,224
Queensland .....	35,458
Commonwealth .....	£407,592
New Zealand .....	52,462
Australasia .....	£460,054

#### BISMUTH.

Bismuth is known to exist in all the Australian states, but up to the present time it has been mined for in New South Wales, Queensland, South Australia, and Tasmania only. The demand for the metal is limited, and mining is hardly remunerative at present prices. The output in New South Wales during 1903 was valued at £9,537, and in Queensland at £2,523, while the total production for each state up to the end of the year was £75,822 and £67,058 respectively.

#### MANGANESE.

Manganese probably exists in all the states, although no deposits have as yet been found in Tasmania. Little, however, has been done to utilise the deposits, the demands of the local markets being extremely limited; but in the event of the extensive iron ores of New South Wales being worked on a large scale, the manganese deposits in that state will become of commercial importance. The ore generally occurs in the form of oxides, manganite, and pyrolusite, and contains a high percentage of sesquioxide of manganese. The production has never attained much importance in any of the states. The value of the output in New South Wales during 1903 was £254, making a total of £1,655 up to the end of that year.



In Queensland the output for 1903, valued at £5,332, was obtained solely from the Mount Miller mine, the entire yield being absorbed by the works of the Mount Morgan mines. The total value of the production of this metal in Queensland to the end of 1903 was £30,312.

In New Zealand the production in 1903 was 70 tons, valued at £210, making the total raised to the end of that year £60,442. In South Australia there was an export during 1902 of 18 tons, valued at £62, but there is no record of production in 1903.

#### PLATINUM.

Platinum and the allied compound metal iridosmine have been found in New South Wales, but so far in inconsiderable quantities, the latter occurring commonly with gold or tin in alluvial drifts. At present mining operations are confined to the deposits in the Fifield district, which, however, give evidence of depletion. The value of the production during 1903 was £1,061, and the total to the end of that year, £15,022. Platinum and iridosmine have also been found in New Zealand.

#### TELLURIUM.

The noble metal tellurium has been found in New Zealand, associated with gold and silver (petzite) and with silver only (hessite). It has also been discovered in New South Wales at Bingara and other parts of the northern districts, as well as at Tarana, on the Western Line, though at present only in such minute quantities as would not repay the cost of working; while at Captain's Flat it has been found in association with bismuth.

At many of the mines at Kalgoorlie, Western Australia, large quantities of ores of telluride of gold have been discovered in the lode formations.

#### LEAD.

Lead is found in each of the Australasian States, but is worked only when associated with silver. In Western Australia the metal occurs in the form of sulphides and carbonates of great richness, but the quantity of silver mixed with it is small, and the production of late years has been very limited. In 1902 it amounted to 36 tons, valued at £277, but there was no production in 1903.

In Queensland the lead raised during 1903 amounted to 3,795 tons, valued at £43,639, obtained from mines in the Herberton district, and from South Australia lead to the value of £1,267 was exported during the year. As will be gathered from the remarks made in a previous portion of this chapter, the association of lead with silver has proved a source of much wealth to the silver mines in New South Wales—those at Broken Hill particularly—several of these mines being only enabled to continue operations owing to the high price of the lead contained in the ore.

## OTHER METALS.

Mercury, in the form of sulphides or cinnabar, is found in New South Wales, Queensland, and New Zealand. In New South Wales cinnabar has been discovered on the Cudjegong River, near Rylstone, and it also occurs at Bingara, Solferino, Yulgilbar, and Cooma. In the last-mentioned place the assays of ore yielded 22 per cent. of mercury. Very large and rich deposits have been found on Noggriga Creek, near Yulgilbar, where a mine has been established, and 40 tons of ore raised, which yielded 1,010 lb. of quicksilver. A bonus of £500 is offered by the Mines Department to the person or company first producing 50,000 lb. of quicksilver from cinnabar ores raised within the state. In New Zealand during 1903 the Waitahuna Company carried on prospecting operations, but although indications of the presence of the ore were in evidence work was discontinued through lack of funds.

Titanium, of the varieties known as octahedrite and brookite, is found in alluvial deposits in New South Wales, in conjunction with diamonds.

Wolfram (tungstate of iron and manganese) occurs in most of the states, notably in New South Wales, Tasmania, Queensland, and New Zealand. For some years there had been a small output in Queensland, and a rise in the price of the mineral so stimulated the industry that in 1899 the production reached £10,060. As the demand is limited, the increased price soon led to overproduction and a consequent fall in prices, and the production in 1902 dwindled to 55 tons, valued at £1,167. Another rise in prices caused increased attention to be devoted to the industry, and the production during 1903 was 197 tons, valued at £7,870. There was a little wolfram exported from South Australia during 1901, the quantity being 5 tons, valued at £175. In 1900 Tasmania produced a small quantity of the metal, valued at £2,058. Scheelite, another variety of tungsten, is found in Queensland and New Zealand, a little mining being carried on in the latter colony, where 39 tons, valued at £1,200, were raised in 1902. Molybdenum, in the form of molybdenite (sulphide of molybdenum), is found in New South Wales, Victoria, and Queensland, but only in the last-mentioned state was there any production during 1903, the value being £2,100.

Zinc ores, in the several varieties of carbonates, silicates, oxide, sulphide, and sulphate of zinc, have been found in several of the Australasian States, but have attracted little attention, except in New South Wales, where the metal is usually found associated with silver, lead, and copper; and various experiments are being made for the purpose of ascertaining whether it can be profitably extracted. For some years attention has been directed by the Broken Hill Companies to the production of a high grade zinc concentrate from the sulphide ores, and a fair measure of success has attended their efforts. Three distinct processes are being used at the Barrier mines, and one of the companies is devoting all its energies to zinc extraction. At Cockle Creek there

are also two zinc-extracting plants operating on purchased ores. As a consequence of these efforts the export of zinc shows a large increase. From a value of £44,187 in 1900 it had diminished to £10,625 in 1902, but in 1903 no less than 20,754 tons, valued at £86,587, were exported, making a value of £258,335 up to the end of that year. The world's production of spelter in 1903 was 585,000 tons.

Nickel, so abundant in the island of New Caledonia, has up to the present been found only in Queensland and Tasmania; but few attempts have been made to prospect systematically for this valuable mineral. In 1894 Tasmania produced 136 tons of nickel ore, valued at £544; but none has been raised since that date.

Cobalt occurs in New South Wales, Victoria, and South Australia, and efforts have been made in the former state to treat the ore, the metal having a high commercial value; but the market is small, and no attempt has yet been made to produce it on any large scale. In South Australia the Cooke's Proprietary Company are working their mine, and have opened up large bodies of ore. Small parcels forwarded to Germany for treatment gave satisfactory results. The manganese ores of the Bathurst district of New South Wales often contain a small percentage of cobalt—sufficient, indeed, to warrant further attempts towards its extraction. The only deposits being worked at the present time are at Port Macquarie, where very promising ore has been opened up. During 1903, 153 tons, valued at £1,570, were exported.

Chrome iron or chrome ore has been found in New Zealand and Tasmania. In New South Wales chromium is found in the northern portion of the state in the Clarence and Tamworth districts, and also near Gundagai, usually in association with serpentine. Mining operations in New South Wales are confined to the deposits at Gobarralong, near Gundagai, as it is uncertain whether those at Bowling Alley Point could be profitably worked. The accessible deposits at these mines are now almost worked out, and the production has consequently slackened. In 1899 the export was valued at £17,416, but in 1903 it had declined to £7,342. In New Zealand, chrome ore to the value of £37,367 was extracted between 1858 and 1866, but there was no further production until the year 1900, when the value amounted to only £110. In 1902 there was also a small output, amounting to 175 tons, valued at £525, but there was no production in 1903.

Sulphur exists in large quantities in the volcanic regions of New Zealand, where it will doubtless some day become an important article of commerce. The output in 1900 was 1,692 tons, valued at £4,824, but in 1902 only 100 tons, valued at £475, were raised. It is also said to occur in small quantities at Mount Wingen, in the Upper Hunter district of New South Wales; at Tarcutta, near Wagga Wagga; and at Louisa Creek, near Mudgee.

Arsenic, in its well-known and beautiful forms, orpiment and realgar, is found in New South Wales and Victoria. It usually occurs in association with other minerals, in veins.

## COAL.

Australasia has been bountifully supplied by Nature with mineral fuel. Five distinct varieties of black coal, of well characterised types, may be distinguished, and these, with the two extremes of brown coal or lignite, and anthracite, form a perfectly continuous series. For statistical purposes, however, they are all included under the generic name of "coal," and therefore these minerals will be considered here only under the three main heads—lignite, coal, and anthracite.

Brown coal or lignite occurs principally in New Zealand and Victoria. Attempts have frequently been made to employ the mineral for ordinary fuel purposes, but its inferior quality has prevented its general use. In Victoria there is usually a small annual output, the quantity raised in 1903 amounting to 5,661 tons, valued at £2,827. The fields of lignite in New Zealand are roughly estimated to contain about 500 million tons; the quantity raised annually is increasing, and in 1903 it amounted to 77,372 tons.

Black coal forms one of the principal mineral resources of New South Wales; and in the other states and New Zealand the rich deposits of this valuable substance are rapidly being developed. That they form an important source of commercial prosperity cannot be doubted, as the known areas of the coal-fields of this class in New South Wales have been roughly estimated to contain about 79,198 million tons, and in New Zealand 500 million tons. New Zealand also possesses a superior quality of bituminous coal, which is found on the west coast of the Middle Island. An estimate places the probable contents of these coal-fields at 200 million tons. Coal of a very fair description was discovered in the basin of the Irwin River, in Western Australia, as far back as the year 1846. It has been ascertained from recent explorations that the area of carboniferous formation in that state extends from the Irwin northwards to the Gascoyne River, about 300 miles distant, and probably all the way to the Kimberley district. The most important discovery of coal in the state so far is that made in the bed of the Collie River, near Bunbury, to the south of Perth. The coal has been tested and found to be of good quality; and there are grounds for supposing that there are 250 million tons on this field. One of the earlier Government Geologists of Queensland gave it as his opinion that the extent of the coal-fields of that state is practically unlimited, and that the carboniferous formations extend to a considerable distance under the Great Western Plains. It is roughly estimated that the coal measures at present practically explored extend over an area of about 24,000 square miles. In Tasmania and Victoria large deposits of coal have also been found; and in all the states the industry is being prosecuted with vigour.

Coal was first discovered in New South Wales in the year 1797, near Mount Keira, by a man named Clark, the supercargo of a vessel called the Sydney Cove which had been wrecked in Bass Straits. Later in

the same year Lieutenant Shortland discovered the river Hunter, with the coal-beds situated at its mouth. Little or no use, however, was made of the discovery, and in 1826 the Australian Agricultural Company obtained a grant of 1,000,000 acres of land, together with the sole right, conferred upon them by charter, of working the coal-seams that were known to exist in the Hunter River district. Although the company held this valuable privilege for twenty years, very little enterprise was exhibited by them in the direction of winning coal, and it was not until the year 1847, when their monopoly ceased and public competition stepped in, that the coal-mining industry began to show signs of progress and prosperity. From the 40,732 tons extracted in 1847, the quantity raised had in 1903 expanded to the large figure of 6,354,846 tons, valued at £2,319,660, both the output and value in the latter year being the highest recorded. The total production of the New South Wales mines, from the date of their opening up to the end of 1903, amounted to 109,741,916 tons, valued at £44,021,103.

The coal-fields of New South Wales are classed in three districts—the Northern, Southern, and Western districts, but it is thought that coal deposits extend over nearly the whole length of the sea-coast. The first of these comprises chiefly the mines of the Hunter River district; the second includes the Illawarra district and, generally, the coastal regions to the south of Sydney, together with Berrima, on the table-land; and the third consists of the mountainous regions on the Great Western Railway, and extends as far as Dubbo. The total area of the carboniferous strata of New South Wales is estimated at 23,950 square miles. The seams vary in thickness. One of the richest has been found at Greta, in the Hunter River district; it contains an average thickness of 41 feet of clean coal, and the quantity underlying each acre of ground has been computed to be 63,700 tons.

It has long been known that a seam of coal existed under Sydney Harbour, and in 1899 a syndicate was formed to determine at what depth the deposit was situated. After boring operations had been carried on to a depth of 2,917 feet, a seam of coal 10 feet 3 inches—supposed to be identical with that at Bulli—was struck, and the syndicate now known as the Sydney Harbour Collieries (Limited) acquired mining rights extending over 10,167 acres. Some difficulty occurred in the selection of a site, but it was at length determined to sink the mine at Balmain, and a small seam of coal was found at a depth of 2,880 feet, while two other seams were struck at depths of 2,933 feet and 2,950 feet. It is fully expected that these seams will be found to unite, and, should this prove to be the case, the effect on the industrial progress of Sydney will be of the utmost importance. At present the output from the mine is limited, but the coal is of good quality, and its capabilities for steaming purposes have been very favourably spoken of.

The number of coal-mines under inspection in New South Wales at the end of the year 1903 was 98, an increase of one since the previous

year. They gave employment to 13,917 persons, of whom 10,910 were employed under ground, and 3,007 above ground. The average quantity of coal extracted per miner was 582 tons, as against an average of 591 tons in the previous year, and 619 tons in 1901. For the ten years ended 1903, the average quantity of coal extracted per miner was 565 tons, which, at the mean price of coal at the pit's mouth, was equivalent to £180 11s. 0d. Taking all persons employed at the mines, both above and under ground, the average for the ten years would be 452 tons, equivalent to £144 8s. 5d. per man. This production is certainly large, and compares favourably with the results exhibited by the principal coal-raising countries of the world, as will be evident from the following figures, giving the averages for the leading countries, based on the number of persons employed :—

Country.	Quantity of coal raised per miner.	Value at the pit's mouth per ton.	Total value of coal raised per miner.
	tons.	s. d.	£ s. d.
New South Wales .....	565	6 5	144 8 5
Great Britain .....	272	10 1	137 2 8
United States.....	536	5 6	147 8 0
Germany .....	317	7 3	114 18 3
France .....	203	11 9	119 15 3
Belgium .....	174	13 5	116 12 6
Austria .....	605	6 3	189 1 3

A large proportion of the coal raised is consumed in the state, and out of a total production of 6,354,846 tons in 1903, 2,638,652 tons—or 41·52 per cent.—were used locally. The exports to Australian ports amounted to 1,761,003 tons, or 27·71 per cent., and to ports outside Australia 1,955,191 tons, or 30·77 per cent. The quantity required for home consumption increases every year, and the annual consumption per head of population has risen from 16 cwt. in 1877 to 18 cwt. in 1903. The increased steam power employed in the manufacturing industries and on the railways accounts for a great deal of the advance in consumption, while the quantities of coal used in smelting works and gas works also account for a large proportion, but it must be borne in mind that the figures include the bunker coal used in the ocean-going steamers, and this amounted in 1903 to about 430,000 tons.

The progress of the export trade of New South Wales, from 1881 to 1903, is shown in the following table:—

Exported to—	Quantity.			Value.		
	1881.	1891.	1903.	1881.	1891.	1903.
	tons.	tons.	tons.	£	£	£
Australian States .....	521,025	1,342,055	1,761,003	200,829	664,847	720,967
New Zealand .....	186,110	168,921	270,470	54,743	90,662	114,819
Fiji .....	3,243	16,864	50,989	1,410	8,038	22,577
Hong Kong .....	99,637	59,227	39,680	40,487	31,761	16,096
India and Ceylon .....	2,700	21,690	57,757	945	12,149	23,240
Straits Settlements .....	5,690	89,183	66,756	1,896	49,989	31,969
United Kingdom and other British Possessions .....	7,081	23,690	39,272	2,830	12,411	19,054
Chili .....	8,017	196,186	499,778	3,243	108,942	266,177
Hawaiian Islands .....	8,479	.....	172,180	3,345	.....	91,614
Peru .....	.....	24,835	49,492	.....	13,821	26,858
Philippine Islands .....	17,969	53,909	228,562	7,174	29,563	113,508
United States .....	150,002	365,622	308,790	68,173	200,851	162,220
Other foreign countries .....	69,871	152,185	176,585	32,460	83,601	91,806
<b>Total .....</b>	<b>1,029,844</b>	<b>2,514,368</b>	<b>3,716,194</b>	<b>417,530</b>	<b>1,306,630</b>	<b>1,704,993</b>

None of the other states is in a position to export coal, but New Zealand is slowly working up an export trade, the progress of which since 1881 is shown below.

Exported to—	Quantity.			Value.		
	1881.	1891.	1903.	1881.	1891.	1903.
	tons.	tons.	tons.	£	£	£
Australasian States .....	6,049	14,277	12,974	5,022	8,488	14,230
United Kingdom .....	.....	68,871	56,740	.....	76,027	55,111
Fiji and Norfolk Island .....	21	3,282	9,299	25	2,469	6,752
Hong Kong .....	.....	.....	65,285	.....	.....	45,035
Pacific Islands, etc. ....	551	5,234	8,034	563	4,189	7,799
<b>Total .....</b>	<b>6,621</b>	<b>91,664</b>	<b>152,332</b>	<b>5,610</b>	<b>91,173</b>	<b>128,927</b>

The exports to the United Kingdom from New Zealand, as well as from New South Wales, consisted entirely of bunker coal for the steamers. The production of the former colony in 1903 was 1,420,193 tons, valued at £762,858. A large proportion is raised from the mines in the Westport district of the Middle Island, which showed an output of 571,306 tons in 1903. The Otago and Greymouth districts produced respectively 307,562 and 198,441 tons. The Government owns two collieries, situated at Port Elizabeth and Seddonville, and the working account of the latter for the year ended 31st March, 1904, shows that a profit of £777 was made on coal-winning, but this was quite insufficient to meet the interest charges, management expenses, &c., the net loss on the year being £882. The Port Elizabeth mine only began to ship coal in May, 1904, but up to the end of June, 5,000 tons had been sent away. From the Seddonville colliery the output during the period from November, 1903, to March, 1904, was 7,190 tons; but

raised in South Australia, but is not yet of sufficient importance to warrant inclusion in the table :—

State.	Quantity. tons.	Value. £
New South Wales .....	109,741,916 tons	44,021,102
Victoria .....	2,237,257 "	1,239,026
Queensland .....	7,704,855 "	3,159,073
Western Australia .....	568,401 "	306,288
Tasmania .....	900,932 "	507,914
Commonwealth .....	121,153,361 "	49,233,403
New Zealand .....	18,563,403 "	9,869,184
Australasia .....	139,716,764 "	£59,102,587

During the year 1903 this industry gave direct employment in and about the mines to the following numbers of persons in the several states :—

	No.
New South Wales .....	14,117
Victoria .....	377
Queensland .....	1,329
South Australia .....	...
Western Australia .....	402
Tasmania .....	143
New Zealand .....	...

A large proportion of the coal-mining industry of New South Wales is carried on in the Lower Hunter district, which includes the mines in the locality of Newcastle. The following table shows the birthplaces of the miners in this district at the census of 1901, from which it will be seen that out of a total of 8,556 persons, only 3,878, or about 45 per cent. were natives of New South Wales :—

Birthplace.	No.
New South Wales ... ..	3,878
Other Australian States and New Zealand .....	525
England and Wales .....	2,833
Scotland .....	972
Ireland .....	173
Other British Possessions.....	15
Germany .....	45
France .....	4
Russia .....	8
Scandinavia .....	30
Italy .....	7
Other European Countries .....	11
United States .....	29
Other Countries .....	26
Total.....	8,556

The average price of coal per ton varies considerably in the states. In New South Wales, from the date of the commencement of mining to the end of the year 1903, the average price obtained has been 8s. 0d. but the mean of the last ten years has not been more than 6s. 5d. In



1903 the average price per ton of coal at the pit's mouth was as follows :—

	s.	d.
New South Wales .....	7	4
Victoria .....	12	9
Queensland .....	6	6
Western Australia.....	10	4
Tasmania .....	8	10
Commonwealth .....	7	4
New Zealand .....	10	9
Australasia .....	7	11

The question of cost of raising coal is of considerable importance in connection with the export trade. In New South Wales, miners in the Northern District were paid at the rate of 4s. 2d. per ton for screened coal, while in the Southern District the rate was 2s. 6d. In New Zealand it is computed that to deliver coal at the pit's mouth costs in labour 6s. per ton. The returns of the United States show that of the 20,172,779 tons of coal mined by manual labour, 87,841 tons were paid for by daily wages, varying from 9s. 5d. to 11s. 4d.; 600,060 tons were paid for by weight after screening at 3s. 9½d., and the balance at an average price of 2s. 3½d. per ton. In 29 mines machinery was exclusively used for winning the coal and 280 machines were thus employed, while 184 machines were in use at 34 mines, in addition to manual labour. The machine-mined coal was paid for at the rate of 1s. 8½d. per ton. In France surface workers are paid at the rate of 2s. 10½d., underground hands at 4s. 2½d., and those employed both within and without the mines at 3s. 9d. per day.

Anthracite is found in several of the Australian states, but systematic attempts to develop the deposits have as yet been restricted to Queensland. While not possessing the combustible properties or commercial value of coal, anthracite has proved a fairly efficient substitute in countries where coal is not available. The deposits in Queensland exist in the localities of the Dawson and Mackenzie Rivers, and bores have been sunk with a view of determining the best position for shafts. Two bulk samples obtained from the outcrop on the Dawson River have been tested with satisfactory results.

The following table shows the annual coal production of the principal countries of the world. The figures refer to the year 1903, except those for the United States and Canada, which refer to the year 1902 :—

Country.	Tons of 2,240 lb.
United Kingdom .....	230,334,000
United States .....	*320,983,000
Germany .....	114,772,000
Austria .....	11,314,000
France .....	33,769,000
Belgium .....	23,529,000
Canada .....	6,821,000
Australasia .....	8,532,000

\* Including lignite.

Kerosene shale (torbanite) is found in several parts of New South Wales. It is a species of cannel-coal, somewhat similar to the boghead mineral of Scotland, but yielding a much larger percentage of volatile hydro-carbon than the Scottish product. The richest quality yields about 100 to 130 gallons of crude oil per ton, or 17,000 to 18,000 cubic feet of gas, with an illuminating power of 35 to 40 sperm candles when gas only is extracted from the shale. The New South Wales Shale and Oil Company, at Hartley Vale, and the Australian Kerosene Oil and Mineral Company, at Joadja Creek and Katoomba, not only raise kerosene shale for export, but also manufacture from it petroleum oil and other products. From the year 1865, when the mines were first opened, to the end of 1903, the quantity of kerosene shale raised has amounted to 1,171,124 tons, worth £2,058,958. The average price realised during that period has been £1 15s. 2d. per ton. The prices ruling in 1903, when 34,776 tons were extracted, averaged 16s. 6d. per ton, representing a total value of £28,617 for the production of the year.

Extensive formations of oil shale have been found in New Zealand, at Otago, and at Orepuki, in Southland, where a mine was opened and extensive works erected to treat the mineral for the extraction of oils, paraffin wax, ammonia, &c., but the venture was not attended with success. The quantity of shale raised in 1901 was 12,048 tons, valued at £6,024, but during 1902 the production was only 2,338 tons, valued at £1,169. Crude petroleum has been obtained in several districts in New Zealand, and boring is in progress with a view to testing the oil-bearing strata.

The annual import of kerosene oil into Australasia, based on the returns of the last three years, is shown below :—

State.	Quantity.	Value.
New South Wales .....	4,812,930 gallons	£139,979
Victoria .....	4,569,825 "	120,541
Queensland .....	2,010,393 "	78,576
South Australia .....	1,363,803 "	35,283
Western Australia .....	1,590,038 "	46,694
Tasmania .....	385,894 "	15,866
Commonwealth .....	14,732,883 "	436,939
New Zealand .....	3,152,397 "	117,454
Australasia .....	17,885,280 "	554,393

#### OTHER CARBON MINERALS.

Of all the mineral forms of carbon the diamond is the purest ; but as it is usual to class this precious substance under the head of gems that custom will be followed in the present instance.

Graphite, or plumbago, which stands second to the diamond in point of purity, has been discovered in New Zealand, in the form of detached boulders of pure mineral. It also occurs in impure masses where it comes into contact with the coal measures. This mineral, up to the

present time, has not been found in any of the other states except New South Wales, where in 1889 a lode 6 feet wide, but of inferior quality, was discovered near Undercliff, in the New England district; and in Western Australia, where, however, owing principally to difficulties of transit, very little of it has been worked.

Ozokerite, or mineral wax, is reported to have been found at Coolah, in New South Wales.

Elastrite, mineral caoutchouc, or elastic bitumen, is said to have been discovered in New South Wales and South Australia. In the last-named state a substance very similar to elastrite has been discovered in the Coorong Lagoons, and has received the name of coorongite. Up to the present time neither the extent of these finds nor their commercial value has been ascertained.

Bitumen is known to exist in Victoria, and is reported to have been found near the township of Coonabarabran, in New South Wales.

Kauri gum, a resinous substance somewhat resembling amber in appearance, and like that product an exudation from trees, is found only in the Auckland province of New Zealand, and is included under the head of minerals, although more logically entitled to be considered as a vegetable product. The best is that dug out of the ground; but considerable quantities of inferior grades are taken from the forks of standing trees. In New Zealand an extensive and lucrative commerce is carried on in kauri gum. It is computed that the total value of this product obtained from 1853 to the end of 1903 was £11,857,270. In the year 1903 the quantity obtained was 9,357 tons representing a value of £631,102, and the industry gave employment to about 7,000 persons, both European and Maori. Kauri gum is included in the figures in this chapter giving the total mineral production.

#### SALTS.

Common rock salt has been found in rock crevices in several parts of New South Wales, but it is not known to exist in deposits large enough to be of commercial importance. Large quantities of salt are obtained from the salt lakes in South Australia. The principal source of supply is Lake Fowler, and in summer the entire area is covered with a saline deposit. The article is only procurable during the period from November to March, and in 1903-4 there were 400 persons engaged collecting and refining it, and the quantity produced amounted to 40,000 tons, valued at £55,000.

Natron is said to occur in the neighbourhood of the Namoi River, in New South Wales. It appears as a deposit from the mud-wells of that region. Epsomite, or epsom salt (sulphate of magnesia), is seen as an efflorescence in caves and overhanging rocks of the Hawkesbury sandstone formation, and is also found in various other parts of New South Wales.

Large deposits of alum occur close to the village of Bulladelah, 30 miles from Port Stephens, New South Wales. Up to the end of the

year 1903, 21,871 tons of alunite had been raised in the locality, most of the product having been sent to England for treatment. During 1903 the Bulladelah mine yielded 2,484 tons of stone, valued at £6,212.

#### STONES AND CLAYS.

Marble is found in many parts of New South Wales, South Australia, New Zealand, and Tasmania. In New South Wales marble quarries have been opened in several districts, and some very fine specimens of the stone have been obtained. The principal quarries are at Caloola, near Newbridge, where an excellent description of white marble is obtained. As showing the quality of marble available in New South Wales it may be mentioned that it has been used exclusively in the construction of the staircase in the new court of the Sydney Art Gallery. There are four distinct varieties of marble represented therein which were obtained from Caloola, Rockley, Fernbrook and Molong, and the artistic use of these has resulted in a charming and universally admired effect.

The Hawkesbury sandstone formation, which underlies the city of Sydney, provides an inexhaustible supply of stone admirably adapted for building purposes, and capable of lending itself to fine architectural effects.

Lithographic stone has been found in New Zealand, where another beautiful species of limestone known as Oamaru stone is also procured. This stone has a fine, smooth grain, and is of a beautiful creamy tint. It is in great demand for public buildings, not only in the colony where it is found, but in the great cities of continental Australia, which import quantities of the stone for the embellishment of public edifices.

Limestone is mined for in New South Wales, and is now being largely used in the manufacture of hydraulic cement, as well as for fluxing purposes in smelting works. At Portland, near Wallerawang, extensive works for manufacturing cement have been erected, and works are also in operation at Granville, near Sydney. In other parts of the state limestone is also raised, the total production in 1903 being 23,579 tons, valued at £17,213. In Western Australia a considerable quantity of limestone is raised for fluxing purposes, the production in 1903 being 1,279 tons, valued at £178. The establishment of the cyanide process for the recovery of gold, in which lime is freely used, has led to the opening up of limestone mines in various parts of Queensland, and the production in 1903 amounted to 13,612 tons, valued at £8,060, the total production up to the end of that year being 28,533 tons, valued at £20,495. In South Australia 40,138 tons of limestone were raised from the deposits at Yorke's Peninsula.

Gypsum is found crystallised in clay-beds in New South Wales, and in isolated crystals in the Salt Lakes of South Australia, where a small proportion of sulphate of lime is present in the water. It is also found in portions of Victoria, the production in that state for 1903 being

3,590 tons, valued at £897. This mineral is of commercial value for the manufacture of cement and plaster of Paris, and also as a fertiliser. A considerable quantity has been raised in South Australia for the latter purpose. Gypsum is also found in the form of an insoluble salt in New South Wales, Victoria, and New Zealand.

Apatite, another mineral of considerable commercial importance, and very valuable as a manure, occurs in several districts of New South Wales, principally on the Lachlan River, at the head of the Abercrombie, and in the Clarence River district.

Quartz is of common occurrence in all parts of Australasia. Rock crystal, white, tinted, and smoky quartz are frequently met with, as well as varieties of crystalline quartz, such as amethyst, jasper, and agate, which possess some commercial value.

Tripoli, or rotten stone, an infusorial earth, consisting of hydrous silica, which has some value for commercial purposes, has been found in New South Wales, Victoria, and New Zealand. In Victoria during 1903, 400 tons of infusorial earth were raised, the value being £2,400. Meerschauum is reported to have been discovered near Tamworth and in the Richmond River district, in New South Wales.

Mica is also found in granitic country, and has been discovered in the New England and Barrier districts of New South Wales. In Western Australia very good mica has been found at Bindoon, and also on the Blackwood River, near Cape Leeuwin. Several attempts at mining were made, but they proved unsuccessful, and have been abandoned. Deposits have also been found near Herberton, in Northern Queensland. In the Northern Territory of South Australia mica has been obtained on a small scale. In 1895 the production was valued at £2,638, and in 1896 at £732; but of late years there has been no production.

Kaolin, fire-clays, and brick-clays are common to all the states. Except in the vicinity of cities and townships, however, little use has been made of the abundant deposits of clay. Kaolin, or porcelain clay, although capable of application to commercial purposes, has not as yet been utilised to any extent, though found in several places in New South Wales and in Western Australia.

Asbestos has been found in New South Wales in the Gundagai, Bathurst, and Broken Hill districts—in the last-mentioned district in considerable quantities. Several specimens of very fair quality have also been met with in Western Australia; and the Government of the state offered a bonus not exceeding £500 for the export of 50 tons of asbestos, of a value of not less than £10 per ton. In Tasmania asbestos is known to exist in considerable quantities in the vicinity of Beaconsfield.

In New Zealand fairly extensive deposits of phosphates have been discovered, and with large supplies of this valuable fertiliser near at hand the necessity for importing phosphatic manures should shortly cease to exist.

## GEMS AND GEMSTONES.

Many descriptions of gems and gemstones have been discovered in various parts of the Australasian states, but systematic search has been made principally for the diamond and the noble opal.

Diamonds are found in New South Wales, Victoria, Queensland, and South Australia, but only in the first-named state have any attempts been made to work the diamond drifts. The existence of diamonds and other gemstones in the territory of New South Wales had been known for years before an attempt was made to work the deposits in 1872. In the course of the following year several deposits of adamantiferous wash were discovered at Bingara, in the New England district, and in later years at Boggy Camp, Copeton. The output has never been very considerable, the largest value realised in any year being £15,375. In 1903 the value amounted to £9,987, and the total value of the diamonds produced up to the end of that year was £86,604; but this amount is believed to be considerably understated.

The finest opal known is obtained in the Upper Cretaceous formation at White Cliffs, near Wilcannia, New South Wales. During the year 1895 good stone was found at a depth of 50 feet, and as the lower levels are reached the patches of opal appear to improve in quality and to become more regular and frequent. On block 7 a patch of stone was found which realised over £3,000. It is difficult to state with exactitude the value of the production, but it is believed that stone to the value of £816,600 has been sold up to the end of 1903. In 1901 a Special Commission was appointed to inquire into matters connected with the opal industry at White Cliffs, and their investigations tended to show that the annual value of production for some years had amounted to £100,000. The production for the year 1902 was valued at £140,000, and in 1903 at £100,000. The number of men engaged in the opal mining industry was 1,115.

In Queensland opal is found in rocks of the desert sandstone formation, sometimes on the surface, but generally at a depth of about 14 feet. The chief fields are at Cunnamulla, Paroo, and Opalton, in the far western and north-western parts of the state, but the scanty water supply has been a great barrier to the progress of the industry. At Station Creek, in the Paroo district, a deposit of opal, valued at £2,000, was unearthed during 1903. In that year the production was valued at £7,300, and the total up to the end of the year, at £146,145. There are 170 men engaged in this industry.

Other gemstones, including the sapphire, emerald, oriental emerald, ruby, opal, amethyst, garnet, chrysolite, topaz, cairngorm, onyx, zircon, &c., have been found in the gold and tin-bearing drifts and river gravels in numerous localities throughout the states. The Emerald Proprietary Company, in the Emmaville district, near Glen Innes, New South Wales, have sunk two shafts, 100 feet and 50 feet

respectively; and 25,000 carats have been won in a rough state. Their value when cut and finished, if of the best quality, is about £2 per carat. Owing to the difficulties of extraction, and the low price of the gems in the London market, the mines were closed for three years. In 1897 they were again opened up, and, although worked for some time during 1898, they are now closed, the company having obtained a suspension of the labour conditions. No gems were produced during the year.

The sapphire is found in all the states, and at the sapphire fields of Anakie, in Queensland, there is now a population of 150 persons. The fields are extensive, but the gems are of a peculiar colour, quite distinct from those of any other country, a characteristic that prejudicially affects their value. The value of the gems produced in 1901 was £6,000, but owing to the low prices and the lack of sufficient water supply on the field, the returns fell away to £5,000 in 1902. The season of 1903 was more favourable, the production being valued at £6,500. The oriental topaz has been found in New South Wales. Oriental amethysts also have been found in that state; and the ruby has been found in Queensland, as well as in New South Wales.

According to an authority on the subject of gemstones, rubies, oriental amethysts, emeralds, and topaz have been chiefly obtained from alluvial deposits, but have rarely been met with in a matrix from which it would pay to extract them.

Turquoises have been found near Wangaratta, in Victoria.

Chrysoberyls have been found in New South Wales; spinel rubies, in New South Wales and Victoria; white topaz, in all the states; and yellow topaz, in Tasmania. Chalcedony, carnelian, onyx, and cat's-eye are found in New South Wales; and it is probable that they are also to be met with in the other states, particularly in Queensland. Zircon, tourmaline, garnet, and other gemstones of little commercial value are found throughout Australasia.

In South Australia some very fine specimens of garnet were found, causing some excitement at the time, as the gems were mistaken for rubies. The stones were submitted to the examination of experts, whose reports disclosed the true nature of the gems, and dispelled the hopes of those who had invested in the supposed ruby-mines of that state.

#### PRODUCTION OF MINERALS.

The foregoing pages show that Australasia possesses invaluable mineral resources, and although enormous quantities of minerals of all kinds have been won since their first discovery, yet the deposits, with the exception perhaps of gold, silver, and coal, have only reached the first period of their exploitation. The development of the deposits of various other minerals has not reached a sufficiently advanced stage to enable an exact opinion to be expressed regarding their commercial value, though it is confidently held by mining experts that this must be

enormous. The mineral production of the various states in 1903 will be found below :—

State.	Total Value.	Proportion in each State.	Average value per head.
	£	per cent.	£ s. d.
New South Wales .....	5,912,612	21·60	4 3 1
Victoria .. .....	3,381,520	12·35	2 15 11
Queensland .....	3,686,086	13·47	7 2 2
South Australia .....	583,926	2·14	1 11 9
Western Australia .....	8,971,698	32·78	40 10 11
Tasmania.....	1,302,921	4·76	7 6 9
Commonwealth .....	23,838,773	87·10	6 1 9
New Zealand .....	3,530,654	12·90	4 6 1
Australasia .....	27,369,427	100·00	5 15 6

The total value of the minerals raised in Australasia during 1903 was £27,369,427, being £2,397,420 in excess of the value for 1901, which had hitherto been the highest recorded in any one year. The great advance of gold-mining in Western Australia and the increased activity displayed in coal-mining in New South Wales have been the chief contributing factors in maintaining the high figures of the past few years. Gold has always constituted the largest proportion of the value raised, but the search for this mineral has led to the expansion of other branches of the mining industry which are commanding more attention each year. At the present time the number of persons in Australasia who gain their livelihood by mining is nearly 125,400. The total employment in each branch of mining during 1903 was :—

State.	Number of Persons engaged in Mining for—						Total.
	Gold.	Silver and Lead.	Copper.	Tin.	Coal, Coke, and Shale.	Other Minerals & Precious Stones.	
New South Wales ....	11,247	6,035	1,816	2,502	14,117	1,842	37,559
Victoria .....	25,208	.....	.....	.....	877	64	25,609
Queensland .....	9,229	458	1,418	1,598	1,329	506	14,533
South Australia .....	2,000	150	4,033	50	50	700	7,033
Western Australia .....	20,716	.....	193	294	402	1	21,606
Tasmania .....	938	.....	*3,269	1,258	143	.....	5,678
Commonwealth ..	69,888	6,643	10,790	5,702	16,418	3,138	112,083
New Zealand .....	10,210	.....	.....	.....	2,852	256	13,318
Australasia .....	79,598	6,643	10,790	5,702	19,270	3,399	125,401

\* Includes silver miners.

The greatest number of persons engaged in mining is in New South Wales, where, owing to the large employment afforded by the coal-mines,



the total is 37,559; the greatest number of gold-miners is in Victoria. The total number of persons in the Commonwealth engaged in mining pursuits is 112,083, and in view of the known resources which await development, this number is likely to be still further increased.

The following table shows the value of the mineral production of each state during the five years 1871, 1881, 1891, 1901, and 1903, as well as the value per inhabitant for the whole of Australasia :—

State.	1871.	1881.	1891.	1901.	1903.
	£	£	£	£	£
New South Wales.....	1,850,000	2,121,000	6,396,000	5,854,150	5,912,612
Victoria .....	5,400,000	3,467,000	2,339,000	3,312,162	3,381,520
Queensland .....	806,000	3,165,000	2,300,000	3,114,702	3,686,096
South Australia.....	725,000	421,000	366,000	613,930	583,926
Western Australia .....	5,000	11,000	130,000	7,445,772	8,971,698
Tasmania .....	25,000	604,000	516,000	1,675,290	1,302,921
Commonwealth.....	8,611,000	9,789,000	12,047,000	22,016,006	23,838,773
New Zealand.....	3,100,000	1,528,000	1,841,000	2,956,001	3,530,654
Total .....	11,711,000	11,317,000	13,888,000	24,972,007	27,369,427
Australasia {					
Per head ..	£ s. d. 6 1 0	£ s. d. 4 1 6	£ s. d. 3 12 3	£ s. d. 5 9 0	£ s. d. 5 15 6

The foregoing table shows that the mineral production of 1903 was nearly fourteen and a half millions more than that of 1891. There were increases in all the states with the exception of New South Wales, in which state a decrease of slightly over £483,000 has to be recorded, owing to the fall in the value of silver and lead. The most notable increases were in Western Australia and Tasmania; the production of the former state exceeded that of 1891 by nearly £8,842,000, mainly on account of the great increase in the gold yield, which advanced in value from £115,182 to £8,770,720 during the period under review. The large expansion in the Tasmanian production was due to the output of the Mount Lyell Copper-mines. In the other states, the increases were also substantial, and New Zealand had an increase of nearly £1,690,000.

Comparing the value of the mineral production in 1903 with the population, the largest amount is shown by Western Australia, with £40 10s. 11d. per inhabitant; Tasmania ranks second, with £7 6s. 9d. per inhabitant; Queensland third, with £7 2s. 2d.; New Zealand fourth, with £4 6s. 1d.; New South Wales fifth, with £4 3s. 1d. Victoria follows with an average of £2 15s. 11d. per head, and in South Australia the production per inhabitant was only £1 11s. 9d. The average per inhabitant for Australasia was £5 15s. 6d., an increase of 8s. 4d. per head on the figures of the previous year, and the average for the states constituting the Commonwealth was £6 1s. 9d. per head.

The following table shows the value of production in each of the states during 1903, distinguishing the principal minerals. With regard to some of the states the data are defective in respect to "other minerals," but not to such an extent as to affect seriously the gross total. The column "other minerals" includes kerosene shale in New South Wales and kauri gum in New Zealand, but does not include salt in South Australia :—

State.	Gold.	Silver and Silver-lead.	Copper.	Tin.	Coal.	Other Minerals.	Total.
	£	£	£	£	£	£	£
New South Wales ....	1,080,029	1,501,403	446,286	155,723	2,319,000	409,611	5,912,032
Victoria .....	3,230,483	2,800	500	2,165	40,818	75,674	3,351,530
Queensland .....	2,839,813	65,588	236,122	243,149	184,798	87,676	3,669,066
South Australia .....	90,081	2,071	472,014	10,772	.....	9,088	883,925
Western Australia .....	8,770,720	19,153	56,541	55,890	69,128	208	8,971,680
Tasmania .....	254,408	268,626	486,640	233,683	20,916	34,553	1,302,922
Commonwealth ..	16,294,479	1,859,571	1,746,108	706,582	2,615,320	616,718	23,838,778
New Zealand .....	2,087,881	91,497	123	.....	762,358	*638,345	3,580,654
Australasia .....	18,332,310	1,961,068	1,746,236	706,582	3,378,178	1,255,063	27,369,227

\* Inclusive of kauri gum valued at £631,102.

The total mineral production to the end of 1903 is shown in the following table, in which the column "other minerals" again includes kerosene shale and kauri gum :—

State.	Gold.	Silver and Silver-lead.	Copper.	Tin.	Coal.	Other Minerals.	Total.
	£	£	£	£	£	£	£
New South Wales ..	50,924,164	35,239,159	6,611,165	6,817,122	44,021,102	5,088,341	148,745,068
Victoria .....	296,810,712	864,319	206,896	718,163	1,239,026	487,535	270,225,456
Queensland .....	58,312,127	928,725	2,724,014	5,053,186	3,156,073	480,245	70,622,370
South Australia .....	2,573,357	140,441	23,725,685	49,530	.....	541,482	27,081,295
Western Australia ..	46,898,094	40,225	391,603	233,872	306,238	418,075	48,318,167
Tasmania .....	5,449,564	2,872,276	4,964,068	7,758,167	507,914	372,569	21,948,169
Commonwealth ..	430,983,018	40,124,145	38,644,930	20,690,040	49,233,408	*7,368,038	569,998,574
New Zealand .....	63,149,147	544,278	18,311	.....	9,869,184	12,125,347	85,706,167
Australasia .....	494,067,166	40,668,423	38,663,161	20,690,040	59,102,592	19,493,395	672,694,761

\* Inclusive of kauri gum of the value of £11,857,370.

Coal was the only mineral raised in New South Wales prior to 1852, and its production up to that date was valued at £279,923. Deducting that amount from the total value of Australasian minerals raised up to the end of 1903, the remainder, £672,414,818, represents the value of mineral production from 1852, equal to an average of £12,647,949 per annum for the fifty-one years.

## THE MANUFACTURING INDUSTRY.

THE progress of the manufacturing industry in Australasia has been somewhat irregular, even in the most advanced states; and although the tabular statement given below shows an increase since 1885 of 91,159 hands in the Commonwealth and 30,533 in New Zealand, a growth proportionately much greater than that of the population, by far the greater part of this extension has taken place during the last eight years. The population of the continent at the present time is not sufficient to maintain industries on an extensive scale, and in past years the field was still further limited by intercolonial tariffs. Now that these barriers have been swept away, and the Australian market secured to a certain extent to the local manufacturer, more rapid progress may reasonably be expected in the manufacturing industry.

The majority of the manufactories of Australasia may be classified as domestic industries—that is to say, industries naturally arising from the circumstances of the population, or connected with the treatment of perishable products; but there are nevertheless a fair number of firmly established industries of a more complex character. A statement of the number of establishments and of the hands employed in Australasia is given below for various years since 1885. The information is obtained annually in the states of the Commonwealth, but only once in every five years in New Zealand:—

Year.	Establishments.		Hands employed.	
	Commonwealth.	New Zealand.	Commonwealth.	New Zealand.
	No.	No.	No.	No.
1885 . . . . .	8,632	1,946	105,265	22,095
1890 . . . . .	8,903	2,264	133,147	25,633
1895 . . . . .	8,247	2,459	133,631	27,389
1900 . . . . .	10,040	3,668	184,160	48,718
1903 . . . . .	11,979	3,960	196,424	52,628

From this it would appear that the number of hands in the Commonwealth increased from 133,631 in 1895 to 184,160 in 1900, but as the returns of the earlier year were not so complete as those of 1900 the figures cannot be accepted as an index of the progress made during the period. The returns for 1900 and 1903 are, however, practically on the same basis, and have accordingly been summarised

so as to show the movement in each branch of the manufacturing industry during the three years.

Class of Industry.	1900.			1903.		
	Hands employed.		H.P. of Machinery used.	Hands employed.		H.P. of Machinery used.
	Males.	Females.		Males.	Females.	
Treating Raw Materials, the Product of Pastoral Pursuits, &c.	7,276	27	6,271	7,402	44	7,820
Oils and Fats, Animal, Vegetable, &c.	1,399	60	2,007	1,650	96	1,801
Processes in Stone, Clay, Glass, &c.	7,308	41	4,890	7,850	85	6,582
Working in Wood	16,413	15	18,505	16,333	30	19,787
Metal Works, Machinery, &c.	35,260	64	15,783	36,285	91	20,659
Connected with Food and Drink, &c.	30,281	4,353	48,113	26,755	4,555	47,421
Clothing and Textile Fabrics and Materials	15,953	27,849	3,852	16,932	36,358	4,908
Books, Paper, Printing, and Engraving	13,448	2,743	3,822	13,756	3,477	4,827
Musical Instruments	141	10	94	239	15	67
Arms and Explosives	176	77	137	135	226	96
Vehicles and Fittings, Saddlery, and Harness, &c.	7,692	86	569	7,457	69	745
Ship and Boatbuilding, &c.	2,117	45	1,196	1,965	14	3,184
Furniture, Bedding, and Upholstery	4,136	778	856	5,012	428	1,156
Drugs, Chemicals, and By-products	961	245	660	1,509	492	1,201
Surgical and other Scientific Instruments	70	15	13	98	19	11
Jewellery, Timepieces, and Plated Ware	786	23	90	1,076	45	81
Heat, Light, and Power	2,668	94	13,789	3,575	91	37,961
Leatherware, not elsewhere included	279	35	51	384	68	135
Minor Wares, not elsewhere included	1,288	349	363	1,314	556	838
Total	147,652	36,508	120,903	149,665	46,759	159,522

Comparing 1900 with 1903, it will be seen that there has been a general increase in the number of persons employed in each of the various classes shown in the foregoing table, with the exception of the industries connected with wood-working, food and drink, the manufacture and repair of vehicles, and the docking and building of ships. The decline in no class of industry was particularly large, except in the industries connected with food. Elsewhere in this volume, the condition of the producing industries during 1903 has been discussed, and it is a natural expectation that with the falling off in the supply of grain there would have been a decrease in the industries connected with milling, while the shortage of fat stock brought about almost a total suspension in certain districts of the large industry of meat-preserving. Queensland was the chief sufferer in regard to the employment in manufactories dependent upon the staple industries. In 1903 there were 2,350 hands employed in meat-preserving and sugar-milling, as

compared with 5,412 hands three years previously. The power of the machinery in average use increased from 120,903 h.p. to 159,322 h.p., but this was largely attributable to the establishment of the electric tramway system in Sydney. As a set-off against this, however, it may be said that the figures of the earlier year include electric-lighting plants in several of the states which were not included in 1903, and the increase of power may be accepted as a satisfactory testimony to the large increase of invested capital.

It is interesting to note the extent to which the employment of female labour has increased during late years.

In 1897, the females engaged in the manufactories of the states which comprise the Commonwealth numbered only 26,837 and represented 17·7 per cent. of the total hands employed; in 1903 their number had increased to 46,759 and the proportion to 23·8 per cent. In New Zealand the experience has been similar, from 4,391 in 1895 the number of females increased to 11,606 in 1903, and their proportion to the total hands employed rose from 16·1 per cent. to 22·2 per cent. The figures are prejudiced to a certain extent by the fact that the returns for the states were not all compiled on the same basis; still there is sufficient evidence that the employment of female labour is increasing, a conclusion borne out also by the information obtained at the Census of 1901 and published in part "Employment and Production" of this volume. The proportion of females employed is largest in Victoria, where there were 23,795 out of a total of 73,229 persons, equal to 32·5 per cent.; South Australia followed with 21·1 per cent., and Western Australia had the lowest proportion with 11·7 per cent. The following table shows the number of males and females employed in the Commonwealth in each year since 1897:—

Year.	Hands Employed.		Total.
	Males.	Females.	
1897 ...	124,938	26,837	151,775
1898 ...	130,389	28,221	158,610
1899 ...	139,755	31,707	171,462
1900 ...	147,652	36,508	184,160
1901 ...	154,000	39,664	193,664
1902 ...	154,775	45,242	200,017
1903 ...	149,665	46,759	196,424

Too much importance is sometimes attached to this apparent intrusion of woman into what is generally considered to be man's sphere, for it would appear that the increased employment of women is mainly confined to industries concerned with the manufacture of clothing, &c. As evidence of this, it may be mentioned that the number of females engaged in the Commonwealth in clothing, tailoring, and dressmaking establishments increased from 20,928 in 1900 to 25,426 in 1903.

## MANUFACTORIES OF VICTORIA.

Victoria was the state which first displayed activity in the manufacturing industries. In 1885 there were employed in factories, properly so called, 49,297 hands, and in 1889 there were 57,432 hands; but the number fell away to 41,729 in 1893. Since that year there has been an increase to the extent of 31,500 hands. Of the 73,229 workers employed in 1903, 3,533 may be said to have found occupation in connection with domestic industries for the treatment of perishable produce for immediate use; 34,502 in other industries dependant upon the natural resources of the country, and 35,194 in industries the production from which comes into competition with imported goods:—

Year.	Establishments.	Males.	Females.	Total Hands employed.
1885	2,813	41,542	7,755	49,297
1886	2,770	39,453	6,320	45,773
1887	2,854	42,019	7,065	49,084
1888	2,975	47,335	7,153	54,488
1889	3,137	49,105	8,327	57,432
1890	3,104	47,596	8,773	56,369
1891	3,123	43,627	10,786	54,413
1892	2,934	35,726	9,689	45,415
1893	2,659	32,209	9,520	41,729
1894	2,614	32,638	10,681	43,319
1895	2,724	35,406	12,240	47,646
1896	2,809	37,728	12,669	50,397
1897	2,759	38,620	14,030	52,650
1898	2,869	40,631	14,147	54,778
1899	3,027	44,041	16,029	60,070
1900	3,097	45,794	18,413	64,207
1901	3,249	47,059	19,470	66,529
1902	4,003	49,658	23,405	73,063
1903	4,151	49,434	23,795	73,229

The number of factories and industrial establishments of various sizes, with the number of hands employed in each class, during 1903, will be found below:—

Number of Hands employed by each Establishment.	Number of Establishments.	Total number of Hands.
Under 4 hands .....	587	1,714
4 hands .....	487	1,948
5 to 10 hands .....	1,631	11,293
11 to 20 „ .....	722	10,509
21 to 50 „ .....	471	14,520
51 to 100 „ .....	135	9,109
101 hands and upwards .....	118	24,136
Total.....	4,151	73,229

The capital invested in these establishments amounted to £20,406,841 sterling, of which the land represented £2,855,174; buildings, £5,112,771; machinery and plant, £5,010,896; and cash and sundries, £7,428,000. The horse-power of the machinery used was 41,091, divided as follows:— Steam engines, 36,727 horse-power; gas, 3,600 horse-power; and oil, 764 horse-power; in addition to which electric engines, of 1,659 horse-power were used, mainly for lighting purposes.

## MANUFACTORIES OF NEW SOUTH WALES.

The manufacturing industries of New South Wales do not cover so wide a field as those of Victoria, nor do they afford employment for as many persons. For the year 1903 the two states compare as follows:—

State.	Establishments.	Hands employed.		Total.
		Males.	Females.	
Victoria .....	4,151	49,434	23,795	73,229
New South Wales ...	3,476	52,453	13,180	65,633

In Victoria, therefore, there were employed 10,615 females more than in New South Wales, and 3,019 fewer males. In order to trace the progress of the manufacturing industry in New South Wales during the last eleven years, it is necessary to adjust the figures for the five years 1891–95, because in 1896 a change was made in the scope of the returns by the inclusion of dressmakers and milliners who were not previously counted as factory hands. Certain other small changes were made, the object of which was to secure uniformity with Victoria. Making the necessary adjustments, the figures since 1891 are as follows:—

Year.	Establishments.	Males.	Females.	Total Hands employed.
1891	3,056	43,203	7,676	50,879
1892	2,657	42,909	5,007	47,916
1893	2,428	37,832	4,225	42,057
1894	3,070	41,070	5,432	46,502
1895	2,723	41,546	6,484	48,030
1896	2,928	42,908	6,932	49,840
1897	2,826	44,333	7,106	51,439
1898	2,839	44,673	7,845	52,518
1899	2,912	47,063	8,583	55,646
1900	3,077	50,516	10,263	60,779
1901	3,367	54,556	11,674	66,230
1902	3,396	54,326	11,943	66,269
1903	3,476	52,453	13,180	65,633

Up to the year 1891 there had been a fairly regular increase in the employment afforded by the factories of the state; in the following year, owing to causes already discussed in another part of this volume, there was a decrease in the number of persons employed, and, from 50,879 in 1891, the number had fallen to 42,057 in 1893—the year of the bank failures. In the following years there was a rapid recovery, so that the employment in 1897 was greater than in 1891, and each year showed a further improvement until, in 1902, there were 15,390 more hands employed than in 1891, and 24,212 more than in 1893. In 1903 there was a decrease in the number of males employed to the extent of 1873, and an increase of females, numbering 1,237, so that the total number of hands employed was 536 less than in the preceding year.

Of the 65,633 workers employed in 1903, 29,800 found employment in connection with industries the products from which come into competition with imported goods, 3,624 were engaged in domestic industries for the treatment of perishable produce required for immediate use, and 32,209 in other industries called into existence by the natural resources of the state.

The number of factories and industrial establishments of various sizes, with the number of hands employed in each class during 1903, were as follows:—

Number of Hands employed by each Establishment.	Number of Establishments.	Total number of Hands.
Under 4 hands .....	588	1,429
4 hands .....	397	1,588
5 to 10 hands .....	1,211	8,414
11 to 20 „ .....	617	8,906
21 to 50 „ .....	424	13,317
51 to 100 „ .....	136	9,414
101 hands and upwards .....	103	22,565
<b>Total .....</b>	<b>3,476</b>	<b>65,633</b>

The capital invested in these establishments amounted to £19,396,504. The value of the lands, buildings, and fixtures, as ascertained at the census of 1901, was £4,969,698, while the machinery and plant used in 1903 was valued by the proprietors at £7,009,806, and the cash and sundries invested were £7,417,000. The average power of the machinery used was 59,353 horse-power, of which steam-engines represented 56,121 horse-power, gas 2,538 horse-power, water 88 horse-power, oil 205, and turbine 401 horse-power, while electric plants, of 18,039 horse-power, were also in operation, but almost solely for lighting purposes.

#### MANUFACTORIES OF QUEENSLAND.

In Queensland systematic statistics relating to manufactories have been taken only since 1892. Until the year 1900, no details were available with reference to the employment of males and females, and



the numbers for previous years have therefore been estimated. The figures for the last ten years are as follows :—

Year.	Establishments.	Persons employed.		
		Males.	Females.	Total.
1894 .....	1,323	13,124	2,100	15,224
1895 .....	1,397	16,128	2,600	18,728
1896 .....	1,332	17,013	2,720	19,733
1897 .....	1,682	19,100	3,060	22,160
1898 .....	1,864	20,830	3,340	24,170
1899 .....	2,172	23,440	3,760	27,200
1900 .....	2,019	23,138	3,766	26,904
1901 .....	2,062	23,431	3,692	27,123
1902 .....	1,977	17,595	3,363	20,958
1903 .....	2,001	16,139	3,147	19,286

To stimulate the progress of the staple industries of the State, two Acts were passed—the “Sugar Works Guarantee Act” and the “Meat and Dairy Produce Encouragement Act.” The former empowered the Government to make advances to sugar mills at a low rate of interest, and under its provisions £526,136 had been advanced up to 31st December, 1903, the amount of indebtedness on that date being £554,783. Under the Meat and Dairy Act, advances amounting to £117,733 had been made, of which £88,600 was owing on 31st December, 1903. Owing to a series of adverse seasons, the manufacturing industries of Queensland, closely allied as they are with the great pastoral and agricultural industries of the state, have suffered severely.

The output from the two principal manufacturing industries, sugar-refining and meat-preserving, which, in 1901, amounted to £3,405,481, fell away to £2,681,456 in 1903. The figures relating to these two industries are worthy of special attention, and are dealt with at some length in another place.

The value of materials used in Queensland industries, excluding butter and cheese factories, in 1903 was £3,955,000, the wages paid £1,522,000, and the value of production £6,636,000; the value added to materials in the process of manufacture was, therefore, £2,681,000.

The capital invested in the manufacturing industries of the state amounted to £8,541,623, of which lands, buildings, and fixtures represented £2,631,039; machinery and plant, £4,052,584; and cash and sundries, £1,858,000. The machinery in use averaged 27.047 horse-power.

## MANUFACTORIES OF SOUTH AUSTRALIA.

In South Australia returns were obtained from manufactories in 1892, but in the following three years no information was obtained; since 1895, however, the returns have been collected annually. The following are the available figures :—

Year.	Establishments.	Males.	Females.	Total Hands employed.
1892	815	9,642	1,847	11,489
1896	767	10,974	1,811	12,785
1897	768	10,930	2,027	12,957
1898	766	12,296	2,085	14,381
1899	841	12,941	2,214	15,155
1900	1,036	14,800	2,859	17,659
1901	1,129	14,881	3,442	18,323
1902	1,325	16,595	3,943	20,538
1903	1,339	14,703	3,941	18,644

Although no definite information is available as to the invested capital in South Australia, it is probably in the neighbourhood of £5,037,000, of which lands and buildings are estimated to represent £1,676,000; machinery and plant, £1,730,000; and cash and sundries, £1,631,000. The machinery in use averaged 11,756 horse-power.

## MANUFACTORIES OF WESTERN AUSTRALIA.

In Western Australia, the manufacturing industry has advanced very rapidly in importance, and the hands employed now number nearly twelve thousand. The following are the figures for the last seven years :—

Year.	Establishments.	Males.	Females.	Total Hands employed.
1897	413	8,683	408	9,091
1898	485	8,521	613	9,134
1899	476	8,641	766	9,407
1900	507	9,440	880	10,320
1901	537	10,238	1,062	11,300
1902	575	10,404	1,301	11,705
1903	586	10,494	1,389	11,883

The capital invested amounts to £4,330,001, of which lands and buildings represent £1,245,186; machinery and plant, £1,631,815; and cash and sundries, £1,453,000. The average power of the machinery used is 13,065 horse-power, in addition to electric lighting plant of 911 horse-power.

## MANUFACTORIES OF TASMANIA.

Tasmania has several long-established industries, but until 1902 little information was available concerning them. A comparison of the information now published in regard to Tasmania with that of former years would convey the idea that a large increase of employment had occurred, but the apparent increase is due to the fact that in 1902, for the first time, complete information was obtained as to the development of the manufacturing industries. The figures for the last two years are :—

	1902.	1903.
Establishments .....	420	426
Hands—Males .....	6,181	6,442
Females .....	1,235	1,307
Total.....	7,466	7,749

The invested capital amounts to £2,688,155 ; lands and buildings are valued at £994,254 ; machinery and plant, £921,901, and cash and sundries at £772,000. The average power of the machinery used in 1903 was 7,010 horse-power ; while electric lighting plants of 1,354 horse-power were also in operation.

## MANUFACTORIES OF NEW ZEALAND.

In New Zealand, information regarding the manufacturing industry is obtained only at the quinquennial census. The figures for the year 1903 have been obtained from the returns of the Department of Labour but, as these include establishments not usually classed as manufactories, certain alterations were deemed necessary, and the figures have been adjusted to bring them into line with those of previous years. The invested capital in 1901 amounted to £13,209,398, of which lands, buildings, &c., represented £4,690,877 ; machinery and plant, £3,962,521 ; and cash and sundries £4,556,000. The average power of the machinery used was 39,939 horse-power. The values of land and machinery do not include either the Government Railway Workshops or Printing Office. The following statement shows the progress made since 1886 :—

Year.	Establishments.	Hands employed.		
		Males.	Females.	Total.
1886	1,946	19,601	2,494	22,095
1891	2,254	22,664	2,969	25,633
1896	2,440	22,945	4,391	27,336
1901	3,668	33,094	10,624	43,718
1903	3,960	41,022	11,606	52,628

The foregoing figures show very marked progress during the last eight years, and from an analysis of the returns it appears that this progress has been general amongst all classes of industries

## VALUE ADDED BY PROCESSES OF MANUFACTURE OR TREATMENT.

Statistics of a more or less exhaustive character are taken annually in all the states in order to show the condition and progress of the manufacturing industry ; but it is only at certain periods, usually on the occasion of a general census, that details of the output of factories are obtained. In New South Wales for the year 1901, and in New Zealand for the previous year, elaborate returns were obtained of the output of all branches of manufacturing industries, the value of materials operated on, wages paid, and other particulars. From the information gathered some interesting deductions may be made. As regards New Zealand, it may be remarked that the totals do not agree in all cases with those shown in the New Zealand Year Book, additional information having been supplied by the Statistician of that colony to complete the values of raw materials, wages and output. The following are some of the salient features of the returns :—

	New South Wales. £	New Zealand. £
Raw materials and other materials worked up .....	12,597,982	9,166,787
Fuel .....	482,428	243,000
Wages .....	4,867,917	3,511,590
Value of goods manufactured and work done (including custom work and repairing) .....	22,820,839	16,339,450

These figures do not take into consideration the returns from butter and cheese factories, the production from which is included elsewhere. From the figures just given the following values are obtained :—

	New South Wales. £	New Zealand. £
Value added to materials and fuel during the process of production	9,740,429	6,929,663
Percentage added to value of materials and fuel .....	74·5	73·6
Value added to materials, fuel, and wages.....	4,872,512	3,418,073
Percentage added to materials, fuel, and wages.....	27·1	26·5

A close examination of the returns of the two countries would probably disclose some discrepancies in details, but these are unavoidable in a general statistical review of the manufacturing operations of separate countries compiled by different persons. Taken as a whole, however, the returns of New South Wales and New Zealand are in very close agreement. The margin above the cost of materials, fuel, and wages includes the interest on land and buildings where these are the property of the manufacturer ; repairs and renewals to buildings and fixtures ;

rent, where the buildings, etc., are not the property of the manufacturer; interest on capital represented by machinery; renewals and depreciation in machinery and conveyance plant; advertising; and insurance, rates, and taxes not in the nature of excise duty or income tax. These, from a close analysis of the returns for New South Wales were found to be represented during the year 1901 by a total sum of £1,492,000. Assuming that approximately the same proportion of expenses obtains in New Zealand, and taking the two countries together, the following results are arrived at:—

	£
Value of Materials Used .....	21,764,769
Fuel .....	725,428
Wages .....	8,379,507
Miscellaneous Expenses.....	2,472,367
	<hr/>
	33,342,071

As the total output was valued at £39,160,289 there remained, when the foregoing charges were met, the sum of £5,818,218, which provides for the interest on capital embarked in the business, and trade losses and profits. This latter figure represents 17·5 per cent. of all the items included in cost of production, or 14·9 per cent. of the value of the production itself. In other words, for every hundred pounds worth of goods produced in the factories of the two countries, the following were the proportions of the various elements included in the price of the goods as they left the manufactories:—

Materials and Fuel.....	57·4
Wages .....	21·4
Miscellaneous Expenses.. ..	6·3
Interest, Provision for Trade Losses, Profits, &c. ....	14·9
	<hr/>
	100·0

The voluminous returns of the industrial census of the United States for 1900 give some very interesting figures relating to the manufacturing industries of that country:—

	Million Dollars.
Value of Materials used, including Fuel .....	7,345·4
Wages .....	2,726·0
Miscellaneous Expenses .....	1,027·7
Interest, Provision for Trade Losses, Profits, &c. ....	1,905·3
	<hr/>
Total Output .....	13,004·4

The proportion of total output borne by each of the above items is given below:—

Value of Materials used, including Fuel .....	56·5
Wages .....	21·0
Miscellaneous Expenses.....	7·9
Interest, Provision for Trade Losses, Profits, &c. ....	14·6
	<hr/>
	100·0

It will be seen that the Australian figures are in close agreement with those of America, nor is this agreement a matter of mere coincidence, for it is characteristic of the great majority of the industries making up the total, and shows that the business of manufacturing tends everywhere to fall into the same lines.

## CLASSES OF INDUSTRY.

As the result of a conference between the statisticians of the various states, the information in regard to industrial establishments is now given in the same form, the following classification having been agreed upon. The table shows the number of hands, male and female, employed in 1903 :—

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Treating Raw Materials, the Product of Pastoral Pursuits.....	5,570	22	2,286	1	7,856	23
Treating Raw Materials, the Product of Agricultural Pursuits, &c. ....	1,862	22	216	10	2,078	32
Oils and Fats, Animal, Vegetable, &c. ....	1,650	96	240	26	1,890	122
Processes in Stone, Clay, Glass, &c. ....	7,859	85	1,273	2	9,132	87
Working in Wood .....	16,232	30	6,635	2	22,867	32
Metal Works, Machinery, &c. ....	36,235	91	6,259	5	42,544	96
Connected with Food and Drink, &c. ....	28,755	4,555	7,080	628	35,834	5,183
Clothing and Textile Fabrics and Materials .....	16,982	36,848	7,667	9,579	24,619	45,957
Books, Paper, Printing, and Engraving .....	12,756	2,477	2,799	754	16,555	4,231
Musical Instruments .....	239	15	23	.....	262	15
Arms and Explosives .....	138	226	21	111	156	267
Vehicles and Fittings, Saddlery, and Harness, &c. ....	7,457	60	2,086	55	10,008	124
Ship and Boat Building, &c. ....	1,965	14	185	.....	2,150	14
Furniture, Bedding, and Upholstery .....	5,012	428	1,887	76	6,899	504
Drugs, Chemicals, and By-products... ..	1,508	492	291	58	1,800	550
Surgical and other Scientific Instruments .....	98	19	14	2	112	21
Jewellery, Timepieces, and Plated Ware .....	1,076	45	72	3	1,148	48
Heat, Light, and Power .....	2,575	91	763	166	4,383	257
Leatherware, not elsewhere included .....	384	68	43	20	427	88
Minor Wares, not elsewhere included .....	1,314	556	623	108	1,927	664
Total .....	146,668	46,759	41,023	11,606	196,667	58,365

Distributing the above total for the Commonwealth amongst the various states, the results shown in the following table are obtained.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Treating Raw Material, the Product of Pastoral Pursuits....	2,499	1,987	501	468	70	117
Treating Raw Materials, the Product of Agricultural Pursuits, &c. ....	288	1,089	25	329	37	106
Oils and Fats, Animal, Vegetable, &c. ....	625	523	165	228	67	68
Processes in Stone, Clay, Glass, &c. ....	3,073	3,076	422	497	679	197
Working in Wood .....	5,167	3,713	2,272	424	3,584	1,102
Metal Works, Machinery, &c. ....	12,851	10,350	3,215	6,090	2,107	1,763
Connected with Food and Drink, &c. ....	10,469	10,602	4,926	2,484	1,335	1,404
Clothing and Textile Fabrics and Materials .....	15,486	26,133	3,735	4,659	1,636	1,533
Books, Paper, Printing, and Engraving .....	6,135	6,525	1,985	1,166	962	510
Musical Instruments .....	219	25	1	9	....	....
Arms and Explosives.....	19	348	....	....	....	....
Vehicles and Fittings, Saddlery, and Harness, &c.....	2,102	2,973	844	815	599	263
Ship and Boat Building, &c. ....	1,591	98	129	111	92	38
Furniture, Bedding, and Upholstery .....	1,923	1,973	465	563	392	209
Drugs, Chemicals, and By-products .....	698	987	34	220	57	....
Surgical and other Scientific Instruments .....	64	35	13	....	....	....
Jewellery, Timepieces, and Plated Ware .....	257	504	53	133	41	45
Heat, Light, and Power .....	1,672	968	367	184	313	142
Leatherware, not elsewhere included .....	133	223	27	....	....	9
Minor wares, not elsewhere included.....	457	1,020	92	189	42	70
Total .....	66,623	73,229	19,296	18,644	11,833	7,749

### INDUSTRIES TREATING RAW MATERIALS THE PRODUCT OF PASTORAL PURSUITS.

A consideration of the details relating to the various classes of industry discloses some very interesting features. The hands employed in the industries treating raw material, the product of pastoral pursuits arranged according to the principal groups, were as follow :—

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Bolling-down and Tallow Refining	206	10	....	....	206	10
Tanneries .....	5,055	11	2,146	1	7,201	12
Wool-scouring and Fellmongering						
Bone Mills .....	207	1	....	....	207	1
Catgut and Sausage Skins .....	100	....	140	....	240	....
Total .....	5,570	22	4,286	1	7,356	23

The horse-power of the machinery in use in the Commonwealth was 5,331, and in New Zealand 1,519, the value of the machinery and plant being £418,125 and £91,423 respectively.

It is difficult to say if the figures for all the states are compiled upon the same basis. In New South Wales and Victoria wool-scouring works on sheep stations are not included, as the hands are employed in such works only during the shearing season, and frequently for not more than a few weeks. In Queensland there are no establishments classed as tallow-refineries, tallow being incidentally extracted in the process of meat-preserving, and the persons engaged therein are included in the latter industry. The hands employed in tallow-refining in New Zealand are included with those engaged in soap and candle-making.

The number of hands employed in treating raw material, the product of the pastoral industries, varies greatly from year to year, and, owing to the decrease in the number of live stock depastured, is much less than in former years. The following is a distribution of the total persons employed in the various states of the Commonwealth :—

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Bolling-down and Tallow Refining	134	84	....	....	....	....
Tanneries .....	907	1,640	202	339	61	102
Wool-scouring and Fellmongering	1,458		278	79	....	....
Bone Mills .....	....	118	21	50	9	15
Catgut and Sausage Skins .....	....	100	....	....	....	...
Total .....	2,499	1,937	501	468	70	117



Tanning, fellmongering, and wool-scouring afford the largest amount of employment amongst industries of this class, and the details show the goods treated or manufactured in tanneries during the latest year available.

State.	Number Tanned.			
	Hides.	Skins.		
		Calf.	Sheep.	Other.
New South Wales .....	433,299	41,565	3,282,600	32,040
Victoria .....	397,376	179,425	522,422	107,043
Queensland .....	*	.....	160,896	.....
Western Australia .....	16,260	.....	38,800	.....
Tasmania .....	†91,212	.....	.....	.....
New Zealand .....	178,075	.....	272,775	.....

\* Not available.

† Includes skins.

The foregoing information is somewhat imperfect, but will serve to convey an idea of the development of the industry in each state.

The quantity of wool washed in ordinary wool-scouring establishments cannot be stated with exactitude, but the following figures will give some idea of the extent of the industry. The figures represent the weight of clean wool exported from each state or locally consumed, in accordance with the latest annual returns.

	lb.
New South Wales .....	43,816,860
Victoria .....	8,961,011
Queensland .....	19,133,581
South Australia .....	3,256,361
Western Australia .....	405,261
Tasmania .....	884,128
New Zealand .....	18,003,426

#### TREATING RAW MATERIALS THE PRODUCT OF AGRICULTURAL PURSUITS.

The principal industry in this class is chaff-cutting, in which 1,914 persons find employment. The hands employed in the Commonwealth and New Zealand were as follow :—

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Bark Mills .....	112	...	...	...	112	...
Chaff-cutting and Corn-crushing ...	1,750	22	141	1	1,891	23
Grass Seed dressing .....	...	...	75	9	75	9
Total .....	1,862	22	216	10	2,078	32

The horse-power of the machinery used in the Commonwealth was 2,559, and in New Zealand, 580, the value of the machinery and plant being £108,148 and £37,565 respectively.

The greatest development of these industries is shown by Victoria, where 1,014 hands are employed in chaff-cutting establishments. The employment afforded by the various industries in each state is shown in the following table :—

Class of Industry.	New South Wales.	Victoria.	Qu'nsland.	South Australia.	Western Australia.	Tasmania.
Bark Mills .....	..	25	...	50	...	37
Chaff-cutting and Corn-crushing .....	288	1,014	25	279	37	129
Total .....	288	1,039	25	329	37	166

#### OILS AND FATS, &c.

There were 2,012 persons employed in factories dealing with oils and fats, the numbers in each industry being as follows :—

Class of Industry.	Commonwealth.		New Zealand.		Australia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Oil and grease .....	147	1	.....	.....	147	1
Soap and candles .....	1,497	95	232	25	1,729	121
Glue .....	6	.....	8	.....	14	.....
Total .....	1,650	96	240	25	1,890	122

The horse-power of the machinery used in the Commonwealth was 1,801, and in New Zealand 428, and the value of the machinery and plant was £474,866 and £44,203 respectively.

Of the 1,746 hands employed in the Commonwealth, 1,592 were engaged in soap and candle factories. The employment afforded by other industries was but small, as will be seen from the next table.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Oil and grease .....	105	43	.....	.....	.....	.....
Soap and candles .....	520	485	159	293	67	68
Glue .....	.....	.....	6	.....	.....	.....
Total .....	625	528	165	293	67	68

In view of the important dimensions attained by the soap and candle-making industry in the several states, the following information regarding the output during the year 1903 may be interesting ; no

information is available as to the production of candles in Queensland, and the New Zealand figures in this and all subsequent tables of a similar character refer to the year 1900 :—

State.	Soap manufactured. cwt.	Candles manufactured. lb.
New South Wales .....	199,807	3,231,842
Victoria .....	151,414	5,045,824
Queensland .....	54,684	.....
Western Australia .....	27,232	1,789,106
Tasmania .....	14,320	925,120
New Zealand .....	92,321	2,989,280

## STONE, CLAY, GLASS, &amp;c.

The industries which are comprised in this class deal with the various processes in stone, clay, and glass, and are each year assuming larger proportions. Brick and tile-making is by far the most important, sixty-two out of every hundred employed being engaged therein.

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Bricks and Tiles .....	4,089	69	996	2	5,084	71
Glass (including Bottles) .....	967	8	.....	.....	957	8
Glass (Ornamental) .....	290	3	10	.....	300	3
Lime, Plaster, and Cement .....	906	3	238	.....	1,174	3
Marble and Slate .....	660	2	.....	.....	650	2
Modelling, &c. ....	89	.....	.....	.....	89	.....
Pottery and Earthenware .....	245	.....	.....	.....	245	.....
Other Industries .....	33	.....	.....	.....	33	.....
Total .....	7,869	85	1,273	2	9,132	87

The horse-power of machinery employed in the Commonwealth was 6,582, and in New Zealand 1,166, the value of the machinery and plant being £675,921 and £68,952 respectively.

The hands employed in each industry for the different states are shown below. Those engaged in the manufacture of pottery and earthenware can be given only for New South Wales and South Australia ; in the other states they are included with brick and tile makers.

Class of Industry.	New South Wales.	Victoria.	Queens- land.	South Aus- tralia.	Western Aus- tralia.	Tas- mania.
Bricks and Tiles .....	1,921	1,581	278	254	550	174
Glass (including Bottles) .....	234	686	.....	46	.....	.....
Glass (Ornamental) .....	129	164	.....	.....	.....	.....
Lime, Plaster, and Cement .....	461	201	45	62	117	23
Marble and Slate .....	169	374	66	53	.....	.....
Modelling, &c. ....	7	70	.....	.....	12	.....
Pottery and Earthenware .....	162	.....	.....	83	.....	.....
Other Industries .....	.....	.....	33	.....	.....	.....
Total .....	3,073	3,076	422	497	679	197

The manufacture of pottery is generally associated with brick-making, and in the following table the products of brickyards and potteries for the year 1903 are shown together.

State.	Number of bricks and fire-bricks made.	Value of—	
		Pipes and tiles made.	Pottery, &c., made.
		£	£
New South Wales.....	202,681,000	73,769	•
Victoria .....	79,105,831	81,732	34,572
Queensland.. .....	12,473,239	11,258	•
Western Australia .....	45,576,179	.....	.....
Tasmania .....	11,312,695	5,030	•
New Zealand .....	41,290,316	27,335	7,475

\* Included with Pipes and Tiles.

#### WORKING IN WOOD.

The persons employed in these industries numbered 22,899, the largest employment being afforded by saw-mills, but the hands employed in these works have decreased considerably in late years. Owing to the lack of uniformity in the statistics of the various states it is impossible to state the strength of the hands in the various industries, but this has been done as far as practicable.

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Boxes and Cases .....	285	2	.....	.....	285	2
Cooperage .....	4,344	12	76	2	21,901	29
Joinery .....						
Saw-mills .....	11,225	15	.....	.....	.....	.....
Wood Turning and Cork Cutting.	220	1	208	.....	483	1
Other Industries .....	198	.....	.....	.....	198	.....
Total.....	16,232	30	6,635	2	22,897	32

Machinery is largely used in these industries, but it is not of a very valuable character. The horse-power of that employed in the Commonwealth was 19,787 and in New Zealand 9,097, the values being £1,644,278 and £425,695 respectively.

The succeeding table shows the distribution of employment in the various states of the Commonwealth. The figures relating to saw-mills and joinery appear slightly misleading; this is due to the fact that the returns for the different states are not compiled on the same basis. In Western Australia the workers in forest saw-mills number 2,777, while 788 hands are engaged in town saw-mills, cooperages, and joinery works; in New South Wales a number of joiners are also included with the saw-mill employees. In South Australia no information is given concerning them, although there must be a considerable number.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania
Boxes and Cases .....	219	.....	49	.....	19	.....
Cooperage .....	174	87	47	57	788	5
Joinery .....	731	1,798	429	.....		
Saw-mills .....	3,986	1,476	1,747	347	2,777	967
Wood Turning and Cork Cutting..	107	154	.....	20	.....	.....
Other Industries .....	.....	198	.....	.....	.....	.....
Total.....	5,167	3,713	2,272	424	3,534	1,102

There is no uniformity in the details published by the various states regarding saw-mills; but the information as to the quantity of timber regularly sawn for the latest year available is given below.

	Square feet, 1 inch thick.
New South Wales .....	100,408,000
Victoria .....	38,841,322
Queensland .....	69,508,800
Western Australia .....	119,465,433
Tasmania .....	35,196,700
New Zealand .....	261,583,518

The figures for New South Wales show a great falling off compared with those for 1900, when the quantity operated on was returned as 168,440,000 feet.

#### METAL WORKS, MACHINERY, &c.

Works connected with the treatment of metals, manufacture of machinery, agricultural implements, and railway rolling stock form a large and growing class of industry. The grouping given below is not

by any means satisfactory. Persons engaged in the various processes connected with the extraction of gold from gold-bearing stone are in a sense just as much entitled to be classified in the following tables as those concerned in the reduction of silver, lead, or copper ore. The determination of what constitutes an establishment classifiable as a work or factory is by no means clear. As regards works for the extraction of metals from their ores, the determining factor seems to be the degree of intricacy involved in the process of reduction; and whereas a quartz battery would not be called a factory or work, an establishment using a cyanide plant might be so classified. The distinction is not very logical, but as it has long obtained in these states it is retained here.

Class of Industry.	Commonwealth.		New Zealand.		Australia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Agricultural Implements .....	1,791	9	660	.....	2,460	9
Brass and Copper.....	754	.....	.....	.....	754	.....
Cutlery .....	72	1	6	.....	78	1
Galvanized Iron .....	1,268	8	261	.....	1,529	8
Engineering, Ironworks and Foundries .....	14,777	28	3,046	1	17,823	29
Lead Mills .....	67	1	.....	.....	67	1
Railway Carriages .....	268	.....	.....	.....	268	.....
Railway and Tramway Workshops	7,547	27	1,698	.....	9,173	27
Smelting.....	7,455	1	.....	.....	7,455	1
Stoves, Ovens, and Ranges .....	314	1	167	.....	481	1
Tinsmithing .....	1,050	2	380	.....	1,419	2
Wireworking.....	453	5	82	4	535	9
Other Metal Works .....	465	8	42	.....	507	8
Total .....	26,285	91	6,250	5	42,544	96

In these industries machinery is very extensively used. The horse-power of the machinery in use in the Commonwealth was 20,659 and in New Zealand 2,780, the values being £3,333,555 and £317,072 respectively.

In considering this and the subsequent tables, several difficulties in making comparisons will be met with. In Queensland, for example, all metal works, except smelting, are grouped in the one line, which is also the case in Western Australia. In Queensland no hands are shown

as being employed in the manufacture and repairs of rolling stock; this, of course, is incorrect, for though little manufacturing may be carried on, each state makes its own repairs. In Victoria 1,777 hands are shown as employed in railway carriage and rolling-stock manufacture and repairs as compared with 3,776 in New South Wales. The employment afforded in railway workshops is chiefly in the nature of repairs, but locomotives, passenger carriages, and goods waggons are built in each state, and it is evident that the repairs in the former state are not on such an extensive scale as in the latter. The number of hands set down as employed in the manufacture of agricultural implements in New South Wales is only 56, few establishments devoting themselves entirely to this business, the manufacture of implements being usually associated with ironworking generally. Included in the 610 workers in tinsmithing in South Australia are a number of plumbers and persons engaged in the manufacture of stoves and ovens. New South Wales and South Australia possess smelting works on a large scale, affording employment to 2,873 hands in the first-named state, and to 2,048 in the latter. The chief smelting works of New South Wales are situated at Cockle Creek, near Newcastle, and at Dapto, in close proximity to the coal-fields. The chief ores treated are copper, tin, silver, and lead, partly the production of the state itself, and partly of Tasmania, South Australia, Western Australia, Queensland, and New Caledonia. The smelting works of South Australia are situated at Port Pirie, and deal with silver and lead ore from Broken Hill. The number of hands employed in each state is shown in the following table:—

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Agricultural Implements .....	56	1,114	.....	565	46	19
Brass and Copper .....	212	499	.....	.....	.....	48
Cutlery .....	16	57	.....	.....	.....	.....
Galvanized Iron .....	405	788	.....	88	.....	.....
Engineering, Ironworks and Foundries .....	4,508	4,614	2,406	1,969	979	244
Lead-mills .....	21	47	.....	.....	.....	.....
Railway Carriages .....	263	.....	.....	.....	.....	.....
Railway and Tramway Workshops .....	3,513	1,777	.....	915	1,068	301
Smelting .....	2,873	769	809	2,048	.....	957
Stoves and Ovens .....	187	178	.....	.....	.....	.....
Tinsmithing .....	352	.....	.....	610	.....	99
Wireworking .....	226	208	.....	.....	14	.....
Other Metal Works .....	174	299	.....	.....	.....	.....
Total .....	12,851	10,250	3,215	6,090	2,107	1,763

## INDUSTRIES CONNECTED WITH FOOD AND DRINK.

The industries connected with food and drink afford employment for a large number of hands, the distribution into detailed groups being as shown in the following table. The figures for the most part afford their own explanation. Included under the head of cornflour, oatmeal, and arrowroot are, in the case of Victoria, a small number of hands making macaroni, and some starch makers; these last are few in number, and it was not found possible to exclude them from the persons employed in making farinaceous foods, otherwise they could have been classed elsewhere. Owing to an arrangement between the statistical offices of New South Wales and Victoria, factories dealing with milk products have been included in the list of manufactories, although they cannot rightly be considered as such. In New Zealand, malthouses are included with breweries, and probably bacon-curing and refrigerating establishments are included with meat preserving works.

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Bacon Curing .....	695	7	....	....	695	7
Butter Factories .....	2,879	56	1,190	43	4,113	106
Cheese Factories .....						
Condensed Milk .....	44	7	....	....		
Meat and Fish Preserving .....	2,098	41	3,002	58	5,100	99
Biscuits .....	2,84	1,521	635	375	8,475	1,896
Confectionery .....						
Cornflour, Oatmeal, &c. ....	436	212	18	....	444	212
Flour Mills .....	2,280	26	471	2	2,751	28
Jam and Fruit Canning .....	2,325	1,047	177	111	2,502	1,158
Pickles, Sauces, and Vinegar .....						
Sugar Mills .....	1,996	....	....	....	1,996	....
Sugar Refineries .....	847	16	212	....	1,059	16
Aerated Waters, Cordials, &c. ....	3,874	107	437	7	3,811	114
Breweries .....	3,383	7	814	2	4,197	9
Condiments, Coffee, Spices &c. ....	661	278	98	3	754	281
Distilleries .....	178	....	....	....	178	....
Ice and Refrigerating .....	638	4	....	....	638	4
Malting .....	220	....	....	....	220	....
Tobacco, Cigars, &c. ....	1,485	1,217	20	27	1,505	1,244
Salt .....	265	2	....	....	265	2
Other Industries .....	121	7	....	....	121	7
Total .....	26,755	4,555	7,009	638	33,824	5,183

In the preparation of foods and drinks machinery enters largely into use; the capital invested in machinery in the Commonwealth was £6,914,101, and in New Zealand £1,035,939, the average horse-power used being 47,421 and 14,792 respectively.



Distributing the persons shown above as employed in the Commonwealth amongst the various states, the most noticeable point is the strong position of Queensland, due entirely to the development of the sugar and meat-preserving industries.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Bacon Curing .....	127	256	93	202	....	24
Butter Factories .....	872	1,819	391	155	....	119
Cheese Factories .....	79					
Condensed Milk .....	51	....	....	....	....	....
Meat and Fish preserving .....	679	439	940	....	....	81
Biscuits .....	856	769	261	218	163	112
Confectionery .....	809	932	241			
Cornflour, Oatmeal, &c. ....	259	379	....	....	....	....
Flour Mills .....	751	661	154	504	101	135
Jam, and Fruit Canning .....	636	1,508	....	217	53	694
Pickles, Sauces and Vinegar .....	78		153	33	....	....
Sugar Mills .....	586	....	1,410	....	....	....
Sugar Refineries .....	415	344	....	104	....	....
Aerated Waters, Cordials, &c. ....	1,335	1,029	546	137	351	83
Breweries .....	969	1,063	391	310	490	197
Condiments, Coffee, Spices, &c. ....	525	245	37	196	21	5
Distilleries .....	18	34	59	67	....	....
Ice and Refrigerating .....	369	122	52	24	75	....
Malting .....	44	176	....	....	....	....
Tobacco, Cigars, &c. ....	1,011	1,268	114	203	106	....
Salt .....	....	63	....	204	....	....
Other Industries .....	....	....	84	....	....	44
Total .....	10,469	10,602	4,926	2,484	1,335	1,494

There are many important industries in this class the details of which would prove interesting, but only for a limited number is the necessary information available. The most important of these is perhaps the meat-preserving and refrigerating industry, and the following table will give some idea of its development in the various states.

The figures show the latest annual output, as far as practicable, although, in several of the states, poultry, fish, tongues, &c., are treated, in addition to the foods shown herein.

State.	Sheep and lambs, frozen.	Beef, frozen and chilled.	Rabbits frozen.	Meat Preserved.		
				Beef.	Mutton.	Rabbits.
	carcases.	lb.	No.	lb.	lb.	lb.
New South Wales .....	299,131	2,392,880	.....	4,133,263	1,496,470	.....
Victoria .....	294,906	.....	5,861,741	985,152	810,544	1,433,152
Queensland .....	102,007	66,483,364	.....	9,773,112	498,416	.....
New Zealand.....	3,348,123	34,285,328	6,040,047	7,867,440		.....

The sugar industry has attained considerable dimensions in New South Wales and Queensland. Some details of the industry for the

year 1903 are given below, but more extended information is given on this subject in the chapter dealing with "Agriculture."

State.	Sugar cane crushed.	Sugar manufactured.	Molasses manufactured.	Spirits distilled.
	tons.	tons.	gallons.	gallons.
New South Wales.....	224,772	21,786	1,267,020	.....
Queensland .....	823,875	91,828	2,407,652	174,933

Detailed information regarding flour-mills is available for each state excepting South Australia, and the following items have been selected as being of most value in showing the progress made. The quantity of flour made compared with the wheat ground seems a little inconsistent in some of the states, but the figures are given as they appear in the official records.

State.	Wheat ground.	Other grain ground.	Flour made.
	bushels.	bushels.	tons.
New South Wales.....	6,030,409	.....	121,074
Victoria .....	5,762,849	139,702	115,368
Queensland .....	1,172,908	55,893	23,738
Western Australia.....	685,652	.....	13,711
Tasmania.....	1,012,258	86,004	20,656
New Zealand .....	4,004,789	762,340	83,017

Breweries afford a large amount of employment, and those of Victoria have attained the most importance and have the largest annual output, as the following figures show :—

State.	Beer and Porter made.	Materials used—		
		Sugar.	Malt.	Hops.
	gallons.	cwt.	bushels.	lb.
New South Wales .....	14,211,868	84,218	571,462	713,451
Victoria .....	15,473,149	102,651	552,042	569,961
Queensland .....	4,324,336	.....	.....	.....
Western Australia .....	4,932,650	27,671	167,177	276,305
Tasmania .....	1,890,673	.....	.....	.....
New Zealand.....	7,379,581	21,647	455,035	562,245

Tobacco factories have assumed important dimensions in several of the states, and the output during 1903 was as follows :—

State.	Tobacco Manufactured.	Cigars.	Cigarettes.
	lb.	lb.	lb.
New South Wales .....	3,329,938	45,297	790,697
Victoria .....	2,390,976	116,669	134,400
Queensland .....	342,477	706	.....
Western Australia .....	94,393	13,832	6,758

## CLOTHING AND TEXTILE FABRICS.

Industries connected with the manufacture of clothing and textile fabrics afford more employment than any other class. The females employed largely outnumber the males, and the excess would be still greater if all persons working in their own homes, or in dwelling-houses not classed as factories, had been included. The following table shows the number of males and females employed in this class of industry :—

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Woolen Mills .....	961	806	787	965	7,688	1,861
Boots and Shoes .....	8,641	3,923	2,145	748	10,796	4,671
Slop Clothing and Tailoring .....	5,265	25,426	1,500	2,300	6,765	31,626
Dressmaking and Millinery .....			.....	3,000		
Underclothing .....	143	3,107	9	224	152	2,331
Dyeworks and Cleaning .....	95	125	46	26	141	151
Furriers .....	39	61	.....	.....	39	61
Hats and Caps .....	759	1,095	110	188	868	1,283
Waterproof and Oilskin .....	104	312	*	.....	104	312
Shirts, Ties, and Scarfs .....	78	333	39	890	117	1,658
Rope and Cordage .....	813	364	148	.....	1,250	363
Tents and Tarpaulins .....			239	99		
Flax Mills .....	.....	.....	2,637	2	2,637	2
Hosiery .....	35	316	20	259	55	575
Other Industries .....	.....	.....	17	48	17	48
Total .....	16,982	36,358	7,667	9,679	24,619	45,937

\* Included with Tents and Tarpaulins.

The use of machinery is not extensive in this class, as compared with the number of hands engaged. The value in the Commonwealth was only £848,845, and in New Zealand £340,933, the average horse-power used being 4,908 and 3,644 respectively.

Victoria shows the greatest development in these industries, and employs more hands than any other state in almost every branch of them. The only exceptions are waterproof clothing, where New South Wales employs more hands, and textiles, in which it is surpassed by New Zealand. The colony last named has 1,692 hands employed in

woollen mills compared with 1,138 in Victoria and 280 in New South Wales. New Zealand has also 2,639 hands in flax mills; in no other state has this industry been established. The classification of the minor industries is a matter of some difficulty as in many cases two or more branches are combined; this will account for the variations in such industries as shirt-making, underclothing, &c. The following table shows the distribution of employment in the various states of the Commonwealth :—

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Woollen Mills .....	280	1,138	57	151	.....	201
Boots and Shoes .....	4,288	5,267	1,145	1,218	302	344
Slop Clothing and Tailoring .....	6,040	6,965	1,837	3,106	846	890
Dressmaking and Millinery .....	2,876	7,149	501		472	
Underclothing .....	†.....	3,201	.....	.....	49	.....
Dyeworks and Cleaning .....	51	149	.....	14	.....	6
Furriers .....	33	62	.....	.....	.....	5
Hats and Caps .....	543	1,129	131	50	.....	.....
Waterproof and Ollskin .....	186	207	.....	23	.....	.....
Shirts, Ties, and Scarfs .....	856	†.....	.....	.....	†.....	55
Rope and Cordage, Mats, &c. ....	157	479	84	58	.....	3
Tents and Tarpaulins .....	176	64		39	17	.....
Hosiery .....	†.....	326	.....	.....	.....	25
Total .....	15,486	26,136	3,785	4,659	1,696	1,538

† Included elsewhere.

There are important boot and shoe factories in each of the states, and the output is attaining considerable proportions, as will be seen from the figures given below. No output of uppers is recorded from New South Wales or Victoria, although there are some establishments solely devoted to upper making; but the great bulk of the uppers is made in the ordinary boot factories.

State.	Articles manufactured.			Value of Output.
	Boots and Shoes.	Slippers.	Uppers.	
New South Wales .....	pairs. 3,166,475	pairs. 397,531	pairs. .....	£ .....
Victoria .....	3,574,761	.....	.....	.....
Queensland .....	682,762	.....	27,472	182,329
Western Australia .....	220,525	.....	.....	.....
Tasmania .....	202,249	.....	4,700	64,270
New Zealand .....	1,161,873	104,583	166,027	529,254

The manufacture of textile fabrics is becoming an important industry, especially in New Zealand, where the hands employed in woollen mills are nearly equal in number to those in the whole of the Commonwealth. Of the Commonwealth states Victoria is the most important, as may be judged by its consumption of wool, which is three and a half times that of New South Wales. The following information shows the output from woollen mills in the various states :—

State.	Wool used.	Articles manufactured.				Value of Output.
		Tweed and Cloth.	Flannel.	Blankets.	Shawls and Ruga.	
	lb.	yds.	yds.	pairs.	No.	£
New South Wales ...	660,002	458,302	3,428	5,000	900	...
Victoria .....	2,130,100	662,381	3,201,275	77,601	6,565	...
Tasmania .....	812,000	.....	.....	.....	.....	...
New Zealand.....	3,257,319	1,445,867	1,191,234	49,523	26,806	359,382

#### BOOKS, PAPER, PRINTING, &c.

The different industries connected with printing, bookbinding, paper-making, &c., afford work to 20,786 persons. The great bulk of these is employed in the various processes of printing, actual manufacturers being comparatively few in number. Australia and New Zealand produce many excellent paper-making materials; nevertheless, only three or four hundred persons are employed in paper-making, and a large proportion of the output of the mills consists of ordinary brown or wrapping papers.

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Electrotyping and stereotyping ..	100	10	.....	.....	100	10
Paper, Paper bags, boxes, &c. ....	629	786	148	114	772	900
Photo-engraving .....	106	20	.....	.....	106	20
Printing and bookbinding .....	12,763	2,658	2,654	640	15,407	3,298
Printing materials .....	53	2	2	.....	55	2
Engraving .....	101	1	.....	.....	101	1
Other Industries .....	14	.....	.....	.....	14	.....
Total .....	13,756	3,477	2,799	754	16,555	4,231

The machinery employed in the above had a value of £1,769,294 in the Commonwealth, and £381,958 in New Zealand. The average horse-power used was 4,827 and 1,762 respectively.

There are several difficulties in the way of making comparisons regarding these industries. Under the headings of electrotyping and stereotyping there are no returns for any state but New South Wales. It must be presumed, therefore, that persons employed in these pursuits in the other states are included with printing,

bookbinding, &c. Under the head of printing are included the composing and mechanical staff of the newspaper offices—persons whom it takes a very wide definition to bring in under the term “manufacturers.” The following table shows the employment afforded in the various states :—

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Electrotyping and stereotyping ..	110	.....	.....	.....	.....	.....
Paper, Paper bags, boxes, &c. ....	622	516	85	167	26	.....
Photo-engraving .....	42	42	.....	.....	42	.....
Printing and bookbinding .....	5,861	5,811	1,836	900	804	510
Printing materials .....	.....	56	.....	.....	.....	.....
Engraving .....	.....	102	.....	.....	.....	.....
Other Industries .....	.....	.....	14	.....	.....	.....
Total .....	6,136	6,525	1,965	1,166	962	510

#### MUSICAL INSTRUMENTS.

The manufacture of musical instruments is not yet firmly established in Australasia, and until recently the employment afforded was mainly in the direction of fitting and repairs.

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Musical Instruments .....	239	15	23	..	262	5

In New Zealand no machinery was employed, and in the Commonwealth the average horse-power used was only 67, and the value £4,870.

New South Wales is the only state which shows much development, 219 persons out of a total for the Commonwealth of 254 being engaged in that state. The greater part of this employment is afforded by one establishment.

#### ARMS AND EXPLOSIVES.

The manufacture of small arms and explosives is of great importance in connection with the defence of these shores, but so far little attention has been devoted to the industry, only 493 hands being employed, these being occupied exclusively in the manufacture of explosives.

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Explosives .....	185	226	21	111	156	337

The horse-power of the machinery used in the Commonwealth was 96, and in New Zealand 39, the value of the plant being £52,766 and £10,650 respectively.

Of the Commonwealth states, Victoria alone shows much development in this industry, and 342 hands are engaged in the manufacture of explosives, the remaining 19 hands being employed in New South Wales.

## VEHICLES, SADDLERY, AND HARNESS.

In connection with the manufacture and repair of vehicles, saddlery, harness, &c., there are 10,217 hands employed. The great bulk of the work done in connection with coaches and waggons consists of repairing; but there are establishments in all the states where vehicles of all classes are manufactured.

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Coach and Waggon Building .....	5,723	24	1,200	.....	7,609	33
Cycles .....	49	4	688	9	49	4
Perambulators .....	1,575	39	750	46	2,325	85
Saddlery and Harness .....	65	1	.....	.....	65	1
Spokes, &c. ....	30	1	.....	.....	30	1
Whips .....	15	.....	.....	.....	15	.....
Other Industries .....	.....	.....	.....	.....	.....	.....
Total .....	7,457	69	2,636	56	10,093	124

The employment of machinery in this class is mainly in tyre-setting. The horse-power of the machinery used in the Commonwealth was 745, and in New Zealand 226, the values being £171,829 and £38,868 respectively.

Victoria shows by far the greatest progress in this class, no less than 2,973 hands being employed in that state.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Coach and Waggon Building .....	1,518	2,210	425	406	345	151
Cycles .....	75	353	153	153	46	60
Perambulators .....	19	34	.....	.....	.....	.....
Saddlery and Harness .....	416	348	404	256	118	72
Spokes, &c. ....	66	.....	.....	.....	.....	.....
Whips, &c. ....	8	23	.....	.....	.....	.....
Other Industries .....	.....	.....	15	.....	.....	.....
Total .....	2,102	2,973	844	815	509	283

## SHIP AND BOAT-BUILDING AND REPAIRING.

The industries depending upon shipping have not attained large dimensions in any of the states, and as regards ship-building itself, the use of iron instead of wood for the frames and hulls of vessels has injuriously affected a promising industry, as the woods of Australia are eminently fitted for ship-building purposes. The following is a statement of the persons employed :—

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Docks and Slips .....	1,965	14	185	.....	2,150	14
Ships .....						
Ship and boat-building and repairs .....						
Total .....	1,965	14	185	.....	2,150	14

The use of machinery of a powerful character is necessary for the purpose of quickly emptying docks, although it is not in constant requisition. The value in the Commonwealth was £276,905, and in New Zealand £209,878, the average horse-power in use being 3,184 and 484 respectively.

In industries connected with ship-building and repairing, New South Wales has a far larger number of hands employed than any other state, mainly due to the fact that Sydney is the terminal port of most of the great lines of steamers trading with Australia. The chief portion of the business is in connection with the docking and repairing of ships, although there are several establishments engaged exclusively in ship and boat building.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Docks and Slips .....	696	98	189	111	92	{ ..... 12
Ships .....	42					
Ship and boat-building and repairs .....	763					26
Total .....	1,501	98	189	111	92	38

## FURNITURE, BEDDING, &amp;c.

Although Australia and New Zealand produce various kinds of wood admirably adapted to the requirements of the furniture trades, it can hardly be said that the industry has attained a development equal to its opportunities. As showing the possibilities of the industry, it may be mentioned that the value of furniture, imported into the



Commonwealth during 1903 was £167,366, and into New Zealand, £43,489. The employment afforded by the industry was :—

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Bedding, Flock, and Upholstery ..	747	313	13	1	760	314
Billiard Tables .....	32	.....	13	.....	45	.....
Chair-making .....	57	.....	.....	.....	57	.....
Furniture and Cabinet-making ..	4,082	114	1,700	69	5,372	196
Picture Frames .....			90	3		
Window Blinds .....	94	1	71	3	165	4
Total .....	5,012	428	1,887	76	6,899	504

The value of the machinery employed in the Commonwealth was £113,132, and in New Zealand £28,249, the average horse-power used being 1,158 and 464 respectively.

The manufacture of furniture, bedding, &c., in the Commonwealth affords employment to 5,440 persons, of whom 1,923 are in New South Wales and 1,978 in Victoria. The distribution in the various states is as follows :—

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Bedding, Flock, and Upholstery ..	382	509	136	.....	*	33
Billiard Tables .....	32	.....	.....	.....	.....	.....
Chair-making .....	57	.....	.....	.....	.....	.....
Furniture and Cabinet-making ..	1,309	1,296	329	521	283	159
Picture Frames .....	104	120		42	19	14
Window Blinds .....	39	53	.....	.....	.....	3
Total .....	1,923	1,978	465	563	302	209

\* Included elsewhere.

The manufacture of billiard tables is an established industry in Victoria, but the number of hands employed cannot be given separately, as they are included amongst those shown in furniture and cabinet-making.

#### DRUGS AND CHEMICALS AND BY-PRODUCTS.

In all the states there are establishments engaged in making chemicals or medicines of some description, while the manufacture of fertilisers is also an established industry in every state.

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Chemicals, Drugs, &c. ....	939	294	166	57	1,205	351
Fertilisers .....			100	.....		
Essential Oils .....	197	13	.....	.....	197	13
Paints and Varnishes .....	138	63	25	1	163	64
Blacking, Blue, &c. ....	235	122	.....	.....	235	122
Total .....	1,509	402	291	58	1,800	550

The horse-power of the machinery used in the Commonwealth was 1,201, and in New Zealand 319, the values of the plant being £233,965 and £32,963 respectively.

The classification for individual states will be found below :—

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Chemicals, Drugs, and Medicines.	457	514	34	67	39	.....
Fertilisers .....	101	.....	.....		27	.....
Essential Oils .....	.....	115	.....		.....	.....
Paints and Varnishes .....	105	69	.....	9	.....	.....
Blacking, Blue, Washing Powders, &c.	.....	293	.....	59	.....	.....
Total .....	693	967	34	230	57	.....

#### SURGICAL AND SCIENTIFIC APPLIANCES.

The employment afforded in these industries is not great, and the major portion of the work is in connection with the manufacture of spectacles, etc.

Class of Industry.	Commonwealth.		New Zealand.		Australia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Surgical, Optical, and other Scientific Instruments .....	93	19	14	2	112	21

The machinery employed was valued at £4,043, and the average horse-power used was 11.

In only four of the Commonwealth states are these industries established, and in none of them have they attained any important dimensions. A few persons engaged in making optical instruments in Western Australia are included with those in the following class, watchmaking, etc.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Surgical, Optical, and other Scientific Instruments .....	64	25	18	.....	.....	.....

#### TIMEPIECES, JEWELLERY, AND PLATED WARE.

There are 1,196 hands engaged in this class, mostly employed in connection with jewellery. The persons shown as engaged in electro-plating

for New Zealand include engravers, and the remaining 24 persons are lapidaries.

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Electro-plating .....	1,076	45	51	.....	1,148	48
Manufacturing Jewellery .....			21	3		
Total .....	1,076	45	72	3	1,148	48

The horse-power of the machinery employed in the Commonwealth was 81, and in New Zealand 14, the values of the plant being £27,966 and £3,822 respectively.

In each of the states certain persons are returned as being engaged in the manufacture of jewellery, but it is extremely doubtful if as many as are set down are employed solely in this industry. It is more than probable that the numbers include some hands principally engaged in the repair of watches and clocks.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Electro-plating .....	74	.....	58	22	.....	48
Manufacturing Jewellery .....	183	594		111	41	
Total .....	257	594	58	133	41	48

#### INDUSTRIES CONNECTED WITH THE PRODUCTION OF LIGHT.

Industries connected with the production of fuel, heat, and light do not afford employment to many hands. The following table shows 4,595 hands, of whom 2,643 are employed in gas-works, 1,243 in electric-lighting works, and 323 in coke-making. Gas supply gives employment to far more persons than the table shows—possibly to twice as many—but the additional hands are not employed in gas making, but in laying down pipes and other work connected with gas supply.

Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Coke-works .....	323	.....	.....	.....	323	.....
Electric Apparatus .....	1,120	3	120	.....	1,240	3
Electric Light and Power .....			.....	.....	.....	.....
Gas-works and Kerosene .....	2,088	.....	605	.....	2,643	.....
Lamps and Fittings, &c. ....	27	40	2	23	29	63
Hydraulic Power .....	34	.....	.....	.....	34	.....
Matches, Firekindlers, &c. ....	33	48	36	143	69	191
Total .....	3,575	91	763	166	4,338	257

Machinery of a very powerful and valuable character is required in these industries, as will be seen from the fact that the value of the plant

in the Commonwealth was £3,205,496, and in New Zealand £871,653, the average horse-power used being 37,931 and 2,419 respectively.

Only in New South Wales is the number of hands employed in each industry specified. The coke-workers in Victoria are included with hands employed in gas-works, while the hands employed in establishments other than gas-works are grouped together in Queensland. The number of hands employed in manufacturing candles is not included in the following table. The soap and candle industries are usually worked together, so that it is not possible to separate the hands employed, which are accordingly classified under the heading of soap and candle workers, in the second group of the series. The manufacture of matches is carried on in Victoria, but the number of hands employed is not disclosed in the official statistics.

Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Coke-works .....	323	.....	.....	.....	.....	.....
Electric Apparatus .....	48	68	6	.....	219	.....
Electric Light and Power .....	434	149	108	91	.....	.....
Gas-works and Kerosene .....	781	679	249	98	94	143
Lamps and Fittings, &c. ....	67	.....	.....	.....	.....	.....
Hydraulic Power .....	19	15	.....	.....	.....	.....
Matches, Firekindlers, &c. ....	.....	77	4	.....	.....	.....
Total .....	1,672	988	367	184	313	143

In view of the magnitude attained by gas-works in the various states, the following particulars as to the quantity of coal used and gas made during 1903, may prove interesting:—

State.	Coal used. tons.	Cubic feet of gas produced.
New South Wales .....	212,059	2,487,807,000
Victoria .....	166,018	1,628,889,400
Queensland .....	35,270	328,698,400
Western Australia.....	5,580	54,434,300
Tasmania.....	10,865	106,004,900
New Zealand .....	80,610	786,531,150

#### LEATHERWARE.

In view of the fact that the tanning industry has assumed such important dimensions, it is unsatisfactory to find that only 515 hands are employed in connection with the manufacture of leatherware.

Class of Industry.	Commonwealth.		New Zealand.		Australia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Leather Belting, Fancy Leather, Portmanteaux, and Bags. }	384	68	43	20	427	86

The machinery employed in the Commonwealth was valued at £12,093, and the average horse-power in use was 135.

The largest development of the industry is in Victoria, where 283 hands are employed, the majority of them—125 males and 48 females—being engaged in the manufacture of fancy leather.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Leather Belting, Fancy Leather, Portmanteaux, and Bags.	133	283	27	.....	.....	9

#### MINOR WARES.

All industries which could not properly be brought under the foregoing classification are included here. The more important of the industries are shown separately, but owing to their varied nature it is impossible to show them all, so that a number of separate industries have been brought together under the comprehensive title of "Other Industries."

Class of Industry.	Commonwealth.		New Zealand.		Australasia.	
	Males.	Females.	Males.	Females.	Males.	Females.
Baskets and Wickerware, Mats, &c. ....	684	192	237	35	1,024	277
Brooms and Brushware .....			113	50		
Rubber Goods .....	474	167	.....	.....	474	167
Toys .....	6	.....	21	1	27	1
Umbrellas .....	96	180	20	22	116	211
Other Industries .....	54	8	242	.....	296	8
Total .....	1,314	556	623	106	1,937	664

The horse-power of the machinery employed in the Commonwealth was 838, and in New Zealand 206, the values of the plant being £66,814 and £22,028 respectively.

The returns of the various states are each compiled on a different basis, so that it is impossible to give accurate information regarding the several industries. The manufacture of brooms and brushware is, however, the most important, while umbrella-making also employs a considerable number of hands. Included in the hands shown for Victoria are a number of persons engaged in making rubber tires. In

Western Australia a few employees at a butter factory are included with the broom makers in order to conceal individual returns.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
Baskets and Wickerware, Mats, &c. ....	57	44	92	175	42	19
Brooms and Brushware .....	199	213				.....
Rubber Goods .....	48	598				51
Toys .....	6	.....				.....
Umbrellas .....	106	165	14	.....	.....	.....
Other Industries .....	41	.....				.....
Total .....	457	1,090	92	180	42	70

#### INDUSTRIES DEPENDENT ON NATURAL RESOURCES, AND OTHER INDUSTRIES.

The relative development of the industries of the states may be measured by the information shown in the following table, in which the industries are arranged in three classes, viz.:—First, those connected with the treatment of perishable products for domestic consumption; second, those dependent upon the natural resources of the country; and, third, those the production from which comes into competition with imported goods:—

State.	Employed in domestic industries for the treatment of perishable products for immediate use.		Employed in industries dependent upon the natural resources of the country.		Employed in industries the production from which comes into competition with imported goods.	
	Males.	Females.	Males.	Females.	Males.	Females.
New South Wales..	3,573	51	26,513	5,696	22,367	7,433
Victoria .....	3,490	43	20,772	13,730	25,172	10,022
Queensland .....	1,337	43	8,394	2,263	6,408	841
South Australia ...	794	11	6,717	3,106	7,192	824
Western Australia.	883	3	6,567	1,097	3,044	289
Tasmania .....	378	21	3,935	723	2,129	563
Commonwealth..	10,455	172	72,898	26,615	66,312	19,972
New Zealand .....	2,441	52	21,173	2,029	17,408	9,525
Australasia .....	12,896	224	94,071	28,644	83,720	29,497

#### PLANT EMPLOYED IN MANUFACTORIES.

The character of the industry chiefly determines the horse-power required and the value of the plant. Thus, in the clothing and allied industries, the average number of persons per 100 horse-power is 825; in industries connected with the preparation of food and drink, the

average is only 63. The value of the plant, compared with the horse-power, also varies greatly in the different industries. In industries working in wood, the value of plant is only about £70 per horse-power, while in gas-making it is about £1,200. The following is a statement of the amount of horse-power and value of plant employed in the various groups of industries, according to the classification used in the foregoing pages :—

Class of Industry.	Commonwealth.		New Zealand.	
	Horse-power.	Value of plant.	Horse-power.	Value of plant.
Treating raw material—	No.	£	No.	£
(a) The product of pastoral pursuits..	5,331	418,125	1,519	91,423
(b) Do agricultural do ..	2,559	108,148	580	37,565
Oils and fats, &c. ....	1,801	474,866	428	44,203
Processes in stone, clay, glass, &c. ....	6,532	675,921	1,166	63,952
Working in wood .....	19,787	1,044,278	9,097	425,696
Metal works, machinery, &c. ....	20,659	3,333,555	2,750	317,072
Connected with food and drink, &c. ..	47,421	6,914,101	14,792	1,035,939
Clothing and textile fabrics, &c. ....	4,908	848,845	3,044	340,953
Books, paper, printing, &c. ....	4,827	1,769,294	1,762	381,958
Musical instruments.....	67	4,870	.....	.....
Arms and explosives ..	96	52,766	39	10,650
Vehicles, saddlery, and harness .....	745	171,829	226	38,868
Ship and boat building, &c. ....	3,184	276,905	484	209,878
Furniture, bedding, and upholstery ..	1,158	113,132	464	23,249
Drugs, chemicals, and by-products....	1,201	233,955	319	32,963
Surgical and other scientific instruments .....	11	4,043	.....	.....
Jewellery, platedware, &c. ....	81	27,966	14	3,322
Heat, light, and power .....	37,931	3,205,496	2,419	871,653
Leatherware not elsewhere included ..	135	12,063	.....	670
Minor wares not elsewhere included ..	838	66,314	206	22,023
Total .....	159,322	20,357,002	39,939	3,982,521

There is a slight inaccuracy in the returns that it is well should be pointed out. The horse-power quoted represents the average power actually used, and is exclusive of electric lighting plants, while the value of machinery and plant represents that of all the usable machinery that the establishments contain.

Similar information for each state of the Commonwealth is given below :

## HORSE POWER.

Class of Industry.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.
	No.	No.	No.	No.	No.	a.
Treating raw material—						
(a) The product of pastoral pursuits .....	1,891	2,213	721	961	143	102
(b) The product of agricultural pursuits .....	285	1,512	43	551	24	142
Oils and fats, &c. ....	563	303	123	673	81	43
Processes in stone, clay, glass, &c. ....	3,329	2,013	323	323	403	181
Working in wood .....	6,268	3,906	4,307	338	3,637	1,332
Metal works, machinery, &c. ....	9,023	4,839	1,636	1,963	561	2,532
Connected with food and drink, &c. ....	13,218	12,648	14,256	4,434	1,413	1,453
Clothing and textile fabrics, &c. ....	968	2,094	234	330	38	164
Books, paper, printing, &c. ....	1,937	1,746	483	470	129	62
Musical instruments .....	66	1	.....	.....	.....	.....
Arms and explosives .....	6	90	.....	.....	.....	.....
Vehicles, saddlery, and harness .....	174	276	52	164	59	20
Ship and boat building, &c. ....	2,642	210	112	116	20	84
Furniture, bedding, & upholstery .....	265	580	89	250	21	13
Drugs, chemicals, and by-products .....	417	500	21	241	22	.....
Surgical and other scientific instruments .....	4	2	5	.....	.....	.....
Jewellery, platedware, &c. ....	27	42	8	4	.....	.....
Heat, light, and power .....	18,094	6,410	4,363	1,965	6,514	890
Leatherware not elsewhere included .....	51	84	.....	.....	.....	.....
Minor wares not elsewhere included .....	90	677	7	63	.....	1
Total .....	59,353	41,091	27,047	11,756	13,065	7,010

## VALUE OF PLANT.

	£	£	£	£	£	£
Treating raw material—						
(a) the product of pastoral pursuits .....	166,770	142,225	72,640	20,645	4,350	11,485
(b) the product of agricultural pursuits .....	18,236	54,402	1,843	22,315	1,470	9,982
Oils and fats, &c. ....	122,901	107,761	33,210	183,594	10,000	7,400
Processes in stone, clay, glass, &c. ....	354,483	160,662	59,574	33,236	53,791	14,799
Working in wood .....	368,512	182,902	277,410	19,334	703,788	92,322
Metal works, machinery, &c. ....	1,356,969	858,943	369,976	311,309	120,430	267,083
Connected with food and drink, &c. ....	2,341,324	1,345,498	2,314,575	651,749	219,905	141,080
Clothing and textile fabrics, &c. ....	225,194	442,157	71,425	55,704	16,649	37,716
Books, paper, printing, &c. ....	607,730	663,209	182,781	163,963	119,368	32,225
Musical instruments .....	3,470	1,300	300	.....	.....	.....
Arms and explosives .....	468	52,298	.....	.....	.....	.....
Vehicles, saddlery, and harness, &c. ....	38,006	53,642	22,154	37,179	17,051	3,787
Ship and boat building, &c. ....	187,702	47,880	19,775	14,568	4,700	2,260
Furniture, bedding, and upholstery .....	33,672	37,652	11,821	22,775	3,992	2,310
Drugs, chemicals, and by-products .....	80,739	91,094	5,650	45,597	10,875	.....
Surgical and other scientific instruments .....	1,800	1,148	696	.....	400	.....
Jewellery, plated ware, &c. ....	8,434	14,474	2,520	1,321	650	247
Heat, light, and power .....	1,167,297	701,654	574,716	141,038	325,318	296,486
Leatherware not elsewhere included .....	4,100	7,280	289	.....	80	244
Minor wares not elsewhere included .....	11,394	45,285	1,330	4,775	90	3,290
Total .....	7,009,808	5,010,396	4,062,584	1,730,090	1,631,815	921,901



The average value of plant per horse-power of machinery employed ranges from £99 in the case of New Zealand to £149 for Queensland, the average for Australasia being £112. The average for each state was as follows:—New South Wales £96, Victoria £117, Queensland £149, South Australia £147, Western Australia £117, and Tasmania £110. A mere statement of values, however, has no special meaning, since the difference in the figures is compatible with two opposite conditions—either the same plant is put to greatest use in the case of New Zealand, or it is of superior character in the case of Queensland.

## CAPITAL EMPLOYED IN MANUFACTURING INDUSTRIES.

The capital employed in the manufacturing industries of Australia aggregates £60,400,000, of which the sum of £19,484,000 is invested in land and buildings, £20,357,000 in machinery and plant, and £20,559,000 represents cash and sundries. In New Zealand, the total capital invested in manufactories is £13,209,398, of which £4,690,877 is the estimated sum in buildings, &c., £3,962,521 in machinery and plant, and £4,556,000, cash and sundries. As regards the item cash and sundries, in some of the states the information obtained is in sufficient detail to enable correct estimates to be arrived at; in other states direct information is wanting, and the amount has been made up on the basis of the capital required by like industries in other states for which information is available. The amount of capital employed in each state of the Commonwealth and New Zealand is shown in the following table:—

State.	Capital.			Total.
	Land, Buildings, &c.	Machinery and Plant.	Cash and Sundries.	
	£	£	£	£
New South Wales.....	4,969,698	7,009,806	7,417,000	19,396,504
Victoria .....	7,967,945	5,010,896	7,428,000	20,406,841
Queensland .....	2,631,039	4,052,584	1,858,000	8,541,623
South Australia.....	1,676,000	1,730,000	1,631,000	5,037,000
Western Australia.....	1,245,186	1,631,815	1,453,000	4,330,001
Tasmania.....	994,254	921,901	772,000	2,688,155
Commonwealth .....	19,484,122	20,357,002	20,559,000	60,400,124
New Zealand .....	4,690,877	3,962,521	4,556,000	13,209,398
Australasia .....	24,174,999	24,319,523	25,115,000	73,609,522

The total value added to materials, as set out in the foregoing table, shows a considerable falling-off on the figures of the previous year. In many respects the year 1903 was an unfortunate one throughout Australia. There was a great shortage in the grain crop, with a consequent diminishing employment in flour-mills and other establishments treating grain. The pastoral industry also gave diminished

returns in all the states, and the decreased production in these industries reacted prejudicially upon other industries which depend more or less for support on the prosperity of the two great producing industries. There were other causes also for diminished production, which have been discussed in the chapter of this volume dealing with industrial progress.

#### VALUE OF PRODUCTION OF MANUFACTORIES.

The value of the articles produced in the manufactories has been carefully estimated for each of the states and is given below. For New South Wales and Queensland the information is now obtained annually; but although this is not the case in the other states, there is no difficulty in arriving at a satisfactory estimate, owing to the ample data at command. The production from butter, cheese, and bacon factories and creameries has not been taken into consideration, as it has already been included under the pastoral and dairying industries. The total value of the output of all factories was £87,237,000, of which £51,280,000 represents the value of materials and fuel used, and £35,957,000 the value added in the processes of treatment. Of the latter sum, £17,857,000 was paid in wages, leaving a balance of £18,100,000, which accrued to the proprietors, and out of which rent, insurance, depreciation, &c., had to be paid, the remainder representing profits on the business. The difference between the value of materials and fuel used and the total output is the real value of production from manufactories; this sum has been stated above as £35,957,000, and the amount in each state was as follows:—

State.	Value of Production.	Value per Inhabitant.
	£	£ s. d.
New South Wales .....	9,600,000	6 14 11
Victoria .....	9,368,000	7 14 11
Queensland .....	2,681,000	5 3 5
South Australia .....	2,729,000	7 8 5
Western Australia .....	2,874,000	12 19 9
Tasmania .....	1,276,000	7 3 9
Commonwealth .....	28,528,000	7 5 8
New Zealand .....	7,429,000	9 1 2
Australasia .....	35,957,000	7 11 10

The above table would seem to indicate that, in proportion to population, Western Australia holds the premier position; but the position occupied by that state is due to the higher prices obtained for the products rather than from any great development of the manufacturing

industries. New Zealand stands second, and its position is ample evidence of the great expansion that has occurred in the manufacturing industries of the colony during the last few years.

#### WAGES PAID IN MANUFACTORIES.

A comparison of the wages paid in the manufactories of the various states would be decidedly interesting, but unfortunately the figures are available only for New South Wales, Victoria, and New Zealand, and even in these states they are not compiled on the same basis. What information is available has, however, been prepared and is presented in the form of a table showing the average weekly wages paid in the various industries where a sufficient number of hands is employed to enable a fair average rate to be stated. The figures for the Commonwealth states refer to the year 1903, and were obtained from returns furnished in connection with the Factories and Shops' Acts; while the New Zealand figures were obtained from the census returns published by the Government Statistician. The average weekly wages of males are given hereunder:—

Industry.	Average Weekly Wages—Males.			
	New South Wales.	Victoria.	Queensland (Brisbane).	New Zealand.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.
Boiling-down and tallow refineries...	1 18 8	.....	.....	.....
Tanneries .....	1 18 0	1 14 6	1 9 0	} 1 11 3
Wool scouring and fellmongery .....	1 18 5	1 16 10	.....	
Chaff cutting .....	1 13 5	1 12 9	1 15 2	.....
Oil and grease .....	2 0 9	.....	.....	.....
Soap and candles.....	1 12 4	1 10 7	1 6 11	1 12 8
Bricks and tiles .....	2 6 3	2 4 6	1 18 11	1 9 0
Glass (including bottles) .....	1 12 5	1 11 4	.....	.....
Glass (ornamental) .....	1 18 5	1 14 10	.....	.....
Lime, plaster, and cement .....	2 0 6	1 16 0	.....	1 14 9
Marble and slate.....	1 14 5	.....	.....	.....
Pottery and earthenware.....	1 12 9	1 15 8	1 9 8	.....
Boxes and cases .....	1 12 11	.....	.....	.....
Cooperage .....	2 5 0	2 4 6	2 0 4	1 10 7
Joinery.....	2 3 10	} 2 3 0	.....	.....
Saw-mills .....	1 15 7		1 13 3	1 9 0
Wood-turning.....	1 16 11	.....	1 14 8	1 9 5
Agricultural implements .....	1 7 10	.....	.....	1 15 6
Brass and copper.....	1 9 8	1 9 8	1 9 4	} 1 12 0
Galvanised iron .....	1 12 0	.....	1 8 10	
Ironworks and foundries .....	1 18 3	1 15 7	.....	.....
Engineering .....	1 14 9	.....	1 16 0	1 13 0
Railway carriage works.....	1 13 4	.....	.....	.....
Smelting .....	2 8 8	.....	.....	.....
Stoves and ovens .....	1 12 3	1 12 8	0 17 8	1 13 9
Tinsmithing, sheet ironworks .....	1 6 2	1 7 7	1 3 7	1 6 5

Industry.	Average Weekly Wages—Males.			
	New South Wales.	Victoria.	Brisbane.	New Zealand.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.
Other metal works .....	1 19 4	.....	.....	1 10 4
Wire working .....	1 13 2	1 2 10	.....	.....
Bacon curing .....	2 2 3	1 18 6	.....	1 8 11
Butter factories .....	1 14 1	1 14 9	.....	1 11 6
Meat preserving .....	1 14 0	2 1 8	1 17 3	1 15 1
Biscuits .....	1 2 5	1 1 11	1 5 8	1 9 0
Confectionery .....	1 4 11	1 11 10	1 4 4	1 7 1
Cornflour, oatmeal, &c. ....	1 14 4	1 7 4	.....	.....
Flour-mills .....	1 17 0	2 1 7	1 14 0	1 17 0
Jam and fruit canning .....	1 0 10	1 6 1	1 2 2	1 8 7
Pickles, sauces, and vinegar .....	1 7 3		1 5 4	1 3 1
Sugar refineries .....	2 0 6	1 15 3	.....	.....
Aerated waters, cordials, &c. ....	1 10 3	1 6 8	1 4 9	1 8 0
Breweries .....	1 16 1	1 17 10	1 10 3	2 7 5
Condiments, coffee, and spices .....	1 8 6	.....	.....	.....
Distilleries .....	2 1 4	1 17 3	.....	.....
Ice and refrigerating .....	1 18 9	2 1 10	2 6 7	.....
Malting .....	.....	2 4 11	.....	1 19 9
Tobacco, cigars, &c. ....	1 9 7	1 14 0	1 12 9	.....
Woollen mills .....	1 3 7	1 3 6	.....	1 15 9
Boots and shoes .....	1 12 9	1 15 1	1 7 6	1 13 4
Slop clothing .....	2 0 3	2 0 7	1 9 3	.....
Clothing (tailoring) .....	2 4 5	.....	1 18 2	1 15 0
Dressmaking and millinery .....	1 8 2	1 11 8	.....	1 17 5
Hats and caps .....	1 15 3	1 19 2	1 2 5	1 7 5
Waterproof and oilskin .....	1 17 5	1 15 7	.....	1 6 9
Shirts, ties, and scarfs .....	1 14 9	1 14 3	1 0 0	1 6 3
Rope and cordage .....	1 3 7	1 4 2	.....	1 6 4
Tents and tarpaulins .....	1 5 9	1 10 4	2 1 3	.....
Paper bags, boxes, &c. ....	1 3 5	1 5 6	0 18 7	.....
Printing and bookbinding .....	1 18 1	1 18 6	1 19 6	1 19 3
Musical instruments .....	1 17 11	1 13 5	2 3 0	.....
Explosives .....	1 4 10	1 10 4	.....	.....
Coach and wagon building .....	1 10 11	1 10 7	1 13 5	1 7 1
Cycles .....	1 11 8	1 7 1	1 2 5	1 1 3
Ship and boat building .....	2 4 10	.....	.....	1 4 7
Iron bedsteads .....	1 9 4	1 15 1	.....	.....
Furniture and cabinetmaking .....	1 16 4	1 19 9	1 6 5	1 7 6
Picture frames .....	1 11 8	1 6 3	1 1 1	.....
Chemicals, drugs, and medicines .....	1 10 10	1 7 0	1 5 2	.....
Manufacturing jewellery .....	1 17 5	2 7 4	1 14 4	.....
Electric light and power .....	2 2 10	1 19 0	1 11 2	.....
Gasworks .....	2 4 9	.....	.....	2 7 8
Leather belting .....	1 14 10	1 9 9	.....	.....
Fancy leather, portmanteaux, and bags .....	1 6 9	1 7 5	1 0 4	.....
Brooms and brushware .....	1 11 7	1 13 4	1 0 5	1 6 8
Saddlery and harness .....	1 15 3	1 14 3	1 5 0	1 4 11
Basket and perambulator factories .....	1 6 8	1 15 4	.....	1 3 5

The average weekly wages of females in the different industries enumerated were as follows:—

Industry.	Average Weekly Wages—Females.			
	New South Wales.	Victoria.	Queensland (Brisbane).	New Zealand
	£ s. d.	£ s. d.	£ s. d.	£ s. d.
Soap and candles.....	0 10 7	.....	.....	.....
Meat preserving .....	0 12 2	.....	.....	0 16 3
Biscuits .....	0 13 2	0 12 2	0 8 1	0 11 2
Confectionery .....	0 9 3	0 13 4	0 7 4	0 8 2
Cornflour, oatmeal, &c. ....	0 12 9	0 12 2	.....	0 9 5
Jam and fruit canning .....	0 12 3	} 0 13 10	0 10 3	0 8 3
Pickles, sauces, and vinegar.....	0 8 11		0 11 5	0 13 3
Aerated waters, cordials, &c. ....	0 17 3	0 15 0	0 11 5	.....
Condiments, coffee, and spices. ....	0 11 1	.....	0 11 5	.....
Tobacco, cigars, &c. ....	0 16 6	1 1 1	0 15 8	.....
Woollen mills .....	0 12 11	0 17 8	.....	0 16 11
Boots and shoes .....	0 12 3	0 14 0	0 12 10	0 13 3
Slop clothing .....	0 14 9	0 18 0	0 10 11	.....
Clothing (tailoring).....	1 1 8	.....	0 13 10	0 15 11
Dressmaking and millinery .....	0 10 5	0 11 9	0 10 0	0 10 3
Hats and caps .....	0 13 4	0 15 0	0 14 0	0 13 3
Waterproof and oilskin .....	0 12 11	0 18 2	.....	0 9 6
Shirts, ties, and scarfs .....	0 12 1	0 14 10	0 11 1	0 10 5
Rope and cordage .....	0 11 0	0 11 8	.....	.....
Tents and tarpaulins .....	0 12 2	0 16 4	0 14 6	.....
Paper bags, boxes, &c. ....	0 10 7	0 11 4	0 10 5	.....
Printing and bookbinding.....	0 11 0	0 13 2	0 11 6	0 12 7
Bedding, flock, and upholstery .....	0 18 4	0 14 5	.....	.....
Chemicals, drugs, and medicines.....	0 10 10	0 15 8	0 11 4	.....
Fancy leather, portmanteaux, and bags .....	0 12 4	0 12 4	0 8 9	.....
Brooms and brushware .....	0 13 7	0 16 2	0 13 7	0 10 11
Saddlery and harness.....	0 16 2	0 15 9	0 10 0	0 17 2

These figures must be accepted with a certain degree of caution. In each state a considerable number of juvenile workers is employed, but only in Victoria is their actual strength ascertained, and as the average weekly wage paid in any establishment would depend to a large extent on the proportion of juvenile labour employed, a fair comparison is impossible while that information is lacking.

## EMPLOYMENT AND PRODUCTION.

TO obtain a fair approximation of the number of persons engaged in the various walks of life in Australasia was impossible before the census of 1891 was taken, for although at the Census enumerations of 1881 and previous years the occupations of the people were made a feature of the inquiry, the classification, which followed closely that originally devised by the late Dr. Farr for the English Census, was unsatisfactory, as it completely failed to distinguish between makers and modifiers, and distributors. To avoid a repetition of this defect the Census Conference, held at Hobart in March, 1890, abandoned the English system and adopted a scheme of classification more in accordance with sound principles. This classification was reviewed at the conference of Statisticians held in Sydney in February, 1900, and was adopted, with very slight modification, for use at the decennial Census of 1901. Under this classification the population is divided into two broad sections—bread-winners and dependents—and the bread-winners are arranged in their natural classes of primary producers, makers and distributors, with their various orders and sub-orders. The classes may be briefly defined as follows:—

### Section A.—Bread-winners.

- |         |     |                                                                  |
|---------|-----|------------------------------------------------------------------|
| Class 1 | ... | Professional.                                                    |
| 2       | ... | Domestic.                                                        |
| 3       | ... | Commercial.                                                      |
| 4       | ... | Transport and Communication.                                     |
| 5       | ... | Industrial.                                                      |
| 6       | ... | Agricultural, Pastoral, Mineral, and other<br>Primary producers. |
| 7       | ... | Indefinite.                                                      |

### Section B.—Dependents: Non-Breadwinners.

- |         |     |             |
|---------|-----|-------------|
| Class 8 | ... | Dependents. |
|---------|-----|-------------|

The information relating to the various classes and orders in each state has been arranged and presented in as concise a manner as practicable, as it is impossible to enter minutely into details in a work such as this, and those who desire to pursue the subject further are referred to the Census Reports of the various states.

### BREAD-WINNERS AND DEPENDENTS.

Of the total population of Australasia whose occupations were ascertained at the Census of 1901, the bread-winners numbered 1,979,484, and comprised 43·67 per cent., and the dependents 2,553,819, or 56·33

per cent. The number in each state and their proportion to the total population are shown below :—

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand	Australia.
NUMBER OF BREAD-WINNERS.									
Males .....	451,408	369,881	182,146	120,338	85,882	57,585	1,286,225	272,077	1,558,302
Females .....	113,396	144,668	36,022	32,968	13,489	15,909	356,452	64,730	421,182
Persons .....	564,799	514,049	218,168	153,306	99,371	73,494	1,642,677	336,807	1,979,484
PROPORTION PER CENT. OF BREAD-WINNERS.									
Males .....	63.75	64.86	65.94	65.25	75.32	64.25	65.25	67.47	65.63
Females .....	17.59	24.27	16.36	18.50	18.98	19.20	19.88	17.70	19.51
Persons .....	41.76	44.94	43.98	42.38	59.83	42.61	43.64	43.80	43.67
NUMBER OF DEPENDENTS.									
Males .....	256,634	210,980	94,084	64,094	27,229	32,039	685,060	131,164	816,224
Females .....	531,164	461,375	184,344	145,214	57,571	66,942	1,436,610	300,985	1,737,595
Persons .....	787,798	662,355	278,428	209,308	84,800	98,981	2,121,670	432,149	2,553,819
PROPORTION PER CENT. OF DEPENDENTS.									
Males .....	36.25	35.14	34.06	34.75	24.18	35.75	34.75	32.53	34.37
Females .....	82.41	75.78	83.65	81.50	81.02	80.80	80.12	82.30	80.49
Persons .....	58.24	55.36	56.07	57.72	46.17	57.29	56.98	56.20	56.33

The largest proportion of bread-winners is found in Western Australia, where this class comprises more than three-fourths of the male and nearly one-fifth of the female population. The striking feature of the table is the large number of bread-winners in the female population of Victoria, the proportion in that state being 24.27 per cent., while the corresponding figure for the Commonwealth is only 19.88 per cent.

It is interesting to compare the figures presented above with those obtained at previous census periods. In 1871 the proportion of bread-winners to the total population of Australia was only 41.36 per cent.; in 1881 it had increased to 42.36 per cent., and in 1891 to 43.14 per cent., while in 1901, as shown above, it was 43.64 per cent. Taking the male population for the same years, the proportion of bread-winners in 1871 was 62.43 per cent.; in 1881 it had risen to 63.26 per cent., and in 1891 to 64.27 per cent., while in 1901 it was 65.25 per cent. In the female population the increase was more striking, the proportion of bread-winners having increased from 16.03 per cent. in 1871 to 19.88 per cent. in 1901, the figures for the intermediate years 1881 and 1891 being 18.07 per cent. and 18.78 per cent. respectively. In New Zealand the proportion of bread-winners to total population was 40.94 per cent. in 1871, and 38.52 per cent. in 1881. Since the latter year there has been a considerable increase, the percentage in 1891 being 39.93, while in 1901 it was 43.80. In the male population the proportion increased

from 60·95 per cent. in 1881 to 62·11 in 1891, and to 67·47 in 1901; while in the female population the bread-winners represented 11·26 per cent. of the population in 1881, 14·86 per cent. in 1891, and 17·70 per cent. in 1901.

The number of bread-winners, male and female, in each of the various classes at the Census of 1901 was as follows:—

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
<b>CLASS I.—PROFESSIONAL.</b>									
Males .....	26,855	20,383	9,122	5,372	5,108	3,067	69,902	14,549	84,451
Females .....	14,529	14,841	4,486	3,485	1,964	1,930	41,225	8,980	50,195
Persons .....	41,384	35,224	13,608	8,857	7,072	4,997	111,127	23,529	134,646
<b>CLASS II.—DOMESTIC.</b>									
Males .....	20,123	13,129	7,790	3,452	4,373	1,463	50,335	6,542	56,877
Females .....	52,690	53,636	16,402	14,529	6,930	6,474	150,711	27,862	178,563
Persons .....	72,813	66,815	24,192	17,981	11,303	7,937	201,046	34,394	235,440
<b>CLASS III.—COMMERCIAL.</b>									
Males .....	67,067	64,633	22,950	17,080	10,230	6,067	183,137	34,409	222,546
Females .....	10,567	14,415	3,524	3,085	1,523	1,400	34,514	5,523	40,042
Persons .....	77,634	79,048	26,474	20,165	11,753	7,467	222,651	39,932	262,588
<b>CLASS IV.—TRANSPORT AND COMMUNICATION.</b>									
Males .....	42,822	30,318	17,745	12,591	10,730	4,518	118,730	21,285	139,905
Females .....	1,045	1,198	341	259	256	330	3,429	485	2,914
Persons .....	43,867	31,516	18,086	12,850	10,986	4,848	122,159	21,770	142,819
<b>CLASS V.—INDUSTRIAL.</b>									
Males .....	122,002	113,527	44,033	34,255	19,002	16,475	350,633	84,874	436,507
Females .....	23,996	32,706	7,407	6,978	2,203	2,275	75,570	16,310	91,890
Persons .....	146,038	146,233	51,489	41,233	21,205	18,750	426,203	101,184	527,397
<b>CLASS VI.—AGRICULTURAL, PASTORAL, MINING, AND OTHER PRIMARY PRODUCERS.</b>									
Males .....	163,212	140,149	79,413	45,898	35,081	25,439	494,192	108,007	602,199
Females .....	4,642	24,998	3,080	3,263	491	2,460	36,944	3,914	42,888
Persons .....	172,854	165,147	82,503	49,161	35,572	27,899	531,136	111,921	645,087
<b>CLASS VII.—INDEFINITE.</b>									
Males .....	3,597	7,342	1,044	1,680	307	526	14,236	2,431	16,727
Females .....	5,927	2,824	772	1,300	117	1,040	12,049	1,681	13,730
Persons .....	9,524	10,066	1,816	2,980	424	1,566	26,285	4,112	30,457
<b>TOTAL NUMBER OF BREAD-WINNERS.</b>									
Males .....	451,403	399,381	182,146	120,323	85,383	57,585	1,286,325	272,077	1,558,308
Females .....	113,896	144,668	36,022	32,968	13,489	15,900	366,452	64,730	421,133
Persons .....	564,799	544,049	218,168	153,291	98,872	73,485	1,652,777	336,807	1,979,441



## PRIMARY PRODUCERS.

From the foregoing table it will be apparent that the principal source of employment in Australasia is in its primary producing industries, no less than 645,057 persons being engaged therein. It is difficult to ascertain the numbers engaged in these industries prior to 1891 as the census returns of earlier years were not compiled on the scientific plan now in use, but from the information available the following statement has been prepared, showing as far as possible the employment since 1871, and the figures may be accepted as giving a fair idea of the extent to which employment in primary producing industries has expanded.

Persons Engaged in—	1871.		1881.		1891.		1901.	
	Australia.	New Zealand.	Australia.	New Zealand.	Australia.	New Zealand.	Australia.	New Zealand.
Agricultural Pursuits .....	159,648	18,223	221,681	42,722	247,896	59,477	276,095	67,812
Pastoral Pursuits .....	31,968	2,361	30,943	5,196	53,996	9,291	67,860	16,872
Dairy-farming .....	9,842	.....	13,704	345	22,732	765	43,952	4,538
Mining .....	84,295	21,226	71,880	14,273	75,605	16,877	118,239	17,816
Other Primary Producers ..	4,467	1,500	5,464	1,800	13,862	4,136	26,940	4,883
Total .....	290,210	43,313	343,672	64,336	414,091	90,546	533,186	111,921

In 1901 there were 602,199 males and 42,858 females engaged in the primary producing industries of Australasia. The employment afforded by the different branches may be seen from the following table.

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand	Australasia.
PERSONS ENGAGED IN AGRICULTURAL PURSUITS.									
Males .....	75,884	78,539	38,260	33,039	8,332	17,348	251,392	65,723	517,115
Females .....	1,735	17,381	2,081	1,147	235	2,074	24,703	2,069	26,792
Persons .....	77,619	95,920	40,341	34,186	8,567	19,422	276,095	67,812	543,907
PERSONS ENGAGED IN PASTORAL PURSUITS.									
Males .....	31,812	11,650	15,576	4,112	1,633	957	65,240	16,877	81,617
Females .....	595	1,692	174	81	52	26	2,520	485	3,115
Persons .....	31,907	13,342	15,750	4,193	1,685	983	67,860	16,872	84,732
PERSONS ENGAGED IN DAIRY FARMING AND POULTRY FARMING.									
Males .....	15,850	11,701	3,154	839	350	561	32,455	3,223	35,678
Females .....	2,285	5,877	825	2,029	144	337	11,497	1,315	12,512
Persons .....	18,135	17,578	3,979	2,868	494	898	43,952	4,538	48,190
PERSONS ENGAGED IN THE CAPTURE OF WILD ANIMALS OR THE ACQUISITION OF PRODUCTS THEREFROM.									
Males .....	949	1,436	762	296	85	399	3,927	970	4,997
Females .....	17	23	2	4	2	15	63	3	66
Persons .....	966	1,459	764	300	87	414	3,990	973	4,963

## EMPLOYMENT AND PRODUCTION.

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
PERSONS ENGAGED IN FISHERIES.									
Males .....	1,289	916	2,211	553	1,503	158	6,579	718	7,297
Females .....	8	2	4	....	4	4	17	2	19
Persons .....	1,241	918	2,215	553	1,507	162	6,596	720	7,316
PERSONS ENGAGED IN FORESTRY, ETC.									
Males .....	2,431	3,824	2,041	109	2,177	525	11,107	2,941	14,048
Females .....	1	3	....	2	....	3	9	2	11
Persons .....	2,482	3,827	2,041	111	2,177	528	11,116	2,943	14,059
PERSONS ENGAGED IN THE CONSERVATION AND SUPPLY OF WATER.									
Males .....	2,170	655	557	649	1,176	25	5,232	247	6,479
Females .....	2	1	2	....	1	....	6	....	6
Persons .....	2,172	656	559	649	1,177	25	5,238	247	6,485
PERSONS ENGAGED IN MINES AND QUARRIES, OR IN THE ACQUISITION OF MINERAL PRODUCTS.									
Males .....	38,378	31,428	16,852	6,301	19,835	5,466	118,290	17,808	136,086
Females .....	4	19	2	....	3	1	29	8	37
Persons .....	38,382	31,447	16,854	6,301	19,838	5,467	118,289	17,816	136,106
ALL PRIMARY PRODUCERS.									
Males .....	168,212	140,149	79,413	45,893	35,081	25,439	494,192	108,007	602,199
Females .....	4,642	24,998	3,090	3,263	491	2,460	38,944	8,914	42,858
Persons .....	172,854	165,147	82,503	49,161	35,572	27,899	533,136	111,921	645,057

Of the primary producers by far the largest proportion is engaged in agricultural pursuits, and, in fact, persons so employed outnumber those in any other calling. The persons engaged therein numbered 343,907, and as the total area under cultivation in Australasia at 31st March, 1901, was 10,456,538 acres, this would give an average of 30·4 acres to each person engaged. The number of persons engaged in agricultural pursuits and the area under cultivation in each state on the 31st March, 1901, was as follows:—

State.	Area under Cultivation.	Number of Persons engaged in Agricultural Pursuits.	Average No. of Acres per Person engaged.
	acres.		acres.
New South Wales .....	2,446,767	77,619	31·5
Victoria .....	3,114,132	95,920	32·5
Queensland .....	457,397	40,341	11·3
South Australia .....	2,369,680	34,186	69·3
Western Australia .....	291,338	8,607	23·4
Tasmania .....	224,352	19,422	11·6
Commonwealth .....	8,813,666	276,095	31·9
New Zealand .....	1,642,872	67,812	24·2
Australasia .....	10,456,538	343,907	30·4

The number of females engaged in agricultural pursuits is large in Victoria in comparison with the other states, as in that state a number of females, relatives of the farmers, who were partly engaged in agriculture and partly in domestic duties, have been counted as engaged in agricultural pursuits, while in the other states they were classified as performing domestic duties, and, consequently, as dependents.

Persons engaged in pastoral pursuits numbered 84,732, and of those in the Commonwealth nearly one-half were in New South Wales. The live stock in Australasia at the end of 1901 consisted of 92,358,824 sheep, 9,827,433 cattle, 1,905,172 horses, and 1,171,381 swine, the total being equal to 209,684,874 sheep, or an average of 2,475 sheep to each person. The number of live stock in each state, expressed in terms of sheep, and the number of persons engaged in pastoral pursuits during 1901 are shown below :—

State.	Live Stock expressed in terms of Sheep.	Persons engaged in Pastoral Pursuits.	Average Number of Sheep per Person.
New South Wales.....	67,198,799	31,907	2,106
Victoria .....	30,788,000	13,342	2,308
Queensland .....	52,379,231	15,750	3,326
South Australia .....	11,641,160	4,193	2,776
Western Australia.....	7,226,944	1,685	4,289
Tasmania.....	3,803,081	983	3,869
Commonwealth .....	173,037,215	67,860	2,550
New Zealand .....	36,647,659	16,872	2,172
Australasia .....	209,684,874	84,732	2,475

In Western Australia the number of primary producers was 35,572, and of these no less than 19,838 were engaged in mining pursuits.

The timber industry has not been specially dealt with in this volume. The interests involved, however, are somewhat large, especially in New Zealand and in the states of Western Australia, Queensland, and New South Wales. The total annual value of the timber industry of the Commonwealth is £2,251,000, and of New Zealand £972,000. This represents the value of the rough timber as it leaves the forest saw-mills and the bark stripped for tanning purposes, the value added to the timber by further treatment in the saw-mills and joinery yards being included in the manufacturing industries. Amongst the states of the Commonwealth, Western Australia stands first as regards timber production. In the year 1903 the value was £807,000, for New South Wales the return was £600,000 during the same period, and for Queensland £517,000. The other states show much smaller amounts, viz., Victoria, £143,000; Tasmania, £148,000; and South Australia about £36,000.

The fisheries of Australia comprise the ordinary coast and river fisheries, and the pearl-fishing industry of Queensland and Western and Northern Australia. The pearl-shell fisheries of Australia have assumed considerable dimensions, and in 1903 the production was valued at £419,000. In Queensland waters there were 301 boats engaged during 1903, and the industry gave employment to 354 divers and 124 other persons, the divers being principally Japanese. The total take of shell for the year was 908 tons, and the exports were valued at £162,547. In Western Australia there were 423 licensed pearling boats, and the persons employed numbered 2,839. Most of these persons belonged to coloured races, only 250 being of European descent. The export of shell during the year was 954 tons, valued at £174,322, while pearls to the value of £50,000 were also obtained. From the Northern Territory, pearl-shell to the value of £28,391 was exported in 1903. Reckoning the home fisheries of all the states and New Zealand, as well as the pearl fisheries, the total production of the industry may be set down at £1,078,000.

In several of the states, fish have been introduced from other countries, and trout may now be taken in many of the inland rivers. A notable feature in this connection was the introduction, during 1902, of English plaice, sole, and turbot, which were successfully landed in New South Wales, and liberated at Port Hacking.

#### THE INDUSTRIAL CLASS.

The persons engaged in industrial pursuits numbered 527,387, being only exceeded by those engaged in the primary producing industries. The largest proportionate number is to be found in Victoria, where 146,233 persons were engaged, being only 455 less than in New South Wales. Of the total number engaged in industrial pursuits 328,545 were employed in the manufacturing industry, and the following table has been prepared so as to show the number of persons engaged in the different branches thereof:—

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
PERSONS WORKING IN ART AND MECHANIC PRODUCTIONS.									
Males .....	26,346	20,676	9,401	5,849	3,636	2,368	68,276	18,479	86,755
Females .....	1,167	1,748	334	803	95	76	3,713	946	4,659
Persons .....	27,503	22,424	9,735	6,152	3,731	2,444	71,989	19,425	91,414
PERSONS WORKING IN TEXTILE FABRICS, DRESS, AND FIBROUS MATERIALS.									
Males .....	9,451	10,664	3,146	2,492	1,088	1,269	28,110	8,173	36,223
Females .....	21,644	28,460	6,606	6,243	2,024	2,069	67,066	14,237	81,303
Persons .....	31,095	39,114	9,752	8,735	3,112	3,368	95,176	22,410	117,586

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australia.
PERSONS WORKING IN FOOD, DRINKS, NARCOTICS, AND STIMULANTS.									
Males .....	11,638	10,251	5,308	2,762	1,638	1,133	32,730	7,302	40,032
Females .....	875	1,402	283	201	74	84	2,919	357	3,276
Persons .....	12,513	11,653	5,591	2,963	1,712	1,217	35,649	7,659	43,308
PERSONS WORKING IN ANIMAL AND VEGETABLE SUBSTANCES.									
Males .....	5,546	5,281	2,060	762	1,356	575	15,570	2,431	18,001
Females .....	50	85	3	3	1	7	149	18	187
Person .....	5,596	5,366	2,063	765	1,357	582	15,719	2,449	18,188
PERSONS WORKING IN MINERALS AND METALS.									
Males .....	15,336	14,315	4,710	6,069	2,583	2,051	45,054	8,280	53,334
Females .....	60	88	6	11	2	1	168	13	181
Persons .....	15,396	14,403	4,716	6,070	2,585	2,052	45,222	8,293	53,515
PERSONS WORKING IN FUEL, LIGHT, AND OTHER FORMS OF ENERGY.									
Males .....	2,012	1,085	286	239	237	120	3,929	580	4,509
Females .....	4	37	1	....	....	....	42	3	45
Persons .....	2,016	1,072	287	239	237	120	3,971	583	4,554
ALL PERSONS ENGAGED IN MANUFACTURING INDUSTRIES.									
Males .....	70,329	62,222	24,901	18,163	10,538	7,516	193,669	45,245	233,914
Females .....	23,790	31,310	7,233	6,761	2,196	2,267	74,057	15,574	89,631
Persons .....	94,119	94,032	32,134	24,924	12,734	9,783	267,725	60,819	323,545

The number shown above as employed in manufacturing industries exceeds that given in the chapter dealing with manufactories, since the factory returns relate to employment in industries coming under the provisions of the Factories Act, and take no account of places where less than four hands are employed, unless machinery is used. In the Census figures also are included casual workers and all single workers engaged on their own account, both of which classes are omitted from the factories returns. The case of New South Wales may be cited as an example to show the difference between the two returns in the number of female workers. According to the Census there were 18,000 dressmakers and tailoresses, many of them on their own account. According to the factories returns there were under 7,000.

At the census of 1891 the persons engaged in the manufacturing industries of the states which comprise the Commonwealth numbered 214,220, so that there has been an increase of 53,506 persons or nearly 25 per cent. during the ten years. The largest increase was in New South Wales, where the total was 74,559 in 1891, and 94,119 in 1901, an addition of 19,560 persons or more than 26 per cent.

The number of persons engaged in the other branches of the industrial class is shown in the following table :—

Sex	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia
PERSONS ENGAGED IN MANUFACTURING INDUSTRIES.									
Males .....	70,329	62,222	24,901	18,163	10,583	7,516	183,609	45,245	228,814
Females .....	23,790	31,810	7,253	6,761	2,196	2,267	74,957	15,574	89,631
Persons .....	94,119	94,032	32,154	24,924	12,784	9,783	267,726	60,819	338,545
PERSONS ENGAGED IN THE CONSTRUCTION OR REPAIR OF BUILDINGS, RAILWAYS, ROADS, &c.									
Males .....	86,898	27,892	9,878	8,652	5,827	3,924	92,571	22,879	115,450
Females .....	11	17	....	....	1	2	31	13	44
Persons .....	86,909	27,409	9,878	8,652	5,828	3,926	92,602	22,892	115,494
PERSONS ENGAGED IN THE DISPOSAL OF THE DEAD, OR OF REFUSE.									
Males .....	1,278	1,260	276	183	222	86	3,306	181	3,486
Females .....	15	24	2	1	....	1	43	2	45
Persons .....	1,293	1,284	278	184	222	87	3,348	183	3,531
PERSONS ENGAGED IN IMPERFECTLY DEFINED INDUSTRIAL PURSUITS.									
Males .....	14,187	22,653	9,027	7,257	3,015	4,949	61,088	16,509	77,657
Females .....	180	355	172	216	11	5	1,489	721	2,160
Persons .....	14,367	23,508	9,199	7,473	3,026	4,954	62,527	17,290	79,817
ALL INDUSTRIAL WORKERS.									
Males .....	122,692	113,527	44,082	34,255	19,602	16,475	350,633	94,874	435,307
Females .....	23,996	32,706	7,407	6,978	2,208	2,275	75,570	16,310	91,880
Persons .....	146,688	146,233	51,489	41,233	21,810	18,750	426,203	101,184	527,387

### THE COMMERCIAL CLASS.

The persons engaged in commercial pursuits in Australasia numbered 262,588, and of these 220,757 were engaged in trade. The following table shows the number of persons engaged in the various branches of trade :—

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
PERSONS DEALING IN ART AND MECHANIC PRODUCTIONS.									
Males .....	4,144	3,720	1,543	810	728	305	11,250	1,966	13,206
Females .....	564	984	216	168	131	54	2,067	334	2,401
Persons .....	4,708	4,664	1,759	978	859	359	13,317	2,290	15,607
PERSONS DEALING IN TEXTILE FASHION, DRESS, AND FIBROUS MATERIALS.									
Males .....	6,957	6,374	2,391	1,654	969	707	18,962	4,175	23,197
Females .....	2,269	2,462	808	739	376	250	6,954	1,376	8,330
Persons .....	9,226	8,836	3,199	2,393	1,345	957	25,906	5,551	31,457

# EMPLOYMENT AND PRODUCTION.

1013

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
PERSONS DEALING IN FOOD, DRINK, NARCOTICS, AND STIMULANTS.									
Males .....	19,522	18,217	6,643	4,460	2,596	1,301	52,739	8,521	61,260
Females .....	2,581	3,428	705	574	294	229	7,611	878	8,490
Persons .....	22,103	21,645	7,348	4,834	2,890	1,530	60,350	9,399	69,749
PERSONS DEALING IN ANIMAL AND VEGETABLE MATTERS.									
Males .....	5,984	3,977	1,540	968	730	329	13,518	2,592	16,110
Females .....	154	198	84	80	14	16	446	55	501
Persons .....	6,138	4,175	1,574	968	744	345	13,964	2,647	16,611
PERSONS DEALING IN FUEL AND LIGHT.									
Males .....	2,084	2,794	911	591	476	255	7,111	748	7,859
Females .....	25	34	5	3	2	4	78	11	84
Persons .....	2,109	2,828	916	594	478	259	7,184	759	7,943
PERSONS DEALING IN MINERALS AND METALS.									
Males .....	2,126	2,044	700	686	543	195	6,263	1,519	7,782
Females .....	60	162	11	4	13	10	260	38	298
Persons .....	2,186	2,206	720	640	556	205	6,523	1,557	8,080
GENERAL AND UNSPECIFIED DEALERS.									
Males .....	16,689	16,091	6,173	5,668	2,647	1,960	49,228	8,948	58,176
Females .....	3,130	4,446	1,139	1,206	433	477	10,891	2,343	13,184
Persons .....	19,819	20,537	7,312	6,934	3,080	2,437	60,119	11,191	71,310
TOTAL PERSONS ENGAGED IN TRADE.									
Males .....	57,516	53,217	19,810	14,777	8,689	5,062	159,061	23,459	187,520
Females .....	8,783	11,654	2,978	2,584	1,263	1,040	23,802	4,985	33,237
Persons .....	66,299	64,871	22,788	17,361	9,952	6,092	182,863	28,444	220,757

The largest number of persons in the above class is found in the division which relates to those dealing in foods, drinks, and stimulants, the total being 69,749. The number of females employed in trade has increased nearly four fold in the Commonwealth since 1891. A classification of the persons engaged in other branches of commercial pursuits will be found below :—

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
PERSONS ENGAGED IN FINANCE AND REAL PROPERTY.									
Males .....	8,985	10,039	3,004	2,267	1,482	1,008	26,785	5,046	31,831
Females .....	1,733	2,760	533	496	254	356	6,182	585	6,767
Persons .....	10,718	12,799	3,537	2,763	1,736	1,364	32,967	5,631	38,598

## EMPLOYMENT AND PRODUCTION.

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
PERSONS ENGAGED IN TRADE.									
Males .....	57,516	53,217	19,810	14,777	8,889	5,052	159,061	28,459	187,520
Females .....	8,783	11,654	2,978	2,584	1,263	1,040	23,302	4,935	33,237
Persons .....	66,299	64,871	22,788	17,361	9,952	6,092	187,363	33,394	220,757
SPECULATORS ON CHANCE EVENTS.									
Males .....	424	284	42	13	33	35	836	41	877
Females .....	....	1	13	5	6	4	29	3	32
Persons .....	424	285	55	18	44	39	865	44	909
PERSONS ENGAGED IN STORAGE.									
Males .....	172	1,003	94	23	71	2	1,455	863	2,318
Females .....	1	....	....	....	....	....	1	5	6
Persons .....	173	1,003	94	23	71	2	1,456	868	2,324
TOTAL, COMMERCIAL CLASS.									
Males .....	67,097	64,633	22,950	17,080	10,220	6,097	188,187	34,409	222,546
Females .....	10,567	14,415	3,524	3,085	1,523	1,400	34,514	5,523	40,042
Persons .....	77,664	79,048	26,474	20,165	11,803	7,497	222,651	39,937	262,588

## THE DOMESTIC CLASS.

The domestic class embraces all persons engaged in the supply of board and lodging, and in rendering personal services for which remuneration is usually paid. The numbers in each state were as follows :—

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
PERSONS ENGAGED IN PROVIDING BOARD AND LODGING.									
Males .....	8,258	6,984	3,056	1,482	2,474	701	22,955	3,398	35,843
Females .....	15,622	14,850	4,502	1,202	3,278	788	40,242	6,749	66,901
Persons .....	23,880	21,834	7,558	2,684	5,752	1,489	63,197	10,147	72,899
PERSONS ENGAGED IN DOMESTIC SERVICE AND ATTENDANCE.									
Males .....	11,870	6,145	4,734	1,970	1,899	762	27,380	3,649	30,029
Females .....	37,068	38,836	11,900	13,527	3,652	5,086	110,469	21,103	181,572
Persons .....	48,938	44,981	16,634	15,297	5,551	6,448	137,849	23,752	161,601
TOTAL, DOMESTIC CLASS.									
Males .....	30,128	13,129	7,790	3,452	4,373	1,463	50,335	6,542	56,877
Females .....	52,690	53,686	16,402	14,629	6,930	6,474	150,711	27,852	178,563
Persons .....	72,818	66,815	24,192	17,981	11,303	7,937	201,046	34,394	235,440

Of all the females employed it will be seen that over 40 per cent. are in the Domestic class. The females shown above as employed in domestic service, perform similar duties to those classed as dependents, but they receive remuneration for their services.



## THE PROFESSIONAL CLASS.

The persons in this class numbered 134,646 and were distributed amongst the various states as follows :—

Sex.	New South Wales.	Victoria.	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Australasia.
PERSONS ENGAGED IN GENERAL GOVERNMENT.									
Males .....	1,545	1,427	847	660	539	298	5,306	1,043	6,349
Females .....	81	91	15	6	12	9	164	47	211
Persons .....	1,576	1,518	862	666	551	297	5,470	1,090	6,560
PERSONS ENGAGED IN LOCAL GOVERNMENT.									
Males .....	349	866	365	174	96	83	1,922	396	2,818
Females .....	5	19	7	3	1	....	35	11	46
Persons .....	354	875	372	177	96	83	1,957	407	2,864
PERSONS ENGAGED IN DEFENCE.									
Males .....	3,511	689	777	237	312	317	5,843	1,033	6,876
Females .....	....	....	....	....	....	....	....	....	....
Persons .....	3,511	689	777	237	312	317	5,843	1,033	6,876
PERSONS ENGAGED IN LAW AND IN THE PRESERVATION OF ORDER.									
Males .....	5,404	3,747	1,826	892	1,040	624	13,533	2,341	15,874
Females .....	74	55	24	20	21	8	202	71	273
Persons .....	5,478	3,802	1,850	912	1,061	632	13,735	2,412	16,147
PERSONS MINISTERING TO RELIGION, CHARITY, HEALTH, EDUCATION, ART, AND SCIENCE.									
Males .....	16,046	13,064	5,307	3,409	3,117	1,755	43,298	9,736	63,084
Females .....	14,419	14,676	4,440	3,456	1,930	1,913	40,834	8,831	49,665
Persons .....	30,465	28,340	9,747	6,865	5,047	3,668	84,132	18,567	102,699
TOTAL, PROFESSIONAL CLASS.									
Males .....	26,855	20,833	9,122	5,372	5,108	3,067	69,902	14,549	84,451
Females .....	14,529	14,841	4,436	3,486	1,964	1,930	41,235	8,960	50,195
Persons .....	41,384	35,224	13,608	8,857	7,067	4,997	111,137	23,509	134,646

The number shown above as engaged in general government does not represent the total persons employed by the state, as the government officers have been included in the sections to which the nature of their work is most closely allied. It is not possible to give the total number of government employees for any state except New South Wales, where they numbered 32,000 at the census of 1901.

## GRADES OF WORKERS.

In all the states except Queensland a distribution of bread-winners was made into the characteristic divisions, viz., employers, workers on their own account, relatives assisting, wage earners, other persons to

whom the grades are not applicable, and unemployed. The figures for the various states and New Zealand were as shown below :—

Sex.	New South Wales.	Victoria.	South Australia.	Western Australia.	Tasmania.	New Zealand.
<b>EMPLOYERS.</b>						
Males .....	48,911	43,157	14,259	7,714	6,205	34,002
Females .....	4,933	4,997	1,089	633	462	2,010
Persons .....	53,844	48,154	15,348	8,347	6,667	36,012
<b>PERSONS ENGAGED ON THEIR OWN ACCOUNT BUT NOT EMPLOYERS OF LABOUR.</b>						
Males .....	65,560	71,384	15,959	10,219	9,388	47,313
Females .....	16,779	22,879	3,547	1,766	2,790	8,759
Persons .....	82,339	94,263	19,506	11,985	12,178	56,063
<b>RELATIVES ASSISTING.</b>						
Males .....	17,635	26,842	5,493	1,904	4,090	17,052
Females .....	6,077	26,748	2,240	931	2,070	4,523
Persons .....	23,712	53,590	7,733	2,835	6,160	21,575
<b>WAGE-EARNERS.</b>						
Males .....	290,095	234,203	78,879	61,840	36,093	166,431
Females .....	72,170	87,397	23,366	9,277	10,231	48,068
Persons .....	362,265	321,600	102,245	71,117	46,324	214,519
<b>OTHERS TO WHOM THESE GRADES ARE NOT APPLICABLE.</b>						
Males .....	8,421	.....	2,381	565	.....	.....
Females .....	9,815	.....	2,038	433	.....	.....
Persons .....	18,236	.....	4,419	998	.....	.....
<b>UNEMPLOYED.</b>						
Males .....	20,781	13,795	3,357	3,140	1,809	7,279
Females .....	3,622	2,647	688	449	356	1,359
Persons .....	24,403	16,442	4,045	3,589	2,165	8,638
<b>TOTAL WORKERS.</b>						
Males .....	451,403	389,381	120,328	85,382	57,585	272,077
Females .....	113,396	144,668	32,968	13,469	15,909	64,730
Persons ..	564,799	534,049	153,296	98,871	73,494	336,807

The ages of 1,978,910 of the workers were ascertained, and are shown hereunder in three groups. Of the total number, 53,505 were under the age of 15 years, 309,252 were aged 15 and under 20, while the remaining 1,616,153 had attained the age of 20 years or over :—

Sex.	New South Wales.	Victoria	Queensland.	South Australia.	Western Australia.	Tasmania.	Commonwealth.	New Zealand.	Antarctica.
UNDER 15 YEARS.									
Males .....	9,142	11,275	4,648	4,415	1,340	2,246	33,066	6,492	39,556
Females .....	2,785	4,788	1,763	1,879	496	778	11,989	1,968	18,947
Persons .....	11,927	16,063	6,411	5,794	1,836	3,024	45,055	8,450	53,505
15 YEARS AND UNDER 20 YEARS.									
Males .....	61,963	52,248	21,657	18,441	6,620	8,606	169,529	33,391	207,920
Females .....	26,381	32,199	10,121	9,024	2,738	3,577	84,040	17,292	101,332
Persons .....	88,344	84,442	31,778	27,465	9,358	12,182	253,569	50,683	309,252
20 YEARS AND OVER.									
Males .....	377,992	324,948	158,697	97,472	77,213	46,631	1,082,953	226,867	1,309,520
Females .....	84,063	107,383	25,105	22,566	10,241	11,552	280,909	45,424	306,333
Persons .....	462,055	432,331	183,802	120,037	87,454	58,183	1,363,863	272,291	1,616,153
TOTAL WORKERS.									
Males .....	449,097	388,466	185,002	120,328	85,173	57,482	1,285,548	271,750	1,557,298
Females .....	118,229	144,370	86,989	32,908	13,475	15,907	356,938	64,674	421,612
Persons .....	567,326	532,836	221,991	153,236	98,648	73,389	1,642,486	336,424	1,978,910

This table, based on the census returns, would seem to show that juvenile labour is employed to a much greater extent in Victoria than in the other states. There is no apparent reason why this should be the case, and a probable explanation of the anomaly will be found in the fact that a large number of children under 15 were returned in Victoria as assisting their parents in farming, &c. These, in the other states, were counted as scholars if shown to be attending school; but in Victoria they appear to have been classified as "relatives assisting," and, consequently, as workers.

It will be seen that the unemployed comprise a considerable section of the community. No information is available regarding the number in Queensland, but in the other five states of the Commonwealth there were 50,644 persons, 42,882 males and 7,762 females, who had been unemployed for a week or more at the date of the Census. These figures represent 3·6 per cent. of the total number of workers, and are but little in excess of those for the same colonies in 1891, when the total was 50,319, consisting of 43,497 males and 6,822 females, the proportion of the total number of workers being 4·3 per cent. Although the number of unemployed in 1901, as stated above, was 50,644, it must not be considered that all these persons were without employment, as a fairly large proportion of them consisted of workers temporarily incapacitated through sickness or accident.

## VALUE OF PRODUCTION FROM ALL INDUSTRIES.

Under the various chapters devoted to the discussion of agriculture, dairying, grazing, mining, &c., particulars regarding the value of the production of the great primary industries have been given at some length; combining the results there shown with the value of manufactures, the total value of production during the year 1903 was £147,748,000, of which amount the total of each state and the value per inhabitant were as follow:—

State.	Value of Production.	Value per Inhabitant.
	£	£ s. d.
New South Wales .....	40,704,000	28 12 2
Victoria .....	31,228,000	25 16 6
Queensland .....	14,611,000	28 3 9
South Australia .....	10,604,000	28 16 9
Western Australia.....	15,497,000	70 0 8
Tasmania .....	5,028,000	28 6 5
Commonwealth .....	117,672,000	30 0 10
New Zealand .....	30,076,000	36 13 4
Australasia .....	147,748,000	31 3 10

The distribution of the production of the states under the various branches of primary and other productive industries was as follows:—

State.	Agriculture.	Pastoral Industries.	Dairying, Poultry, and Bee Farming.	Mining Industries.	Forestry and Fisheries.	Manu- factories and Mechanical Industries.
	£	£	£	£	£	£
New South Wales....	8,359,000	12,777,000	3,276,000	5,913,000	779,000	9,000,000
Victoria .....	10,156,000	4,410,000	3,644,000	3,331,000	269,000	9,368,000
Queensland.....	2,069,000	4,439,000	969,000	2,096,000	777,000	2,631,000
South Australia .....	4,090,000	2,230,000	892,000	584,000	139,000	2,729,000
Western Australia ...	923,000	1,206,000	442,000	8,972,000	1,060,000	2,674,000
Tasmania .....	1,265,000	558,000	451,000	1,303,000	175,000	1,276,000
Commonwealth...	26,792,000	25,630,000	9,674,000	23,639,000	3,219,000	23,623,000
New Zealand .....	7,296,000	7,577,000	3,191,000	*3,531,000	1,062,000	7,429,000
Australasia.....	34,068,000	33,197,000	12,865,000	27,370,000	4,301,000	36,967,000

\* Including value of production of Kauri gum.

In the following statement the total value of production in each state in 1903 is compared with that of each decennial period since 1871. In 1901 the value per head was £31 4s. 3d., being greater than in 1891, and nearly equal to that of 1881, although the year could not be called a favourable one to Australia. In 1902 the value per head was only £30 0s. 5d., a decrease of £1 3s. 10d., but that year was one of the most disastrous ever experienced, especially as regards the primary producing industries. The value for the year 1903 rose to £31 3s. 10d., and the advance affords valuable evidence of the wonderful recuperative powers of the country. If the prices of 1870-4, shown on page 910, had been maintained, the following would have been the value of production in the years indicated; for purposes of comparison the actual results are also quoted:—

Year.	Average value of Production per Inhabitant.	Average value of Production if 1870-4 prices had been obtained in each year.
	£ s. d.	£ s. d.
1871.....	29 3 8	29 3 8
1881.....	31 9 10	35 2 2
1891.....	30 13 5	44 10 4
1901.....	31 4 3	47 7 3
1903.....	31 3 10	41 17 4

During the interval of eleven years between 1891 and 1902 the sheep depastured in Australasia declined in number from 124 millions to 74 millions, the decrease in 1902 alone numbering 18,000,000, while there was also a large decline in other classes of stock. The total value of production for each of the years named was as follows:—

State.	1871.	1881.	1891.	1901.	1903.
	£	£	£	£	£
New South Wales ...	15,379,000	25,180,000	36,739,760	38,954,000	40,704,000
Victoria.....	19,280,000	22,750,000	30,319,610	30,807,000	31,228,000
Queensland .....	3,995,000	10,200,000	14,273,660	16,933,000	14,611,000
South Australia .....	5,228,000	8,457,000	9,025,675	10,314,000	10,604,000
Western Australia ...	707,000	943,000	1,806,340	12,544,000	15,497,000
Tasmania .....	2,131,000	3,586,000	3,920,940	5,033,000	5,028,000
Commonwealth..	46,700,000	71,116,000	96,085,985	114,585,600	117,672,000
New Zealand .....	9,739,000	16,490,000	21,518,915	28,452,000	30,076,000
Australasia .....	56,439,000	87,606,000	117,604,900	143,037,000	147,748,000

The results per inhabitant for the same years were as follow :—

State.	1871.	1881.	1891.	1901.	1908.
	£ s. d.	£ s. d.	£ s. d.	£ s. d.	£ s. d.
New South Wales.....	30 5 3	32 18 3	32 3 5	28 7 9	28 12 2
Victoria .....	28 2 8	28 3 6	28 9 3	25 12 2	25 16 6
Queensland.....	33 3 10	45 0 7	35 19 11	33 11 5	28 3 9
South Australia.....	28 7 7	29 19 11	28 1 1	28 8 2	28 16 9
Western Australia .....	28 0 9	31 19 0	36 5 8	66 17 11	70 0 8
Tasmania .....	21 0 10	30 16 6	26 8 9	28 19 10	28 6 5
Commonwealth .....	27 17 2	31 1 3	29 19 9	30 2 6	30 0 10
New Zealand .....	37 15 10	33 9 8	34 3 1	36 10 4	36 13 4
Australasia.....	29 3 8	31 9 10	30 13 5	31 4 3	31 3 10

Taking the figures for the ten year periods from 1871 to 1901 it will be seen that the value of production per head of population increased in all the states of the Commonwealth with the exception of Victoria and New South Wales, while the decrease in those states was more than counterbalanced by the increased production in the other states, so that the net total for the Commonwealth showed an increase. For the period of ten years, 1891-1901, South Australia, Western Australia, Tasmania, and New Zealand show increases, but the average for Australasia also increased slightly, and this must be regarded as satisfactory when it is considered that the year 1901 was by no means a favourable one as regards the pastoral and agricultural industries.

Compared with the older countries of the world, the amounts stated in the table given above are by no means insignificant, and in production per head Australasia exceeds any other country for which records are available. Although the data on which an exact statement can be founded are incomplete, there is sufficient information to warrant the assertion that from primary industries alone, in an ordinary year, Australasia produces more per inhabitant than is produced from the combined industries of any other country, and a consideration of this fact will, perhaps, explain the ease with which these states bear their apparently great indebtedness, and the general prosperity they enjoyed until the disturbances incident to the banking crisis unsettled general business. The following figures, giving the value of production from primary industries in the principal

countries of the world, are, with the exception of those for the Commonwealth of Australia and New Zealand, which refer to the year 1903, taken from Mulhall's *Dictionary of Statistics* :—

Country.	Total Production in Primary Industries.	Per head of Population.		
		£	s.	d.
United Kingdom .....	317,000,000	7	18	6
France .....	451,000,000	11	11	6
Germany .....	465,000,000	8	13	4
Russia .....	594,000,000	4	19	8
Austria .....	347,000,000	8	7	11
Italy .....	212,000,000	6	17	1
Spain .....	143,000,000	8	4	3
Portugal .....	28,000,000	5	10	2
Sweden .....	50,000,000	10	1	11
Norway .....	15,000,000	7	6	2
Denmark .....	36,000,000	10	4	0
Holland .....	37,000,000	7	17	5
Belgium .....	55,000,000	8	16	6
Switzerland .....	21,000,000	7	2	1
United States .....	1,037,000,000	14	14	0
Canada .....	83,000,000	16	5	6
Commonwealth of Australia .....	89,144,000	22	15	2
New Zealand .....	22,647,000	27	12	3
Australasia .....	111,791,000	23	12	0

Judged by the aggregate production, New South Wales stands above the other Commonwealth states, a position which it owes to the largeness of its pastoral interests. The value of the return from the pastoral industry was £12,777,000, a sum almost equal to the combined total of all the other Commonwealth states. In value of primary production per inhabitant, Western Australia stands easily first with the very high production of £57 Os. 11d. per head. New Zealand comes next, followed by New South Wales. The high position occupied by Western Australia is due to its great production of gold, and to its large timber industries.

A comparison of the production of the states from primary industries per head of population, however, is liable to give an undue importance to those which have large territories and scanty population; for it is but a natural expectation that where the population of a country is dense a large proportion of the inhabitants will be engaged in other than primary industries. If the value of primary production, therefore, be compared with the extent of territory enjoyed by each state, it will be found that the positions of several of the provinces are reversed. Thus, of the Commonwealth states, Victoria occupies first position with an average primary production of £248 14s. 9d. per square mile, while

Western Australia has the second lowest return with £12 18s. 8d. The following, as well as the preceding table, bears testimony to the great natural resources of New Zealand, which has an average production per head of £27 12s. 3d., and per square mile of £216 15s. 7d. :—

State.	Production of Primary Industries per square mile.
	£ s. d.
New South Wales .....	100 2 2
Victoria .....	248 14 9
Queensland.....	17 16 11
South Australia.....	8 14 3
Western Australia .....	12 18 8
Tasmania .....	143 2 6
Commonwealth.....	29 19 9
New Zealand.....	216 15 7
Australasia.....	36 6 6


If the value of production in all the industries be related to the area of territory possessed by each state, which is a favourite comparison with some statisticians, the following results are obtained. There is, however, no necessary connection between the production of the manufacturing industries of a country and the area of its territory, the development of manufactures depending upon entirely different considerations :—

State.	Total production per square mile.
	£ s. d.
New South Wales .....	131 0 2
Victoria .....	355 6 8
Queensland .....	21 17 1
South Australia .....	11 14 8
Western Australia .....	15 17 7
Tasmania .....	191 14 0
Commonwealth .....	39 11 8
New Zealand ..	287 17 9
Australasia .....	48 0 3



The question is often asked, as to the relation between production of a country and the amount of its domestic exports. In the year 1903, the production of the Commonwealth, as shown in the foregoing tables, was valued at £117,672,000, and during the same period, goods of local production were exported, to the value of £45,578,935. These latter, however, are valued at the points of export, whereas in the case of the former the value is taken as at the point of production. Reducing the exports of domestic produce by 10 per cent., so as to bring them also to the value at the point of production, the figure works out at £41,021,000, and represents 35 per cent. of the total production.

In New Zealand, the export of domestic produce was £14,838,192. Reducing this by 10 per cent., to arrive at the value at the point of production, the net value is £13,354,000, whereas the total production was £30,076,000. The export, therefore, was equivalent to 44.4 per cent. of the total production. Both in the case of New Zealand and in that of the Commonwealth, the proportion of production exported was extremely large. No very recent figures can be given of the proportion of exports compared with production in other countries. Such statistics as are available point to an export of about 11 per cent. in the United States, and 20 per cent. in the United Kingdom.



## INDEX.

- Ability Tax, Tasmania, 682  
 Aboriginal Half-castes, 166  
 Aborigines, Statistics of, 170  
 Absentee Incomes, 531  
 Accident, Deaths from, 188-9, 206  
 Accidents, 833  
     On Railways, 582  
 Accumulation, 781  
 Acquisition of Property for Public Pur-  
     poses Bill, 80  
 Adelaide, 474, 486, 487  
     Population of, 155-6  
     Rainfall, 57  
     Port, 31, 33  
         Population of, 156  
         Shipping, 223-4  
 Adults, Proportion of, in population, 159  
 Advances to Settlers, Farmers, &c.,  
     396-399  
 "Adventure," Visit to New Zealand, 64  
     Voyage of Discovery, 67  
 Aerated Water Factories, 982  
 Africa, Density of Population, 151  
 Africans, Right of Naturalisation refused  
     to, 175  
 Agate, 955  
 Age Constitution of Female Popula-  
     tion, 160  
 Ages at Death, 184  
     Of the People of Australasia, 157  
 Agricultural Bank Act, Queensland, 398  
     Western Australia, 398  
 Agricultural Colleges and Farms, 394  
     Exports, 244  
     Imports, 232  
     Implements (imports), 235  
     Implement Works, 980  
     Products, Factories Treating, 975  
 Agriculture (1872-1893), 476  
     Advances to Settlers, 396-400  
     Area under Crop in each State, 456  
     Education in, 394  
     Effect of Gold Discoveries on, 456  
     Export Depôts, 396  
     In Australasia, 345  
     Persons employed in, Statistics *re*,  
         404  
 Agriculture—State Advances to  
     Farmers, 396  
     State of, in 1862, 471  
     Water Conservation, 400  
 Albany, 26, 36, 39  
     Population of, 156  
     Shipping, 223-4  
 Albury, 15, 22  
     Capital Site, 83  
     Population of, 156  
 Alcohol, Exports, 243  
     Imports, 231  
 Aliens (coloured), Exclusion of, 172  
     Excluded from Franchise, 85  
     In Australasia, Statistics of, 171  
     Number in Australian States at  
         30th June, 1904, 86  
     Restriction of Immigration of, 79, 80  
 Alum, 953  
 Alunite, 954  
 America, Density of Population, 151  
     Mail Service, 738, 745  
 American Vessels Trading to Austra-  
     lasia, 218  
 Amethyst, 955, 956  
 Ammunition, Exports, 253  
     Imports, 241  
 Amygdalina, Eucalyptus, 23  
 Angora Goats, Breeding of, 419  
 Anthracite, 951  
 Antimony, 939  
 Apatite, 955  
 Apoplexy, Deaths from, 203  
 Apples, Cultivation of, 389  
 Arbitration Bill, 80, 91, 92  
     Legislation, 492  
 Area of Australasian Colonies, 1  
 Argentine Republic, Meat Export  
     Trade, 432  
 Armidale, Capital Site, 83  
     Climate, 55  
 Arms, Manufacture of, 988  
 Arnheim Land, Discovery of, 61, 31  
 "Arnheim" Yacht, Voyage of Dis-  
     covery, 61  
 Arrowroot Growing, Wide Bay Dis-  
     trict, 29

- Arsenic, 943
- Artesian Bores, Warrego District, 29
- Artesian Water, 35
  - Discovered 1879, 400
  - Source of, 5
  - Wells Sunk, 401
- Art Galleries, 831
- Articles of Common Use, Price Levels of, 908
- Artillery Forces, 535
- Asbestos, 955
- Asia, Density of Population, 151
- Asiatics, Right to Naturalisation Refused to, 175
- Assurance (Life), 814
  - Companies, Assets and Liabilities, 819
  - Expenses of Management, 820
  - Industrial, 822
  - In Various Countries, 821
- Asylums for the Destitute, 834
- Auckland, 46, 47, 155
  - Population of, 156
  - Rainfall, 59
  - Shipping, 223-4
- Audit Act, Commonwealth, 81
- Australia del Espirito Santo, De Quiros, 60
- Australian Alps, 3, 15, 21
  - Commonwealth Horse, Boer War, 84
- Austria, Natives of, in Australasia, 166
- Bacon, Production of, 438
  - Curing Works, 982
  - Prices of, 906
- Ballarat, Climate, 56
  - Population of, 156
- Ballast, Shipping in, 217
- Bananas, Cultivation of, 392
- Bank Clearing Houses, 798
  - Crisis of 1893, 482, 483
- Banking, 781
  - Bill, Commonwealth, 92
  - Business of each State, 794
  - Expenses of, 796
  - Facilities, Expansion of, 484
- Bank Notes, 807, 811
- Bankruptcies, 828
- Banks, Capital Resources of, 781
  - Deposits, Total, 805
  - Dividends, 793
  - Earnings compared with Resources, 797
  - Liabilities and Assets of, 783
  - Reserves—Metallic, 785
  - Results of Working of, 793
  - Savings Banks, 801
- Banks, Sir Joseph, 63
- Baptist Church, 834
- Bark Mills, 975
- Barley, Acreage under Crop, 366
  - Imports and Exports, 368
  - Production of, 346, 367
  - Value of Crop, 368
  - Yield per acre, 367
- Barton, Sir E., Appointed High Court Judge, 89
  - Prime Minister and Minister for External Affairs, Commonwealth, 76
  - Resignation of Premiership, 88
- Barwon River, Navigation of, 460
- Basket Factories, 995
- Bass, Discovery of Bass Strait, 68
- Bateman's Bay, Description of, 8
- Bathurst, Climate, 56
  - Population of, 156
- Bay of Inlets, Discovery of, 66
  - of Islands, French visit in 1772, 67
- Beaconsfield, Population of, 156
- Bedding Factories, 991
- Beef, Price of, 903
  - Price of, before the Discovery of Gold, 446
- Bee-keeping Industry, 439
- Beer Excise Bill, 81
- Beer Exports, 243
  - Imports, 231
  - Prices of, 906
  - Quantity made, 984
- Beeswax, Production of, 439
- Beetroot, Cultivation for Sugar Production, 335
- Bega, Labour Settlement, 298
- Belgium, Shipping Trade of Australia with, 215
  - Trade with, 265
- Bendigo, Climate, 56
  - Population of, 156
- Benevolent Societies, 834
- "Betterment" Principle applied in Victoria, 308
- Bicycle Exports, 253
  - Imports, 240
- Billiard Table Factories, 991
- Birthplaces of the Population, 165, 166
- Birth-rate, Decline in, 161, 178
  - Effect on Death Rate, 181-2
  - Lower than that of most European Countries, 182
  - Of Australasia and Foreign Countries, compared, 177
  - Per 100 Married Women, 179
  - Royal Commission re, 179
- Births, Excess over Deaths, 150
  - In Australasia, 177

- Births, Legitimate, 179  
     Illegitimate, 183  
 Bischoff Mount, Tin Mine, 476  
 Biscuit Factories, 982  
 Bismuth, 940  
 Bitumen, 953  
 Blacking Factories, 991  
 Black Labour, Abolition of, 79  
     On Sugar Plantations, 380  
 Blacksmith's Wages before Gold Discoveries, 445  
 Blankets, Manufactures of, 987  
 Blaxland crossed Blue Mountains (1813), 10  
 Blue Factories, 991  
 Blue Mountains crossed by Wentworth, Blaxland and Lawson (1813), 10  
 Blue Mountain Scenery, 10  
 Bluff Harbour—Shipping, 223  
 Boards (Local) in the various States, 773  
 Boat-building Works, 990  
 Boer War (see South African War)  
 Boiling-down Works, 431, 974  
 Boiling Springs—New Zealand, 48  
 Bombala chosen as site for Capital by Senate, 83, 89  
 Bone Mills, 974  
 Bonus on Cotton Growing in Queensland, 394  
 Bonuses on Fruit Cultivation, 392  
     Sugar Cultivation by White Labour, 380  
 Boot Factories, 985  
 Boots—Exports, 252  
     Imports, 239  
 Boronia—King George's Sound, 36  
 Boroughs—New Zealand, 771  
 Borrowing Boom, 478-9  
 Borrowings of Municipalities, 519-521  
     the State, 519  
 Botanic Gardens, 831  
 Botany Bay—Discovery by Cook, 65  
     First British Expedition to, 68  
 Boulder, Population of, 156  
 Bounty on Sugar produced by White Labour, 380  
 Bourke, Climate, 56  
 Bowen, Sir George, 137  
 Braddon—Sir E., death of, 91  
 Box-making Industry, 978  
 Braddon Clause—"Braddon Blot," 91  
 Brandy Production, 376  
 Brass Works, 980  
 Bread, Prices of, 903  
     Price of before Discovery of Gold 446  
 Breadwinners, Number of, 1005  
 Breweries, 982, 984  
 Brick Works, 977  
 Bridge Boards (Queensland), 776  
 Brisbane, 486, 487  
     Population of, 155-6  
     Rainfall, 57  
     Shipping Returns, 223-4  
     Temperature, 57  
 British Australasia, Area of, 1  
     Cotton Growing Association of Manchester, 393  
     Empire, Area of, 1  
     Possessions, Natives of, in Australasia, 166  
     Shipping Trade of Australasia with, 215  
     Vessels trading to Australasia, 218  
 Broken Bay, Discovery of, 66  
 Broken Hill, Population of, 156  
     Railway Traffic, 609  
     Silver Mines, 925  
 Bronze Specie—Exports, 255  
     Imports, 242  
 Brookite, 942  
 Broom Factories, 995  
 Brown Coal, 944  
 Brush Factories, 995  
 Building Trades—Effect of 1893 Crisis 491  
 Bulli, Coal Seams, 11  
 Bullion, Exports, 252, 255  
     Imports, 242  
     Issued by the Mints, 808  
 Bunbury, Shipping, 223  
 Bundaberg, Population of, 156  
 Burra Burra Copper Mine, 444  
 Burrangong Gold-field, 470  
 Burrum River, Coal Deposits, 29  
 Bustard Bay, Discovery of, 66  
 Bushrangers, 475  
 Butter, Argentine production, 437  
     Consumption of Australian States, 436  
     Production, 433  
     European Consumption, 436  
     Exported to the United Kingdom, 436  
     Factories, 982  
     Imports and Exports, 232, 244, 434  
     Prices of, 903  
 Cabinet-making Establishments, 991  
 Cable (Submarine) Services, 750  
     New Zealand to Australia, 49  
 Cadell, Captain, Navigation of the Murray, 460  
 Cadet Corps, 537  
 Cairngorm, 956  
 Cairns, Shipping, 223  
 California Diggings, Emigration to, 447

- Camels, Use of, 420
- Canada, Natives of in Australasia, 166
  - Shipping Trade of Australia with, 215
  - Trade with, 263
- Canadian-Australian Royal Mail Line, 745
- Cancer, Death Rate from, 199, 201
- Candle and Soap Works, 448, 976
- Capital Employed in Manufactures, 99
  - Importation of, 519
  - Effects Discussed, 481
  - (Private), Imported for Investment, 479
  - Introduced to Australasia, 523
  - Movement of, 522
- Capital Punishment, 122
- Prerogative of Mercy, 119
- Cape Colony, Gold Exported to, 282
- Shipping Trade of Australia with, 215
  - Trade with, 263
- Capital Site Bill, 92
  - Question, 89
- Carpentaria, Gulf of, Discovery, 51
- Carriage Building Works (Railway), 980
- Case-making Industry, 978
- Castlemaine, Population of, 156
- Catgut Works, 974
- Cats' Eyes (Gemstone), 957
- Cattle Production, Value of, 423
  - Statistics of, 406, 414
- Causes of Death, 188
- Cement, Exports, 250
  - Imports, 237
  - Manufacturing, 954, 977
  - Works, 977
- Census (Commonwealth), Argument in favour of, 87
- Centennial Park, 831
  - Lands, 697
  - Swearing-in of First Federal Ministry, 77
- Central Australia, once covered by the Sea, 9
- Centralisation of Population, 154
- Ceylon, Gold Exported to, 282
  - Natives of, in Australasia, 166
  - Trade with, 263
- Chaff and Hay, Imports and Exports, 373
- Chaff-cutting Works, 975
- Chair-making Factories, 991
- Chalcedony, 957
- Charitable Institutions, 833
- Charities, Public, 832
- Charters Towers Gold-field, 29
  - Population of, 156
- Chatham Islands, Remnant of Morioris, 171
- Cheese Factories, 962
  - Imports and Exports, 434
  - Prices of, 903
  - Value of Production, 433
- Chemicals, Exports, 250
  - Imports of, 238
- Chemical Works, 991
- Childbearing, Deaths from Diseases of, 188-9
- Childbirth, Deaths in, 204
- Children, Destitute, Care of, 834
  - Number of, to a Marriage, 209
- Chili, Shipping Trade of Australia with, 215
- Chilling Works, 431
- China, Naval Contingent sent to, 539
  - Shipping Trade of Australia with, 215
  - Trade with, 265
- Chinese, Agitation Against Admission of, 470
  - Cabinet-making, Regulation of, 493
  - Empire, Natives of, in Australasia, 166
  - in Australasia, Statistics of, 172
  - knowledge of Australia in 13th Century, 60
  - Laundries—Regulation of, 492
  - Market Gardeners, 393
  - on Steamers, Wages of, 227
  - Prohibitive Laws against Influx of, 173
- Cholera, Death Rate of, 197
- Christchurch, Population of, 156
- Chrome Iron, 943
- Chrysoberyls, 957
- Chrysolite, 956
- Church of England, 881
- Cigar Factories, 982
- Cinnabar, 942
- Cingalese in Australasia, Statistics of, 172
- Circulatory System, Deaths from Diseases of, 188-9, 203
- Cities and Ports, Shipping Trade compared, 223-4
- Cities, Comparison of, 772
  - Growth of, 154
  - Population of, 156
- Citrus Fruit, Cultivation of, 390
- Clearing Houses, 798
- Clifton Coal Seams, 11
- Climate of Australia, 2, 54
- Clock-making Works, 992
- Cloncurry, Gold and Copper, 29
- Closer Settlement in Victoria, 313
  - in New Zealand, 341
- Clothing, Export, 246
  - Imports, 234

- Clothing Factories, 985  
     Increase of Employment of Women, 964  
 Coach Building Works, 989  
 Coal, 944  
     Burrum River, 29  
     Converted into Coke by Volcanic action, Illawarra District, 3  
     Exports and Imports, 241, 254  
     Export Trade, 914  
     Field, Hunter River Valley, 13  
     Leichhardt district, 29  
     Miners of Australia—  
         Nationality of, 950  
         Number of, 958  
     Mines, number of men employed, 950  
     Mining, cost of, 946, 951  
         Industry, 1863-72, 465  
         1872-1893, 476  
     Price of, 951  
     Progress of the Production of, 459  
     New Zealand, 52  
     Seams in Illawarra Range, 3, 11  
 Coast Line of Australia, Length of, 2  
 Cobalt, 943  
 Coffee Growing in Australia, 394  
     Mills, 982  
     Prices of, 906  
 Coinage, 807  
     Decimal System, 88  
     Select Committee on, 88  
 Coke, Natural, Illawarra District, 3  
     Works, 993  
 Colonial Hereditary Nobility—Proposal to create, 69  
 Coloured Races in Australasia—Statistics of, 171  
 Commerce of Australasia, 228  
 Commercial Class, The, 1012  
 Commissioners appointed to rearrange Electorates for each State, 85  
 Commodities, Prices of, 902  
 Commonwealth of Australia, Account of, 69  
     Account of Movements which led to formation of, 69  
 Companies, Investment, 800  
     Tax, Western Australia, 679  
 Conciliation and Arbitration Bill, 80  
     Legislation, 492  
 Condensed Milk Factories, 982  
 Condiment Factories, 982  
 Confectionery Works, 982  
 Confinements, Deaths in, 205  
 Congregational Church, 884  
 Conjugal Condition of Population of Australasia, 163  
 Constitution Act, Commonwealth, 93  
 Constitutional Diseases, Deaths from, 188-9  
     Death Rate, 199  
 Constitution of the Commonwealth, Framing of, 70, 71  
     of New South Wales, 117  
 Contract Labour, Exclusion of 172  
     Importation of, 87  
 Convictions, 553  
 Convulsions, Deaths from, 203  
 Cook, Captain James, Voyages of Discovery, 11, 63, 67  
 Cooktown, Shipping, 233  
 Coolgardie, Population of, 156  
 Co-operative Settlement in Queensland, 319  
 Coopering Industry, 978  
 Coorongite, 953  
 Copper, Discovered in 1844, 444  
     Exports, 254  
     Miners, Number of, 958  
     Mining Industry, 465  
         in 1850, 449  
         1872-1893, 476  
     Mining, 929  
     Works, 980  
 Cordial Works, 982  
 Cork Cutting Works, 978  
 Corn Crushing Works, 975  
 Carnelian, 957  
 Corn-Flour Works, 982  
 Corowa Federation Conference, 1893, 71  
 Cost of Living, 889  
 Cotton Growing, Bonus on, 394  
     Wide Bay District, 29  
     Suitability of Australia for Growing, 393  
 Credit Foncier System, 396  
 Crime, 544  
 Crisis of 1893, Effect of, 483, 484, 488  
 Croup, Deaths from, 195  
 Crozet, Lieutenant, Voyage of Discovery, 67  
 Cultivated Area in each State, 456  
     of Australasia, 348  
 Cunningham, Explorations by, 457  
 Currants, Cultivation of, 390  
 Currency, 807  
     Paper, 811  
 Customs Act, Validity Impugned, 87  
 Customs Administration of Australia taken over by Commonwealth, 77  
     transferred to Commonwealth, 635  
     and Excise before Federation, 648-9  
     Commonwealth, 644  
 Customs Bill, 80, 81

- Customs Department undertakes compilation of Returns, Immigration and Emigration, 86  
 Duties, Average Rate of, 283  
 Bill, Commonwealth, 79  
 Revenue, 285  
 Cutlery Works, 980  
 Cycle Works, 989  
 "Cygnets," Visit to Australia, 1688, 62
- Dairy and Pastoral Production, Combined Value, 440  
 Cows, Number of, 433  
 Farming in Australasia, 433  
 Industry of Australasia, 406  
 Products, Value of, 433  
 Dairying, Persons engaged in, 441  
 Dalgety chosen as Site for Federal Capital, 83, 89  
 Dalrymple, Exploration by, 460  
 Dampier, William, Discoveries of, 63  
 Darling River, Description of, 4  
 Early Navigation of, 460  
 Darwin, Port, Description of, 32  
 Shipping, 223  
 Death, Ages at, 184  
 Causes of, 188  
 Deaths, 180  
 during 1903, with ages, 185  
 in Age Groups, 185  
 Death Rate and Birth Rate, 180, 181-2  
 lower than in Europe, 180  
 of Australasia and Foreign Countries compared, 182  
 of Legitimates and Illegitimates, 187  
 steadily declining, 180  
 Debt, Public (*See also* Loans).  
 Growth of, 700  
 Interest on, 703  
 Quotations of Stock, 710  
 Redemption of, 704  
 Sinking Funds, 705  
 Debts of the States, Question of the Commonwealth taking over, 657  
 Decimal System of Coinage, 88  
 Defence, 535  
 Defence Act, 89  
 Defence Administration transferred to Commonwealth, 635  
 Bill, 80  
 Cost of, 542  
 Naval, 539  
 Denmark, Natives of, in Australasia, 166  
 Denominations, Religious, 887  
 Density of Population, 151
- Dependents, Number of, 1005  
 Proportion of in, Population, 159, 160-1  
 Depression in 1842, 444  
 in 1893, 479, 483, 484, 488  
 De Quiros, Search for Terra Australia, 60  
 Destitute Asylums, 834  
 Developmental Diseases, Deaths from, 188-9  
 Death-rate, 202  
 Devonport, Shipping, 223  
 De Witt, Voyage of Discovery, 61  
 Diamonds, 956  
 Diarrhœa, 197  
 Dietetic Diseases, Deaths from, 188-9  
 Death-rate, 199  
 Digestive System, Deaths from Diseases of, 188-9  
 Diphtheria—Statistics and Death Rate, 190, 195  
 Dirk Hartog, Discoveries of, 61  
 Diseases, Deaths from, 188-9  
 Discovery of Australia and New Zealand, 60  
 Distilleries, 982  
 District Council, South Australia, 706  
 Dividend Tax, Queensland, 676  
 Western Australia, 679  
 Divorce, 844  
 Docks, 990  
 Domestic Class, The, 1014  
 Dookie Agricultural College, 394  
 Drainage Boards, New Zealand, 777  
 Dressmaking Factories, 985  
 Drowning, Deaths from, 207  
 Drug Factories, 991  
 Drugs, Exports, 250  
 Import of, 238  
 Ductless Glands, Deaths from Diseases of, 188-9  
 Dunedin, Population of, 156  
 Rainfall, 59  
 Shipping, 223  
 Dutch Discoveries in Australian Waters, 61, 63  
 Duties, Cost of Collection of, 286  
 Customs and Excise, Amount of, 285  
 Duty on Imports, Average of, 283  
 "Duyfken," Voyage of Discovery, 61  
 Dye Works, 985  
 Dysentery, Death Rate, 197
- Eaglehawk, Population of, 156  
 Early Closing of Shops Legislation, 495  
 Eastern Extension Telegraph Company, Cable Service, 750



- Echuca, Rainfall, 56**  
**Education, 855**  
     Diffusion of, 871  
     Primary, Cost of, 864  
     Secondary, 867  
     Technical, 874  
     University, 872  
**Edwards River, Navigation of, 460**  
**Eggs, Prices of, 906**  
     Production of, 439  
**Elastic Bitumen, 953**  
**Elaterite, 953**  
**Elections, First Federal, 77, 78**  
     Legislation re Commonwealth, 80  
     Senatorial, 1903, 87  
**Electoral Bill, 92**  
**Electorates, Commonwealth, Redistri-**  
     **bution of, 85-87**  
**Electric Apparatus Works, 993**  
**Electro-plating Works, 992**  
**Emeralds, 956**  
**Emigration, Excess over Immigration,**  
     **153**  
     Returns, 86  
         to California Diggings, 447  
**Employment and Production, 1004**  
**"Endeavour" H.M.S., Voyage of Dis-**  
     **covery, 24, 63**  
**Endeavour River, Discovery of, 66**  
**Engineering Works, 990**  
**England and Wales, Natives of, in**  
     **Australasia, 166-8**  
     Typhoid Death-rate, 199  
**Engraving Works, 987**  
**Enrolment at State Schools, 863**  
**Enteric Fever, Death-rate, 198**  
**Enumeration of the Population (See**  
     **Census), 87**  
**Epsomite, 953**  
**Epsom Salts, 953**  
**Europe, natives of, in Australasia, 166**  
**Exchanges, 798**  
**Excise Bill, 81**  
**Excise Duties Bill, Commonwealth, 79**  
**Excise Revenue, 285**  
**Executions, 188-9, 554**  
**Expenditure, adjusted, 695**  
     by the Government and Local  
         bodies, 735  
     from Loans, 729  
     heads of, 692  
     of the Commonwealth, 636  
     of the States, 662  
     on Living, 899  
**Explosives, Manufacture of, 988**  
**Exports from Australasia, 228, 243**  
     of Domestic Produce, 277  
         Relation of, to Production, 1023  
**Exports, Price Levels of, 909**  
**External Shipping, 214**  
**Factories, 961**  
     Agricultural Products, 975  
     Books, Paper, and Printing, 987  
     Clothing and Textiles, 985  
     Drugs and Chemicals, 991  
     Food and Drink, 982  
     Furniture and Bedding, 990  
     Metals, 979  
     Oils and Fats, 976  
     Pastoral Products, 974  
     Vehicles, Saddlery and Harness, 989  
     Wages paid in, 1001  
     Wood working, 978  
**Factory Hands, Male and Female,**  
     Number employed in each in-  
         dustry, 972  
     Legislation, 492  
**Farmers, State Assistance to, 396**  
**Farm Labourers' Wages, before Dis-**  
     **covery of Gold, 445**  
**Fats and Oil Factories, 976**  
**Febrile Diseases, Deaths from, 188-9**  
**Fecundity of Marriages, 209**  
**Federal Conference, 70**  
     Convention (1891), 70  
         1897, 72  
     Council formed, 69  
     Court (see High Court), 87  
     Elections Bill, 80  
     Electorates. (See Commonwealth)  
     Franchise Bill, 80  
**Federation Bill of 1891, 71**  
     of 1898, 72  
     Effect of, on State Finance, 652  
**Fellmongering Works, 974**  
**Female Factory Workers, Wages of, 1003**  
     Labour in Factories, 963  
     Population, Age Constitution of, 160  
     Number employed in various Indus-  
         tries, 1007  
     Unmarried, 165  
**Fertiliser Factories, 991**  
**Fertility of Marriages, 208**  
**Fiji, Shipping Trade, 215**  
     Trade with, 263  
**Finance, 519**  
     Commonwealth, 635  
**Finances of the States, 660**  
**Finance, State, Effect of Federation on,**  
     **652**  
**Financial Crisis of 1842, 444**  
**Fiords, New Zealand, 49**  
**Fire Brigades, New South Wales, 774**  
     Victoria, 776

- Fireclay, 955
- Fisheries of Australia, 1010
- Fish Preserving Works, 982
- Flax Mills, 995
- Flock Factories, 991
- Floods of 1863, 466
  - of 1865, 466
  - of 1867, 466
  - of 1870, 466
- Flour Mills, 982
- Flour, Price of, before the Discovery of Gold, 446
  - Quantity made, 984
  - Trade, 1850, 449
- Fodder, Compressed, 265
- Food, Expenditure on, 899
  - Imports, 232, 244
  - Prices of, before Discovery of Gold, 446
  - Prices of, in 1860-62, 464
  - 1859-1871, 472-4
  - Supply, 889
- Forage, Green, Production of, 373
- Foundries, 980
- France, Natives of in Australasia, 166
  - Trade with, 265
- Free Selection before Survey, 288, 462
- Freezing Works, 431
- Fremantle, Population of, 156
  - Shipping, 223-4
- Friendly Societies, 824
- Frozen Meat (See Meat.)
- Fruit Canning Works, 982
- Fruit Cultivation, production, area under crops, imports and exports, &c., 389
  - Drying, 390
  - Exports of, 244
  - Imports of, 232
  - Pests, 389
  - Production, 1903, 346
  - Pulp, Import and Export Trade, 391
- Furniture Exports, 250
  - Imports, 238
  - Factories, 991
- Furriers, 985
- Galvanised Iron Works, 980
- Gambier District—volcanic crater lakes, 3
- Garnet, 956
- Gas Works, 993
- Gatton Agricultural College, 395
- Gems, 956
- Geological Age of Australia, 4
- German Empire, Natives of in Australasia, 166
- German Land Credit Banks, 396
- Germany protest against Commonwealth Customs Administration, 84
- Shipping Trade of Australia with, 215
  - Trade with, 215
- Geysers, New Zealand, 48
- Glacial Action—signs of Australian Continent, 3
- Glaciers, New Zealand, 49-50
- Glass Works, 977
- Glue Factories, 976
- Goats, Angora, Breeding of, 419
- Gold, Discovery of, 151, 213, 443, 449
  - Discovery (1851) Effect of, 447
  - Effect on Agriculture, 456
  - Pastoral Industry, 458
  - Wages, 451
- Industrial revolution effected by, 450
  - In Queensland, 475
  - Western Australia, 39
  - Enoggera Ranges, 28
  - Exports, 252, 255
  - Imports, 239, 242
  - Miners, Number of, 958
  - Wages, 451
- Mining, 913
  - Movement of, 282
  - Nuggets, 923
  - Production, 1859, 460
  - 1859-1862, 461
  - 1893 and 1903, 490
  - Received for Coinage, 808
- Gonneville, Sieur de—discoveries of, 60
- Government Savings Banks, 801
- Grain, Exports, 244
  - Imports, 232
- Grapes, Production, 346, 374
- Graphite, 952
- Grass Seed, Dressing Works, 975
  - Production, 1903, 346
  - Production of, 374
- Gregory, A. C., exploration by, 460
- "Gulden Zeepaard," voyage of discovery, 61
- Gypsum, 954
- Habitations, 852
- Half-castes, Statistics of, 170
- Hams, Production of, 438
- Harbour Boards, New Zealand, 777
- Harbours of Australia, 4
- Hares, Frozen, Trade in, 439
- Harness Works, 989
- Hat Factories, 985
  - Number of before Discovery of Gold, 448
- Hatters, The Six, 87

- Hawaiian Islands, Shipping Trade of  
     Australia with, 215  
 Hawkesbury Agricultural College, 394  
     Sand Stone, 954  
 Hay, Acreage under Crop, 371  
     Imports and Exports, 373  
     Production, 1903, 346, 372  
     Yield per Acre, 372  
 Health Boards, Local, Western Aus-  
     tralia, 776  
 Heart Disease, Deaths from, 203  
 "Heemakirk" Voyage of Discovery, 61  
 Hides, Number tanned, 975  
 High Courts, 87  
 High Court Bill, 79, 80, 83  
 Hindoos Employed on Canefields, 390  
     in Australasia, Statistics of, 172  
 Hobart, Population of, 155, 156  
     Rainfall, 58  
     Shipping, 223, 224  
     Temperature, 58  
 Homicide Statistics, 189-9  
 Honey, Production of, 439  
 Hong Kong, Shipping Trade of Aus-  
     tralia with, 215  
     Trade with, 263  
 Hops, Production, 1903, 346  
 Horse Breeding, 417  
 Horses, Indian Demand for, 418  
     South African War Demand, 418  
     Statistics of 406, 417  
     Value of Production of, 423  
 Hosiery Factories, 985  
 Hospitals, 833  
     for the Insane, 833  
 Hot Springs of New Zealand, 48  
 Hume, Explorations by, 457  
 Hunter District, Water and Sewerage  
     Board, 774  
 Hydatids, Death Rate from, 199  
 Hydraulic Power Works, 993  
  
 Iceworks, 982  
 Illegitimacy, 983  
 Illegitimates, High Death Rate, 187  
 Immigration, 151-3  
     Excess over Emigration, 150-4  
     Lecturers sent to England from  
         New South Wales, 468  
 Immigration Restriction Act, 172  
     The Six Hatters Question, 87  
     Aliens, 80-1  
     Returns, 86  
     State-Aided, 149, 153, 446, 474, 485  
 Imperial Conference in London, 84  
 Imports into Australasia, 223, 231  
     of Free and Dutiable Goods, 283  
     Price Levels of, 909  
 Income Tax, New South Wales, 670  
     New Zealand, 685  
     Queensland, 676  
     South Australia, 677  
     Tasmania, 680  
     Victoria, 673  
 Incomes of Absentees, 531  
     Private, 512, 530  
 Index of Mortality, 183  
 India, Natives of in Australasia, 166  
     Shipping Trade of Australasia with,  
         215  
     Trade with, 263  
 Industrial Assurance, 822  
     Class, The, 1010  
     Legislation, 492  
     Progress, Period preceding Gold  
         Discoveries, 1788-1851, 443  
         During 1851-1858, 449  
         1859-1862, 460  
         1863-1872, 464  
         1872-1893, 475  
         1893-1904, 489  
     Recent Industrial Legislation, 492  
     Schools, 832  
     Unions, 492  
 Industries connected with Food and  
     Drink, 982  
     Value of Production from All, 1018  
     Grades of Workers, 1015  
     Classes of Manufactories, 972  
 Infantile Mortality, 186, 190-195  
     Legitimate and Illegitimate, 187  
     Royal Commission, 179  
 Insane, Care of, 833  
 Insanity, 848  
 Insolvencies, 828,  
 Insurance Companies, Assets and Liabi-  
     lities, 819  
     Expenses of Management, 820  
 Insurance in various countries, 821  
     Life, 814  
 Integumentary System, Deaths from  
     diseases of, 188-9  
 Interest on Loans, 703  
     Payment on Loans, 522  
 International Statistical Institute, 183  
 Interstate Commission Bill, 80  
     Shipping, 212  
 Intoxicants, consumption of, 896  
 Investment Companies, 900  
 Ireland, Natives of in Australasia, 166-8  
 Iron, Exports, 248  
     Imports, 235  
 Iron Foundries, Number of before Dis-  
     covery of Gold, 448  
     Mining, 936  
     Works, 980  
 Irrigation, 390, 421

- Irrigation by Artesian Water, 401, 403  
     Trusts, Victoria, 775  
 Italy, Natives of, in Australasia, 166  
     Trade with, 265  
  
 Jam Factories, 982  
 Jansen, Captain Jerriit, Voyage of Discovery, 61  
 Japan, Shipping trade of Australia with, 215  
     Trade with, 265  
 Japanese in Australasia, Statistics of, 172  
     Shipping Subsidies, 222, 259, 269  
 Jarrah Forests of Western Australia, 38  
 Jasper, 955  
 Java, Shipping Trade of Australia with, 215  
     Trade with, 265  
 Jewellery, Manufactories, 992  
 Jewish Community, 884  
 Joinery Works, 978  
 Judiciary Bill, 80, 83, 87  
 Justice, Expenditure on, 556  
 Juvenile Labour, 1017  
  
 Kalgoorlie, Population of, 156  
 Kanakas (see Pacific Islanders)  
 Kangaroo, Early Notice of, 61, 62  
 Kaolin, 955  
 Karri Forests of Western Australia, 38  
 Kauri Gum, 953  
 Kerguelen Island, Commonwealth Action re, 78  
 Kerosene Duty, 83  
     Shale, 952  
     Works, 993  
 King, Discoveries by, 33  
  
 Labour Colonies in Queensland, 319  
     in Victoria, 313  
     Legislation, 492  
     Settlements in New South Wales, 298  
     Troubles preceding crisis in 1903, 483  
     under Contract, exclusion of, 172  
 Lakes and Volcanic Craters, South Australia, 3  
 Lambing Flat Gold-field, anti-Chinese agitation, 471  
 Lamp Works, 993  
 Land Boom, 480  
     Classification Boards, Victoria, 300  
     Laws, 287  
     Privately owned, value of, 512  
  
 Land Revenue derived from Rents and Sales, 600  
 Shafton Bank, 396  
 Settlement, 287  
 Speculation, 443, 480  
 Tax, New South Wales, 670  
     New Zealand, 685  
     South Australia, 677  
     Tasmania, 680  
     Victoria, 673  
 Lapidaries, 993  
 Lard, Production of, 438  
 Lascars, Wages of, 227  
 Launceston, Population of, 156  
     Shipping, 223-4  
 Law, 544  
 Lawson crossed Blue Mountains, 1813, 10  
 Lead, 941  
     Mills, 980  
 Leather Bag Works, 994  
     Belting works, 994  
 Leatherware manufacture, 994  
 Letters, 830  
 "Leeuwin"—Voyage of discovery, 61  
 Le Maire—discoveries of, 62  
 Letters posted, number of, 740  
     Registered, 741  
 Libraries, Public, 879  
 Life Assurance, 814  
 Life Assurance Companies, Assets and Liabilities, 819  
     Expenses of Management, 820  
     Industrial, 822  
     in various countries, 821  
 Lignite, 944  
 Limestone, 954  
 Limestone Caves, Western Australia, 39  
 Lime Works, 977  
 Lithographic Stone, 954  
 Live Stock of Australia, 1009  
 Living, Cost of, 889  
     Before Gold Discoveries, 483  
     1851-8, 483  
     1859-1862, 464  
     1863-1872, 472  
     1872-1893, 482  
     Expenditure on, 899  
 Loans (See also Debt, Public)  
 Loans, 700  
     Character of Stock Issued, 714  
     Conversion and Consolidation of, 716  
     Expenditure from, 729  
     Expenses of Negotiation, 707  
     Late Issues, 717  
     Maturity, date of, 705  
     Municipal, 256  
     Redemption of, 704

- Loans**—Sinking Funds, 705  
     State, 256  
**Local Diseases**, Death Rate, 202  
**Local Government**, 757  
     Borrowing of Municipalities, 520  
     Comparison of Cities, 772  
     Debts, 779  
     Effect of Absence of, 692  
     Expenditure 735  
     Land Values, 780  
     Loans, 779  
     Rates, 780  
     Rating on Unimproved Value, 758,  
     765, 771  
     Revenue, 778  
**Lymphatic System**, Deaths from Dis-  
     eases of, 188-9
- MacArthur**, Captain, 406, 408  
**Machinery** employed in factories, 996  
     Manufacture of, 979  
**Maffra Sugar Beet Industry**, 386  
**Mail Services**, Oversea, 743  
**Mails**, Carriage of, 222  
**Maize**, Acreage under Crop, 364  
     Prices of, 903  
     Production, 346, 364  
     World's Production, 366  
     Yield per Acre, 365  
**Malarial Diseases**, Deaths from, 188-9  
**Male Population** of Australasia, 187  
     Proportion in the Different Age  
     Groups, 161  
**Males and Females**, Unmarried, 165  
     in Supporting Ages, 160  
**Mallee Scrub**, 296, 308  
**Malting Works**, 982  
**Manganese**, 940  
**Manufactures**, 961  
     Capital Employed in, 999  
     Machinery Employed in, 996  
     State of, in 1862, 471  
     1872-93, 478  
     Value Added by Process of Treat-  
     ment, 970  
     Value of Production, 1000  
     Wages Paid, 1001  
**Manufacturing Industries**—Condition  
     of before Discovery of Gold, 448  
**Maoris Entitled to Vote in New Zea-  
     land**, 147  
     Statistics of, 170  
**Marble**, 954  
     Works, 977  
**Marine Boards**, Tasmania, 776  
**Market Gardens**, Production, &c., of,  
     392
- "Marquis de Castries," Voyage of Dis-  
     covery**, 67  
**Marriages and Marriage Rates**, 207  
     Fecundity of, 209  
     Fertility of, 208  
**Married**, Proportion of Population, 163  
**Mat-making Works**, 995  
**Match Factories**, 993  
**"Mascarin," Voyage of Discovery**, 67  
**Masons' Wages Before Gold Discov-  
     eries**, 445  
**Mauritius**, Trade with, 263  
**Measles**, Deaths from, 190-1  
**Meat**—Boiling-down Works, 431  
     Chilling Works, 431  
     Exports, 245  
     Export Trade, Argentine Republic,  
     432  
     Freezing Works, 431  
     Frozen, Trade in, 427  
     Trade with South Africa, 428  
     Imports, 233, 245  
     Preserving Industry, Encourage-  
     ment in Queensland, 967  
     Works, 431, 448, 982  
     Price of before the Discovery of  
     Gold, 446  
**Meerschaaum**, 955  
**Melbourne**, 20, 23, 460, 463, 468, 473,  
     480, 486, 487  
     Climate, 56  
     Effect of Gold Discoveries on, 454  
     Harbour Trust, 775  
     Metropolitan Board of Works,  
     Water and Sewerage, 775  
     Population of, 155-6  
     Rainfall, 56  
     Shipping Returns, 223-4  
     Temperature, 56  
     Tramway Trust, 775, 778  
**Mercury**, 942  
**Merino Sheep Introduced**, 408  
**Metal Works**, 979  
**Miasmatic Diseases**, Deaths from, 188-9  
**Mica**, 955  
**Mildura Fruit Drying**, 390  
**Militia**, 535  
**Military Forces**, 535  
     Service, Males of, Age for, 160  
**Milk Production**, 433  
**Millinery Factories**, 985  
**Mineral Caoutchouc**, 953  
     Resources, 913  
     Wax, 953  
**Minerals**, Production, 957  
     Value of Production of, 959  
**Miners**, Number of, 958  
     Wages, 451

- Mining Industry, revival of after crisis of 1893, 490  
 Mints, 807  
 Mitchell, Explorations by, 457  
 Modelling Works, 977  
 Mohair, production of, 419  
 Molasses, 934  
 Molybdenum, 942  
 Money Orders, 743, 826  
 Money, Purchasing Power of, 911  
 Moreton Bay, Discovery of, 66  
 Morioris, 171  
 Mortality, Index of, 183  
 Municipal Institutions, 757  
     Loans, 256, 520  
     Rating on Unimproved Value, 758, 765, 771  
 Murray River, Early Navigation of, 460  
 Murrumbidgee River, Navigation of, 460  
 Museums, 831  
 Musical Instruments, Manufacture of, 988  
 Mutton, Frozen, 427  
     Price of before the Discovery of Gold, 466  
  
 Natal, Shipping Trade of Australia with, 215  
     Trade with, 263  
 National Australasian Convention, 70  
 Nationality of Population, 166  
 National Park, Sydney, 531  
 Natron, 953  
 Natural Increase of Population, Excess of Births over Deaths, Statistics of, 182  
 Naturalisation, Act, Commonwealth, 89, 174  
     Conditions of, 174  
 Naval Agreement Act, 542  
     Defence, 539  
 Navigation Bill, Royal Commission on, 92  
     Laws, Commonwealth, 80  
 Negligence, Deaths from, 188-9  
 Nervous System, Deaths from Diseases of, 188-9  
     System, Diseases of, 202  
 Netherlands, Shipping Trade of Australia with, 215  
     Trade with, 265  
 New Caledonia, Cable Service, 752  
     Shipping Trade of Australia with, 215  
     Trade with, 265  
 New Guinea, Geographical Description of, 44  
     British Transfer to Commonwealth, 83  
 New Hebrides, Commonwealth Government Action re. 78  
 Newspaper Postage, 740, 741  
 Newspapers, 830  
 Nickel, 943  
 Nippon Yusen Kaisha, 212, 269  
 Nobility, Proposal to create a Colonial Hereditary, 69  
 North German Lloyd Mail Service, 746  
 Norway, Natives of in Australasia, 166  
     Trade with, 265  
 Note Circulation, 811  
  
 Oamaru, Population of, 156  
     Stone, 954  
 Oatmeal, Prices of, 906  
     Works, 982  
 Oats, Cultivation of, 361  
     Imports and Exports, 363  
     Production, 1903, 346  
     Value of Crop, 363  
     World's Production, 364  
     Yield per acre, 362  
 Ocean Mail Services, 743  
 Octahedrite, 942  
 Occupation Licenses, New South Wales, 296  
 Oil and Grease Works, 976  
 Oil-skin Factories, 985  
 Old-age, death-rate from, 202  
     Pensions, 834, 837  
         Commonwealth, 80, 92, 941  
 Onyx, 956  
 Opal, 956  
 Opium, Consumption of, 895  
 Optical Appliance Factories, 992  
 Oranges, Cultivation of, 389  
 Orchards, Area, production of, &c., 389  
 Organs of Generation, Deaths from Diseases of, 188-9  
     of Locomotion, Deaths from Diseases of, 188-9  
     of Special Sense, Deaths from Diseases of, 188-9  
 Orient-Pacific Royal Mail Line, 221  
 Oriental Emerald, 956  
     Steam Navigation Company, Mail Service, 739, 743.  
 Orphanages, 832, 834  
 Oven Manufacturing Works, 980  
 Oxley, Explorations by, 457  
 Ozokerite, 953

- Pacific Cable, 751  
   Laid, 83  
   Islanders in Australasia, Statistics of, 172  
   Right of Naturalisation Refused to, 175  
 Pacific Islands, Density of Population, 151  
   Labourers' Act, 172  
   Labourers, Deportation of, 81  
   in Sugar-cane Fields, 380  
   Statistics of, 381  
   Relations of Commonwealth with, 80  
 Paint Works, 991  
 Paper Box and Bag-making, 287  
 Paper Currency, 811  
 Parasitic Diseases, Death Rate, 188-9, 199  
 Parcels Post, 742  
 Parks, 831  
 Parturition, Deaths from Diseases of, 188-9, 204  
 Pastoral and Dairy Production, Combined Value, 440.  
   Industry, 1872-1893, 477, 483  
   Effect of Gold Discovery on, 456  
   Progress of, 457  
   Information and Statistics, 406  
   Lease of Land in New South Wales, 296  
   Produce before and after Discovery of Gold, 458  
   Production, Value of, 422  
   Products, Factories treating, 974  
   Property, value of, 422  
   Pursuits, Persons engaged in, 441  
   Resources of Australasia, 406  
 Patents Act, 89  
 Patent Laws, Uniform, Commonwealth, 79  
 Patents Office, transfer to Commonwealth, 635  
 Paulmyer, Binot, Discoveries of, 60  
 Paupers, 837  
 Payment of Members of Parliament, Commonwealth, 72  
   New South Wales, 130  
   New Zealand, 146  
   Queensland, 138  
   South Australia, 141  
   Tasmania, 144  
   Victoria, 135  
   Western Australia, 142  
 Peaches, Cultivation of, 389  
 Pears, Cultivation of, 389  
 "Pelsaert," Voyage of Discovery, 61  
 Peninsular and Orient Company, Mail Services, 738, 743  
 Penny Postage, Universal, 80  
 People's Federal Convention, 71  
 "Pera," Voyage of Discovery, 61  
 Pera Bore, Experimental Farm, 401  
 Perambulator Factories, 989  
 Perth, Climate, 58  
   Population of, 155-6  
   Rainfall, 58  
 Peru, Shipping Trade of Australia with, 215  
 Petroleum, 952  
 Phillip, Captain, Arrival at Sydney, 148  
 Philippine Island, Shipping Trade of Australia with, 215  
 Phosphates, 955  
 Phthisis, Death Rate from, 199, 200  
 Phylloxera, Outbreak, 375  
 Pickles, Sauces, and Vinegar Factories, 982  
 Picture Frame Factories, 991  
 Pig Breeding, 438  
 Pigs, Statistics of, 406  
   Value of Returns from, 433  
 Pineapples, Cultivation of, 392  
 Pirie, Port, Population of, 156  
   Shipping, 223  
 Plaster of Paris, 955  
 Plaster Works, 977  
 Plaice, Acclimatisation of, 1010  
 Platinum, 941  
 Plumbago, 952  
 Police, Expenditure on, 556  
   Force, 555  
 Polynesians in Queensland, 168  
 Pool—Voyage of Discovery, 61  
 Poor Relief, 834  
 Population born at Sea, 169  
   in 1850, 460  
   in Age Groups, 158  
   Increase during 1872-1893, 485  
   Married, Unmarried, Widows, or Widowers, 163-4  
   of Australian States at 30th June, 1904, 86  
   of Cities of Australasia, 155  
   of Commonwealth on 30th June, 1904, 86  
   Statistics, 148  
 Porcelain Clay, 955  
 Pork, Frozen, 438  
   Salt, 438  
 Porter, 984  
 Portmanteau Factories, 994  
 Ports of Australasia, Relative Importance of, 222-4  
   Shipping Trade Compared, 223-4  
 Postage Rates, 741  
 Postal Business, Growth of, 739

- Postal Departments of Australia handed over to Commonwealth, 77  
     Facilities, 743  
     Notes, 743, 827  
     Service Transferred to Commonwealth, 635  
 Post and Telegraph Bill, 80  
 Post Office Saving Banks, 801  
 Posts and Telegraphs, 737  
     Finances, 755  
     Ocean Mail Services, 743  
 Potatoes, Acreage under Crop, 369  
     Imports and Exports, 370  
     Prices of, 903  
     Production of, 346, 369  
     Yield per acre, 370  
 Potteries, 448, 977  
 Poultry, Frozen, Trade in, 439  
     Production, 439  
 Powder Factories, 988  
 Preferential and Reciprocal Trade Act, of 1903, New Zealand, 273  
     Trade, New Zealand and Great Britain, 219  
 Premature Birth, Death Rate from, 202  
 Premiers' Conference re Federation, 371-75  
 Presbyterian Church, 882  
 Prevention of Conception, 179  
 Price Levels of Articles of Common Use, 908  
     of Imports and Exports, 909  
 Prices of Commodities, 902  
 Primary Education, Cost of, 864  
     Producers, 1007  
 Printing Works, 987  
 Prisons, Expenditure on, 556  
 Private Capital Imported for Investment, 479  
     Property and Incomes, 512  
     Schools, 889  
 Privy Council Appeals, Federal Constitution and, 74, 75  
 Probate and Succession Duties, 666  
 Production, Comparison of Australia with other countries, 1021  
     Employment and, 1004  
     of all Industries, Value of, 1018  
     Relation of to Domestic Exports, 1023  
 Professional Class, the, 1015  
 Property Acquisition Bill, 80  
     Distribution of, 516  
     Private, 512  
 Protectionist Policy Adopted by Victoria, 467  
 Provisions, Cost of, 482  
 Public Charities, 832  
     Debts, (See D)  
 Public Libraries, 879  
     Servants, Separate Representation in Parliament in Victoria, 134  
     Service, Administration of Commonwealth, 79  
 Puerperal Fever, Deaths from, 204  
 Punishment of Offences Act, 83  
 Purchasing Power of Money, 911  
  
 Quarantine Laws, Commonwealth, 80  
 Quartz, 955  
 Quicksilver, 942  
 Quota, for Purposes of Redistribution of Electorates, 86  
  
 Rabbits, Frozen Trade in, 439  
 Railway Carriage Building Works, 980  
     Officers, Separate Representation in Parliament of Victoria, 134  
 Railways, Accidents, 582  
     Average Weight of Train Load, 579  
     Broken Hill Traffic, 609  
     Coaching and Goods Traffic, 578  
     Comparison of Facilities, 567  
     Construction of, 458, 462  
     Cost of Construction, 569  
     Earnings and Expenses per mile, 576  
     Expansion of, 484  
     Foreign, Financial Results of, 577  
     Gauge, Diversity of, 566  
     History of Construction of, 558  
     Interest Returned on Capital, 574  
     Light Lines for Removing of Stock in Time of Drought, 422  
     Mileage open, 560  
     New South Wales, System, 583  
     New Zealand Superannuation Fund, 632  
         System, 628  
     Northern Territory System, 611  
     Passenger Traffic, 578  
     Pioneer Lines, 565  
     Privately Owned, Particulars of, 563  
     Queensland System, 599  
     Revenue and Working Expenses, 570  
     Rolling Stock, 581  
     State, Contract of, 565  
     South Australian System, 606  
     Tasmania System, 620  
     Trans-continental (See T)  
     Victorian System, 593  
     Western Australian System, 615  
     Wheat Traffic—Facilities for, 357  
     Workshops, 980



- Rainfall, 54**  
     Distribution of in Australasia, 59  
**Range-making Works, 980**  
**Re-export Trade, 256, 271**  
**Reformatories, 832**  
**Refrigerating Works, 982**  
**Registered Letters, 741**  
**Relief Works, 479**  
**Religion, 880**  
**Renmark, Irrigation Experiments, 390**  
**"Resolution," Voyage of Discovery, 67**  
**Respiratory System, Deaths from Diseases of, 188-9**  
**Revenue Accounts of the State, Position of, 696**  
     Adjusted, 695  
     From Customs and Excise, 295  
     From Leasing and Selling Land, 690  
     Of the Commonwealth, 636  
     Of the States, 661  
     Sources of, 664  
**Rice, Prices of, 906**  
     Price of before Discovery of Gold, 447  
**Rifle Clubs, 537**  
**River Boards, New Zealand, 777**  
     Navigation, 460  
**Road Boards, Western Australia, 768**  
     Trusts, Tasmania, 770  
**Rockhampton, Population of, 156**  
     Shipping, 223  
     Temperature, 57  
**Rock Salt, 953**  
**Rodney Irrigation Trust, 421**  
**"Roebuck," Voyage of Discovery, 62**  
**Roman Catholic Church, 881**  
**Rope Works, 985**  
     Number of, before Discovery of Gold, 448  
**Roseworthy Agricultural College, 395**  
**Rotten-stone, 955**  
**Royal Commission on Decline of Birth Rate, 179**  
**Rubber Works, 995**  
**Ruby, 956**  
**Rugs, Manufacture of, 987**  
**Russia, Natives of in Australasia, 166**  
  
**Saddlery Works, 989**  
**Sailing and Steam Vessels, 219**  
     Vessels, Registered, Number of, 225  
**Sail-making Factories, 990**  
**Sailors, Wages of, 226**  
**Salt, Prices of, 906**  
     Works, 982  
**Salts, 953**  
**Salvation Army, 885**  
**San Francisco, Mail Service, 738, 745**  
  
**Sapphire, 956**  
**Sausage Skin Works, 974**  
**Savings Banks, 801**  
**Saw Mills, 978**  
**Scarlet Fever, Statistics, 190-2**  
**Scandinavia, Trade with, 265**  
**Scandinavian Vessels Trading to Australia, 218**  
**Scandinavians in Australasia, 166-9**  
**Scheelite, 942**  
**Schools, Private, 869**  
     State, 860  
**Schouten, Discoveries of, 62**  
**Scientific Appliance Factories, 991**  
**Scotland, Natives of in Australasia, 166-8**  
**Seamen, Wages of, 226**  
**Selection, Free, before Survey, 288, 462**  
     of Land, Principle of, 287  
**Senatorial Elections, 1903, 87**  
**Septic Diseases, Deaths from, 188-9**  
**Service and Execution of Process Bill, 80, 83**  
**Settlement, Australasian, 341**  
**Settlers, Advances to, New South Wales, 396**  
     New Zealand, 399  
**Shaw Savill and Albion Company Mail Service, 746**  
**Shawls, Manufacture of, 987**  
**Sheep Breeding, 1863-1872, 467**  
     Introduction of Merinos, 408  
     Compared with Population, 1009  
     Production, Value of, 423  
     Statistics of, 406, 408  
**Ship Building Yards, 990**  
     Works, Number of before the Discovery of Gold, 448  
**Shipping, at Ports, 223-4**  
     External, 214  
     Foreign Lines, 268-9  
     Increase in Average Tonnage, per Vessel, 221  
     Interstate, 212  
     Laws, Commonwealth, 80  
     Nationality of, 218  
     Of Australasia, 210  
     Tonnage in Ballast, 217  
     Wages Paid, 226  
**Shirt Factories, 985**  
**Shop Legislation, 492**  
**Silver, 924**  
     Coinage of Commonwealth, 83  
     Lead Miners, Number of, 958  
     Mining, 1872-1893, 476  
**Sinking Funds, 701**  
**Six Hatters, The, 87**  
**Slate Works, 877**  
**Slips and Docks, 990**

- Smelting Works, 980  
 Soap Works, Number of, before Discovery of Gold, 448  
 Soap and Candle Works, 976  
 Social Condition, 830  
 Sole, Acclimatisation of, 1010  
 Soap, Prices of, 906  
 South Africa, Frozen Meat Trade, 428  
 South African War, 538  
   Demand for Horses, 418  
   Troops Sent, 83, 538  
 South Sea Islanders, Restriction of Importation of, 79  
   (See Pacific Islanders)  
 South Sea Islands, Trade with, 265  
 Specific Febrile or Zymotic Diseases, Deaths from, 188-9  
 Speculation, 491  
   Boom in, 480  
   In Land, 443  
 Sperm Oil Trade, 1850, 449  
 Spice Factories, 982  
 Spirits, Consumption of, 897  
 Spoke-making Works, 989  
 Spreckels, J. D., Company, Mail Service, 745  
 Starch, prices, 906  
 State Debts, Question of Commonwealth Taking Over, 657  
 State Finance, 680  
 State Finance, Effect of Federation, 652  
   Schools, 860  
   Servants, Proposal to include in Arbitration Bill, 91  
 Steam and Sailing Vessels, 219  
 Steam Communication with Great Britain, 458  
   Vessels Registered, Number of, 225  
 Stewart Island, Description of, 52  
 "St. Jean Baptiste,"—Voyage of Discovery of, 64  
 Stock Carrying Capacity of Australasia, 420  
 Stock Raising (See Pastoral Industry).  
 Stokes, Discovery of Victoria River, 33  
 Stove Works, 980  
 Straits Settlements, Shipping Trade of Australia with, 215  
   Trade with, 263  
 Strikes, 482  
 Sugar Beet Industry, Government assistance in Victoria, 386  
   Production of, 385  
 Sugar Bonus Bill, 87  
   Bounties, 380  
   Cane, Acreage, Production, yield per acre, &c., 378  
   Duty on, 646  
   Cane Production, 1903, 346  
 Sugar Consumption in Australia, 383  
   Growing Experiments, 395  
   Pacific Islands' Labourers' Act, 380  
   Production, &c., 383  
 Industry, 983  
   Encouragement in Queensland, 967  
   Manufacture of 385  
   Mills, 982  
   Plantations, Coloured Labour on, 380  
   Prices of, 903  
   Price of, before Discovery of Gold, 447  
   Question of Establishing Export Trade, 384  
   Rebate Abolition Bill, 388  
   Refineries, 982  
     Number of before Discovery of Gold, 448  
     Wholesale Price, Variations of, 385  
 Suicide, 206  
 Suicides, 842  
   Statistics, 188-9  
 Sulphur, 943  
 Sultanas, Cultivation of, 390  
 Superannuation Fund, New Zealand Railways, 632  
 Supporters, (Breadwinners) Proportion of to the Population, 160-1  
 Surgical Appliance Factories, 992  
 Surville, Captain de, Voyage of discovery, 64  
 Swan River, Discovery of, 63  
 Sweating, 493, 494, et seq.  
 Sweden, Natives of in Australasia, 166  
   trade with, 265  
 Swine Breeding, 438  
   Statistics of, 406  
   Value of Return from, 433  
 Switzerland, Natives of in Australasia, 166  
 Sydney, 460, 463, 472, 480, 486, 487  
   Climate of, 55  
   Harbour Trust, 292, 774  
   Municipal Government of, 757  
   Population of, 155, 156  
   Rainfall, 56  
   Shipping Returns, 223-4  
   Temperature, 55  
 Tailoring factories, 985  
 Tallow refineries, 974  
   Rise in Price, 427  
   Trade, 1850, 449  
 Tanneries, 974  
   Number of, before Discovery of Gold, 448

- Tariff Bill, 85
- Tarpaulin Factories, 985
- Tasman, Abel Janszoon, Voyage of Discovery, 61
- Tasmanian Gold Mining Company, 475
- Taxation, direct, 665, 666
  - indirect, 665
- Tea, prices of, 903
  - Price of before Discovery of Gold, 447
- Technical Education, 874
- Telegraph Rates, 750
- Telegraphs, 746
- Telephones, 754
- Tellurium, 941
- Temperature of Australasia, 54
- Tent Factories, 985
- Testu, Guillaume le, 60
- Textile Fabrics, 985
- Tie Factories, 985
- Tile Works, 977
- Timber Industry, 1009
- Tin Miners, Number of, 958
  - Mining, 933
    - 1872-1893, 476
- Tinsmithing Works, 980
- Titanium, 942
- Tobacco, Consumption of, 893
  - Factories, 982, 985
    - Number of before Discovery of Gold, 448
- Tobacco Growing, Area, and Production of, &c., 387
  - Prices of, 906
  - Production, 1903, 346
- Topaz, 956
- Tourmaline, 957
- Town Boards, Tasmania, 770
- Townsville, Population of, 156
  - Shipping Returns, 223
  - Temperature, 57
- Toy Factories, 995
- Trade, Comparison of Australasian with Foreign Countries, 257
  - Early History of, 443 et seq.
  - Exports, 243
    - of Domestic Produce, 277
  - Imports, 231
    - of Free and Dutiable Goods, 283
  - Interstate, 271
    - of Australasia, 228
    - of each Australian State shown separately, 269-270
    - of New Zealand, 272
    - of Various Countries, 230
  - Re-exports, 256, 271
  - State of, immediately prior to Discovery of Gold, 449
  - With British Possessions, 263
- Trade with Foreign Countries, 265
  - United Kingdom, 280
- Trades Unions Legislation, 492
- Tramway Workshops, 980
- Tramways, 633
- Trans-continental Railway, 80, 91, 92, 564
- Transshipments, 225
- Treasury Bills, 699, 715
  - late issues of, 717
- Tripoli, 955
- Trout, Acclimatisation of, 1010
- Trust Funds, 699
- Trusts, Local in the Various States, 773 et seq.
- Turbot, Acclimatisation of 1010
- Turnips, Production of, in New Zealand, 393
- Turquoise, 957
- Tweed Factories, 987
- Typhoid Fever, Death rate, 198
- Umbrella Factories, 995
- Underclothing Factories, 985
- Unemployed, The, 1017
- Unimproved value, rating on 758, 765, 771
- University Education, 872
- Unmarried proportion of population, 163
- Upholstering Works, 991
- Urinary System, deaths from diseases of, 188-9
- Van Diemen's Land, Discovery of, 62
- Van Edels, Voyage of Discovery, 61
- Varnish Works, 991
- Vegetables, Production, &c., of, 392
- Venereal Diseases, deaths from, 188-9
- Vessels, Registration of, 225
- Village Settlements in New Zealand, 339
  - In South Australia, 323
  - In Victoria, 311
- Vine Growing, production, &c., 374
- Vinegar Factories, 982
- Violence, Deaths from, 188-9, 206
- Volcanic Action in Australasia, 34, 35, 42, 47, 48
- Volunteer Land Orders, New South Wales, 293
- Volunteers, 536
- Voting Percentage, Federal elections, 1903, 89-90
- Wages—1859-1862, 463
  - Rates, 1861 and 1871, 469
  - 1872-1893, 485

- Wages—1873-1892, 482  
 1893-1902, 490  
 Boards in Victoria, 502-6  
 Effect of Gold Discoveries on, 451  
 In various industries before Gold Discoveries, 445  
 In various Trades, 505 et seq.  
 Paid in Factories, 1001  
 Victoria, before and after establishment of Wages Boards, 505-6  
 Wales, Natives of in Australasia, 166  
 Watchmaking Works, 992  
 Water Boards, Western Australia, 768  
 Conservation, 400  
 Illustration of importance of, 421  
 Frontages, Sale of in New South Wales, 292  
 Waterproof Factories, 985  
 Water Supply and Sewerage, Country Towns, New South Wales, 774  
 Water and Sewerage Board, Sydney, 774  
 Water Supply Boards, New Zealand, 777  
 Water Trusts, Tasmania, 776  
 Water Works, Queensland, 776  
 Trusts, Victoria, 775  
 Wollongong Harbour Trust, 774  
 Wattle Cultivation in Victoria, 311  
 Wax, Mineral, 953  
 Wax, Production of, 439  
 Wellington, New Zealand, Population of, 155, 156  
 Rainfall, 59  
 Shipping, 223-4  
 Wesleyan Church, 883  
 Whaling Industry, 448, 455  
 Wheat, Average Yield per Acre, 355  
 Consumption per Head, 359  
 Cost of Raising, 356  
 Elevators, 357  
 Exports, 244  
 Imports, 232  
 Fall in Prices, 358  
 Ground for Flour, quantity, 984  
 Growing, Darling Downs district, 29  
 Effect of Manuring, 356  
 Increase in, 352  
 Stimulated by discovery of Gold, 447  
 Wheat, Price of, before discovery of Gold, 446  
 Production, 346  
 of Australasia and Foreign Countries compared, 346, 354  
 Railway facilities, 357  
 Storage Sheds, 357  
 Value of Yield per Acre, 358  
 Whip-making Works, 989  
 White Australia Agitation, 80, 470  
 White Labour in Sugar Growing. (See Sugar Bonus Bill)  
 Whooping-cough, Epidemic, 185  
 Statistics, 190, 193  
 Widows or Widowers, Proportion of population, 163  
 Wilberforce Labour Settlement, 298  
 Window Blind Factories, 991  
 Wine, Consumption of, 898  
 Making, 375  
 Production, 377  
 Wire Works, 980  
 Wolfram, 942  
 Women Voting, Percentage, 90  
 Wood Turning Works, 978  
 Wood Working Factories, 978  
 Wool, European Importations, 423  
 Exports, 255  
 Imports, 242  
 Excess of Exports over Imports, 425  
 Greasy, Production of, 424  
 Output and Value, 406  
 Price of, 425  
 Scouring Works, 974  
 Trade, 278  
 1850, 449  
 Value of Production, 423  
 Weight per Sheep, 424  
 Woollen Mills, 985  
 Number of, before Discovery of Gold, 448  
 Workers, Grades of, 1015  
 Workshops, Legislation, 492  
 "Zeehan," Voyage of Discovery, 61  
 Zinc Ores, 942  
 Zircon, 956  
 Zoogenous Diseases, Deaths from, 188-9  
 Zymotic Diseases, Deaths from, 188-9





UNIVERSITY OF MICHIGAN



3 9015 06510 8741